Reason 14

Operation Manual



Reason Studios

Reason Studios

reasonstudios.com

The information in this document is subject to change without notice and does not represent a commitment on the part of Reason Studios AB. The software described herein is subject to a License Agreement and may not be copied to any other media except as specifically allowed in the License Agreement. No part of this publication may be copied, reproduced or otherwise transmitted or recorded, for any purpose, without prior written permission by Reason Studios AB.
©2026 Reason Studios and its licensors. All specifications subject to change without notice.
Reason, Reason Intro, Reason Lite and Rack Extension are trademarks of Reason Studios AB.
All other commercial symbols are protected trademarks and trade names of their respective holders. All rights reserved.



Table of Contents

Introduction 33

Welcome! 34
A few words from the writer 34

About this chapter 34

About this manual 34

About the Reason operating system versions 34

Conventions in the manual 34

About the Authorization system 36
Registering Reason (licensed version only) 36
Authorizing Reason 36
Authorizing a computer for long-term off-line use 37
What happens if an authorization expires? 38
Running Reason in Demo Mode 39

Managing additional content 40

About automatic program updates 41

Reassigning the Function Keys in macOS 42

Common Operations and Concepts 45

About this chapter 46

Windows, areas and basic navigation 46
Document window overview 46
Application Zoom 47
Device Palette overview 47
Track Panel overview 48
The Sequencer 49
The Transport Panel 50
The ReGroove Mixer 50
The Main Mixer 51
The Rack 52
Navigating between the areas 54
About different Themes 55
Working with several Reason Documents 56
The On-screen Piano Keys window 56

General window techniques 57
Resizing 57
Scrolling 58
Zooming in the Sequencer 59
Scrolling and zooming using the Zoom/Scroll areas in the Sequencer 61
Scrolling and zooming using a wheel mouse 61
Scrolling and zooming using an XY "wheel" mouse 62
Scrolling and zooming using an XY track pad 62

Editing parameters 62
Knobs 63
Faders and sliders 63
Buttons 63
Fold/Unfold buttons 64
Multi Mode selectors 64
Numerical controls 65
Alpha-numeric controls 65
Numerical segment displays 66

Tool Tips 67

Context menus 68
Parameter context menus 68
Device context menus 69
Main Mixer channel strip context menu 69
Rack "background" context menu 70
Main Mixer "background" context menu 70
Sequencer context menus 70

Undo and Redo 71

On-screen Piano Keys 73

About this chapter 74

Using the On-screen Piano Keys 74
Opening the Piano Keys window 74
Mouse mode 75
Computer Keys mode 76

Audio Basics 79

About this chapter 80

How Reason communicates with your audio hardware 80
Manual audio routing 80
Audio quality 81
Audio settings 81
About audio levels 84

System signal paths 86
Audio Track signal paths 86
Instrument Track signal paths 87

General information about audio and computers 88
About latency 88
About processors 89
About RAM 89

Sequencer Functions 91

About this chapter 92

Introduction 92

Sequencer overview 92
The Arrange Area and the Edit Area 93
Toolbar overview 95
Track List overview 95
Tracks overview 95
Lanes overview 96
Clips overview 96
Arrange Area Inspector overview 96
Ruler/Timeline overview 96
Track scrollbar overview 97
Song Navigator overview 97
Transport Panel overview 97

Track details 98
Track definition 98
The relationship between the track, the rack and the Main Mixer 99
Master Keyboard Input 104
The relationship between tracks, lanes, clips and events 105
Track types 105
Track List elements 107
Creating tracks 107
Selecting tracks 111
Resizing tracks 112
Moving tracks 113
Deleting tracks 113
Duplicating/copying tracks and devices 114
Coloring tracks 115
Naming tracks 115
Muting tracks 115
Soloing tracks 116

Lane details 117
Audio lane 117
Note lane 118
Parameter automation lane 119
Pattern lane 120
Creating/adding lanes 121
Deleting lanes 123
Moving note lanes 124
Copying (duplicating) note lanes 124
Muting lanes 125

Clip basics 125
Clip types 125

Toolbar details 126
Toolbar tools 126
Alternate tools 129
Snap 129
Sequencer Toolbar keyboard shortcuts 131

Ruler (timeline) details 132

Transport Panel details 132
Click Level 132
Click On/Off 133
Tap Tempo 133
Pre(-count) On/Off 133
Tempo 133
Time Signature 133
Song Position 133
Time Position 134
Rewind and Fast Forward 134
Play and Stop 134
Record 135
Dub and Alt 135

Loop On/Off 135
Left and Right Locator Positions 136
Go to Left and Right Locators 136
Quantize value 136
Quantize 136
Q Rec 136
Sync Mode 136

Transport keyboard commands and modifier keys 137

About the Arrange Area Inspector 138
About subticks in the Position and Length displays 138
About the "Match Values" function 138

The Track Panel 139
Track Panel elements 139
Adding devices on the Track Panel 140
Bypassing Effects on the Track Panel 141
Replacing devices or patches on the Track Panel 142
Moving and re-routing devices on the Track Panel 143
About signal splits, parallel channels and merges 143
Using Send Effects on the Track Panel 145
Showing the devices in the Rack 148
Deleting devices from the Track Panel 148

Recording in the Sequencer 149

About this chapter 150

General recording functions 150
Record enabling 150
Click and Pre-count 154
Loop mode 155
General recording procedure 156
Undoing a recording 157
Recording tips 157

Audio recording details 157
Setting up the audio track 157
Recording audio 161
Recording audio in Loop mode 161
Overdubbing audio using the "Dub" function 162
Duplicating audio tracks using the "Alt" function 162
Recording over or into an existing audio clip 163
Recording audio from Mix Channel outputs 164
Recording a mixdown of several audio tracks 166

Note recording details 170
Setting up the instrument track 170
Recording notes 170
Recording notes in Loop mode 170
Recording over or into an existing note clip 171
Recording notes using the "Dub" and "Alt" functions 172

Parameter automation recording details 174
Performance controllers vs. track parameter automation 174
Recording performance controller automation 175
Recording parameter automation into Note Clips 176
Recording performance controller automation over or into an existing clip 176
About performance controller automation on multiple lanes 177
Recording parameter automation 177
Recording parameter automation in Loop mode 178
Recording parameter automation over or into an existing clip 179
Adjusting automated parameters during playback - "Live mode" 180
Recording parameter automation on multiple tracks 180
Recording parameter automation into note clips 180

Pattern automation recording details 181
Recording pattern automation 181

Tempo automation recording 182
Recording tempo automation 182

Arranging in the Sequencer 185

About this chapter 186

Clip handling 186
Creating Clips 186
Selecting clips 186
Setting audio clip Level and Fades 188
Deleting clips 189
Resizing (masking) clips 190
About masked recordings and events 191
Tempo scaling clips 193
Moving clips 195
About overlapping clips 197
Duplicating clips 197

Cutting, Copying and Pasting clips 197
Naming clips 198
Coloring clips 198
Splitting clips 199
Crossfading audio clips 201
Joining clips 202
Reversing clips 204
Muting clips 204
Merging clips on note lanes 205
Bounce in Place 205
Matching clips using the “Match Values” function 208

Looped Clips 210
Looping clips 210
Changing loop length 211
Editing the looped clip contents 211
Additional Looped Clips functions 215

Inserting bars 216

Removing bars 216
About removing bars that contain audio recordings 217

Track Folders in the Sequencer 219

About this chapter 220

Introduction 220

Working with Track Folders 220
Adding Track Folders 220
Track Folder settings and functions 222
Folder Clips 224

Audio Editing in the Sequencer 227

About this chapter 228

Edit Modes, Stretch & Transpose Types and Clip Types 228
Edit Modes 228
Selecting Stretch and Transpose Type 229
Tempo 230
Clip Types 231
Opening audio clips for editing 231
Auditioning audio in the Audio Overview Edit Mode 232
Stretching and repositioning Slices in the Audio Overview Edit Mode 232
Cutting (splitting) Audio Clips in the Audio Overview Edit Mode 233
Closing the Audio Overview Edit Mode. 233

Editing audio in Slice Edit mode 234
Audio clip elements in Slice Edit mode 234
Slice Edit mode tools 235
Selecting Slices and Slice Markers 235
Adding Slice Markers 236
Deleting Slice Markers 237
Repositioning Slice Markers 237
Moving/stretching Slices 237
Nudging Slices 239
Quantizing audio 239
Split at Slices 240
Bounce Clip to REX Loop 240
Revert All Slices 241
Closing Slice Edit mode 241

Editing audio in Vocal Edit mode 242
Pitch Editor elements 242
Selecting notes 243
Auditioning notes 243
Correcting pitches 244
Changing transposition 244
Resetting pitches 244
Splitting the clip at notes 244
Reverting all notes 244
Attenuating pitch drift/vibrato 245
Editing transition times 245
Moving notes and changing note lengths 246
Splitting and joining notes 248
About switching from Vocal Edit mode to Slice Edit mode 248
Audio pitch editing in the Edit Area Inspector 249

Editing audio in the Comp Editor 251
Audio clip elements in the Comp Editor 251
The relationship between Clips, Comp Rows and Recordings 255
Comp Editor window handling 257
Comp Editor audio editing tools 257
Selecting a Comp Row for playback in a Single Take clip 258
Selecting Comp Rows 259

Deleting Comp Rows 259
Moving Comp Rows 260
Duplicating Comp Rows 260
Cutting, copying and pasting Comp Rows 261
Adjusting the Comp Row Level 261
Adjusting the Recording Offset 262

Comping audio 263
Adding Cuts 263
Adding Segments 264
Adding Crossfades to Cuts 264
Deleting Cuts 265
Moving Cuts 265
Changing Comp Row assignments 266
Bounce Clip(s) to New Recording(s) 267
Creating a comped audio clip 268

Common audio editing functions 272
Delete Unused Recordings 272
Bounce Clip(s) to New Sample(s) 272
Bouncing audio to MIDI notes 273
Normalizing audio clips 274
Reversing audio clips 275

Changing the tempo and transposition of the audio 276
Tempo scaling Clips 276
Transposing Audio Clips 277

Editing audio using the Inspector 279
Editing recordings and cuts in the Edit Area Inspector 279
Matching audio values using the "Match Values" function 280

Note and Automation Editing 283

About this chapter 284

The Edit Area 284
Selecting what to edit 285
Opening note and automation clips for editing 285
Edit Area elements 287
Edit Area window handling 288
Note Edit View Modes 289
Creating empty clips 291

Note editing 292
Selecting notes 292
Drawing notes 293
Deleting notes 295
Resizing notes 295
Muting notes 298
Splitting notes 298
Joining notes 299
Chopping notes 299
Moving notes 299
Duplicating notes 302
Using Cut, Copy and Paste 303
Quantize 304
Note Pitch & Transposition 307
The selected notes will be randomly transposed within the set note range. 309
Velocity functions 309
Extract Notes to Lanes 312
Scale Tempo 314
Reverse 315

Multi Lanes editing 317
Overview 317
Selecting multiple lanes for editing 317
Editing notes in Multi Lanes mode 319

Automation editing 320
Overview 320
Editing parameter automation 320
Drawing parameter automation events 323
Creating curves between automation points 324
Deleting automation events 324
Reversing automation events 324
Editing performance controller automation 325
About Automation Cleanup 327
About Automation Cleanup 327
Editing pattern automation 328
Drawing pattern automation 329
Moving, resizing and duplicating pattern automation clips 330
Deleting pattern automation clips 330
The “Convert Pattern Automation to Notes” function 331
Editing tempo automation 331
About tempo changes and tempo automation of audio tracks 332
Automating time signature 333
Moving, resizing and duplicating time signature automation clips 334
Deleting time signature automation clips 334

Note and automation editing in the Inspectors 335
Editing notes and events in the Inspectors 335
Matching notes or events using the "Match Values" function 336

Working with Blocks in the Sequencer 339

About this chapter 340

Introduction 340
The idea behind Blocks 340

Arrangement Views 341
Song View (with Blocks disabled) 341
Song View (with Blocks enabled) 341
Block View 342

Editing Blocks in the Block View 342
Selecting a Block for editing 342
Renaming Blocks 343
Defining the Block length 343
Changing Block color 343
Recording in the Block View 343
Editing clips in the Block View 343
Arranging clips in the Block View 344

Arranging Blocks in the Song View 344
Creating Block Automation Clips 344
Resizing Block Automation Clips 346
Reassigning Blocks in Block Automation Clips 346
Muting lanes in Block Automation Clips 347
Converting Block Automation Clips to Song Clips 349
Combining Block Automation Clips with Song Clips 351

Working with the Rack 355

About this chapter 356

Rack device procedures 356
Viewing the Rack and the Devices 356
Navigating in the rack 360
Resizing the rack 360

The Device Palette 361
About using the Device Palette when the Rack is in a separate window 361
Choosing what device types to show in the Device Palette 362
Using the Favorite tag 362
Filtering the view in the Device Palette 364
Filtering on Categories on the Device Palette 365
Assigning Categories to devices on the Device Palette 366
Using Tags on devices 366
Assigning Tags to devices 367
Hiding devices from the Device Palette 368

Working with devices 369
Creating devices 369
About Device Groups 372
Selecting devices 372
Deleting devices 374
Re-ordering and re-routing devices 374
Creating new rack columns 375
Replacing devices 376
Duplicating devices 376
Cut, Copy and Paste devices 377
Naming devices 377
Folding and unfolding devices 378
Flipping the rack 379

Working with Players 381

About this chapter 382

Overview 382
General recording methods 383

Using Players 384
Creating Players 384
Chaining Players 384
Replacing Players 384
Deleting Players 384
Naming Players 384
About Players in Combinators 385
Common Player device parameters 385

Beat Map 386
Included content 386
The front panel 387
Map Select 388
Density 388

Lock Position 389
Mirror notes 389
Setting MIDI note numbers 390
Global settings 391
Beat Map and the sequencer 391
Editing the drum notes 393
Using CV 393

Dual Arpeggio 394
The Display sections 396

Note Echo 402

Note Tool 403
Mode 403
Filter 403
Adjust 405
In/Out 407
Using CV 408

Random Tool 409
Conditional 409
Probability 409
Random Pitch 410
Random Velocity 410
Random Note Length 411
Sync Chance 411
Using CV 411

Scales & Chords 412
Scales 412
Filter Notes 413
Chords 414

Tips & Tricks 417
Generating scale-correct arpeggios from single notes 417
Generating chord arpeggios 417
Creating parallel chords 417
Using a Scales & Chords device as a "MIDI Note monitor" 418

Working with Rack Extensions 419

About this chapter 420

What are Rack Extensions? 420
Future compatibility 420

Trying and buying Rack Extensions 420
Trial versions of Rack Extensions 420
Buying Rack Extensions 420

Installing and managing Rack Extensions 421

Using Rack Extensions in Reason 422
About missing Rack Extensions 424

Working with VST Plugins 425

About this chapter 426

About VST plugins 426
VST compatibility in Reason 426

Installing and enabling VST plugins 426
About VST licenses 426
Installing VST plugins under Windows 426
Installing VST plugins under Mac 427
Enabling VST plugins in Reason 427

Using VST plugins in Reason 428
Adding VSTs to the rack 428

The Plugin Rack Device 429
Front panel 429
Rear panel 430
About auto-routing of VSTs in the rack 431
The Plugin Window 431
Editing the VST parameters 433
Automating VST parameters 433
CV modulation of VST parameters 435
Remote controlling VST parameters 438
Selecting VST presets/programs 439
About saving songs that contain VSTs 440
Combining VST plugins in Combinator devices 440
About missing VST plugins 440

Managing VST plugins 441
Auto-scale (Windows only) 442
Plugin Status 444
Defining custom VST folders 444

Sounds, Patches and the Browser 445

About this chapter 446

About patches 446
Patches and references to samples/REX files 446
Loading patches 447
Saving patches 448
Copying and pasting patches between devices 449
Initializing patches and resetting device parameters 449

Using the Browser 450
Browser overview 450
Important notes about where to store your files so that Reason can find them 453
Creating a device by browsing patches 454
Browsing patches for a device 455
Browsing samples for a device 456
Selecting multiple files 458
About patch formats and sampler devices 458
About browse lists 458
Other Browse Focus modes 459
Using the browser without Browse Focus 459
The Locations list 460
Filtering in the Browser 462
Editing Categories, Tags and Author 466
Other Browser functions 469
Handling Missing Sounds 471

About ReFills 473

Reason file formats 474

Routing Audio and CV 477

About this chapter 478

Signal types 478
Audio signals 478
CV/Gate signals 478
P-LAN signals 479
About MIDI routing 479

About cables 479
Cable appearance 479
Checking and following cable connections 480
Cable color 481

Automatic routing 481
Auto-routing of audio input signals 481
Auto-routing of Instrument devices 482
Auto-routing of Effect devices 482
Auto-routing of CV/Gate signals 483
Auto-routing devices after they have been created 483
About re-routing devices in songs created in Reason Version 5 or earlier 484

Manual routing 485
Connecting cables 486
Connecting cables using pop-up menus 486
Disconnecting cables 487
Disconnecting devices 487

Using CV and Gate 488
Routing CV and Gate signals 488
About CV Trim knobs 488

The Main Mixer 489

About this chapter 490

Overview 490
The Audio Track, its device and mixer channel strip 491
The Mix Channel device and channel strip 492
The Master Section device and mixer strip 493

Navigating in the Main Mixer 494
Viewing the Main Mixer area 494
Scrolling and navigating in the Main Mixer 494
Showing and hiding channel strip sections 495
Switching between channels, rack devices and tracks 496

Managing mixer channels 497
Creating and deleting channels 497
Selecting channels 497
Moving channels 498
Copying and duplicating channels 498
Copy channel settings 499
Resetting channel settings 499
Naming mixer channels 499
Coloring mixer channels 500

The channel strip 501
Input section 501
Dynamics section 502

EQ section 505
The Spectrum EQ Window 506
Insert FX section 509
FX Sends section 509
Fader section 510
Channel Header section 512

The Master Section strip 513
Master Compressor section 514
FX Send section 515
Master Inserts section 516
FX Return section 517
Master Fader section 518
Master Section Header 519

Automating mixer parameters 519

Working with effects 520
Insert FX 520
Send FX 523

Output Busses 526
Creating an Output Bus 526
Deleting an Output Bus 528
Recording a sub-mix onto an audio track 529

Parallel Channels 530
Creating Parallel Channels 530
Deleting Parallel Channels 533
Naming Parallel Channels 533

Solo, Mute and Send FX logic 534
Solo and Mute logic 534
Send FX level and mute logic 536

Remote controlling the Main Mixer 538
Remote controlling a single mixer channel 538
Remote controlling multiple mixer channels 538

Advanced routing tips and tricks 541
Chaining Send effects from Redrum or Mixer devices 541
Using compression sidechaining 543
Using the Mix Channel and Audio Track devices' Direct Outs 544
Creating an input channel for recording with effects 545

Delay Compensation 549

About this chapter 550

About Delay Compensation in Reason 550
Activating the Delay Compensation 550
Delay Compensation rules and limitations 551

How the Delay Compensation works 554
Delay Compensation in individual mixer channels 554
Delay Compensation with Busses and Parallel Channels 558
Delay Compensation to Send FX busses 559
About the Master Insert FX 559
Problematic configurations 560
About using the Direct Out connections of the mixer channels 564
About the Metronome Click 564
Recording with Delay Compensation 564
Playing and monitoring with Delay Compensation 564
About bouncing mixer channels 564

Song File Handling 565

About this chapter 566

Opening Songs 566
Opening a Reason Song 566
Opening a Reason Demo Song 567
Opening the last Song at program launch 567

Closing Songs 568

Creating Songs 568
Creating a new Song 568
Setting up a Default Song 568
Creating a new Song from a Template 569

Saving Songs 569
Saving a Song 569
Saving and optimizing a Song 569
Including Song Information 570
About Self-Contained Songs 571
Making a Song appear as a Template Song 572
A note about saving Songs as audio files 572

Audio data and Scratch Disk settings 573
About audio data in Song files 573
Changing Scratch Disk folder location 573
About "Orphan Audio Streams" 574

Importing and exporting Standard MIDI Files 574
Importing Standard MIDI Files 574
Exporting Standard MIDI Files 575

Importing and Exporting Audio 577

About this chapter 578

Importing audio 578
Audio formats, sample rates and tempo matching 578
About tempo matching imported audio to the sequencer 578
Importing audio to the sequencer 579

Exporting audio 582
Exporting Songs or parts of Songs 582
Bouncing Mixer Channels 584
Bouncing Audio Clips 586

Sampling 589

About this chapter 590

Overview 590
One-click sampling 590
The Edit Sample window 590
About sample format, rate and resolution 591

General sampling functions 591
Setting up for sampling 591

Sampling 593
The Sample buttons 593
Sampling procedure 593
The Song Samples location 596

Editing samples 598
The Edit Sample window 598
Setting Sample Start and End 600
Cropping samples 602
Normalizing samples 602
Reversing samples 602
Fading in/out samples 603
Looping samples 604
Saving edited samples 606
Renaming samples 606

Sample management 607
About Assigned and Unassigned samples 607
Saving samples in a song 608
Deleting samples from a song 608
Loading samples into a device 609
Duplicating samples 610
Exporting samples 611
About self-contained samples 613

The ReGroove Mixer 615

Introduction 616
ReGroove basics 616

The ReGroove Mixer 617
Global parameters 617
Channel parameters 618
Copy, Paste and Initialize ReGroove channels 622

Groove Settings 622

Working with grooves 625
Applying grooves to your music 625
Commit to Groove - making the grooves "permanent" 627
Creating your own ReGroove patches 629

Groovy tips & tricks 630

ReGroove patches in the Factory Sounds bank 631

Remote - Playing and Controlling Devices 633

About the various MIDI inputs 634

About Remote 634

Setting up 635
Automatic set-up using the Easy MIDI Inputs function 635
Adding a specific control surface or keyboard 635
Other functions 638
Example Setups 639

Remote basics 640
About Standard vs Remote Override mapping 640
About mapping variations 640

Locking a surface to a device 642
Locking a surface 642
Unlocking a surface 644

Remote Override 645
Activating Remote Override Edit mode 645
Remote Override mapping 646

Additional Remote Overrides... 649
Assigning Additional Overrides 650

Keyboard Control 651
Enabling Keyboard Control 651
Editing Keyboard Control 651

Saving Remote Setups 652

Synchronization and Advanced MIDI 653

About this chapter 654

Synchronization to MIDI Clock 654
What is synchronization and MIDI Clock? 654
Using Reason as MIDI Clock Host 654
Syncing Reason to an external MIDI application or instrument 656
Syncing Reason to another program on the same computer 656
External synchronization considerations 657

Synchronization using Ableton Link 659
About Ableton Link 659
Synchronizing Reason's sequencer with Ableton Link 659

Advanced MIDI - The External Control Bus inputs 661
About the External Control Bus inputs 661
Routing MIDI to devices 662
Receiving Controller data via MIDI 662
About recording Pattern Changes 662

Optimizing Performance 663

Introduction 664
Checking overall processing power 664
Checking processing power for individual devices 664

Optimization and latency reduction 665
About Latency Compensation 666

Optimizing your computer system 667

Optimizing Songs 669

RAM requirements 671

Hardware Interface 673

Introduction 674

Sampling Input section 675

Advanced MIDI Device 676

More Audio 676

The Big Meter 677

Dr. Octo Rex Loop Player 679

Introduction 680
ReCycled Loops 680

About REX file formats 681

Loading and saving Dr. Octo Rex patches 681
About the Dr. Octo Rex patch format 681
About opening songs that previously used Dr. Rex devices 681

Playing Loops 682
Switching playback between Loop Slots 682

Adding Loops 683
Loading Loops "On the Fly" 684
Removing Loops 684
Cut/Copy and Paste Loops between Loop Slots 684

Playing individual Loop Slices 684

Creating sequencer notes 685

Slice handling 687
Selecting Slices 687
Editing individual Slices 687
Editing in the Waveform Display 688
The Slice Edit Mode 689

Dr. Octo Rex panel parameters 690
Pitch and Mod wheels 690
Trig Next Loop 690
Note To Slot 690
Loop Slot buttons 691
Enable Loop Playback and Run 692
Volume 692
Global Transpose 692

Dr. Octo Rex synth parameters 693
Select Loop & Load Slot 693
Loop Transpose 693
Loop Level 694
Oscillator section 694
Mod. Wheel 694
Velocity section 695
The Filter Section 695
Envelope section 697
LFO section 698
Pitch Bend Range 699
Setting number of voices - polyphony 699
Audio Quality settings 700

Connections 700
Modulation Inputs 700
Modulation Outputs 701
Gate Inputs 701
Gate Output 701
Slice Outputs 701
Main Outputs 701

Europa Shapeshifting Synthesizer 703

Introduction 704

Panel overview 705

Signal flow 706

Playing and using Europa 707
Loading and saving patches 707
Global output controls 707
Global performance and "play" controls 707

Panel reference 709
Sound Engines On/Off and Edit Focus section 709
The Oscillator section 709
The Modifiers section 712
The Spectral Filter 714
The Harmonics section 716
The Unison section 718
The User Wave and Mixer section 719
The Filter section 720
The Amplifier section 722
The Envelopes section 724
The LFO section 728
The Effects section 729
The Modulation Bus section 732

Connections 736
Sequencer Control inputs 736
CV Modulation inputs and outputs 736
Audio Output 736

Tips and Tricks 737
Creating an individual "pre amp envelope" for a Sound Engine 737
Recording display movements in the sequencer 738

Grain Sample Manipulator 739

Introduction 740
A few words about granular synthesis 740

Panel overview 742

Playing and using Grain 743
Loading and saving patches 743
Global performance and "play" controls 743
Global output controls 744

Panel reference 745
The Sample section 745
The Playback Algorithms section 747
The Oscillator section 752
The Filter section 752
The Amplifier section 754
The Envelopes section 755
The LFO section 759
The Effects section 759
The Modulation Bus section 763

Connections 767
Sequencer Control inputs 767
CV Modulation inputs and outputs 767
Audio Output 767

Tips and Tricks 768
Automating sample playback parameters from the sequencer 768

Humana Vocal Ensemble 771

Introduction 772

Panel overview 772

Using Humana 773
Loading and saving patches 773

Global performance and "play" controls 773

Panel controls 774
The Instruments section 774
The Filter section 780
The Amp section 782
The Delay section 784
The Reverb section 785

Connections 787
Sequencer Control inputs 787
Modulation Inputs 787
Audio Out 787

ID8 Instrument Device 789

Introduction 790
The Sounds 790
The ID8 and Standard MIDI Files 790

Using the ID8 791
Selecting Sounds 791
Controlling Sounds 791
About saving edited Sounds 792

Klang Tuned Percussion 793

Introduction 794

Panel overview 794

Using Klang 795
Loading and saving patches 795

Global performance and "play" controls 795

Panel controls 796
The Instruments section 796

The Filter section 801
The Amp section 803
The Delay section 804
The Reverb section 806

Connections 807
Sequencer Control inputs 807
Modulation Inputs 807
Audio Out 807

Kong Drum Designer 809

Introduction 810

Overview 810
The Pad Section 810
The Drum Control Panel 811
The Drum and FX Section 811
About using custom backdrops 811

About file formats 811

Using patches 812
Loading a Kit Patch 812
Checking the sounds in a Kit Patch 813
Creating a new Kit Patch 813
Creating an empty Kit Patch 814
Saving Kit Patches 814

Pad Settings 815
Assigning Drums to Pads 815
Renaming Pads 816
Copying & Pasting Drums between Pads 816
Assigning Hit Type to Pads 816
Muting and Soloing Pads 817
Working with Pad Groups 818

The Drum and FX section 819
Signal flow 820
The Drum Control Panel 822
Sampling in Kong 824
The Drum Module slot 824
The FX slots 825

The Drum modules 826
NN-Nano Sampler 826
Nurse Rex Loop Player 830
Physical Bass Drum, Snare Drum and Tom Tom 835
Synth Bass Drum, Snare Drum and Tom Tom 837
Synth Hi-hat 838

The Support Generator modules 839
Noise Generator 839
Tone Generator 840

The FX modules 841
Using CV modulation of Bus FX and Master FX parameters 841
Drum Room Reverb 842
Transient Shaper 842
Compressor 843
Filter 844
Parametric EQ 844
Ring Modulator 845
Rattler 846
Tape Echo 846
Overdrive/Resonator 847

Connections 848
Sequencer Control 848
Modulation Input 848
Aux Send Out 848
Gate In and Out 849
Audio Out 3-16 849
Main Audio Out 849

Using Kong as an effect device 849

Using external effects with Kong 850

Malström Synthesizer 851

Introduction 852
Features 852
Theory of operation 853
Loading and Saving Patches 853

The Oscillator section 854
Setting oscillator frequency 855
Controlling playback of the graintable 855
The amplitude envelopes 856

The Modulator section 857
Modulator parameters 857
Destinations 858

The Filter section 859
The Filters 860
The Filter Envelope 862
The Shaper 863

Routing 865
Routing examples 866
The output controls 869

The play controls 869
Polyphony - setting the number of voices 870
Porta (portamento) 870
Legato 870
The Pitch Bend and Modulation wheels 871
The Velocity controls 871
The Modulation wheel controls 872

Connections 873
Audio Output 873
Audio Input 873
Sequencer Control 873
Gate Input 874
Modulation Input 874
Modulation Output 874

Routing external audio to the filters 875

MIDI Out Device 877

Introduction 878

Using the MIDI Out Device 878
Setting up for controlling an external MIDI instrument 878
Controlling the sound of your external MIDI instrument 879
Using MIDI Program Change 879
Recording MIDI Controller automation 880
Modulating MIDI Controllers from CV signals 884

Connections 887
Sequencer Control 887
CV In to MIDI CC Out 887

Tips & Tricks 887
Audio recording of MIDI controlled external instruments 887

Mimic Creative Sampler 891

Introduction 892

Panel overview 893

Signal flow 894

Playing and using Mimic 895
Loading and saving patches 895
Global output controls 895
Slot Mode 895
Slot Select 898
Performance and “play” controls 898

Panel reference 900
The Sample section 900
Start Position 902
Speed and Speed Mod 904
Stretch 904
Slices 907
Pitch 908
The Filter section 909
The Filter Envelope and Amp Envelope sections 912
The LFO section 913
The Amp section 914
The Compressor 915
The Effect section 915
The EQ section 916
The Send section 916

Connections 917
Sequencer Control inputs 917
CV In 1-4 917
Slot Out 1-8 917
FX Send Out 917
Audio Output 917

Tips and Tricks 918
Optimizing performance/DSP Load 918
Creating a “velocity layered” instrument 918
Extending the sample “tail” (without looping) 919
Automating the sample Start and End markers 920

Monotone Bass Synthesizer 921

Introduction 922

Panel overview 923

Signal flow 924

Playing and using Monotone 925
Loading and saving patches 925
Global output controls 925
Global performance and "play" controls 925

Panel reference 926
The Oscillator section 926
The Filter section 927
The Amplifier section 929
Chorus 930
Delay 931
The LFO section 931
The Envelope section 932

Connections 933
Sequencer Control inputs 933
Modulation inputs 933
Audio Output 933

NN-XT Sampler 935

Introduction 936

Sampling in NN-XT 936

Panel overview 937
The main panel 937
The Remote Editor panel 937

Loading complete Patches and REX files 938
Loading NN-XT Patches 938
Loading NN-19 Patches 938
Loading SoundFonts 939
Loading complete REX files as Patches 939

Using the main panel 940
The Pitch and Modulation wheels 940
The External Control wheel 940
High Quality Interpolation 941
Global Controls 941

Overview of the Remote Editor panel 943
The Key Map display 943
Sample parameters 944
Group parameters 944
Synth Parameters 945

About Samples and Zones 945

Selections and Edit Focus 946
Selecting Zones 947
Moving Edit Focus 949

Adjusting parameters 949
Adjusting Synth parameters 949
Adjusting Group parameters 949
Sample parameters 950

Managing Zones and Samples 951
Creating a Key Map 951
About file formats and REX slices 952
Adding more samples to the Key Map 952
Replacing a sample 952
Quick browsing through samples 953
Removing samples 953
Auditioning samples 953
Adding empty Zones 953
Duplicating Zones 954
Removing Zones 954
Rearranging Zones in the List 954

Working with Grouping 954
About Groups 954
Creating a Group 954
Moving a Group to another position in the List 955
Moving a Zone from one Group to another 955
Selecting a Group and/or Zones in a Group 956
The Group Parameters 956

Working with Key Ranges 956
About Key Ranges 956
Setting up Key Ranges 956
About the Lock Root Keys function 960
About the Solo Sample function 961
Sorting Zones by Note 962



Setting Root Notes and Tuning 963
About the Root Key 963
Setting the Root Note manually 963
Tuning samples manually 963
Setting the Root Note and Tuning using pitch detection 964
About changing the pitch of samples 964

Using Automap 964

Layered, crossfaded and velocity switched sounds 965
Creating layered sounds 965
About velocity ranges 965
Setting velocity range for a Zone 967
About Crossfading Between Zones 967
Setting crossfading for a Zone 969

Using Alternate 969
About the Alternate function 969

Sample parameters 970
Root Note and Tune 970
Sample Start and End 970
Loop Start and End 970
Play Mode 971
Lo Key and Hi Key 971
Lo Vel and Hi Vel 971
Fade In and Fade Out 971
Alt 971
Out 971

Group parameters 972
Key Poly 972
Legato and Retrig 973
LFO 1 Rate 973
Portamento 973

Synth parameters 974
The Modulation controls 974
The Velocity controls 975
The Pitch section 976
The Filter section 977
The Modulation Envelope 979
The Amplitude Envelope 981
The LFOs 982

Connections 985
Sequencer Control 985
Modulation Input 985
Gate Input 985
Audio Output 985

NN-19 Sampler 987

Introduction 988

General sampling principles 988
Background 988
Multisampling vs. single samples 988

About audio file formats 989
Loading a Sample Patch 989
Loading REX Files as Patches 990

Sampling in NN-19 990

About Key Zones and samples 991
Loading a Sample into an empty NN-19 991
Loading SoundFont samples 992
Loading REX slices as samples 992
Creating Key Zones 992
Selecting Key Zones 993
Setting the Key Zone Range 993
Deleting a Key Zone 994
About Key zones, assigned and unassigned samples 994
Adding sample(s) to a Key Map 994
Setting the Root Key 995
Removing sample(s) from a Key Map 995
Removing all unassigned samples 995
Rearranging samples in a Key Map 995
Setting Sample Level 995
Tuning samples 995
Looping Samples 996
About the Solo Sample function 996

Automap Samples 997
Mapping samples without Root Key or Tuning information 997
How Mapping Information is saved 997

NN-19 synth parameters 998
The Oscillator Section 998
The Filter Section 999
Envelope Section 1000
LFO Section 1001

Play Parameters 1003
Velocity Control 1003
Pitch Bend and Modulation Wheels 1003
Legato 1004
Retrig 1004
Portamento (Time) 1004
Setting Number of Voices - Polyphony 1004
Voice Spread 1005
Low Bandwidth 1005
Controller Section 1005

Connections 1006
Audio Outputs 1006
Mono Sequencer Control 1006
Modulation Inputs 1006
Modulation Outputs 1006
Gate Inputs 1007

Pangea World Instruments 1009

Introduction 1010

Panel overview 1010

Using Pangea 1011
Loading and saving patches 1011

Global performance and "play" controls 1011

Panel controls 1012
The Instruments section 1012
The Filter section 1017
The Amp section 1019
The Delay section 1021
The Reverb section 1022

Connections 1024
Sequencer Control inputs 1024
Modulation Inputs 1024
Audio Out 1024

Polytone Dual-Layer Synthesizer 1025

Introduction 1026

Panel overview 1027

Signal flow 1028

Playing and using Polytone Dual-Layer Synthesizer 1029
Loading and saving patches 1029
Global output controls 1029
Global performance and "play" controls 1029
Layer controls 1030

Panel reference 1032
Glide 1032
Wheels 1033
P.Bend Range 1033
The Oscillator section 1034
The Mixer 1036
The Filter section 1036
The Filter Envelope section 1039
The Amp section 1040
The Amp Envelope section 1040
The Mod LFO section 1042
The Mod Envelope section 1043
The Global LFO section 1044
The Chorus section 1045
The Reverb section 1045

Connections 1046
Sequencer Control 1046
Mix/Morph 1046
CV Modulation inputs 1046
Audio Output 1046
Wheels 1046

Radical Piano 1047

Introduction 1048
The pianos 1048

Using Radical Piano 1050
Loading and saving patches 1050
Selecting piano sound sets 1050

Character 1050
Volume 1051
Velocity Response 1051
Tune 1052
Sustain 1052
Resonance 1053
Envelope 1053
Mechanics 1054
EQ 1054
Ambience 1055
Output 1055

Connections 1056
Sequencer Control 1056
Modulation In 1056
Audio In 1056
Audio Out 1056

Additional external control 1057

Redrum Drum Computer 1059

Introduction 1060

Sampling in Redrum 1060

About file formats 1061

Using patches 1062
Loading a patch 1062
Checking the sounds in a patch 1062
Creating a new patch 1063
Creating an empty patch 1063

Programming patterns 1064
Pattern basics 1064
Pattern tutorial 1065
Setting pattern length 1066
Setting pattern resolution 1067
Step dynamics 1067
Pattern Shuffle 1068
Flam 1068
The Pattern Enable switch 1069
The Enable Pattern Section switch 1069
Pattern functions 1070
Chaining patterns 1070
Converting Pattern data to notes in the main sequencer 1071

Redrum parameters 1072
Drum sound settings 1072
Global settings 1075

Using Redrum as a sound module 1076

Connections 1077

Rytmik Drum Machine 1079

Introduction 1080

Panel overview 1081

Signal flow 1082

Global controls 1082
Loading and saving patches 1082

The Drum Channel sections 1083
Auditioning samples 1083
Selecting a Drum Channel 1083
Muting and soloing Drum Channels 1083
Setting the Drum Channel volumes 1083
Setting the Send Effect levels 1084

The Sample Playback section 1084
Selecting Samples 1084
Setting the Sample Start and End 1085
Setting the Panning 1085
Setting the Pitch 1085
Setting Fade In and Fade Out 1086

The Insert Effects section 1086
Distortion 1086
Low Cut and Hi Cut Filter 1087

The Master FX section 1087
Delay 1088
Reverb 1089
Compressor 1090
Master Pitch 1092
Master Reverb 1092
Master Filter 1092
Master Volume 1093

Connections 1094
Drum Gate In/Out 1094
Separate Outputs 1094
Main Output L & R 1094

Subtractor Synthesizer 1095

Introduction 1096
Loading and Saving Patches 1096

The Oscillator Section 1097
Oscillator 1 Waveform 1097
Setting Oscillator 1 Frequency - Octave/Semitone/Cent 1099
Oscillator Keyboard Tracking 1099
Using Oscillator 2 1099
Oscillator 2 Waveform 1100
Noise Generator 1100
Phase Offset Modulation 1101
Frequency Modulation (FM) 1102
Ring Modulation 1103

The Filter Section 1104
Filter 1 Type 1104
Filter 1 Frequency 1107
Resonance 1107
Filter Keyboard Track (Kbd) 1107
Filter 2 1108

Envelopes - General 1109
Amplitude Envelope 1110
Filter Envelope 1110
Mod Envelope 1111

LFO Section 1112
LFO 1 Parameters 1112
LFO 2 Parameters 1113

Play Parameters 1114
Velocity Control 1114
Pitch Bend and Modulation Wheels 1115
Legato 1116
Retrig 1116
Portamento (Time) 1116
Setting Number of Voices - Polyphony 1117
About the Low Bandwidth button 1117

External Modulation 1117

Connections 1118
Audio Output 1118
Sequencer Control 1118
Modulation Inputs 1119
Modulation Outputs 1119
Gate Inputs 1119

Thor Polysonic Synthesizer 1121

Introduction 1122
Loading and Saving Patches 1122

Thor elements 1123

The Controller panel 1124

Using the Programmer 1126
Basic connections - a tutorial 1127
The Oscillator section 1130
Mix section 1137
Filter slots 1137
Shaper 1141
Amp section 1141
LFO 1 1142
Envelope sections 1143
Global section 1144

Modulation bus routing section 1146

Step Sequencer 1155
Basic operation 1155

Connections 1159

Alligator Triple Filtered Gate 1161

Introduction 1162
About the Patch format 1162

Overview and signal flow 1162

Parameters 1164
Common effect device parameters 1164
Pattern section 1164
Gate and Amp Envelope 1165
Filters and Modulation 1166
Effects 1168
Mix controls 1170

Audio connections 1171
Main Inputs and Outputs 1171
Separate Outputs 1171

CV connections 1172
Gate inputs 1172
CV Modulation inputs 1172
Gate Outputs 1172
LFO CV Out 1172

The built-in patterns 1173

Methods and Tips 1173
Playing the Alligator live 1173
Playing the gates from Matrix patterns 1174
Controlling other sounds and effects 1174

Audiomatic Retro Transformer 1175

Introduction 1176

Using Audiomatic Retro Transformer 1176
Gain 1176
The Presets 1177
Transform 1178
Dry/Wet 1178
Volume 1179

Connections 1179
CV Modulation In 1179
Input L&R 1179
Output L&R 1179

BV512 Vocoder 1181

Introduction 1182
How does a vocoder work? 1182

Setting up for basic vocoding 1183
Vocoding vocals in real-time 1183
Vocoding an existing audio track 1185

Using the BV512 as an equalizer 1187

BV512 parameters 1188

Connections 1189

Automation 1190

Tips and tricks 1191
Choosing a carrier sound 1191
Choosing a modulator sound 1192
Using the modulator as carrier 1193
Controlling the Hold function 1194
Using the individual band level connections 1194
“Playing” the vocoder from a MIDI keyboard 1195
Using the BV512 as a reverb 1196

Channel Dynamics Compressor & Gate 1199

Introduction 1200

Panel reference 1200
Global controls 1200
The Compressor section 1201
The Gate/Expander section 1202
External Sidechain 1203

Connections 1204
CV Outputs 1204
Sidechain Input Left & Right 1204
Input Left & Right 1204
Output Left & Right 1204

Channel EQ Equalizer 1205

Introduction 1206

Panel reference 1206
Global controls 1206
The Filter section 1206
The Equalizer section 1207

Connections 1210
CV Inputs 1210
Input Left & Right 1210
Output Left & Right 1210

Master Bus Compressor 1211

Introduction 1212

Panel reference 1212
Global controls 1212
Compression controls 1213
External Sidechain 1214

Connections 1215
Comp Gain Reduction 1215
Sidechain Input Left & Right 1215
Input Left & Right 1215
Output Left & Right 1215

The MClass Effects 1217

The MClass effects 1218

The MClass Equalizer 1219

The MClass Stereo Imager 1220

The MClass Compressor 1221

The MClass Maximizer 1224

Neptune Pitch Adjuster and Voice Synth 1225

Introduction 1226
Typical use cases 1226

Overview and basic concepts 1227
Sections overview 1227
The display 1228

Setting up for pitch processing 1228
Setting up for pitch processing of recorded audio tracks 1228
Setting up for pitch processing of “live” audio 1229

Using pitch correction 1229
Basic settings for pitch correction 1230
Using automatic pitch correction 1231
Using manual pitch correction 1235

Using pitch shifting (Transpose) 1236

Using Formant control 1237
What are formants? 1237
Using the Formant function 1238

Using the Voice Synth 1238

Panel parameters 1239
Level Meter and Bypass/On/Off switch 1239
Bend and Vibrato wheels 1239
Input signal type 1240
MIDI Input 1240
Pitch Adjust section 1241
Transpose section 1242
Formant section 1242
The Output Mixer section 1242

Connections 1243
Sequencer Control 1243
CV In 1243
CV Out 1244
Audio In 1244
Voice Synth Out 1244
Audio Out 1244

Pitch adjustment tips and tricks 1245
Using automation for temporary pitch correction 1245
Hard pitch correction of a vocal track 1246
Pitch correction with changed voice character 1246
Octave dub 1246
Pitch-shifting drums (non-pitched input) 1246
Speech effects 1247
About "freezing" pitch adjustments on audio tracks 1247

Pulveriser 1249

Introduction 1250
About the Patch format 1250

Parameters 1250
Common effect device parameters 1250
Signal Routing selector 1251
The Squash section 1252
The Dirt section 1252
The Filter section 1253
The Tremor section 1254
The Follower section 1255
Blend 1256
Volume 1256

Modulation inputs and outputs 1257
CV Modulation inputs 1257
Audio Modulation inputs 1257
CV Modulation outputs 1258

Demolition tips and tricks 1258
Beef up your sounds 1258
Make your pads tremble 1258

Quartet Chorus Ensemble 1259

Introduction 1260

Panel reference 1260
Global controls 1260
Chorus 1261
BBD 1263
FFT 1264
Grain 1266

Connections 1268
CV Input 1268
Input Left & Right 1268
Output Left & Right 1268

Ripley Space Delay 1269

Introduction 1270

Panel overview 1270

Signal flow 1271

Panel reference 1272
Loading and saving patches 1272
The Delay section 1272
The Feedback Filter section 1274
The Reverb section 1276
The Noise section 1276
The Distortion section 1277
The Digital section 1277
The EQ section 1278
The Output section 1279
The Ducker section 1279
The Modulation and Modulation Matrix sections 1279

Connections 1284
Audio jacks 1284
CV Inputs 1284
CV Outputs 1285

RV-9 Reverb Station 1287

Overview 1288

Panel reference 1289
Loading and saving patches 1289
Common parameters 1289
Ducking section 1290
Predelay section 1291
EQ section 1291
Shimmer section 1292
Room/Hall/Arena/Cathedral Reverb parameters 1292

Spectral Reverb parameters 1293
Granular Reverb parameters 1294
Echoverb parameters 1295
Plate parameters 1295
Spring parameters 1295

Connections 1296
Audio jacks 1296
CV Inputs 1296
CV Output 1296

RV7000 Mk II Advanced Reverb 1297

Overview 1298
About the Patch format 1298
Connections 1298
The main panel 1299
The Remote Programmer 1299

Reverb algorithms and parameters 1300
Common effect device parameters 1300
About the main panel parameters 1300
Selecting an algorithm 1300
Small Space 1301
Room 1301
Hall 1302
Arena 1302
Plate 1302
Spring 1302
Echo 1303
Multi Tap 1303
Reverse 1304
Convolution 1305

The EQ section 1308

The Gate section 1309

CV Inputs 1310

Scream 4 Sound Destruction Unit 1311

Scream 4 Sound Destruction Unit 1312
About the Patch format 1312

Parameters 1312
Common effect device parameters 1312
Damage section controls 1312
Description of the various Damage Type algorithms 1313
Cut section (EQ) 1314
Body section 1314
About the envelope follower 1315
About the Master level control 1315
CV inputs and outputs 1316

Screamy tips and tricks 1317
Creating a heavy drum sound 1317
Warming up a mix with the Tape effect 1317
Using the Body section as a sound enhancer/phaser/wah 1317
Emulating vintage digital gear 1318
Creating a real dynamic wah effect with the envelope follower 1318

Sidechain Tool 1319

Introduction 1320

Panel reference 1320
Loading and saving patches 1320
Auto Pump/Trigger/Sidechain mode switch 1320
Ducking curve parameters (Auto Pump and Trigger modes) 1320
Auto Pump mode specific parameters 1322
Trigger mode specific parameters 1322
Sidechain mode specific parameters 1323
Common parameters for all modes 1325

Connections 1325
CV Input 1325
CV Output 1326
Sidechain Input Left & Right 1326
Input Left & Right 1326
Output Left & Right 1326

Softube Amps 1327

Introduction 1328
Basic usage 1328
Front panel 1329

Using the Softube Amps 1330
Loading and saving patches 1330
Selecting Amp and Cabinet model 1330
About the Amp and Cabinet models 1331
Amp panel controls 1332
Connections 1333

Stereo Tool 1335

Introduction 1336

Panel reference 1336
Widening 1336
Low Bypass 1336
Frequency Adjust 1336
Mono 1337

Connections 1338
CV In 1338
Input Left & Right 1338
Output Left & Right 1338

Sweeper Modulation Effect 1339

Introduction 1340

Panel reference 1340
Global controls 1340
The Phaser 1343
The Flanger 1346
The Filter 1348
LFO 1351
The Envelope Modulator 1352
The Audio Follower Modulator 1355

Connections 1356
CV Input 1356
CV Output 1356
Input Left & Right 1357
Output Left & Right 1357

Synchronous Timed Effect Modulator 1359

Introduction 1360

Panel overview 1361

Using Synchronous 1362
Loading and saving patches 1362
Drawing and assigning modulation curves - a tutorial 1362
Editing modulation curves - a tutorial 1364

Panel reference 1365
The display section 1365
Modulation controls 1368
Dist section 1369
Filter 1370
Delay 1372
Reverb 1374
Level 1375
Master Controls 1375

About automation of display section parameters 1376

Connections 1377
CV In 1377
CV Out 1378
Audio In L&R 1378
Audio Out L&R 1378

The Echo 1379

Introduction 1380
About the Patch format 1380

Parameters 1380
Common effect device parameters 1380
The Mode section 1381
The Delay section 1382
The Feedback section 1383
The Color section 1384
The Modulation section 1385
The Output section 1386

CV/Gate inputs 1387

The Breakout Jacks 1387

Tips and Tricks 1388
Using the Roll function 1388
Creating "pitched" delay 1388
Distorted external feedback 1388

Half-Rack Effects 1389

Common effect device features 1390

DDL-1 Digital Delay Line 1392

CF-101 Chorus/Flanger 1393

Spider Audio Merger & Splitter 1395

Spider CV Merger & Splitter 1397

RV-7 Digital Reverb 1401

D-11 Foldback Distortion 1403

ECF-42 Envelope Controlled Filter 1404

PH-90 Phaser 1408

UN-16 Unison 1410

COMP-01 Auto Make-up Gain Compressor 1411

PEQ-2 Two Band Parametric EQ 1412

The Combinator 1413

Introduction 1414

Combinator overview 1415

Creating a Combinator device 1416
Creating an empty Combinator device 1416
Creating a Combinator by combining devices 1416
Creating a Combinator by browsing patches 1416

About internal and external audio connections 1417
External audio connections 1417
Internal audio connections 1417
About External Routing 1418

Adding devices to a Combi 1419
Creating new devices in a Combi 1419
Adding existing devices to the Combi from the rack 1420
Combining two Combis 1420

Combinator handling 1421
Moving the entire Combi 1421
Moving devices within a Combi 1421
Moving devices out of a Combi 1421
Deleting devices in a Combi 1421
Uncombining devices 1421

Sequencer tracks and playing Combis 1421

Configuring the Combinator panel 1422
Opening the Configuration panel 1422
Setting the front panel size 1423
Selecting front panel background color 1423
Selecting a backdrop image 1423
Selecting, positioning and editing front panel controls 1425

Assigning panel controls to parameters in the Editor 1429
Key Mapping instrument devices 1429
Setting Velocity Ranges for instrument devices 1431

Using Modulation Routing 1432
About Rotary/Slider and Switch controls 1433
About the CV Inputs 1433
Assigning panel controls to device parameters 1433

CV Connections 1438
Sequencer Control inputs 1438
Control CV In 1438
Wheel CV In and Source CV In 1439

Gain Tool 1441

Introduction 1442

Signal flow 1442

Panel reference 1442
The input mode switch 1442
The Gain input mode 1443
The Mix input mode 1443
The X-Fade input mode 1443
The output mode switch 1444
The Width/Pan output mode 1444
The Dual Pan output mode 1444
The Router output mode 1445
The Output buttons 1445
The output level meters 1445

Connections 1446
Audio Inputs 1446
CV Inputs 1446
Audio Outputs 1446

The Line Mixer 6:2 1447

Introduction 1448

Channel parameters 1448

The Auxiliary Return section 1448

Master level 1448

Connections 1449

Matrix Pattern Sequencer 1451

Introduction 1452
About the three Output types 1452

Programming patterns 1453
Pattern basics 1453
Tutorial 1456
Using Curve Patterns 1458
Setting Pattern Length 1459
Using Tied Notes 1459
Setting Pattern Resolution 1460
Pattern Shuffle 1460
Pattern Mute 1460
Pattern Functions 1461
Chaining Patterns 1461
Converting Pattern data to notes in the main sequencer 1462

Example usage 1463
Using the Matrix for modulation 1463
Programming “Acid Style” lead lines 1464
Triggering samples 1464

Mixer 14:2 1465

Introduction 1466

The Channel Strip 1466
Channel Strip Controls 1467

The Mixer signal flow 1468

About the EQ modes 1468

The Auxiliary Return Section 1469

The Master Fader 1469

Connections 1469

Chaining several Mixer 14:2 devices 1471

Pulsar Dual LFO 1473

Introduction 1474

Panel parameters 1474
LFO 1&2 common parameters 1474
LFO 1 specific parameters 1476
LFO 2 specific parameters 1476
LFO 2 to LFO 1 modulation parameters 1476
Envelope 1477
KBD Follow 1479

Modulation inputs and outputs 1480
LFO 1&2 input sections 1480
LFO 1&2 output sections 1481
Output LFO 1+2 1481
Envelope connections 1481

Tips and Tricks 1482
Patch between LFO 1 and LFO 2 on the back for more flexibility 1482
Using Pulsar as a monophonic synth 1482

RPG-8 Arpeggiator 1483

Introduction 1484

Using the RPG-8 1485
Setting up 1485
Recording MIDI note data for the RPG-8 - simple tutorial 1487
Rendering arpeggio notes to track 1489

RPG-8 Parameters 1490
MIDI-CV Converter parameters 1490
Arpeggiator parameters 1491
Pattern editor 1493

CV connections 1495

Tips and tricks 1498

Menu and Dialog Reference 1499

Reason menu (macOS) 1500

File menu 1501

Edit menu 1505
Settings – User Interface 1524
Settings – Browsing 1527
Settings – Audio 1530
Settings – MIDI 1535
Settings – Sync 1538
Settings – Other Controls 1539
Settings – Folders 1541
Settings – Account 1542

Create menu 1543

View menu 1544

Options menu 1546

Window menu (Windows version) 1550

Window menu (macOS version) 1551

Help menu 1552

Key Commands 1553

About the Key Commands chapter 1554
General keyboard shortcuts 1554
General modifier keys 1555
Transport keyboard shortcuts 1555
Sequencer keyboard shortcuts 1556
Sequencer modifier keys 1557
Arrow keys 1558
Save dialog keyboard shortcuts 1558
On-screen Piano Keys keyboard shortcuts 1558
NN-19 modifier keys 1559
NN-XT keyboard shortcuts 1559
NN-XT modifier keys 1559
Dr. Octo Rex keyboard shortcuts 1559

Dr. Octo Rex modifier keys 1559
Redrum keyboard shortcuts 1560
Redrum modifier keys 1560
Kong modifier keys 1560
Matrix keyboard shortcuts 1560
Matrix modifier keys 1560
RPG-8 keyboard shortcuts 1561
MIDI Out Device keyboard shortcuts 1561
Europa modifier keys 1561
Grain modifier keys 1561
Sweeper modifier keys 1561
Mimic modifier keys 1561

Index 1563



Chapter 1
Introduction



Welcome!

This is the Operation Manual for Reason Version 14 music production software from Reason Studios. The information in this manual is also available as html files from the Reason Help menu. The separate Operation Manual for Reason Rack Plugin can be downloaded here.

Don't forget to check out the Video Tutorials web site, which can be accessed from the Reason Help menu.

Also, be sure to regularly check out www.reasonstudios.com for the latest news!

A few words from the writer

This is the last Reason manual I'll be writing as part of Reason Studios. I started back in 2007 (when it was still Propellerhead Software), and the first manuals I worked on were for Record 1.0 and Reason 5. Since then, I've had the chance to write manuals for pretty much all our products—which has been an amazing ride!

I've always tried to keep things clear and easy to follow, whether you're just getting started or you've been using Reason for years. I hope that's come through.

Just wanted to say a big thanks for all these great years—and I hope you keep enjoying making music with Reason!

Fredrik Hylvander, Stockholm, May 2026

About this chapter

The Introduction chapter describes some of the general conventions used throughout the Reason Operation Manual. It also contains instructions on how to utilize the Reason authorization system.

About this manual

In this Operation Manual, all aspects of the Reason program are described in detail. The first chapters deal with general methods and techniques, e.g. how to connect audio sources, mix and record. Then follow descriptions of all rack devices in Reason.

! **The information in this document is subject to change without notice and does not represent a commitment on the part of Reason Studios AB.**

About the Reason operating system versions

Reason comes in two platform versions: one for Windows 10/11 (64-bit) and one for macOS 11 (Big Sur) (64-bit) or later. The screenshots in this manual were taken from both platform versions of Reason. Since the program layout is more or less identical in these versions, there shouldn't be any problem following the instructions.

Conventions in the manual

This manual describes both the Windows and macOS versions of Reason; wherever the versions differ this is clearly stated in the text.

Text conventions

The text conventions are pretty straightforward. The examples below describe when certain text styles are used:

▶ **This style instructs the user to perform the task(s) described in the sentence.**

! **This text style means IMPORTANT INFORMATION. Read carefully to avoid problems!**

▶ **This text style is used for tips and additional info.**



Key command conventions

In the manual, computer keyboard commands are indicated with brackets. For example:

▶ **Hold down [Shift] and press [C].**

However, some modifier keys are different on Windows and Mac computers. Whenever this is the case, the manual separates the commands with "(Win)" and "(Mac)" indications as in the following example:

▶ **Hold down [Ctrl](Win) or [Cmd](Mac) and press [S] to save your song.**

References to context menus

Whenever the manual instructs you to select an item from the "context menu", it means that you should right-click (or [Ctrl]-click if you're using a Mac with single-button mouse) on the specific area, section or device, and then select the item from the pop-up menu that appears - the context menu. The item list in context menus varies depending on where in the application you click. See "Context menus" for an overview of the context menus in Reason.

Frames and circles (call-outs)



In pictures throughout this manual there might be circles and/or rectangles highlighting certain areas or objects. These are indicated by filled lines according to the examples in the picture above. Sometimes these highlighting frames/circles might also be accompanied by descriptive texts. The different colors of the frames and texts are only to enhance the contrast to the background pictures.

Dashed arrows



A dashed arrow in a picture indicates the directions in which the pointer (or other tool) should be dragged to perform the desired operation. The example in the picture above shows in which directions (up and down) to drag the pointer to change the knob's setting.

About the Authorization system

Reason uses an authorization system designed to be as flexible as possible, while at the same time providing the best possible copy protection for the product.

- **The core of the authorization system is your Reason Studios account (and license number, if you are using a licensed version of Reason).**

Registering Reason (licensed version only)


To be able to run your licensed version of Reason, the program must be registered to your account on the Reason Studios web site.

▶ **If you purchased a Reason license in a music store, follow the instructions you received from the shop.**

! **If you purchased Reason directly from the Reason Studios Shop web site, the Reason license has already been automatically registered to your user account and you can use Reason by running it on a computer connected to the Internet.**

Authorizing Reason

! **Note that Internet connection is initially required for the procedures described below.**



▶ **Launch Reason and enter you Username/e-mail address and Password for your Reason Studios account and click the Log in button.**
Reason launches in Authorized Mode.

- **The first time you log in to the "Welcome to Reason" login dialog, the program will automatically store your user credentials.**
  The next time you launch Reason it will start without showing the login dialog. This also automatically enables off-line use, allowing Reason to run even if you have no Internet connection. Reason will then run off-line for a month. This period is continuously renewed when you run Reason (licensed or Annual Reason+ subscription) with an Internet connection. You do not have to do anything manually, except connecting to the Internet once a month.

Logging out from Reason

Logging out means removing the stored login credentials - do this if you're not going to use Reason on that computer, or if you need to log in to another Reason Studios user account.


- ▶ **In Reason, select "Quit/Exit and Log out" from the Reason (Mac) or File (Windows) menu.**
  The next time you run Reason, you will need to enter your Username/e-mail and password in the "Welcome to Reason" dialog again. Internet connection is then required again.

Authorizing a computer for long-term off-line use

In addition, if you have an Annual (yearly) Reason+ subscription or own a licensed version of Reason, you can authorize your computer for long-term off-line use. This can be useful if you are traveling or working in a studio without Internet access, etc. The long-term authorization allows for staying off-line on the authorized computer for one (1) year. If you are a Reason+ subscriber you are limited by the subscription end date, though. In most situations, authorizing a computer for long-term use is not necessary, though.

Authorizing Reason for long-term off-line use

1. **Open Reason's Settings on the Reason (Mac) or Edit (Win) menu, and click the Account tab.**
2. **Click the "Add long-term authorization" button:**




- **The authorization expiry date for your computer is now shown in the Offline Authorization section.**
- **You can authorize up to three (3) computers for long-term off-line use.**

Removing a long-term authorization for a computer

If you've already long-term authorized three computers and would like to authorize another computer, you will need to remove the authorization for one of the computers first:

1. **Launch Reason on one of the computers that already has a long-term authorization.**
2. **Open Reason's Settings and click the Account tab.**
3. **Click the "Remove long-term authorization" button:**



- **If you can no longer access any of your authorized computers, you need to contact support to have them remove the authorization(s). This can be done here.**


What happens if an authorization expires?

- **If a Reason authorization should expire during a session, the program will automatically enter Demo Mode, see "Running Reason in Demo Mode".**
  You can continue to work, and save your songs as usual.
- **When you reconnect to the Internet and log in, Reason will automatically revert to authorized mode (provided that you have a valid Reason license or a Reason+ subscription).**

Running Reason in Demo Mode

If you don't have a Reason license, a Reason+ subscription, or if you don't have an authorized computer and don't have a working Internet connection, you can run Reason in Demo Mode:

1. **Launch Reason.**
   The following window appears:



2. **Click "Run in Demo Mode".**
   Reason launches in Demo Mode.

   The Demo Mode LED lights up to the right on the Transport Panel:



Running Reason in Demo Mode allows you to perform all operations as in authorized mode, with three exceptions:


- **You cannot export audio or bounce mixer channels to disk.**
- **You will only have access to the built-in devices in Reason, not to any Rack Extensions installed by the Reason Companion app.**
- **You cannot open songs.**
  The only songs that can be opened in Demo Mode are the dedicated demo songs (file extensions ".rsndemo" (Reason Demo Song). See "Opening a Reason Demo Song".

Managing additional content


Reason comes with some additional content (Rack Extensions and ReFills) that you can download separately, either right after the Reason installation or at a later point. To download additional content, proceed as follows:

! **Note that this procedure requires Internet connection!**

1. **Open the Reason Companion app and click the Devices tab.**
2. **At the top of the Devices tab, install the desired additional device(s).**
   Alternatively, click the "Install All" button to install all Rack Extensions in one go:



3. **Then, click the "ReFills" tab and install the desired additional ReFill(s).**
   Alternatively, click the "Install All" button to install all ReFills in one go:



4. **After installation, restart Reason for the installed items to become available.**

The additional content is stored on your computer as follows:

- **The additional Rack Extension devices are stored in the following folders:**
  Windows: C:\Users\[your.user]\AppData\Roaming\Propellerhead Software\Optional REs
  macOS: ~/Library/Application Support/Propellerhead Software/Optional REs
- **The additional ReFills are stored in the "Music > Reason Studios > ReFills" sub-folder.**


About automatic program updates

Reason supports automatic program updates (within each major release). When you launch Reason it automatically checks for new updates on the Reason Studios web site - provided your computer is connected to the Internet.

If you are working with Reason off-line, and then connect to the Internet, you can manually check for updates by selecting the "Check for Updates..." item on the Reason (Mac) or Help (Win) menu.


! **Note that the automatic program update function only works within each major Reason release version, i.e. there will be no automatic update between Reason 13.x and 14.x.**

Each time a new Reason version is available, an "update bar" appears at the top of the Reason song document after launch. In the update bar you can choose to either download the update now or later:




If you click "Not Now" Reason will wait a number of days before it checks for updates again.

If you click "Download" the update is downloaded and prepared for installation. A download progress bar appears in the update bar:



- ▶ **If you want to abort the download, click "Cancel".**
- ▶ **If you want to hide the download progress bar, click "Hide".**

When the download is ready, two options are available:



- ▶ **Click "Restart and Install Now" to install the update and launch the updated version of Reason.**
- ▶ **Click "Install on Quit" to continue running the current Reason version and install the update after you quit the current Reason session.**
- ▪ **When you launch Reason after an update, the blue "Open Companion" banner will appear.**
  Click to open the Reason Companion app. When you open Reason the next time, the banner will be gone.


Reassigning the Function Keys in macOS

When you work with Reason, you will do a lot of navigating between the three main areas - the main mixer, the rack and the sequencer. The quickest way to switch between these areas is to use the function keys F5, F6 and F7 (see "Navigating between the areas" for details). Also, the F2, F3, F4, F8 and F9 keys are shortcuts for showing and hiding the Spectrum EQ window, Device Palette, On-screen Piano Keys window, Edit Area and the Browser, respectively.


However, on many Macintosh models (especially MacBooks), the function keys double as hardware control buttons. For example, they might control the volume of the built-in speaker, the display brightness or keyboard backlight. To make these keys actually work as function keys for software such as Reason, you need to hold the "Fn" key while pressing them.

This can work perfectly OK, but to get the best workflow in Reason we recommend that you change this behavior, so that pressing e.g. the F5 key actually sends "F5" to Reason (and you hold down the Fn key to get the hardware control functions instead). Here is how you change this:


1. **Open the System Preferences in macOS and select the "Keyboard" item.**



2. **Click the "Keyboard Shortcuts..." button:**



3. **Select the "Function Keys" tab and make sure "Use F1, F2, etc. keys as standard function keys" is switched on.**
   Now you can use F2-F8 for controlling functions in Reason. To use hardware control features such as volume and display brightness, you need to hold down the "Fn" key before pressing the function keys.



Some function keys might also be pre-assigned to macOS keyboard shortcuts, which will have priority over software such as Reason. This is easily changed:

4. **Now you're finished with the settings and can exit System Preferences.**
   From now on, the function keys and keyboard shortcuts will perform their intended functions in Reason.



Chapter 2
Common Operations and Concepts




About this chapter

This chapter gives a basic overview of the Reason application and describes general methods and techniques employed throughout the Reason software. It also explains the terminology used throughout the program, manuals and help files.

Windows, areas and basic navigation

Document window overview



A Reason document window with the Device Palette, Track Panel, Sequencer and Transport Panel areas.

The Reason document window is divided into five main areas:

- **The Top Bar**
  Here are buttons for showing/hiding various windows and panels. You can also access the Settings and Help here.
- **The Device Palette**
  The Device Palette is where you find and can create devices in your Reason document.
- **The Track Panel**
  The Track Panel shows how the devices in the selected Sequencer track are organized. You can also add devices to the Track Panel (as an alternative to adding devices to the Rack).
- **The Sequencer**
  The Sequencer is where you record your audio and instrument tracks. Here you can also record automation of device parameters in the Rack and of channel strip parameters in the Main Mixer.
- **The Transport Panel**
  Below the Sequencer is the Transport Panel, where all sequencer transport controls are located.

Application Zoom

It's possible to choose a suitable zoom level for the Reason application. This can be useful if you are using a very high-resolution screen and want to make Reason larger. Since all built-in rack devices and most Rack Extensions are high-resolution, you will not lose any image quality when you enlarge the application.

- ▶ **Select "Application Zoom >" from the View menu and then select the desired zoom factor.**
- ! **Note that the very first time you select a new Application Zoom level, all devices in the song will recalculate their high-resolution panels in the background, which could take a little while.**

Device Palette overview

The Device Palette to the left in the document window (and also in the Rack window, if the Rack is detached in a separate window) features short-cuts for creating devices:



The Device Palette with the Instruments palette selected.

- ▶ **Press [F3] to toggle between Show and Hide Device Palette.**
  You can also click the Devices button at the top of the document window to show/hide the Device Palette.
- ▶ **Hold [Cmd]+[Shift](Mac) or [Ctrl]+[Shift](Win) and press [F] set focus to the filter text field in the Device Palette.**
- ▪ **See "The Device Palette", "About using the Device Palette when the Rack is in a separate window" and "Creating devices" for information on how to use the "Device Palette" functions.**

Track Panel overview

The Track Panel to the left of the Sequencer features short-cuts for adding Rack devices to the selected sequencer track:



Track Panel button (Show/Hide)

Sequencer track name

Player section

Instrument section

Effects section (Effects attached directly to the Instrument)

Insert FX section (in Mix Channel)

Send Effects section


Mixer Fader section

Channel routing selector

The Track Panel, which shows the device configuration for the currently selected (instrument) sequencer track.

- ▶ **Click the Track Panel button, or Select Show Track Panel from the View menu, to show/hide the Track Panel.** See "The Track Panel" for more details.
- ▪ **The Track Panel for a selected audio track or Output Bus channel only has Insert FX, Sends, Mixer Fader and Channel routing sections.**

The Sequencer



The Sequencer with a number of recorded audio tracks.


To the left in the Sequencer, all tracks in the Reason song are listed in the Track List. By clicking on a track in the Track List you select the track for playback from a connected MIDI master keyboard and/or for recording.

At the top to the left is the Toolbar, with various sequencer editing tools.

The big center section of the Sequencer is called the Arrangement Pane. Here is where all recorded sequencer data is displayed in Clips.


You can scroll in the Sequencer by using the Track scrollbar to the right and the Song Navigator at the bottom of the Sequencer - see "Scrolling" and "Zooming in the Sequencer".

- **If the Rack or Mixer are shown, you can press the [F7] button to see the Sequencer only. If the document window is split in two or more areas you can also double click the Sequencer Divider to maximize the Sequencer area.**



For more details about the sequencer, refer to "Sequencer Functions".

The Transport Panel



At the bottom of the Reason Song window is the sequencer Transport Panel. From here you control the sequencer transport functions, such as Rewind, Fast Forward, Stop, Play and Record. You can also set Tempo and Time Signature and various other parameters.


The Transport Panel is always available together with the Sequencer.

To the right on the Transport Panel are indicators for Audio In and Out levels, DSP Load, Disk Overload, Audio Calculation, Demo Mode and Automation Override status.

- **The Transport Panel can be shown/hidden on the View menu.**

For more details about the Transport Panel, please refer to "Transport Panel details".

The ReGroove Mixer



To the right on the Top Bar is the "Groove" button. Clicking this will bring up the ReGroove Mixer.



The ReGroove Mixer is used for adding advanced grooves to your instrument tracks in the Sequencer.

- **Click the Groove button in the top bar to show/hide the ReGroove Mixer.**

For more details about the ReGroove Mixer, please refer to "The ReGroove Mixer".

The Main Mixer

The Main Mixer can be shown in the document window or as a separate floating window.

- **Choose your preferred way of viewing the Mixer with the setting "Show Mixer in Separate Window" on the View menu.**
- **Click the Mixer button in the top bar of the Document window, or press [F5], to show/hide the Main Mixer.**



If "Show Mixer in Separate Window" is on, it will open in a separate, floating window. If not, it will open as an area in the document window:



The Main Mixer with the Fader sections currently scrolled into view.

- **To hide the Mixer, close its window, click the Mixer button or press [F5] again.**
  When the Mixer window has focus, you can quickly close it by pressing [Esc].

In the Main Mixer, all channel strips of the Reason song are visible. You can scroll vertically in the Main Mixer by clicking and dragging inside the frame in the Channel Strip scrollbar to the right. This way you will be able to access all channel strip parameters. If you have a lot of channels in your song you can also scroll horizontally by clicking and dragging the Mixer scrollbar at the bottom of the Main Mixer.

- **Note that you can use the Track Panel to change level, pan and other crucial mixer settings for the selected track. Typically, you only need to open the Main Mixer when you want to make detailed changes or mix several channels at the same time.**

For more details about the Main Mixer, please refer to "The Main Mixer" chapter.

The Rack

The Rack is where all the devices in your Song (instruments, effects, Players, etc) are found. It can be shown in the document window or as a separate window.

- **Choose your preferred way of viewing the Rack with the setting "Show Rack in Separate Window" on the View menu.**
- **Click the Rack button in the top bar, or press the [F6] function key, to show/hide the Rack area/window.**




If "Show Rack in Separate Window" is on, it will open in a separate, floating window. If not, it will open as an area in the document window:



- **To hide the Rack, close its window, click the Rack button or press [F6] again.**
  When the Rack window has focus, you can quickly close it by pressing [Esc].

By default, "Show Rack in Separate Window" is on, and the Rack will open in a separate window, showing the Rack column of the currently selected track:

- **If you want to see all columns of the Rack, click the Single Column button to exit the Single Column view:**




Now, the Rack window displays all columns of the Rack and you can scroll sideways in the window.

Please also see the "Rack per Track mode" for information about the "Rack per Track" mode.

Navigating in the Rack

- **When the Rack is in "Rack per Track" mode (see "Rack per Track mode"), you typically navigate by selecting tracks in the Sequencer track list.**
  This scrolls the Rack sideways to show the rack column for the selected track.
- **When the Rack is in one of the other modes, devices are not divided into rack columns - rather you view the rack as one big container, containing all your devices.**
  Then you can navigate by scrolling vertically or horizontally with a track pad or scroll wheel, by clicking the wooden frames and dragging in any direction or by using the Rack Navigator (see "Scrolling with the scrollbars and Navigators").



The Rack with three Rack columns next to each other.

When you have the Rack in a separate window, there can also be a second instance of the Browser and the Device Palette available to the left in the Rack window. By pressing [F9] you can toggle between Show and Hide Browser and by pressing [F3] you can toggle between Show and Hide the Device Palette. This is especially useful if you are using multiple screens.

For more details on how to work with the Rack, refer to "Working with the Rack".

Navigating between the areas

If you have de-selected both the “Show Mixer in Separate Window” and “Show Rack in Separate Windows” on the View menu, you can view all areas in the Document window:



- **Press [F5] or click the Mixer button in the top bar to open r close the Main Mixer.**
  If “Show Mixer in Separate Window” is off, it will be opened as an area in the document window. You can adjust the size of this area by dragging the divider below the mixer - this size will be remembered next time you open the Mixer area. This means that if you make the Mixer area cover the whole screen, clicking the Mixer button (or pressing [F5]) will toggle between showing the Sequencer and the Mixer.

  Alternatively, if you drag the divider so that the Mixer area only covers part of the window (showing just the fader section for example), Mixer button/[F5] will show/hide this area only.

  If “Show Mixer in Separate Window” is on, the Mixer will open in a floating window, on top of the document window. Close the Mixer window to get back to the Sequencer. If you have more than one monitor, you can also move the Mixer window to another screen, and leave it open.

- **Press [F6] or click the Rack button in the top bar to open or close the Rack.**
  If “Show Rack in Separate Window” is off, you can drag the divider to set the desired size of the Rack area whenever you open it.

  If “Show Rack in Separate Window” is on, the Rack will open in a floating window, on top of the document window. This is especially useful when you're working in Rack per Track and Single Column mode (see “Rack per Track mode”, since the Rack window is narrow enough to sit on one side of the screen, letting you navigate between rack columns by clicking in the Sequencer track list. Close the Rack window to get back to the Sequencer. If you have more than one monitor, you can also move the Rack window to another screen, and leave it open.


- **Press [F7] to show only the Sequencer area.**
  It's a quick way to get back to the Sequencer view, by closing both Rack and Mixer (regardless of whether they are shown as areas or separate windows).

! **It’s not possible to toggle between views/windows by repeatedly pressing the same function key.**

About different Themes

In Reason you can choose from a two different visual themes, i.e. how the user interface should be visually presented. The default setting is the Dark theme. The selected theme affects the Mixer, Sequencer, Browser and Transport Panel areas - the devices in the Rack are not affected by the Theme.


- **Select Settings from the Edit menu (Win) or Reason menu (Mac) and then choose the Theme on the User Interface tab:**



The selected Theme becomes active after restart of Reason:



The default "Dark" theme.




The "Light" theme.

Working with several Reason Documents


You can have several Reason songs open at the same time. Each song will appear in a separate Document window. Each Document window can be moved, minimized and resized using the standard Windows and Mac procedures.

The On-screen Piano Keys window

The On-screen Piano Keys floating window features a virtual keyboard which lets you play instrument devices without needing to have a MIDI master keyboard connected to your computer. The On-screen Piano Keys window can be accessed from the Top Bar:



- **Open the On-screen Piano Keys window by pressing [F4], or by clicking the "Keys" button to the left on the Transport Panel. Alternatively, select "Show On-screen Piano Keys" from the View menu.**
  The [F4] key can be used for toggling between showing and hiding the On-screen Piano Keys window.



The On-screen Piano Keys window in "Computer Keys" mode.

See "On-screen Piano Keys" for more information.

General window techniques

Resizing



Adjustable dividers in the Reason Document window, with the Mixer and Rack incorporated in the Document window.

Between each area in the Reason Document window are dividers that separate the areas from each other, when the Rack and/or the Mixer are incorporated in the Document window. The dividers can be adjusted, making it possible to resize the areas. The horizontal dividers between the Main Mixer and Rack, and between the Rack and Sequencer can be adjusted, as well as the vertical divider to the left of the Rack Navigator in the Rack.

When you hover with the mouse pointer on any of the horizontal dividers, a red line appears and the pointer changes to a double-arrow symbol. Clicking and dragging these dividers vertically makes it possible to resize the adjacent areas.

You can also double click the horizontal dividers to maximize the Rack and Sequencer areas respectively.

Scrolling

Reason offers a few different options for scrolling in the different areas.

Scrolling with the scrollbars and Navigators



Navigators and scrollbars in a Reason Document window, with the Mixer and Rack incorporated in the Document window.


Whenever there is information "outside" the visible screen area, you may want to scroll to the desired destination. The Reason Document window features a number of scrollbars that can be used for scrolling. The Rack Navigator is also present in the Rack.

The Device Palette, Main Mixer and the Sequencer have horizontal and vertical scrollbars.

The Rack has a Rack Navigator which can be used for scrolling both vertically and horizontally (when using more than two rack columns next to each other). The Rack Navigator can also be resized by moving the vertical "divider" to the left of the Rack Navigator. Resizing the Rack Navigator will also resize the rack devices inside the Navigator, making them easier to distinguish.

- ▶ **To scroll with the Rack Navigator, click anywhere inside the frame in the Rack Navigator and drag the frame to the desired position.**
  As the pointer enters the blue frame, it automatically switches to a hand symbol.
- ▶ **Alternatively, click anywhere in the Rack Navigator area to immediately jump to the desired position.**
- ▪ **At high zoom values in the Sequencer, you can hold [Shift] and drag the Song Navigator frame sideways to scroll with greater precision.**
- ▪ **It's also possible to scroll sideways in the Sequencer, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".**

Scrolling with the Hand tool



Scrolling with the Hand tool in the Rack.

In the Rack and Sequencer, you can also use the Hand tool for scrolling the view.

1. **In the Rack, place the pointer on a wooden side panel of a rack column.**
   The pointer will switch to a hand symbol.
2. **Click and drag the rack vertically and/or horizontally to scroll in the rack, as shown in the picture above.**

! **If the Single Column button is On, it's only possible to scroll vertically.**

- **In the Sequencer you have to manually switch to the Hand Tool by selecting it from the sequencer Toolbar.**
  With the Hand Tool selected, you can scroll in any direction on the Edit/Arrangement Pane. Refer to "Hand Tool" for more information.

Zooming in the Sequencer

In the Sequencer it's possible to zoom in and out horizontally using the Song Navigator. You can also use the Magnifying Glass Tool on the Sequencer Toolbar to zoom vertically - see "Magnifying Glass Tool". In addition to this, it's also possible to set a zoom level for the audio recordings inside the Audio Clips.

Zooming vertically in the Sequencer

▶ **To zoom in vertically in the Sequencer arrangement, and thus increase the Track height, click on the "+" magnification button at the bottom of the Track List:**



Increase the Track height by clicking the + magnification button at the bottom of the Track List.

▶ **To zoom out vertically, click on the "-" magnification button.**

- **When the Edit Area is open in the Sequencer, individual vertical zoom controls become available.**
- **You can also set individual track heights - see "Resizing tracks".**
- **It's also possible to zoom vertically using the zoom/scroll areas in the Sequencer, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".**


Waveform Zoom Mode



- ▶ **Choose between three zoom modes for the audio recording(s) inside all Audio Clips.**
- ! **The zoom modes only affect the visual presentation of the waveform, not the audio levels.**

Zooming horizontally in the Sequencer

You can also zoom in and out horizontally in the Sequencer by using the Song Navigator.



- ▶ **To zoom in and out horizontally, click and drag a Song Navigator handle sideways.**
  The pointer changes to a double arrow symbol and you can now zoom in by resizing the Song Navigator Frame.
- ▶ **[Shift]-click on a Song Navigator handle and drag horizontally to zoom in and out symmetrically.**
- ▶ **By right-clicking (Win) or [Ctrl]-clicking (Mac) inside the Song Navigator frame you can both scroll (drag sideways) and zoom (drag up or down) simultaneously.**
- ▪ **It's also possible to zoom horizontally using the zoom/scroll areas in the Sequencer, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".**

Zooming to selection



- ▶ **Click the Zoom To Selection button or press [Z] to do one of two things:**
  Zoom horizontally to fit the current selection (e.g. selected clips in the arrangement).


  Zoom out horizontally to "Show All".

"Show All" happens if there is no selection, or if you are already zoomed in on the current selection (i.e. you can press Z repeatedly and go between zoomed in and zoomed out).

"Show All" means different things depending on the mode:

- ▪ **If you're in Song mode, Show All = from the first clip to the last in song.**
- ▪ **If you're in Edit mode (with no open clip), Show All = all clips on this track.**
- ▪ **If you're in an open clip, Show All = see the whole clip.**
- ▶ **Hold down [Shift] and click the Zoom To Selection button (or press [Shift]+[Z]) to zoom to the current selection both vertically and horizontally.**

Scrolling and zooming using the Zoom/Scroll areas in the Sequencer



It's possible to zoom and scroll simultaneously in the Sequencer, using the Zoom/Scroll areas. The Zoom/Scroll areas are available both in the Arrangement Area and in the Edit Area.

! **It's important that you place the mouse pointer in the upper grey area of the Ruler/Timeline, for it to switch to the Zoom/Scroll Tool.**

1. **Move the mouse pointer to the Zoom/Scroll area in the upper gray part of the Ruler/Timeline.**
   The mouse pointer switches to the Zoom/Scroll Tool.
2. **Drag sideways to scroll in the Timeline and/or drag up/down to zoom out/in.**
   You can scroll and zoom at the same time if you like.

Scrolling and zooming using a wheel mouse

If you're using a mouse equipped with a vertical scroll wheel, this can be used for the following scrolling and zooming operations:

Scrolling in the Main Mixer with a wheel mouse

- **Spin the scroll wheel to scroll vertically in the Main Mixer.**
- **Press [Shift] and spin the scroll wheel to scroll horizontally in the Main Mixer.**

Scrolling in the Rack with a wheel mouse

- **Spin the scroll wheel to scroll vertically in the Rack.**
- **Press [Shift] and spin the scroll wheel to scroll horizontally in the Rack.**
  Note that the Rack must have at least two rack columns next to each other for this to work.

Scrolling in the Sequencer with a wheel mouse

- **Spin the scroll wheel to scroll vertically on the Edit/Arrangement Pane.**
- **Press [Shift] and spin the scroll wheel to scroll horizontally on the Edit/Arrangement Pane.**

! **Note that scrolling horizontally cannot be done when the Song Navigator frame is fully expanded.**

Zooming in the Sequencer with a wheel mouse

- **Press [Ctrl](Win) or [Cmd](Mac) and spin the scroll wheel to zoom in and out horizontally on the Edit/Arrangement Pane.**
  The "center" point/line for zooming horizontally in the sequencer is the mouse pointer, so place it where you want the zooming to commence from.
- **Press [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and spin the scroll wheel to zoom in and out vertically on the Edit/Arrangement Pane.**

Scrolling and zooming using an XY "wheel" mouse

Scrolling in all areas using an XY wheel mouse

- **Move your finger up/down to scroll vertically in all areas.**
- **Move your finger sideways to scroll horizontally in all areas.**

Zooming in the Sequencer using an XY wheel mouse

- **Press [Ctrl](Win) or [Cmd](Mac) and move your finger up/down to zoom in and out horizontally on the Edit/Arrangement Pane.**
  The "center" point/line for zooming horizontally in the sequencer is the mouse pointer, so place it where you want the zooming to commence from.
- **Press [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and move your finger up/down to zoom in and out vertically on the Edit/Arrangement Pane.**

Scrolling and zooming using an XY track pad

Scrolling in all areas using an XY track pad

- **Use two fingers and move them up/down to scroll vertically in all areas.**
- **Use two fingers and move them sideways to scroll horizontally in all areas.**

Zooming in the Sequencer using an XY track pad

- **Pinch to zoom in and out horizontally on the Edit/Arrangement Pane.**
  The "center" point/line for zooming horizontally in the sequencer is the mouse pointer, so place it where you want the zooming to commence from.
- **Press [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and pinch to zoom in and out vertically on the Edit/Arrangement Pane.**

Editing parameters

Since a large part of Reason is laid out like "real" hardware devices, such as the Main Mixer, instrument and effect devices etc., almost all controls are designed like their real world counterparts - mixer faders, effect unit knobs, transport buttons, etc. How to adjust these controls is described in the following paragraphs.



Knobs

- **To "turn" a knob, point at it, hold down the mouse button and drag up or down (as if the knob was a vertical slider).** Dragging upwards turns the knob clockwise and vice versa.



- **If you press [Shift] and drag, the knob will turn slower, allowing for higher precision.** You can also adjust the knob precision with the "Mouse Knob Range" setting on the User Interface tab in Settings. This dialog is opened from the Edit menu (or from the Reason menu if you are running macOS).
- **To reset a knob to its default value (usually zero, center pan or similar), press [Ctrl](Win) or [Cmd](Mac) and click on the knob.**

Faders and sliders

- **To move a fader or slider, click on the handle and drag in the fader/slider direction.**



- **You can also click anywhere on the fader/slider to instantly move the handle to that position.**
- **If you press [Shift] and drag, the fader/slider will move more slowly, allowing for higher precision.**
- **To reset a fader/slider to its default value (usually zero, 100, center pan or similar), press [Ctrl](Win) or [Cmd](Mac) and click on the fader/slider handle.**

Buttons



Many functions and modes are controlled by clicking buttons. Many of the buttons in Reason have a "built-in" LED, or the button itself lights up, indicating whether the button is on or not.

Fold/Unfold buttons

Fold/Unfold buttons are distinguished by a small triangle at the top to the left on a device. Clicking on a Fold/Unfold button will unfold the device panel so that more controls are visible and can be accessed for editing on the screen.

On some devices, such as the RV7000 Advanced Reverb, there are more than one Fold/Unfold button. Clicking on the second Fold/Unfold button on the unfolded front panel will open up the Remote Programmer panel from which more parameters can be accessed:



Click on the Fold/Unfold Button to unfold the front panel.



Click on the second Fold/Unfold Button on the unfolded panel to bring up the Remote Programmer.



The Fold/Unfold buttons on an RV7000 Advanced Reverb device.

Multi Mode selectors

Some parameters allow you to select one of several modes. There are two different graphical representations of this in Reason.

The multi mode selector type below consists of a button with the different modes listed above it:



- **Click the button to step through the modes or click directly on one of the modes printed on the panel, or click on the corresponding LED, to select mode.**
  The currently selected mode is indicated by a lit LED.


The multi mode selector type below is a switch with more than two positions:



- **To change mode, click and drag the switch, or click directly at the desired switch position (just as when adjusting a slider).**

Numerical controls


In Reason devices, numerical values are often displayed in numerical displays with “spin controls” (up/down arrow buttons) on the side. Some parameter values, such as oscillator and LFO waveforms, are displayed graphically in the displays. There are two ways of changing values in these types of controls:



- **By using the up and down buttons on the spin controls.**
  To adjust a value in single steps, click on its up or down arrow button. To scroll a value continuously, click on an arrow button and keep the mouse button depressed.
- **By clicking and holding the mouse button depressed in the actual display and then dragging the mouse up or down.**
  This allows you to make coarse adjustments very quickly.

Alpha-numeric controls

In Reason, alpha-numeric values and/or device presets are displayed in alpha-numeric readouts with “spin controls” (up/down arrow buttons) on the side. There are two ways to change alpha-numeric/preset values:



- **By using the up and down buttons on the spin controls.**
  To adjust a value or select a preset in single steps, click on the up or down arrow button. To scroll a value continuously, click on an arrow button and keep the mouse button depressed.
- **By clicking and holding the mouse button depressed in the actual alpha-numeric display and selecting from the list that appears.**
  This allows you to make coarse adjustments very quickly or to immediately change to a preset anywhere in the list.
- **This type of control is used to select, e.g., patch and reverb algorithms and some oscillator waveforms.**

Numerical segment displays

In the numerical segment displays on the sequencer Transport Panel and in the sequencer Inspector, values can be edited in a number of different ways. The editing principle is exactly the same for the Transport Panel and Inspector displays, which is shown in the two examples below.


Transport Panel segment displays

The segment displays of the Transport Panel can be edited as shown in the following Tempo display examples. The Tempo display segments show (from left to right) BPM and 1/1000 BPM:

Click on the left display segment to select the "whole BPM" value. Then, either click and drag up or down or use the mouse scroll wheel to change tempo in steps of 1 BPM. You can also use the [Up]/[Down] arrow keys on the computer keyboard to change the value.

Alternatively, type in the new tempo and press [Enter] on the computer keyboard.


You can also type in a number preceded by [+] or [-] to add or subtract the number from the current tempo value. Then, press [Enter] on the computer keyboard.



Click on the right display segment to select the "1/1000 BPM" value. Then, either click and drag up or down or use the mouse scroll wheel to change tempo in steps of 1/1000 BPM. You can also use the [Up]/[Down] arrow keys on the computer keyboard to change the value.

Alternatively, type in the new tempo and press [Enter] on the computer keyboard.

You can also type in a number preceded by [+] or [-] to add or subtract the number from the current tempo value. Then, press [Enter] on the computer keyboard.



Double-click on the display, type in the new tempo and press [Enter] on the computer keyboard.



The other segment displays on the Transport Panel can be edited in the same way as described above. Some displays also features up/down arrow buttons.

Inspector segment displays

The segment displays in the Inspector can be edited as shown in the following Position display examples. The Position display segments show (from left to right) Bars, Beats, 1/16th Note and Ticks:


Click the up/down buttons to change the value in steps of 1 Bar (the leftmost segment).



Click in the display to select either the Bar, Beat, 1/16th note or Ticks segment. Then, click the up/down buttons to change the value of the selected segment in steps of 1 unit.



Click in the display to select either Bar, Beat, 1/16th note or Ticks. Then, click and drag the cursor up/down to change in steps of 1 unit. Alternatively, change the value with the mouse scroll wheel. You can also use the [Up]/[Down] arrow keys on the computer keyboard.



Click in the display to select either Bar, Beat, 1/16th note or Ticks. Then, type in a number and press [Enter].

Alternatively, select a segment, type in a number preceded by a [+] to add or a [-] to subtract the number from the current value. Then, press [Enter].



Double-click in the display. Then, type in the desired value and press [Enter].




The other segment displays in the sequencer Inspector can be edited in the same way as described above.

Tool Tips

If you hover with the mouse over a control on a device panel and wait a moment, a tool tip appears. The tool tip shows the name of the parameter associated with that control and its current value. This helps you fine-tune settings, set several parameters to the same value, etc.




▶ **You can turn off the Tool Tips function by deactivating the option "Show parameter value tooltip" on the User Interface tab in Settings.**



Context menus

Context menus are “tailored” to contain only menu items that are relevant to the current circumstances. Using the various context menus allows you to work more quickly and more efficiently with Reason.

▶ **To bring up a context menu, right click the desired object, section or area in Reason:**



The Mixer 14:2 device panel context menu

▶ **If you are using a Mac with a two button mouse, you may want to set this up so that clicking the right mouse button generates a [Ctrl]-click. This way, you can right-click to bring up context menus.**

The contents of the context menus depend on where you click. These are the primary types of context menus you will encounter in Reason:

Parameter context menus

If you click on an automatable control (a mixer parameter, a device parameter, a fader, etc.), the context menu will contain the following items:

- **Functions for editing and clearing the recorded automation data for the control.**
- **Functions for associating computer keyboard commands and/or MIDI messages to the parameter.**
  This allows you to remote control parameters from a MIDI device or from the computer keyboard.

Device context menus

If you click anywhere on a device panel in the Rack (but not on a parameter or display), the context menu will contain the following items:

- **Cut, Copy, Paste, Delete and Duplicate Device and Track items, allowing you to rearrange and manage the devices in the rack.**
- **Commands for managing Device Groups.**
- **A duplicate of the Create menu, allowing you to create new devices.**
- **A "Go To" sub-menu, listing all devices connected to the current device.**
  Selecting a device from the Go To sub-menu scrolls the rack to bring that device into view.
- **Auto-routing and Disconnect functions.**
  This allows you to automatically route (connect) or disconnect a selected device in a logical way.
- **Combine and Uncombine are used when you want to use the selected device in, or exclude it from, a Combinator setup.**
- **A Browse Instruments item which lets you browse for sounds for a selected Instrument device.**
  This item is available only for Instrument devices.
- **Additional device-specific items.**
  If the device is pattern-based, there will be various pattern functions (Cut/Copy/Paste, Clear, Shift, Randomize, etc.). These affect the currently selected pattern in the device.

  If the device uses patches, there will be functions for managing patches.

  Depending on the device there may also be various device-specific functions available. For example, the drum machine device has functions for manipulating the pattern for the selected drum sound only, etc.
- **"Create Track for..." and "Delete Track for..." are used if you want to create a Sequencer Track for the selected device, or delete the Sequencer Track used for the device without deleting the actual device.**
- **The "Go To Track for ..." will scroll the corresponding Sequencer Track into view in the Sequencer.**
- **The "Lock Control Surface to this Device" lets you lock a connected control surface to the selected device.**
- **The "Track Color" item lets you select color for the associated Sequencer Track (and Main Mixer channel strip, if the selected device is an Audio Track device).**

Main Mixer channel strip context menu

If you click anywhere on a channel strip in the Main Mixer (but not on a parameter or display), the context menu will contain the following items:

- **Cut, Copy, Paste, Delete and Duplicate Channels and Track items, allowing you to rearrange and manage the channel strips in the Main Mixer.**
- **Commands for managing Device Groups.**
- **The "Create Send FX" lets you browse for an effect patch to connect and use as a send effect.**
  The send effect will be automatically connected to the first available Send FX connectors of the Master Section device in the Rack, see "Creating Send effects".
- **A duplicate of the Create menu, allowing you to create new devices.**
- **"Route to" lets you create and connect to an Output Bus for sub-mixing.**
- **"Create Parallel Channel lets you create and connect to an additional channel for parallel processing.**
- **The "Copy Channel Settings" item lets you copy groups of settings for the selected channel strip.**
  The groups that can be selected are: "Dynamics", "Filters and EQ", "Insert FX", "FX Sends" and "All".



- **The “Paste Channel Settings” item appears if you have previously copied any channel settings and want to paste these to the selected channel strip.**
- **The “Browse Insert FX Patches” lets you browse for, and load, Effect Combi patches to the Insert FX section.**
- **The “Clear Insert FX” lets you delete any Insert Effects devices used in the channel.**
- **The “Reset All Channel Settings” resets all channel strip parameters to their default values.**
  It also automatically removes any used Insert FX devices from the channel strip.
- **The “Set Remote Base Channel” item lets you set the remote base channel to the selected channel strip.**
  This is useful when you remote control channel strips from a control surface via MIDI.
- **The “Lock Control Surface to this Device” lets you lock a connected control surface to the selected channel strip.**
- **The “Channel Color” item lets you select color for the Main Mixer channel strip (and the associated Sequencer Track, if the selected channel has a track in the sequencer).**

Rack “background” context menu

If you click in an empty area of the rack, the context menu will contain the following items:

- **A Paste Devices and Tracks item, allowing you to paste any copied or cut devices and tracks.**
- **A duplicate of the Create menu, allowing you to create new devices.**

Main Mixer “background” context menu

If you click in an empty area of the Main Mixer, the context menu will contain the following items:

- **A duplicate of the Create menu, allowing you to create new devices.**
- **The “Create Send FX” lets you browse for an effects device, or Effect Combi patch, to connect and use as a send effect.**
  The send effect will be automatically connected to the first available Send FX connectors of the Master Section device in the Rack.

Sequencer context menus


If you click in the Sequencer, the context menus will contain items related to editing tracks, clips and events. The available items will differ depending on in which section or lane you click (Track List, note lane, etc.), and depending on whether you click on a note or automation event or not.

For example, the sequencer context menus contain functions for inserting or removing bars, deleting tracks, changing or deleting note and automation events.

Undo and Redo

Virtually all actions in Reason can be undone. This includes creation, deletion and reordering of devices in the rack, parameter value adjustments, recording and editing in the sequencer etc. You can undo hundreds of actions.

- **To undo the latest action, select "Undo" from the Edit menu, or hold down [Ctrl](Win) or [Cmd](Mac) and press [Z].**



The action to be undone is indicated next to the Undo command on the Edit menu. For example, if your latest action was to delete some device(s) from the rack, the Edit menu will display "Undo Delete Devices and Tracks".

- **To redo the last undone action ("undo the undo operation"), select "Redo" from the Edit menu, or hold down [Ctrl](Win) or [Cmd](Mac) and press [Y].**
  Similarly, the action to be redone is shown on the Edit menu.

About multiple Undos and Redos

The concept of multiple undos may require an explanation.

Let's say you have performed the following actions:

1. **Created a Mixer device.**
2. **Created a synth device.**
3. **Adjusted the Attack parameter of the synth device.**
4. **Changed the panning for the synth device in the Mixer.**
5. **Adjusted the playback tempo on the Transport Panel.**

After these five actions, the Undo History will look as follows:

UNDO
5. Adjust tempo
4. Change pan
3. Adjust Attack
2. Create Synth Device
1. Create Mixer Device

If you now select Undo, your latest action (the tempo change) will be undone, and moved to a "Redo list":

UNDO	REDO
4. Change pan	
3. Adjust Attack	
2. Create Synth Device	
1. Create Mixer Device	5. Adjust tempo

Selecting Undo again undoes the next action in the list (the panning adjustment):

UNDO	REDO
3. Adjust Attack	
2. Create Synth Device	4. Change pan
1. Create Mixer Device	5. Adjust tempo

If you now select Redo, the most recently undone action will be redone. In this case, your panning adjustment will be performed again (and added to the Undo History again):

UNDO	REDO
4. Change pan	
3. Adjust Attack	
2. Create Synth Device	
1. Create Mixer Device	5. Adjust tempo

At this point, you still have the option to Redo the tempo change. But if you instead perform another action (e.g. change the level of the synth device in the mixer), this would become the action at the top of the Undo History - and the Redo list would be cleared.

UNDO	REDO
5. Change level	
4. Change pan	
3. Adjust Attack	
2. Create Synth Device	
1. Create Mixer Device	(Empty)

You can no longer redo the “undone” tempo change!




Chapter 3
On-screen Piano Keys

About this chapter

This chapter describes the functions of the On-screen Piano Keys window.

The On-screen Piano Keys window enables you to play instrument devices using either your mouse or computer keyboard. This provides a simple and convenient way to input notes or chords when using the program without an attached MIDI master keyboard.




Using the On-screen Piano Keys

Opening the Piano Keys window

- ▶ **To open the window, press [F4] or select "Show On-screen Piano Keys" from the View menu - or click the Keys button on the top bar of the Document window.**
  Like the Tool window, the On-Screen Piano Key window "floats" on top of other windows, remaining visible most of the time.
- ▪ **You can choose between two basic operational modes to enter notes; "Mouse" or "Computer Keys".**
  Mouse Mode is for entering notes with the mouse, and Computer Keys Mode for using the computer keyboard to enter notes. The two modes are described separately below.

The respective buttons in the middle of the window are used to switch modes.




Mode buttons.


- ▪ **Regardless of mode, the On-screen Piano Keys window always follows Master Keyboard input.**
  This means that the Piano Keys will trigger the device associated with the track that has Master Keyboard Input. The Piano Keys input is merged with any attached keyboard/control surface input so you can use both simultaneously.
- ▪ **The available note range is 10 octaves (C -2 to E 8).**
- ▪ **When the On-screen Piano Keys window is in Mouse mode, you can resize it by clicking and dragging the window frame according to standard procedures.**
  This is especially useful in "Mouse" mode, since you can adapt the window to show the desired note range.

The Keyboard Navigator

This is present in both modes and shows the total key range. The green area indicates the key range available in the On-screen Piano Keys window.




Keys that produce sound are indicated by a gray strip above the keyboard in the Keyboard Navigator. This is useful when playing a patch where only certain keys or key ranges produce sound, e.g. a REX file or a sampler patch.



Setting Octave range

There are several ways to set the Octave range:


- **Click the arrow buttons on either side of the Keyboard Navigator.**
  Each click will shift one octave up or down.



- **Click and drag the green key range area in the Keyboard Navigator.**

The current octave number is always shown for the leftmost key - by default the [A] key on the computer keyboard.


Mouse mode



When Mouse Mode is selected, the Piano Keys window shows a standard piano keyboard.

- **To enter notes, simply click on the keyboard with your mouse.**
  As described above, the selected sequencer track governs what instrument device is played.

- **The keys are velocity sensitive. The higher up on the key you click, the lower the velocity and vice versa.**
  The velocity range is between 40 and 127.



Low and high note velocities.

- **The keyboard octave range can be set using the arrow buttons at each side of the navigator keyboard.**
  Each C key is labeled with the octave number. You can also simply drag the green key range area to where you want. It will snap to octave ranges.
- **In Mouse Mode, the keyboard can be resized both vertically and horizontally.**
  Resizing horizontally extends or diminishes the key range. By resizing the window vertically you change the key size for the keyboard, as well as the key range.


Adding sustain

If you press [Shift] when clicking notes, the notes will sustain, just like when using a sustain pedal.

Repeat and Hold functions

- **The Repeat function will continuously repeat the last clicked note as quarter notes with a quarter note pause in between (at the current tempo).**
  This feature can be useful when tweaking synth parameters or browsing for patches. It is activated/deactivated by checking/unchecking the box.
- **The Hold function will keep any keys you click on pressed down for as long as Hold is active.**
  Hold is activated/deactivated by checking/unchecking the box.

Computer Keys mode



When Computer Keys Mode is selected, the On-screen Piano Keys window shows a graphic (partial) representation of a computer keyboard. The window cannot be resized in this mode.

- **In Computer Keys Mode you can play notes and chords using your computer keyboard.**
  The Computer Keys keyboard range is fixed to 18 notes (from C to F), although the octave range will give you access to any notes within the ten octaves shown in the navigator. You can also click on the keys with your mouse to trigger notes. The numerical keys in the top row are not used to enter notes but to set velocity, see "Velocity".
- **The default layout of the Computer Keys logically reflects the layout of a piano keyboard's black and white keys.**
  The first (leftmost) key represents C and so on up to F an octave above. By default, the [A]-key will play the first C, the [W]-key a C# and so on, according to piano keyboard standards. If you wish, you can customize the note to key assignment in Settings - Other Controls tab (see "Settings – Other Controls").

Octave range

- **Press [Z] or [X] on your computer keyboard to shift one octave down or up, respectively.**
  There are also "Z" and "X" Octave buttons in the On-screen Piano Keys window that function in the same way.

  See "Setting Octave range" for more ways of changing the Octave range.


Repeat and Hold functions

See "Repeat and Hold functions".

Adding sustain

- **Press [Shift] when entering notes to make the notes sustain, just like when using a sustain pedal.**
  There is also a Sustain button in the On-screen Piano Keys window that has the same functionality.

Velocity




In Computer Keys Mode, velocity for notes you play can be set using the numerical keys in the top row. The currently set value is also shown in the Velocity value field. The numerical keys correspond to the following velocity values:

Numerical key	Velocity value
1	1
2	14
3	28
4	42
5	56
6	70
7	84
8	98 (default)
9	112
0	127

- **You can also click in the Velocity box and enter the desired velocity value numerically.**

Velocity Variation



This feature will randomly vary the velocity values for the notes you enter. There are four options; None (default), Light, Medium and Heavy. The degree of velocity variation is as follows.

Item	Variation
None (default)	0
Light	+/- 5%
Medium	+/- 10%
Heavy	+/- 25%

Chapter 4
Audio Basics



About this chapter

This chapter contains some useful information about how audio is handled by Reason and how the audio is routed. Some of it may seem a bit technical, but we recommend that you read it to get the most out of Reason.

How Reason communicates with your audio hardware

Reason receives, generates and plays back digital audio - a stream of numerical values in the form of ones and zeroes. For you to be able to record and play back anything, the audio must be converted from analog to digital when recording, and from digital to analog when playing back through some kind of listening equipment (a set of speakers, headphones, etc.).

This conversion is most often handled by the audio card installed in your computer, or by an external audio interface connected via USB. To achieve the best possible performance, Reason requires that the audio card uses an ASIO driver on Windows systems. On macOS systems, Reason supports Core Audio.

To receive and deliver digital audio to the computer's audio hardware, Reason uses the driver you have selected in the Settings dialog. In the Rack on screen, this connection is represented by the Hardware Interface (also known as the Hardware Device):




The Hardware Interface is always located at the top of the rack.

The Hardware Interface contains 64 input and 64 output "sockets", each with an indicator and a level meter. There are also two Sampling Inputs that can be used for sampling audio to sampler devices. 16 input and 16 output sockets are shown on the main panel, and an additional 48+48 sockets are shown if the "More Audio" button is activated on the main panel. Each one of these indicators represents a connection to an input or output on your hardware audio interface.

However, the number of available inputs and outputs depends on the number of inputs and outputs on your hardware audio interface. For example, if you are using a standard sound card with stereo inputs and outputs, only the first two inputs and outputs will be available. In the Hardware Interface, the indicators are lit green for all currently active and connected inputs and outputs. Activation of inputs and outputs on your hardware audio interface is done on the Audio tab in the Settings dialog (see "Settings – MIDI").

Inputs and outputs that are currently connected have green indicators. Available but unconnected inputs and outputs have yellow indicators and any connections made to unavailable inputs and outputs have red indicators.



In this case, Inputs 1 and 2 are available, but not connected, Outputs 1 and 2 are available and connected, whereas Output 3 is unavailable, but connected on the back of the Hardware Interface.

! **You never have to connect any cables to the Audio In jacks of the Hardware Interface to be able to record audio on sequencer tracks. This routing is made internally "in the background", which means you just have to select audio interface inputs from the Audio Input drop-down list - see "Selecting audio input(s) and defining mono or stereo".**

Manual audio routing

In most cases, you will want to have the Main Mixer Master Section device connected to outputs 1 and 2 of the Hardware Interface. This connection is made automatically as soon as you create a new Song document. However, there might be situations where you want to manually route audio to other outputs of the Hardware Interface. For example if you want to use the Control Room Outputs of the Main Mixer (see "Control Room output section").

To send the sound of a device in the Rack to a specific output, you route the device output to the corresponding Output jack on the Hardware Interface. This is done by using the patch cables on the back of the rack, as described in "Manual routing". If we flip the rack around, by pressing the [Tab] key, the Hardware Interface looks like this:



On the rear of the Hardware Interface, Inputs 1 and 2 are available but not connected, Outputs 1 and 2 are available and connected, whereas Output 3 is connected but unavailable.

! **You never have to connect any cables to the Audio In jacks of the Hardware Interface to be able to record audio on sequencer tracks. This routing is made internally "in the background", which means you just have to select audio interface inputs from the Audio Input drop-down list in the sequencer Track List - see "Selecting audio input(s) and defining mono or stereo".**

Audio quality

The audio quality in a computer based recording system depends on two things:

- **The quality of the software calculating the audio.**
  In our case, this is the Reason DSP (Digital Signal Processing) code.
- **The quality of the hardware audio interface used for recording and playing back the sound.**

Software

- **Reason uses 32-bit floating point arithmetic for all internal audio operations, with 64-bit summing in the mix bus in the Main Mixer Master Section.**
  This ensures the highest possible audio quality throughout the entire signal chain.
- **Reason supports 16, 20, and 24 bit resolution for input and output audio.**
- **Reason supports all standard sample rates between 44.1 kHz and 192 kHz.**
  Reason also supports lower sampling frequencies, but using a sample rate of less than 44.1 kHz is not recommended since it might affect the audio quality negatively.
- **A number of digital audio techniques that reduce the risk of "aliasing", background noise, unwanted distortion and "zipper noise" are implemented in Reason.**

Audio hardware

How good a hardware audio interface actually sounds depends on a number of things; its frequency range and frequency response curve, the resolution (bit depth), the signal to noise ratio, the distortion under various circumstances, etc. Furthermore, some designs are more prone to disturbance from the other electronics in the computer than others. Such disturbance might add hum or high pitched noise to the signal.

The only advice we can give is that if you are serious about sound, choose your audio hardware carefully!

Audio settings

Sample rate and resolution are properties of digital audio which determine the quality of the sound. Generally, higher sample rate and resolution result in better audio quality (but also larger audio files and higher demands on computer performance and audio hardware). The table below shows some common sample rate/resolution combinations:


Sample rate:	Resolution:	Comment:
44.1 kHz	16 bit	This is the format used on standard audio CDs.
44.1 kHz –192 kHz	24 bit	These are formats used in professional studios and high-end recording equipment.

To cater for all different situations, Reason supports multiple sample rates and resolutions.

Sample Rate settings for recording and playback

Reason handles all internal audio processing in 32-bit floating point resolution, with 64-bit summing in the mix bus in the Main Mixer Master Section. However, the resolution of the input and output audio is determined by the hardware audio interface. That is, if you have a 24-bit audio card, Reason will record and output audio in 24-bit resolution, and if you have a 20-bit audio card, audio will be recorded and played back in 20-bit resolution.

The recording and playback sample rate can be specified on the Audio tab in the Settings dialog (accessed from the Edit menu (Win) or Reason menu (Mac)):



▶ **Select the desired sample rate from the drop-down menu.**
Note that the available options on this pop-up menu depend on which sample rates are supported by the audio hardware.

! **Reason supports multiple sample rates in the same song!**

Reason allows import (or recording) of audio of any sample rate. If the original sample rate of a recording is different than the rate currently set for the audio card, Reason will automatically do a sample rate conversion.

First, a real-time sample rate conversion algorithm is used (allowing the audio to be played back immediately). Meanwhile, in the background, the program calculates a sample rate conversion of the highest quality, which will be used as soon as it is calculated. The CALC progress indicator on the transport panel lights up whenever the program is doing high quality calculations in the background:



The CALC progress indicator on the Transport Panel appears when Reason performs high quality audio calculations.

Buffer Size settings

The Buffer Size can be adjusted on the Audio tab in the Settings dialog (accessed from the Edit menu (Win) or Reason menu (Mac)):



▶ **Select Buffer Size by clicking and dragging the slider sideways - or by clicking the up/down spin controls.**

The trick here is to find the optimum relationship between audio quality, DSP Load and latency. Experiment with different Sample Rate settings in combination with different Buffer Size settings to get the best result.

A professional audio interface used together with a state-of-the-art computer should normally be able to handle a combination of a high sample rate (96 kHz) and a small Buffer Size (64-128 samples) without problems. A budget priced audio interface normally requires a lower sampling frequency (44.1 kHz) in combination with a little higher Buffer Size (256-512 samples).


See "About latency" for more information about buffer size and latency. Also see "About audio rendering using the audio card buffer size setting" below for information on how to improve the DSP performance.

About Max Audio Threads

Reason fully supports multi-core audio rendering. This means that if your computer has multiple CPU Cores, or multiple CPUs, Reason takes advantage of this to significantly enhance the performance. A higher system performance allows for more tracks and devices in your songs.


Here you can select the maximum number of audio threads Reason should be allowed use. The “Default” setting equals the total number of physical cores in your computer’s CPU (corresponding to the old "Use multi-core audio rendering" option, but without the "Use hyper-threading audio rendering" option in older Reason versions). On Apple M1/2/3/4 the Max audio threads setting defaults to the number of Performance cores.

This preference can also be used to limit the number of threads if you want to leave room for other apps or perhaps multi-core VSTs.



See “Max audio threads” for more details.

About audio rendering using the audio card buffer size setting



The “Render audio using audio card buffer size setting” function should be selected (checked) for best plugin performance. When selected, the audio batches are rendered internally according to the set Buffer size (see “Buffer Size settings” above). For example, if you have a Buffer size of 512 Samples, each audio batch will be 512 samples internally. Raising the Buffer size will let Reason process larger audio batches in one go, which is often more efficient. Many plugins are also more efficient when doing larger audio batches. if you are using DSP-heavy VSTs (mastering effects, for example), these will run a lot smoother with this function selected.


! Note that old songs might sound different with this function selected, if the songs use feedback routings and CV connections.

If unchecked (off), all audio batches are rendered internally at a fixed size of 64 samples - regardless of the Buffer size setting. This might be desirable if you are using feedback signal routings and CV connections in your songs, and want the internal latency of those connections to be fixed at a short value all the time. This might result in performance problems for DSP-heavy VSTs, though.

Master Tune setting

By default, Reason plays back a “middle A” at 440 Hz, which is the standard tuning in most instruments. However, if you are playing Reason together with other instruments, you may want to adjust the tuning:

1. **Select “Settings...” from the Edit menu (Win) or Reason menu (Mac).**
2. **Click the “Audio” tab.**
3. **Adjust the global tuning with the Master Tune button controls.**



- **If you like, you can also adjust the Master Tune during playback.**


! The Master Tune setting affects the tuning of all sound sources in Reason, including the Tuner function on the Audio Tracks. It also affects the tuning of the Redrum and Dr. Octo Rex loop player.

! **Note that the Master Tune setting does NOT affect the pitch of the audio on audio tracks!**

! **Note that the Master Tune setting does NOT affect the pitch of any VST plugins used in the song!**


About audio levels

When recording and playing back in Reason, you should keep an eye on the Audio In and Audio Out Clip indicators on the Transport Panel, or on the Hardware Interface and the Big Meter. You should also keep an eye on the clip indicators on the Main Mixer Master Section. If any of the clip indicators light up, the audio level is too high, resulting in clipping (digital distortion).



The Clip indicators will stay lit for a short moment, to make them easier to spot.


The Clip indicators on the Audio In and Audio Out meters on the Transport Panel.



If the audio out level is, or has been, too high, the Clip indicators in the Master Section will stay lit until you click the "Reset" button.

The Clip indicators in the Master Section of the Main Mixer.

! **Note that the Main Mixer Master Section Clip indicators will only work if there are no other devices connected between the Master Section device and the Hardware Interface!**



The Big Meter on the Hardware Interface.

- ▶ **To remedy Audio In clipping, adjust the level at the input source, i.e. on the hardware audio interface or on the pre-amp connected to the hardware audio interface.**
- ! **When recording or sampling external audio signals, clipping cannot be adjusted in the Reason application - it must be adjusted at the audio input source!**
- ! **When sampling audio internally from devices in the rack, you have to adjust the Output Level on the source device to make sure clipping doesn't occur in the Hardware Interface.**
- ▶ **To remedy Audio Out clipping, lower the master level on the Mixer (or other device) that is connected to the Hardware Interface, until Audio Out clipping doesn't light up on playback.**
  You could also use the MClass Maximizer as an insert effect on the Master Section in the Main Mixer to ensure that clipping never occurs - see "The MClass Maximizer".
- ▶ **To get a better overview of the levels, bring up the Big Meter on the Hardware Interface, by clicking the "Big Meter" button on the front panel. Then, select the input or output pairs to view in the Big Meter by clicking on the corresponding channel selection button below each input or output pairs. Alternatively, select channel by turning the channel selection knob.**
  If the audio level is, or has been, too high, the Clip indicators on the Big Meter will stay lit until you click the Reset button, or select new audio channels for the Big Meter.
- ! **In some situations, the Audio Out Clip indicator on the Transport Panel and the Output Clip indicators on the Reason Hardware Interface might light up if the metronome Click is active in the sequencer during playback (see "Click and Pre-count"). This is nothing to worry about and won't cause any distortion in your song. To determine if the metronome is causing the clipping indication, just disable Click and see if the clipping stops.**
- ! **Note that it doesn't matter if the level meters on the individual devices (effects, MIxer channels, etc.) "hit the red". Output clipping can only occur in the Hardware Interface.**

  The technical reason for this is that internally, Reason uses high resolution floating point processing, which ensures highest audio quality and virtually limitless headroom. In the Hardware Interface, the floating point audio is converted to the resolution used by the computer's audio interface, and that's where audio out clipping might occur.

If you are using multiple outputs

If you are using an audio interface with more than two outputs, you might want to have different devices connected to different outputs. If the Audio Out Clip indicator on the Transport Panel lights up, you should play back the section again while checking the Reason Hardware Interface. Each output socket has a level meter - if the red meter segment lights up, the output is clipping.



Output 7 indicates audio clipping.

The indicator for Output 7 on the Hardware Interface indicates clipping.


- ▶ **If necessary, bring up the Big Meter and select the output pair where the clipping occurs. Lower the output level of the device connected to the clipping output, until no clipping occurs.**

System signal paths

Depending on the track types in the sequencer, the default signal chain varies. In this section we're going to describe the default audio signal paths for Audio Tracks and Instrument Tracks.

Audio Track signal paths


When you're recording and playing back audio that originates from an external source, like a guitar or a vocalist, the audio signal must first travel from the source, via a hardware audio interface, into the Reason application. Then, when played back, the audio travels from the Reason application, via the hardware audio interface, to a speaker system or similar. The figure below shows a schematic overview of the audio signal paths for a "standard" auto-routed Audio Track in Reason:



An Audio Track signal path in Reason.

Instrument Track signal paths

When you're recording and playing back audio from an instrument device, like the ID8 Instrument device, the audio signal only has to travel only in one direction: from the Instrument device, via the hardware audio interface, to a speaker system or similar. The figure below shows a schematic overview of the audio signal paths for an auto-routed Instrument Track in Reason:



An Instrument Track signal path in Reason.

General information about audio and computers

About latency

On any personal computer system, there is a delay between the moment you input a sound, or "tell" the hardware to play a sound, and when you actually hear it. This delay is referred to as the "latency" of the design. This imposes a problem for any system where you want real-time user input to affect the sound.

Why is there latency?

All audio applications receive and generate their audio in chunks. These chunks are then passed on to the audio card where they are temporarily stored before being converted into regular audio signals. The storage place for these chunks are called "buffers" (an analogy would be a bucket brigade, where a number of people each have a bucket, and water is poured from one bucket to another to reach its final destination).

The smaller the buffers and the fewer they are, the more responsive the system will be (lower latency). The general rules regarding the buffer size are these:

- **A small buffer size reduces the latency (the time it takes for the audio to "travel" from the audio interface input(s) to the application and from the application to the audio interface output(s)).**
  However, a small buffer size also increases the DSP Load. Too small a buffer size setting could also make the sound crackle and distort.
- **A large buffer size reduces the DSP Load (allowing for more tracks to be played back simultaneously) and also ensures good audio quality.**
  However, a large buffer size also increases the latency.

A high sample rate will also reduce the latency. However, this will also raise the demands on the computer and its software. If the system can't cope with moving the data to and from the buffers fast enough, there will be problems that manifest themselves as glitches in audio playback.

To make things worse, audio playback is always competing with other activities on your computer. For example, a buffer size that works perfectly under normal circumstances might be too small when you try to open files during playback, switch over to another program while Reason is playing or simply play back a very demanding song.

What is acceptable?

On a regular PC, the latency can vary quite a lot. This is an effect of the fact that computers and their operating systems were created for many purposes, not just for recording and playing back audio. For multimedia and games, a latency of a 100 ms might be perfectly acceptable, but for recording and playing back audio it is definitely not!

- **PC audio cards running under Windows with a MME driver might at best give you a latency of around 160ms.**
- **The same card with a DirectX driver running under Windows provides at best around 40ms.**
- **A card specifically designed for low latency, with an ASIO driver under Windows, or a Core Audio driver under macOS, can usually give you figures as low as 2-3 ms. This is definitely good enough for audio applications. That's also why ASIO or Core Audio drivers are required to run Reason.**

Reducing latency

There are a few general methods for making sure latency is as low as possible:

- **Make sure you are using the latest version of the drivers for your hardware audio interface.**
- **Adjust the Sample Rate and Buffer Size parameters as described in "Audio settings".**
- **Remove unnecessary background tasks on your computer.**
  This might be any background utility you have installed as well as networking, background Internet activities etc.

- **Optimize your songs.**
  You might run into situations where you have to raise the Output Latency setting to be able to play back a very demanding song on your computer. Another option would be to actually optimize the song. See "Optimizing Performance" for details.
- **Get a better audio interface.**
  This is only required if you find that you need to increase Output Latency because your audio card can't really cope with the songs you try to play.
- **Get a faster computer.**
  This is only required if you find that you need to increase Output Latency because your computer can't really cope with the songs you try to play.

About processors

When you run Reason, the numbers of physical CPU cores and the CPU clock speed are major factors determining how many audio tracks and devices you can use at the same time.

If you plan to buy a computer specifically for Reason, you could play it safe and choose a computer with at least a quad-core Intel i7 processor, or equivalent AMD processor, or an Apple Silicon (M) processor. Processors with more cores will give better performance and are highly recommended.

Reason also supports Windows On Arm computers running Prism.

About RAM

Another important performance factor is the amount of installed RAM in the computer. Generally, one could say: the more the better, especially if you're running several applications simultaneously. To run Reason, a minimum of 4 GB RAM is required, but more is highly recommended for better performance.

Chapter 5
Sequencer Functions


About this chapter

This chapter describes the layout and general functions of the main sequencer. Recording, editing clips and events, arranging and working with Blocks in the sequencer are described in detail in the chapters "Recording in the Sequencer", "Audio Editing in the Sequencer", "Note and Automation Editing", "Arranging in the Sequencer" and "Working with Blocks in the Sequencer".

Introduction

The sequencer is where you record your songs. The sequencer is used for recording audio tracks as well as instrument tracks, performance controllers, parameter automation and pattern automation. You can also arrange your songs, or parts of your songs, in Blocks. In Blocks mode you can build complete "sections" - consisting of a desired number of bars and tracks - that can be reused throughout the song. This chapter mainly describes the Song View and Edit Area. Functions specific to Blocks and the Blocks View are described in the separate chapter "Working with Blocks in the Sequencer".

Sequencer overview



The Arrange Area and the Edit Area


The Arrange Area is the "normal view" where you are working with your song arrangement. The Arrange Area gives a good overview of the contents of the tracks in your song. If the Enable Blocks function on the Options menu is active, the Blocks track is also visible at the top in the Track List. If the Enable Blocks function is off, there is no Blocks track in the Track List.

On the Blocks track you arrange the Block automation clips that control which Block should play back (see "Working with Blocks in the Sequencer").

The Edit Area is where you edit the contents of the clips in your song.

- ▶ **Press [F8] to open (and close) the Edit Area. Alternatively, double click a clip, or select a clip and hit [Enter].** The Edit Area shows detailed information about the content of one track (see "Tracks overview"), or lane (see "Lanes overview") at a time and you can edit the events in individual clips (see "Clips overview").
- ▪ **Instrument Tracks only have a single Edit Mode, whereas Audio Tracks have three different Edit Modes depending on what and how you want to edit the audio.**
- ▪ **When you open a note or audio clip by double-clicking it in the Arrange Area, the sequencer automatically opens the Edit Area.**

The Arrange Area




In the Arrange Area, all clips on all tracks can be viewed. Use this mode to get an overview of your arrangement, and when you want to perform clip-based editing such as rearranging whole sections of your song, etc.

! **Note that if the Enable Blocks function on the Options menu is off, there is no Blocks track in the Track List.**


The Edit Area

You can double click a clip in the Arrange Area to open it in the Edit Area - or press [F8]. In the Edit Area, you get a close-up look at the recordings on a track/lane. For Note clips the Edit Pane is divided into two horizontal edit rows, showing the notes at the top and one selectable parameter at a time at the bottom (Velocity in the example below). To the left in the Edit Area is the Edit Area Inspector, where you find editing functions for the contents of the currently open clip:



The Edit Area for an open Note clip

Similarly, if you double click an Audio clip in the Arrange Area, it opens up in the Edit Area and could look as follows:



The Edit Area for an open Audio clip


See "Audio Editing in the Sequencer" and "Note and Automation Editing" for details about editing clips in the Edit Area.

About the Follow Song function

The Arrange Area and Edit Area have separate Follow Song buttons. In the Edit Area this is off by default but if you turn it on, the Edit Area will scroll to follow the song position during playback:



Toolbar overview




The sequencer Toolbar features various sequencer editing tools as well as the Snap function. The tools can be used both in the Edit Area and in the Song/Block Views, with slightly different purposes in the respective modes. See "Toolbar details" for details about each tool.

Track List overview



To the left in the sequencer, all tracks are listed in the Track List. Each track in the sequencer is associated with a specific device in the rack. By clicking on a device icon in the Track List you automatically set Master Keyboard Input (see "Setting Master Keyboard Input") to the corresponding device in the rack for playing and/or recording.


Tracks overview



Most rack devices in a song automatically get their own dedicated track in the sequencer when you create the device. Each track can feature one or several lanes on which audio, note, performance controller, pattern and parameter automation events can be recorded - in clips. See "Track details" for more details about tracks.


! If the Blocks button on the Transport Panel is on, the Blocks Track is also shown at the top in the Track List.

Lanes overview




Each track consists of one (default) or several parallel lanes. The lanes can contain clips that feature note events or audio recordings, depending on track type. A track can also feature automation lanes that contain clips with parameter automation events - or pattern automation for pattern based devices. See "Lane details" for more details about lanes.

Clips overview




Note, audio, performance controller, pattern and parameter automation events are always contained in clips. A clip is basically a "container" for recorded data. Audio clips are displayed in the Arrange Area as a rectangular box with one or two graphical audio waves inside (mono or stereo). Note events are displayed in a "piano roll" fashion in the clip. Performance controllers and parameter automation events are displayed as continuous lines, and pattern events are displayed as repeated rectangles in the clips. See "Clip basics" for information about the different clip types.

Arrange Area Inspector overview




The context sensitive Inspector shows the properties of the currently selected clip(s) in the Arrange Area of the sequencer. The properties of the selected item can be edited by changing the values in the various displays. See "About the Arrange Area Inspector" for more info.

Ruler/Timeline overview



The Ruler is the song's "time line", measured in bars. In the Ruler, the Song Position Pointer indicates the current position in the song, i.e. in which bar the song is, or will begin, playing. The Ruler also shows the Left and Right Loop Locators as well as the Song End Marker. See "Ruler (timeline) details" for more details.

Track scrollbar overview



To the far right in the sequencer is the Track scrollbar. With the Track scrollbar you can scroll vertically in the Arrange Area. See "Scrolling" and "Zooming in the Sequencer" for more details.

Song Navigator overview



Below the Arrange Area is the Song Navigator. With the Song Navigator you can scroll and zoom horizontally in the Arrange Area. The Song Navigator also features indicators for the Ruler's Loop Locators, Song Position Pointer and Song End Marker. In the Song Navigator, all clips on all lanes are displayed as colored lines, indicating their positions in the song. See "Scrolling" and "Zooming in the Sequencer" for more details.

Transport Panel overview




The Transport Panel features the sequencer transport controls (Rewind, Fast Forward, Stop, Play and Record) as well as controls for Tempo, Time Signature, Position, Time and Loop Locator placements and some other functions. See "Transport Panel details" for more details.

Track details

Track definition


The tracks in the sequencer are where you record your audio, note and automation to create your songs. A track is always associated with a device in the rack (except for the Transport track and Blocks track). An icon with a picture of the associated device is shown in the Track List on the left hand side in the sequencer. In the Track List, the name of the associated device is shown, as well as icons and buttons related to the specific track. Each track can incorporate various lane types (depending on track type). To the right of the Track List - in the Arrange Area - each track has its own dedicated area for recorded events.

In the picture below, six sequencer tracks are shown. From the top down are the Transport Track (which is always present and cannot be moved or deleted), two audio tracks, two instrument tracks associated with one ID8 instrument device each, and one automation track for the ID8 2 Mix Channel strip.




The relationship between the track, the rack and the Main Mixer

A track in the sequencer is always associated with a device in the rack; i.e. there can never be a sequencer track without an associated rack device (except for the Transport track, Blocks track and Track Folders). Audio Track devices and Mix Channel devices in the rack also have their corresponding channel strips in the Main Mixer. Mixer channel strips can be considered "remote controls" for their corresponding rack devices. Depending on track type, the signal chain differs somewhat. The picture below shows the signal flow in five scenarios with three different track types:



Audio track relationships

An audio track is always associated with an Audio Track device in the rack and its corresponding Audio Track channel strip in the Main Mixer. An Audio Track device can also house insert effects.



In the figure above, the audio track is associated with the Audio Track device in the rack, which in turn is controlled from the Audio Track channel strip in the Main Mixer. The audio track features recorded audio and mixer automation.

Instrument track relationships (for internal instruments)

An instrument track is always associated with an instrument device in the rack. The instrument device in the rack is, in most situations, connected to a Mix Channel device in the rack. The Mix Channel device in the rack is controlled from the corresponding channel strip in the Main Mixer. A Mix Channel device can also house insert effects.



In the figure above, the ID8 track is associated with the ID8 instrument device in the rack. The ID8 instrument device is connected to the ID8 Mix Channel device in the rack, which in turn is controlled from the ID8 channel strip in the Main Mixer. The ID8 track features recorded MIDI notes and parameter automation.

Note that when you create an instrument, the connected Mix Channel device doesn't automatically get a track in the sequencer. If you want to record Mixer Channel automation, you have to first create a separate sequencer track for the Mix Channel device. See "Automation (non-instrument) track relationships".

Instrument track relationships (for external MIDI instruments)


If you want to control an external MIDI instrument from the Reason sequencer you have to use the MIDI Out Device (see "MIDI Out Device"). The device works as a MIDI router in which you can define which MIDI Out Port and MIDI Channel you want the MIDI signals to be sent to from Reason. Since there is no internal audio involved in this setup, there is no Audio Track device or Mix Channel device present in the configuration.



In the figure above, the MIDI Out Device track is associated with the MIDI Out Device in the rack. The MIDI Out Device track features recorded MIDI notes and parameter automation (MIDI CC#) that is sent via the MIDI Out Device to the desired MIDI Out Port and MIDI Channel.

Automation (non-instrument) track relationships

A pure automation track is always associated with a "non-instrument" device, i.e. a device which can't receive MIDI *Note* information. Consequently, an automation track can only consist of parameter automation lanes. Examples of non-instrument devices are Mix Channel devices with their corresponding Mix Channel strips, effect devices, mixer devices and Spider Merger & Splitter devices. The picture below shows an example with an automated Mix Channel:



In the figure above, the Mix Channel automation track is associated with the Mix Channel device in the rack, which in turn is controlled from the channel strip in the Main Mixer.

The picture below shows an example with an automated MClass Equalizer device. Note that no mixer channel strip is involved in this situation since the automation only concerns a non-instrument device and not any Mix Channel device:



In the figure above, the Equalizer automation track is associated with the Equalizer device in the rack.

Master Keyboard Input

The standard way of routing MIDI from a connected MIDI master keyboard or control surface to a device in the rack is to set the Master Keyboard Input in the sequencer. When MIDI is routed to a selected track in the sequencer, the notes and controller data are automatically echoed to the associated device in the rack. However, it is also possible to set Master Keyboard Input from the rack, see "Playing devices from the rack".


- **Setting Master Keyboard Input to an instrument track is necessary if you want to play notes on an instrument device from your MIDI master keyboard (and control the instrument device parameters via MIDI).**
  By locking additional MIDI keyboards to separate devices in the rack, you will be able to play and record on several sequencer tracks simultaneously, see "Locking a surface".
- **Setting Master Keyboard Input to an audio track is only necessary if you want to control the Main Mixer channel strip parameters via MIDI.**
- **Setting Master Keyboard Input to a "non-instrument" (parameter automation only) track is only necessary if you want to control the device's parameters via MIDI.**

Besides the standard routing described above, it's also possible to lock certain rack devices to specific control surfaces. See "Locking a surface" for more details.

! **If you have several MIDI keyboards/control surfaces locked to individual devices in the rack, it is possible to control and record on several tracks simultaneously!**

Setting Master Keyboard Input

▶ **To set Master Keyboard Input to a track and its associated device, click the device icon in the Track List.**



Master Keyboard Input set to an instrument track.



Master Keyboard Input set to an audio track.


The track gets a gray "arrow" symbol to the left, indicating that the track and associated device has Master Keyboard Input. The track and device will now respond to incoming MIDI data from a connected MIDI keyboard/control surface. By default, setting Master Keyboard Input also automatically selects the track, which is indicated by the gray color of the track in the Track List.

It's also possible to set Master Keyboard Input and track selection independently from each other by selecting "Separated" on the "MIDI" page in Settings - see "Settings – MIDI".

- **Only one track at a time can have Master Keyboard Input. However, if you have locked additional MIDI keyboards to specific devices in the rack via Remote (see "Locking a surface"), you will be able to play and record these together with the track that has Master Keyboard Input.**

The relationship between tracks, lanes, clips and events

A track is the top level in the sequencer Track List hierarchy. A track can consist of one or several parallel lanes. A lane can contain clips, which in turn can contain audio recordings, note events, performance controller events, parameter automation events or pattern events, depending on track type.




An instrument track with four note lanes featuring clips with note events.

- **A device in the rack can never have more than one track in the sequencer.**
- **A clip is a "container" for various types of events (audio recordings, note, performance controller, parameter automation or pattern events).**

Track types

These are the different track types:

- **The Blocks track**



The Blocks track is present at the top of the Track List only when the Enable Blocks function on the Options menu is on. On the Blocks track you can create Block Automation clips to decide which Blocks should play back. Refer to "Working with Blocks in the Sequencer" for more information about the Blocks feature.

- **The Transport track**




The Transport track is always present at the top of the Track List and cannot be moved or deleted. The Transport Track can have a maximum of two lanes: one containing time signature automation, and the other containing tempo automation. See "Automating time signature" and "Editing tempo automation" for more details.

- **Audio tracks**



An audio track can only have a single audio lane containing clips with mono or stereo audio recordings. However, each audio clip can contain several recordings, i.e. different "takes". You can view and comp these takes in the Comp Editor. See "Audio Editing in the Sequencer" for more details. An audio track can also have parameter automation lanes containing automation for the Audio Track Channel strip parameters in the Main Mixer.

- **Instrument tracks**



Devices that can receive MIDI notes, such as the ID8 device, will automatically be assigned a record enabled track when created. On an instrument track you can create a number of separate note lanes that can incorporate clips containing a combination of note and performance controller events. Multiple lanes are perfect if you, for example, are recording a drum track and want to record each drum sound on a separate lane. An instrument track can also have a number of parameter automation lanes that can contain clips with instrument parameter automation events.

- **Parameter automation ("non-instrument") tracks**



Tracks for devices that do not receive MIDI note data (e.g. effects and mixer devices and mixer channels in the Main Mixer) can only contain parameter automation lanes. These "non-instrument" devices are not automatically assigned a track when created. To automate parameters for non-instrument devices you need to manually create a track for these. The number of available lanes is limited by the number of parameters of each device. There can be one lane for each automatable parameter in the device.

- **Track Folders**




Track Folder tracks have a folder icon and contains other tracks inside of them. Track Folder clips don't contain any data - they only represent the contents of the contained clips. Please refer to "Track Folders in the Sequencer" for more information about Track Folders.

Track List elements

In the picture below, a Track List with four different tracks is shown. From the top down are the Transport Track (which is always present and cannot be moved or deleted), an Audio Track associated with an Audio Track device, an Instrument Track associated with an ID8 Instrument device and an Automation Track associated with the Mix Channel device.


The Transport Track in the picture features two parameter Automation Lanes (for Time Signature and Tempo) that have been manually created for the track. The audio track features only a single audio lane. The ID8 1 track features four note lanes and has two parameter automation lanes added. The Mix Channel 1 track is associated with the Mix Channel 1 device and has three parameter automation lanes added.



Depending on track type, the elements shown in the Track List can vary. The only common element for all track types is the "Record Enable Parameter Automation" button which should be enabled when you want to record parameter automation for the associated device. This and the other track elements will be described in detail later in this chapter.

Creating tracks

Regardless of the desired track type, you can always click the “+ Track” button at the bottom of the Track List and select the desired track type from the pop-up menu that appears:




Creating an audio track

An audio track can be created as follows:


1. **Hold down [Ctrl](Win) or [Cmd](Mac) and press [T]. Alternatively, select "Add Audio Track" from the "Create" menu or from the context menu in the Track List, rack or Main Mixer.**

▶ **Alternatively, double click the Audio Track device in the Utilities palette in the Device Palette.**



2. **An audio track is created in the sequencer and the associated Audio Track device is created in the rack. The Audio Track device's channel strip is created in the Main Mixer.**
   By default, the audio track is set up in mono. You can easily change to stereo by selecting "Stereo Input" in the "Audio Input" drop-down list - see "Selecting audio input(s) and defining mono or stereo". If you select "Stereo Input", the Audio Track channel strip in the Main Mixer automatically switches to a stereo channel.

! **Note that if you drop a stereo audio file on the audio track, its mixer channel will automatically convert to stereo. You don't need to change the track inputs for this.**



An audio track in the sequencer, its channel strip in the Main Mixer, and the Audio Track device in the separate Rack window.


Creating an instrument track

To create an instrument track, you need only create the instrument device. An instrument track is automatically created when you create a device which can receive MIDI notes:

1. **Drag and drop or double click the desired instrument device from the Instruments palette in the Device Palette.**

▶ **Alternatively, click the + Track button at the bottom of the track list and create an Instrument from the menu that appears.**
Selecting "Add Instrument" opens the browser where you can find an instrument patch by filtering on name, category, tags and more - this is great if you need a sound of a certain type, e.g. a distorted, electric bass. The "Instrument Devices" submenu lets you select an instrument - useful if you know you want a certain device, e.g. a Polytone synthesizer.

2. **An instrument device is created in the rack and the associated track is automatically created in the sequencer.**
In addition, a Mix Channel device for the instrument is automatically created in the rack and its channel strip is created in the Main Mixer. All devices are automatically connected. The Mix Channel device automatically adapts its inputs to the created instrument type - if the instrument is in mono, the Mix Channel device will be in mono, and if the instrument has stereo outputs, the Mix Channel device will be in stereo.



An instrument track in the sequencer, its channel strip in the Main Mixer, and the instrument and Mix Channel devices in the separate Rack window.

! **Note that no automation track is created for the Mix Channel device. This has to be manually created if you want to automate any of the Mix Channel strip parameters (see "Creating a parameter automation track for a non-instrument device").**

▶ **If you want to control an external MIDI instrument, create a MIDI Out Device from the Device palette or Instrument Devices submenu.**
A MIDI Out Device is created in the rack and the associated track is automatically created in the sequencer. See "MIDI Out Device" for more details on how to configure the MIDI Out Device for controlling external MIDI instruments.

Creating a parameter automation track for a non-instrument device

For non-instrument devices, such as effects devices and Mix Channel devices, you need to manually create a track if you want to record parameter automation. You can do that either by following the description below or by following either of the two last descriptions in "Creating/adding parameter automation lanes".

The track creation procedure described below also applies if you have manually deleted a track for an instrument device or an Audio Track device and want to create a new track for the device:

1. **Select the device by clicking on it in the rack.**



A border around a device in the Rack indicates that it has been selected.

2. **Select "Create Track for ((patch) name of device)" from the Edit menu or the device context menu.**

! **Note that if a track already exists for the device, this menu item will not be available - a device can only have one track.**

- **The new track will be automatically associated with the device and will get the same name as the device.**




- **Alternatively, right-click its miniature in the Track Panel and select "Create Track for…" from that context menu.**
- **Another way of creating a parameter automation track is by holding [Alt](Win) or [Option](Mac) and clicking on a parameter on the device panel. Alternatively, right click a parameter and select "Edit Automation" from the parameter context menu.**
- **If you press [Alt](Win) or [Option](Mac) when you create a non-instrument device, this will automatically create an associated automation track for the device.**

Short-cut for creating a Mix Channel track or Audio track

A faster way of creating a track for a Mix Channel device, or to create a new audio track (if you deleted the original one), is to go via the corresponding mixer channel strips in the Main Mixer:

1. **Scroll to the Main Mixer and locate the channel strip you want to create a track for.**



2. **[Shift]-click the SEQ (Goto Sequencer Track) button at the bottom of the channel strip.**
   A new track will be automatically created in the sequencer for the selected channel strip.

! **If a track should already exist for the selected channel strip, [Shift]-clicking the SEQ (Goto Sequencer Track) button will only scroll the corresponding sequencer track into view, not create any new track.**

Selecting tracks

▶ **Select a track by clicking it in the Track List.**
A selected track gets a highlighted background color.



- **Selecting a track shows its devices in the Track Panel.**
- **Selecting a track in the sequencer automatically scrolls to the corresponding device into view in the rack.**

▶ **Double click a device icon in the Track List to automatically reveal the associated device in the rack.**

- **Selecting an audio track will set Edit Focus to its channel strip in the Main Mixer.**
- **Selecting another type of track (e.g. an instrument track) will set Edit Focus to the Mix Channel belonging to that device group.**
  See "Creating devices" for information about device groups.

▶ **You can also select the next or previous track in the Track List list by using the up and down arrow keys on the computer keyboard.**


! **By default, selecting a track will automatically set Master Keyboard Input to that track. If you'd rather select tracks independent of the Master Keyboard Input selection, select "Separated" mode in the Settings menu ("MIDI" page). In "Separated" mode, you can select another track without automatically changing Master Keyboard Input. To change Master Keyboard Input, click the device icon on the desired track in the Track List.**

- **It is possible to select several tracks by using the standard [Shift], or [Ctrl](Win) or [Cmd](Mac), selection techniques.**
  This allows you to e.g. move or delete several tracks in one go.
- **It is also possible to select several instrument tracks (by using standard [Shift], or [Ctrl](Win) or [Cmd](Mac), selection techniques) and then edit the Note Clips using the Multi Lanes function, see "Multi Lanes editing".**

Resizing tracks

If you like you can resize tracks vertically, for a more detailed overview:

- **Click the bottom edge of the track in the Track List and drag down/up to resize the track height.**
  The cursor switches to a vertical "double arrow" as you hover over the bottom edge of a track in the Track List.



- **To resize multiple tracks in one go, select the desired tracks and drag the bottom edge of one of the selected tracks.**
  If the selected tracks have different heights to begin with, they will be scaled proportionally.
- **To scale multiple tracks to the same heights, hold [Alt](Win) or [Option](Mac) and drag one of the track bottom edges.**
- **To scale all track heights proportionally, click the -/+ Track Height buttons:**



- **To set all track to the same height, hold [Alt](Win) or [Option](Mac) and click the -/+ Track Height buttons:**

! **Note that if you drag upwards far enough, the track(s) will eventually be folded (minimized), see "Muting tracks".**

Minimizing track height


To minimize the visible height of the track, and thus allow for a better overview of the tracks in the sequencer, you can use the Minimize Tracks function:

1. **Select the tracks you want to minimize.**
2. **Right-click one of the tracks and select Minimize Tracks from the context menu. Alternatively, press [Alt][M] (Win) or [Option]-[M] (Mac).**

- **To change the tracks back to normal height, select "Restore Track Heights" from the context menu or use the same key command again.**

You can also minimize tracks by dragging:

- **To minimize a track, drag the bottom edge of the track in the Track List upwards, until the track snaps to minimum height.**



- **To restore a track, drag its bottom edge downwards until it goes back to normal height.**

A minimized track will not show the individual lanes in the Track List, and on the Edit/Arrangement Pane the clips are shown as horizontal strips. If the minimized track has several lanes, all the clips on the lanes will be shown as vertically stacked strips on the Arrangement Pane. No events in the clips are shown.


- **Basic clip operations (selecting, moving, copying etc.) are available also for minimized tracks, although it is generally better to restore the track height if you want to edit its contents, as this gives you a better overview.**
- **To minimize or restore all tracks in the sequencer in one go, use Select All in the track list and then the Minimize/Restore function.**
- **It's also possible to fold/unfold only the parameter automation lanes on a track by clicking the triangle on the parameter automation tab:**



See "Parameter automation lane elements" for more details.

Moving tracks

- **To move a track to another position in the Track List, click it in the Track List and drag the track up or down.**
  A red insertion line is shown, indicating where the track will be placed after releasing the mouse button. All clips on all lanes of the track will be moved along with the track.



You can use the same technique to move several selected tracks at once. Use standard [Shift]-select or use [Ctrl](Win) or [Cmd](Mac) to select non-adjacent tracks.

Deleting tracks

The most common scenario would probably be to delete a track together with its associated device(s). However, it's also possible to delete only the track while keeping the associated device(s) in the rack.

Deleting tracks together with their associated devices

- **To delete one or several tracks together with their associated devices in the Rack, select the tracks and then select "Delete Track(s) and Device(s)" from the Edit menu or from the track's context menu. Alternatively, press [Delete] or [Backspace].**

- **If you're deleting an Audio Track or Instrument Track, the result depends on the selected mode on the Options/Rack Settings menu:**
  In Rack per Track mode, this will normally delete the entire Rack column for the track, including other devices there (and their automation tracks). The exception is if there are devices in this column that are connected to other tracks/racks (CV connections, sidechain routings, etc). Then you will be asked whether to keep these devices.

  In Auto-Group Devices mode, you will be asked whether you want to delete the whole device group or just this device. If you hold down [Ctrl](Win) or [Cmd](Mac) while deleting, the whole device group will be deleted without the alert.

  In No Grouping mode, only the selected device will be deleted.

  See "Rack device procedures" for more information about Rack Sorting modes, Device Groups etc.

Deleting tracks only

▶ **To delete one or several tracks, select them and then select "Delete Track(s)" from the Edit menu or from the track's context menu.**
The tracks will be deleted without an alert but you can always use the Undo function. See "Undo and Redo".

! **If you delete an audio track, all recordings on that track will be removed!**

If you have deleted a track for a device and want to create a new track for the device, follow the descriptions in "Creating a parameter automation track for a non-instrument device" or "Short-cut for creating a Mix Channel track or Audio track".

Duplicating/copying tracks and devices

As it is not possible for a specific instance of a device to have more than one track, you cannot copy or duplicate only a track. These operations will instead duplicate/copy both the track (including all clips on the track) and its associated device(s) (with all settings). The duplicated/copied devices are really just like separate devices but with the same name and settings as the original devices, although their names will have the extension "Copy" to differentiate them from the original.

To make copies of tracks and their associated devices, complete with all lanes and recorded clips, use any of the following methods:

! **If Rack per Track mode or Auto-Group Devices mode is selected (see "Rack device procedures"), the entire Rack column or device group for the track will be copied/duplicated.**

▶ **Hold down [Ctrl](Win) or [Option](Mac), click on the track handle and drag the selected track(s) to a new position in the track list.**

▶ **Select the track in the Track List, hold down [Ctrl](Win) or [Cmd](Mac) and press [D].**
The duplicated track(s) will be inserted below the original track.

▶ **Select "Duplicate Device(s) and Track(s)" from the Edit menu or from the track's context menu.**
To bring up the context menu, right-click (Win) or [Ctrl]-click (Mac) on the track in the Track List. The duplicated track(s) will be inserted below the original track.

▶ **Select "Copy Device(s) and Track(s)" from the Edit menu or from the track's context menu.**
This allows you to insert the copied track(s) and device(s) by selecting "Paste" from the Edit menu or from the track's context menu. The copied track(s) will be pasted below the currently selected track.

▶ **When you copy or duplicate devices and tracks, they will normally be auto-routed at their new position, if needed. For example copying and pasting an effect device will connect it as an effect to the device above where you paste it. To paste or duplicate without auto-routing, hold down [Shift].**

Coloring tracks

A track can be assigned a color in the sequencer as follows:

- ▶ **To assign a new color to a selected track, select "Track Color" from the Edit menu or from the track's context menu and then select color from the palette.**
  The track color is shown in the track background in the Track List. The associated Audio Track device or Mix Channel device in the rack and its corresponding channel strip in the Main Mixer will also be assigned the new color. The selected track color will be reflected in all *new* clips you record or draw on this track.

- ! **If existing clips have the function "Use Track Color" active on the Clip context menu, these clips will also change color - otherwise they won't. To manually change color of previously recorded clips, refer to "Coloring clips".**

- ▶ **To automatically set a new color for new tracks, make sure the "Auto-color New Sequencer Tracks" box in the Options menu is ticked.**
  The track color will be automatically selected from the palette when you create a new track.

Naming tracks

Devices (and tracks) get the name of their loaded patch by default, but you can override this by manually renaming:

- ▶ **Name, or rename, a track by double-clicking its name tag in the Track List, typing in a name and pressing [Return].**
  Note that naming/renaming a track also changes the name of the associated Source Device in the rack (and vice versa). Furthermore, renaming an audio track also changes the name of the associated Audio Track device in the rack as well as its corresponding channel strip in the Main Mixer. If you rename the track of a source device in a device group, its Mix Channel will get the same name. If you want a separate name for the Mix Channel, double-click in the Mix Channel name tag, in the rack or Main Mixer, type in a new name and press [Return].

  See "Creating devices" for more information about device groups.

Muting tracks

To mute a track means to silence it, so that no data is sent from the track during playback. This can be useful when you are trying out different versions of an arrangement, for bringing elements in and out of the mix during playback.

- ! **Note that muting a sequencer track is NOT the same as muting a mixer channel in the main mixer (see "MUTE/SOLO buttons").**


- ▶ **To mute a track, click the corresponding Mute (M) button in the Track List.**
  Everything present on the track will be muted.



A red "M" button in the Track List indicates that the track is muted.

- ▶ **To unmute the track, click the "M" button again.**

- ▶ **Several tracks can have Mute active at the same time, in which case you can unmute them all by clicking the master "M" button at the top of the Track List.**




- ▶ **It's also possible to mute individual lanes and individual clips on a track. Refer to "Muting lanes" and "Muting clips".**

Soloing tracks

To solo a track means that all tracks in the sequencer, except for the soloed track, are muted.

! **Note that soloing a sequencer track is NOT the same as soloing a mixer channel in the main mixer (see "MUTE/SOLO buttons").**


▶ **To solo a track, click the corresponding Solo (S) button in the Track List.**
This mutes all other (un-soloed) tracks. Soloed tracks have green S buttons.



Here, the "Filmscore Pad" track is soloed (indicated by the green "S" button).
All other tracks are automatically muted (indicated by red "M" buttons).

▶ **To turn solo off, click the green "S" button again.**

▶ **Several tracks can have Solo active at the same time, in which case you can turn off Solo for all of them by clicking the master "S" button at the top of the Track List.**



Lane details


A track consists of one (default) or several parallel lanes. Depending on track type, the clips on the lanes can contain various types of events. A lane can also contain clips with performance controller and parameter automation events - or pattern selection for pattern based devices.

Audio lane



The audio lane is not distinguished by a separate lane tab in the Track List like the other lane types. This is simply because an audio track can only have a single audio lane. Consequently, all audio lane elements reside in the audio track section instead.

Audio lane elements



- **Record Enable button**
  To the right of the Record Enable Parameter Automation button is the Record Enable button. Make sure this button is on (red) before recording audio on the track. By default, this is activated when you select an audio track. If you want to record several audio tracks at the same time you need to click their Record Enable buttons first.
- **Monitor button**
  To the right of the Record Enable button is the Monitor ("speaker") button. Click this button to monitor the input signal of the track. The signal is monitored after the audio track channel strip which means that all channel strip parameters, including any Insert FX, Dynamics etc., will be monitored.

! **The Monitor button activation/deactivation depends on the setting in the "Monitoring" section on the "User Interface" tab in Settings. If "Manual" is selected, you will have to manually activate the Monitor button. If "Automatic" is selected, the Monitor button is automatically activated when the Record Enable button is on.**


- **Enable Tuner button**
  Below the buttons is the Enable Tuner button. Click the button to switch to Tuner mode. The Input Meter to the right will switch to a Tuner.



Audio track in Tuner mode.


In Tuner mode, you can tune a connected instrument - an electric guitar, for example. See "Using the Tuner" for more info.

- **Select Audio Input drop-down list**
  To the right of the Tuner button is the Select Audio Input (IN) drop-down list. Here, you select which audio input(s) to use for the track. See "Selecting audio input(s) and defining mono or stereo" for more info.



- **Input Meter**
  The Input Meter shows the level(s) of the input signal(s). If the selected audio input is mono, the Input Meter displays a single LED bar. If the audio input is in stereo, the Input Meter displays two parallel LED bars. See "Setting input level(s)" for details about setting input levels.

Note lane



As the name implies, the note lane can contain clips that feature note events. Clips on a note lane can also contain performance controller events. One or several note lanes can be present on an instrument track.

Note lane elements



- **Name**
  At the bottom to the left is the name of the lane. As soon as you create a note lane it will automatically be named "Lane n" where "n" is the number of the lane - in chronological order. You can change the name of the lane by double-clicking in the name field, typing in a new name and then pressing [Return] on the computer keyboard.


! **Note that depending on the current magnification of the Arrange Area, the note lane names could sometimes be hidden. To make the note lane names visible, increase the Track height, for example, by dragging the bottom edge of the track downwards, or by clicking the + magnification button below the sequencer Track List.**



Increase the track height to reveal any hidden Lane names.

- **Record Enable button**
  Above the note lane name is the "Record Enable" button. Make sure this button is on (red) before recording on the lane. By default, the "Record Enable" button on the latest created/added note lane is automatically activated when you select an instrument track.
- **Groove Select drop-down list**
  To the right of the "Record Enable" button is the "Groove Select" drop-down list. Here you can select a ReGroove channel for all clips on the lane. See more about ReGroove in "The ReGroove Mixer".
- **M (Mute) button**
  Clicking the "M" button will mute the playback from the lane.
- **Delete (X) button**
  To the far right is the "Delete Note Lane" (X) button. Clicking this button will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion.

Parameter automation lane



An instrument track with two parameter automation lanes.

Parameter automation is used for controlling changes of device parameter values in a song. You could, for example, automate a filter cutoff parameter and record filter sweeps at various positions in your song. These kind of parameter value changes are recorded on parameter automation lanes.

Parameter automation lanes can exist in all track types and can contain clips with device and/or channel strip parameter automation. A track can have as many automation lanes as its device has automatable parameters. For Mix Channel and Audio Track devices, parameter automation could be used for any of their corresponding channel strip controls.

Parameter automation lane elements




- **Fold/Unfold button**
  Parameter automation lanes in a track can be folded/unfolded, as a group, by clicking the small triangle on the handle to the far left on the parameter automation lane tab.

▶ **To fold/unfold all parameter automation lanes on all tracks in the sequencer, hold down [Alt](Win) or [Option](Mac) and click on the triangle on a parameter automation lane tab.**

- **Name**
  The name of the automated parameter is displayed on the parameter automation lane tab. Since the name reflects the original device/channel strip parameter name, this cannot be changed. When parameter automation lanes are folded, the name will simply be "Automation".

- **M (Mute) button**
  Clicking the "M" button will mute the parameter automation playback from the lane. Muting a parameter automation lane will freeze whatever value the parameter had when you muted the lane. Deactivating the Mute button reactivates the automation.
- **Delete Automation Lane (X) button**
  To the far right is the "Delete Automation Lane" (X) button. Clicking this button will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion. See "Deleting parameter automation lanes" for alternative ways of deleting parameter automation lanes.


Pattern lane



A Redrum track featuring a pattern lane.

A pattern lane can only exist in a track featuring a pattern based device, such as the Redrum Drum Module or the Matrix Analog Pattern Sequencer. A pattern lane can only contain clips with pattern Bank and pattern Number automation data. There can only be a single pattern lane per track.

Pattern lane elements



- **Name**
  The name of the automated parameter is displayed on the pattern automation lane tab. Since the name reflects the original device parameter name, this cannot be changed.
- **M (Mute) button**
  Clicking the "M" button will mute the pattern automation playback from the lane. Muting a pattern automation lane will freeze whatever value the parameter had when you muted the lane. Deactivating the Mute button reactivates the pattern automation.
- **Delete Pattern Lane (X) button**
  To the far right is the "Delete Pattern Lane" (X) button. Clicking this button will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion. See "Deleting pattern lanes" for alternative ways of deleting pattern lanes.

Creating/adding lanes


Adding note lanes

You can add additional note lanes on an instrument track. This can be useful under the following circumstances:

- **If you want to overdub notes or performance automation but don't want to record in existing clips.**
- **If you want to record a series of takes on separate note lanes, to later decide which take is the "best" (or to edit together a composite).**
- **If you want to apply different ReGroove grooves to different parts of a track, or want different grooves on separate drums on a drum track.**


You can create new note lanes for selected instrument tracks in the following ways:

- **Select "New Note Lane" from the Edit menu or from the context menu.**
  A new note lane will be created and will also be automatically record enabled.
- **Click on the "New Note Lane" (Lanes +) button at the top of the Track List.**




  A new Note Lane will be created and automatically record enabled.

- **Click on the "Dub" button on the Transport Panel.**



  A new note lane will be created and automatically record enabled. See "Recording notes using the "Dub" and "Alt" functions" for more details.

- **Click on the "Alt" button on the Transport Panel.**



  A new note lane will be created and automatically record enabled. At the same time, the previous note lane, or (if loop is activated and the Song Position Pointer is between the Left and Right Locators) the clips between the Left and Right Locators, will be muted. See "Recording notes using the "Dub" and "Alt" functions" for more details.

- **Note that the "Dub" and "Alt" functions can also be used on-the-fly during recording without stopping the sequencer.**

Creating/adding parameter automation lanes

Parameter automation lanes can be created for all track types.

- **During recording of a track, changing any parameter values on the device/channels strip will automatically create a new parameter automation lane for each unique parameter. See "Recording parameter automation" for more details.**


Do as follows to manually create a parameter automation lane on a selected track:

▶ **Hold down [Alt](Win) or [Option](Mac) and click on a device parameter in the rack, or on a channel strip parameter in the Main Mixer. Alternatively, select "Edit Automation" from the parameter's context menu.**
A new parameter automation lane will be automatically created in the track for the corresponding device or channel strip. The automated parameter on the device in the rack or channel strip in the Main Mixer will get a green border, indicating that it has been automated.

! **Note that if a track hasn't already been created for the device/channel strip, it will be automatically created during this operation.**

Other ways of creating/adding a parameter automation lane are as follows:

1. **Click on the "Track Parameter Automation" drop-down list at the top of the Track List.**



2. **Select the parameter you want to automate from the list.**
A new parameter automation lane is automatically created on the selected track.


   If you click the Track Parameter Automation drop-down list again, any selected parameters will have a symbol to the left of the parameter name, indicating that an automation lane already exists for the parameter.

   The automated parameters on the device in the rack or channel strip in the Main Mixer will get green borders, indicating that they have been automated.

Creating a pattern lane

For pattern based devices such as the Redrum Drum Module and Matrix Analog Pattern Sequencer, a single pattern lane can be created on a selected track. Do either of the following:

▶ **Click the "Create Pattern Lane" button at the top right of the Track List.**



▶ **Select "Create Pattern Lane" from the Edit menu or from the context menu.**

▶ **Hold down [Alt](Win) or [Option](Mac) and click on the "Pattern" button section of the device in the rack.**

▶ **Right-click (Win) or [Ctrl]-click (Mac) on the "Pattern" button section of the device in the rack and select "Edit Automation" from the context menu.**

When you create a pattern lane, the bank buttons on the device in the rack get a green border to indicate that they have been automated.

▶ **Clicking the Pattern and/or Bank buttons on the device during recording will automatically create a pattern lane. See "Recording pattern automation" for more details.**

Deleting lanes

Deleting note lanes

A note lane can be deleted as follows:

- **Click the "Delete Note Lane" (X) button on the lane tab in the Track List.**
  This will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion.



- **To delete the lane without the dialog, hold down [Ctrl](Win) or [Cmd](Mac) and click the Delete Note Lane button.**

Deleting parameter automation lanes

There are a number of different ways of deleting a parameter automation lane:

- **Click the "Delete Automation Lane" (X) button on the lane tab in the Track List.**
  This will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion.




- **To delete the lane without the dialog, hold down [Ctrl](Win) or [Cmd](Mac) and click the Delete Automation Lane button.**

Another way is this:

- **Right-click (Win) or [Ctrl]-click (Mac) on the automated device parameter in the rack and select "Clear Automation" from the context menu.**
  The green border around the device parameter disappears and the corresponding parameter automation lane is deleted from the track.

Alternatively, do the following:

1. **Select a track by clicking on it.**
2. **Click on the "Track Parameter Automation" drop-down list at the top of the Track List.**




3. **De-select the parameter you want to delete from the list.**
   All selected parameters will have a symbol to the left of the parameter name in the list indicating that it has been selected. Selecting a parameter with a symbol in the list will automatically delete the corresponding lane, with its clips, from the track. If there are clips on the lane, a dialog appears prompting you to confirm deletion.

   The green borders that surrounded the automated parameters on the device/channels strip will also be removed.

Deleting pattern lanes

There are two ways of deleting a pattern lane:

- ▶ **Click the "Delete Pattern Lane" (X) button on the lane tab in the Track List.**
  This will delete the lane (and all clips on it). If there are clips on the lane, a dialog appears prompting you to confirm deletion.



- ▶ **To delete the lane without the dialog, hold down [Ctrl](Win) or [Cmd](Mac) and click the Delete Pattern Lane button.**


Alternatively:

- ▶ **Right-click (Win) or [Ctrl]-click (Mac) on the automated pattern section on the device in the rack and select "Clear Automation" from the context menu.**
  The green border around the device pattern section disappears and the corresponding pattern lane is deleted from the track.

Moving note lanes

A note lane has a "handle" and can be moved vertically together with all clips on the lane. Move a note lane to another position on the same track like this:

1. **Click on the lane handle (the leftmost area of the lane).**



2. **Drag the note lane up or down and release at the desired destination.**
   Just as when moving tracks, a red insertion line is shown indicating where the note lane will be placed after you release the mouse button.

- ▪ **It is also possible to move note lanes, with their clips, between tracks.**
  Just drag the note lane to the other track and release on the new track in the Track List.

! **Parameter automation lanes and pattern lanes cannot be moved since they are tightly connected with their associated devices However, you can move or copy clips from one lane to another.**

Copying (duplicating) note lanes

You can copy (duplicate) one note lane at a time, together with its clips, by doing the following:

1. **While pressing [Ctrl](Win) or [Option](Mac), click and drag a copy of the note lane to the desired destination.**
   The cursor gets a + sign next to it to indicate duplication. The destination of the duplicated note lane could be the same track or another track.
2. **Release the mouse button.**

! **Parameter automation lanes and pattern lanes cannot be duplicated.**

Muting lanes

Muting a note lane


▶ **To mute a note lane, click its "M" (Mute) button.**



The note lane's "M" (Mute) button.

Muting a parameter automation lane

▶ **To mute a parameter automation lane, click its "M" (Mute) button.**




The parameter automation lane's "M" (Mute) button.

Clip basics

Only the basic properties and functions pertaining to clips are described here. See "Arranging in the Sequencer" for in-depth details about what you can do with clips.


Clip types

Here are the different clip types:



- **Block automation clips (only if Blocks are on) that contain information of which Block should play back.**
- **Folder clips are not actual clips, but graphical representations of the clips inside the folder. See "Track Folders in the Sequencer".**
- **Note clips contain note events with velocity values. Note clips can also contain performance controller events.**
- **Parameter automation clips contain events for an automated device/channel strip parameter.**
  A parameter automation clip can easily be distinguished by the shape of its frame: the top right corner is "cut off".
- **Audio clips contain mono or stereo audio recordings.**
  If the audio clip is a Comp clip, or a Single Take clip which contains several takes, there is a small symbol in the lower right corner of the clip.
- **Pattern automation clips contain device bank+pattern number.**


Toolbar details



The Sequencer Toolbar can be found to the top left in the Sequencer Area. From the Sequencer Toolbar you can select various sequencer editing tools.

Toolbar tools


Selection Tool



The Selection (arrow) Tool is the main tool for selecting and moving tracks, note lanes, clips and events and recordings in clips. It's also used for resizing clips and events in clips. It is selected by default when a song is opened.

- **You can also select the Selection Tool by pressing [Q] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Selection Tool to the Pencil Tool - or to the Speaker Tool when editing an open audio clip inline - or to the Cut (Razor) Tool when editing an open audio clip in the Comp Editor.**

Pencil Tool




The Pencil Tool is used for manually drawing clips and events in clips. It can also be used to edit the velocity values of notes in open note clips.

- **You can also select the Pencil Tool by pressing [W] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Pencil Tool to the Selection Tool.**

! **When a note clip is open in the Edit Area, there two different Pencil Tools are available - one for drawing single notes with varying lengths and one for drawing repetitive notes of the same length, see "Drawing notes".**


Eraser Tool



The Eraser Tool is used for deleting clips and events. In audio Pitch Edit mode you can also join notes with the Eraser.

- **You can also select the Eraser Tool by pressing [E] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Eraser Tool to the Pencil Tool.**


Razor Tool



The Razor Tool is used for splitting clips and notes - and for creating cuts when comping audio recordings in the Comp Editor.

- **You can also select the Razor Tool by pressing [R] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Razor Tool to the Pencil Tool - or to the Selection Tool when editing an open audio clip on the Edit Pane.**


Mute Tool



The Mute Tool is used for muting clips in the arrangement - or lanes in Block automation clips (see "Muting lanes in Block Automation Clips").


- **You can also select the Mute Tool by pressing [T] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Mute Tool to the Razor Tool.**

Magnifying Glass Tool




The Magnifying Glass Tool lets you zoom in and out both horizontally and vertically on the Arrangement Pane. The Magnifying Glass Tool offers a couple of possibilities:

- **To zoom in with the Magnifying Glass Tool, click in the Arrange Area where you want the origin of magnification.**




Place the Magnifying Glass Tool in the Arrangement Pane and click.




After three clicks, the Arrangement Pane looks like this. The magnification is equal in vertical and horizontal directions.

- **To zoom out with the Magnifying Glass Tool, hold down [Ctrl](Win) or [Option](Mac) and click.**
  You'll notice that the "+" sign in the Magnifying Glass Tool changes to a "-" sign.

- **You can also click and drag with the Magnifying Glass Tool to create a selection rectangle.**
  The view will then be zoomed in so that the selected area fills the entire Arrange Area.




Place the Magnifying Glass Tool in the Arrange Area, click and drag to create a selection.



After releasing the mouse button, the zoomed selection fills up the Arrange Area. The magnification can be different in vertical and horizontal directions depending on the shape of the selection rectangle.


- **You can also select the Magnifying Glass Tool by pressing [Y] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Magnifying Glass Tool to the Hand Tool.**
- **It's also possible to zoom in the Arrange Area by using the Sequencer Area Navigators and Zoom To Selection function as described in "Zooming in the Sequencer" and "Zooming to selection".**

Hand Tool




The Hand Tool is used for scrolling in the Edit/Arrangement Pane.

- **Select the Hand Tool and click anywhere in the Edit/Arrangement Pane, keep the mouse button depressed and drag to desired view.**



- **You can also select the Hand tool by pressing [U] on the computer keyboard.**
- **Press [Alt](Win) or [Cmd](Mac) to momentarily switch from the Hand Tool to the + Magnifying Glass Tool.**
- **Press [Ctrl]+[Alt](Win) or [Cmd]+[Option](Mac) to momentarily switch from the Hand Tool to the - Magnifying Glass Tool.**
- **It's also possible to scroll in the Arrange Area by using the Sequencer Area Navigators as described in "Scrolling with the scrollbars and Navigators".**

Speaker Tool




The Speaker Tool is used for auditioning slices or notes in Single Take audio clips, and for auditioning individual recordings on Comp Rows in Comp Clips. See "Slice Edit mode tools", "Auditioning notes" and "Comp Editor audio editing tools" for details.

Alternate tools

For every tool mode described earlier, there is a so called alternate tool that can be momentarily selected by holding down [Alt](Win) or [Cmd](Mac) on the computer keyboard. Below is a summary of the alternate tools:

Selected tool	Alternate tool
Selection tool	Pencil tool (Speaker tool when editing an audio clip in the Edit Area, except for Comp Edit where the alternate tool is the Cut (Razor) tool)
Pencil tool	Selection tool
Eraser tool	Pencil tool
Razor tool	Pencil tool (Selection tool when editing open audio clip on the Edit Pane)
Mute tool	Razor tool
Magnifying Glass tool	Hand tool
Hand tool	+ Magnifying Glass tool
Hand tool	- Magnifying Glass tool by pressing [Alt]-[Ctrl](Win) or [Option]-[Cmd](Mac)


Snap




The Snap function in the sequencer toolbar is used for "restricting" editing of clips and events to a user-selectable note value grid.

! **Note that when a clip is open in the Edit Area, there is a separate Snap section at the top of the Edit Area Inspector. This Snap function relates to the currently open clip in the Edit Area.**

▶ **Activate the Snap function by pressing [S], or by clicking the Snap button:**




! **When moving clips or events, the Snap function can work either absolute (to the closest absolute position in the grid) - or relative to the clip(s)/event(s) original position(s), in steps of the set Snap value:**



Absolute Snap set to "Bar" (top) and Relative Snap set to "Bar" (bottom).

1. **Select the grid you wish to snap to by selecting the note grid value from the drop-down list:**



2. **Click the drop-down list again and select if you want the Snap to be "Relative" or "Absolute" from the bottom of the drop-down menu.**

! **Note that you can select different Snap values for selected clips in the Arrange/Block View and for open clips in the Edit Area (see "About separate Snap values for selected clips and for open clips").**

The Snap function affects the following operations:


- **Moving the Song Position Pointer, Loop Locators and Song End Marker.**
  When you adjust the Locators with Snap activated, they will always snap to the selected Snap value on an absolute grid, regardless of the setting on the Snap drop-down menu.
- **Moving clips and events, recordings and Comp Row cuts.**
  When you move objects with Snap activated, they will move relative or absolute to the Snap value, depending on what you selected on the Snap drop-down menu.
- **Drawing clips.**
  When you create clips with the Pencil tool, their start and end positions will snap to the selected note value positions on an absolute grid.
- **Drawing events in open clips.**
  The Snap value determines the absolute grid points on which you can draw a note or an automation point. The Snap value also determines the shortest possible note length that you can draw.


- **Splitting clips with the Razor tool.**
  The Snap value determines the absolute grid to which a clip can be split.
- **Nudging clips, events and recording.**
  When you nudge clips, events or recordings with Snap activated, they will move relative or absolute to the Snap value, depending on what you selected on the Snap drop-down menu.
- **Creating Comp Row cuts**
  The Snap value determines the absolute grid to which you could add cuts in open Comp audio clips.
- **Moving Comp Row cuts**
  The Snap value determines the relative or absolute grid to which you could move cuts in open Comp audio clips.
- **Adding and moving Slice Markers**
  The Snap value determines the absolute grid to which you could add and move Slice Markers in open Single Take audio clips.

About the "Grid" Snap value

The "Grid" value at the top in the list is dynamic and automatically changes the snap value, from "Bar" to "1/128", depending on the current horizontal zoom level in the Arrange/Edit Area.

The picture below shows the same clips in the Arrange Area at two different horizontal zoom levels:





About separate Snap values for selected clips and for open clips

There are two different Snap settings, one for when a clip is open for editing in the Edit Area, and one for when no clip is open (e.g. in Song/Block View). Typically, you would set a fine Snap value (e.g. 1/16) for open clips in the Edit Area and have the other Snap value set to "Bar" for convenient clip arranging in the Song/Block View. You can also choose to turn Snap off in either of these areas, independently of the other setting.

- **The Snap value for editing is used when a clip is open in the Edit Area or when an automation clip is opened inline in the Arrange Area.**

Sequencer Toolbar keyboard shortcuts

Below is a complete list of the computer keyboard shortcuts for selecting tools on the sequencer Toolbar:

Function	Key command
Selection tool select	[Q]
Pencil tool select	[W]
Eraser tool select	[E]
Razor tool select	[R]

Function	Key command
Mute tool select	[T]
Magnifying Glass tool select	[Y]
Hand tool select	[U]
Snap On/Off	[S]

Ruler (timeline) details

The Ruler is the song's timeline. In the Ruler, the Song Position Pointer indicates the current position in the song, i.e. in which bar the song is, or will start, playing. The Ruler also shows the Left (L) and Right (R) Loop Locators as well as the Song End Marker (E). Above the Ruler is a Zoom/Scroll area, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".




You can change the positions of the Song Position Pointer, Locators and Marker in the Ruler by clicking and dragging them to desired positions in the Ruler. Note that you have to click and drag the "flags" in the Ruler - not the lines. The Song Position Pointer and Loop Locators can also be moved by typing in new positions in the respective Position displays in the Sequencer Transport Panel (see "Song Position" and "Left and Right Locator Positions"). Another way of moving the Song Position Pointer is by using the Rewind and Fast Forward controls on the sequencer Transport Panel (see "Go to Left and Right Locators").

! **To change the Marker positions, make sure you click in the Ruler/Timeline and not in the darker gray Zoom/Scroll Area above the Ruler.**

Transport Panel details

At the bottom of the Reason song window is the sequencer's Transport Panel. From here you control the sequencer transport functions. You can also set tempo, time signature and various other parameters.



Click Level

▶ **Adjust the audio level of the metronome (and Pre-count) with this slider.**

Click On/Off

- **Click this button to hear an audible metronome click as the sequencer plays.**
  The click will sound on every beat, with the first beat in every bar accented (higher pitched). See "Click and Pre-count" for more details.

Tap Tempo

Instead of setting the Tempo with the Tempo control (see above), you can manually tap in the desired tempo in real-time.

Pre(-count) On/Off

- **Click the Pre button to hear a pre-count (count-in) click sound before recording.**
  Pre-count will only be present before recording - not before regular playback. See "Click and Pre-count" for details about selecting number of pre-count bars etc.

  See "Click and Pre-count" for more details.

Tempo

The current song tempo is shown in the display in BPM (Beats Per Minute) and 1/1000 of a BPM. You can edit the tempo according to the descriptions in "Transport Panel segment displays". The Tempo range is 1.000-999.999 BPM.

- **Click the Tap button repeatedly to set desired sequencer tempo.**
  The tempo is defined by averaging the time between a minimum of two clicks and a maximum of 16 clicks. The more clicks, the more "steady" the tempo. The time-out between two series of clicks is 2 seconds. The detectable tap tempo range is 30-999.999 BPM.

Time Signature

The current song time signature is shown in the display. You can edit the time signature according to the descriptions in "Transport Panel segment displays".

The available Signatures are: 1/2-16/2, 1/4-16/4, 1/8-16/8 and 1/16-16/16.


Song Position

The current song position is shown in the display. The song position is where the Song Position Pointer in the Ruler (see "Ruler (timeline) details") is at the moment. The display is divided into Bars, Beats, 1/16th Note and Ticks (there are 240 Ticks for each 16th note) segments. You can edit the position of the Song Position Pointer, and thus change the song playback position, according to the descriptions in "Transport Panel segment displays".

About subticks in the Song Position display

When editing notes and automation events in the sequencer you have a resolution of 240 ticks per 1/16th note, which allows for very accurate positioning. But for the Song Position Pointer, the internal resolution is even higher (15360 ppq) which means that the position can end up on a fraction of a tick, a so called subtick.

If the Song Position Pointer value is on a fraction of a tick, this is displayed with an asterisk (*) in the Tick section of the Song Position display.



- **To adjust the Song Position Pointer to the closest tick value, press [Ctrl](Win) or [Cmd](Mac) and click on the asterisk in the display.**
  The Song Position Pointer will now adjust to the closest tick value and the asterisk disappears.

Time Position

The current position of the Song Position Pointer in the Ruler (see "Ruler (timeline) details") is shown in time format (hours, minutes, seconds and milliseconds) in the display. You can change the position in time of the Song Position Pointer, and thus change the song playback time position, according to the descriptions in "Transport Panel segment displays".

Rewind and Fast Forward

- **Click on the Rewind or Fast Forward buttons to move the Song Position Pointer in steps of one bar (from its current position).**
- **To move the Song Position Pointer several bars at once, click and hold the mouse button depressed.**

Instead of clicking the buttons, you can use the computer keyboard:

- **Press [4] on the numeric keypad for Rewind and [5] for Fast Forward.**
- **If you click and hold the Rewind or Fast Forward buttons, or press and hold the [4] or [5] keys, the positioning speed will be faster after the first 20 bars.**

Play and Stop

- **Click the Play button to start playback from the Song Position Pointer's current position.**
- **Alternatively, press [Enter] on the numeric keypad on the computer keyboard.**
- **Click the Stop button to stop playback (or recording).**
- **Alternatively, press [0] on the numeric keypad or [Shift]+[Return] on the computer keyboard.**

By default, if you click the Stop button or use the keyboard "Stop" commands when the song is already stopped, the Song Position Pointer is moved according to the following rules:

- **Clicking/pressing Stop the first time moves the Song Position Pointer to where playback was last started.**
- **Clicking/pressing Stop a second time moves the Song Position Pointer to the beginning of the song.**
- **If the Song Position Pointer already is at the beginning of the song, nothing happens.**
  This means you can always click twice on the Stop button in "stop mode", to return to the beginning of the song.

- **Press [Spacebar] on the computer keyboard to toggle between Play and Stop.**


- **To have the Song Position Pointer automatically return to its last start position when you hit Stop, select "Return to last start position on stop" on the "User Interface" tab in Settings, see "Return to last start position on stop".**

About MIDI Note Chase


When playing back notes in note clips, the notes trigger (start) when the Song Position Pointer (playhead) advances past the beginning of the notes. If the Song Position Pointer has advanced past the note start and is then stopped, clicking Play again won't re-trigger the notes by default.

You can change this behavior so that notes re-trigger, even when the Song Position Pointer has advanced past the note starts.

▶ **Select “Chase Notes During Playback” on the “Playback and Recording” sub menu in “Options”:**



Now, if you stop the sequencer in the middle of notes in a note clip, and then click Play again, the notes will automatically re-trigger:



! **The “Chase Notes During Playback” function retriggers the notes, i.e. sends a new “Note On” to the notes.**

Record

▶ **Click the Record button to begin recording on the selected track/lane in your song.**
Alternatively, press [*] on the numeric keypad or hold down [Ctrl](Win) or [Cmd](Mac) and press [Return] on the computer keyboard. If Pre-count has been activated (see “Pre(-count) On/Off” above), the recording will begin after the set number of pre-count bars.

! **Nothing will be recorded during the pre-count period.**

Dub and Alt

Clicking on any of these buttons will add additional audio tracks or note lanes for overdub purposes. Refer to “Overdubbing audio using the “Dub” function” and “Recording notes using the “Dub” and “Alt” functions” for more details about these functions.

Loop On/Off

▶ **Click the Loop button or press [L] to activate the Loop function.**

When the loop function is activated, recording and playback will be continuously looped between the Left and Right Locators. Some general rules regarding loop mode are these:

- **If the Song Position Pointer is to the left of (before) the Right Locator when playback is started, the song will play to the Right Locator and then immediately jump back and seamlessly continue from the Left Locator.**
- **If the Song Position Pointer is to the right of (after) the Right Locator when playback is started, the Locators will be ignored and the song will continue to play “un-looped”.**

- **If the Left Locator is to the right of the Right Locator, i.e. in "reversed" order, the song will play to the Right Locator and then immediately jump and seamlessly continue from the Left Locator, skipping the part of the song in-between the Locators. The song will then continue to play "un-looped".**

Left and Right Locator Positions

The current positions of the Left and Right Locators in the Ruler (see "Ruler (timeline) details") are shown in the displays. The display is divided into Bar, Beat, 1/16th Note and Ticks (there are 240 Ticks for each 1/16th Note). You can change the positions of the Locators, and thus change the loop playback region, according to the descriptions in "Transport Panel segment displays".

Go to Left and Right Locators

- **Click on the "L" or "R" button to move the Song Position Pointer to the Left or Right Locators respectively.**
- **Alternatively, press [1] on the numeric keypad on the computer keyboard to move the Song Position Pointer to the Left Locator or [2] to move to the Right Locator.**

Quantize value

- **Select the desired quantization value from the drop down list.**
  Refer to "Quantize" for more information on quantization.

Quantize

- **Click the Quantize button to quantize the notes in the selected clips to the selected Quantize value - after they have been recorded.**
  Refer to "Quantize" for more information on quantization.

Q Rec

- **Click the Q Record (Quantize during recording) button to quantize notes as they are being recorded.**
  When the Q Record button is on, all recorded MIDI notes will be quantized to the currently selected quantization grid.
  Refer to "Quantize" for more information on quantization.

Sync Mode


Here you can set the desired synchronization mode for the Reason sequencer: Internal, MIDI Clock (if applicable) or Ableton Link (if applicable). You can also choose "Send MIDI Clock" to sync other applications/instruments from Reason (if applicable). See the chapter "Synchronization and Advanced MIDI" for more information about synchronization.

Transport keyboard commands and modifier keys

Below is a complete list of the computer keyboard shortcuts for the Sequencer Transport functions:

Function	Key command
Stop, Go to start position, Go to start of song	[0] on the numeric keypad or [Shift]+[Return]
Play	[Enter] on the numeric keypad
Toggle Stop/Play	[Spacebar]
Rewind	[4] on the numeric keypad
Fast Forward	[5] on the numeric keypad
Record	[*] on the numeric keypad or [Ctrl](Win) or [Cmd](Mac)+[Return]
Go to Left Locator	[1] on the numeric keypad
Go to Right Locator	[2] on the numeric keypad
Go to the start of the song	[.] on the numeric keypad
Move forward one bar	[8] on the numeric keypad
Go back one bar	[7] on the numeric keypad
Tempo up	[+] on the numeric keypad
Tempo down	[-] on the numeric keypad
Loop On/Off	[/] on the numeric keypad or [L]
Click On/Off	[C] or [9] on the numeric keypad
Pre-count On/Off	[Ctrl](Win) or [Cmd](Mac)+[P]
Set the Left and Right Loop Locators to encompass selected clips.	[Ctrl](Win) or [Cmd](Mac)+[L]
Set the Left and Right Loop Locators to encompass selected clips and start play-back in Loop Mode.	[P]
Set Left Locator in ruler.	[Ctrl](Win)/[Option](Mac)+Click in the ruler
Set Right Locator in ruler.	[Alt](Win)/[Cmd](Mac)+Click in the ruler
Set End Marker in ruler.	[Shift]+Click in the ruler

About the Arrange Area Inspector




The Arrange Area Inspector, located above the Arrange Area, can be used for a number of different editing purposes pertaining to clips. The Arrange Area Inspector is context sensitive, meaning it will have different content and functionality depending on what is currently selected. How to edit using the Inspector is described in detail in the "Arranging in the Sequencer" chapter.

! **When the Pencil Tool is selected, the Inspector isn't visible. Instead, menus pertaining to Time Signature, Pattern Automation and Blocks Automation are displayed.**

About subticks in the Position and Length displays

When editing notes and automation events in the sequencer you have a resolution of 960 ppq (240 ticks per 1/16th note), which allows for very accurate positioning. But when you record, the internal resolution is even higher (15360 ppq) which means that notes and automation events can end up on a fraction of a tick, a so called subtick.


If the value is a fraction of a tick, this is displayed with an asterisk (*) in the Tick section of the Position or Length display.



▶ **To adjust the clip or event position (or length) to the closest tick value, press [Ctrl](Win) or [Cmd](Mac) and click on the asterisk in the display.**
The position or length value will now adjust to the closest tick value and the asterisk disappears.

! **When it comes to audio editing, you will have access all the way down to the sub-tick level. This means there won't be any sub-tick asterisks when editing audio.**

About the "Match Values" function




The "Match Values" function in the Arrange Area Inspector can be used to match the positions, lengths and/or values of several selected clips, notes, events or recordings to the position, length and/or value of the topmost (or leftmost) selected clip, note, event or recording. Refer to "Matching clips using the "Match Values" function", "Matching audio values using the "Match Values" function" and "Matching notes or events using the "Match Values" function".

The Track Panel


To the left of the Sequencer Track List is the Track Panel. The Track Panel displays the Rack devices (instruments, effects, Players, etc.) that are associated with the currently selected sequencer track. Using the Track Panel is a "shortcut" to creating your device configurations, without needing to go to the Rack area/window.

! **Everything you do on the Track Panel is automatically reflected in the Rack - and vice versa.**

▶ **Click the Track Panel button in the top bar to show the Track Panel.**
Alternatively, select "Show Track Panel" from the View menu.



Track Panel elements



Example of a Track Panel configuration for an Instrument track, with an additional Player and some Effects

The device sections on the Track Panel are laid out as follows:

- **At the top of the Track Panel, below the sequencer track name label, is the Player section.**
  Here you can add one or more Player devices to your Instrument device.
- **Below the Player section is the Instrument section.**
  Here is where the Instrument device is located. If you like you could add Effect devices below the Instrument device, by dragging and dropping from the Device Palette (see below). This will automatically route the Effect device(s) to the Instrument device - or to another Effect, if there already is one in there.
- **In the Mix Channel section you can add Effect devices you want to have in the Insert Effect container of the Mix Channel.**
  You can add Effect devices by dragging and dropping from the Device Palette, or by using the Browser, as described below. You could add several Effect devices here, and also re-route, if you like.
- **In the Sends section you can add Effect devices to any of the eight Send Effect buses in Reason's Main Mixer.**
  Note that adding Send Effects will also make the Effects available to the other Mix Channels in the song, since Send Effects are shared among all Mix Channels.
- **The Mixer Fader section mirrors the Fader section of the track in the Main Mixer.**
  Editing a parameter here will automatically change the corresponding parameter in the Main Mixer - and vice versa.
- **With the Channel routing selector you select where you want to route the signal - to the Master Section, or to an Output Bus.**
  To view the Master Section or the selected Bus in the Rack, click the arrow button next to the Output Bus name.
- **The Track Panel for a selected audio track or Output Bus channel only has Insert FX, Sends, Mixer Fader and Channel routing sections.**

Adding devices on the Track Panel


Devices can be added to the Track Panel in two different ways:

- **By clicking the + buttons and selecting the device from the context menu that appears:**



! **Note that you can only add Players, Insert Effects and Send Effects using the + buttons.**


- **By dragging devices from the Device Palette and dropping in the desired Track Panel section:**



An orange insertion line with a + sign appears where the device will be inserted

Bypassing Effects on the Track Panel

- **Hover over the Effect device and click the green circular button, to bypass the effect.**
  The Bypass/On/Off switch on the Rack device will automatically switch to Bypass to mirror the setting:




Bypassing the Effect on the Track Panel will switch the Rack device to Bypass as well

Replacing devices or patches on the Track Panel


Devices or patches can be replaced on the Track Panel in two different ways:

- **By clicking the folder button on the selected device and selecting a new device patch in the Browser:**



Hovering over the device brings up a folder button that you can click to select a new patch

- **By dragging a device from the Device Palette and dropping onto an existing device on the Tack Panel:**




An orange rectangle appears around the device that will be replaced

Moving and re-routing devices on the Track Panel

Devices can be moved and automatically re-routed on the Track Panel in as follows:

- **By dragging the desired device and dropping at the desired new position on the Track Panel.**
  The connections between the devices will be automatically re-routed.



An orange insertion line with a + sign appears where the device will be moved/rerouted

! **Note that only Players and Effects can be moved and automatically rerouted.**

About signal splits, parallel channels and merges


The Track Panel shows the signal path for a single Source Device (typically an instrument or audio track). But this path may be split into several. Some examples:

- **Instrument devices can have multiple outputs.**
  For example, drum instruments such as Kong and Redrum have individual outputs that can be connected to separate effect chains and mixer channels.
- **A Mix Channel or Audio Track may have parallel channels (see "Parallel Channels").**
- **Some devices can split the signal (e.g. Spider Audio Splitter or Gain Tool).**

Signal splits

When the signal path is split, the Track Panel shows a selector with number buttons. Click a button to show that signal path in the Track Panel:






A Redrum with main outputs + two individual Drum outputs connected to separate Mix Channels. The three channels have different insert effects.

Parallel channels

Parallel channels are shown with number buttons in the Insert FX container headers on the Track Panel:






This audio track has a parallel channel, with a Stereo Tool and an Audiomatic effect.

Signal merges

Two or more signal paths within the Device Group can also be merged, e.g. by a Spider Audio Merger or a Rack Mixer device. This is indicated by a Merge symbol:






The signal path is split in two with a Spider (Splitter); then merged back again with a Gain Tool in X-fade mode.

Using Send Effects on the Track Panel

Adding Send Effects on the Track Panel


Send Effects can be added on the Track Panel as follows:

- **By clicking the + button and selecting the Send Effect patch or device from the popup menu:**



Hovering over the device brings up a folder button that you can click to select a new patch

- **By dragging Effect devices from the Device Palette and dropping at the bottom of the Sends section:**




An orange insertion rectangle with a + sign appears where the device will be inserted

! **Note that you cannot add a Send Effect between existing Send Effects - only at the last (bottom) position.**

! **Note that adding a Send Effect will allow all Mixer channels to use that specific effect.**

Setting Send Effect Levels on the Track Panel

▶ **Click and drag the green level bar sideways to set the desired Send Level:**



Turning Send Effects on/off on the Track Panel

▶ **Click the green circular button on the desired Send Effect, to turn off the effect.**
The Send FX button on the Main Mixer channel will automatically mirror the setting:



Turning off the Send Effect on the Track Panel will switch off the corresponding Send FX button for the channel in the Main Mixer.

Replacing Send Effects on the Track Panel

▪ **Drag an Effect device from the Device Palette and drop onto an existing Send Effect device on the Tack Panel:**




An orange replacement rectangle appears around the device that will be replaced

! **Note that replacing a Send Effect will affect all Mixer channels that uses that specific effect.**

Showing the devices in the Rack


- **To show a device in the Rack (to edit the device parameters, for example), double click it on the Track Panel.**
  You can also hover over the device and click the arrow button, or right-click it and select "View in Rack" from the context menu.



Deleting devices from the Track Panel

Devices can be deleted from the Track Panel in following ways:

- **By selecting the device on the Track Panel and pressing [Delete] or [Backspace].**



- **By right clicking the device on the Track Panel and selecting “Delete Device” from the context menu.**

In all scenarios, the signal chain between the remaining devices will be preserved.

! **The Source Device (instrument or audio track) cannot be removed from the Track Panel. To delete a Source Track, select it in the track list and press Delete or Backspace.**

Chapter 6
Recording in the Sequencer


About this chapter

This chapter describes the different recording techniques that you can use in Reason. The chapter covers both audio, notes and parameter automation recording. Before you read this chapter, it's recommended that you are familiar with the basic sequencer functions and definitions described in the "Sequencer Functions" chapter. A lot of functions are common for all types of recording methods. These will be described first in this chapter. Later in the chapter we will go into functions specific to audio, notes and parameter automation recording.

General recording functions

Record enabling

Before you can start recording on a track in the sequencer, the track needs to be record enabled. There are two types of buttons for record enabling: the Record Enable button, which is used when recording audio clips and note clips, and the Record Enable Parameter Automation button, which is used when recording device/channel strip parameter automation and tempo automation:



Five tracks with their Record Enable and Record Enable Parameter Automation buttons.

Activated Enable Record and Enable Record Parameter Automation buttons are indicated with a red color. Recording can be simultaneously enabled on an unlimited number of audio tracks (limited only by the computer's processing and hard disk performance) - plus one note lane on an instrument track. However, if you have locked several MIDI keyboard controllers to specific instrument devices in the rack - using Remote (see "Locking a surface") - you can record MIDI on these instrument tracks simultaneously. Recording of parameter automation can be simultaneously enabled on as many tracks as you like.

Record enabling an audio track




▶ **To record enable an audio track, click on the Record Enable button on the audio track.**
The Record Enable button goes red.

Selecting an audio track will automatically record enable the track if you have selected "Standard" mode in the "Master Keyboard Input" section on the "MIDI" tab in the Settings dialog (see "The Master Keyboard Input setting") - and if the Manual Rec button in the Track List is Off, see "About the Manual Rec function".

Also, depending on the setting in the "Monitoring" section on the "User Interface" tab in Settings, monitoring of the input signal to the audio track may, or may not, be automatically activated - see "Monitoring".


Record enabling multiple audio tracks

▶ **If you want to record audio from separate audio inputs on several tracks at once, click the Record Enable buttons on all desired audio tracks in the Track List.**
Each record enabled audio track will automatically unfold to show the Tuner button, the Select Audio Input drop-down list and the Input Meter. When recording audio on several tracks simultaneously, it doesn't matter which audio track has Master Keyboard Input.



Multiple audio tracks record enabled, for recording audio on several tracks at once.

Record enabling an instrument track



- ▶ **To record enable an instrument track, click on the Record Enable button on a note lane on the instrument track.** The Record Enable button lights up red and the track has Master Keyboard Input.


  If you have selected "Standard" mode in the "Master Keyboard Input" section on the "MIDI" tab in the Settings dialog (see "The Master Keyboard Input setting"), selecting an instrument track will automatically set Master Keyboard Input to that track - if the Manual Rec button in the Track List is Off, see "About the Manual Rec function". An instrument track that has Master Keyboard Input will automatically be record enabled, and will also be enabled for parameter automation recording, indicated by the red Record Enable Parameter Automation button.

- ▶ **If you want to record on another note lane on the instrument track, just click the corresponding Record Enable button on the note lane.**

- ! **Only one note lane on one instrument track can have Record Enable active at a time, unless you have locked additional MIDI keyboard controllers to specific instrument devices in the rack (see "Locking a surface" in the Remote chapter). If you only have one MIDI keyboard controller (assigned as Master Keyboard), you can only record notes on one note lane at a time (see "Setting Master Keyboard Input").**

Record enabling several instrument tracks


If you have locked additional MIDI keyboard controllers to specific instrument devices in the rack (see "Locking a surface" in the Remote chapter), the corresponding tracks for all these locked devices are automatically record enabled - if the Manual Rec button in the Track List is Off, see "About the Manual Rec function". These additional record enabled tracks are all displayed with the gray "Master Keyboard Input" symbol to the left of the device icon in the track list, and their Record Enable buttons are also automatically switched on. The track with "normal" Master Keyboard Input is also indicated with the gray Master Keyboard Input symbol to the left of its device icon.



The "Combinator 3" track with Master Keyboard Input and the "Combinator 1" and "Combinator 2" tracks controlled from additional MIDI keyboards locked to the corresponding devices in the rack.

- ▶ **To manually enable/disable any additional record enabled instrument tracks that are locked to specific MIDI keyboard controllers, click the Record Enable buttons on a note lane on any of these tracks.**


About the Manual Rec function



The Manual Rec button in the Track List.

The Manual Rec function in the Track List can be used if you don't want automatic record enabling of a selected track. For example, when you are finished recording your audio tracks and want to proceed with recording channel strip parameter automation, you probably don't want the audio tracks to be record enabled for audio.

- ▶ **Click the manual Rec button to disable automatic record enabling of selected tracks.**




The Manual Rec function activated.

If you change your mind and want to record audio on an audio track, you have to manually record enable it by clicking its Record Enable button as described in "Record enabling an audio track". Alternatively, switch off the Manual Rec button to enable the automatic record enabling again.

- ! **The Manual Rec function affects both audio tracks and instrument tracks.**

Record enabling parameter automation

Parameter automation can be recorded on all track types, on one track at a time or on multiple tracks simultaneously.



- ▶ **Click on the Record Enable Parameter Automation button(s) on the desired track(s) in the Track List to enable parameter automation recording.**
  All tracks enabled for parameter automation recording will be indicated by red Record Enable Parameter Automation buttons.
- ▶ **Setting Master Keyboard Input to a track will automatically enable parameter automation recording, as indicated by the red Record Enable Parameter Automation button.**


Record enabling pattern automation

Pattern automation can be recorded on tracks associated with pattern based devices such as the Redrum Drum Module, Dr. Octo Rex Loop Player or Matrix Analog Pattern Sequencer. Enabling pattern automation works in the same way as enabling regular parameter automation (see "Record enabling parameter automation").

- ! **Note that enabling the Record Enable Parameter button on a track featuring a pattern based device will also allow automation recording of other device parameters besides the Bank and Pattern select buttons. Any additional device parameters will be recorded on separate parameter automation lanes just like with non-pattern devices.**

Click and Pre-count

During recording and playback it's possible to have a metronome-style click sound to indicate the tempo of the song. In recording mode it's also possible to have the metronome click sound appear a selectable number of bars before the start of the actual recording, a so called pre-count. Activation of click and pre-count are managed on the Transport Panel:



The Click and Pre-count controls on the Transport Panel.


Click

- ▶ **Click the Click button to get an audible metronome click as the sequencer plays. Alternatively, press [C].**
  The click will sound on every beat, with the first beat in every bar accented (higher pitched).

Pre-count

- ▶ **Click the Pre button to get a pre-count (count-in) click sound before the recording starts. Alternatively, press [Ctrl](Win)/[Cmd](Mac)+[P]**
  Pre-count will only be present before you record - not when you start regular playback.
- ! **Note that Pre-count does not have any effect if you are using Ableton Link for synchronization, see "Synchronization using Ableton Link".**
- ▶ **Select the number of pre-count bars in the Options > Playback and Recording > Number of Precount Bars menu.**
  You can choose between 1 to 4 bars.
- ▶ **Feel free to experiment with different pre-count settings. For up-tempo (faster) songs it's generally more convenient to have a little longer pre-count (3 or 4 bars) whereas for slower songs it's often sufficient with 1-2 bars.**

Click Level




Click Level slider.

- ▶ **Adjust the audio level of the metronome click (and pre-count click) with the slider.**
- ! **Note that since the click sound is also routed via the selected audio card/interface on your computer - but not through the Reason mixer, the click sound will be summed to the rest of the sounds playing in your song. A high Click Level setting could therefore cause the Audio Output Meter on the Transport Panel, and the "Big Meter" in the Reason Hardware Interface, to indicate clipping. If this should occur, either lower the Click Level or deactivate Click to determine if it's the click sound or the recorded sounds that cause clipping.**

Loop mode

In loop mode, the song is automatically looped between the Left and Right Loop Locators on the Edit/Arrangement Pane during playback and/or recording:




Loop mode activated by clicking the Loop button on the Transport Panel.

The behavior when recording in loop mode differs depending on what you're recording - audio, MIDI or parameter automation. Refer to "Recording audio in Loop mode", "Recording notes in Loop mode" and "Recording parameter automation in Loop mode".

General recording procedure

The following description applies to all types of recording: audio, MIDI and parameter automation. For specific details of audio, MIDI and parameter automation recording, refer to "Recording audio", "Recording notes", "Recording performance controller automation" and "Recording parameter automation".

1. **If desired, select Click and/or Pre-count according to the descriptions in "Click and Pre-count".**
2. **Move the Song Position Pointer to the position in the Ruler where you want to start your recording (see "Ruler (timeline) details").**
3. **Click the Record button on the Transport Panel. Alternatively, press [*] on the numeric keypad, or hold down [Ctrl](Win) or [Cmd](Mac) and press [Return].**
   The Record button turns red. If Pre-count is enabled, wait for the set number of pre-count bars before starting to record audio, MIDI or parameter automation. During pre-count, nothing will be recorded.




During pre-count, only the Record button is active (red) and nothing will be recorded.

4. **Start recording on the track.**
   As the recording begins, the Play button on the Transport Panel goes dark while the Record button remains red.



During recording, both the Play and Record buttons are active and any input data will be recorded.

   If the lane is currently empty, a new clip is automatically created on the record enabled lane on the track. As the recording progresses, the clip expands following the Song Position Pointer. The clips are shaded in red during recording according to the picture below:



5. **When you're done recording, click the Stop button on the Transport Panel. Alternatively, press [Spacebar], [0] on the numeric keypad, or hold down [Shift] and press [Return].**
   The Record and Play buttons turn gray, the Song Position Pointer stops and the red shading of the clip(s) disappears. The clip(s) show the recorded events as different types of graphical objects, depending on clip type.

! **If nothing was recorded in a note clip, clicking Stop will automatically remove the empty note clip.**

Undoing a recording

- **If you're not satisfied with the finished recording, you can select "Undo Record Track" from the Edit menu or select the clip on the Edit/Arrangement Pane and press [Delete] or [Backspace].**
  This will delete the clip and its contents.

Undoing while recording a note clip

- **If you're not satisfied with your ongoing recording of a note clip, press [Delete] or [Backspace].**
  This will delete the current note clip and all its contents and at the same time create a new clip starting at the current song position. The sequencer will continue recording during the entire process.

! **Note that this only works when recording note clips.**

Recording tips

Lowering the Tempo during recording

If you are going to record complex/difficult takes, a good suggestion is to lower the song tempo during recording and then speed up the song to normal tempo again during playback. For audio tracks, Reason features very sophisticated functions for audio stretching. Audio stretch enables you to alter the song tempo up or down without changing the pitch of the recorded audio. See "About tempo changes and tempo automation of audio tracks" for more details.


When recording MIDI, just lower the tempo when recording the difficult parts and speed up to normal tempo during playback.

Audio recording details

Setting up the audio track

Selecting audio input(s) and defining mono or stereo

- **Select audio input(s) for the track from the Audio Input drop-down list.**



Selecting audio inputs for the Audio Track.

At the top of the drop-down list you can select whether you want to use mono or stereo inputs. Depending on your selection, the LED meter switches to a stereo or mono display. Further down in the drop-down list you can select the audio interface input(s) you want to use for the track.

Setting input level(s)

Before you start recording audio on the track it's very important to set correct input level(s). The input signal should be loud enough to minimize noise and provide high quality, but not so loud that it causes clipping and distortion.

If you're using a 24-bit audio interface (recommended), aim at having the level of the input signal around -12dB on the track Input Meter according to the picture below. For 16-bit audio interfaces you may want to raise the level another couple of dB's.




"Safe" input level ~ -12dB (first yellow LEDs lit)

▶ **To get a better view of the input levels, use the separate Recording Meter Window, see "The Recording Meter Window".**

! **Always adjust the input level at the source (e.g. the preamp connected to, or built-in to the audio interface).**

! **If the input signal level should exceed 0dB (red clipping LEDs to the right) on the track Input Meter at any time during recording, there could be audible distortion in the recording:**



Audio clipping LED = distortion (Clipping LED lit)

If the input level should clip, at any time, the red clipping LED(s) in the Input Meter will be constantly lit until you click on the Input Meter. This is to notify that there is, or has been, too loud an input signal present on the track.

! **The input level cannot be adjusted using the Channel strip controls in the Main Mixer. The Channel strip controls are used only for adjusting the level and characteristics of the monitored signal and/or the playback signal of an existing recording on the track.**

Monitoring

Monitoring means listening to the input signal of an audio track. Monitoring works according to the following principles:


- **By default, monitoring is automatically enabled as soon as an audio track is record enabled.**
  This makes it possible to hear what you will be recording - before and during recording to disk.
- **During playback of an audio track, monitoring is automatically disabled.**
  During playback, you will only hear the recorded signal - not any input signal.

▶ **Note that you can manually activate or deactivate monitoring for a track by clicking the Monitor button.**

The input signal is monitored after the Channel strip and Master Section in the Main Mixer which means that all mixer parameters, including any Insert Effects, Dynamics etc., will also be applied to the monitored signal.

! **Note that the Main Mixer parameters will only affect the monitored (and/or played back) signal - they will not affect the signal being recorded to disk.**

Depending on the technical specifications and/or settings in your hardware audio interface, the latency of the monitored input could become a problem. If this is the case, it's probably better to monitor the input signal before it reaches the Reason program, i.e. directly on the external audio interface/mixer/preamp. If you don't want to monitor through the Reason program you should select "External" or “Manual” in the Monitoring section on the “User Interface” tab in the Settings dialog:



The “Monitoring” section on the User Interface tab in the Settings dialog

- **Select “Automatic” to select automatic monitoring of the Audio Track in Reason.**
  Each time you select and/or record enable an Audio Track in the Track List, monitoring in Reason will be automatically enabled. It's possible to manually disable monitoring in this mode if you like.
- **Select “Manual” to manually select if monitoring should be on or off.**
  This mode should be selected if you prefer to have manual control over monitoring, or when you are monitoring through external mixer or audio interface. In the latter case, you would select "Manual" mode and just don't click any monitor buttons.
- **Select “External” to deselect automatic monitoring of the Audio Track in Reason.**
  When you select and/or record enable an Audio Track in the Track List, monitoring in Reason will be automatically disabled. It's not possible to manually enable monitoring in this mode.

Using the Tuner

An audio track also features a built-in tuner function. The Tuner detects and displays the input pitch of a connected instrument - an electric guitar, for example.

1. **Click the “Enable Tuner” button below the device icon to switch to Tuner mode.**
   The Input Meter switches to a Tuner.




An audio track in Tuner mode.

2. **Play a note on the connected instrument and watch the Tuner.**
   When the input pitch is detected, the Tuner lights up and indicates how far the pitch is from the displayed note value to the right of the Tuner. The center LED on the Tuner Meter indicates a perfectly tuned note pitch. The green arrow LEDs on either side of the Tuner Meter indicate how the connected instrument should be tuned. The left arrow LED means raise the pitch and the right means lower the pitch.


! **Note that the input note has to sustain for a little while before the pitch can be detected.**

The Recording Meter Window



The main purpose of the Recording Meter floating window is to provide a good overview of recording levels and/or tuner values when you are located some distance away from the computer screen. The Recording Meter mirrors the information from the input level meter and Tuner of the currently selected record enabled Audio Track.

- **Toggle the Recording Meter window on and off by selecting "Show/Hide Recording Meter" from the View menu.**
- **Move the Recording Meter window by clicking on the window background and then dragging.**
- **If you have manually record enabled several Audio Tracks in the sequencer, you can choose which track to display in the Recording Meter window by clicking the right/left arrows on either side of the Audio Track name.**
  By default, the first record enabled Audio Track in the sequencer is displayed in the Recording Meter window.
- **Click the pitchfork symbol in the Recording Meter window to bring up the Tuner for the selected Audio Track.**
  A large Tuner display is shown at the bottom of the Recording Meter window.



See "Using the Tuner" for more information about the Tuner.

Recording audio

! **To minimize the song saving time, we strongly recommend saving the song before recording many or large audio recordings.**

1. **Set up the audio track according to the descriptions in "Setting up the audio track".**

▶ **When you are going to record on an audio track you can set up which Stretch and Transpose Type you want to have on the recordings on that track, by right clicking the Audio Track and selecting "Stretch Type for New Recording > Allround/Melody/Vocal".**
You can also change this afterwards if you like, see "Selecting Stretch and Transpose Type".

2. **Record the track according to the descriptions in "General recording procedure".**
3. **When the recording is finished, the audio clip on the track shows the recorded audio as one or two continuous waves inside the clip, depending on whether the input was in mono or stereo:**



An audio clip with a stereo audio recording.


Recording audio in Loop mode

Recording audio in Loop mode is very useful if you want to record alternative takes of the same part of the song. For example, let's say you want to sing a couple of takes of the chorus part of your song to later create the perfect chorus by selecting the best parts of the different takes.

! **To minimize the song saving time, we strongly recommend saving the song before recording many or large audio recordings.**


Proceed as follows to record audio in Loop mode:

1. **Set up the audio track according to the descriptions in "Setting up the audio track".**
2. **Set the Left and Right Locators to span the chorus part of your song.**
3. **Enable the Loop function by pressing [L] or by clicking the Loop On/Off button on the Transport Panel:**



Loop mode activated on the Transport Panel.

4. **Click the L button on the Transport Panel to move the Song Position Pointer (play head) to the Left Locator.**




5. **Record the track according to the descriptions in "General recording procedure".**
6. **Start singing to record audio on the track.**
When the Song Position Pointer has reached the Right Locator, the recording starts over from the Left locator again and you can now record a second take. The audio recorded in the previous take won't be heard but is saved in the "background" on a Comp Row.

   Continue recording for as many loop cycles as you like.

7. **When the recording is finished, the audio clip on the track shows the last recorded audio take as one or two continuous waves inside the clip (depending on whether the input was in mono or stereo).**

8. **Double-click the clip to open it in the Edit Area.**
9. **Open the clip in the Comp Editor by clicking the "Comp Edit" button at the bottom of the Edit Area Inspector.**
   In the Comp Editor, you can see that there is one Comp Row for each of the recorded loop cycles (Takes):



Audio recorded in Loop mode with 5 loop cycles (Takes) recorded.

From here, it's easy to assign the best parts from the different takes and comp them into a final clip. See "Creating a comped audio clip" for details.

Overdubbing audio using the "Dub" function

Back in the tape recorder days, overdubbing was used to record additional takes on additional tracks on the same section of the tape, to create a complete arrangement. For example, recording a vocal chorus part could be done by overdubbing the singer three or four times on additional tracks. Overdubbing in Reason works in a similar way, but with much better control, and much better editing possibilities afterwards.

- **After you have recorded the first take on an audio track, click the "Dub" button on the Transport Panel.**
  This will create a new audio track with a duplicate of the original audio track settings, including the channel strip settings (with insert effects etc.). Now, you can continue recording on the new audio track as described in "Recording audio" and "Recording audio in Loop mode". Afterwards, you can edit the new track completely independently of the original track.
- **The "Dub" function can also be used on-the-fly while recording.**

Duplicating audio tracks using the "Alt" function

Closely related to the "Dub" function, described in "Overdubbing audio using the "Dub" function", is the "Alt" function. This function can be used to create a new audio track with an identical copy of the selected audio track's settings. The only difference between the "Alt" and "Dub" functions is that the Alt function will automatically mute the original audio track.

- **Select the audio track you want to duplicate and then click the "New Alt" button on the Transport Panel.**
  This will create a new audio track with a duplicate of the original audio track settings, including the channel strip settings (with insert etc.). Now, you can continue recording on the new audio track as described in "Recording audio" and "Recording audio in Loop mode". Afterwards, you can edit the new track completely independently of the original track.
- **The "Alt" function can also be used on-the-fly while recording.**

Recording over or into an existing audio clip

If you start recording over an existing clip on an audio track, the new recording will incorporate (replace, but not erase) the previous recording in the clip. When you open the audio clip in the Comp Editor afterwards, there will be one Comp Row for each of the takes, the same result as when recording audio in Loop mode (see "Recording audio in Loop mode").

Let's have a look at the following example:

In the picture below, we have the original audio clip spanning bars 1-8 on the track:



An audio track with an existing clip.


Now, we want to re-record the part that spans bars 5-6. We place the Song Position Pointer at bar 5 and record 2 bars:



A new recording made on bars 5-6 on the audio track.

The new recording is made over the original clip. The recording in the original clip has therefore been incorporated into the start of bar 5 to the end of bar 6.

Now, let's double-click the clip and open it in the Comp Editor:



The new and original recordings (takes) in the Comp Editor.

The new recording has incorporated bars 5-6 of the original recording. However, the original recording in bars 5-6 has been left totally unaffected. The entire original audio recording now resides on the "Take 1" Comp Row and the latest recording resides on the "Take 2" Comp Row. The resulting clip will now play back the "Take 1" recording in bars 1-4 and 7-8. Bars 5-6 will play back the "Take 2" recording.

See "Creating a comped audio clip" for details on how to extract parts from individual takes and comp into a final clip.

Recording audio from Mix Channel outputs

Besides recording external audio from the inputs of your audio interface, it's also possible to record audio internally from the outputs of Mix Channel or Audio Track devices. Typical applications for this could be:

- **Recording the audio from an Output Bus (sub mixer) Mix Channel.**
  You might have the individual drums of your drum kit on separate tracks and these tracks are routed to a Mix Channel which is set to work as an Output Bus (see **"Output Busses"**). You then want to record the audio from the Output Bus onto a new Audio Track.

  In this situation, all you need to do is create a new Audio Track, activate the Rec Source button on the Output Bus Mix Channel device, and then select the Output Bus in the Select Audio Input drop-down list on the Audio Track in the Track List. Then, record the audio from the Output Bus as described in **"Recording audio"**.
- **Re-recording of an audio track with effects applied.**
- **Recording when playing back an instrument or audio track while making live manipulations of effects or parameters.**

▶ **If you want to record the audio from an Instrument track onto an audio track, without making any live manipulations, you can also use the "Bounce Mixer Channels" function - see "Bouncing Mixer Channels".**

The example below describes how to capture and record the audio from an ID8 device, but the general method can be used for other recording scenarios as well:


1. **Create an instrument track for the instrument device you want to record according to the descriptions in "Creating an instrument track".**
   You won't actually be recording on the instrument track in this situation. However, you will need the instrument track to be able to play the instrument device from your connected master keyboard.
2. **Create an audio track according to the description in "Creating an audio track".**
3. **In the rack, locate the Mix Channel device connected to the ID8 instrument device and click its "Rec Source" button.**
   The "Rec Source" button on Mix Channel devices is used for real-time audio recording of devices connected to the Mix Channel device.

   The "Rec Source" button on Audio Track devices are used for real-time re-recording of audio tracks.




Enabling the Rec Source button on the Mix Channel device in the rack.

4. **Locate the audio track and select “Stereo Input” and “ID8 1” as input source in the “Select Audio Input” drop-down list.**
   All Mix Channel and Audio Track devices that have their “Rec Source” button enabled will appear in the list. In this example, we only have the Rec Source button active on the “ID8 1” Mix Channel.




“Stereo Input” and “ID8 1” selected in the “Select Audio Input” drop-down list.

5. **Select the instrument track, in this example the ID8 1, so that it has Master Keyboard Input and disable the “Record Enable” button.**



Select the ID8 1 track and disable the Record Enable button.


6. **Locate the audio track and record enable it by clicking the Record Enable button.**



Engage Record Enable on the Disk Channel track.

! **Don’t set Master Keyboard Input to the audio track - only click the “Record Enable” button on the audio track! This way, the ID8 1 instrument track will still have Master Keyboard Input.**

7. **Play the master keyboard and set the input level to the audio track by adjusting the Level Fader on the ID8 1 Mix Channel strip in the mixer.**



Adjusting the instrument's level to the audio track.

! **A Volume setting of -0.0 dB on the instrument device and a Level Fader setting of -0.0 dB on its corresponding Mix Channel strip in the mixer is often the optimal setting to avoid audio signal clipping. As when recording external audio, it's the track's Input Meter that should be observed for any clipping.**

8. **Start recording audio on the audio track according to the description in "Recording audio".**

▶ **By using the recording method described above, it's also possible to record the audio from previously recorded note clips on instrument tracks.**

Recording a mixdown of several audio tracks

Another useful feature is to record a real-time mixdown of several previously recorded audio tracks onto a new, additional audio track. This is sometimes also referred to as recording stems or sub-mixes. Let's say we have four backing vocal tracks that we want to mix down and record on a new audio track. We can do this as follows:

1. **Create a new audio track according to the description in "Creating an audio track".**
   This is the track we're going to use for recording the mixdown. We name the track "Mixdown" to make it easier to distinguish.

2. **Locate the Master Section device in the rack and click its "Rec Source" button.**



The "Rec Source" button on the Master Section device.

This will allow you to record the output from the Master Section onto the new audio track.


3. **Locate the four backing vocal Audio Track devices in the rack, or their corresponding channel strips in the mixer, and click their "Solo" buttons.**



The four backing vocal Audio Track devices soloed.

Since we're going to record the four backing vocal tracks through the outputs of the Master Section, we only want the backing vocal tracks to sound. All other tracks in the song should therefore be muted.

4. **Select the "Mixdown" track in the sequencer and select "Stereo" and "Master Section" from the "Select Audio Input" drop-down list.**



"Stereo" and "Master Section" selected as Audio Input source.

Selecting "Stereo" makes it possible to pan the backing vocal tracks in stereo before recording on the mixdown audio track.

5. **Adjust the parameters of each of the backing vocal track channel strips as desired.**

▶ **Don't forget to set the panning of each of the tracks to spread them in the stereo panorama.**

6. **Select the “Mixdown” track in the sequencer and click the “Rec” button on the Transport Panel to start recording the mixdown.**




Recording the mixdown of the four backing vocal tracks to the “Mixdown” track.

- **During recording, you might want to perform real-time adjustments of the backing vocal tracks’ channel strip parameters to create a “live” mix.**

7. **When you have recorded the mixdown, click “Stop” on the Transport Panel.**

8. **Before you play back the song with the mixdown track, remember to un-solo the four backing vocal Audio Track devices/channel strips. Also, mute the four original backing vocal tracks in the sequencer to avoid "double" sounds.**



Playing back the Mixdown track with the original backing vocal tracks muted in the sequencer.

- **Another alternative, if you want to record several Audio Tracks or Mix Channels onto a single audio track, is to create a sub-mixer setup - see "Output Busses".**

Note recording details


Note events can be recorded for instrument devices and are contained in note clips. Performance controller events, such as Mod Wheel, Pitch Bend and Aftertouch events, can also be recorded for instrument devices, and be contained in note clips, but they are described separately in "Parameter automation recording details".

Setting up the instrument track

To record notes for an instrument device - or for an external MIDI instrument - on a track in the sequencer, you need only create an instrument track as described in "Creating an instrument track". The instrument track will automatically have Master Keyboard Input and the note lane will automatically be record enabled. Since you will only be recording MIDI events on the instrument track - and no audio - there is no need to adjust audio levels etc. These can always be adjusted afterwards.

If you want to control an external MIDI instrument, simply create a MIDI Out Device and select the appropriate MIDI port and channel on the device panel. See "MIDI Out Device" for more details.

About "Quantize During Recording"



The Q Rec (Quantize During Recording) button on the Transport Panel.

It's possible to quantize MIDI notes as they are being recorded. This will automatically align the start positions of the recorded notes to a pre-defined grid. Refer to "Quantize" for more details.

Recording notes

1. **Set up the instrument track according to the description in "Setting up the instrument track".**
2. **Record the track according to the description in "General recording procedure".**
3. **When the recording is finished, the note clip on the lane shows the recorded note events in a piano-roll fashion inside the clip:**



A note clip with note events.

The note clip's start and end boundaries will automatically snap to the closest bar to make it easier to arrange (move etc.) later on.

! **If no MIDI events (notes and/or performance controllers) were recorded, the empty note clip will be automatically removed from the lane after you have clicked Stop.**


▶ **It's also possible to manually insert notes by drawing them with the Pencil tool. Refer to "Drawing notes".**

▶ **You can also use Player devices to automatically generate various types of MIDI Note sequences, patterns and chords when you record your instrument, see "Working with Players".**

Recording notes in Loop mode


Recording on a note lane in Loop mode allows you to continuously add new notes in a defined section of your song:

1. **Set up the instrument track according to the description in "Setting up the instrument track".**
2. **Set the Left and Right Locators to span the desired part of your song.**
3. **Enable the Loop function by pressing [L] or by clicking the Loop On/Off button on the Transport Panel:**



Loop mode activated on the Transport Panel.

4. **Click the L button on the Transport Panel to move the Song Position Pointer (play head) to the Left Locator.**




5. **Record the track according to the description in "General recording procedure".**
   When the Song Position Pointer has reached the Right Locator, the recording starts over from the Left Locator again and you can record additional notes. Any new recorded notes will be added to the previously recorded ones and all notes will be heard during the recording.

   Continue recording for as many loop cycles you like.

Recording over or into an existing note clip


Recording over or into an existing note clip will simply add new note events to the previously recorded events in the note clip as described in "Recording notes in Loop mode". However, If the new recording should start before the original clip, and expand into the original clip, a new clip will be created and will engulf the original clip. Let's have a look at the following example:

In the picture below, we have the original note clip spanning bars 4-13 on the track:



A note lane with an existing clip.

Now, we're going to record an intro which is going to span the first four bars:



A new note clip recorded on bars 1-4 on the same note lane.


The new clip is partly recorded over the original clip. The part of the original clip that has been recorded over is incorporated in the new clip; the events from the original clip are now contained in the new clip, and the start of the original clip has been moved to bar 5, where the new clip ends.

! **If you're recording over or into a masked clip and the new clip engulfs masked events, the masked events will be permanently deleted! See more about masked events in "About masked recordings and events".**

▶ **Another, perhaps more convenient, way of overdubbing on an instrument track is to create additional note lanes and record new clips on these using the New Dub or New Alt functions described in "Recording notes using the "Dub" and "Alt" functions". This way, you will get a better overview of exactly what you added in each of your recordings.**


Recording notes using the “Dub” and “Alt” functions

A practical way of recording additional MIDI events on an instrument track is to use the “Dub” and “Alt” functions.




The “Dub” function

The “Dub” function creates additional record enabled note lanes on which you can record “overdubs”. This is the function to use when you want to add new notes in the same section of the instrument track but want the notes to end up in new clips on additional note lanes instead of in the original clip. All note lanes will play back together.



The “Dub” function used for creating two additional lanes for overdub purposes. Loop mode is Off.



The “Dub” function used for creating two additional lanes for overdub purposes in Loop mode.


▶ **Creating a new note lane using the “Dub” button can also be done on-the-fly while recording.**

The “New Alt” function

The “Alt” function creates additional record enabled note lanes on which you can record alternative takes. At the same time, the previous note lane will be muted. Only the most recently added note lane will play back.


! **Note that if Loop is activated and the Song Position Pointer is between the Locators, the clips between the Locators will be muted (instead of the lanes).**

Here are two examples where the “Alt” function has been used:



The “Alt” function used for creating two additional lanes for alternative takes. Loop mode is Off.

When using the “Alt” function with Loop mode off, the previous note lane will be automatically muted.



The “Alt” function used for creating two additional lanes for alternative takes in Loop mode.

When using the “Alt” function in Loop mode, the clips *between the locators* will be muted - not the entire note lane. If the locators are placed over an existing clip, as in the example above, clicking the “Alt” button in Loop mode will split the clip and mute the clip between the locators.

▶ **Creating a new note lane using the “Alt” button can also be done on-the-fly while recording.**

Parameter automation recording details

In Reason, you can automate virtually any device and channel strip parameters and create completely automated mixes if you like. This is done by recording parameter events in the sequencer. It's also possible to record sequencer Tempo automation (see "Tempo automation recording").

Performance controllers vs. track parameter automation

Recording parameter automation can be done in two different ways; either as performance controller automation or as track parameter automation.

- **Performance controller automation is automatically recorded together with note events in note clips on note lanes.** Any standard MIDI performance controllers that you apply when playing (Pitch Bend, Mod Wheel etc.) will be recorded as performance controller automation in the note clip. A clip on a note lane can contain any combination of note events and performance controller automation events.
- **Track parameter automation creates separate parameter automation lanes on a track, one for each automated parameter.**

Which method you should use depends on how you prefer to work. The main differences to take into account are the following:

- **Performance controller automation allows you to contain the automation data in a note clip together with note events.**
  The key feature with performance controller automation is that it's contained together with the notes in the note clip. Moving the note clip moves the performance controller automation as well. Therefore, if your controller changes are part of your "note performance" (e.g. Pitch Bend and Sustain Pedal), then you want them as performance controllers (see "Recording performance controller automation").

  Filter sweeps played together with the notes etc. can also be recorded as performance controllers (see "Recording parameter automation into Note Clips").
- **If your parameter changes are for sound design or mixing purposes (e.g. a slow opening of a filter, a gradual change in level), they would probably work better as track parameter automation.**
  Track parameter automation is recorded on separate lanes on the track (one lane for each automatable parameter). Track parameter automation clips can be moved individually, independent from any note clips. See "Recording parameter automation".

Recording performance controller automation

If you use any MIDI performance controllers when recording on a note lane, these are automatically added to the recorded clip. This makes sense as performance controllers are usually recorded at the same time you record notes, as a part of the performance. Standard MIDI performance controllers are Pitch Bend, Modulation Wheel, Sustain Pedal, Aftertouch, Breath Control and Expression.

▶ **To record standard performance controller automation, just follow the descriptions in "Recording notes".**
When you have recorded performance controllers in the note clip, the clip will have automation curves visible in it along with the recorded note data.



Performance controllers are shown as curves in the note clip. In this picture, Mod Wheel, Pitch Bend and Sustain Pedal controllers have been used.

Green borders will appear around the automated device parameters to indicate that they are automated.



The Pitch Bend and Mod Wheel parameters have been automated, indicated by the green borders.

! **After you stop recording, you need to click Stop again, or click the "Automation Override" indicator to the right on the Transport Panel, for the green automation borders to appear on the device panel.**



The Automation Override indicator on the Transport Panel.

The performance controller automation is shown differently in the clip depending on the type of controller used. Controllers with bipolar range (such as Pitch Bend) are shown as lines in the middle when at zero (no pitch bend) with curves traveling up or down from the zero value. Controllers with only positive values (such as Mod Wheel) have zero at the bottom of the clip with applied modulation shown as curves traveling up from the zero value. Controllers with off/on values (such as Sustain Pedal) are shown as rectangular curves (on - duration- off).

▪ **If you open a note clip in the Edit Area (by double-clicking on the clip), the recorded performance data can be viewed and edited on the separate Performance Controller Edit Lanes on the Edit Pane.**



Performance controller automation on separate Edit lanes in the Edit Area.

▶ **Note that you can record notes and performance controllers separately. I.e. you can first record notes on one note lane and then record performance controllers on another note lane on the same instrument track. The automation will be contained in note clips placed on a separate lane and can also be moved or muted separately.**

! **If several note lanes contain performance controller automation, the topmost lane has priority (see "About performance controller automation on multiple lanes").**

▶ **It's also possible to manually insert performance controller events by drawing events with the Pencil tool. Refer to "Drawing parameter automation events".**

Recording parameter automation into Note Clips

Besides the standard performance controllers (Pitch Bend, Mod Wheel etc.), you can choose to record automation of any type of instrument device parameter into a note clip:

1. **Select "Record Automation into Note Clip" from the Options > Playback and Recording menu.**
2. **While recording on a note lane according to the description in "Recording notes", tweak the parameter(s) you want to automate on the instrument device panel in the rack - or use a Remote MIDI controller (see "Remote - Playing and Controlling Devices").**
   Any parameter you tweak on the device will be recorded as automation inside the note clip - just like Performance Controller automation.

   Green borders will appear around the automated device parameters to indicate that they are automated.

! **After you stop recording, you need to click Stop again, or click the "Automation Override" indicator next to the audio meters on the Transport Panel, for the green automation borders to appear on the device panel.**

▶ **While this method is perfect for making a note clip self-contained, there are some trade-offs. If you use this method to record device parameters, you won't have the same overview as with track parameter automation. You also won't be able to later mute a separate parameter automation lane, or move to parameter lanes independently.**

! **It is possible to have overlapping track parameter automation and automation inside a note clip for the same parameter. In such a case, the track parameter automation overrides the note clip automation. As soon as the track parameter automation clip ends, any automation inside the remaining part of the note clip takes over.**


Recording performance controller automation over or into an existing clip

- **If you record over a note clip with performance automation data and you adjust any of the performance controllers used in the clip, the automation will be replaced with new performance events from this point onward until you stop recording.**
  However, if the new recording should start before the original clip's start position, a new clip will be created which will incorporate the original clip. The new automation data will replace the existing one, but any existing note events will not be affected (see "Recording parameter automation over or into an existing clip" and "Recording over or into an existing note clip").

About performance controller automation on multiple lanes

If you have several active (un-muted) note clips with performance controller automation on different lanes of the same track, and these note clips overlap position-wise, the following rule applies:

- **Performance controllers in clips on the topmost lane override performance controllers of the same type in other overlapping clips on lanes below:**



The clip on Lane 2 has Mod Wheel automation, and the clip on Lane 1 also has Mod Wheel automation - plus Pitch Bend and Sustain Pedal automation and note events. The Mod Wheel automation affecting the notes will follow the automation curve of the clip on Lane 2 for its duration. As soon as the clip on Lane 2 ends, the notes will be affected by the Mod Wheel automation in the clip on Lane 1.

Recording parameter automation

Parameter automation is the standard way to automate device and channel strip parameters. Each automated device/channel strip parameter will generate a separate automation lane on the track. It's also possible to record automation of the Tempo on the Transport Panel. This is described in detail in "Tempo automation recording".

Before you start recording parameter automation

Before you start recording automation of a device/channel strip parameter, you may want to set it to a suitable start value, what we call its "static value". By static value we mean the value the parameter should have whenever it is not automated in the song. Here is why:

Let's say you want to create a fade-out by recording a fader movement in a mixer channel strip. It's a good idea to first set the fader to the correct static value (i.e. the value the fader should have before you start the fade-out). The same thing is true if you want to create a filter sweep somewhere in the song: first set the filter frequency to the value it should have elsewhere in the song, then record the filter sweep. This makes it possible to set up a static mix first, and then add some automated parameter changes anywhere in the song while maintaining the static values elsewhere in the song.

You can think of the static value as a "default" or "fall-back" position for the duration of the song.

▶ **You can change the static value at any time, by opening the automation clip in the Edit Area (Performance Controller only). See "Editing parameter automation in the Edit Area". Static Values for regular Track Parameter Automation can be edited on the Parameter Automation Lane.**

Parameter automation recording procedure

1. **Make sure there is a sequencer track for the device you're going to record parameter automation for.**
   For audio track devices and for instrument devices, a sequencer track is automatically created together with the device. For mix channel and effect devices, that might not necessarily have a sequencer track, the easiest way to create a track for parameter automation is by right-clicking (Win) or [Ctrl]-clicking (Mac) on the device/channel strip parameter and selecting "Edit parameter Automation" from the pop-up.
2. **Set up the track for parameter automation recording according to the description in "Record enabling parameter automation".**
   If the track has note lanes you may want turn off the "Record Enable" button for the active note lane (unless you plan to record notes and parameter automation simultaneously of course).

! **Note that it is not necessary for the track to be selected, or for the track to have Master Keyboard Input, to be able to record parameter automation. The "Automation Record Enable" button is completely independent from Master Keyboard Input. However, if you want to adjust the parameters from a control surface or MIDI Controller keyboard, this is most easily done by setting Master Keyboard Input to the track - see "Setting Master Keyboard Input".**

3. **Record the track according to the description in "General recording procedure".**
4. **Record the parameter automation by changing device/channel strip parameter(s) in the rack or in the mixer.**
   During recording, adjust the desired parameter(s), from the device panel or from a MIDI control surface. You can automate any parameter for the device - each parameter you tweak will automatically generate a separate parameter automation lane and a clip will be recorded on the corresponding lane from the point you changed the parameter.

▶ **It is also possible to record automation of the channel strip EQ and Filter parameters from the Spectrum EQ window, see "The Spectrum EQ Window".**

5. **When you're done, click the "Stop" button on the Transport Panel to stop recording.**
   In the Song View or Blocks View, the parameter automation clip(s) on the lane(s) show the recorded parameter automation events as curves or lines inside the clip.



Parameter automation clip with parameter events

If you click the "Stop" button again, or click the "Automation Override" indicator on the Transport Panel, the automated parameters on the device(s) will be marked with green borders, indicating that they have been automated.

If you play back the recorded section again, the automated parameters will change automatically. Outside the clip boundaries, the parameters will have their original settings (the static values they had before you started recording).

▶ **It's also possible to manually insert parameter automation events by drawing events with the Pencil tool. Refer to "Drawing parameter automation events".**

Recording parameter automation in Loop mode

Recording parameter automation events in Loop mode works similar to "non-looped" recording (see "Recording parameter automation"), except that for every new loop cycle any changed parameter value will replace the previously recorded value for the corresponding parameter.

Recording parameter automation over or into an existing clip

Recording parameter automation events over or into an existing automation clip will simply replace the previously recorded automation events. However, If the new recording should start before the start position of the original automation clip, and expand into the original clip, the new clip will merge with the original clip. After the new clip ends, the parameter automation in the original clip will "take over".

If you need to redo a section of the recorded automation in an existing clip, or simply record more automation for a parameter, proceed as follows:

1. **Set up and start recording in the same way as described in "Parameter automation recording procedure".**
   As long as you don't change the parameter value, its automation data will be played back normally, and nothing will be changed.
2. **At the desired position, adjust the parameter.**
   As soon as you start changing the parameter value, the Automation Override indicator will light up on the transport panel.



The Automation Override indicator on the Transport Panel.

   From this point on, the previously recorded automation values will be replaced with the new automation values. Automation recording is different from recording note events where nothing is erased when you record over previously recorded clips. A parameter automation "overdub" will replace any previous automation values at the same position for the duration of the recording. Automation clips logically cannot be "overdubbed" as a parameter cannot have more than one specific value at a given point in time.

3. **When you're done, click the "Stop" button on the Transport Panel to stop recording.**
   You have now replaced the automation values from where you started recording to where you stopped recording. The Automation Override indicator will still be lit but it will go off if you click Stop or Play on the Transport Panel.

- **You can also click the "Automation Override" indicator during recording.**



  This "resets" the parameter to the previously recorded value and the automation recording will stop (making the previously recorded automation active again, from that position). You are still in record mode, so as soon as you adjust the parameter again, the Automation Override indicator will light up.

Adjusting automated parameters during playback - “Live mode”

Even if you have automated a device/channel strip parameter, you can still “grab it” and adjust it during playback, overriding the recorded automation:

1. **During playback, adjust an automated parameter.**
   The Automation Override indicator lights up on the Transport Panel.



   From this point onward, the recorded automation for the parameter is temporarily disabled.

2. **To activate the previously recorded automation again, click the “Automation Override” indicator.**
   This returns the control of the parameter to the parameter automation lane in the sequencer.

- **Note that you can also temporarily turn off automation for a parameter by clicking the “M” (Mute) button on the parameter automation lane in the sequencer (see “Muting a parameter automation lane”).**

Recording parameter automation on multiple tracks

Although only one track can have Master Keyboard Input, it is possible to record enable any number of tracks for automation recording.

- **Activate the Record Enable Parameter Automation button for all the tracks you wish to record automation for.**
  When recording is activated, all automation record enabled tracks will record track parameter changes from their respective devices in the rack. This is especially useful if you have assigned parameters on several devices to a single control on a MIDI control surface, or have multiple control surfaces controlling different devices in the rack while you’re recording. See “Remote - Playing and Controlling Devices” for details.

Recording parameter automation into note clips

If you want to record your parameter automation straight into the note clips (the same way as with performance controllers) instead of on separate parameter automation lanes, proceed as follows:

- **Select “Record Automation into Note Clip” from the Options menu.**
  When you record and edit any parameters on the device panel, the automation will be included inside the note clip. To edit the automation you will have to open the note clip in the Edit Area and then select the corresponding automation lane using the Controller selector, see “Editing parameter automation in the Edit Area”.

Pattern automation recording details

If your song contains pattern based devices such as the Redrum Drum Computer, Matrix Analog Pattern Sequencer or Dr. Octo Rex, you probably want to use more than a single pattern throughout the song. To facilitate this you can record pattern changes in the sequencer.


Recording pattern automation

1. **Before you start recording on the track, make sure the "Record Enable Parameter Automation" button is on (red).**
   You can disable the "Record Enable" button for the note lane for now as it won't be needed.
2. **Make sure that the "Enable Pattern"/"Enable Loop Playback" button is activated on the device in the rack.**



The "Enable Pattern" buttons on the Redrum (top) and Matrix (bottom) devices.

3. **Set the desired start pattern on the pattern device.**
4. **Start recording on the track from the desired position.**
   When recording starts, the pattern device will automatically start. Although no clip will be created until you change pattern on the device for the first time, the start pattern is still being recorded.
5. **During recording, change patterns with the "Bank" and "Pattern" buttons on the device panel.**
   As soon as a Pattern or Bank value is changed on the device, a pattern lane is automatically created on the track. On the lane, a pattern clip is automatically created and the pattern selection is recorded in the clip. Make sure you change the patterns slightly in advance - the actual pattern change will be recorded (and happen) on the next downbeat according to the sequencer time signature setting.
6. **When you are done, click "Stop" on the Transport Panel to stop recording.**
   The automated pattern selection buttons on the device in the rack will marked with a green border, indicating that they have been automated. A pattern automation lane with pattern clips has also been created on the Edit/Arrangement Pane.



Pattern automation clips on the pattern automation lane.

- **Pattern automation has no "static value". Patterns will only be played back where there are pattern clips on the lane. Where the pattern lane has no clips, the device will stop and no pattern will be played back.**

- **Each pattern change will be recorded on a downbeat (at the start of a new bar in the sequencer).**
  You can move pattern changes to other positions by moving or resizing the pattern clips, see "Editing pattern automation".
- **You can "punch in" on recorded pattern changes, to replace a section of the pattern lane with new pattern automation events. This can be done the same way as described in "Recording parameter automation over or into an existing clip".**
- **After recording the pattern changes, you can use the function "Convert Pattern Track to Notes", to transfer the notes in the patterns to regular notes in the main sequencer.**
  This allows you to create unlimited variations by later editing the notes in Edit mode. See "The "Convert Pattern Automation to Notes" function".
- **On the Redrum, Matrix and Dr. Octo Rex devices, you could also use the "Copy Pattern/Loop to Track" function.**
  This function lets you convert a defined range of pattern clips into notes in a new note clip. See "Copy Pattern to Track".

▶ **You can also manually draw automation clips on the Pattern automation lane - see "Drawing pattern automation"**

Tempo automation recording


In Reason it's possible to record automation of the sequencer's tempo. This means that a song can automatically change tempo whenever you like. You can record tempo automation events on the parameter automation lanes on the Transport track.

Recording tempo automation


Automating tempo is done much in the same way as with other parameter automation. You record the tempo changes by changing the Tempo value on the Transport Panel. When you later play back, audio clips will automatically be stretched to follow the tempo changes (unless you have disabled stretch for the clips - see "About disabling Stretch for audio clips"). Note clips and automation clips will always follow tempo changes.

To record tempo automation, do as follows:

1. **Set the desired song tempo in the Tempo display on the Transport Panel.**
   This will be your static value, i.e. the tempo of the song wherever there is no clip present on the tempo automation lane.
2. **Press [Alt](Win) or [Option](Mac) and click in the Tempo display on the Transport Panel.**
   This will both select the Transport track and create a Tempo automation lane at the same time. The Tempo display will also be marked with a border, indicating that the Tempo parameter has been automated.



3. **Start recording in the sequencer and record the tempo changes by changing the value in the Tempo display.**
   Click and drag up/down in either of the display segments to change tempo in BPM steps or 1/1000 BPM steps.



or

▶ **You can also manually draw Tempo automation events in the parameter automation clip, using the Pencil tool - see "Drawing tempo automation events".**

Chapter 7
Arranging in the Sequencer

About this chapter

This chapter describes how you can arrange and work with the clips in your song. The chapter covers both audio, note and parameter automation clip arrangement. Special arrangement techniques pertaining to the Blocks View are described in the separate chapter "Working with Blocks in the Sequencer".

Before reading this chapter, it's recommended that you are familiar with the sequencer functions and definitions described in the "Sequencer Functions" and "Recording in the Sequencer" chapters.

Clip handling

Clip arrangement in the sequencer is done mainly in the Arrange Area. The descriptions in this chapter refer to arrangement in the Song View in the Arrange Area, unless otherwise stated.

Creating Clips

Clips are created automatically when you record, but you can also create empty clips and add notes and other events in them by drawing with the Pencil Tool.


- **To create a clip, double click with the Selection (Arrow) Tool on a track.**
  This will create an empty clip with the length of the current Snap value setting (e.g. 1 bar). To create longer clips, double click, keep the mouse button pressed and drag to the right.
- **You can also create clips by selecting the Pencil Tool and drawing on a Lane in the sequencer.**

Selecting clips

- **To select any type of clip in the Song View, just click it.**
  A selected clip is distinguished by a darker top part.



Audio clip



Note clip



Parameter automation clip




Pattern clip

Selected clips in the Arrange Area.

- **To de-select clips, just click anywhere on the Arrange Pane background.**

Inspector displays for selected clips

In the sequencer Arrange Area Inspector, the Position and Length displays shows the start position and length of the selected clip. For selected audio clips, four additional displays are shown: Fade In, Fade Out, Level and Transpose. If several clips are selected, the displays show the values for the earliest (or topmost) selected clip in the song.



The Inspector displays for selected Audio Clips.


- **Clip Position display**
  The clip Position display shows at what position in the song the clip begins. The display readout is divided into Bar, Beat, 1/16 Note and Ticks (1/16th note=240 Ticks). The position can be edited according to the descriptions in "Moving clips using the Inspector".
- **Clip Length display**
  The clip Length display shows the length of the clip. The display readout is divided into (from left to right) Bar, Beat, 1/16 Note and Ticks. The length can be edited according to the descriptions in "Resizing clips using the Arrange Area Inspector".
- **Loop Clips**
  This box is checked for Looped Clips, see "Looped Clips".
- **Fade In and Fade Out displays (audio clips only)**
  The Fade In and Fade Out displays for selected audio clips show the Fade In and Fade Out times for the audio in the clip. The readout is divided into 1/16 Note and Ticks. The Fade times can be edited as described in "Inspector segment displays".
- **Level display (audio clips only)**
  The Level display for selected audio clips shows the level of the audio in the clip. The readout is divided into dB and 1/100 dB. The level can be edited as described in "Inspector segment displays".
- **Transpose display (audio clips only)**
  The Transpose display shows the transposition of the audio recordings in the selected Audio Clip(s) - relative to the original pitch. The display readout is divided into (from left to right) Semitones and Cents, See "Transposing Audio Clips".

Selecting multiple clips

In Song View, several clips can be selected, e.g. for cutting, copying, pasting, deleting, moving and resizing purposes. If you select multiple note clips, these can be opened for Multi Lanes editing, see "Multi Lanes editing".

- **Press [Ctrl](Win) or [Shift](Mac) and select the clips.**
  Under Windows, you can also press [Shift] and click to select a range of clips on the same lane.

- **Draw a selection rectangle with the Selection Tool (arrow) on the Arrange Pane background.**



Click, hold and draw a rectangle with the Selection Tool to select multiple clips.

All clips that are touched by the selection rectangle will be automatically selected when the mouse button is released.

- **If you hold down [Shift] when you select clips with the selection rectangle technique, any previously selected clips will remain selected.**
  This allows you to make multiple, non-contiguous selections: first select some clips, then hold [Shift] and select some more clips, and so on.
- **Use the "Select All" function on the Edit menu or on the clip context menu to select all clips in the song.**
  Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and press [A].


Selecting clips with the arrow keys

Another way of selecting clips on the Arrange Pane is to use the arrow keys on the computer keyboard.

- **Press the [Left] or [Right] arrow keys to select the previous or next clip on the lane.**
- **Press the [Up] or [Down] arrow key to select the closest clip on the lane above or below.**
- **Hold down [Shift] and use the [Left]/[Right] arrow keys to make multiple selections on the same lane.**

Setting audio clip Level and Fades

Besides the Clip Resize handles, a selected audio clip also has Fade In and Fade Out handles plus a Clip Level handle. These can be edited at any time, either by using the handles as described below, or using the Inspector as described in "Fade In and Fade Out displays (audio clips only)" and "Level display (audio clips only)":



A selected audio clip in the Arrange Area.

Fade In and Fade Out Handles

- **Click and drag these handles horizontally to introduce a fade in and/or fade out of the audio in the clip.**
  The Fade settings can be set individually for each audio clip in the song. The fading is non-destructive and can be changed at any time. If Snap is activated (see "Snap"), the set Snap value is taken into account when setting the fade time(s).

Clip Level Handle

- **Click and drag this handle vertically to adjust the audio level in the audio clip.**
  The Level can be set individually for each audio clip in the song. The Level setting is non-destructive and can be changed at any time.

Deleting clips

- **To delete a clip, select it and press [Delete] or [Backspace] or select "Delete" from the Edit or context menu.**
  You can also draw selection rectangles with the Selection tool, encompassing several clips and delete them all at once. The same rules apply as when selecting clips (see "Selecting clips").

! **If you delete an audio clip which contains recordings that are not used elsewhere in the song, those audio recordings will be permanently deleted! However, if you accidentally erase an audio clip, you can always use the "Undo" function.**

Deleting clips with the Eraser tool

You can also use the Eraser tool to delete clips on the Arrange Pane. The Eraser tool can be used in two ways: you can click on single clips or you can make a selection rectangle encompassing several clips:


- **Select the Eraser Tool and click on the clip you want to delete.**



Select the Eraser Tool and click on the clip you want to delete.

Alternatively, if you want to delete multiple clips:

▶ **Select the Eraser Tool, click and hold the mouse button and draw a selection rectangle on the Edit/Arrange Pane background.**




Click, hold and draw a rectangle with the Eraser Tool to erase multiple clips.

All clips that are touched by the selection rectangle will be deleted once you release the mouse button.

Resizing (masking) clips

All clip types can be resized by clicking and dragging the lower parts of the clip's edges. This can be done both in the Song View and in the Edit Area. When you hover with the Selection (arrow) Tool over either of the edges, the Clip Resize symbol appears:



Resizing a note clip.

If you resize a clip and make it smaller, any recordings or events that will end up outside the clip boundaries will not sound, or have any effect, when played back. However, they are not deleted - just masked. If you make the clip larger again, the recordings or events that were masked will become visible and will play back again. See "About masked recordings and events".

If you enlarge an unmasked clip, nothing will happen except that the clip becomes longer.

- **If you resize an audio clip which uses Fade In and/or Fade Out, the fade slopes will follow along, unaffected, with the clip boundaries.**


Resizing multiple clips

It's possible to resize several clips by first selecting the clips, and then dragging the left/right edge on one of the selected clips. All selected clips will be resized by the same amount.

Resizing clips using the Arrange Area Inspector

Another way of resizing clips is to change the clip length(s) in the Arrange Area Inspector. This can be done in the following way:

- **Select one or several clips on the Arrange Pane and then change the Length value in the Arrange Area Inspector, by clicking on the up/down arrow buttons.**
  In the example below, we expand the clip lengths by 2 bars by clicking the up arrow button twice.



  All selected clips become 2 bars longer.


- **See "Inspector segment displays" for more details on how to edit in the Inspector displays.**

- **If the Tick segment in the Length display shows an asterisk (*), it means that the value is a fraction of a Tick - a sub-tick. See "About subticks in the Position and Length displays" for more info.**

About masked recordings and events

Masked recordings in audio clips


If you resize an audio clip and make it smaller, the masked part of the recording will be silent during playback. If you open a masked audio clip in the Comp Editor, the part of the recording that will actually play back is shown in the Clip Overview area. The masked part of the recording will appear grayed out on a Comp Row:



An open audio clip in the Edit Area before and after masking.

Masked events in note and parameter automation clips

In the picture below is an open note clip in the Edit Area with notes and Mod Wheel performance controller events, before and after resizing the clip:



An 8-bar note clip with notes and Mod Wheel controller events.

The same note clip resized to 4 bars

After resizing the clip from 8 to 4 bars, all events that begin in bars 5-8 are now masked and won't play back. All masked events will still be there - and follow along with the clip if the clip should be moved, cut or copied.


Masked events will be a blue color on the Note Edit Lane, to indicate that they won't play back. The first three-note chord in the masked area is still an orange color. That's because the notes begin in bar 4 (just before the downbeat) and thus will play back in their entirety, also after resizing the clip.

Masked performance controller events, parameter automation events and pattern automation events will be inactive - but could still affect the masked clip (see "About masked performance controllers and automation events" below). Outside a masked clip, the controller/parameter/pattern values will default to their Static Values in the masked area (see "Static Value handle").

! **A clip has to be opened in the Edit Area before you can view these events. You can remove all masked note and parameter automation events using the "Delete Events Outside Clips" function on the Edit menu (see "The "Delete Events Outside Clips" function").**

About masked performance controllers and automation events

Masked performance controller and parameter automation events just outside a clip can still affect the clip, since they affect the curve shape. The example below shows a masked note clip with Mod Wheel performance controller.



Masked event which still affects the clip

The first Mod Wheel automation event to the right of the masked part of the clip determines the direction of the automation curve from the last event in the unmasked area. These types of automation events are not blue, but black and white, just like unmasked events.

The result in this example is that the Mod Wheel value will continue to rise all the way to the end of the masked clip, at which point the value will drop down to the Static Value - in this case "0".

The "Delete Events Outside Clips" function

There may be situations when you want to delete all masked events, i.e. events located outside the left and/or right clip boundaries.

! **This function only works for note and parameter automation clips and will delete all masked notes that begin in the masked clip section, plus any performance controller or parameter automation events.**

1. **Reduce the size of the clips to your liking.**
2. **Select one or several clips and choose "Delete Events Outside Clips" from the Edit menu or from the context menu.**
3. **After the operation, all events outside the clip have been deleted.**

Tempo scaling clips

It is possible to tempo scale the content of clips, i.e. make the clip play back at faster or slower tempos. This can be achieved in two different ways:


- **By manually stretching selected clip(s).**
- **By using the Scale Tempo function on the clip context menu.**

! **Tempo scaling can be applied to all clip types, except for Time Signature automation clips.**


! **Note that Pattern Automation Clips will only be resized - the pattern tempo in the source device will NOT be scaled but will still be synced to the main sequencer tempo!**

Below, we will describe how to use the “scale tempo” tool to manually stretch clips. The Scale Tempo function on the clip context menu is explained in “Scale Tempo” in the “Note and Automation Editing” chapter.

1. **Select one or several clips on the Arrange pane in Song/Blocks View.**
2. **With the Arrow Tool selected, hold down [Ctrl](Win) or [Option](Mac) and place the mouse cursor over one of the clip edges.**
   The arrow symbol switches to a "scale tempo" symbol.



3. **Hold down [Ctrl](Win)/[Option](Mac) and click and drag the cursor sideways in either direction to scale the tempo of the clip contents.**
   In this example, we “stretch” the upper clip four bars, by dragging the right clip edge four bars to the right.



Now, all selected clips have been tempo scaled and the clip contents have been stretched to match the new clip length. Note that the content of all selected clips have been scaled proportionally. The Pattern Clip has only been resized, though. The pattern tempo in the source device has NOT been scaled.

For more details about tempo scaling audio clips, refer to “Tempo scaling Clips” in the “Audio Editing in the Sequencer” chapter.

Moving clips

Moving clips on the same lane

- **To move a clip, drag and drop it to the desired destination on the lane.**
  It's also possible to select and move several clips by dragging and dropping them at the desired destination. If the Snap function is selected (see "Snap"), you will only be able to move the clip(s) in steps of the selected Snap value - or to absolute positions on the grid, depending on the Snap settings.
- **You can also use the "Cut" and "Paste" functions on the Edit menu or context menu to cut the selected clip(s) and then paste them at the current Song Position Pointer position (see "Cutting, Copying and Pasting clips").**

Nudging clip positions

You can use the left and right arrow keys on the computer keyboard to "nudge" the positions of selected clips in a couple of different ways:


1. **Select the Snap value by which you want to nudge the clip(s).**
2. **Press [Ctrl](Win) or [Cmd](Mac) and use the Left and Right arrow keys to move the clip position back or forward by the set Snap value.**
   It doesn't matter if Snap is on or off - the clip will always be moved in steps of the set Snap value.

- **Press [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and use the left and right arrow keys to move the clip position back or forward in Beat increments.**
- **Press [Ctrl]+[Alt](Win) or [Cmd]+[Option](Mac) and use the left and right arrow keys to move the clip position back or forward in Tick increments.**
  There are 240 ticks per 1/16 note so this is very fine editing - check the tick positions in the inspector when you nudge because typically you won't "see" the position changes unless you're working at a very high zoom level.

Moving clips using the Inspector

Another way of moving clips is to change the clip position in the Inspector. This can be done in the following way:

- **Select one or several clips on the Arrange Pane. Then, change the Position value in the Inspector, either by clicking on the Up/Down spin controls, or by using any of the methods described in "Inspector segment displays".**
  In this example, we move the clips position 2 bars forward by clicking the "Up" spin control twice.



All selected clips are moved forward by 2 bars.

- **If the Tick segment in the Position display shows an asterisk (*), it means that the value is a fraction of a Tick - a subtick. See "About subticks in the Position and Length displays" for more info.**


Moving clips between lanes

You can move clips between lanes, either on the same track or between lanes on different tracks:

- ▶ **Click and drag the clip(s) to the desired position on the new lane.**
  The set Snap value is taken in to account if the function is activated (see "Snap"). It's also possible to move several selected clips in one go.
- ▶ **Hold down [Shift] when you drag the clip(s), to restrict the clips to vertical movement.**
- ! **If you want to move several clips in the Windows version of Reason, press the [Shift] key after you have pressed the mouse button, otherwise pressing [Shift] will select or deselect clips, and that's not what we want here.**
- ! **For a successful result, it's important that the source and destination lanes are of the same, or similar, type (see "About alien clips" below).**

About alien clips

An alien clip is a clip containing types of event, or different parameter range/resolution, other than that the lane is intended for. For example, if we move a note clip from a note lane to a parameter automation lane, the note clip would become alien and won't play back on the automation lane:



If a note clip is moved from a note lane to a parameter automation lane, for example, the clip becomes alien.

An alien clip can be distinguished by its red stripes, which indicate that the clip is currently inactive. If you place the cursor over an alien clip, a tool tip appears with detailed information:



Tool tip for an alien note clip.

- **A parameter automation clip can also become alien if it is moved to a parameter automation lane for a parameter with a different range or resolution.**
  In most cases, you can resolve this by first selecting the clip and then selecting "Adjust Alien Clips to Lane" from the Edit menu or from the context menu.

  For example, if a parameter automation clip for a parameter that has a bipolar (-64 to 63) value range is moved to a parameter automation lane with a unipolar (0 to 127) value range, it will become alien. Selecting "Adjust Alien Clips to Lane" from the Edit menu or context menu will adjust the parameter automation events of the clip to fit the range of the parameter on the destination lane.

Moving clips with performance controller automation to another track


If you move note clips that contain performance controller automation events to another track (for a different type of instrument device), there are a few things to note:

- **If you have only recorded standard performance controllers (Pitch Bend, Mod Wheel and Sustain pedal) in the note clip, these will usually translate without any problems when moved to another device track.**
  Be aware that all devices do not respond to all performance controllers - the Malström device, for example, does not respond to Aftertouch, Expression or Breath performance controller data.
- **If you have recorded non-standard controller parameters for a device in the note clip using the "Record Automation into Note Clip" option (see "Recording parameter automation into Note Clips") some automated parameters may not have an equivalent parameter in the target device.**
  In such cases the automation data for an incompatible controller will simply be ignored.
- **Parameters common to most instrument devices (filters, envelopes etc.) will be transferred to the target device whenever applicable.**

About overlapping clips

If you move or resize clips so that the clips overlap each other, the following rules apply:

- **Clips or sections of clips that are hidden (overlapped) will not play back.**
  Any lane can only play back a single clip at a time - if you want to mix two clips, put them on separate lanes (note clips) or on separate tracks (audio clips). See "Adding note lanes" and "Duplicating/copying tracks and devices".
- **The clip with the latest start position have priority (and will be played back).**
  This means if a shorter clip is placed "in the middle" of a longer clip, as in the picture below, the sequencer will play the beginning of the long clip, then the shorter overlapping clip and then the end of the long clip.



! **If both clips start at the same position and have the same length, the clip which was moved last will sound. Consequently, the "hidden" clip won't play back at all.**

! **Note that it's possible to cross-fade adjacent audio clips, for smooth overlaps. See "Crossfading audio clips".**

Duplicating clips

▶ **To duplicate selected clips, hold down [Ctrl](Win) or [Option](Mac), then click with the Selection Tool and drag a copy of the clip(s) to the desired destination.**
  As you begin dragging, the cursor displays a "+" sign next to it to indicate duplication.

- **You can use the Duplicate function ([Ctrl]/[Cmd]-[D]) to quickly make copies of clips, lined up after each other and spaced according to the Snap value.**
- **It's also possible to duplicate only a part of one or several clips by using the Razor Tool as described in "Duplicating a part of one or several clips"**

Cutting, Copying and Pasting clips

You can move or duplicate clips using the "Cut", "Copy" and "Paste" commands on the Edit menu or the context menu. When you paste, the clips will end up at the current song position, on their original lane(s).

If you paste a clip into another Reason song document, the pasted clip will be placed on the track with edit focus, if possible. Typically, you can just select a track in the other document, place the song position pointer where you want, and paste the clip(s) onto the selected track.

New tracks will be created when necessary. Since all tracks must have a device associated with them, the new tracks will be associated with empty Combinator devices. You can then use the Patch browser on the Combinator to select a suitable patch and device type. The above rules also apply when pasting alien clips and parameter automation clips.

Using Cut/Copy and Paste to repeat clips

When you cut or copy clips, the song position will automatically move to the end of the selection (or, if Snap is activated, to the closest Snap value position after the end of the longest clip). This allows you to quickly repeat a section of clips in the following way:

1. **Make sure the sequencer is stopped.**
2. **Activate Snap (see "Snap") and set the Snap value to "Bar" (or to the length of the section you want to repeat).**
3. **Select the clips you want to repeat.**
   Since you can select clips on several tracks , this is a quick way to copy entire song sections.
4. **Select "Copy" from the Edit menu or context menu, or hold down [Ctrl](Win) or [Cmd](Mac) and press [C].**
   The song position is moved to the closest snap value after the end of the longest clip in the selection (provided that the sequencer is stopped).
5. **Select "Paste" from the Edit menu, or hold down [Ctrl](Win) or [Cmd](Mac) and press [V].**
   The copied section is pasted in, and the song position is moved to the end of pasted selection.
6. **Paste again, as many times as you want to repeat the selection.**

Naming clips

You can give clips names, in the following way:

1. **Select the clips you want to name.**
2. **Select "Edit Clip Name" from the Edit menu or context menu.**
3. **Type in a name and then press [Return].**
   If you had multiple clips selected, they will all get the same clip name.

Renaming clips or removing clip names

- **To rename a clip, double click its name label, type a new name and press [Return].**
- **If you want to remove the clip name, double click it, press [Backspace] or [Delete] and then [Return].**
- **If you want to remove the names from multiple clips, select them, use the "Edit Clip Name" function and delete the highlighted name.**
  This will remove names from all selected clips.

Coloring clips

By default Clips are set to "Use Track Color", and will have the same color as their tracks. You can override this by selecting individual colors from the Clip Color sub-menu.


- **Select "Clip Color" from the Edit menu or the context menu and then choose a color from the palette on the sub-menu.**
  All selected clips will be colored according to the selected color. If you record new clips on the lane, they will be colored according to the set track color.




Splitting clips

You can split clips using the Razor Tool in Arrange Mode. To split a single clip, proceed as follows:

1. **Select the Razor Tool and place it where you want to split the clip.**
   On the Razor Tool's left edge is a cross-hair which indicates where the split will take place. If activated, the Snap setting is taken into account (see "Snap").



2. **Click with the Razor Tool to split the clip at the cross-hair's position.**
   The clip is now split into two separate clips.



A vertical line appears where the clip is split.


! **Recordings and events in a split clip will always remain intact, e.g. notes in a note clip will not be split even if they span over the split point.**

It's also possible to split clips on all tracks in a song:

1. **Place the Razor Tool's cross-hair on the Ruler where you want to split the clips on all tracks and lanes of the song.**
2. **Click in the Ruler to split the clips on all tracks and lanes at the current position.**
   Clips on tracks and lanes - including tracks and lanes that might not be visible - on the Arrange Pane will also be split.

You can also cut out a section of one or several clips in one go to:


1. **Place the Razor Tool on the Arrange Pane background close to where you want to split the clips.**
2. **Click and drag with the Razor Tool to select the split section - on one or several lanes.**



3. **Release the mouse button to split the clips.**

If you want to "cut" out a section of all clips on all tracks in the song, this can be done as follows:

1. **Place the Razor Tool's cross-hair on the Ruler where you want to split the clips on all tracks of the song.**



2. **Click and drag the Razor Tool in either direction on the Ruler to make a range selection.**
3. **Release the mouse button to split the clips on all tracks and lanes in the song.**

! **Clips on tracks and lanes that might be scrolled out of view on the Arrange Pane will also be split.**

Duplicating a part of one or several clips


By using either of the methods described above, it's also possible to duplicate the "split" section of the clip(s) and then move them to a new destination. Here's how:

- **With the Razor Tool selected, hold down [Ctrl](Win) or [Option](Mac) and drag to create a duplicate of the "cut out" section of the clip(s). Then, use the Selection Tool to move the duplicated clip(s) to a new destination.**
  The original clips will remain uncut, just as they were before the operation.

Splitting clips at song position

The "Split Clips at Song Position" function on the Edit/clip context menu makes it possible to split all selected clips (on several) tracks, at the current song position:

1. **Select the clips you want to split at the current song position - and move the song position marker where you want the split:**




2. **Hold down [Alt](Win) or [Option](Mac) and press [X] - or select "Split Clips at Song Position" from the Edit menu or the clip context menu.**
   The selected clips are now split at the current song position marker.

Chopping clips

You can choose to chop up selected clips to a number of preset lengths. This will cut the selected clips into equal smaller clips. This can be useful if you want to cut a drum beat in an audio clip into smaller clips and then change the order of the clips, for example.

1. **Select the clips you want to chop:**




2. **Select "Chop Clips to >" and select the desired clip length from the Edit menu or the clip context menu.**
   The selected clips are now chopped to the selected length.

! **Note that the chopping is done relative to the sequencer absolute grid.**

Crossfading audio clips

When two audio clips have overlapping edges, it's possible to add a crossfade in the overlap area. By "crossfade" we mean "crossfade to previous clip".

1. **Drag one of the audio clips so that it overlaps the edge of the other audio clip:**



Moving the last (orange) clip....



...so that it partly overlaps the first (green) clip.

2. **Press [X] or right click the last (orange) clip and select "Crossfade" from the bottom of the context menu.**
   The overlap area is now crossfaded, as shown by the white crossfade curves:



3. **You can adjust the crossfade zone by clicking on either edge of the crossfade zone and drag sideways:**
   This actually resizes the clips; adjusting the left edge changes the start of the orange clip and adjusting the right edge changes the end of the green clip.




Adjusting the right edge of the crossfade zone.

4. **You can also change the crossfade symmetry by clicking the crossfade curve and dragging sideways:**



Adjusting the crossfade symmetry.


▶ **To remove a crossfade, select the last (orange) clip and press [X] - or deselect Crossfade from the context menu:**




Joining clips

Separate clips on the same lane can be joined into one clip. You can also join clips that aren't directly adjacent on the lane, or clips that overlap each other.

1. **Select the clips you wish to join.**



2. **Select "Join Clips" from the Edit menu or from the clip context menu. Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and press [J].**



A single clip is created. If there was a gap between the clips before the operation, this area will be empty - the original positions of all events in the original clips will be preserved in the joined clip.


- **Only clips on the same lane can be joined.**
  It's possible to select several clips on several lanes, but only selected clips on the same lanes will be joined.
- **You can also join selected clips that have other non-selected clips in-between them.**
  The non-selected clips in-between will then overlap and mask the joined clip at their current positions.

! **If you join note or parameter automation clips that contain masked events in the area(s) between the clips, the masked events will be permanently deleted! This is to make the resulting clip play back the same as the original clips did before joining. (See "Masked events in note and parameter automation clips").**


! **If you join overlapping note or parameter automation clips, the events in the clip which lies on top will replace and permanently delete the events in the overlapped region of the "hidden" clip.**

About joining audio clips


Joining audio clips basically works in the same way as joining note and parameter automation clips - except when it comes to joining overlapping audio clips. What happens if you join overlapping audio clips is that the clips will be placed on separate Comp Rows - and be automatically comped to a "final" clip. No recording will be deleted. Let's have a look at the example in the picture below:



The original audio clip (blue) with an overlapping audio clip (yellow) selected in Arrange Mode.



The two audio clips joined into a single audio clip in Arrange Mode.



The "joined" audio clip open in the Comp Editor.

As you can see, the entire audio recording in the original clip is preserved - only masked where the overlapping clip is located. If you change your mind afterwards, you will still be able to access the entire original recording.

- **If overlapping clips have different Clip Levels, the Comp Row Levels will change to these levels after joining.**
  The Clip Level in the joined clip will be set to -0 dB.
- **If overlapping clips use Fade In and/or Fade Out and the clips overlap in the Fade In/Out area(s), the Fade(s) will be removed after joining.**
  Also, if you join audio clips that aren't directly adjacent, any Fade Out in the first clip and Fade In in the second clip will be removed.
- **Any Cut Crossfades used in comped audio clips will be preserved after the joining.**


About joining crossfaded audio clips

If audio clips you are joining have a crossfade between them, this is what happens:


1. **Select the two crossfaded clips:**



2. **Select "Join Clips" from the Edit menu or from the clip context menu. Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and press [J].**
   The "joined" clip shows up on the track:



3. **Double click the clip to open it in the Comp Edit Area:**



As you can see, the crossfade zone has been automatically bounced to a new recording on a separate Comp Row.

! **Note that even though we joined two mono audio clips, the resulting audio clip automatically becomes stereo (with two identical mono audio “channels”). This happens by default when crossfaded audio clips are bounced, but does not affect the audible result.**


Reversing clips

It’s also possible to reverse clips, i.e. play the content of the clip “backwards” (from the end to the start). This works a little differently for audio clips and note clips. Please refer to “Reverse” for information about reversing note and automation clips, and to “Reversing audio clips” for information about reversing audio clips.


Muting clips

Clips can be muted as follows:

▶ **Select the Mute Tool from the Toolbar and click on the clips you want to mute.**



Muted clips are indicated with gray stripes, borders and events:



Muted clips.

▶ **Select the clips and then select “Mute Clips” from the Edit menu or from the clip context menu. Alternatively, select the clips and press [M] on the computer keyboard to mute them.**

Unmuting clips


Muted clips can be unmuted as follows:

- ▶ **Click on muted clips with the Mute Tool.**
- ▶ **Select muted clips with the Arrow Tool and select "Unmute Clips" from the Edit menu or context menu - or press [M].**
- ! **Muted clips cannot be joined with other clips.**
- ! **Muted note clips will not be included when using the "Merge Note Lanes on Tracks" function described in the "Merging clips on note lanes" section.**

Merging clips on note lanes


Several note lanes on a track can be merged into a single note lane:

1. **Select the track with the note lanes you wish to merge.**



A selected instrument track with separate note lanes.

2. **Select "Merge Note Lanes on Tracks" from the Edit menu or from the context menu.**
   The clips on all note lanes will be merged on the topmost note lane.



The same instrument track after merging.

- ▪ **If there are time gaps between the clips on the lanes, several clips will be created on the merged note lane.**
- ▪ **Muted note lanes or muted clips on the track will not be included in the merge.**
- ▪ **It's also possible to select several tracks and merge the note lanes on each individual track, all in one go.**

Bounce in Place

The Bounce in Place function lets you bounce the sound generated from playing back note or audio clips, with any insert effects and channel strip coloration - but without Send FX and Master Section settings - to a new audio clip on a new audio track. The Bounce in Place function is mainly intended for creative audio work, for example:


- ▪ **creating audio clips out of note clips, that you could then manipulate the slices in - or cut up.**
- ▪ **creating audio clips out of note (or audio) clips - with the sound from any effects included.**
- ▪ **creating audio clips out of note clips that you could then reverse (see "Reversing clips").**
  This is great for reverberated drum hits or vocals etc. that you could then play backwards for interesting effects.
- ▪ **for creating audio clips that you could use as samples in any sample player device (see "Bounce Clip(s) to New Sample(s)") or as REX loops in the Dr Octo Rex (see "Bounce Clip to REX Loop").**

- ▶ **If you want to bounce entire tracks to audio, use the Bounce Mixer Channels function instead. See "Bouncing Mixer Channels".**

- ! **Note that if you bounce audio clips that are in mono, the bounced clip will be in stereo because the bounce is post-pan on the channel strip. Thus, if a mono channel is panned left or right, the two channels will not be identical. Also, even though the audio clip is in mono, there may be insert fx turning the channel to stereo.**

Here is an example of how you can use the Bounce in Place function:

1. **Select the clip you want to bounce.**
   In this example we choose a note clip on an ID8 instrument track:



2. **Select "Bounce in Place" from the context menu (or Edit menu). (If you bounce an audio clip, select "Bounce > Bounce in Place" instead).**
   A new audio clip is created on a new audio track, colored and named according to the original track - with the addition of the word "Bounced" in the destination track name. The destination track inherits the settings from the source track, i.e. mixer settings and any Output Bus routing.



   The bounced audio clip always has the same position and length as the original source clip.

   Note also that the source clip is automatically muted.

3. **If the source clip generated any sustaining (or reverberating) audio, this might be masked in the bounced audio clip. To reveal any audio tail, just resize (expand) the bounced clip:**



   Expand the bounced audio clip to reveal any sustaining audio tail.

- **Similarly, if a note clip should contain any notes that extend to the right outside the clip boundary, the audio from the notes will be bounced to the new audio clip in its entirety.**
  The audio from the extended note(s) will be masked in the audio clip, so you will have to expand the bounced audio clip to hear the complete rendering.

! **The maximum length of any sustaining/reverberating "tail" in the bounced clip is automatically limited to 5 seconds after the last "note off" in the original note clip - or 5 seconds after the end of an audio clip.**

- **Completely masked notes in a source clip will not be rendered to audio - only the notes you can hear.**
- **Any parameter automation of the source device that affects the audio are also taken into account when bouncing.**
  This means that what you heard when you played back the source track is exactly what you will hear when you play back the bounced clip on the destination track.

Bouncing multiple clips

If you have selected multiple clips to “Bounce in Place”, this is what happens:

- **Clips that are on the same source track will result in bounced clips on the same destination track.**
- **If the clips are on different source tracks, the bounced clips will be on separate, new destination tracks.**

Bouncing overlapping clips

If you have selected multiple overlapping clips to “Bounce in Place”, this is what happens:

- **The separate ranges for each of the source clips are bounced. The bounced clips are then placed overlapping in the same way on the destination track.**


Bouncing clips on instrument tracks that use several Mix Channels

- **If you want to bounce a note clip for an instrument that uses separate Mix Channels (e.g. individual outputs of an instrument device connected to separate Mix Channels), a separate audio track will be created for each used Mix Channel.**
  On each of these audio tracks there will be a separate audio clip rendered from each of the Mix Channels.

About tracks with no Mix Channel of their own

- **If a track's device is not connected to its own separate Mix Channel, the Bounce in Place function will be disabled.**
  For example, if an instrument device is connected to a Mixer 14:2, which has other instrument devices connected to it, and then routed to a single Mix Channel device, there's no obvious way to isolate the audio from a single instrument device (since other devices connected to the Mixer 14:2 might be playing as well). Thus, the Bounce in Place function will be disabled.

Matching clips using the “Match Values” function




The “Match Value” function in the Arrange Area Inspector can be used for matching the positions or lengths of several selected clips to the position and/or length of the topmost selected clip (or leftmost if the clips are on the same lane).

Matching clip positions

To match clip positions:

1. **Select a couple of clips on the Arrange Pane.**
2. **Click the “Match Values” button to the right of the Position display to move all selected clips to the start position of the topmost clip - or leftmost clip, if the clips are on the same lane.**




All selected clips are moved to the start position of the topmost selected clip.

! **Note: If you match the position of several clips on the same lane, they will all start at the same position, and thus overlap.**

Matching clip lengths

Another Match Value function in the Arrange Area Inspector can be used to match the lengths of several selected clips to the length of the topmost (or leftmost if on the same lane) selected clip:

1. **Select a couple of clips on the Arrange Pane.**
2. **Click the "Match Values" button to the right of the Length display to resize all selected clips to the length of the topmost clip - or leftmost clip, if the clips are on the same lane.**




All selected clips are resized to a length of 6 bars - the same as the topmost selected clip.

Matching audio clip levels, fades and transposition

In addition to Position and Length matching, audio clips can have their Fades, Levels and Transpose values matched:


1. **In Arrange Mode, select a couple of audio clips.**
2. **Click the "Match Values" buttons to the right of the respective displays to match to the values of the topmost clip - or leftmost clip if the clips are on the same lane.**



After having clicked the Match Values buttons, all selected audio clips get the same values as the topmost selected audio clip.

Looped Clips

A looped clip is a note clip, audio clip or automation clip that has been lengthened to repeat a number of times.




A looped note clip (looped 4 times)


- **A looped clip is distinguished by beveled corners.**
- **If you click to select a looped clip, its top bar will go slightly dark. The loop instance where you clicked will get an even darker top bar, indicating edit focus.**

Looping clips

1. **To create a looped clip, hover over the upper right part of the clip until the cursor switches to a Loop symbol.**
2. **Click and drag the right clip edge to the right for as long as you want to loop the clip:**




A note clip



The same note clip looped (3.5 times)

- **The clip inspector indicates this by turning on the Loop Clips checkbox, and adding Loop Offset and Loop Length fields:**



- ▶ **To turn loop off and return to the original clip, turn off the Loop Clips check box for the clip, or resize it back to a single loop length.**

Changing loop length

Dragging the intersection between loop instances (or changing the Loop Length field in the inspector) will make each loop instance (the "original clip") longer or shorter. This will change the number of loops but keep the total clip length.

- ▶ **Drag the intersection between two loop instances sideways to decrease (left) or increase (right) the loop length.**
  The number of loops will also change accordingly:



The loop clip length reduced from 4 to 3 bars


- **It's also possible to Tempo Scale the looped clip, by holding [Ctrl](Win) or [Option](Mac) and resizing the leftmost or rightmost clip edge.**
  This will stretch each loop instance equally.

Editing the looped clip contents

You can edit a looped clip by double clicking it on the Arrangement Pane as usual. This opens the loop instance you double clicked in the Edit Area. Making an edit in a looped clip will affect all loop instances in the clip. For example adding or removing a drum hit in a drum pattern will instantly happen throughout the whole looped clip.

Editing looped note clips


1. **Double click one of the loop instances in a looped clip to open it in the Edit Area.**
2. **In this example we drag a note to a new position and we also move a performance controller automation point.**
   As you can see in the pictures below, the edits we make in one loop instance are automatically mirrored in the others:



Editing looped parameter automation clips


Looping parameter automation clips is a great way to create custom “LFO-type” modulation. If you want to edit the "shape" of the modulation, just open one of the loops and edit the automation points.

1. **Double click one of the loops in the automation clip to open it in the Arrange Area.**
2. **In this example we drag a parameter automation point to another position.**
   As you can see, the edits we make in loop instance are automatically mirrored in the others:



Editing looped audio clips

1. **Double click one of the loops in the audio clip to open it in the Edit Area.**
2. **In this example we drag the Fade In handle to create a smother fade-in for all loop instances.**
   As you can see in the pictures below, the edits we make in one loop instance are automatically mirrored in the others:




- **Any audio editing you do in a looped audio clip (comping, pitch editing or slice editing, for example) will be mirrored in all loop instances.**

Additional Looped Clips functions

Edit single Looped Clips without affecting the other

If you want to make a change to a single loop instance without affecting all loops, there are a couple of ways:

- **Overlapping clips have priority. This means you can "mute" a part of a looped clip by drawing an empty clip on top of it.**
- **If you right-click a loop instance and open the "Looped Clips" sub menu, you can select "Duplicate Loop Instance".** This makes a copy of this instance only and places it on top of the looped clip. You can now make edits to this clip, affecting only this loop instance:



Right clicking a loop instance and selecting "Duplicate Loop Instance" creates a regular clip on top of the loop instance.

- **You can also use the Razor tool to cut a looped clip in two - this creates two separate looped clips.** This could be useful if you have a drum loop that should change halfway through the song, etc.


Converting Looped Clips to regular clips

The "Looped Clips" sub menu on the Edit menu and on the clip context menu also contains functions for turning a looped clip into a regular clip:

- **"Convert to Single Clip" renders the whole looped clip into one clip.** For a looped audio clip, this creates a new audio recording.
- **"Convert to Separate Clips" turns each loop instance into a regular clip.**

Inserting bars


The “Insert Bars Between Locators” function in the Timeline section on the Edit menu, or context menu, can be used for inserting empty bars between the Left and Right Locators. All clips that intersect the locator positions on all tracks after the Left Locator are split and moved to the Right Locator to make room for the inserted bars.



Different tracks with lanes before and after insertion of 4 extra bars between bars 13-17.

Removing bars

The “Remove Bars Between Locators” function in the Timeline section on the Edit menu, or context menu, removes all events between the Left and Right Locators. All clips that intersect the locator positions will be cut (when necessary), and the cut section (between the locators) will be removed. All clips that originally were located to the right of the Right Locator will then be moved to the Left Locator, closing the gap.




Different tracks with lanes before and after removal of 4 bars starting at bar 13.


! Any removed note and parameter automation events between the Left and Right Locators will be deleted!

About removing bars that contain audio recordings

As opposed to note and parameter automation events, audio recordings in removed bars will not be deleted. Instead, they will be placed on a Comp Row and masked. If we open the second audio clip in the previous example in the Edit Area, we can see that the audio recording in the removed bars has been moved forward and masked:



The audio clip in the Arrange Area before and after removal of four bars (yellow frame) between the locators.



The audio clip in the Comp Editor after removal of four bars.

"Removed" recording moved forward on the Comp Row and masked



Chapter 8
Track Folders in the Sequencer

About this chapter

This chapter describes how you can arrange your sequencer tracks in Track Folders, to get a "cleaner" arrangement.

Before reading this chapter, it's recommended that you are familiar with the sequencer functions and definitions described in the "Sequencer Functions", "Recording in the Sequencer" and "Arranging in the Sequencer" chapters.

Introduction

Track Folders are a special track type that can contain other tracks, much in the same way folders on a computer desktop can contain files or other folders. There are several benefits to working with Track Folders:


- **If you have a song with many tracks, sorting them into folders will keep the arrangement tidy and easier to navigate.** You could for example put all drum tracks in a folder, with sub folders for percussion and so on.
- **If you close folders, the arrangement takes up less vertical screen space and you can focus on the tracks you're working on right now.**
- **Folders can also be used for putting away alternative takes, unused ideas or trash recordings (that you still don't really want to delete).**
- **Finally, Folder Clips allow you to work with multiple clips at the same time - moving them, cutting them with the Razor tool, muting, transposing and so on.**

Working with Track Folders

Adding Track Folders

To move tracks into a new Track Folder, proceed as follows:

1. **Select the tracks in the Track List.**
2. **Right-click one of the selected tracks to bring up the track list context menu, and select "Move Selected Tracks to New Folder" from the Track Folder submenu.**
   The keyboard shortcut for this is [Shift]+[Cmd]+[T] (Mac) or [Shift]+[Ctrl]+[T] (Win).



Moving selected tracks to a new Track Folder.

This will create a new Track Folder above the selection, and move the tracks into that folder:



Tracks moved to a new Track Folder.

- **Alternatively you can select "Add Track Folder" from the Track Folder sub menu or the +Track menu (at the bottom of the Track List).**
  This will create a new, empty Track Folder.

! **Note: Track Folders can be nested (a folder may be within another folder). The maximum nesting depth is three layers (a Track Folder within a Track Folder within a Track Folder).**

About Track Folder Color

When you create a Track Folder with the "Move Selected Tracks to New Folder" function, the folder will get the color of the topmost selected track.

At the top of the Track Color sub menu for a Track Folder is a setting called "Apply to All Tracks in Folder". Turn this on to apply the folder color to all tracks within it. This is a quick way to keep things visually sorted and tidy:




Applying the same color to all tracks in the selected Track Folder.

- **With the setting on, changing the color of the Track Folder will affect all contained tracks.**
- **Turning this setting off will bring back the original track colors.**
- **The "Apply to All Tracks" does not affect nested sub folders.**
  This means you can have all tracks in your Vocals folder dark green, but the Backing Vocals sub folder can have its own color.

Track Folder settings and functions

Opening and Closing Folders


- **Open or close a Track Folder by clicking the arrow button in the track list, or by double clicking the Folder symbol.**
  Hold [Option](Mac) or [Alt](Win) and click the arrow button to open or close all folders in the track list.



Folding and unfolding a Track Folder.

Moving Tracks and Folders


- **Move tracks into a Track Folder by dragging and dropping them on the Track Folder.**
  A special drop icon shows that the tracks will be moved into the Track Folder:



Moving a Monotone track into a Track Folder.

- **If the Track Folder contains tracks already, the newly added tracks will be added at the top.**
- **If the Track Folder is closed, holding the track over the folder for a couple of seconds will open it.**
  If the Track Folder is open, you can drop tracks at any position within it.
- **If the song is in Rack per Track or Auto-Group Devices mode (see $), moving a track into a Track Folder will also move any other tracks for that device group, keeping them together.**
  For example, moving an instrument track will move any automation tracks for its effects or mix channels.
- **When you drag a Track Folder into another folder, the maximum nesting depth of three applies.**
  If the target folder is already a sub folder to another sub folder, there will not be a drop icon and you cannot move the folder there.

- **If you are dragging a track into nested folders, the insertion line indicates into which folder the track will go:**



In the left picture, the track will drop into the upper Track Folder. If you move the dragged track to the right (right picture), it will drop it the subfolder instead.

- ▶ **To move a track out of a Track Folder, open the Track Folder and drag the track to a position above or below the Track Folder.**

Unpacking and Deleting Track Folders

Unpacking a Track Folder is the same as moving all tracks out of the folder, and then removing the empty folder. To do this, right-click the Track Folder in the track list and select "Unpack Track Folder" from the Track Folder submenu.

Deleting the Track Folder will remove it and all tracks within it. This is done like deleting other tracks (e.g. by selecting the Track Folder and pressing Backspace/Delete). Doing this will show a warning that all tracks in the folder will be deleted - you can choose to Unpack the folder instead. To delete without getting the warning, hold [Cmd](Mac) or [Ctrl](Win) and delete it.

About Mute and Solo

Track Folders have Mute and Solo buttons in the track list.

- **Muting a Track Folder will "implicitly mute" all tracks within the folder, indicated by their Mute buttons being dimmed red.**
  You can still solo a track inside a muted folder, if you need to hear what's on it.



Muting a Track Folder


- **Soloing a Track Folder will "implicitly solo" all tracks within the folder - except any tracks that you have manually muted.**
  For example, if you have alternative, unused takes on a muted track in your Vocal folder, that track will stay muted even if you solo the Vocals.



Soloing a Track Folder

Folder Clips

When there are clips on regular tracks inside your Track Folder, they will be represented by Folder Clips. These are shown on the Folder Tracks, both for open and closed Track Folders. The Folder Clips has the color of its Track Folder:



Track Folder clips.


It's important to understand that these are not actual clips, but representations of the clips that exist on the tracks inside the folder. When you add, move or delete clips on the tracks, the folder clips will adapt to the changes. In the same way, any actions you perform on the folder clips will actually be done to the clips on the tracks within.

A folder clip starts where the first contained clip starts and spans all overlapping contained clips:




The single clip to the left is represented by a separate folder clip (A). The three clips to the right overlap, resulting in a single folder clip (B) for them.

If contained clips are not overlapping each other, there will be individual folder clips for these:



The light blue clip has been shortened so that it no longer overlaps the upper clip - it gets its own folder clip.

When you move clips on the tracks, the folder clips will automatically adapt:



The light blue clip is moved to the left - it's now represented by the first folder clip (A) instead.

Selecting Folder Clips

- **Select a folder clip by clicking it or by using the arrow keys.**
  A selected folder clip has a dark top bar, and if the folder is open, the area below the clip is shown with a slightly darker background:




A selected Folder Clip gets a dark top bar.

- **Selecting folder clips allows you to use menu items such as Delete or Duplicate Clip, or their keyboard shortcuts.**
- **You can also use functions that affect the contents of the clips, like Quantize and Transpose.**
- **When a function is applied to a selected folder clip, this affects all clips that are represented by the folder clip (as if you had selected all these clips).**

Moving Folder Clips

Moving a folder clip is the same as selecting all clips under it and moving them. You can only move folder clips sideways, not to other tracks.

! **If you move the folder clip so that it overlaps another folder clip, they will become a single clip.**




Moving a Folder Clip so it overlaps another Folder Clip turns them into a single Folder Clip.

▶ **If you should do this by mistake, you can always Undo by holding [Command](Mac) or [Ctrl](Win) and pressing [Z].**

Muting Folder Clips

Muting a Folder Clip (by selecting it and pressing M) is the same as muting all clips under it. When all clips are muted, the folder clip is shown striped. Press M again to unmute all clips:



Muting a Folder Clip mutes all the contained clips.

▶ **You can still unmute individual clips in the Track Folder as usual.**

Other useful Folder Clip functions

- **Use the Razor tool or the Chop Clips function to split all clips under a folder clip at the same positions.**
- **Right-clicking a folder clip and selecting Reverse will reverse the individual clips without changing their relative positions.**
- **Select a folder clip and press [P] to set the locators around this section and start loop playback.**

Chapter 9
Audio Editing in the Sequencer

About this chapter

This chapter describes how to edit audio clips after you have recorded them in the sequencer. General sequencer functions, recording, note and automation editing, and arranging in the sequencer are described in detail in the chapters "Sequencer Functions", "Recording in the Sequencer", "Note and Automation Editing" and "Arranging in the Sequencer".

Edit Modes, Stretch & Transpose Types and Clip Types


After you have recorded your audio clips, you might want to adjust levels, trim starts and ends, add fades etc. If you have recorded several takes in your audio clips, or several cycles in Loop Mode, you can also cut out segments of the various takes and compile (comp) them into a final "perfect" audio clip.

You can also quantize audio clips, manually change the timing of individual notes or beats in the clips and even export audio clips as REX files.

In addition to this you can also edit and correct the pitches of monophonic audio recordings, in the Vocal Edit mode.

Edit Modes

When you open an audio clip (for example, by double clicking it in the Arrange Area) it will normally open up in the Edit Area in Audio Overview Edit mode. There, the audio clip shows one (mono) or two (stereo) waveforms inside the audio clip:



An audio clip in Audio Overview Edit mode.

In Audio Overview Edit mode you can perform a number of basic functions: In the Edit Area Inspector, you can rename recordings, change the tempo (stretch), transpose, reverse and normalize. In the Edit Area you can also preview the recordings with the Speaker Tool, move Slice Markers (in Single Take clips) and cut (split) audio clips.

To further edit the audio there are three main modes in the Edit Area:


- **Slice Edit mode.**
  Slice editing can be made on Single Take clips (see "Clip Types" below). Slice editing allows you to adjust the positions (timing) of the automatically detected and distributed transient slice markers that appear in the audio clip. The timing can be adjusted by moving and stretching (warping) the audio slices. See "Editing audio in Slice Edit mode".
- **In Vocal Edit mode you can graphically correct and edit the pitches of monophonic audio in Single Take clips - perfect for vocal pitch correction/manipulation. See "Editing audio in Vocal Edit mode" for more information.**
- **Comp Edit mode, to create compiled clips out of multiple recordings in the clip.**
  In Comp Edit mode you can cut out segments of several Takes (recordings) and compile into a final clip. Here you can also insert silence segments to e.g. remove noise from silent parts in your audio clips. See "Editing audio in the Comp Editor".

Selecting Stretch and Transpose Type

When you are stretching, transposing and/or changing the tempo of the audio it's important that the Stretch and Transpose Type for the corresponding audio clip - or Comp Rows in Comp clips - is set according to the type of audio that's in the clip. Otherwise, the sonic result might not be what you'd expect.

Stretch and Transpose Type can be selected as follows:

▶ **With a clip open in Audio Overview Edit mode, select the desired Stretch and Transpose Type from the Stretch Type dropdown:**



▶ **In the Arrange Area, select the desired audio clip(s), then select the desired Stretch and Transpose Type from the Edit menu or clip context menu.**

! **For Comp Clips, the active Stretch and Transpose Type for all active Comp Rows are shown in the menu - if the Stretch and Transpose Type is the same. If there are active Comp Rows with different Stretch and Transpose Types, none of the options on the menu are shown as selected.**


Selecting a Stretch and Transpose Type from the sub-menu for a Comp Clip will change the stretch and transpose type for all active Comp Rows in the clip.

If there are Slice/Vocal Edits done to any of these Comp Rows (and these edits cannot be preserved in the new Stretch Type), there will be an alert asking if you want to bounce the clip to a new recording.

- **For polyphonic material, select "Allround".**
  The formants are transposed along with the audio.
- **For monophonic material select "Melody".**
  The formants are transposed along with the audio.
- **For vocal material select "Vocal".**
  The formants are preserved and are not transposed along with the audio. This will keep the original character of the vocal and will only affect the pitch. "Vocal" is also the default Stretch and Transpose Type for editing audio in Vocal Edit mode, see "Editing audio in Vocal Edit mode".

! **For the Stretch and Transpose function to be active, make sure that you have selected Enable Stretch from the clip context menu!**

Tempo



In the Tempo section you can scale the tempo of the audio clip:

- **Click the x2 button to double the tempo of the audio in the clip (making the clip half as long).**
- **Click the /2 button to halve tempo of the audio in the clip (making the clip twice as long).**
- **Type in, drag up/down, or click the up/down buttons to set s desired scale factor in %. Then click the Scale button to scale the audio.**

! **These settings are only available if Stretch is enabled for the audio clip. See "Enable/Disable Stretch (Audio Clips)".**

Edit


When you an import an audio file into a song (and the "Stretch to Song Tempo" option is selected in the Preferences, see $), Reason looks for tempo metadata in the file. If none can be found, the program attempts to guess the tempo based on the file length (if the length matches a 1, 2, 4 or 8 bar loop in a normal tempo range). This read or calculated tempo is then stored with the audio recording, and used as basis for stretching the audio to tempo: Reason compares the stored tempo with the song tempo, and stretches the audio clip so that they match.

This often works well, but there are cases where imported audio doesn't play back as expected. For example:

- **The actual length of the audio file was some other number of bars, or it wasn't in 4/4 time signature.**
- **The audio file was too long to be considered a loop on import.**
- **There was audio metadata in the file, but it wasn't correct.**

There are two ways to fix this:

- **If you know the actual length of the clip (e.g. 5 bars) you can just scale-resize the clip to this length.**
- **If you know the actual tempo of the clip (e.g. 94 bpm) you can click the Edit button in the Tempo section in the Edit Area inspector. This opens the Edit Tempo dialog:":**



- **Enter the known tempo in the "Actual tempo..." box and click OK.**
  The new tempo will be stored with the audio recording, and the clip will be re-stretched to match the song tempo.
- **If you want the audio to play back as the file on disk, click "Reset to Unstretched Tempo".**
  This will write the current song tempo into the audio recording, thus causing no stretch at all. This is preferable to Disabling Stretch for the clip, since it still allows you to do tempo-based operations such as quantize, Slice edit and more.

Clip Types

An audio clip can be either a Single Take clip or a Comp (multiple takes) clip:

- **A Single Take clip is set to play back only a single Take (Comp Row) throughout the audio clip.**
  If you have recorded only once in an audio clip, or recorded several complete Takes, the clip is automatically set to Single Take mode. A Single Take clip could also contain several Comp Rows, where one Comp Row has been manually selected for playback.


  Single Take clips can be edited in any of the three edit modes Slice Edit, Vocal Edit and Comp Edit.
- **A Comp clip is built up by segments from several recordings on multiple Comp Rows in the clip.**
  If you have recorded (or imported) several takes (recordings) in the same audio clip - or recorded several loops in Loop Mode - and then compiled segments of the various Comp Rows in the Comp Editor, the clip becomes a Comp clip.

  A Comp clip can also be edited in all three edit modes, but then it first has to be converted into a Single Take clip This can be done automatically when you switch edit mode.


Opening audio clips for editing

In the Arrange Area, audio recordings are displayed as one or two (mono or stereo) waves in the audio clips. The selected audio clip in the pictures below contains a mono recording.

- **Open an audio clip by double-clicking it, or by selecting it and pressing [Return].**
  The audio clip opens in the default Audio Overview Edit mode:



Double-click an audio clip in the arrangement...



...to open it for editing in the Edit Area.

Audio clips normally open in the Audio Overview Edit mode, with the following exceptions:

- **If you already have an open clip in Comp Edit mode and then select another audio clip, the new clip will also open in Comp Edit mode.**
- **If you already have an open clip in Vocal Edit mode and then select another audio clip that has Vocal Stretch Type, the new clip will also open in Vocal Edit mode.**

- **If you already have an open clip in Slice Edit mode and then select another Single Take audio clip, the new clip will also open in Slice Edit mode.**

By clicking any of the three Edit Mode buttons at the bottom of the Edit Area Inspector you can choose how you want to edit your audio recordings:


- **Click the Slice Edit mode button if you want to stretch, move and quantize audio slices etc., see "Editing audio in Slice Edit mode".**
- **Click the Vocal Edit mode button if you want to pitch-correct and transpose individual notes (pitches) in monophonic audio recordings, see "Editing audio in Vocal Edit mode".**
- **Click the Comp Edit mode button if you want to alternate the playback between several recordings and compile into a single recording, see "Editing audio in the Comp Editor".**

- **If Reason detects monophonic, melodic audio when you import an audio file, the clip will be automatically set to Vocal Stretch Type.**
  You can change Stretch Type manually if you like.

Auditioning audio in the Audio Overview Edit Mode

You can audition the audio recordings in Audio Overview Edit Mode, without needing to start playback of the sequencer:

1. **Select the Speaker Tool and place the cursor on the clip, at the position you would like to begin the auditioning:**




2. **Click and hold for as long as you want to audition.**

Stretching and repositioning Slices in the Audio Overview Edit Mode

It's possible to stretch and reposition slices in Single Take clips already in the Audio Overview Edit mode, i.e. you don't have to enter Slice Edit Mode first.

- **With the Selection (Arrow) Tool, select the desired Slice Marker at the top of the clip and drag sideways to stretch:**



Stretching Slices in the Audio Overview Edit Mode.


- **Hold down [Option](Mac) or [Ctrl](Win) and drag sideways to reposition the Slice Marker without stretching the audio.**
  Note, though, that this is easier to do in Slice Edit mode, see "Repositioning Slice Markers".

! **You cannot move Slice Markers past their closest adjacent Slice Markers.**

Cutting (splitting) Audio Clips in the Audio Overview Edit Mode

It's possible to cut audio clips in the Audio Overview Edit Mode.


- **With the Razor Tool, click at the desired position (or Slice Marker) at the top of the clip to split the audio clip:**
  The Razor Tool can snap to Slice Markers (transients/notes pitches) when you click in the top area. This makes it possible to split clips exactly on transients/note pitches.



Cutting an audio clip in the Audio Overview Edit Mode.

Closing the Audio Overview Edit Mode.

- **To close the Edit Area for an open audio clip, press [Esc].**
  Alternatively, click the Close button in the Edit Area:




Editing audio in Slice Edit mode

! **If you plan to comp the audio in your clips in Comp Edit mode, always do that before you start to work with slice stretching etc. in Slice Edit mode. It will save you a lot of work if all the comping has been done beforehand!**


! **To get the best sound quality when you are stretching and quantizing audio it's important that you have selected the correct Stretch Type for the audio clip, see "Selecting Stretch and Transpose Type".**

▶ **In the Audio Overview Edit Mode, click the Slice Edit button below the Edit Area Inspector:**



Audio clip elements in Slice Edit mode

When you have clicked the Slice Edit button, the audio clip could look something like this:



A Single Take clip open in Slice Edit mode.

▶ **You might have to zoom in quite a bit on the clip to get a good view of the Slices, see "Zooming in the Sequencer".**

- **Slice Markers with handles**
  When a Single Take audio clip is opened in Slice Edit mode, Reason automatically detects the transients in the sound and marks these with vertical white lines - Slice Markers. By moving Slice Markers left or right you stretch (warp) the audio between the nearest Slice Markers on either side, i.e. you change the timing without affecting the pitch. You can manually add and remove Slice Markers. It is also possible to "decouple" and move the Slice Markers without stretching the audio.
- **Slices**
  Slices are the areas between two adjacent Slice Markers. Each slice represents a part of the audio in the clip.


Slice Edit mode tools

When editing audio in Slice Edit mode, some of the Toolbar tools have different functionality than when editing note and automation clips. There are also some additional tools that are unique to slice editing of audio.

Speaker Tool

It's possible to audition individual Slices without needing to start playback of the sequencer:

- **Select the Speaker Tool in the Toolbar and click in the waveform area on the Slice you want to audition.**



The Slice is played back once in its entirety, from the start Slice Marker to the end Slice Marker of the desired Slice, each time you click.


- **With the Selection Tool (Arrow) selected, pressing [Alt](Win) or [Cmd](Mac) will momentarily switch to the Speaker Tool.**

! **Note that auditioning Slices will play back the unprocessed sound - bypassing the Main Mixer settings.**

Selecting Slices and Slice Markers

A Slice is the portion of audio between two adjacent Slice Markers. A Slice Marker indicates the beginning of a Slice - and consequently the end of the preceding Slice (if it's not the first Slice in the clip).

- **To select a Slice Marker, click the Slice Marker or its handle:**




As you hover over a Slice Marker or a Slice Marker Handle, the arrow switches to a double-arrow. A selected Slice Marker is indicated by a black Slice Marker Handle.

- **To select several individual Slice Markers, hold down [Ctrl](Win)/[Shift](Mac) and click the desired Slice Markers or their handles.**




If more than one Slice Marker has been selected, a Slice Group Handle appears below the waveform. You could then click and drag the Slice Group Handle sideways to move all selected Slice Markers as a group, see "Moving several Slice Markers".

- **To select a range of Slice Markers, draw a rectangle with the Selection Tool (Arrow), in the Slice Marker Handles area or in the waveform area, that touches the desired Slice Markers:**



Draw a rectangle over the desired Slice Markers to select a complete range.



As you release the mouse button all touched Slice Markers are selected.

The range of Slice Markers can then be moved as a group by clicking and dragging the Slice Group Handle sideways. You can also stretch the range in an "accordion style" fashion by clicking and dragging any of the selected Slice Marker Handles in the range, see "Stretching a range of Slices".

- **Under Windows it's also possible to select a range of Slice Markers by clicking a Slice Marker and then holding down [Shift] and clicking the first or last Slice Marker in the desired range.**
- **You can expand a Slice/Slice Marker selection range by holding [Shift] and pressing the left/right arrow keys.**
- **To select all Slices/Slice Markers in the clip, select "Select All" from the clip's context menu or from the Edit Menu.** Now, you can move all Slice Markers as a group by dragging the Slice Group Handle sideways (see "Moving several Slice Markers"), or stretch the entire range of Slices (see "Stretching a range of Slices").

Adding Slice Markers

When you open a Single Take clip in Slice Edit mode, there will be a Slice Marker at each transient, plus one at the start and one at the end of the clip. If you are not satisfied with Reason's automatic Slice Marker assignments you can add Slice Markers manually:

! **You might want to turn off Snap to be able to position the Slice Markers more precisely (see "Snap").**

1. **Open the Single Take clip for editing in Slice Edit mode.**
2. **Select the Pencil Tool from the Toolbar.**
3. **Click in the open clip to add new Slice Markers.**
   If you are not satisfied with the position of the Slice Marker, you can reposition it afterwards, see "Repositioning Slice Markers".

! **You cannot add Slice Markers before the first Slice Marker or after the end Slice Marker in the clip.**

Deleting Slice Markers

To delete Slice Markers, proceed as follows:

1. **Select the desired Slice Marker(s) as described in "Selecting Slices and Slice Markers".**
2. **Press [Delete] or [Backspace] to delete the marked Slice Makers.**
   This deletes the Slice Markers but not the audio that's in the clip.

! **If you delete Slice Markers that were previously moved, the stretched audio will revert to the original timing.**

! **You cannot delete the first Slice Marker or the end Slice Marker in the clip.**

Repositioning Slice Markers

To reposition a Slice Marker without stretching the audio, proceed as follows:

! **You might want to turn off Snap to be able to position the Slice Marker more precisely (see "Snap").**

1. **Place the Selection Tool (Arrow) on a Slice Marker or Slice Marker Handle.**
   The arrow switches to a double-arrow symbol.
2. **Hold down [Ctrl](Win) or [Option](Mac) and click and move the Slice Marker sideways.**

! **You cannot move Slice Markers past their closest adjacent Slice Markers.**

Moving/stretching Slices

Stretching can be used for adjusting the timing of the transients in the audio clip. You can also use stretching to create special effects such as increasing or decreasing the lengths of the Slices. Stretching can be applied on single Slices as well as on a selection of Slices.

! **To get the best sound quality when you are stretching audio it's important that you have selected the correct Stretch and Transpose Type for the audio track, see "Opening audio clips for editing".**

! **You might want to turn off Snap to be able to position the Slice Marker more precisely (see "Snap").**

! **You cannot move Slice Markers past their closest adjacent Slice Markers.**

Preview vs. High Quality Stretching

Reason features very sophisticated audio stretch and transpose algorithms for pristine results. Reason always performs audio stretching in two parallel steps:

- **A real-time "preview" stretch so that you can instantly hear the result of your changes.**
- **A high quality stretch "in the background" to further improve the sonic results.**
  As soon as high quality stretch is in progress, the "Calc" indicator on the Transport Panel shows a progress meter:



The CALC progress meter appears when Reason performs high quality stretching of audio.

Since the high quality stretch is performed in the background, you can still continue to work with your song without any interruption. When the high quality stretch data has been calculated, the Calc indicator goes out and the high quality audio data will be heard on playback.


Moving a Slice Marker

▶ **To adjust the timing of a single note or beat, just click and drag its Slice Marker to the desired position.**
If Snap is on, the Slice Marker will snap to the grid as set with the Snap value. When you move a Slice Marker, the slices on either side of it will be stretched accordingly.

Moving several Slice Markers

If you need to adjust the timing of several notes or beats (e.g. move all snare hits a little later in the beat), proceed as follows:

1. **Select the desired Slice Markers as described in "Selecting Slices and Slice Markers".**
2. **Click and drag the Slice Group Handle to move all selected Slice Markers.**
   As you hover over the Slice Group Handle, the arrow switches to a double-arrow



All selected Slice Markers will be moved as a group. The Slices between the selected Slice Markers and their closest unselected Slice Markers will be stretched.

▪ **It's also possible to move a range of Slices by selecting a range of Slice Markers as described in "Selecting Slices and Slice Markers" and then dragging the Slice Group Handle sideways.**
This is useful if you want to move a whole phrase (e.g. a vocal phrase) later or earlier in the clip.


! **You cannot move the selection past any unselected Slice Markers.**

Stretching a range of Slices


It is also possible to stretch a range of Slices, proportionally, in an "accordion style" fashion:

1. **Select the desired range of Slice Markers as described in "Selecting Slices and Slice Markers".**
   The range is indicated by a light gray Stretch Range Marker above the waveform.

▶ **If you drag the start or end Slice Marker in the range, the whole range will be stretched as if it were a single slice:**



▶ **If you drag a Slice Marker within the selected range, all selected Slices will be stretched proportionally against the start and end Slice Markers of the selected range:**



Nudging Slices

You can nudge the Slice Marker(s) by using the following standard key commands:

- **Hold down [Ctrl](Win) or [Cmd](Mac) and press the left/right arrow keys to nudge in Snap value steps.**
- **Hold down [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) to nudge in Beat steps.**
- **Hold down [Ctrl]+[Alt](Win) or [Cmd]+[Option](Mac) to nudge in Ticks steps.**

Quantizing audio

Audio quantizing can be made in the Quantize section on the Transport Panel, in the Edit Area Inspector, or from the context menu or Edit menu.

! **Audio can only be quantized after recording, not during recording.**

! **Quantize requires that the clips have Stretch enabled (see "Enable/Disable Stretch (Audio Clips")).**

! **To get the best sound quality when you are quantizing audio it's important that you have selected the correct Stretch Type for the audio clip, see "Opening audio clips for editing".**

! **Note that quantization of audio clips that have "Vocal" Stretch and Transpose Type is made on the pitch transitions (where the "notes" start) and not on the level transients as in Slice Edit mode, see "Editing audio in Vocal Edit mode".**


! **The difference between quantizing audio and MIDI notes is that several Slice Markers cannot be quantized to the same position. Instead, only the Slice Markers closest to the quantization grid will be moved - the remaining Slice Markers will be left unaffected.**

It's possible to use the quantize audio function in the following ways:

Quantizing selected Slice Marker(s) in Slice Edit mode


Quantizing Slice Markers has the same effect as moving the Slice Markers to a quantization grid:

1. **Select the Slice Markers you want to quantize:**



A range of Slice Markers selected for quantization.

2. **Select Quantize grid (and Amount and/or random Range values) in the Edit Area Inspector and click the Quantize (and/or Randomize buttons):**




The selected Slice Markers that are closest to the quantization grid are automatically moved to the quantization grid.

- **Note that you can quantize to "Shuffle" in the Value list - this will use the Global Shuffle setting made in the Re-Groove Mixer, see "Global Shuffle".**

▶ **Alternatively, select Quantize Value and click the Quantize button on the Transport Panel.**
This alternative is very handy if you only want to quantize to a set quantization value, and don't need the extra options featured in the Edit Area Inspector.

Quantizing one or several selected Single Take audio clips in the Arrange Area

1. **Select one or several Single Take audio clips on the Arrange pane.**
2. **Right click an audio clip and select "Quantize Setup...**



This brings up the Quantize Setup dialog, where you can set up the Quantize parameters, the same way as in Slice Edit mode.

Split at Slices

The Split at Slices function allows you to create separate audio clips out of a Single Take clip. Splitting can be useful if you, for example, want to reverse parts of the original clip or if you want to export single or multiple Slices as separate samples for use in any of Reason's sampler devices. The split point(s) will be located at the selected Slice Markers in the clip.

The following example shows how the "Split at Slices" function can be used:

1. **Select the split points for the new clips by selecting the desired Slice Markers in the open Single Take clip:**



The selected Slice Markers define the split points for the new clips.

2. **Select "Split at Slices" from the context menu or click the "Split at slices" button in the Edit Area Inspector.**



The original Single Take clip is now split into four separate audio clips (the picture shows the split clips in the Arrange Area).

If you like, you can now select the desired clip(s) and move, reverse (see "Reversing audio clips") or choose to bounce the clip(s) to samples (see "Bounce Clip(s) to New Sample(s)").

Bounce Clip to REX Loop

A great feature with Single Take clips is that you can bounce them to REX Loops. You could then load your bounced REX file for further processing in a Dr Octo Rex device, for example! Here is how:


1. **Open a Single Take clip in Slice Edit mode.**
2. **Make sure the Slice Markers are located exactly where you want them in the clip.**
This is where the slices in the REX Loop will appear after bouncing.

▶ **You might have to remove some Slice Markers in the clip to reduce the number of slices in the final REX Loop, see "Deleting Slice Markers".**

3. **Adjust the audio clip length to the closest full Beat.**
This way you make sure that the REX Loop will sound the same as the original audio clip.

! **If the clip is not adjusted to a full Beat, Reason will automatically expand the clip end to the closest full Beat during the bounce operation.**

4. **Select "Bounce > Bounce Clip to REX Loop" from the context menu or Edit menu.**
   The bounced REX file ends up in the "All Self-contained Samples" folder in the Song Samples location in the Browser, and is named after the original clip name:



5. **To load the bounced REX file in a new Dr Octo Rex device, select the REX file and click the "Create" button at the bottom of the Browser.**
   This is a shortcut for creating a Dr Octo Rex device and loading the selected REX Loop in Slot 1 of the Dr Octo Rex device in one go.

▶ **Refer to the "Dr. Octo Rex Loop Player" chapter for information on how to work with REX Loops in the Dr Octo Rex device.**

! **If you want to load your REX Loop in another sampler device, you first have to un-self-contain the REX file, see ""Un-self-containing" a Song". Then, create the sampler device and load the un-self-contained REX file from disk.**

About exporting bounced REX Loops to disk

You can also export your bounced REX Loops to disk if you like:

1. **Select the REX Loop in the Song Samples location in the Browser and select Export Sample(s) from the context menu.**
2. **Choose a location for the REX Loop (and change the file name, if desired).**
3. **Click Save.**
   The REX Loop is exported and saved in .rx2 format.

Revert All Slices

If you get lost in the Slice Edit mode editing, there is a handy command for reverting the Slice Markers back to where they were before you started editing the clip:

1. **Open the Single Take clip in Slice Edit mode.**
2. **Select "Revert All Slices" from the context menu or Edit menu - or click the "Revert. all slices" button in the Edit Area Inspector.**
   This will revert all slice edits and the clip will play back with its original timing. Any manually removed Slice Markers will reappear, and any manually added Slice Markers will be removed.

Closing Slice Edit mode

▶ **To close the Slice Edit mode and revert to the Audio Overview Edit mode, press [Esc] or click the Slice Edit Close button:**




Editing audio in Vocal Edit mode

In Vocal Edit mode you can correct and/or transpose the pitches of individual detected notes in monophonic recordings. Vocal Edit mode is developed especially for editing and correcting the pitches of vocal recordings. The audio pitch editing is made graphically in a way similar to other pitch correction/editing software on the market.

! **As soon as you open an audio clip in Vocal Edit mode, the Stretch and Transpose Type will be automatically set to "Vocal".**

Pitch Editor elements



A clip with a lead vocal stereo recording open in Vocal Edit mode.

The Pitch Editor contains the following elements:

- **Close button**
  Click this button to close the Vocal Edit mode and exit to Audio Overview Edit mode.
- **Clip Overview**
  The Clip Overview area at the top shows the clips on the selected audio track. In the Clip Overview area, selected audio clips are displayed in the same fashion as in the Arrange View, i.e. with Clip Resize handles. However, in Vocal Edit mode the Level handle and Fade handles are not available. You can select one or several audio clips in the Clip Overview and perform clip-based editing (e.g. moving and resizing) - just like in the Arrange View.
- **Clip Overview Divider**
  Drag this divider up/down to resize the Clip Overview vertically.
- **Note Level handle**
  With the Note Level handle you can adjust the level(s) of the selected note(s).
- **Note handle**
  Hold this and move sideways to move the note back or forth in time. The range is limited by the adjacent notes, which are indicated by the Note Lines, see "Moving notes and changing note lengths".
- **Note Lines**
  These indicate where the notes start and end. You can adjust the start/end positions by click-holding a Note Line and dragging it sideways. Changing the position(s) and/or length(s) will also automatically stretch the note(s). See "Moving notes and changing note lengths".

- **Drift handle**
  The Drift handle appears when you select the note(s). Drag the Drift handle downwards to reduce the amount of any natural pitch drift/vibrato present in the selected note(s), see "Attenuating pitch drift/vibrato".
- **Transition handle**
  The Transition handle(s) control the pitch transition times between the selected note(s) and the previous adjacent note(s), see "Editing transition times".
- **Correct Pitch button**
  The Correct button transposes all selected notes to their nearest exact semitone. If no note is selected, the Correct function corrects all notes in the open audio clip.
- **Reset to Original Pitch button**
  The Reset button removes any transposition/pitch correction changes you have made for all selected notes. If no note is selected the Reset function resets the pitches of all notes in the audio clip.
- **Transpose mode buttons**
  This is a three-way switch that determines what happens when you drag notes up/down on the note pane:
  Snap = the notes snap to absolute semitones.
  Jump (default) = the notes snap relative to their original pitches, i.e. moves in semitone steps but preserves any fine tuning.
  Fine = the notes can be transposed freely, in cents.
  See "Changing transposition" for more details about transposing notes.
- **Monitor button**
  With the Monitor button on, you will hear the pitch of a note as a continuous reference tone, when you click the note and hold the mouse button depressed. The reference tone changes pitch when you drag the note up/down on the note pane. The reference tone reflects the pitch+fine-tune setting of the note. It doesn't matter where in the note you click.
- **Reference Keyboard**
  The Reference Keyboard is there as a visual guide for the notes on the note pane.

Selecting notes

Selecting notes in Vocal Edit mode can be done as follows:

- ▶ **Click a note on the note pane, or on the note's corresponding section in the clip overview.**
- ▶ **You can also select one or several notes by dragging a selection rectangle on the note pane,**
- ▶ **Select all notes on the note pane by selecting "Select All" from the Edit menu or context menu.**
- ▶ **Click anywhere on the note pane background to deselect the note(s).**

Auditioning notes

It's possible to audition individual notes without needing to start playback of the sequencer:

- ▶ **Select the Speaker Tool in the Toolbar and click on the desired note, or its corresponding section in the clip overview.**
  Each time you click, the note is played back once in its entirety.
- ▶ **With the Selection Tool (Arrow) selected, pressing [Alt](Win) or [Cmd](Mac) will momentarily switch to the Speaker Tool.**

! **Note that auditioning notes plays back the unprocessed audio - bypassing the Main Mixer settings.**

Correcting pitches

1. **Select the note(s) you want to pitch-correct. If no note is selected, all notes will be affected by the pitch correction.**
2. **Click the "Correct Pitch" button in the Edit Area Inspector.**
   The Correct function moves all selected notes to their nearest exact note pitch.

- **Alternatively, hold down [Shift]+[Ctrl](Win) or [Shift]+[Cmd](Mac) and press [C].**
- **To undo the pitch correction and revert to the original pitch(es), click the "Reset to Original Pitch" button.**
  If no note is selected, the Reset function will reset the pitches of all corrected (and transposed) notes in the clip!

Changing transposition

1. **Select the note(s) you want to transpose.**
2. **Click and drag the note(s) up/down on the note pane to transpose.**
   The Transpose buttons to the left of the note pane determine how the notes will be transposed:

   Snap = the notes will snap to absolute semitones.

   Jump (default) = the notes will snap relative to their original pitches, i.e. move in semitone steps but preserves any fine tuning.

   Fine = the notes will be transposed freely, in cents.

- **You can also fine-tune by holding down [Alt]+[Shift](Win) or [Cmd]+[Shift](Mac) while dragging the notes up/down on the note pane.**
- **If the Monitor button is on, a reference tone will play the pitch of the held note.**
- **To undo the transposition and revert to the original pitch(es), click the "Reset to Original Pitch" button.**
  If no note is selected, the Revert function will reset the pitches of all transposed (and pitch-corrected) notes in the clip!
- **Alternatively, you can edit the transposition numerically in the Edit Area Inspector, see "Note" and "Fine-tune".**

Resetting pitches

- **Click the Reset to Original Pitch button to reset any transposition and/or pitch correction and revert to the original pitch(es) of the selected note(s).**
  If no note is selected, the Reset function will reset the pitches of all transposed and pitch-corrected notes in the open audio clip!

Splitting the clip at notes

It's possible to split an audio clip at the edges of selected notes in Vocal Edit mode (similar to splitting at slices in Slice Edit mode):

- **Select the note(s) where you want to split the clip and then select "Split at Notes" from the Edit menu or context menu.**

Reverting all notes


It's possible to "undo" all edits you have made in Vocal Edit mode (similar to the "Revert Slices" function in Slice Edit mode):

- **Select "Revert All Notes" from the Edit menu or context menu.**
  The clip will be completely re-analyzed and any pitch, timing and timbre edits will revert to the original.

Attenuating pitch drift/vibrato

You can attenuate the pitch drift or vibrato for each note individually:

1. **Select the note(s) you want to change the pitch drift/vibrato for.**
2. **Lower the Drift handle to "straighten out" the pitch curve in the note, removing large scale pitch drift.**
   The default setting is always 100%, which means you can only attenuate the pitch drift/vibrato - not increase it.



- **Alternatively, you can edit the Drift numerically in the Edit Area Inspector, see "Drift".**
- **If you want to preserve small pitch fluctuations in the note, you can use the Preserve Expression parameter in the Inspector, see "Preserve".**


Editing transition times

When you have recorded your audio and haven't (yet) made any pitch changes (transpositions) of notes, editing the transition times won't have any effect at all.

! **It's only after you have edited note pitches (moved notes up/down on the note pane) that editing transition times will have any effect.**

You can edit the pitch transition times between transposed notes as follows:

1. **Select the note(s) you want to change the transition time(s) for.**
2. **Drag the Transition handle(s) up/down to control the pitch transition between the selected note(s) and the previous adjacent note(s).**
   The important thing here is to get a smooth pitch curve (the line) from the preceding note to the following note. Adjust the Transition handle until the pitch curve is a smooth line between the notes. The dark blue colored transition zones in the notes themselves indicate the transition times. The Transition times can be max 200 ms - or half of the note length (if the note length is less than 400 ms).




- **Alternatively, you can edit the Transition times numerically in the Edit Area Inspector, see "Transition".**
- **To get the best result when editing transition times you might also have to change the actual note positions without moving/stretching the audio, see "Changing note start positions (without affecting the audio)".**

Moving notes and changing note lengths

Moving notes

To move a note back or forth in time, proceed as follows:

1. **Select the note(s) you want to move.**
2. **Click and hold the Note handle in the Clip Overview and drag sideways.**
   The closest adjacent notes will then be stretched.
   You may want to deactivate the Snap function if you want to fine-adjust the note position(s).




- **Alternatively, you can move the note(s) numerically in the Edit Area Inspector, see "Position".**
- **If you want to change the note start position(s) and/or note lengths, see "Changing note start positions and lengths".**

Changing note start positions and lengths

To change note lengths, and thus stretch the note(s), proceed as follows:


1. **Select the note(s) you want to adjust.**
2. **Click and hold the desired Note line, on the note pane or in the Clip Overview, and drag sideways.**
   Adjusting the length of a note automatically changes the start position of the consecutive note - and vice versa. You may want to deactivate the Snap function if you want to fine-adjust the note(s).



Changing note start positions (without affecting the audio)

Similar to when editing in Slice Edit mode it's possible to "decouple" the notes from the actual audio in the note. This can be useful if the automatic note placement wasn't perfect and you have a hard time adjusting the transition times between transposed notes (see "Editing transition times").

- **Hold down [Ctrl](Win) or [Option](Mac) and drag the note line sideways to change the note start/length without affecting the audio.**




You may want to deactivate the Snap function if you want to adjust the note start position with greater precision. As you can see in the picture above, the pitch curve is left unaffected (unstretched) and only the note start/length is affected.

Proportional stretching of multiple notes

Like in Slice Edit mode it's possible stretch a range of notes, proportionally, in an "accordion style" fashion:

1. **Select the desired consecutive range of Notes on the Note pane.**

- **If you drag the start or end Note line in the range, the whole range will be stretched as if it were a single note:**




- **If you drag a Note line within the selected range, all selected notes will be stretched proportionally against the start and end Note lines of the selected range.**

Splitting and joining notes

Splitting notes

To split a note, proceed as follows:

1. **Select the Razor tool from the Toolbar.**
2. **Click on a note where you want to split it, or click in the Clip Overview at the desired split position.**
   You may want to deactivate the Snap function if you want to split the note with more precision.




The two halves of the note are now re-analyzed and placed in suitable pitch positions of the note range. This could mean that the new notes are placed differently than the original note.

Joining notes

To join notes, proceed as follows:

1. **Select the Eraser tool from the Toolbar.**
2. **Click on a note that you want to join with the preceding note, or click in the corresponding section in the Clip Overview.**



The new "joint" note is now re-analyzed and placed on the suitable pitch position in the note range. This could mean that the new note is placed differently than the original notes.

- ▶ **To join several notes in one go, draw a selection rectangle with the Eraser tool and then release the mouse button.**
  The result will be one long note, re-analyzed and placed on the most suitable pitch position in the note range.


About switching from Vocal Edit mode to Slice Edit mode

- ! **When you have edited an audio clip in Vocal Edit mode and then switch to Slice Edit mode (with the "Vocal" Stretch and Transpose Type still selected), the slices are now based on the note transitions from Vocal Edit mode, and not on the level transients.**

Audio pitch editing in the Edit Area Inspector

In Vocal Edit mode a series of additional audio pitch editing boxes appear in the Edit Area Inspector. These are unique to the Vocal Edit mode and apply to selected notes on the note pane.

▶ **Click the small triangular buttons to expand the Position and Fine-tune sections:**



The Inspector elements for a selected note in Vocal Edit mode.

Position

Here you can edit the start position of the note in Bars, Beats, 1/16th notes and Ticks.

Quantize

Quantizing notes in Vocal Edit mode works just like when quantizing in Slice Edit mode, see "Quantizing audio".

! **Note, though, that the quantization is made on the pitch transitions (where the notes start) and not on the level transients as in Slice Edit mode.**

Randomize

Randomizing note starts in Vocal Edit mode works just like when randomizing in Slice Edit mode, see "Quantizing audio".

! **Note, though, that the randomization is made on the pitch transitions (where the notes start) and not on the level transients as in Slice Edit mode.**

Note

Here you can set the note value to transpose to, in semitone steps. If the note has a Fine-tune setting, this will be preserved also after the semitone Note transposition.

Fine-tune

Here you can detune the note up/down in steps of 1 cent. If you fine-tune more than +/- 50 cents, the Note value will change and the fine-tuning will now be based on the new Note value instead. This way you will be able to use the Fine-tune function throughout the entire MIDI note range.

Drift

Here you can attenuate the pitch drift/vibrato of the audio in the note. The default 100% keeps the pitch drift/vibrato unaffected, and at 0% the audio in the note doesn't contain any pitch drift/vibrato at all.

Preserve

The Preserve Expression function works in tandem with the Drift function. If you raise the Preserve Expression value, small pitch fluctuations (vibrato and other expressions) are maintained even when you "straighten out" the note by lowering the Drift value.

Transition

This controls the pitch transition time between the selected note and the preceding note.

There are dark blue colored transition zones in the notes themselves, which changes according to your edits. The Transition times can be max 200 ms - or half the note length (if the note length is less than 400 ms).

Formant

Here you can edit the formant "position" of the selected note(s). Changing the Formant downwards creates a deeper tone and changing it upwards generates a brighter tone to the vocals.

Range +/-1 octave, in steps of 0.01 semitones.

For more information about formants, please have a look at "What are formants?" in the Neptune Pitch Adjuster and Voice Synth chapter.

Level

Here you can change the level of the selected note(s). The range is -70 dB to +18 dB.



Editing audio in the Comp Editor

In this section we will describe audio editing procedures that are common for Single Take clips and Comp clips when edited in the Comp Editor. Comp clip specific procedures are described in "Comping audio".


Audio clip elements in the Comp Editor

When an audio clip is open for editing in Comp Edit mode, its contents are shown on the Edit Pane below the Clip Overview area. An open audio clip can have one or several Comp Rows on which the audio recordings reside. The number of Comp Rows depends on how you recorded your audio clip. If you only recorded once in the clip, there will only be one single Comp Row. If you have recorded several times in the same clip, or several cycles in Loop Mode, there will be one Comp Row for each take, or cycle.

There are vertical zoom controls for resizing the Clip Overview area and the Comp Row area. You can also scroll in the Comp Row area by using the scroll bars on the right hand side of the Edit Pane.

Single Take clips in the Comp Editor

For Single Take clips, only the recording on the selected Comp Row is played back. If there is only one single Take (Comp Row) in the clip, this will play back by default. This is how an open Single Take clip with only one recording on one Comp Row could look like when opened in Comp Edit mode:



A Single Take clip open in the Comp Editor.


- **Clip Overview**
  The Clip Overview area at the top shows the clips on the selected audio track. In the Clip Overview area, selected audio clips are displayed in the same fashion as in the Arrange View, i.e. with Clip Resize handles, Level handle and Fade handles. You can select one or several audio clips in the Clip Overview and perform clip-based editing (e.g. moving and resizing) - just like in the Arrange View.
- **Clip Overview Divider**
  Drag this divider up/down to resize the Clip Overview vertically.

- **Fade In and Fade Out handles**
  Click and drag these handles horizontally to introduce a fade in and/or fade out of the audio in the clip. The fading is non-destructive and can be changed at any time. If Snap is activated in the Edit Area, the set (Edit Area) Snap value is taken into account when moving the Fade Handles.
- **Clip Level handle**
  Click and drag this handle vertically to adjust the audio level of the recordings in the clip. The level adjustment is non-destructive and can be changed at any time.
- **Comp Row**
  Depending on how you recorded the audio clip, there can be one or several Comp Rows, containing one audio recording each. Comp Rows can be described as "virtual tracks" in the sense that you can have many parallel Comp Rows in an audio clip but only play back from one Comp Row at a time (see "Creating a comped audio clip"). In Single Take clips, only the audio recording on the currently selected Comp Row will play back.
- **Comp Row handle**
  If there are several Comp Rows in the audio clip, it's possible to rearrange the order of the Comp Rows by clicking and dragging the Comp Row handles vertically.
- **Comp Row Level fader**
  Use the Comp Row Level fader to adjust the volume of the recording on the corresponding Comp Row. This is especially useful in Comp Mode, when you want to trim and balance the levels of the recordings on several Comp Rows.
- **Single Take Mode button**
  Click this to manually select the desired Comp Row for playback - and thus set the clip to Single Take Mode.

! **If the clip only has one single Comp Row, this is automatically selected "in the background" by default - i.e. its Single Take Mode button is not depressed.**

Comp clips in the Comp Editor

A Comp clip consists of several Comp Rows, with one recording on each Comp Row. If you have recorded several takes in an audio clip and want to cut out sections of the various takes and comp into a final clip, this can be done in the Comp Editor (see "Creating a comped audio clip"). This is how an already comped audio clip could look like in Comp Edit mode:



A Comp clip open in the Comp Editor.


From the top down in the preceding picture, the Edit Pane contains the following elements:

- **Vertical Zoom buttons**
  Click these to increase/decrease the Comp Row heights
- **Cut Row**
  The area between the Clip Overview and the topmost Comp Row is called the Cut Row. This is where the Cut Handles are placed.
- **Segment Focus Indicator**
  The gray Segment Focus Indicator appears if you click on the Cut Row, or if you double-click on a Comp Row. A Segment is the area between two Cuts. The Segment Focus Indicator shows which segment currently has edit focus. Edit focus is required for editing using keyboard short-cuts (see the "Keyboard Commands" pdf document).
- **Cut Crossfade Zones**
  When you have comped an audio clip by creating cuts and assigning different Comp Rows to the resulting segments, it's possible to set individual crossfades between the segments. This makes it possible to get smooth transitions between the audio recordings in the different segments. Any crossfades are indicated by boxes. The widths of the boxes indicate the crossfade times.
- **Clip Overview Divider**
  Drag this divider up/down to resize the Clip Overview vertically.


- **Cut Handles and Cut Lines**
  Each cut in a comped audio clip is indicated by a Cut Handle and a Cut Line. The Cuts indicate where the playback changes from one segment to another (in most situations from one Comp Row to another). You can edit the Cut positions by clicking and dragging any of the Cut Handles or Cut Lines sideways.
- **Silence Row**
  The Silence Row can be used for inserting silent segments in the comped audio clip, e.g. for removing breath noise between vocal phrases.
- **Comp Rows**
  All of your audio recordings reside on Comp Rows. Depending on how you recorded the audio clip, there might be one or several Comp Rows, each containing one audio recording. The most recent take is on the topmost Comp Row. In a Comp clip, the colored part(s) of each Comp Row (or Silence Row) will play back. All Comp Rows used in the clip have colored Comp Row Handles. Any unused Comp Rows in the clip are indicated by gray Comp Row Handles.

The relationship between Clips, Comp Rows and Recordings

In the Comp Editor, the contents of an open clip are displayed on the Comp Row(s) on the Edit Pane:




A Single Take clip with four Comp Rows, with the topmost Comp Row manually selected for playback.




A Comp clip with alternating playback from four Comp Rows.

- **A recorded audio clip, or an audio clip containing imported audio, can consist of one or several Comp Rows.** The number of Comp Rows and their position can be unique for each individual audio clip. Any edits you make in an audio clip will never interfere with other clips in the Song.
- **On each Comp Row there is one single Recording, i.e. the audio that you have recorded or imported.** If the clip was recorded in one single take, it will have a single Comp Row. If the clip was recorded in several takes one after another, or recorded in Loop Mode, it will contain one Comp Row for each take or loop. Also, if you imported audio files to a clip, each audio file will end up on a separate Comp Row.

- **Only one Comp Row can play back at a time.**
  In a Single Take clip with more than one Comp Row, only the Comp Row you have selected by clicking the Single Take Mode button will play back. In a Comp clip, you can alternate the playback between the Comp Rows by assigning regions of the different Comp Rows to different Segments in the Clip. What you hear when you play back an audio clip is displayed in the Clip Overview area at the top on the Edit Pane. (The Clip Overview area displays the same content as the clip in the Arrange View.)



A Single Take clip with four Comp Rows, with the topmost Comp Row manually selected for playback.



A Comp clip with alternating playback from three Comp Rows plus the Silence Row.

- **The Comp Row configuration, and the Recordings on the Comp Rows, are unique to each individual audio clip.**
  This means that you could move Comp Rows up or down on the Edit Pane, change Comp Row Levels and Crossfades, or move Recordings back and forth on the Comp Rows, without affecting any neighboring audio clips.
- **If you duplicate a Clip, or a Comp Row with its Recording, you can freely edit the duplicated Clip, Comp Row or Recording without affecting the original.**
  However, the actual audio data is not duplicated. Reason features a very sophisticated internal audio management system which re-uses Recordings throughout the entire Song whenever necessary. This means that the Song file size won't increase when you duplicate audio clips or Comp Rows.

Comp Editor window handling

Resizing, zooming and scrolling

- **Use the Zoom/Scroll Tool in the Zoom/Scroll area in the Timeline to zoom and scroll horizontally, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".**
- **Click the Zoom buttons to the upper left of the Comp Edit pane to zoom in and out vertically (see "Windows, areas and basic navigation").**
- **The Magnifying Glass tool can be used for zooming in and out (see "Magnifying Glass Tool").**
- **The Hand tool can be used for scrolling the view in any direction (see "Hand Tool").**
- **For extensive editing, you may want to maximize the Sequencer and/or detach the Main Mixer and Rack so that the sequencer covers the entire computer screen. Refer to "Windows, areas and basic navigation".**


Comp Editor audio editing tools

When editing audio in the Comp Editor, some of the Toolbar tools have different functionality as when editing note and automation clips. There are also some additional tools that are unique to audio editing.

Razor (Cut) Tool

When editing audio in the Comp Editor, the Razor Tool on the sequencer Toolbar is used for creating Cuts. When you place the Razor Tool over the Comp Rows, Silence Row or Cut Row, it changes into a "Cut Tool".

- **With the Selection Tool selected, hold down [Alt](Win) or [Cmd](Mac) to temporarily switch to the Cut Tool.**
- **Click with the Razor Tool on a Comp Row to assign the recording to the right of the cursor to a new Segment.**



Assigning the recording on the "Take4" Comp Row to a new segment.


See "Adding Cuts" for more details on how to use the Cut Tool.

The Razor Tool can also be used for assigning a complete Segment, with a start and end Cut, by clicking and dragging (swiping) the Razor Tool horizontally on the desired Comp Row. See "Adding Segments" for more details on how to swipe with the Cut Tool.

Speaker Tool

It's possible to audition individual recordings on Comp Rows, without needing to start playback of the sequencer. This is very useful when you're going to select what Comp Rows to use in the clip:

1. **Make sure the Speaker Tool is selected and place the cursor at the position on the Comp Row you would like to audition.**
   The cursor switches to a speaker symbol with crosshairs next to it.



Auditioning a recording on a Comp Row.

2. **Click and hold the mouse button depressed for as long as you want to listen.**
   The playback starts at the current crosshairs position and proceeds for as long as you keep the mouse button depressed. The playback position is indicated by a vertical moving line on the auditioned Comp Row.


▶ **With the Selection Tool (Arrow) selected, holding down [Alt]+[Shift](Win) or [Cmd]+[Shift](Mac) will switch to the Speaker Tool.**

! **Note that auditioning recordings on Comp Rows will play back the unprocessed sound of the recording - bypassing any settings in the Main Mixer.**

▶ **Using the Speaker Tool, it's possible to audition recordings anywhere on any Comp Rows. The Comp Row doesn't have to be selected - it's even possible to audition recordings on masked Comp Row segments.**

Selecting a Comp Row for playback in a Single Take clip


In a Single Take clip, only the selected Comp Row will play back throughout the entire clip length. It's also possible to change Comp Row Levels and Recording Offsets in a Single Take clip. The picture below shows an open Single Take clip in the Comp Editor. The clip consists of four separate takes, each on a separate Comp Row. When played back, the recording on the selected "Take 4" Comp Row will play back:



A Single Take clip open in the Comp Editor with four recorded takes.

If you want to change which Comp Row should play back in a Single Take clip:

- **Click the Single Take Mode button for the Comp Row you want to play back.**




The "Take 2" Comp Row is now manually selected for playback throughout the clip.

Now, the "Take 2" Comp Row will play back instead when the sequencer is started.

Selecting Comp Rows

- **To select a Comp Row, e.g. for moving, cutting, copying, duplication or deletion, click (don't double-click!) with the Selection Tool anywhere on the Comp Row, or on the Comp Row Handle.**
  The selected Comp Row is shown in a darker color:



The selected Comp Row is shown in a darker color.

- **Select multiple Comp Rows by holding down [Ctrl](Win) or [Cmd](Mac) and clicking with the Selection Tool.**
- **Select a range of Comp Rows by holding down [Shift] and clicking with the Selection Tool on the first and last Comp Row in the desired range.**

! **Don't double-click on a Comp Row to select it. Double-clicking on a Comp Row will automatically assign the recording on it to the segment at the current click position.**


Deleting Comp Rows

- **Select one or several Comp Rows (see "Selecting Comp Rows") and then press [Backspace] or [Delete], or select "Delete" from the Edit menu or context menu.**
- **Alternatively, select the Eraser Tool and click anywhere on the Comp Row you wish to delete.**

Moving Comp Rows

Moving Comp Rows up or down on the Edit Pane can be useful to make it faster and easier and to access the desired Comp Rows when editing a comped clip. Let's say you have recorded six takes but you're only going to edit takes 1, 3 and 5. In this case, it would be more practical to have these Comp Rows right below one another at the top of the Edit Pane.

- **To move a single Comp Row up or down, click and hold the Comp Row Handle and drag vertically.**
  A red insertion line is shown, indicating where the Comp Row will be placed after you release the mouse button.



Moving a Comp Row.

- **To move several Comp Rows in one go, select them and then click and hold one of the selected Comp Row Handles and drag to the new destination.**
  A red insertion line is shown, indicating where the Comp Rows will be placed after you release the mouse button. Note that if you move non-adjacent Comp Rows, they will be placed as a group (adjacent) on the Edit Pane.
- **To move Comp Rows between clips, use the cut/copy and paste functions described in "Cutting, copying and pasting Comp Rows".**
- **Moving Comp Rows sideways is the same as changing the Recording Offsets - see "Adjusting the Recording Offset" for more details.**

Duplicating Comp Rows

Duplicating Comp Rows can be useful if you want to re-use the same part of a take several times in a comped clip. Duplicate the Comp Row and then adjust the Recording Offset (see "Adjusting the Recording Offset") in the duplicated Comp Row to access the same part of the recording in another segment of the comped clip. Duplicating Comp Rows will not use up any more space on your hard disk, so you can do this as many times as you like.

- **To duplicate one or several Comp Rows, select them and hold [Ctrl](Win) or [Cmd](Mac) and press [D], or select "Duplicate Comp Rows" from the Edit menu or context menu.**
  The duplicated Comp Rows will be placed below the lowest selected Comp Row. Note that if you duplicate non-adjacent Comp Rows, they will be placed as a group (adjacent) below the lowest selected Comp Row.
- **You can also duplicate a Comp Row and assign the duplicated Comp Row to a new segment in one go. With the Razor (Cut) Tool selected, hold down [Ctrl](Win) or [Option](Mac) and click, or swipe, on a Comp Row to assign a new segment to a duplicate of the recording on a new, additional Comp Row.**

Cutting, copying and pasting Comp Rows

To move recordings between clips, you can cut or copy and paste Comp Rows as follows:


1. **Select one or several Comp Rows and then hold [Ctrl](Win) or [Cmd](Mac) and press [X] to cut or [C] to copy the Comp Rows to the clipboard memory.**
   Alternatively, select "Cut" or "Copy" from the Edit menu or context menu.
2. **Open the audio clip into which you want to paste the Comp Row(s).**
   This can be in the same song or a different one.
3. **To paste the cut or copied Comp Rows, hold down [Ctrl](Win) or [Cmd](Mac) and press [V] - or select "Paste" from the Edit menu or context menu.**
   The pasted Comp Rows will be placed at the top of the Edit Pane. Note that if you paste non-adjacent Comp Rows, they will be placed below each other, starting at the top of the Edit Pane.

! **If you paste Comp Rows into another song, the actual audio recordings will be added to that song as well and consequently increase the file size.**

Adjusting the Comp Row Level

If you are comping different Takes where the levels differ a bit, you might want to adjust the levels individually for the Takes:

1. **Click on a Comp Row to select it.**
   The Comp Row is displayed in a darker color to indicate it's selected.
2. **Adjust the level, either by clicking and dragging the Comp Row Level Fader, or by adjusting it in the Level (dB) display in the Edit Area Inspector.**
   The Level (dB) display is divided into dB and 1/100th of a dB.



Adjusting the audio level of a recording on a Comp Row.


3. **Repeat the procedure for the other Comp Rows, if necessary.**

▶ **It's also possible to edit the entire Clip Level in the Comp Editor by clicking and dragging the Clip Level Handle in the Clip Overview.**
Any level adjustments you make on the Comp Row and in the Clip Overview are summed.

Adjusting the Recording Offset

In some situations you might want to move, or nudge, the entire recording on a Comp Row to make it play back exactly when you want. Maybe you just need to fine tune the position by a couple of Ticks:

1. **Click on the Comp Row to select it.**
2. **Either click and drag the recording horizontally, or adjust the position in the Recording Offset display in the Inspector.**
   The Recording Offset display is divided into Bars, Beats, 1/16th notes, Ticks and Subticks. There are 240 Ticks for each 1/16th note and 16 Subticks for each Tick.



The "Recording Offset" display shows the offset of the recording on the selected Comp Row relative to the Clip Position.

If you move the recording on the selected Comp Row back or forth, the Offset Display will update. Similarly, if you resize the Clip by changing its start position (left Clip Handle), the Offset Display will also update.

However, If you resize the clip using its right Clip Handle, or move the entire clip, all recordings on all Comp Rows will follow along and the Recording Offset will remain unaffected.

Adjusting the offset (position) of a recording on a Comp Row.

You can also nudge the Recording Offset of the selected recording by using the arrow keys on the keyboard.

- **To nudge the recording in Snap value steps, hold [Ctrl](Win) or [Cmd](Mac) and press the left/right arrow keys.**
  Note that Snap doesn't have to be activated for this to work.
- **To nudge the recording in steps of Ticks, hold [Ctrl]+[Alt](Win) or [Cmd]+[Opt](Mac) and press the left/right arrow keys.**
- **To nudge the recording in steps of Beats, hold [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and press the left/right arrow keys.**
- **To make it easier to find the exact positions in the recording, you can audition the recording at desired positions (see "Speaker Tool").**

Comping audio


In this section we will describe procedures that are specific to audio editing in Comp clips. At the end of this section is a detailed example on how to use the various procedures to create a complete comped audio clip - see "Creating a comped audio clip". General audio editing procedures are described in "Editing audio in the Comp Editor".

Adding Cuts

! **If the clip is in Single Take mode, because a Single Take Mode button is depressed, you will have to click that Single Take Mode button to deselect the Comp Row before you can start adding Cuts!**

! **If the clip only contains one single (not manually selected) Comp Row, and thus is a Single Take clip, adding a Cut on the Silence Row will automatically turn the clip into a Comp clip.**

▶ **Place the Razor Tool on the Comp Row which contains the recording you want to assign, and click.**
A new Cut Handle is added on the Cut Row. The recording to the right of the Cut Line on the Comp Row is assigned to a new Segment:



Assigning the recording on the "Take4" Comp Row to a new Segment.

▶ **Click with the Razor Tool on the Silence Row to assign silence to a new Segment to the right of the cursor.**

▶ **Click with the Razor Tool on the Cut Row to create a new Cut without changing the currently assigned recording.**
A new Cut Handle is added on the Cut Row. The previous recording assignment is retained throughout the new segment.

▪ **If you hold down [Ctrl](Win) or [Option](Mac) and click with the Razor tool on a Comp Row, this will first create a duplicate of the Comp Row. Then, the duplicated Comp Row will be assigned to the new Segment.**
You can then adjust the timing (Recording Offset) or level of the duplicated Comp Row as needed, without affecting any segments playing the original Comp Row.

! **Note that Snap is taken into account (if activated).**

▶ **A quick way to toggle Snap on or off is to press [S].**


▶ **For a practical example on how to add Cuts, see "Creating a comped audio clip".**

▶ **It's also possible to assign a complete Segment, with a start and end Cut, by swiping with the Cut Tool on the Comp Rows - see "Adding Segments".**


Adding Segments

The Razor Tool can be used for assigning a complete Segment, with a start and end Cut, by clicking and dragging (swiping) the Razor Tool horizontally on the desired Comp Row.

▶ **Swipe (click-hold and drag) with the Razor Tool to assign a part of a Comp Row to a new segment.**



Place the Razor Tool on the desired start position on a Comp Row and swipe...



...and release where you want the segment to end.

▶ **To insert a new Segment in an existing Segment, swipe with the Razor Tool on a Comp Row or on the Cut Row.** Swiping on a Comp Row will automatically assign the recording on that Comp Row to the new segment. Swiping on the Cut Row will insert a new segment but won't change the recording assignment. The result after inserting a new segment in an existing segment is three separate segments. Swiping over an existing Cut will remove that Cut.

▪ **If you hold down [Ctrl](Win) or [Option](Mac) and click or swipe with the Razor tool on a Comp Row, this will first create a duplicate of the Comp Row. Then, this duplicated Comp Row will be assigned to the new Segment.** You can then adjust the timing (Recording Offset) or level of the duplicated Comp Row as needed, without affecting any segments playing the original Comp Row.

! **Note that Snap is taken into account (if activated).**


▶ **A quick way to toggle Snap on or off is to press [S].**

▶ **For a practical example on how to add a Segment, see "Creating a comped audio clip".**


Adding Crossfades to Cuts

To add a crossfade zone to a Cut (between two Segments), proceed as follows:

▶ **Select a Cut Handle and then drag the Cut Crossfade Handle to the right.**



Click and drag the Cut Crossfade Handle...




...to introduce a crossfade between the segments.

The crossfade slopes are indicated by curves on the assigned Segments. The longer the crossfade time, the flatter the curves.

▶ **To remove a crossfade, simply drag the Cut Crossfade Handle all the way to the left.**

Deleting Cuts

- ▶ **To delete a Cut, click on the left Cut Handle and press [Backspace] or [Delete], or select "Delete" from the Edit menu or context menu.**
  The segment to the right of the deleted Cut will be deleted. The segment to the left of the deleted Cut will expand and replace the deleted segment:



Click on a Cut Handle to select it.


Press [Backspace] or [Delete] to delete the segment to the right of the Cut Handle.

- ▶ **Alternatively, select the Eraser Tool and click on the Cut Handle.**

Moving Cuts

Moving Cuts has a similar effect to resizing a clip, i.e. you select what part of the recording on the Comp Row should be active for playback. Recordings outside the active segment on the Comp Row will be masked (silent) but not affected in any other way.

- ▶ **To move a Cut, click and hold its right Cut Handle, or Cut Line, and drag it horizontally in either direction.**
  The segment to the left of the Cut Line will be resized. The segment to the right of the resized segment will now have a new start position:



Click on a Cut Handle to select it.


Drag the Cut Handle to horizontally to move it.

- ! **Recordings in the segments will not be moved back or forth - only masked according to the current positions of the Cut Handles/Lines. Any Cut Crossfades will also move along with the Cut Handles/Lines.**
- ! **Two Cuts can never exist on the same position. If you drag a Cut to the position of another Cut and release the mouse button, the moved Cut will disappear. If you do this by mistake, you can always use the Undo function.**
- ▶ **To move a Cut and have the recording on the Comp Row move along with the Cut, select the Comp Row and the Cut Handle using the standard [Ctrl]-click (Win) or [Shift]-click method. Then, click and drag the Cut to the desired position.**
- ! **Note that Snap is taken into account (if activated).**
- ▪ **It's also possible to use the Inspector to move Cuts numerically - see "Editing recordings and cuts in the Edit Area Inspector".**

Changing Comp Row assignments

When you have created a comped audio clip, you might later want to change which Comp Rows are assigned to play:

- **Choose the Selection Tool and double-click on the Comp Row that contains the recording you want to assign to the Segment.**
  Make sure you double-click in the area between the desired Segment's Cut Lines.




Double-click on the Comp Row you want to assign to the segment.

The segment will now play back this recording instead.

You can also use keyboard commands to change comp row assignments and segment focus as follows:

- **Hold down [Ctrl](Win) or [Cmd](Mac) and press the up/down arrow keys to select which Comp Row that should be assigned.**
- **To change Segment focus, hold down [Ctrl]+[Alt]+[Shift](Win) or [Cmd]+[Option]+[Shift](Mac) and press the left/right arrow keys.**
  This will move the Segment Focus Indicator between the segments. Note that you can still change comp row assignments using this keyboard command together with the up/down arrow keys.




The Segment Focus Indicator shows which segment has currently focus.

Bounce Clip(s) to New Recording(s)

A very nice way to "clean up" among the recordings in a comped audio clip is to bounce the clip to a new recording. Bouncing to a new recording is also a prerequisite to be able to edit the clip in Slice Edit mode and stretch and quantize the audio.


What happens is that the audio recordings in all segments of the comped clip, including any Cut Crossfades and individual Comp Row Levels, are combined into a single recording on an additional Comp Row. After the clip has been bounced to a new recording, you can delete the unused recordings to reduce the file size. Bouncing clips to new recordings can be made for one or several selected audio clips:

- **Select the clip(s) in the Clip Overview area in the Comp Editor and then click the Bounce button.**




Clicking the Bounce button will bounce the recordings of the comped clip to a new recording, automatically select the bounced recording's Comp Row - and thus set the clip type to Single Take. The same thing happens automatically if you click the Slice Edit or Vocal Edit buttons in the Edit Area Inspector.

- **If you want to return to Comp Edit mode, click the Return to Comp Mode button in the Edit Area Inspector.**
- **Alternatively, select the clip(s) in the Clip Overview area in the Comp Editor, or select the clip(s) in the Arrange Area, and then select "Bounce > Bounce Clip(s) to New Recording(s)" from the Edit menu or context menu.**
  A new "combined" recording is created on a new Comp Row, which is created above the other Comp Rows on the Edit Pane. The new Comp Row is assigned the suffix "(bounced)".



Select the clip in the Clip Overview.



Select "Bounce Clip to New Recording" to create a new "combined" recording on an additional Comp Row.

As the clip is bounced, the clip automatically switches from a Comp clip to a Single Take clip. If you play back the clip now, you will only hear the bounced recording on the automatically selected (topmost) Comp Row. However, the clip will sound exactly the same as before the bounce.


If you're happy with the result and don't plan to edit the clip any further, you can use the "Delete Unused Recordings" function to delete the recordings on the original Comp Rows and reduce the file size (see "Delete Unused Recordings"). If file size is not an issue, you can keep the original takes in the clip. This way you can switch to Comp Mode at any time if you need to edit the comp.

- **The "Bounce Clip to New Recording" function is very useful if you have imported a large audio file and only want to use a part of it. You can bounce the part of the clip you want use to a new recording and then delete the remaining unused part on the Comp Row to reduce the file size.**
- **It's also possible to bounce Audio Clips to disk and to a Sample - see "Bouncing Audio Clips" and "Bounce Clip(s) to New Sample(s)".**

Creating a comped audio clip

If you have recorded more than one loop cycle of audio in Loop Mode (see "Recording audio in Loop mode"), or recorded over or into an existing audio clip (see "Recording over or into an existing audio clip"), each recording has been placed on a separate Comp Row. If you like, you can now select the best parts (segments) of the recordings on the various Comp Rows and create a final "comped" audio clip. All editing described below is non-destructive and can be changed at any time:

1. **Open the audio clip in Comp Edit mode.**
   Each take has generated a separate Comp Row, each with a separate recording on it. The latest take, on the topmost Comp Row, is the one that will play back.




An audio clip (in Single Take Mode) with four separate takes recorded in Loop Mode.

! **If the clip is in Single Take Mode, because a Single Take Mode button is depressed (as in the picture above), you will have to click that Single Take Mode button to deselect the Comp Row before you can start adding Cuts!**

2. **Locate the best parts of the recordings in the different Comp Rows.**
   Audition the recordings on the Comp Rows to decide which recordings to use at what position in the comped clip. Select the Speaker Tool and click-hold at desired positions on the different Comp Rows (see "Speaker Tool" for details).


▶ **If you're using the Selection Tool, you can temporarily switch to the Speaker Tool by holding down [Alt]+[Shift](Win) or [Cmd]+[Shift](Mac).**

3. **Double-click with the Selection Tool on the Comp Row you want to use first in the clip.**
   In this example, we decide to use the recording on the "Take 2" Comp Row:




Double-click on the "Take 2" Comp Row to assign it to the first segment of the clip.

4. **Select the Razor Tool in the Sequencer Toolbar - or, with the Selection Tool still selected, hold down [Alt](Win) or [Cmd](Mac).**
   We want the recording on the "Take 2" Comp Row to play until beat 3 of Bar 7. After beat 3 of bar 7 we want the clip to be silent to get rid of some background noise that could be heard when we recorded without playing anything. Therefore, place the Razor Tool on the Silence Row at Beat 3 of bar 7 and click:



Place the Razor Tool on the Silence Row at beat 3 of bar 7...




...and click to assign the Silence Row to the second segment of the clip.


Now, you have assigned the recording on the "Take 2" Comp Row from the beginning of the clip to beat 3 of bar 7. At the same time you have assigned the Silence Row to a second segment of the clip.

5. **Use the Audition Tool to find a suitable recording to assign to a new segment in the clip.**
   We found a good recording that we want to use on the "Take 4" Comp Row between beat 3 and 4 of bar 8 until beat 1 of bar 11.

6. **Assign a complete segment by swiping with the Razor Tool.**
Swipe with the Razor Tool on the "Take 4" Comp Row from beat 3 and 4 of bar 8 until beat 1 of bar 11:




Place the Razor Tool between beat 3 and 4 of bar 8 on the "Take 4" Comp Row and swipe...



...and release at beat 1 of bar 11.


Now the recording on the "Take 4" Comp Row is assigned to a third segment in the clip. Two new Cut Handles have been added: one at the beginning of the swiped segment and one at the end.

7. **Assign a recording to the last segment of the clip.**
We used the Audition Tool and found that the recording on the "Take 1" Comp Row was just what we were looking for to play through to the end of the clip. Since a fourth segment was already created when you swiped in the previous step, you just need to double-click with the Selection Tool on the "Take 1" Comp Row, to the right of the last Cut Line, to assign the recording to the fourth segment:



Double-click on the "Take 1" Comp Row, to the right of the last Cut Line, to assign it to the last segment in the clip.

8. **To eliminate any clicks that might occur between the recordings in the different segments of our clip, let's introduce some crossfades.**
   Crossfades can be applied by first selecting a Cut Handle and then clicking with the Selection Tool and dragging the Cut Crossfade Handles that appear above the selected Cut Handle:




Click and drag the Cut Crossfade Handle... *...to introduce a crossfade between the segments.*

   The crossfade slopes are indicated by curves on the assigned Segments. The longer the crossfade time, the flatter the curves.

   Repeat the procedure for the other Cut Crossfade Handles in the clip if needed.

- **If you want to set the same crossfade time for several Cuts, select the Cut Handles and use the "Match Value" function in the Inspector (see "Matching Cut Crossfades").**

9. **Finally, you might want to trim the audio levels of the different recordings on the Comp Rows in the clip.**
   Click with the Selection Tool and drag the Comp Row Level Faders on the respective Comp Row to achieve a balanced audio level throughout the clip. The Comp Row level adjustments can be made anytime during the creation of the comped audio clip.



Adjusting the individual Comp Row audio levels.

- **If you want to set the same level for several Comp Rows, select the Comp Rows and use the "Match Value" function in the Inspector (see "Matching Comp Row Levels").**

- **When you're satisfied with your comped clip, you might want to click the "Bounce" button to generate a single recording that plays back your comped audio.**
  The clip is then also automatically set to Single Take mode, which makes it possible to edit the clip in Slice Edit mode, where you can stretch and quantize the audio etc. (see "Editing audio in Slice Edit mode"), or in Vocal Edit mode, where you can correct and edit the pitches of monophonic audio recordings (see "Editing audio in Vocal Edit mode").

  Bouncing also helps you keep things organized and can be a way to create a "snapshot" of your current comp, for comparison while you continue to fine-tune the edits.

- **If you're finished with a comp and want to keep the file size down, you can use the "Bounce" function together with the "Delete Unused Recordings" function to permanently remove all original takes (see "Delete Unused Recordings").**


Common audio editing functions

The functions below apply to all audio clip types.

Delete Unused Recordings

After you have edited your audio clips in the Comp Editor, there might be unused recordings left on Comp Rows that you don't plan to use. To reduce the file size of your song, you can choose to delete all unused recordings in one or several audio clips.

- **Select the clip(s) in the Clip Overview area in the Comp Editor, or select the clip(s) in the Arrange View, and then select "Delete Unused Recordings" from the Edit menu or context menu.**
  Alternatively, click the Delete button next to "Unused recordings" in the Comp Edit Area Inspector:



  All recordings that are not used in the clip(s) will be permanently deleted.

- **If a clip is in Single Take Mode, only the selected Comp Row will be played back - all other Comp Rows are per definition "unused". However, there may still be Cuts and assigned Segments among these Comp Rows, visible and audible if you switch the clip to Comp Mode.**
  As a safety measure, if you use the "Delete Unused Recordings" function on such a clip, you will be asked to confirm that you really want to remove all Comp Rows other than the selected one.
- **After deleting audio recordings, you will have to use the "Save and Optimize" function on the File menu to minimize the Song file size - see "Saving and optimizing a Song".**

Bounce Clip(s) to New Sample(s)

You can bounce one or several Audio Clips to new Song Samples. You could then edit the samples in the Edit Sample window and then load into a sampler device for playback. Proceed as follows:

- **Select the clips in the Clip Overview area in the Comp Editor, or select them in the Arrange View, and then select "Bounce > Bounce Clip(s) to New Sample(s)" from the Edit menu or context menu.**
  The Audio Clips are bounced to new Song Samples and named according to the Audio Clip name (if the clip was named) or according to the Audio Track name with serial numbers. The bounced Audio Clips then end up as sample files in the Song Samples location in the Browser. Refer to "Sampling" for more details about sampling and sample editing.

About the "Bounce Clip to Disk" function

The "Bounce > Bounce Clip to Disk" function on the Edit menu and clip context menu allows you to export the audio of a selected clip to disk as a single WAV or AIFF file. This might be useful if you want to process an audio clip in an external application and then re-import the clip to the track again. See "Bouncing Audio Clips" for more details.

Bouncing audio to MIDI notes

It's possible to convert Single Take audio clips to note clips. This is especially useful for monophonic audio that can be edited in Vocal Edit mode. But if you like to experiment you could try it on polyphonic audio as well. The result in any situation will be a monophonic note clip on a default Subtractor instrument track.


- ▶ **Select one or several Single Take audio clips in the Arrange View and select "Bounce > Bounce Audio Clips To MIDI" from the Edit menu or context menu.**
  A Subtractor instrument track is automatically created for each of the audio tracks. On the Subtractor track(s) a note clip for each of the selected audio clips are created.
- ▶ **Alternatively, drag one or several Single Take audio clips and drop onto an Instrument track.**
  The audio clips are automatically converted into note clips as you drop them on the Instrument track. Once dropped, you could play back the note clips using the present Instrument sound.
- ▪ **Clips that have "Vocal" Stretch and Transpose Type selected will generate Note clips with different MIDI notes in them.**
- ▪ **Clips that have "Allround" or "Melody" Stretch and Transpose Type selected will generate Note clips with only MIDI note C3 in them. In other words, you will basically only get a "rhythm" played by note C3.**
  This can be very useful if you, for example, want to bounce drums to MIDI notes. You may then have to move the MIDI notes to the correct notes in the generated Note clip afterwards.
- ! **If you drag Single Take audio clips from several audio tracks, you will need the same number of Instrument tracks to be able to drop all clips. As a rule of thumb, always create the instrument tracks right below the respective audio track.**




Normalizing audio clips

Normalizing means increasing the overall audio level so that the loudest peak in the sound touches 0 dB. Normalizing can be made on any audio clip, regardless of if they are Single Take clips or Comp clips.


1. **Select the Audio Clip(s) in the Arrange View:**



2. **Select "Normalize" from the Edit menu or Clip context menu in the Arrange Area.**
   Alternatively, click the "Normalize Clip" button in the Audio Overview Edit Mode:



3. **If you want to see what has happened, open the clip in Comp Edit Mode:**



A new Comp Row is automatically created at the top and named after the Audio Track, with the extension "(normalized)". The new Comp Row contains the "bounced" normalized audio and the Audio Clip has also automatically switched to Single Take Mode. The original audio is preserved on their original Comp Rows.

! **Only the audio within the Audio Clip boundaries will be normalized. Any masked audio will be disregarded.**


! **Note that normalizing a clip that contains audio that already reaches the full headroom (touches 0 dB) won't have any effect.**

! **When you normalize a Single Take clip, Reason automatically re-analyzes the audio and distributes new Slice Markers at the detected transients.**


Reversing audio clips

Reversing an audio clip means playing it backwards, from the end to the start. Reversing can be made on any Audio Clips, regardless of whether they are Single Take clips or Comp clips.


1. **Select the Audio Clip(s) in the Arrange View:**



2. **Select "Reverse" from the Edit menu or Clip context menu in the Arrange Area.**
   Alternatively, click the "Reverse Clip" button in the Audio Overview Edit Mode:



3. **If you want to see what has happened, open the clip in Comp Edit Mode:**



A new Comp Row is automatically created at the top and named after the Audio Track, with the extension "(reversed)". The new Comp Row contains the "bounced" reversed audio and the Audio Clip has also switched to Single Take Mode. The original audio is preserved on their original Comp Rows.

! **Only the audio within the Audio Clip boundaries will be reversed. Any masked audio will be disregarded.**

! **When you reverse a Single Take clip, Reason automatically re-analyzes the audio and distributes new Slice Markers at the detected transients.**


▶ **You can also reverse Note and Automation Clips (and individual events in these), see "Reverse".**

Changing the tempo and transposition of the audio

Tempo scaling Clips

Besides the automatic time stretching function applied when you change the Tempo in the main sequencer, there is a Scale Tempo function which can be applied to scale the tempo of one or several clips. The Scale Tempo function works in the same way for audio clips, note clips and parameter automation clips. However, it might be interesting to see what happens when you tempo scale an audio clip.

1. **Open an audio clip in the Comp Editor.**
   In this example we use a Comp clip with four Comp Rows and a number of Cuts. The tempo scaling works exactly the same way, regardless if the clip is a Single Take clip or Comp clip.
2. **With the Arrow Tool selected, hold down [Ctrl](Win) or [Option](Mac) and place the mouse cursor over one of the clip edges (in the Clip Overview).**
   The arrow symbol switches to a "scale tempo" symbol.



3. **Hold down [Ctrl](Win)/[Option](Mac) and click and drag the cursor sideways in either direction to scale the tempo of the clip.**
   In this example, we make the clip one bar longer by dragging the right clip handle one bar to the right.



   Now, the audio clip has been tempo scaled and the audio recordings have been stretched to match the new clip length. Note that the distance between the Cuts, as well as the lengths of the recordings on all Comp Rows have been expanded proportionally.

! **When you use the Scale Tempo function on Single Take clips (in the Arrange View), the Slice Markers will follow proportionally.**

The Scale Tempo function can also be applied to clips numerically, see "Scale Tempo".

! **When you scale the tempo of large clips, it could take a while before the high quality stretch is finished, see "Preview vs. High Quality Stretching".**


Transposing Audio Clips

Audio clips can be transposed. That is, all the audio recordings in a selected audio clip can be transposed up or down 12 semitones, in steps of 1 Cent, relative to their original pitch. The transposition can be applied to all types of audio - including polyphonic material.

! **The transposition is non-destructive, i.e. the original audio is always preserved and left unaffected.**

! **To get the best sound quality when you are transposing audio it's important that you have selected the correct Stretch and Transpose Type for the audio track, see "Opening audio clips for editing".**

1. **Select one or several audio clips.**
   The Transpose display shows up to the right in the Inspector:



Three audio clips selected on the arrangement pane in the Song View.

2. **Click the up/down arrow button next to the Transpose display to change the transposition in Semitones and Cents.**
   The audio in the selected clips are now transposed relative to their original pitch.

▶ **You can also edit the transposition value by clicking and dragging the respective display segment up/down or entering numeric values according to standard procedures.**

▪ **It's also possible to transpose individual Comp Rows in a Comp clip - see "Transposing Comp Rows" below.**


▪ **Audio Clips and MIDI notes in Note Clips can be transposed in whole semitone steps in the Transpose section - see "Note Pitch & Transposition".**

▶ **If you want to edit and/or correct the pitches of individual notes in monophonic audio recordings (e.g. vocal recordings), you can open the audio clip in Vocal Edit mode, see "Editing audio in Vocal Edit mode".**

Transposing Comp Rows


Besides the Audio Clip Transpose function described above, individual Comp Rows in a Comp clip can be individually transposed:

1. **Open a comped audio clip in the Comp Editor and select a Comp Row to be transposed.**



The selected Comp Row is shown in a darker color.

2. **Change the Transpose value in the Edit Area Inspector as desired.**



3. **Select another Comp Row and change its Transpose value in the Edit Area Inspector as desired.**
   Now the Comp Rows will have individual transposition values.

- **If you decide to change the Transpose value for the entire audio clip - by selecting the clip in the Arrange Area - the relative transpositions of the Comp Rows will be preserved.**


Editing audio using the Inspector

The Inspector can be used for editing audio recordings numerically.


! **For Inspector editing specific to Vocal Edit mode, please refer to "Audio pitch editing in the Edit Area Inspector".**

Editing recordings and cuts in the Edit Area Inspector

If you select a Comp Row, the three displays in the Edit Area Inspector show the Recording Offset, Comp Row Level and Comp Row Transpose value:



If you select a Cut Handle in Comp Mode, two other displays appear instead, showing the Cut Handle's Position and Cross-fade time:




▶ **Edit the values by clicking on a segment in a display and then dragging up/down, using the up/down spin controls, or typing in new values. Snap is not taken into account.**
See "Inspector segment displays" for details on how to edit in the Inspector displays.

Editing multiple recordings or multiple cuts in the Inspector

When you edit values for several selected Comp Rows or objects (Cut Handles etc.), the changes will always be relative. For example, if you change the Recording Offset, Level or Transpose values when several Comp Rows are selected, the recordings will all be changed by the same amount; their relative values will be retained.


- **If several Comp Rows are selected, the displays will show the values for the topmost selected Comp Row.**
- **If several Cut Handles are selected, the displays will show the Position and Crossfade values for earliest Cut Handle in the clip.**
- **If several Comp Rows, or several Cut Handles, are selected and any of their values differ, Match Value (=) buttons appear next to the corresponding display:**



For Cut Handles, only Crossfade values can be matched - not the Positions. See "Matching audio values using the "Match Values" function".

- **If Comp Rows and Cut Handles are selected in combination (e.g. for moving Cuts and recordings together as a group), no displays are shown in the Inspector.**

Matching audio values using the "Match Values" function



The Match Values buttons in the Edit Area Inspector


The “Match Values” function in the Edit Area Inspector can be used for matching Recording Offsets, Comp Row Levels and Transpose values of several selected Comp Rows to the offset/level/value of the topmost selected Comp Row. It can also be used for matching Cut Crossfade values of several selected Cut Handles to the Crossfade value of the Cut Handle with the earliest start position in the clip.

The “Match Values” function can also be used for matching the following parameters of several selected notes in Vocal Edit mode: Note, Fine-tune, Drift, Preserve Expression, Transition, Formant and Level. See “Audio pitch editing in the Edit Area Inspector” for more info.

Matching Recording Offsets

Matching Recording Offsets is useful if you want to make sure that the Recordings on multiple Comp Rows start at the exact same position.

1. **Select more than one Comp Row:**




Three selected Comp Rows (the three topmost).

The topmost Comp Row has the Recording Offset set to 2 beats.

2. **Click the Match Value button to the right of the “Recording Offset” display:**



The Recording Offsets on all selected Comp Rows have now been moved to 2 beats.




The Recording Offsets of the recordings on the three topmost Comp Rows have been moved to 2 beats.

Matching Comp Row Levels

Here's an example showing how to match Comp Row Levels:

- **Select several Comp Rows on the Edit pane.**

3. **Click the Match Value button to the right of the "Level (dB)" display:**



The Levels on the three selected Comp Rows are matched and adjusted to -19.82 dB.


Matching Comp Row Transpose values

- **Select several Comp Rows and then click the Transpose Match Value button.**
  The transposition is matched to the Transpose value of the topmost selected Comp Row.

Matching Cut Crossfades

Matching Cut Crossfades is a time-saving function if you want to apply the same Crossfade times to several Cuts throughout the clip. If you want to eliminate any clicks between segments in your comped clip, you could apply a Cut Crossfade to the first Cut and then match the other Cuts to get the same Crossfade times in one go:

1. **Select several Cut Handles.**
2. **Click the Cut Crossfade Match Value button.**



The Crossfades of the selected Cuts are matched and adjusted to the Crossfade times of the earliest selected Cut.



Chapter 10
Note and Automation Editing

About this chapter


This chapter describes how to edit note and parameter automation events after they have been recorded in the sequencer. It also describes how to manually create note and automation events in clips. General sequencer functions, recording, editing audio, arranging in the sequencer and working with Blocks are described in detail in the chapters "Sequencer Functions", "Recording in the Sequencer", "Audio Editing in the Sequencer", "Arranging in the Sequencer" and "Working with Blocks in the Sequencer".

The Edit Area

After you have recorded in note clips or parameter automation clips, you might want to edit and correct any mistakes you made during the recording. For example, if you accidentally hit the wrong notes or used the Mod Wheel too extensively when you recorded a note clip, there is no need to redo the recording. Individual notes and parameter automation events can easily be edited and corrected in a number of different ways.


The Edit Area in the sequencer is where you can perform detailed editing of note and automation events.

- **To enter the Edit Area, either double-click a note clip in the Arrange Area, or select the note clip and press [Return] - or right click a note clip and select "Open in Edit Area" from the context menu.**
  You can also toggle the Edit Area by clicking the Edit Area button in the document window top bar or by pressing [F8].



Double-clicking a note clip in the Arrange Area opens it for editing in the Edit Area.

- **Exit the Edit Area by pressing [Esc], or by clicking the Close button:**




Click the Close button to close the Edit Area.

Selecting what to edit

The Edit Area shows the contents of a single lane at a time on the Edit Pane - unless you use the Multi Lanes function, described in "Multi Lanes editing", where you can see the contents of multiple note lanes in a "ghosted" fashion underneath the currently open clip. On instrument tracks, only one note lane can have edit focus at a time.

- **If a sequencer track is selected when you enter the Edit Area, the contents of the note lane that has edit focus will be shown.**
  To be able to edit or draw notes and/or Performance Controller events, you need to open the clip, for example by double-clicking it (see "Opening note and automation clips for editing").
- **If the selected track has multiple note lanes, the contents of the currently selected note lane will be shown.**
  To switch edit focus between note lanes, click on the note lane handle in the Track List.



A note lane handle.

- **You can change edit focus at any time, by clicking a Note Lane in the Track List - or clicking another Note Clip in the Arrange Area.**
  This way you can stay in the Edit Area and change edit focus between different tracks and note lanes, without having to close the Edit Area first.


Opening note and automation clips for editing

Open a note clip for editing


Note clips can contain both note events - with velocity values - and performance controller events. By default, performance controllers include Mod Wheel, Pitch Bend, Sustain Pedal, Aftertouch, Expression and Breath Controller. However, the controller configuration can easily be changed (see "Creating new performance controller automation lanes" and "Deleting performance controller automation lanes").

In the Arrange Area, note events are displayed in a "piano roll" fashion whereas performance controllers are displayed as curves or lines in the clip. In the Arrange Area, it's not possible to distinguish one performance controller from another since all controllers are displayed together in the clip.

- **To edit the events in a note clip, open the clip by double-clicking it, or by selecting it and pressing [Return].**
  Opening a note clip in the Arrange Area automatically opens it in the Edit Area.



Double-clicking a note clip in the Arrange Area...




...opens it for editing in the Edit Area. An open clip in the Edit Area is highlighted.

- **Click on an unselected (grayed out events) note clip in the Edit Area to select it for editing.**
- **To close a clip and exit the Edit Area, press [Esc] or click the Close button.**

Open a parameter automation clip for editing

A parameter automation clip contains automation events for a single parameter.

- **Double-click a parameter automation clip in the Arrange Area to open it for editing in the Arrange Area.**
  The parameter automation lane expands in height to make it easier to edit the automation events. Now you can edit the parameter automation events.




A parameter automation clip before and after opening it in the Arrange Area.

- **To close an open parameter automation clip in the Arrange Area, press [Esc] or click on another lane.**

See "Editing parameter automation clips in the Arrange Area" for information on how to edit parameter automation events in the Arrange Area.

Edit Area elements

In the Edit Area, a note clip is divided into various Edit Lanes which are used for editing different types of events and values (i.e. note events, velocity values and performance controller/parameter automation events). The Edit Lanes can be resized by adjusting the horizontal divider between the Note Edit Lane and the Controller Edit Lane. You can also scroll and zoom in the Note Edit Lane, by using the scroll bar to the right and the Vertical Zoom tools on the top left of the Edit Pane. You can also zoom and scroll using the Zoom/Scroll areas shown in the picture below:



The picture shows three note clips in the Edit Area. The center clip is open for editing and therefore highlighted. Adjacent (unselected) clips on the same lane are visible but the events are grayed out.

From the top down in the picture above, the Edit Pane contains the following elements:


- **Vertical and horizontal Zoom/scroll areas**
  Place the mouse pointer in any of these areas, and click and drag to magnify and/or scroll in the Edit pane, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".
- **Close button**
  Click the Close button to exit the Edit Area.
- **Edit Area Inspector**
  Here you can view and edit various parameters pertaining to notes and parameter automation.
- **Interactive Keyboard**
  The interactive Keyboard highlights the notes you play on your MIDI keyboard, as well as notes you edit on the Edit Pane. You can also play (and record) notes by clicking on the Interactive Keyboard.

- **Note Edit View Mode selector**
  In the Edit Area Inspector is the Note Edit View Mode Selector. Click to choose between Key Edit, Drum Edit or REX Edit View. Depending on selected mode, the Note Edit Lane will display differently. See more about the different modes in "Note Edit View Modes".
- **Controller selector**
  Any recorded performance controller/parameter automation in the note clip has its own separate Controller Edit Lane. You can select the desired performance controller/parameter automation for editing using this selector. Here is also where you select Velocity. The selected parameter will show up in the Controller Edit Lane. See the "Creating new performance controller automation lanes" and "Deleting performance controller automation lanes" for more details.
- **Note Edit Lane**
  Here you can edit the notes of one open clip at a time. Note events are displayed as orange horizontal "boxes" in a piano roll fashion on the Note Edit Lane. The left side of each box indicates Note On (key down) and the right side Note Off (key up). The color intensity of each box indicates the velocity for the corresponding note. Depending on selected Note Edit View (see "Note Edit View Modes"), the contents of the Note Edit Lane will display differently.
- **Controller Edit Lane**
  On the Controller Edit Lane are the performance controller events for Mod Wheel, Pitch Bend, Sustain Pedal etc. depending on what you select in the Controller dropdown. Here is also where you can edit Velocity. Performance controller events are automatically distributed on separate lanes for each recognized controller during recording. Even though performance controllers belong to separate note clips, they will affect *all* active parallel note lanes on a track. See "Automation editing" for details on how to edit performance controller events.
- **Static Value handle**
  The Static Value handle to the left of the Controller Edit Lane indicates to what value the automated controller/parameter will default to where there are no clips on the lane. Basically, this value reflects the parameter's initial value, before it was automated. You can easily change a parameter's Static Value by dragging the Static Value handle up or down. See "Automation editing" for more details.

Edit Area window handling

Resizing, zooming and scrolling

▶ **You can resize the Edit Lane areas by dragging the divider between them:**



▶ **The Magnifying Glass tool can be used for zooming in and out (see "Magnifying Glass Tool").**

▶ **The Hand tool can be used for scrolling the view in any direction (see "Hand Tool").**


- **Use the Note Edit Lane scroll bar to scroll vertically on the Note Edit Lane.**
- **Use the Horizontal scroll bar to scroll sideways on the Note Edit Lane.**
- **Click the Zoom buttons to the top left to zoom on and out vertically in the Note Edit Lane.**
- **Place the mouse pointer in any of the Zoom/Scroll areas, and click and drag to magnify or scroll in the Edit pane, see "Scrolling and zooming using the Zoom/Scroll areas in the Sequencer".**
- **Resize the clip by dragging either of the clip edges sideways.**
- **For extensive editing, you may want to maximize the sequencer and/or have it in a separate window covering the entire computer screen. Refer to "Windows, areas and basic navigation".**

Note Edit View Modes

When you open a note clip in the Edit Area, the device used on the selected instrument track determines which Note Edit View Mode is selected. For instrument tracks associated with synth devices such as the ID 8 device, for example, Key Edit is automatically selected. For Redrum tracks Drum Edit is selected and for Dr. Octo Rex tracks REX Edit is automatically selected.

In all three Note Edit View Modes, the note events are shown as "boxes", with the note length indicated by the width of the box and the velocity values indicated by the color intensity of the box (the darker the color, the higher the velocity). The basic note editing procedures are the same for all three Note Edit View Modes.


- **You can manually change Note Edit View Mode by clicking the View Mode selector and selecting another mode from the dropdown.**



Selecting Note Edit View Mode.

The selected Note Edit View Mode is automatically remembered for each note lane on a track. The next time you open a clip on that note lane in the Edit Area, the correct Note Edit View Mode will be recalled.

Key Edit View Mode




Key Edit View Mode.

Key Edit View Mode is best suited for viewing and editing notes recorded for instrument devices, such as the ID 8. The piano keyboard to the left indicates the notes values, covering the entire MIDI note range (C-2 to G8). By clicking on any of the keys, you can audition the notes. As soon as the mouse pointer reaches the keyboard section, the cursor changes to a speaker symbol.

- **Note that the black and white keys are reflected in the background colors of the Note Edit Lane grid, making it easier to locate the desired note when drawing and moving note events.**


Drum Edit View Mode



Drum Edit View.

Drum Edit View Mode is best suited for viewing and editing notes recorded for a Redrum device. In Drum Edit View Mode the keyboard has been replaced by a list showing the corresponding Redrum drum sound channel names. If the track is associated with another type of instrument device, the list shows MIDI note numbers (0-127) instead. By clicking on any of the names (or note numbers) in the list, you can audition the sounds.

REX Edit View Mode



REX Edit View.

REX Edit View Mode is designed for viewing and editing Dr. Octo Rex Loop Player slices. In REX Edit View the keyboard has been replaced by a list showing the corresponding loop slice numbers in a Dr. Octo Rex device. Slice #1 in the list corresponds to the note C3. By clicking on any of the slice numbers in the list, you can audition the corresponding sound of the Rex loop.

Creating empty clips

When you record in the sequencer, clips are automatically created on the record enabled lane when necessary. However, there might be situations when you want to manually draw empty clips in the Arrange Area to record or edit in later on:

- **To create an empty clip, double click with the Selection (Arrow) Tool on a track in the Arrange Area.**
  This will create an empty clip with the length of the current Snap value setting (e.g. 1 bar). To create longer clips, double click, keep the mouse button pressed and drag to the right.

Alternatively, do as follows:

1. **Select the Pencil Tool from the sequencer Toolbar.**



2. **Place the Pencil on the lane where you want the clip to begin.**
   If you want to create a note clip, draw it on a note lane. If you want to create a parameter automation clip, draw it on a parameter automation lane. If Snap is activated, the clip start and end boundaries will snap to the set Snap value (see "Snap").
3. **Click and drag the Pencil to the right where you want the clip to end.**



An empty note clip in the Song View created using the Pencil Tool.

- **See also "Drawing notes" and "Drawing parameter automation events".**


Note editing

Notes can be edited using the mouse in the Edit Area. It's also possible to edit notes by using the functions in the Edit Area Inspector to the left of the Edit pane, see "Note and automation editing in the Inspectors".


Selecting notes

To select notes in an open clip in the Edit Area, use one of the following methods:

- **Click on a note with the Selection (Arrow) Tool.**



The Selection tool.



A selected note on the Edit pane

- **Selected notes are distinguished by a darker color.**
  The selected notes are also highlighted in the interactive keyboard to the left.
- **To select several notes, hold down [Ctrl](Win) or [Shift](Mac) and click on the desired notes, one after the other. You can deselect individual notes by [Ctrl](Win)-clicking or [Shift](Mac)-clicking them again. In Windows it's also possible to select a range of notes by [Shift]-clicking the first and last note in the range.**
- **You can also click and drag a selection rectangle around the notes you want to select.**
- **You can select the next or previous note on the lane by pressing the right or left arrow key on the computer keyboard.**
  Holding down [Shift] and using the arrow keys allows you to make multiple selections.
- **To select all notes of the same pitch (note value) in a clip, double-click the corresponding key in the Interactive Keyboard display to the left of the Edit pane.**
- **To select notes of the same pitch(es) of one or several notes, first select the note(s) in the open clip and then use the function "Select Notes of Same Pitch" on the Edit menu or context menu.**
- **To select all notes in the open clip, use the "Select All" function on the Edit menu. Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and press [A].**
- **To deselect all notes, click somewhere in an empty area in the clip (where there are no notes).**

Drawing notes

Notes are usually drawn and edited in Key Edit View on the Note Edit Lane, but the actions described below also apply to the Drum Edit View and the REX Edit View.


! **If you want to restrict note input to certain note values (e.g. 1/16th notes), activate Snap (see "Snap") and set the snap value accordingly.**

Drawing single notes

▶ **Double click with the Selection (Arrow) tool in the open clip to insert a note with a length of the current Snap value.**
This will create a note with the length of the current Snap value setting (e.g. 1/16th note). To create longer notes, double click, keep the mouse button pressed and drag to the right.

Alternatively, proceed as follows:

1. **Select the Pencil tool.**



▶ **With the Selection (Arrow) tool selected, you can toggle temporarily between the Selection tool and the Pencil tool by holding down [Alt](Win) or [Cmd](Mac). To switch between the Pencil and "Multiple notes" tools (see "Drawing multiple notes of the same length"), hold down [Alt]+[Ctrl](Win) or [Cmd]+[Option](Mac).**


2. **Click at the desired position on the Note Edit Lane.**
A note will be inserted at the closest Snap value position. By default, the note will be given the Velocity value '100'. (This can be edited afterwards according to the descriptions in "Velocity functions"). If an open or closed clip is already present on the Note Lane, at the position where you draw the note, the note will be placed in that clip. If no clip is available, refer to "About drawing notes outside an open clip" and "About drawing notes outside a closed clip" below.

- **If you just click, and Snap is activated, the note will get the length of the set Snap value.**
If Snap is off, the note will get the length of the shortest possible Snap value, i.e. 1/128th note.
- **If you click and keep the mouse button depressed, you can drag to the right to set the length of the note.**
If Snap is on, the length will be a multiple of the Snap value.

! **If you are drawing drum notes for a Redrum device, refer to the info about drum note lengths in "About resizing drum notes".**


Drawing multiple notes of the same length

1. **Click the Pencil tool (twice) and select "Draw multiple notes".**




▶ **With the Selection (Arrow) tool selected, you can toggle temporarily between the Selection tool and the Pencil tool by holding down [Alt](Win) or [Cmd](Mac). To switch between the "Multiple notes" and "single notes" tools, hold down [Alt]+[Ctrl](Win) or [Cmd]+[Option](Mac).**

2. **Select the desired note length from the Snap value selector:**



3. **Click at the desired position on the Note Edit Lane, click and draw sideways to the right:**



Multiple notes of the currently selected Snap value length are now added after one another (at the same pitch) in the note clip. By default, the notes will be given the Velocity value '100'. (This can be edited afterwards according to the descriptions in "Reverse").


About drawing notes outside an open clip

If you draw notes outside the boundaries of an open clip, the result depends on the setting "Keep Events in Clip While Editing" on the User Interface tab in Settings:


- **If the "Keep Events in Clip While Editing" option is active, the notes will belong to the open clip after they have been drawn, but become masked since they are drawn outside the clip boundaries.**
  The clip position and length will remain unchanged.
- **If "Keep Events in Clip While Editing" is deactivated and you draw notes outside the clip, the notes will be placed in an existing clip - or in another new clip on the lane, depending on where you draw.**
  The picture below shows three scenarios when drawing a note outside an open clip with the "Keep Events in Clip While Editing" option off:




Here, we're going to draw a note in beat 3 of bar 5...




The open clip expands by the set Arrange Mode Snap value (1 bar) to fit in the new note.




Here, we're going to draw a note in beat 3 of bar 8...



The note is placed in the existing clip at beat 3 of bar 8.



Here, we're going to draw a note in beat 1 of bar 12...



A new clip is created at bar 12 with a length of the set Snap value (1 bar) and the new note is placed in beat 1.

About drawing notes outside a closed clip


If you draw notes outside the boundaries of a closed clip in the Edit Area, i.e. where there are no clips available on the lane, a new clip will be automatically created and opened. The clip length is determined by the Arrange Area Snap value, if Snap is activated.

- **This works best with "Keep Events in Clip while Editing" turned OFF because then you can continue drawing notes - the clip will be resized to fit the new notes.**

Deleting notes

You can delete notes by doing any of the following:

- **To delete individual notes, click the notes with the Pencil tool or double click them with the Selection (Arrow) tool.**
- **Select one or several notes with the Selection (Arrow) tool and press [Backspace] or [Delete], or select "Delete" from the Edit or context menu.**
- **Select the Eraser tool and click on the notes you want to delete.**




The Eraser tool.

- **You can also draw a selection rectangle with the Eraser tool to delete several notes in one go.**

Resizing notes

Resizing notes manually

When you move the mouse over the edge of note, the pointer changes to a resize symbol. Click and drag left or right to resize the note:



- **If Snap is on (see "Snap"), the beginning and/or end of the note will be magnetic to the (absolute) Snap value positions.**
- **If several notes are selected, the note you resize with the mouse will be magnetic to absolute Snap value positions.** The other selected notes will be resized by the same amount.
- **When resizing notes, the event may extend outside the clip boundaries.** As long as the start position of events is inside the clip, the note will play for the whole duration, i.e. it won't be cut off when the clip ends.


! **If a note is resized to the left, outside the clip start position, the note will no longer belong to that clip and will thus be masked (silent). to unmask the note, resize the clip to the left so that the note's start position gets inside the clip.**

About resizing drum notes

Redrum drum notes can be resized, just like any other notes. However, the audible result of this depends on the settings of the Decay/Gate switch and the Length knob for the drum sound on the Redrum device panel:

- **If Decay mode is selected, the drum sound will play to its end, regardless of the note length in the sequencer.**
  Or rather, it will fade out according to the Length parameter setting on the Redrum device panel.
- **If Gate mode is selected, the note lengths in the sequencer affect the resulting sound.**
  However, the maximum length of the sound is determined by the Length knob setting - the sound will be cut off after this length, regardless of the note length in the sequencer. Also, even if the Length knob is set to its maximum value, the sound will not play longer than the length of the drum sample.

Resizing notes with the "Length" function in the Edit Area Inspector



The Length pane in the Edit Area Inspector

The "Length" function in the Edit Area Inspector allows you to add or subtract length values to selected notes. You can also double click in the display, type in a Length value and hit [Return] to apply the length to all selected notes.

Note length resizing can be applied to selected note(s) in a note clip.

1. **Select the desired note(s) on the Note Edit Lane.**
2. **Add or subtract the desired length using any of the following techniques:**


- **Click and hold a segment in the display and drag up/down.**
- **Click a segment in the display and then click the up/down arrow buttons.**
- **Double click the display and type in "x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to set all selected notes to a fixed note length value.**
- **Double click the display and type in "+x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to add the desired note length value to the selected notes:**



Adding two 1/16th notes to the original note length

- **Double click the display and type in "-x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to subtract the desired note length value from the selected notes.**

Using the "Overlap" function to create legato or gaps between notes



The Overlap section on the Length pane in the Edit Area Inspector

The "Overlap" function can be used to extend each selected note so that it reaches or exceeds the start position of the next selected note. You can also shorten the note lengths for selected notes and set a gap between them. You specify the desired gap or overlap in the displays. Only the note length is affected by the Overlap adjustments - note start positions are never changed.


Overlap adjustments can be applied to selected notes in a note clip.

1. **Select the desired notes on the Note Edit Lane.**
2. **Add or subtract the desired Overlap length (in ticks) using any of the following techniques:**

- **Click and hold in the display and drag up/down.**
- **Click the up/down arrow buttons.**
- **Double click the display and type in a value. A positive values results in an overlap and a negative value results in a gap between the notes.**


3. **Click the Make Legato button to apply the overlap/gap.**
   The range is +/-960 tics, which corresponds to +/- four 1/16th notes (240 ticks = 1/16th note).

- **An Overlap value of "0" extends the selected note length(s) to the start of the next selected note(s):**
  (This is the same as "Abut" in earlier Reason versions.)




A group of notes before and after applying "0" in the Overlap display.

- **A positive Overlap value extends the selected note(s) to overlap the next selected note(s) by the set Overlap (ticks) value:**



A group of notes before and after applying a positive value in the Overlap display.

- **A negative Overlap value introduces a gap between the selected notes:**




A group of notes before and after applying a negative value in the Overlap display.


Muting notes

You can mute individual notes in an open note clip:

1. **Select the Mute tool.**



2. **Click the notes you want to mute.**
   Muted notes are highlighted in blue in the open clip:




- **To mute multiple notes in one go, select the desired notes with the Selection (Arrow) tool and press [M].**
  Press [M] again to unmute the selected notes.

Splitting notes


You can split (slice) one or several notes in an open note clip by using the Razor tool:

1. **Select the Razor tool.**




The Razor tool.

2. **Place the Razor where you want to split the note, and then click:**



A note before and after splitting it.

- **You can also split several notes by selecting the Razor tool and drawing a selection rectangle that intersects the desired split points:**




Splitting two notes by drawing a selection rectangle with the Razor tool.

The split notes get the same velocity values as their "parent" notes.

Joining notes

It's possible to join several selected notes on the same note number(s):

1. **Select the notes you want to join:**




2. **Hold down [Ctrl](Win) or [Cmd](Mac) and press [J] - or select "Join Notes" from the Edit/note context menu.**
   Selected notes on the same note number(s) will be joined into single longer notes.

Chopping notes

You can choose to chop up selected notes to a number of preset lengths. This will cut the selected notes into equal smaller notes:

1. **Select the notes you want to chop:**




2. **Select "Chop Notes to >" and select the desired note length from the Edit menu or the note context menu.**
   The selected notes are now chopped to the selected length.

! **Note that the chopping is done relative to the sequencer absolute grid.**

Moving notes

Moving notes with the "Position" function in the Edit Area Inspector



The Position pane in the Edit Area Inspector


The "Position" function in the Edit Area Inspector allows you to change the position (in the timeline) of one or several selected notes by adding or subtracting position values to selected notes. You can also double click in the display, type in a Position value and hit [Return] to apply the new position.

Note positioning can be applied to selected note(s) in a note clip. If you have selected several notes, the position value applies to the earliest note in the selection. The other notes are positioned after with their original timing relationship.

1. **Select the desired note(s) on the Note Edit Lane.**
2. **Add or subtract the desired position using any of the following techniques:**

- **Click and hold a segment in the display and drag up/down.**
- **Click a segment in the display and then click the up/down arrow buttons.**
- **Double click the display and type in "x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to position the (first) note at the entered position.**

- **Double click the display and type in "+x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to move the position(s) forward by the entered value:**




Moving the position forward by 6 Bars, 1 Beat and one 1/16th note compared to the original note position


- **Double click the display and type in "-x.x.x.x" (where x represents Bar, Beat, 1/16th note and Ticks) and press [Return] to move the position(s) back by the entered value.**

Moving notes manually

- **To move a note, click and drag it to a new position, or new pitch (note number), using the Selection Tool.**
  If several notes are selected, all will be moved. If Snap is on (see "Snap"), the moved events will keep their relative distance to the Snap value positions - or will be moved to new positions on an absolute grid - depending on whether you have selected "Absolute" or "Relative" in the Snap value list.



- **By default, when manually moving notes to new pitches (note numbers), the notes will trigger and sound. This makes it easier to move (transpose) the notes to where you want them.**
  If you don't want notes to sound during editing, it's possible to disable the function on the "User Interface" tab in Settings, by deselecting the "Trigger notes while editing" box:




The "Trigger notes while editing" function in Settings.

- **If you hold down [Shift] when you drag, the movement is restricted to horizontal or vertical direction.**
  This helps you move notes without accidentally transposing them, or transpose notes without accidentally changing their position.
- **You can also edit the note pitches numerically using the "Pitch (Transpose)" function.**
  See "Note Pitch & Transposition".
- **You can also move selected notes to a new note clip, on a new additional note lane, by right-clicking (Win) or [Ctrl]-clicking (Mac) and selecting "Move Selected Notes to New Lane" from the context menu.**
  A new note clip and note lane will be automatically created.


About moving notes outside or between clips

If you want to move notes outside the boundaries of an open clip, the result depends on the setting "Keep Events in Clip While Editing" on the User Interface tab in Settings:


- **If the "Keep Events in Clip While Editing" option is active, the notes will belong to the open clip after they have been moved, but become masked since they are moved outside the clip boundaries.**
  The clip position and length will remain unchanged.
- **If "Keep Events in Clip While Editing" is deactivated and you move notes outside the clip, the notes will be placed in an existing clip - or in a new clip on the lane, depending on to where you move them to.**
  The picture below shows three scenarios when moving three notes outside a clip with the "Keep Events in Clip While Editing" option off:




We're going to move the last three notes in the clip to beat 3 in bar 5.




The open clip expands by the set Arrange Area Snap value (1 bar) to fit in the moved notes.




Here, we're going to move the last three notes in the clip to beat 4 in bar 10.



The notes are placed in the other existing clip at beat 4 in bar 10.



Here, we're going to move the last three notes in the clip to beat 1 in bar 12.



A new clip is created at bar 12 with a length of the set Snap value (1 bar) and the notes are placed in beat 1.

Changing note pitches (transpose) with the arrow keys

You can use the up/down arrow keys to change the pitches of selected notes by moving them up or down:

- ▶ **Hold [Ctrl](Win) or [Cmd](Mac) and use the up or down arrow key to move the selected notes in semi-tone steps.**

You can also move/transpose notes in whole octave steps:

- ▶ **To move the selected notes up/down in octave steps, hold [Shift]+[Ctrl](Win) or [Shift]+[Cmd](Mac) and use the up or down arrow key.**

Nudging note positions with the arrow keys

You can use the left or right arrow keys to "nudge" the positions of selected note events:

- **Hold [Ctrl](Win) or [Cmd](Mac) and use the left or right arrow key to move the position back or forward by the set Snap value.**
- **Hold [Ctrl]+[Alt](Win) or [Cmd]+[Option](Mac) and use the left or right arrow key to move the position back or forward in Tick increments.**
  There are 240 ticks per 1/16 note so this allows for very fine editing. Check the Tick value in the Inspector when you nudge because typically you won't see the position changes on the Edit Pane, unless you have zoomed in a lot.
- **Hold [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and use the left or right arrow key to move the position back or forward in Beat increments.**

About nudging notes outside an open clip

If you nudge notes outside the boundaries of an open clip, the notes will belong to the open clip, but become masked since they are nudged outside the clip boundaries. The "Keep Events in Clip While Editing" setting has no effect when nudging notes. If you want to move notes between clips, or to a new clip, you have to do that using the Selection Tool as described in "About moving notes outside or between clips".

Moving notes with the "Extract Notes to Lanes" and "Explode" functions

It's possible to move defined notes in a clip to new clips on new, additional lanes. See "Extract Notes to Lanes".

Moving notes in the Inspector

You can also edit the note positions and pitches numerically in the inspector. See "Note and automation editing in the Inspectors".

Duplicating notes

Duplicating notes manually

- **To duplicate selected notes, hold down [Ctrl](Win) or [Cmd](Mac) and press [D].**
  This will duplicate the selection and place it after the selection, at the closest Snap value after the last note in the selection. Repeat the command to continue the duplication for as many times as you like.
- **To duplicate selected notes, hold down [Ctrl](Win) or [Option](Mac) and click and drag a copy of the selection, similar to when moving notes manually (see "Moving notes").**
- **You can also duplicate selected notes to a new note clip by right-clicking (Win) or [Ctrl]-clicking (Mac) and selecting "Duplicate Selected Notes to New Lane" from the context menu.**
  This will automatically copy the selection and paste it in a new note clip on a new, additional note lane.

Duplicating notes with the "Extract Notes to Lanes" function

It's possible to duplicate defined notes in a clip and automatically place them on new, additional lanes. See "Extract Notes to Lanes".



Using Cut, Copy and Paste


You can move or duplicate events using the Cut, Copy and Paste commands on the Edit menu or context menu.

- **When you use Cut or Copy, the Song Position Pointer is automatically moved to the end of the selection.**
  This is very useful for repeating events, i.e. pasting the selection several times one after another in the song.


Pasting events outside an open clip

When you use the Paste command, the events will appear at the Song Position Pointer, on the original lane. Depending on the "Keep Events in Clip While Editing" setting on the User Interface tab in Settings, the following rules apply:


- **If "Keep Events in Clip While Editing" is on, the notes will belong to the open clip after they have been pasted, but become masked since they are pasted outside the clip boundaries.**
  The clip position and length will remain unchanged.
- **If "Keep Events in Clip While Editing" is deactivated and you paste notes outside the clip, the notes will be placed in an existing clip - or in another new clip on the lane, depending on where you paste them.**
  The picture below shows three scenarios where three notes are being cut and pasted at different positions outside the open clip with the "Keep Events in Clip While Editing" option off. We determine the paste positions by moving the Song Position Pointer:




We're going to cut the last three notes in the open clip and paste at beat 3 in bar 5.




The open clip expands by the set Arrange Area Snap value (1 bar) to fit in the pasted notes.




Here, we're going to cut the last three notes in the open clip and paste at beat 4 in bar 10.



The notes are pasted in the other existing clip at beat 4 in bar 10.



Here, we're going to cut the last three notes in the open clip and paste at beat 1 in bar 12.



A new clip is created at bar 12, with a length of the set Snap value (1 bar), and the notes are pasted in beat 1.


Quantize

The “Quantize” function on the Transport Panel is normally used for applying quantization to notes - but can also be used for quantizing recorded audio. The Quantize section in the Edit Area Inspector can only be used for notes, though. Clicking the Quantize or Apply button will automatically align the start positions of the selected notes to a pre-defined, absolute grid. You can also choose to automatically quantize MIDI notes as they are being recorded - see “Quantizing notes during recording”.


Quantization can be applied to:

- **Individual (selected) notes in a note clip.**
  This has to be done in the Edit Area Inspector.
- **All notes in one or several selected note clips.**
  This is done in the Arrange Area. Select the note clip(s) and then apply the quantization on the Transport Panel. Alternatively, select “Quantize” from the clip context or Edit menu. If you need more detailed quantization, select “Quantize Setup...” from the clip context or Edit menu.
- **All notes in all note clips on one or several selected tracks.**
  This is done in the Arrange Area. Select the note clip(s) and then apply the quantization on the Transport Panel. Alternatively, select “Quantize” from the clip context or Edit menu. If you need more detailed quantization, select “Quantize Setup...” from the clip context or Edit menu.

The quantization grid is selected in the Quantize Value drop-down list on the Transport Panel and/or on the Quantize pane in the Edit Area Inspector:



The Quantize Value drop-down list on the Transport Panel.



The Quantize pane in the Edit Area Inspector.


In most situations the Quantize functions on the Transport Panel are probably sufficient. However, if you want more in-depth note quantization functionality, perform the quantization in the Edit Area Inspector instead.

▶ **You could also use the ReGroove functions for groove quantizing of notes. See “The ReGroove Mixer”**

Quantizing after recording

1. **Select the note(s), note clip(s) or instrument track(s) you want to quantize.**
   Only the notes in the clip(s) will be affected - not any parameter automation events.


2. **Select a quantize value from the Quantize Value drop-down list on the Transport Panel, or from the Value drop-down list in the Edit Area Inspector.**
   This determines to which note value grid the notes will be moved when you quantize. For example, if you select 1/16, the note starts will be moved to (or closer to) the closest sixteenth note position.



The Quantize Value drop-down list in the Edit Area Inspector.


A 'T' letter next to some quantization value means Triplets. The effect of using triplets is that three notes are equally distributed over the same time period as two "regular" (non-triplet) notes of the same note value.

3. **Select a value from the Quantize Amount drop-down list.**
   This is a percentage, governing how much each note should be moved. If you select 100%, the note starts will be moved all the way to the closest Quantize value positions; if you select 50%, the notes/audio slices will be moved half-way, etc.



The Quantize Amount drop-down list in the Edit Area Inspector.

4. **Click the Quantize button.**
   The selected notes are quantized.



A sloppily recorded hi-hat pattern is quantized to straight 1/4 notes (Quantize Value 1/4, Amount 100%).

- **Quantization can also be applied to note(s) and audio slice(s) in selected clip(s) or track(s) in the Arrange Area, by right-clicking(Win) or [Ctrl]-clicking(Mac) and selecting "Quantize" from the context menu.**
  If you want to change the quantization settings, select "Quantize Setup..." from the clip/track context menus.

Quantize to Shuffle


In the Value drop-down list, you will also find an option called “Shuffle”. If this is selected when you quantize, the note starts are moved towards sixteenth note positions, but with Shuffle applied.

Shuffle creates a “swing feel” by delaying the even-numbered sixteenth notes (the sixteenth notes that fall in between the eighth notes). The amount of Shuffle is set with the Global Shuffle control in the ReGroove Mixer. Quantizing to Shuffle is useful if you want to match the timing with pattern devices in the song (if Shuffle is activated in their patterns).

A more flexible way of doing this for notes and note clips is to use the ReGroove mixer - see “The ReGroove Mixer” chapter for details.

! **The Amount setting applies as when quantizing to “regular” note values.**

Randomize




You can offset the note positions using the Randomize function. The note’s start positions will be randomly offset within the range of the set tick value. E.g. if you set Randomize to 10 ticks, the notes starts will randomly vary within a +/- 10 tick range after applying randomization.

Quantizing notes during recording

It’s also possible to quantize input notes directly during recording. Activation of this function is done on the Transport Panel:

▶ **Enable automatic note quantization by clicking the “Q Rec” (Quantize Notes During Recording) button on the Transport Panel:**




The Q Rec (Quantize Notes During Recording) button on the Transport Panel.

Any notes recorded after having activated this function will be automatically quantized to the current settings on the Transport Panel.

! **Audio cannot be quantized during recording!**

Note Pitch & Transposition



The Note (pitch) pane in the Edit Area Inspector.


The "Note" functions in the Edit Area Inspector can transpose selected MIDI notes up or down in whole semitone steps.

There is also an "Alter Notes" function which lets you alter the pitches between several selected notes. A Randomize function lets you randomly transpose the pitch of selected MIDI notes in a note clip.

The "Note" functions can be applied to:

- **Individual (selected) note events in a note clip.**
  This has to be done in the Edit Area Inspector.
- **All note events in one or several selected note clips.**
  This is done in the Arrange Area. Select "Note Tools > Transpose" from the clip context or Edit menu.
- **All note events in all note clips on one or several selected instrument tracks.**
  This is done in the Arrange Area. Select "Note Tools > Alter Notes" from the track context or Edit menu.
- **In Arrange Area you can transpose a combination of selected note clips/tracks and audio clips/tracks in one go.**
  This is done in the Arrange Area. Select "Note Tools > Alter Notes" from the clip/track context or Edit menus.

Note




▶ **Select one or several notes on the Edit pane, then click the up/down arrow buttons - or drag the note name in the display up/down to transpose the note(s) up/down one semitone per step.**

▶ **You can also double click in the display, type in a note (or "+x" or "-x" to add/subtract semitones) and press [Return] to change the note pitch(es).**

! **The note transposition is "absolute", i.e. the notes are permanently moved to new note positions in the clip.**


▶ **You can also transpose notes by manually moving them using the mouse or arrow keys, as described in "Moving notes manually" and "Changing note pitches (transpose) with the arrow keys".**

Transpose (Semitones)




- ▶ **Select one or several notes on the Edit pane, then select the number of semitones you want to transpose it/them. Then, click the "Transpose" button.**
- ▶ **You can also double click in the display, type in a note (or "+x" or "-x" to add/subtract semitones) and press [Return]. Then, click the "Transpose" button to change the note pitch(es).**
- ! **The note transposition is "absolute", i.e. the notes are permanently moved to new note positions in the clip.**
- ▶ **You can also transpose notes by manually moving them using the mouse or arrow keys, as described in "Moving notes manually" and "Changing note pitches (transpose) with the arrow keys".**

Octave



- ▶ **Select one or several notes on the Edit pane, then click the Up or Down buttons to transpose the notes up/down one octave per click.**

Alter (Note pitches)




The "Alter Notes" function in the Edit Area Inspector alters the pitches between selected notes, in a random fashion, without changing their positions.

The "Alter Notes" function can be applied to:

- **Individual (selected) note events in a note clip.**
  This has to be done in the Edit Area Inspector.
- **All note events in one or several selected note clips.**
  This is done in the Arrange Area. Select "Note Tools > Alter Notes" from the clip context or Edit menu.
- **All note events in all note clips on one or several selected instrument tracks.**
  This is done in the Arrange Area. Select "Note Tools > Alter Notes" from the clip context or Edit menu.
- **The Alter Notes function will only use the note positions that already exist among the selected notes.**

- **Select several notes on the Edit pane, then select a Chance (%) value and click the Alter button to alter the pitches of the selected notes between each other.**
  The pitches will only be altered between the currently selected note pitches.
- **This function is especially useful for experimenting with rearranging Dr. Octo Rex loop slices. Select some slices on a Dr. Octo Rex track and use Alter Notes to rearrange the slices and create instant variations, without losing the timing and rhythmic feel of the loop.**

Randomize Notes




1. **Select one or several notes on the Edit pane.**
2. **Select the note range in which to transpose the selected MIDI notes. Click "Randomize" to transpose.**

The selected notes will be randomly transposed within the set note range.

Velocity functions

Editing note velocity with the "Velocity" functions




The Velocity pane in the Edit Area Inspector.

The "Velocity" functions in the Edit Area Inspector can be used for adjusting the velocity of selected notes in a number of different ways.

Note velocity can be applied to:


- **Individual (selected) notes in a note clip.**
  This has to be done in the Edit Area.
- **All notes in one or several selected note clips.**
  This is done in the Arrange Area. Select "Note Tools > Note Velocity" from the clip context or Edit menu.
- **All notes in all note clips on one or several selected instrument tracks.**
  This is done in the Arrange Area. Select "Note Tools > Note Velocity" from the track context or Edit menu.

Velocity



1. **Select one or several notes on the Edit pane.**
2. **Edit the Velocity according to the following alternatives:**


- **Click the up/down arrow buttons to increase or decrease the Velocity value(s).**
  If several notes have been selected, the value refers to the earliest (leftmost) note on the Edit pane.
- **Drag the Velocity value in the display up/down to increase/decrease the Velocity value(s).**
- **Double click the Velocity display, type in a Velocity value and press [Return].**
  If you want to add a value to the current Velocity value, type in "+" before the value and press [Return]:



Adding 20 to the original Velocity value.


To subtract a value from the current Velocity value, type "-" before the value and press [Return].

Scale




- **The "Scale" function allows you to scale velocities by a percentage factor.**
  Scaling by a factor of more than 100% will increase the velocity values, but also make the difference between soft and hard notes bigger.
  Scaling by a factor of less than 100% will decrease the velocity values, but also make the difference between soft and hard notes smaller.
- **By combining the "Velocity" and "Scale" functions, you can adjust the "dynamics" of the notes in various ways. For example, by using a Scale factor below 100% and adding a suitable value in the Velocity display, you can "compress" the velocity (decreasing the difference between the velocity values without lowering the average velocity level).**

Randomize




- **"Randomize" will randomize the velocity values by a set percentage value.**

Make Ramp



This allows you to create a Velocity Ramp between the first and last notes in a selected range of notes.

1. **Select a range of notes on the Edit pane.**
2. **Set the Range values for the first and last note and click Make Ramp.**
   The note velocities will now ramp from the first value to the last value, looking something like this on the Velocity Controller Lane, if the range begins with a low value and ends with a higher:




Editing note velocity manually

- **Below the Edit Area Inspector, select "Velocity" in the Controller selector:**



The velocity values of notes can be edited manually on the Velocity Edit Lane:




The velocity values are shown as bars with handles, with taller bars indicating higher velocity.
Note also that the color intensity of the notes and velocity bars reflect the velocity values.

- **To change the velocity of a note, click its velocity handle and drag it up or down.**
- **You can select multiple velocity handles (by Shift-clicking or dragging a selection rectangle) and adjust them at the same time.**
  All note velocities will be changed by an equal amount.

It's also possible to "draw" velocity curves with the Pencil tool:

- **When the Pencil Tool is selected and you press [Ctrl](Win) or [Option](Mac) on the Velocity Edit Lane, the pencil will change to a cross.**
  This is the Line Tool which is a special tool only available on the Velocity Edit Lane. By dragging across the velocity "lines", at the desired height, you can quickly draw velocity ramps.



Drawing a velocity ramp with the Line Tool.

The Line Tool is probably the preferred method for creating regular, smooth ramps, or for giving all the notes the same velocity (by drawing a straight line), while the Pencil tool can be used for creating more irregular curves.

Extract Notes to Lanes

The "Extract Notes to Lanes" function is used for moving or duplicating user-defined notes of a certain pitch, or notes within a defined pitch range, to a new note clip on a new, additional note lane. This function is very useful if you, for example, have recorded a drum track, with all notes in the same clip, and then want to extract individual drum sounds (note pitches in this case) to separate lanes to be able to edit them more easily - or to apply ReGroove channels (see "The ReGroove Mixer").


The "Extract Notes to Lanes" function is executed in the Song/Blocks View and can be applied to:

- **Notes of defined pitches in one or several selected note clips.**
- **Notes of defined pitches in all note clips on one or several selected instrument tracks.**

Extract Notes to Lanes example


We have recorded a 4-bar drum beat, consisting of kick, snare and open+closed hi-hat, in a single clip on a note lane. Now, we want to extract the open and closed hi-hat sounds to a new separate note lane:

1. **Just to see what the note clip contains, open the note clip in the Edit Area (this is only to show what it contains):**




The original 4-bar drum beat clip opened in the Edit Area.

2. **In the Arrange Area in the Arrange Area, right click the clip and select "Extract Notes to Lanes...".**
   Since the Extract Notes to Lanes function applies to selected *clips* and not to selected notes, you have to right click the clip in the Arrange Area. The Note Extract dialog appears:




3. **Define which notes you want to move.**
   We want to move the open and closed hi-hat notes, i.e. the note range from G#1 to B1. We therefore select the note range in the "From:" and "To:" displays.



Select the note range to be moved.

4. **Click the "Move" button:**




The open and closed hi-hat notes are now moved to a new clip on a new note lane. If we open the new clip in the Edit Area, we can see the moved hi-hat notes in the new clip:



The moved notes in a new clip on a new note lane.

In the Arrange Area in the Arrange Area, we can see both the original clip and the new clip:




The original clip and the new clip in the Arrange Area.

▶ **If you want to move or duplicate notes of a certain note number only, click the "Single Note" radio button and select the note pitch in the display. Then click, the "Move" or "Duplicate" button.**
Only the notes of the selected note number will be moved or duplicated to a new clip on a new note lane.

! **Any recorded performance controller automation will remain on the original note lane.**

The “Explode” function



- **Click the “Move” or “Duplicate” button in the “Explode” section at the bottom of the dialog to move or duplicate notes of the same note numbers to new individual clips on separate note lanes.**
  Notes of the same note number will be moved or duplicated to new separate clips on separate note lanes. A new lane will be created for each of the used note numbers in the original clip
- **The “Explode” function is perfect if you have recorded a drum track and want to move, or duplicate, each individual drum sound to a separate note lane for further editing. Applying different ReGroove channels to each of the generated note lanes could provide extremely nice grooves to the rhythm! See “The ReGroove Mixer” for more details.**

Scale Tempo


The “Scale Tempo” function can be applied to selected notes and/or automation events in the Edit Area. It can also be applied to selected note, audio and automation clips in the Arrange Area in the Song/Blocks View. The Scale Tempo function will make the selection play back faster (Scale factor above 100%) or slower (Scale factor below 100%).

For notes and automation events, this is achieved by changing the position of the events (starting from the earliest selected event) and adjusting the length of the notes accordingly. For audio clips, high-quality stretching is applied to all audio recordings in the clip.

Tempo scaling can be applied to:


- **Individual (selected) note and/or parameter automation events in an open clip.**
  This has to be done in the Edit Area.
- **All note and/or parameter automation events and/or audio recordings in one or several selected clips.**
  This is done in the Arrange Area.
- **All note and/or parameter automation events and/or audio recordings in all clips on one or several selected tracks.**
  This is done in the Arrange Area.

1. **Select a number of events in the open note clip and then select “Scale Tempo > Specify...” from the Edit menu.**
   The Scale Tempo dialog appears:



2. **Select the desired scaling by clicking the up/down buttons, or by dragging up/down, or by entering a numeric % value in the display. Then, click the Scale button.**
   The range is 1-800%. Values below 100% will slow down the tempo and values above 100% will speed up the tempo.

- **The "x2" (Double) and "x/2" (Half) buttons are "shortcuts" to Scale factors 200% and 50%, respectively.**
  These are probably the most common values used, simulating double tempo and half tempo scaling.



The result of applying Scale Tempo on note events with the Scale factor 200% (x2).

▶ **To Tempo Scale the contents of selected clips, select the clips in the Arrange Area and select "Scale Tempo > Specify..." from the Edit or clip context menu**

! **The Scale Tempo function affects note, performance controller, parameter automation, pattern change, tempo automation events and audio clips! It does NOT affect time signature automation.**

! **When you are tempo scaling audio clips, make sure you have selected the appropriate Stretch Type, otherwise the sonic result might not be what you'd expect, see "Opening audio clips for editing".**

! **Note that Pattern Automation Clips will only be resized - the pattern tempo in the source device will NOT be scaled but will still be synced to the main sequencer tempo!**

Reverse

It's possible to reverse note (and automation) clips and events, i.e. play the events of the clip "backwards" (from the end to the start). The main difference between reversing note (and automation) clips compared to audio clips is that in note clips the notes and automation points are reversed (mirrored) - not the actual audio that the notes generate. With audio clips, however, the actual audio is reversed (played backwards).

The Reverse function can be applied to:

- **Individual (selected) note events in a note clip.**
  This has to be done in the Edit Area.
- **Individual (selected) automation points in a note clip or in an automation clip.**
  This has to be done in the Edit Area.
- **All note and automation events in one or several selected note and automation clips.**
  This is done in the Arrange Area.
- **All audio recordings in one or several selected audio clips.**
  This is done in the Arrange Area. See "Reversing audio clips" for more details about reversing audio clips.
- **All note and automation events in all note and automation clips on one or several selected instrument tracks.**
  This has to be done in the Arrange Area.
- **All audio recordings in all audio clips (and all automation clips, if any) on one or several selected audio tracks.**
  This has to be done in the Arrange Area.


! **In Arrange Area you can reverse a combination of selected note clips/tracks and audio clips/tracks in one go!**

There are two different types of Reverse functions for note clips: the "Reverse notes graphically" and the "musical reverse". The "Reverse notes graphically" function considers the note lengths when the new start positions are calculated, whereas the "musical reverse" function only considers the notes' start positions.

▶ **Select or deselect "Reverse Notes Graphically" on the User Interface tab in Settings to select the desired way of reversing notes.**


▶ **Select the desired events/clips/tracks and then select "Reverse" from the Edit menu (or from the clip/track context menus in Song/Blocks View).**

Here is an example of a masked note clip in Edit mode, with automation points before and after using the “Reverse notes graphically” function:



As you can see, all end positions (Note Offs) of the notes become the new start positions (Note Ons) after the reverse procedure. Also, any masked notes and automation points are also “flipped around”.


Here are examples of using the Reverse functions on a selected note clip and on selected notes in a note clip:



A note clip selected before reversing.

The note clip reversed using the “Reverse notes graphically” function.

The note clip reversed using the “musical” Reverse function. Here, only the notes’ start positions are mirrored.



Selected notes in a note clip before reversing.


The selected notes reversed using the “Reverse notes graphically” function.

The notes reversed using the “musical” Reverse function. Here, only the notes’ start positions are mirrored.

Multi Lanes editing

Overview

Multi Lanes editing lets you have note clips of multiple lanes visible at the same time on the Edit pane, in a layered fashion. This makes it a lot easier to edit notes in relation to other notes in other clips on other lanes/tracks:




Four clips on four different lanes in Multi Lanes edit mode, with the note lane on the EuroBass tack currently selected.

Selecting multiple lanes for editing


The easiest ways of selecting what note lanes should be available for Multi Lanes editing are these:

- **By selecting multiple instrument tracks, by [Cmd](Mac)/[Ctrl](Win)-clicking in the track list and then entering the Edit Area in the Sequencer.**
- **By selecting multiple note clips on the Arrange pane and pressing [Return], or right clicking one of the selected clips and then selecting "Open in Edit Area" from the Edit or context menu.**


▶ **In the Edit Area, make sure the Multi Lanes button is on:**



The Edit pane now shows all (un-muted) clips on all selected lanes in a layered fashion, with the notes of the currently selected note lane in red and the notes of the other lanes in dark gray:



▪ **If a single sequencer track contains multiple lanes, selecting the track will automatically display all clips on all un-muted lanes:**




The RnB Kit 03 track, which contains six lanes, selected for Multi Lanes editing.

▶ **With the Multi Lanes editing feature, the functions "Move/Duplicate Selected Notes to New Lane" and "Extract Notes to Lanes" are very useful, especially when working with drum tracks.**

Editing notes in Multi Lanes mode


Editing notes in Multi Lanes editing mode is done in the same way as when editing one clip on one lane at a time, as described earlier in this chapter. The only important thing to bear in mind is which lane you want to edit:

▶ **Select the lane you want to edit, either by clicking the desired Lane selector in the track list...**



The lane on the EuroBass track is currently selected.

▶ **... or by clicking a note on the Edit pane:**



The notes of the currently selected EuroBass lane shown in red on the Edit pane and the notes of the other lanes are shown in gray.

▪ **If you click any of the gray notes on the Edit pane, the lane that this note belongs to is automatically selected in the track list.**
Now, all notes of the newly selected lane become red, and the notes of the other lanes become gray.


! **It's not possible to edit multiple notes on multiple lanes together - only notes of the currently selected lane can be edited together (e.g. moved, transposed, etc.).**

! **If the tracks selected for Multi Lanes editing has different Note Edit Modes (e.g. REX Edit View or Drum Edit View), you might want to switch to regular Key Edit View for the entire note range to become visible and accessible on the Edit pane. See "Note Edit View Modes" for more details.**

Automation editing

Overview

Parameter automation is stored in clips as automation events (points), connected by lines. When recorded or drawn, the automation lines are straight. However, if you wish you could edit the lines into curves afterwards.



Automation lanes for a Mix Channel device Level slider (bottom), FX1 Send Level knob (middle) and FX1 Send On/Off button (top) in the Arrange Area. The Level automation clip at the bottom is open for editing.

- **Parameter automation is contained in automation clips on Parameter Automation Lanes (see "Edit Area elements").** Each automated parameter has its own Parameter Automation Lane.
- **Performance controller automation is stored on Performance Controller Edit Lanes in note clips (see "Edit Area elements").**


Editing parameter automation

Parameter automation events can be edited in the Arrange Area if they are contained in separate parameter automation clips on parameter automation lanes. If the automation is contained inside a note clip (e.g. performance controllers, such as Mod Wheel, Pitch Bend etc.) the automation has to be edited in the Edit Area.

In the Arrange Area the parameter automation clip can be opened for editing in the Arrange Area. Double clicking an automation clip in the Arrange Area opens it and shows the automation events of the selected clip. You can also edit the parameter's Static Value. Editing automation events works in the same way, whether in the Arrange Area or in the Edit Area.

Editing parameter automation clips in the Arrange Area

▶ **In the Arrange Area, double-click the parameter automation clip on the parameter automation lane.**
The parameter automation clip is now opened in the Arrange Area:




A parameter automation clip before and after opening it in the Arrange Area.

Here you can edit the parameter's Static Value (see "Static Value handle") with the up/down arrow buttons to the left of the open clip. Alternatively, double-click the control and type in a new Static Value in the box.


In the open parameter automation clip, it's possible to move, add and delete automation events in the same way as in the Edit Area, using the Selection (Arrow), Pencil and Eraser tools - see "Editing parameter automation in the Edit Area".

- **A selected automation event's position and value is also shown in the Arrange Area Inspector.**



The event's position and value can be edited numerically in the displays - see "Note and automation editing in the Inspectors".

- **To close an open parameter automation clip in the Arrange Area, press [Esc] or click on another lane in the Arrangement Area.**
- **If you resize the automation clip and make it longer, the first and/or last automation value will be extended all the way to the clip boundary.**



In the picture above, a Mixer 14:2 Mute button is automated. The clip only contains a single automation point, but as we extend the clip in both directions, the value is automatically extended to the start and end of the clip. This means you can adjust the Mute automation time by moving and resizing the clip, without having to open the clip.

Editing parameter automation in the Edit Area

By default, only performance controller automation (i.e. Velocity, Mod Wheel, Pitch Bend, Sustain Pedal, Aftertouch, Expression and Breath Control) are automatically recorded into note clips. Other parameters, such as device panel controls, are normally recorded in separate clips on separate Parameter Automation Lanes in the Song/Blocks View.


However, it is possible to edit automation for device panel parameters also in the open clip in the Edit Area. This is especially useful if you have already recorded the device panel parameter automation into the note clip, using the "Record Automation Into Note Clips" function on the Options menu (instead of as separate parameter automation clips on automation lanes), see "Recording parameter automation into note clips".

1. **Double click a note clip on the Arrange pane to open it in the Edit Area.**
   Automation events (if available) are located at the bottom of the Edit Area, below the gray divider.

2. **Select which automation to display by selecting the corresponding parameter from the Controller selector:**




   Let's say we have recorded some automation for Parameter 1 of an ID8 instrument device. Now we want to edit the automation so therefore we select Parameter 1 from the Controller selector:



The "Parameter 1" automation open for editing in the Edit Area.

   In the Edit Area, the parameter's Static Value is shown to the left in the automation lane. In this example, the Static Value is set to 20 - this means that the "Parameter 1" value will be set to 20 everywhere in the song except where there are automation clips for the parameter.

▶ **To change the Static Value, click and drag the handle up or down, or double-click and type in a new value.**
To fine adjust the Static Value, hold down [Shift] when you click and drag.



▶ **The Static Value can also be edited in the Song/Block view, see "Editing parameter automation clips in the Arrange Area".**

3. **When a note clip is open, you can select, move, copy or delete automation events, using the Selection (Arrow) Tool.**
   When moving automation events with the Selection (Arrow) Tool, Snap (see "Snap") is taken into account if enabled. You can also resize the clip by dragging the clip handles.

▶ **If you resize the note clip and make it longer, the duration of the first or last automation event will be extended all the way to the clip boundaries (see the last example in "Editing parameter automation clips in the Arrange Area").**


▪ **A selected automation event's position and value is also shown in the Edit Area Inspector.**
These values can be edited numerically in the Edit Area Inspector displays.

Drawing parameter automation events

To add new parameter automation events, do any of the following:


- **Double click with the Selection (Arrow) Tool in the open automation clip to insert an automation point.**
  Double click, hold, and then drag to draw a series of automation points in the clip.
- **Click or drag with the Pencil Tool in the open automation clip.**
  When dragging, the resulting curve (i.e. the number of points) depends on two factors; the selected "Automation Cleanup" setting on the "User Interface" tab in Settings (see "About Automation Cleanup"), and the snap value if Snap is activated (see "Snap").
- **To add an additional automation point onto an existing automation line, hold down [Shift] and click with the Pencil tool at the position you want the point to be added.**
  This is also useful if the automation clip doesn't yet contain any automation points, and you want to add the first automation point with the same value as the Static Value.

! **Note that if the automation line is curved (see "Creating curves between automation points"), the line will become straight (not curved) to the right of the added point.**




Three examples of Shift-clicking automation points with the Pencil tool: adding the first point in an empty clip, adding a point on a straight line and adding a point on a curved line.

- **Holding down [Ctrl](Win) or [Option](Mac) and clicking or dragging with the Pencil tool will insert an automation range (the same parameter value over a period of time).**
  The length of the range is set with the Snap value.



Drawing an automation range.

- **When the automated parameter is "stepped" rather than continuous, there will be abrupt steps between the automation events instead of linear ramps.**
  Examples of stepped parameters could be device buttons and multi-mode selectors, and the Sustain Pedal performance controller.



Stepped automation.

About drawing parameter automation events outside an open clip


If you draw parameter automation events outside the boundaries of an open clip, the same rules apply as when drawing note events outside an open clip. See "About drawing notes outside an open clip".

Creating curves between automation points

When you record or draw automation, the lines between the automation points are always straight (vectors). This works perfectly fine in most situations. However, if you like you could change the straight lines into curves, to create different character to your parameter automation.

Creating curved automation works both in the Song/Blocks View and in the Edit Area.

1. **Open an automation clip (in the Arrange Area or a note clip in the Edit Area).**
2. **With the Selection (Arrow) tool selected, click and drag an automation line to make it curved:**
   The arrow switches to a "curve tool" as you hover over an automation line.



Creating curved automation in an automation clip open in Song View.

- ▶ **To edit the curve shape, repeat the procedure above and drag in the desired direction.**
- ▶ **To make a curve straight again, hold down [Shift] and click the automation line.**
- ▶ **Double click an automation curve/line to add an automation point on the line.**

! **Note that it's not possible to create a curve from a straight horizontal automation line (which has automation points with the same value).**

Deleting automation events


- ▶ **Deleting automation events is done in the same way as when deleting note events. I.e. click on events to select them or draw selection rectangles and then press [Backspace] or [Delete] - or use the Eraser tool (see "Deleting notes").**
- ▶ **To clear all automation events in a clip, hold down [Ctrl](Win) or [Cmd](Mac) and press [A] to select all events, then press [Backspace] or [Delete]. Alternatively, delete the clip (or remove the whole lane to clear all automation for that parameter).**
- ▶ **If you want to delete single parameter automation events, you can double click on an event with the Selection (Arrow) tool in the clip.**

Reversing automation events

It's possible to reverse the order of selected automation events in an open note or automation clip, see "Reverse".

Editing performance controller automation

- **To edit, draw or delete performance controller events, open the note clip in the Edit Area.**




Performance controllers (Mod Wheel in the example above) are shown on the currently selected Controller Lane at the bottom of the open note clip. The performance controller curves are also indicated in the clip in the Arrange Area.

- **You can edit performance controller events using the Selection (Arrow), Pencil and Eraser tools, just like when editing parameter automation events in the Edit Area (see "Editing parameter automation in the Edit Area").**

Creating new performance controller automation lanes


If you want to manually draw performance controller automation events for a controller which hasn't already been automated, you just select the desired parameter in the Controller selector:

1. **Open the note clip in the Edit Area.**
2. **Select the new controller to be automated by clicking the Controller selector and selecting the desired controller from the pop-up list that appears:**



In this example, we select Aftertouch.


3. **A new Performance Controller Edit lane is created for the Aftertouch controller:**



4. **Now, you can draw Aftertouch performance controller events in the clip using the Pencil Tool as described in "Drawing parameter automation events".**
   Afterwards, you can edit the performance controller events the same way as with regular parameter automation events (see "Editing parameter automation in the Edit Area").

▶ **It's also possible to add any of the available device panel parameters as performance controllers.**
Just select the desired parameter from any of the sub-menus at the bottom of the Controller selector.


! **If you have automated the same parameter, both as a performance controller inside the note clip and as a separate parameter automation clip in the Song/Blocks View, the parameter automation clip in the Song/Blocks View takes precedence (overrides the performance controller automation:**



The Volume automation in the clip in the Song/Blocks View overrides the Volume performance controller automation.

Deleting performance controller automation lanes

▶ **To delete a performance controller automation lane, select it in the Controller selector and then click the Clear button:**



This brings up a confirmation alert if there is data on the lane. You can delete without the alert by pressing [Ctrl](Win) or [Cmd](Mac) when you click the Clear button.

Hiding the performance controller automation lane

▶ **To hide the performance controller edit lane (to make more room for the note edit lane), select "Hide" from the top of the Controller selector list:**




! **Note that this only hides the performance controller edit lane visually. Any performance controller automation will still remain and have effect.**

About Automation Cleanup


Automation Cleanup is a function for controlling the amount of parameter automation events that should be created during recording and/or manual drawing. The Automation Cleanup function applies to parameter automation events as well as to performance controller automation events. The Automation Cleanup level can be set on the "User Interface" tab in Settings and will apply to all new recorded automation events. You can also use the function on previously recorded parameter automation events.

Automation Cleanup in "Settings"

- **If you feel you get too many automation events when recording or drawing events, you can adjust the "Automation Cleanup" setting on the "User Interface" tab in Settings to "Heavy" or "Maximum":**




This automatically removes superfluous automation events next time you record or draw events and simplifies the curves. Note that Snap (see "Snap") also governs the number of events when drawing events.



Drawing automation with "Normal" Cleanup (left), and with "Maximum" Cleanup (right).

The "Cleanup Automation" function

You can also apply automation cleanup to already recorded/drawn events. This is done on the clip or automation event context menu - or on the Edit menu for selected clips/automation events:



The Cleanup Automation function.


The "Automation Cleanup" function can be applied to:

- **Individual (selected) parameter automation events in an open clip.**
  This is done in the Edit Area for performance controllers. For parameter automation, it's normally done in the Arrange Area.
- **All parameter automation events in one or several selected clips.**

- **All parameter automation events in all clips on one or several selected tracks.**


Editing pattern automation

Pattern automation clips are viewed and edited in the Pattern Select lane, which is available on Dr. Octo Rex, Redrum and Matrix tracks, for example:



Pattern changes are shown as clips with a Pattern Selector at the top (when the clip is selected). A single pattern automation clip can only contain data for a single pattern. In practice this means that each pattern automation clip only contains one pattern automation "event". All pattern changes in the song will therefore require unique clips.

- **Pattern (group and number)**
  The Pattern (group and number) indicate which pattern in the source device is playing in this clip. For Dr. Octo Rex devices, the Bank is of no importance.
- **Pattern Selector**



  Click the Pattern Selector triangle, or double-click anywhere in the clip, to bring up a pop-up list featuring all available patterns (groups and numbers) of the source device. Select another pattern from the list if you wish to change pattern in the selected clip. If several pattern clips are selected, selecting a pattern for one of them will set them all to play that pattern.
- **Clip Resize handles**
  Click and drag any of the Clip Resize handles horizontally to resize the clip and thus change the pattern playback start position and/or duration.


! **If there is pattern automation for a device, it will only play patterns where there are pattern clips.**

Drawing pattern automation


You can draw pattern automation clips on a Pattern Select lane as follows:

1. **Activate Snap and set the Snap value to the note position where you want to insert the pattern change clip (see "Snap").**
   It is probably a good idea to set the Snap value to "Bar", at least if you are working with patterns of a length corresponding to the time signature (e.g. 16 or 32 step patterns and 4/4 time signature). However, if you are working with patterns of another length, it can make sense to use other Snap values when drawing pattern automation clips.

2. **Select the Pencil Tool.**
   A Pattern/Loop drop-down list appears in the Inspector. Use this to select the pattern you wish the clip to play. For Dr. Octo Rex devices, the Bank is of no importance.



3. **Draw a clip for length you want the selected pattern to play.**



4. **Continue using the same method to draw clips for all the patterns you wish to use.**


▶ **Don't draw pattern change clips with Snap turned off, unless you want chaotic pattern changes!**

▶ **If you want to add single pattern change clips, you can also double click with the Selection (Arrow) tool on the Pattern Select lane.**
This will create an empty pattern change clip with the length of the current Snap value setting (e.g. 1 bar). To create longer clips, double click, keep the mouse button pressed and drag to the right.

Moving, resizing and duplicating pattern automation clips


- **You can move, resize and duplicate pattern automation clips in the same way as with note or automation clips.** However, it is recommended that Snap is activated (and in most cases set to "Bar") when you do this (see "Snap").

! **If you resize a pattern automation clip by clicking and dragging the left resize handle, and thus change the start position, the clip will be masked (just like a note clip). This means the pattern won't necessarily begin on beat 1. A selected pattern automation clip that has a masked start position will indicate this in the Pattern Offset display in the Inspector.**



A pattern automation clip drawn between bar 1 and 5.

Now, if we resize the clip by dragging the left resize handle two beats to the right, the Pattern Offset will change but the pattern will play back as expected:



The same pattern automation clip "resized" to begin at beat 2.

- **You can also move or duplicate pattern automation clips using the Cut, Copy and Paste commands on the Edit menu or context menu.**
  Again, the same rules apply as for note and parameter automation clips.

Deleting pattern automation clips

▶ **Deleting pattern automation clips is done in the same way as deleting note clips. I.e. you can select or draw selection rectangles and then press [Backspace] or use the Eraser tool etc.**

▶ **To clear all automation in a clip, simply delete the clip (or remove the whole lane to clear all pattern change automation on the track).**

The “Convert Pattern Automation to Notes” function

If you have recorded or drawn pattern automation on a Redrum or Matrix track, you can automatically convert the whole pattern automation lane into note events on an additional note lane. Proceed as follows:

1. **Select the track with the pattern automation.**
2. **Select “Convert Pattern Automation to Notes” from the Edit menu or the track’s context menu.**
   For each pattern automation clip, the corresponding device pattern is converted to note clips on an additional note lane on the track. The generated note lane will play back just the same as when you played the pattern device with the pattern changes.

- **The pattern automation lane is automatically muted after this operation.**
  You can later go back to pattern automation if you wish, by turning on the pattern lane again.

Redrum specifics:

- **The “Enable Pattern Section” switch on the Redrum device is automatically turned off when you use the “Convert Pattern Track to Notes” function.**

Matrix specifics:

- **Make sure that the correct track is selected (normally the track for the device that the Matrix is connected to)!**
  Creating notes for the Matrix itself is pointless, as the Matrix cannot produce any sound.
- **You may want to disconnect or even remove the Matrix device after performing this function.**
  This is because you probably don’t want both the Matrix and the sequencer notes to play the device at the same time.

Editing tempo automation

Tempo automation is edited in the same way as regular parameter automation. See “Editing parameter automation”.

Drawing tempo automation events

Drawing tempo automation events is done in the same way as drawing regular parameter automation events. See “Drawing parameter automation events”.



About tempo changes and tempo automation of audio tracks

The built-in Stretch function allows you to change the tempo of the song without affecting the pitch of the recordings on the audio tracks. This is great if you want to adjust the tempo after you have recorded your audio tracks. In Reason, the Stretch is enabled by default for all audio clips.

! **The Stretch function also affects the sonic result when transposing audio clips using the Transpose function (see "Transposing Audio Clips").**

There are three selectable Stretch and Transpose Type algorithms which are suitable for playing back different types of audio material:

- **The "Allround" Stretch and Transpose Type is suited for most types of polyphonic audio material.**
- **The "Melody" Stretch and Transpose Type is best suited for sources sounding one note at a time e.g. solo instruments.**
- **The "Vocal" Stretch and Transpose Type is best suited for stretched and/or transposed vocal material.**
  In the "Vocal" Stretch and Transpose Type the formants of the original vocal are preserved, which prevents the vocal from sounding artificial when transposed and/or stretched.

▶ **Select "Stretch and Transpose Type" from the Audio Track context menu or from the Edit menu.**

Stretch preview vs. high quality stretch

Stretch and transposition of audio are always made in two parallel steps: a real-time "preview" so that you can instantly hear the result of your tempo changes or transpositions, and a high quality stretch "in the background" to further improve the sonic results. As soon as high quality stretch is in progress, the "Calc" indicator on the Transport Panel shows a progress indicator:



The CALC indicator appears when Reason performs high quality stretching of audio.

Since the high quality stretch is performed in the background, you can still continue to work with your song without any interruption. When the high quality stretch is finished, the "Calc" indicator goes out and the high quality audio automatically replaces the "preview" audio.

About disabling Stretch for audio clips

In some situations, you might want to exclude audio clips from tempo automation. For example, if you have recorded dialogue or sound effects that shouldn't adapt to tempo changes. In such situations, you can select the audio clip(s) you want to exclude from the tempo changes and select "Disable Stretch" from the Edit menu or clip context menu.

! **Note that disabling stretch does not affect the Transpose function for audio clips!**


Automating time signature

Time signature automation events can only be manually drawn with the Pencil tool - not recorded like tempo automation, parameter automation or performance controller automation. A single time signature automation clip can only contain a single time signature value. In practice this means that each time signature automation clip can only contain one time signature automation "event". All time signature changes in the song will require a unique clip.

1. **Set the desired time signature in the Signature display on the Transport Panel.**
   This will be the Static Value, i.e. the time signature of the song wherever there is no clip present on the time signature automation lane.
2. **Hold down [Alt](Win) or [Option](Mac) and click in the Signature display on the Transport Panel.**
   This will select the Transport track and create a time signature automation lane in one go. The Signature display will also be displayed with a green border, indicating that the time signature has been automated.

▶ **It is generally a good idea to activate Snap (see "Snap") and have the Snap value set to "Bar" when drawing clips.**

3. **Select the Pencil Tool.**
   When the Pencil tool is selected, a Time Signature drop-down list appears in the Inspector. Select the desired time signature from the drop-down list.




▶ **If you select "Other" the Time Signature dialog appears where you can specify another time signature.**



The available signatures are: 1/2-16/2, 1/4-16/4, 1/8-16/8 and 1/16-16/16. The Time Signature display in the dialog can be edited according to the descriptions in "Transport Panel segment displays".

4. **Draw a clip over the area on the Time Signature lane on the Transport track where you want the time signature to change.**
   The time signature will change for the duration of the clip.



5. **Continue using the same general method wherever you want the time signature to change in your song.**

▶ **If you want to add single time signature clips, you can also double click with the Selection (Arrow) tool on the Time Signature lane.**
The clip gets the length of the currently selected Snap value.

▶ **You can change the time signature for the automation clip at any time by simply double-clicking the clip with the Selection (Arrow) Tool and changing the value on the pop-up that appears. Alternatively, select the clip and then click the small triangle in the clip to bring up the time signature pop-up.**

Moving, resizing and duplicating time signature automation clips

- **You can move, resize and duplicate time signature automation clips in the same way as with note or automation clips.**
  However, it is recommended that Snap is activated (and in most cases set to "Bar") when you do this.
- **You can also move or duplicate clips using the Cut, Copy and Paste commands on the Edit menu or context menu.**
  Again, the same rules apply as for cutting, copying and pasting note and parameter automation clips.

Deleting time signature automation clips


- **Deleting time signature automation clips is done in the same way as deleting note clips. I.e. you can select or draw selection rectangles and then press [Backspace] or [Delete], or use the Eraser Tool.**
- **To clear the time signature automation in a clip, simply delete the clip (or remove the whole Time Signature Lane to clear all time signature automation on the track).**

Note and automation editing in the Inspectors

In the Inspector you can edit note and automation events numerically using the displays.

Editing notes and events in the Inspectors

If you select a note in the Edit Area, four displays in the Edit Area Inspector show the event (start) Position, Length, Note number and Velocity value:



If you select a parameter automation event, two displays appear in the Arrange Area Inspector, showing the event's Position and Value:



If you select a pattern automation clip, three displays appear in the Arrange Area Inspector, showing the clip's Position, Length and Pattern Offset:




- ▶ **Edit the values by clicking on a segment in a display and then drag up/down, use the up/down spin controls, or type in new values. Snap is not taken into account.**
  See "Inspector segment displays" for details on how to edit in the Inspector displays.
- ! **Note that when moving the position of events, these may end up outside the clip and be masked (not played). There will be no warning or indication if this should happen. However, since the clip is open in the Edit Area, you will be able to see if events are masked.**
- ▪ **If the Tick segment in the Position and/or Length displays shows an asterisk (*), it means that the value is a fraction of a Tick - a subtick. See "About subticks in the Position and Length displays" for more info.**

Editing values for multiple notes or events in the Inspector

When you edit values for several selected events, the changes will always be relative. For example, if you change the position, length, pitch or velocity when several notes are selected, they will all be changed by the same amount, retaining their relative values.

- ▪ **If several events are selected, the displays will show the values for the event with the earliest start position in the song.**
  If several selected events have the same start position, the displays will show the values for the event with the lowest Note value (for note events) or lowest Value (for automation events).
- ▪ **If several events are selected and any of their values differ, Match Value buttons appear next to the corresponding display.**
  See "Matching notes or events using the "Match Values" function".

Matching notes or events using the “Match Values” function



The Match Values buttons appear as ‘=’ symbols in the Arrange Area Inspector (left) or as buttons in the Edit Area Inspector (right).


The “Match Values” function in the Edit Area and Arrange Area Inspectors can be used for matching the positions, lengths and velocities of several selected note events to the position/length/velocity of the selected event with the earliest start position in the song. It’s always the values of the earliest event that are shown in the displays. Similarly, automation events can be matched to the position and/or value of the earliest selected automation event in the song.

If several selected events have the same start position, the matching will be to the values for the event with the lowest Note value (for note events) or lowest Value (for automation events).

Matching notes


Here’s an example on how to match note values:

1. **In the Edit Area, select several notes.**



Four selected notes in the Edit Area.

2. **Click the respective Match Values button to achieve the following results:**



Position values matched


Length values matched

Velocity values matched

Matching parameter automation events

Matching parameter automation event values can be useful if you want an automated device parameter to be modulated to the same value throughout the clip, for example. It could also be useful if you want to create an instant "jump" between two values. Matching parameter automation events is done in the Edit Area Inspector for performance controller events and in the Arrange Area Inspector for regular track parameter automation.


- **Let's say you want to modulate a parameter to a maximum value of 80 several times throughout the clip. Then, just select all "max value" events, click the "Match Values" button and then adjust the Value to 80 for the selected events.**



Matching Values for a performance controller using the Edit Area Inspector (in the Edit Area)

Matching automation events positions could also be useful:

- **If you want to match the positions of two adjacent automation events in a clip to create an instant "jump" between the two values.**



Matching Positions for track parameter automation events using the Arrange Area Inspector (in the Arrange Area)

Note that matching the positions of more than two automation events in a single clip is not really useful. It will only place them in a "pile" on the same position. The effect during playback would be an instant jump between the extreme values. In practice, all events in between the extreme values would be disregarded.

Chapter 11
Working with Blocks in the Sequencer

About this chapter

This chapter describes how to work with Blocks and Block Automation Clips in the main sequencer. Basic sequencer functions, recording, editing clips and events and arranging in the sequencer are described in detail in the chapters "Sequencer Functions", "Recording in the Sequencer", "Audio Editing in the Sequencer", "Note and Automation Editing" and "Arranging in the Sequencer".

Introduction

The arrangement in the sequencer has two basic views: the Song View (which is exactly the same as the "Arrange Mode" in previous Reason versions), and the Block view. The Block View is designed for creating shorter multi-track "sections" that can be repeated anywhere in the song arrangement. In most situations a Block would probably consist of 4-8 bars.

An analogy to a Block would be a traditional drum machine pattern where you would record several (drum) instrument tracks and save as a complete "pattern". Then, you would build up your song arrangement by arranging your patterns, one after another, with repetitions etc.


The Song and Block Views share the same Track List but use separate clips and recordings. Any track and clip types can be used when working with Blocks, e.g. instrument tracks with note clips, audio tracks with audio clips, automation tracks with parameter automation clips and pattern tracks with pattern automation clips.

32 different Blocks are available in the program and each Block can be reused and repeated in the song arrangement as many times as you like. By working with Blocks you can create complete verse and chorus blocks and arrange and reuse them as desired in the song. When you arrange your Blocks in the song - using Block Automation Clips - you can also choose to temporarily mute desired lanes for the duration of each Block Automation Clip to create variations.

The idea behind Blocks

Working with the sequencer in a "pattern based" fashion appeals to many users. It is the way traditional hardware sequencers worked when they were first introduced on the market. The linear working method of most software sequencers also have many advantages. So, why not combine these two basic working methods to get the best of both worlds!


A very neat way of working with Blocks is by combining Block data with regular linear song data. In the picture below, Block data is being used as base for the song. Then, a number of shorter linear clips are used to override parts of the Block data to introduce nice variations in the song:



Linear clips override Block data to create nice variations in the final arrangement.

Arrangement Views

Song View (with Blocks disabled)




The sequencer in the Song View.

This is the Song View, which is the same as "Arrange Mode" in older versions of the program. Here you work with your song in a linear fashion, by recording and arranging your clips from the start of the song to the end. Songs created in previous versions of the program will automatically open up in the Song View, so it will all look very familiar.

Song View (with Blocks enabled)

When you create a new song, or a song from a template, the sequencer will automatically have the Blocks function activated. However, if you open a song that was previously saved with the Blocks function off, you will have to manually activate Blocks:

- **Select "Enable Blocks" on the Options menu to enable the Blocks function.**




The sequencer in Song View with "Enable Blocks" activated

With Enable Blocks activated on the Options menu, an additional track - the Blocks Track - becomes available above the Transport Track. On the Blocks Track you can arrange your Block Automation Clips once you have recorded your Blocks. There are also two buttons to the left on the Blocks Track in the Track List: the Block and Song View buttons.

Block View

▶ **Click the Block button on the Blocks Track to switch to the Block View.**
A colored area appears on the arrangement pane with the Block name at the top on the Blocks Track. By default, the Blocks are named "Block n" where "n" is a number between 1 and 32. If you like, you can rename your Blocks to more suitable names (see "Renaming Blocks"). The Block View is where you record the clips you want to include in a specific Block. The clips present in the colored Block area in the Block View are unique only to that specific Block.



The sequencer in Block View


! **The Song View and Block View share the Track List. However, the clips on the lanes are unique to the respective views. This means you can have clips in the Song View "on top" of clips in Blocks. See "Combining Block Automation Clips with Song Clips" for more details.**

Editing Blocks in the Block View

Selecting a Block for editing

Selecting a Block for editing is done in the Block View. Select the Block you want to work with as follows:

1. **Make sure "Enable Blocks" is activated on the Options menu.**
2. **Click the Block button on the Blocks Track to switch to Block View.**
Block 1 appears by default on the arrangement pane:



3. **Select a Block (1-32) from the Blocks drop-down list in the Track List if desired.**
In this example, we will stick to Block 1. The Block name is shown on the Blocks Track.



Renaming Blocks

If you don't want to use the default Block names you can easily rename them:


▶ **Double-click the Block name on the Blocks Track in the Block View, type in a new name and press [Return].**



Defining the Block length

The length of a Block is defined using the End Marker in the Blocks view:

1. **Select desired Block in the Block View as described in "Selecting a Block for editing".**
2. **Adjust the End Marker to the desired position by clicking and dragging it in the Ruler.**



- **The Block length is always defined from the beginning of the Ruler to the End Marker.**
  The Left and Right Loop Locators have no influence on the Block length.
- **When the sequencer is running in Block View, it will automatically loop at the End Marker.**
  The Loop Locators can also be used in Block View to loop at other positions, if Loop On/Off is activated on the Transport Panel. However, in Song View the Loop Locator settings used in the Block View will be ignored.
- **The Block length can be set individually for each of the 32 Blocks.**
- **The Block length can be changed at anytime by adjusting the End Marker in the Blocks view.**

Changing Block color

Selecting separate colors for your blocks can be useful when you arrange your blocks in the Song View later on. All 32 Blocks already have default colors but these can easily be changed:

▶ **Select a color from the Block Color palette on the Blocks Track context menu or from the Edit menu.**
This applies the selected color to the Block. The sequencer tracks and any clips in the Block will maintain their original colors.

Recording in the Block View

Recording on tracks in the Block View is done in the same ways as when recording in the regular Song View.

! **Any events or recordings to the right of the End Marker in the Block View will be ignored when the Block is played back in the Song View.**

Refer to "Recording in the Sequencer" for details about recording.

Editing clips in the Block View

Editing events in clips in the Block View is done in the same way as when editing clips in the Song View.

▶ **Double-click desired clip to open it for editing in the Edit Area.**
Refer to "Note and Automation Editing" and "Audio Editing in the Sequencer" for details about editing clips.

Arranging clips in the Block View

Arranging clips in the Block View is done in the same ways as when arranging clips in the Song View.

! **Any clips, or parts of clips, to the right of the End Marker in the Block View will be ignored when the Block is played back in the Song View.**

Refer to "Arranging in the Sequencer".

Arranging Blocks in the Song View


Once you are finished with your clips on the tracks and lanes in the Block View, it is time to arrange the Blocks to build up your song in the Song View. Setting up the Blocks and their playing order is done by creating Block Automation Clips on the Blocks Track in the Song Arrange view.

The following section describes functions and routines that are specific to Block Automation Clips. General clip handling procedures (e.g. naming, coloring etc.) are described in the general "Clip handling" section.


Creating Block Automation Clips

A Block Automation Clip is very similar to a Pattern Clip (for a Redrum device, for example). A Block Automation Clip defines which Block should play back, and for how long. To create Block Automation Clips, proceed as follows:

1. **Click the Song button to switch to the Song View.**




2. **Select the Pencil tool.**
   The Block selector appears in the Arrange Area Inspector:



3. **Select desired Block (1-32) from the Block Selector List.**
   In this example, we will use Block 1.

4. **Draw a clip on the Blocks Track.**
   This creates a Block Automation Clip which instructs the sequencer to play back the events you have previously recorded in Block 1:



A Block Automation Clip drawn on the Blocks Track in the Song View.

The contents (clips and events) of Block 1 are displayed on the respective sequencer tracks in a ghosted fashion on a colored background. This way you will see what events and/or recordings the Block will play back. This also allows for muting of individual lanes in the Block (see "Muting lanes in Block Automation Clips").

- **If you don't want to see the ghosted contents of the Block clips in the song arrangement in the Song View, you can disable this on the User Interface tab in Settings, see "Show Block clip content in Song View".**

The following rules apply to Block Automation Clips:

- **If the Block Automation Clip is longer than the actual Block length (defined by the End Marker in the Block View), the Block is repeated over and over for as many times as necessary.**
  In the picture above, the Block length is 8 bars and the Block Automation Clip is 20 bars. This means that Block 1 is repeated at bars 9 and 17. The repetitions are indicated with thin vertical lines in the Block Automation Clip and on the sequencer tracks (similar to a Pattern Automation clip).
- **If the Block Automation Clip is shorter than an even multiple of the Block length, the remaining content of the Block is masked out (muted) in the Song View arrangement.**
  In the picture above, the last 4 bars of the third repetition are masked out.

▶ **If you want to add single Block Automation Clips, you can also double click with the Selection (Arrow) tool on the Blocks Track.**
The clip gets the length of the currently selected Snap value. To create longer clips, double click, hold and drag to the right.

Resizing Block Automation Clips

As with other clip types Block Automation Clips can be resized by clicking and dragging the clip handle(s) with the Selection (Arrow) tool or by editing the Position and Length values in the Inspector.

- **If you resize a Block Automation Clip by clicking and dragging its left clip handle, and thus changing its start position, the Block Offset will change.**
  This means that the Block Automation Clip could start playing in the middle of the Block, i.e. not from the beginning. The picture below shows a Block Automation Clip before and after resizing the start position:




Changing the start position by resizing a Block Automation Clip

In the example above, the Block Automation Clip will begin playing at Bar 7, and will start playing back the events that begin at Bar 7 in the Block.

- **If a Block contains sequencer tracks that use Pattern Automation (a Redrum track, for example), a Block Offset will make the pattern start playing back from the correct position within the pattern and sound just as you would expect.**

Reassigning Blocks in Block Automation Clips

▶ **To assign another Block to an existing Block Automation Clip, click the small triangle button on the Block Automation Clip and select another Block from the drop-down list:**




The Block Automation Clip color changes to the color of the new Block and the ghosted clips on the tracks switch to show the contents of the new Block.

Muting lanes in Block Automation Clips

When you have arranged your Block Automation Clips as desired on the Blocks Track, it is possible to mute individual lanes contained in any Block. These lanes will remain muted until the end of the Block Automation Clip.


This way you can use the same Block to create a song intro, by gradually introducing more and more sequencer tracks/ lanes. The example below shows how to mute lanes in individual Block Automation Clips to create a song intro.

We are going to use one single Block - Block 1 - to create a song intro. The Block is 8 bars long and uses four sequencer tracks. In the Block View we have recorded on all four sequencer tracks:



Block 1 in the Block View with four sequencer tracks.

Now, we want to arrange our song so we switch to the Song View and draw an 8 bar Block Automation Clip on the Blocks Track:




An 8 bar Block Automation Clip assigned to Block 1.

In our intro we want the Piano and Bass track to play the first eight bars. In the next eight bars we want to have the drums playing as well. Then, we want the song to continue for another 16 bars with all tracks playing except the Piano track.


To achieve this, we need to create several Block Automation Clips that play back the same Block. This is because when we're going to mute lanes later on, we need to define for how many bars we want the mutes to be active. The duration of the mutes are defined solely by the lengths of the Block Automation Clips.

We begin by copying and pasting the Block Automation Clip twice. Then we resize (expand) the last Block Automation Clip to 16 bars:



The Block Automation Clip assigned to Block 1 copied and pasted twice, with the last Block Automation Clip resized to 16 bars.

Now, we want to mute individual lanes for the duration of each Block Automation Clip to create our intro. We select the Mute tool from the Toolbar and click on the lanes we want to mute in each Block Automation Clip:



Muted lanes throughout the length of each Block Automation Clip.

Now, we have our intro with the Piano and Bass playing the first 8 bars. Then, the song continues for another 8 bars with Piano, Bass and Drums. Finally the song plays another 16 bars with Drums, Bass and Synth Pad. All we needed for this intro was one single 8 bar Block.


! **Note that the lanes will be muted for the duration of each Block Automation Clip. If the Block contents are repeated in the Block Automation Clip, as in the last clip above, the lane will be muted throughout the entire Block Automation Clip length. If you resize a Block Automation Clip, any muted lanes will be resized accordingly.**

Converting Block Automation Clips to Song Clips

After you have arranged your Block Automation Clips in the Song View, you might want to convert the content of the Block(s) to "regular" clips on the sequencer tracks and lanes. There are a few ways of doing this:

Converting single Block Automation Clips to clips in the Song View


1. **Choose the Block Automation Clip(s) you want to convert by selecting it on the Blocks Track.**
2. **Select "Convert Block Automation to Song Clips" from the Edit menu or Block Clip context menu.**
   All unmuted clips in the Block(s) are automatically converted to regular clips on the tracks. The Block Automation Clip and its contents are preserved and left unchanged:



Before and after the "Convert Block Automation To Song Clips" command used on the first Block Automation Clip.

Converting all Block Automation Clips to clips in the Song View

▶ **Select "Convert Block Automation to Song Clips" from the Track List context menu.**
All unmuted clips in all Block Automation Clips are automatically converted to regular clips on the tracks. The Block Automation Clips and their referenced Block contents still are preserved but the Blocks Track is automatically muted. This is made to reduce the clutter on the arrangement pane:



Before and after the "Convert Block Automation To Song Clips" command on the Track List context menu.

▶ **If you want to activate the Blocks Track again, click the "M" button on the Blocks Track.**


Using Cut/Copy and Paste for individual clips

You can of course also use the standard Cut/Copy & Paste functions to copy clips from the Block View to the Song View, and vice versa.

1. **Select the clip(s) on the arrangement pane (in Blocks or Song View).**
2. **Use the standard Cut or Copy command.**
3. **Switch to the other View (Song or Blocks)**
4. **Use the Paste command.**

Combining Block Automation Clips with Song Clips

It's possible to combine Block Automation Clips with regular clips in the Song View. The general rule is that clips in the Song View have priority over Block data. This means that if a clip in the Song View overlaps a (ghosted) clip on the same lane in a Block, the Song Clip will play back and the clip in the Block "underneath" will be silent (masked):




Song clips and Block Automation Clips in combination in the Song View.

If we play back the song in the picture above, this is what we will hear:

- **In Bars 1-8 the song clips on the Piano and Bass tracks will play. Any Block data "underneath" these clips will be silent.**
- **In Bars 9-16 the Block data for the Piano, Drums and Bass tracks will play back since there are no overlapping Song Clips.**
- **In Bars 17-32 the Block data for the Drums, Bass and Synth Pad tracks will play back since there are no overlapping Song Clips.**

Practical tips on combining Blocks and Song Clips

A nice way of working with Block Automation Clips and Song Clips is to first create a couple of Blocks in the Block View and then arrange Block Automation Clips in the Song View. When you have arranged your Block Automation Clips, you could record a couple of shorter Song Clips with variations in the Song View. Then, place these short clips at desired positions in the arrangement to create nice variations in the song, according to the example below:




Short Song Clips combined with Block Automation Clips in the Song View to create nice variations.

- **Since Song Clips automatically mute (mask) the "underlying" Block data, short Song Clips are perfect for introducing temporary variations in a Block based song.**

About Performance Controllers and Parameter Automation

Since the sequencer tracks and lanes are shared between the Blocks and the Song arrangement, the following rules apply regarding Performance Controller and Parameter Automation:

- **Performance Controller and Parameter Automation data in the Song View arrangement always overrides automation in Blocks.**
- **If a sequencer track uses Parameter Automation in the Block, the automation will also affect all clips on the corresponding lanes in the Song View.**
  The picture below shows a piece of an arrangement with an instrument track which has one note lane and one parameter automation lane. The arrangement is built up by Blocks (the ghosted data) and one short Song Clip for variation in bars 28 through 29 (the blue clip on the note lane). The Block uses Mod Wheel Performance Controller automation (the gray line inside the note clips in the Block) and automation of the Rotary 4 parameter (the gray line in the parameter automation clips in the Block):



- **The song only plays Block data from the start to bar 28.**
  During this time, the Rotary 4 automation is active. (However, no notes are played back in bars 1 through 16 since the note lane in the Block is muted.)
- **At bar 17 the note lane is played back together with the Mod Wheel Performance Controller data in the Block.**
  The Rotary 4 automation is still active.
- **At bar 28 the (blue) Song Clip takes over the note playback and Mod Wheel Performance Controller automation.**
  Since the Mod Wheel isn't touched at all in the Song Clip, its value is set to zero. However, note that the Song Clip is still affected by the Rotary 4 automation in the Block!
- **At bar 30 the note clip in the Block takes over again and controls note playback and Mod Wheel Performance Controller automation.**
  The Rotary 4 automation is still active.

Chapter 12
Working with the Rack



About this chapter

This chapter describes the procedures and techniques for managing devices and Device Groups in the rack.

Rack device procedures

Viewing the Rack and the Devices

The Rack shows the devices in your song. This is where you make parameter changes, route cables, add and remove devices and much more.

▶ **To show or hide the Rack, click the Rack button in the top bar or press the [F6] function key.**




- **You can also go directly to a device in the Rack by double clicking a device icon in the Sequencer track list, or in the Track Panel.**
- **You can choose whether you want the Rack to open as an area in the document window (above the Sequencer) or as a separate window.**
  This is done with the setting "Show Rack in Separate Window" on the View menu.

! **Note that the "Show Rack in Separate Window" setting is global and affects all your songs.**


- **When the Rack window has focus, you can quickly close it by pressing [Esc].**

How the devices are shown in the Rack depends on the Device Sorting mode on the Options > Rack Settings menu:



Rack per Track mode

In Rack per Track mode (default), each "source track" in the Sequencer has its own Rack column. This means when you select an instrument track or audio track in the Sequencer, the Rack will show the devices for that particular track (just like the Track Panel). Select another track to scroll to the Rack column for that track instead, and so on.




The Rack in "Rack per Track" mode, with one Rack Column per sequencer track.

- **If you're using Rack per Track mode, and Show Rack in Separate Window is on (on the View menu), you can turn on Single Column mode.**
  This resizes the window to show one Rack column at the time, and automatically hides the Rack Navigator. You can only scroll vertically in Single Column mode - select another track to go to another Rack Column.



The Single Column button in the separate Rack window.



The separate Rack window in Single Column mode showing the devices for the currently selected sequencer track.

▶ **Rack per Track mode is great for keeping things organized and focusing on one track at a time.**

Auto-Group Devices mode

In Auto-Group Devices mode, all devices are shown in a single rack (although you can create additional rack columns manually if you like). Devices that belong to the same Device Group are kept together. For example, an Instrument may have a Player on top, some effects below and a Mix channel at the bottom. All these devices belong to the same Device Group.



A Device Group, consisting of a Player, a Polytone synthesizer, two effect devices and a Mix Channel with an Insert FX.

Reason attempts to keep the Device Group intact in Auto-Group mode. For example:

- **You cannot add other Instruments or Audio Tracks in the middle of an existing Device Group.**
- **Moving the Source Device (the Instrument or Audio Track device) will move all other devices in the Device Group as well.**
- **Deleting the Audio Track or Instrument (device or track) will let you choose whether to delete the whole group or just the selected device.**
- **When you select a Sequencer track, the Rack will scroll to show that device, but you may also see devices belonging to other tracks.**

▶ **Auto-Group mode is good if you work with CV or audio connections between devices in different groups, or if you're used to the classic Reason rack.**

No Grouping mode

In this mode, devices are shown in a single rack, but you are free to move them any way you like. Moving or deleting devices will only include the selected ones. Use this mode if you have very specific ways of organizing your rack, or if you need to use devices in unconventional ways:




The Rack in "No Grouping" mode, with several devices freely distributed in the Rack.

Device Sorting vs new and old songs

Device Sorting mode is stored per song. You may prefer working in "Rack per Track" mode most of the time, but some documents might require "Auto-Group Devices" mode, and so on.

- **When you create a new song, it will be set to the mode selected in the Settings dialog on the Browsing tab:**



- **When you open a song made in an earlier version of Reason, it will be set to "Auto-Group Devices" mode.**
- **Changing mode to "Rack per Track" will go through the Sequencer track list, create a new Rack column for each Instrument or Audio track, and move the devices for the track there.**
  The Hardware Interface, Master Section and Send Effect devices are placed in the leftmost column. All connections are kept.
- **If you switch to "Rack per Track" and change your mind, this setting can be undone from the Edit menu.**


Navigating in the rack

To navigate in the rack, use one of the following methods:


- **Click and drag the blue frame in the Rack Navigator to scroll continuously in the rack, both vertically and horizontally.**
  Just clicking in the Rack Navigator will directly scroll to the corresponding position in the rack.
- **In Single Column mode (Rack per Track), navigate between rack columns by selecting Sequencer tracks.**
  You can go directly to a specific device by double clicking it in the Track Panel.
- **If you're using a mouse equipped with a scroll wheel, you can use it to scroll up or down in the rack.**
  Hold down [Shift] and use the scroll wheel to scroll horizontally in the rack.
- **Press the [Page Up] and [Page Down] buttons on the computer keyboard to move the view one "full screen" up or down in the rack column currently in view.**
  Note that the rack area must have Edit Focus, i.e. there must be a frame surrounding the rack area. Set Edit Focus by clicking anywhere in the rack area.
- **Press the [Home] and [End] buttons on the computer keyboard to scroll the top or bottom of the rack column currently in view.**
  Note that the rack area must have Edit Focus.

Resizing the rack

If you have de-activated "Show Rack in Separate Window" on the View menu, the Rack shows up in the Document window, between the Mixer and Sequencer areas. In the picture below, the "Show Rack Navigator" on the View menu is activated:




- **Resize the rack area by clicking and dragging either of the gray horizontal dividers above or below the rack area.**
  Making the Rack area larger will shrink the other areas and vice versa. The size you set for the Rack area will be recalled next time you open the Rack.
- **You can also resize the Rack area by clicking and dragging the vertical divider to the left of the Rack Navigator.**
  Dragging the divider to the left will expand the Rack Navigator area and enlarge the devices, making it easier to get a good overview of all devices in your rack.
- **To make the rack fill the entire song document window, double click the divider above it:**



The Rack divider.

- **See also "Creating new rack columns" for information on how to create several rack columns.**

The Device Palette




The Show/Hide Device Palette button at the top of the Reason song window.

▶ **Click the Devices button, or press [F3] to bring up the Device Palette (or to hide it).**

The devices are sorted on four different palettes in the Device Palette: Instruments, Effects, Utilities and Players. The Utilities palette contains device types such as mixers, modulation devices, etc. On each device type palette the devices are listed in the following sections: Reason Devices, and then by Rack Extension and/or VST manufacturer in alphabetical order. The Players palette is a little special; it contains a number of MIDI "generators" that can be used when recording Instrument tracks in the sequencer, see "Working with Players".

▶ **To show all devices and device types in one single list, click to turn off all group buttons.**



- **You can also hold [Cmd](Mac) or [Ctrl](Win) and click the device type buttons to show the devices of multiple palettes at the same time.**

About using the Device Palette when the Rack is in a separate window

When the rack is in its separate window, it can also feature a second instance of the Device Palette. The Device Palette is available to the left in the detached rack.

▶ **Click the Devices button, or press [F3] to bring up the Device Palette (or to hide it):**




The Show/Hide Device Palette button at the top of the rack window.

- **The Device Palette in the detached rack can be used independently from the Device Palette in the Song window.** This means you can be in two completely different palettes in the two Device Palettes.

Choosing what device types to show in the Device Palette

- **Click the "menu" button to select/deselect what device types you want to display.**
  "Reason Devices" includes both native Reason devices and Rack Extension devices.

  If both VST2 and VST3 are ticked, you can also choose to hide any VST2 "duplicates" of the same device by clicking "Hide VST2 Duplicates".




Reason devices, VST2 plugins, and VST3 plugins selected for display.

Using the Favorite tag


Assigning the Favorite tag to devices makes it possible to view only your favorite devices in the Device Palette. Great if the Device Palette is getting crowded by devices you normally don't use. The Favorite tag is represented by a heart symbol next to the devices in the Device Palette.

1. **Hover over the device and click the gray heart symbol.**




2. **Repeat the procedure for the other devices you want to tag as Favorites.**

3. **When you're done, click the "Show Favorites Only" button to only show these devices in the Device Palette:**



- **To remove a Favorite tag, hover over the device in the Device Palette and click the red heart symbol to remove the tag.**




Filtering the view in the Device Palette

It's possible to filter (search for) devices, manufacturers and device descriptions in the Device Palette.

- **Press [F3] to show the Palette (if hidden) and set the focus to the text field at the top of the Device Palette.**
- **Type in (part of) the device name, or the device description, or the manufacturer you are searching for.**
  The text you type will also be matched against Device Categories and Tags, see "Filtering on Categories on the Device Palette" and "Assigning Tags to devices".

  In this example we type in "kon" in the Search box and get the following results:




Typing in "kon" results in Kong, Konarie Chirp Synthesizer and Kontakt 7.

- **To clear the text in the text field, click the x button to the right (or press [Delete] or [Backspace]).**

Filtering on Categories on the Device Palette

You can apply Category filters to specify what type of devices you want to display on the Device Palette:

- **Click the unfold button to the left of the Search field.**
  Then, click the Categories unfold button and select device types/characteristics by selecting one or several of the Categories:




Clicking the "Bass" Category displays devices suitable for bass sounds.

- **To select multiple Categories, hold down [Cmd](Mac) or [Ctrl](Win) and select.**
- **You can also use the Search and Categories in combination, if you like.**
  The functions work exactly the same regardless of what device types (Instruments/Effects/Utilities/Players) you have selected.

Assigning Categories to devices on the Device Palette

▶ **You can also assign or re-assign Categories to devices, by selecting the desired devices, right clicking one of the devices and choosing the desired Category from the context menu:**



- **If you have selected multiple devices any Category you select will be applied to all selected devices.**
- **If any of the selected devices are already assigned to one or several Categories, this is indicated by a "-" sign to the left of the Category name.**
  Selecting such a Category will assign all selected devices to that Category and the sign will switch to a check mark instead.

▶ **To de-assign a Category from a device, right click the device(s), select "Categories >" and click the check mark for the Category you want to de-assign.**


Using Tags on devices

It's also possible to assign Tags to devices, so they will be easy to find when you filter for devices. You could, for example, tag devices with the Tag "Granular" or "Psytrance". Then, when clicking the "Granular" or "Psytrance" Tags, these devices will show up on the Device Palette.

If you turn on multiple Tag buttons (by [Ctrl](Win) or [Cmd](Mac)-clicking their buttons) - the palette will then only show devices that match all these tags.


▶ **If you only want to assign devices to the generic "Favorite" tag, please have a look at "Using the Favorite tag" above.**

1. **Click the unfold button to the left of the Text field, and then click the Tags unfold button:**



By default there are two fixed Tags: “Favorite” and “Hidden”, but you can also create your own tags.

2. **Click the “+ Add...” text, type in the name you want to use for your new Tag and hit [Enter].**




The new Tag now appears as a new button in the Tags section.

- ▶ **Alternatively, right click a device in the Device Palette and select “Tags > + Assign New Tag...” from the context menu.**
- ▪ **You can delete or rename Tags you have created, by right clicking the desired Tag button and selecting “Delete Tag” or “Rename Tag...” from the context menu.**

Assigning Tags to devices

1. **Select one or several devices in the Device Palette.**
   To select multiple devices, hold [Cmd](Mac) or [Ctrl](Win) and click the devices.
2. **Right click one of the selected devices and choose, for example, the “Favorite” (=heart) Tag from the context menu:**




Now, the selected devices have been assigned the Favorite tag. If you click the Favorite Tag button in the Device Palette, only the added devices are shown.

- ▶ **To assign Tags that you have created yourself, select the desired Tag from the “Tags >” context menu.**
- ▪ **You can use Tags in conjunction with Categories and the Filter (Search) function, so that you can e.g. filter on all Reverb devices with the Favorite tag.**
  Typing into the text field will then match against device name, manufacturer name, category and tag.

Hiding devices from the Device Palette

To make the Device Palette look “cleaner” it’s also possible to hide devices that you don’t want to see/use:

- **Select the desired device(s) in the Device Palette, right click one of the devices and select “Hide” from the context menu.**
  Now, these devices will be hidden in the Device Palette. Hidden devices are still available on the Create menus, though.
- **If you want to make hidden devices appear again, click the “Hidden” Tag button, select the desired devices and then right click one of the selected devices and uncheck the Hide item on the context menu:**



The Hidden Tag will be removed from the device(s) and the devices will re-appear in the regular Device Palette.

Working with devices

Creating devices

Devices can be created in a number of different ways. These first methods apply to any device types:


- **Use drag and drop, or double-click a device in any of the Device Palette groups.**
  A device can be dropped in the Rack or in the Track List or Track Panel in the Sequencer. As you drag a device to the Rack, Track Panel or Sequencer Track List, a +-sign is shown together with an orange divider to indicate where the device will be placed:



Adding a Polytone Dual-Layer Synthesizer device by dragging it from the Instruments palette and dropping in the rack.

- **! If you are using the "Rack per Track" Rack Settings option, dragging a device to the Rack will add the device between the existing Rack columns where the mouse cursor is currently located (if you don't manually place it to the far right).**


If you have clicked the Track Panel button in the top bar (or selected "Show Track Panel" on the View menu) in the document window, you can also add devices to the Track Panel:




Adding an Audiomatic Retro Transformer device by dragging it from the Effects palette and dropping on the Track Panel to the left of the Sequencer in the document window.

- **Use drag and drop from the Device Palette, Windows Explorer (Win), Finder (Mac), or double click (or drag) a patch in the Browser.**
  When you drop a patch in the rack or in the Sequencer Track List, the corresponding device is automatically created in the rack.

- ▶ **Select a device in the rack and click the + sign at the top or bottom of the blue frame, to add a new device above or below the selected device in the rack.**
  The menus give you the options to either create a device by selecting it from the submenus, or to create a device by browsing patches in the Browser. Selecting the top item in the menus ("Add Player..."/"Add Instrument..."/"Add Effect...") will open the Browser, see "Creating a device by browsing patches".
- ▪ **Clicking the top + sign on an Instrument device gives you the option of adding a Player device above the instrument:**



- ▪ **Clicking the bottom + sign on an Instrument device gives you the option of adding an Effect device, and auto-route the effect to the instrument. You can also choose to create a new Instrument device as a new separate instance in the rack.**



- ▪ **The "Add Device" menus differs depending on what device type you select in the rack.**
  For example, clicking the + signs on a Player device will give you the option of adding more Players only. Clicking the + signs on an Effect device will give you the option of adding more Effect devices, or adding a new separate Instrument device instance below.
- ▶ **Select desired device from the "Create" menu.**
  Any device type can be created. The "Create" menu is available both on the main menu and on the rack and device context menus and is divided into the four groups: Instruments, Effects, Utilities and Players. At the top of each group (Instruments/Effects/Utilities/Players) are the devices you create most often. Below are all available devices, on submenus per manufacturer.
- ▪ **When you add a new device, Reason attempts to automatically route it in a logical way.**
  For more information about the auto-routing features, see "Automatic routing".

Depending on what type of device you've created, and also the "Auto-Group Devices and Tracks" setting, the results will differ:

- ▪ **If "Auto-Group Devices and Tracks" on the Options menu is not selected, the new device is added directly below the currently selected device in the rack.**
  If no device is selected, the new device is added at the bottom of the rack.
- ▪ **If "Auto-Group Devices and Tracks" on the Options menu is selected, devices will not be created in the middle of existing Device Groups (except if they are effect devices - see "Effect devices specifics").**
  This means a device might not end up below the selected device in the rack, but below that device's Device Group.
- ! **See below for information specific to certain device types.**

Instrument device specifics

The following additional methods can be used for creating Instrument devices:

- ▶ **Select "Add Instrument..." from the Create menu.**
  This will open Reason's Browser. Here you can choose patches that will automatically create the corresponding device in the rack - see "About patch formats and sampler devices".

- **If you have created an Instrument device, a new sequencer track will be automatically created. Also, a new (or unused) Mix Channel device will be connected to the Instrument device. The Mix Channel device's channel strip will appear in the Main Mixer.**
  The track, the Mix Channel device and its channel strip will be given the same name as the created Instrument device. Master Keyboard Input will also automatically be set to the new track, allowing you to immediately play the created Instrument device via MIDI (see "Master Keyboard Input"). By default, the Instrument device and Mix Channel device will be treated as a "Device Group" from here on (see "Creating devices").

! **By default, the automatic creation of a sequencer track and Mix Channel device only applies to instrument devices, not to mixers or effect devices.**

- **If you hold down [Alt](Win) or [Option](Mac) when you create an Instrument device, by dragging and dropping from the Device Palette, a sequencer track will not be created.**
- **If you hold down [Shift] when you create an Instrument device, there will be no automatic routing or connections made.**

Audio Track device specifics

The following additional methods can be used for creating Audio Track devices:

▶ **Select "Add Audio Track" from the Create menu.**
This will create an Audio Track device (with its corresponding channel strip in the Main Mixer) and a sequencer track.

Mix Channel device specifics

- **If you hold down [Alt](Win) or [Option](Mac) when you create a Mix Channel device, by dragging and dropping from the Device Palette, a sequencer track will be created for the Mix Channel device.**

Effect devices specifics

The following additional method can be used for creating Effects devices:

▶ **Select "Add Effect..." from the Create menu.**
This will open the Browser. Here you can choose patches that will automatically create the corresponding Effect device in the rack - see "About patch formats and sampler devices".

The results when creating Effect devices depend on the following criteria:

- **If an Audio Track (device or channel strip), or a Mix Channel (device or channel strip), was selected in the rack when you created an effect, the effect device will be added and connected as an Insert Effect, inside the Insert FX container for that Audio Track or Mix Channel device.**
- **If an Instrument device was selected in the rack when you created an effect device, the effect device will be added and connected as an "insert effect", between the Instrument device and the Mix Channel device.**
- **If a Mixer 14:2 or Line Mixer 6:2 was selected in the rack when you created an effect, the effect device will be added and connected as a Send Effect, on the first available Send FX connectors of the mixer device.**
- **If you hold down [Alt](Win) or [Option](Mac) when you create an effect device, a sequencer track will be created for the device.**
  Note, though, that some effect devices (e.g. BV-X Vocoder) automatically get a sequencer track by default.
- **If you hold down [Shift] when you create an effect device, the effect device will not be connected.**

Mixer device specifics

- **If you hold down [Alt](Win) or [Option](Mac) when you create a mixer device, a sequencer track will be created for the mixer device.**
- **If you hold down [Shift] when you create a mixer device, it will not be connected to a Mix Channel device.**



About Device Groups


A Device Group is a series of interconnected devices that "belong together" - for example, an instrument device connected to an effect device and then to a Mix Channel device.

A Device Group contains:

- **One Source device (and its track). This is typically an instrument or audio track.**
  If it's an instrument, any Players connected to the instrument device - plus their tracks if they have any - are in the same Device Group.
- **The devices to which the Source device feeds audio (typically effect devices) - plus their tracks.**
- **All mixer channels in the Main Mixer for the devices in the group.**
- **In Rack per Track mode, the Device Group is typically the devices in the Rack column for the selected track.**
- **In Auto-Group Devices mode, the Device Groups are kept together, but many Device Groups can live in the same rack.**

By default, when you create an Instrument device, a new (or currently unused) Mix Channel device will be automatically connected to the Instrument device, as described in "Creating devices". In this situation, the Instrument device and the connected Mix Channel device will now be considered a Device Group - with the Instrument device as the Source device.

If you want to keep all devices in a Device Group physically together in the rack (e.g. if you want to move all devices in the group), there is an option "Auto-group Devices" on the "Rack Settings" sub menu on the Options menu.



The "Auto-group Devices" option.

The advantage of using the "Auto -group Devices" option is that it's much easier to get a good visual overview over what devices are connected to each other and associated with specific sequencer tracks and with a specific channel strip in the Main Mixer. It's also easier to rearrange devices in the rack since all devices in the Device Group will move together if one device in the Device Group is moved.

- **If you want to view what devices belong to a specific Device Group, select a device, track or mixer channel and then select "Select All in Device Group" from the Edit menu or context menu.**
  All devices, tracks and channels in the Device Group now get blue selection borders in the rack.

Selecting devices

Some operations, such as cutting, copying, moving and deleting devices (see "Cut, Copy and Paste devices" and "Deleting devices"), require that you select one or several devices in the rack. This is done according to the following:

- **To select a single device, click on it in the rack.**
  The selected device is displayed with a blue border.



- **To select several devices, hold down [Shift] and click on the desired devices.**
  In other words, [Shift]-clicking a device selects it without de-selecting any other selected devices.

- **To de-select all devices, click in the empty area at the bottom of, or next to, the rack.**
- **To de-select a device in a multiple selection, hold down [Shift] and click on it.**
  All other selected devices remain selected.

- **You can also use the arrow keys on the computer keyboard to select the device directly above, below or next to the currently selected one.**
  When you use this method, Reason will automatically scroll the rack so that the selected device is fully visible. This is a quick way of "stepping through" the rack. Narrow devices (e.g. half-width devices such as some effects) are ordered left-to-right, i.e. pressing the down arrow key will step through the devices from left to right before moving on the next device row.
- **If you hold down [Shift] when using the up or down arrow keys, the currently selected device will remain selected.**
  This allows you to select a range of devices.
- **Adjusting a parameter in a device will automatically select the device.**
  In other words, you don't have to select a device as a separate operation before editing its parameters.

Playing devices from the rack

When you create an instrument device it automatically gets a corresponding sequencer track, and Master Keyboard Input is set to that track so you can play the instrument device from your MIDI keyboard. You can change Master Keyboard Input by selecting another sequencer track, but you can also change Master Keyboard Input from the rack. This is useful if you, for example, have the rack detached and maximized, so you can't see the sequencer area.

When you select a device in the rack it is surrounded by a colored border. At the top left of the border is a Master Keyboard Input tab:




The Master Keyboard Input tab on a selected ID8 device in the rack.

- **Click the Master Keyboard Input tab to automatically set Master Keyboard Input to the device.**
  Master Keyboard input is automatically switched in the sequencer as well and you can now play the device from your MIDI keyboard:



Master Keyboard Input set from the ID8 1 device in the rack.



Master Keyboard Input automatically set to the ID8 1 Sequencer.

When you play the device, incoming MIDI is indicated by the Master Keyboard Input symbols on the device in the rack as well as on the sequencer track.

- **If a selected device doesn't have a sequencer track (e.g. effect devices), one will be automatically created if you click the Master Keyboard Input tab.**

About selecting all devices in a Device Group

To select all devices in a Device Group, do as follows:

1. **Select any device in the desired Device Group.**
2. **Select "Select All in Device Group" from the Edit menu or the device context menu.**
   All devices in the Device Group will be selected as indicated by the colored borders around the devices.

Deleting devices

To delete one or several devices:

1. **Select the device(s) in the rack.**
2. **Press [Backspace] or [Delete], or select "Delete Devices and Tracks" from the device context menu.**
   Depending on the device and the Rack mode, an alert may appear asking you to confirm.

▶ **To delete without getting this alert, hold [Ctrl](Win) or [Cmd](Mac) when deleting.**

- **If you delete a device connected between two other devices, the connection between these will be preserved.**
- **The Reason Hardware Interface device and Master Section device cannot be deleted.**

! **Deleting a device will also remove its track, including any audio recordings or MIDI notes on it**

Re-ordering and re-routing devices

To move devices in the rack:

1. **If you want to move more than one device, [Shift]-click to select them.**
2. **Click on the panel of one of the devices (but not on a control or a display).**
3. **Drag the device to its new position in the rack.**
   What happens when you move a device depends on the Rack Sorting mode and the type of device:

Rack per Track mode

In this mode, you typically drag devices within a Rack column. For example, moving an effect device will re-route it at its new position, changing the signal processing order. If Single Column mode is off, it is also possible to move effects, utilities or Players between Rack columns (e.g. if you want to move a Player from one instrument to another).

The Source Device (the instrument or audio track at the top of the column) cannot be moved in Rack per Track mode.

Auto-Group Devices mode

- **Moving a Source Device (instrument or audio track device) will automatically move all other devices in the Device Group.**
- **Moving an effect or Player will re-route it at its new position, either in this Device Group or in another.**

No Grouping mode

- **All devices can be moved freely.**

About re-routing effects

- **When moving effect devices (or utility devices that auto-route like effects), they will be re-routed (as if you had deleted it and created it at the new position).**
  This allows you to change the order of effect devices in a signal chain by just dragging them.

▶ **To move devices without re-routing them (keeping their existing connections), hold [Shift] and drag them.**


Creating new rack columns

If your song is in Rack per Track mode, each Device Group will automatically be put in a separate Rack column. In the other two modes, the Rack starts as a single column and new devices will be created below each other in this rack. It's possible to move devices to new Rack columns, though. This is very useful if your rack gets crowded, or if you want to arrange devices to get a better overview.


By dragging and dropping devices to either side (left or right) of the original rack, you can move the devices and at the same time create a new rack column. You can create as many rack columns as you like - the only condition is that at least one device must be present in a neighboring rack column. In other words, you can't create empty rack columns.

In the example below, we drag and drop an RV7000 reverb device to the right of the original rack:

Click on the RV7000 device panel and drag to the right...



... Release the mouse button and the RV7000 device is automatically placed in a new rack column to the right.



A large white arrow symbol appears on the right wooden rack side of the original rack column to indicate that the device is about to be moved to a new rack column.


Replacing devices

If you want to replace an Instrument, Effect or Player device in the rack with another device of the same category, proceed as follows:

1. **Bring up the Device Palette in the Browser for the desired device type (Instruments, Effects or Players).**

! **Utility devices cannot be replaced using these methods!**

2. **Drag the desired device from the Device Palette to the rack and place on top of the device you want to replace.**
   The device to be replaced is dimmed in orange and gets a "replace" symbol in the center:



Replacing a Subtractor with a PX7 FM Synthesizer device.

3. **Release the mouse button to replace the device in the rack.**
   The new device is automatically routed like the previous device. The Mix Channel now also gets the name of the current patch in the new device. The new device also gets "browse focus" in the Browser, see "Loading patches".

▶ **You can also drag and drop devices on existing device icons in the Track Panel or track list in the sequencer. The result is exactly the same as dropping devices on existing devices in the rack.**

▶ **In the same way, you can drag a patch from the Browser or the desktop and drop them on a device in the rack, Track Panel or track list to load the patch, see "Loading patches".**

! **Note that Instrument devices can only be replaced by other Instrument devices. The same goes for Effect devices.**

Duplicating devices

▶ **To duplicate a device in the rack, hold [Ctrl](Win) or [Option](Mac) and drag it to a new position.**
Alternatively, select the device(s) and select "Duplicate Devices and Tracks" from the context menu.

What happens when you duplicate a device depends on the Rack Sorting mode and the type of device:

Rack per Track mode

- **An effect, utility or Player can be duplicated within its Rack column.**
  If Single Column mode is off, it is also possible to copy-drag a device between Rack columns. The duplicated device will be auto-routed at its new position - to duplicate without routing, hold [Shift].
- **The Source Device (the instrument or audio track at the top of the column) cannot be copy-dragged in Rack per Track mode.**
  It is possible to use the "Duplicate Devices and Tracks" function on a Source Device though - this will create a copy of the whole Device Group in a new Rack column to the right.

Auto-Group Devices mode

- **Duplicating a Source Device (instrument or audio track device) will automatically include all other devices in the Device Group.**
- **Duplicating an effect or Player will re-route it at its new position, either in this Device Group or in another (unless you hold [Shift]).**

No Grouping mode

- **Only the selected device(s) will be duplicated.**

Cut, Copy and Paste devices

Selected devices or Device Groups can be moved or duplicated using the Cut, Copy and Paste Device functions on the Edit menu or device context menu. This allows you to copy one or several devices (such as an instrument device and all its "insert" effects) from one Reason Song document to another. Cutting/Copying and Pasting will have different results depending on the "Auto-group Devices and Tracks" setting on the Options menu (see "Creating devices"):

- **Cut and Copy affects all selected devices or Device Groups, and works according to the standard procedures.**
  That is, Cut moves the devices/Device Groups to the clipboard (removing them from the rack) while Copy creates copies of the devices/Device Groups and puts these in the clipboard memory, without affecting the rack.

▶ **If your song is in Rack per Track or Auto-Group Devices mode you can copy a complete Device Group by selecting its Source Device, and then selecting Cut/Copy and Paste.**
All devices in the Device Group will be cut/copied and pasted with preserved connections (in the same Song or in another Song document).

- **When you Paste devices or Device Groups, these are inserted into the rack below the currently selected device.**
  If no device is selected, the pasted devices/Device Groups will appear at the bottom of the rack column.

! **As when creating devices, you cannot paste a Source device into an existing Device Group if "Auto-group Devices and Tracks" is on. It will be inserted below the Device Group.**

- **If you Copy and Paste several devices, any connections between these are preserved.**
- **Pasted devices will automatically be routed at their new position, if possible.**
  To Paste without routing, hold [Shift].

Naming devices

Each device has a "tape strip" which shows the name of the device. When you create a new device it is automatically named according to the current patch in the device. Devices that don't use patches are automatically named according to the device type, with an index number (so that the first ID8 device r you create is called "ID8 1", the next "ID8 2" and so on). If you like, you can rename a device by clicking on its tape strip and typing a new name (up to 16 characters).



For instrument devices connected to Mix Channel devices, the device names are automatically copied to the tape strips for the corresponding Mix Channel devices and their channel strips in the Main Mixer, as well as on their corresponding sequencer tracks. Similarly, the names of the FX Returns in the Main Mixer show the names of the effect devices connected to the corresponding FX Return inputs.

- **When you create a device for which an associated sequencer track is created, the track in the sequencer will be assigned the same name as the device. Renaming the device will also rename the corresponding sequencer track, and vice versa.**
- **Note that the mixer channel tape strips always show the patch name (or device name) of the source device connected to the Mix Channel device! This means that if you have an instrument device routed through one or several effect devices, the Mix Channel tape strip will show the name of the instrument device (as this is the Source device).**
- **You can rename Mix Channels manually, for example, if you use multiple outputs from a sampler device going to separate Mix Channels. If you later delete the custom name, the Mix Channel will default to showing the Source device's name. For audio tracks, the Audio Track device is always the Source device and will never change name unless you manually rename it.**

- **If you delete your custom device name, the name reverts back to the default name, i.e. the patch name or device name (for non patch devices).**

Folding and unfolding devices

If you don't need to edit the parameters for a device, you can fold the device to make the rack more manageable and to avoid having to scroll a lot.

▶ **Click the "Fold/Unfold" button to the left on the device panel to fold the device.**



The "Fold/Unfold" button on an RV7000 device.

▶ **To unfold the device, click the "Fold/Unfold" button again.**

- **In rack rows containing devices of smaller width, the "Fold/Unfold" button is placed to the left of the leftmost device and affects all devices in the row:**



The "Fold/Unfold" buttons for devices of smaller width.

▶ **Hold down [Alt](Win) or [Option](Mac) and click the "Fold/Unfold" button of an unfolded device to fold all devices in the current rack column.**
Conversely, hold down [Alt](Win) or [Option](Mac) and click the "Fold/Unfold" button of a folded device to unfold all devices in the current rack column.

- **For folded devices, no parameters are shown and you cannot reroute any cables on the rear of the rack as long as the devices are folded.**
However, if you want to make a connection to a folded device, you can drag a cable to it and hold it there for a moment. This will cause the folded device to automatically unfold and let you make the connection.
- **Folded devices can be renamed, moved, duplicated and deleted just like unfolded devices.**
- **For devices that use patches, you can select patches in folded mode as well.**
- **Playback is not affected by folding.**

Flipping the rack

To be able to connect, delete or reroute cables between devices in the rack, you need to flip the rack.

▶ **To flip the rack to show the rear panels of the devices, either press [Tab], or click the Flip Rack button at the top of the document window, or select "Flip Rack" from the View menu.**



The Flip Rack button at the top of the song window.

The rear panels of the devices are now shown in the rack area:



The rear panels of the devices in the rack.

See "Manual routing" for information about routing cables between devices in the rack.



Chapter 13
Working with Players




About this chapter

This chapter describes the procedures and techniques for working with the Players device type.

Overview

A Player is a special type of device that automatically processes, filters and generates MIDI Notes, based on input MIDI Notes to an Instrument device in the rack. Players can also play back MIDI on their own, without any MIDI input; this could for example be pattern sequencers.

The Player devices can be found on the Players palette on the Device Palette:



The Players palette

The basic idea behind Players is that you first create an Instrument device (or instrument track), then hook up one or more Player devices to the Instrument device. If the Player device is a chord generator, for example, you can have it generate chords in the desired key and scale by just playing single notes on your MIDI Control Keyboard. Absolutely great for inspiration!

Player devices are a little narrower than regular devices, and are always created directly above their corresponding Instrument device(s):




Two Player devices (in series) attached to an ID8 Instrument device in the rack.

General recording methods


Apart from sequencer Players, recording Instrument tracks using Players can be done in two different ways:

- **By recording the notes exactly as you play them on your MIDI Control Keyboard.**
  This is the default mode and means you just record the notes straight onto the Instrument track from your MIDI Control Keyboard, just as you would a regular Instrument track (without any Player). During playback the recorded notes are then run through the Player, which generates the Player notes in real-time.
- **By recording the notes that are generated by the Player(s).**
  This is called Direct Recording and means that instead of recording the notes you play on your MIDI control keyboard, you record the notes that are generated by the Player(s). This way you automatically get the rendered notes onto your Instrument track (as chords, arpeggios etc. depending on the Player(s)). During playback the recorded notes bypass the Player(s), so the result is exactly what you heard when you recorded.

The pictures below illustrates the two different recording modes:



The default recording mode principle.



The Direct Record mode principle.

Using Players

Creating Players

Creating a Player device is very similar to creating other device types, with a few exceptions:

- **A Player device can not exist on its own, without an associated instrument device.**
- **A Player device can only be created for devices in the Instruments group in the Device Palette.**
  All Instrument types are supported: native devices, Rack Extensions and VST instruments.

Here are the different ways you can create a Player device:

- ▶ **Drag a Player from the Players palette and drop above an Instrument device (between the Instrument and Mix Channel devices) in the rack, to attach it to the Instrument device.**
  The insertion point is indicated by the standard orange insertion line with the + symbol.
- ▶ **Select the Instrument device you want to attach a Player to in the rack, and then double-click the Player device in the Players palette.**
  The Player device is attached to the Instrument device.
- ▶ **Right-click an Instrument device in the rack, select "Player devices >" and then the desired Player device from the context menu. Alternatively, select "Add Player..." to open the Browser and load a Player patch.**
  The Player device is attached to the Instrument device.
- **If you only create a Player device, an ID8 device will be automatically created and attached to it.**
  You could then replace the ID8 with another instrument device, as described in "Replacing devices".

Chaining Players

If you like, you can attach several Player devices to a single Instrument device in the rack. Just follow the instructions in "Creating Players" above and make sure you insert the additional Player(s) somewhere in between the Instrument device and the top section of the topmost Player device.

! **When you chain several Player devices the MIDI is processed from the top device and down.**

See "Tips & Tricks" for some interesting combinations!

Re-ordering chained Players

You can also rearrange the order of the chained Players:

- ▶ **Drag the desired Player and drop at the new position.**
  The insertion point is indicated by the standard orange insertion line with the + symbol.

Replacing Players

Replacing a Player device with another Player device can be done in exactly the same way as when replacing other device types, see "Replacing devices".

Deleting Players

Deleting Players is done in exactly the same way as when deleting other device types, see "Deleting devices".

Naming Players


Naming Players is done in exactly the same way as when naming other device types, see "Naming devices".



About Players in Combinators

Players can also live inside Combinators, if there are instrument devices there. A Combinator device can also have Players attached to it (outside of it).

Common Player device parameters



Fold, Bypass All, Direct Record and Send to Track

At the top of the Player device - or above the topmost Player device, if you are using several chained Players - are the Fold, Bypass All, Direct Record and Send to Track buttons.

- **Click the triangular Fold button to fold/unfold all Player devices attached to the Instrument device.**
- **Switch on Bypass All to send the MIDI from your MIDI Control Keyboard/On-screen Piano Keys straight to the instrument device, bypassing any Player devices.**
- **Activate Direct Record to record the MIDI notes generated by the Player(s), instead of the notes you play from your MIDI Control Keyboard.**
  Direct Record mode is for when you use Players as an input tool (record chords, etc) and for when you want to capture your live tweaking (for example, play an arpeggiator and tweak the parameters in real time) and want to get the generated notes recorded straight into the note clip.

  If you play back already recorded notes from the sequencer track of the instrument, they are not affected/processed by the Player (i.e they bypass the Player(s) and are sent directly to the instrument itself).

  See "General recording methods" for more information.
- **Click the Send to Track button to render the notes generated by the Player(s), based on the notes in the original note clip(s) on the Instrument track in the sequencer.**
  The result is a new note clip on a new note lane, on the instrument's track. The original note clips on that track are automatically cut at the Left and Right Locators. The original clip(s) between the Locators are muted. Also, the Bypass All switch will automatically be turned on after the rendering is done.

! **Only the section between the Left and Right Locators in the sequencer is rendered. If the Right Locator is to the left of the Left Locator position, the function doesn't do anything (like with Redrum etc.).**

- **If you have recorded in Direct Record mode, or used the Send Notes to Track function, the rendered notes are already in the note clip in the sequencer. If you don't need the Player(s) anymore after this you can just delete them to save some DSP load.**

On button

- **Click to activate or deactivate the Player.**
  When deactivated (off), the MIDI notes from your MIDI Control Keyboard bypass the Player.


Patch section

Here is where you can browse, load and save your Player patches. The functionality is exactly the same as for other patch based devices, see "About patches".

Inputs and Outputs

Player devices can also feature CV In/Out connectors as well as Audio In connectors on the rear panel.

Beat Map



The Beat Map Algorhythmic Drummer is a Player that generates drum patterns based on built-in beats, algorithms and simple but powerful controls. It's normally used with a drum instrument such as Kong, Rytmik or Umpf, but can also be used with melodic instruments for interesting results.

Included content

▶ **To browse the content of Beat Map, click the "Browse patch" button to open the Browser, where you can select Beat Map patches.**

Beat Map comes with a number of patches, both for the Player itself and for several different drum devices. The drum device patches are tailored to work well with Beat Map, but you can of course use any patch from the Factory Sound Bank, or make your own.

If you want immediate results, start by loading one of the patches in the Combinator Style Patches folder! These combine Beat Map with drum devices and effects for instant rhythmic goodness.


If you want a taste of what can be done with multiple Beat Maps in combination with other devices, check out the Demos and Song Starters folder.

1. **To browse for Beat Map Combinator patches, hold [Ctrl](Win) or [Cmd](Mac) and press [F] to open the Browser without Browse Focus.**
2. **Navigate to the "Reason Library > Rack Extensions > Beat Map" folder, where all the subfolders with Combinator patches can be found.**

! **Note that some of the Combinator patches use Rack Extensions only included in Reason+.**

Finally, the Template Key Mappings folder contains Beat Map patches where the keys (note numbers) have been adapted for other drum configurations such as GM, Reason Drum Kits and various 3rd party drummers.

The front panel



The central item on Beat Map's panel is the Map display. This is where you select a basic rhythm, by clicking and dragging the cross-hair.

- **The cross-hair position is also indicated with the X and Y position parameters, which you can edit directly if you like.**

Each integer XY position corresponds to a different beat. The map graphics are there for visual reference and for the nice looks – there is no particular rhythmic significance to the elements on the map. However, as a general rule, moving the position to the right will make the bass drum pattern more syncopated and moving the position upwards will make the snare pattern more syncopated.

- **Clicking the Spawn XY button drops you at a random position:**



Map Select


1. **Click the Map Select button to show the four included maps:**



They contain beats in different styles – click on a map to see some info about it in the display.

2. **To select a map for use, either double click it or select it and click Map Select again.**

Density




The beats consists of four different rhythmic patterns, for kick, snare, hi-hat and percussion. Once you've found a beat that you like, you can adjust the Density of each drum. This means reducing or increasing the number of notes. Turning Density down to zero will mute that drum. The Density parameters can be automated or CV controlled, for continuous variations.

- **Clicking the Random Density button to the left will change all four Density controls to random values, useful for live variations:**



Lock Position




You may find a beat where for example the kick is perfect, but not the other drums. Then you can click Lock Pos for the kick. This will put a "pin" on the map – the kick beat will stay at this position but you can continue exploring the map for the other instruments.


This can be done independently for all four drums, locking them to different map positions. This way you can combine rhythms from different basic beats, for infinite variations.

! **You can still adjust Density for locked drums.**


Mirror notes



Each of the four drums has a "Mirror" function, which plays a note in between two note positions from it's main drum. For example, if the kick beat plays like this:



... then its Mirror notes (dark red) will play like this:



This means that the Mirror notes will be affected by the Density of the main drum, creating interesting counter-rhythms or ghost notes.

Use the Mirror knobs to set the velocity (typically level) of the Mirror notes. Turning the knob down completely will turn off the Mirror note.

Setting MIDI note numbers

Each drum and Mirror function sends out notes on a separate MIDI note number, meaning that Beat Map can control eight different drum sounds.

- **Clicking the red signal LED for a drum will send out that note, for quick auditioning of drum sounds:**



The Perc drum sends out MIDI Note F#1

- **You can set which note a drum should send by clicking and dragging the note number on the panel:**



Alternatively, use the Learn function:

1. **Click Learn Key:**



2. **Click the note number value for a drum or Mirror to highlight it.**



3. **Play the desired note on your MIDI controller.**
4. **Repeat for the other notes.**
5. **Click the Learn Key again to exit Learn mode.**
   This is required for the changes to stick when you save the patch or song.

Global settings



To the right are three settings that affect the overall playback:

- **Rate is the note value of each step. Normally this is set to 1/16th notes.**
- **Shuffle allows you to add a swing feel to the beats by delaying the offbeat 1/16th notes.**
  You can set it manually from 50-75% or select "Global" to use the Global Shuffle setting (found in the Groove mixer in Reason).
- **Reset Step determines the number of steps before the beat starts over from the beginning.**
  The default is 64, but it can be useful to lower this to make a beat less varying or to impose some structure on a chaotic rhythm.


Beat Map and the sequencer

You can click the Run button manually for auditioning the beat, but the Run function is normally controlled by the Play function in the main sequencer.


However, if you want Beat Map to play in certain parts of your song but not in others, it's also possible to control this using Pattern automation. Here's how to do this in Reason:

1. **Right-click Beat Map and select "Create Track".**
   This creates a sequencer track for the Beat Map device.


2. **With the Beat Map track selected, click the Create Pattern Lane button above the track list**



This creates a Pattern lane on the Beat Map track. Since there are no pattern clips on the lane, Beat Map will be stopped. This will be indicated in the map display:



3. **Draw pattern clips in the sections where you want Beat Map to play:**



Unlike other pattern devices, there is only one pattern to select from here – Pattern 1. This is just a nifty way to control playback – you can also use pattern offset to start playback with an upbeat or in the middle of a bar.


- **Alternatively, you could automate the On button to automate the Beat Map playback:**



In addition, most Beat Map parameters can be automated. For example, you can record map movements or Density changes.

A couple of special features:

- **The Locked XY positions can be automated for each drum.**
  This allows you to lock a single drum to a rhythm but change it with automation:




- **The Map selection ("Beat Map" parameter) can be automated or controlled from a Combinator.**
  Switching to another map can be useful as a break or fill.

Editing the drum notes

To manually edit the beats from Beat Map, you need to send the MIDI notes to a sequencer track. You do this with the Send To Track function on the Player top panel, see "Common Player device parameters".

Using CV



On the back of Beat Map, you'll find a comprehensive selection of CV inputs and outputs.

- **Density CV in and Mirror Velocity CV in for each drum.**
  Using these with a Pulsar CV LFO can create longer, varying rhythmic patterns or random variations. There are plenty of examples of this among the Combinator Style Patches.
- **Gate Out from main drums and Mirror sections, allowing you to trigger other sounds or effects in parallel.**
- **Reset Step Trig In.**
  Whenever this receives a positive CV value, the beat will start over from the first step.
- **Map XY CV Inputs, for automatically modulating the map position during playback.**
- **Map XY CV Outputs.**
  These send out the X/Y coordinates as CV values, letting you use the Map display as an XY controller for other devices in Reason.

Dual Arpeggio



The Dual Arpeggio device accepts one or several notes as input and generates rhythmic patterns based on these notes. You can use it as a traditional "monophonic" arpeggiator, where arpeggio lines are played back one note at a time, based on the notes you play/hold on the MIDI Control Keyboard.

You can also use it in Pattern Mode, where you can create polyphonic (up to 4 notes) rhythmic patterns, depending on how many notes you play/hold on your MIDI Control Keyboard.

You can control the Velocity of the arpeggiated notes from your MIDI Control Keyboard, or by activating the Velocity switch and drawing in Velocity values in the display.

Dual Arpeggio has two independent arpeggiator sections, that are identical. The sections can either be played by the same input notes (parallel) or you can set up separate key ranges for them (key split). Input notes that are outside the set range(s) will be throughput as is, which means you can play melodies on top of arpeggiated chords etc.

The Dual Arpeggio device plays back in sync with the Reason sequencer, as soon as you input notes to it.

Arp1/Arp2

These are the "on/off" buttons for each of the sections.

Input Range

Here you can define the input note range, to which the arpeggiator should respond. Input notes outside the set range(s) are bypassed and let through unaffected. This is very useful if you, for example, want to play melodies on top of arpeggiated chords.

- **Set the lowest and highest input note that should be routed to the corresponding arpeggio section, by click-holding the notes in the displays and dragging up/down.**

You can also set the Input Range by using the LRN (Learn) buttons:

- **Press a key on your MIDI Control Keyboard and then click the desired LRN button to input the note number for the pressed key.**
  Repeat the procedure in the other display for the other note in the range.

Rate

- **Set the time division to which to play back the arpeggiated notes.**
  Values: 8 bars, 4 bars, 3 bars, 2 bars, 7/4, 6/4, 5/4, 4/4, 3/4, 2/4, 3/8, 1/4, 3/16, 1/8, 1/8T, 1/16, 1/16 Shuffle*, 1/16T, 1/32, 1/32T, 1/64.

  * The Shuffle amount is set with the Global Shuffle knob in the ReGroove Mixer, see "Global Shuffle".

Octave

- **Set how many octaves the arpeggiated notes should cover.**
  Range: 1-4 octaves.

Provided the Pattern function (see "Pattern") is not active, this is what will be played back:

Octave range	Description
1 Oct	The arpeggiated notes will be those that you press down on the keyboard.
2 Oct	If you select this, the arpeggio will be extended to a two octave range, i.e, the arpeggio pattern is played then repeated one octave up. In Random mode, the notes you input are played in random order over 2 octaves.
3 Oct	Same as 2 Oct but extended to a three octave range.
4 Oct	Same as 2 Oct but extended to a four octave range.

Repeat

- **Activate this to repeat each note in the generated arpeggio.**
  Since each note is played back twice at the set Rate, the total length of the arpeggio will be twice as long.

Direction

- **Click-hold in the display and drag up/down to select the direction of the arpeggio/pattern notes.**
  Values: Up, Down, Up+Down and Random.

Provided the Pattern function (see "Pattern") is not active, this is how it works:


Mode	Description
Up	This will generate an arpeggio that plays from the lowest note to the highest note.
Down	Notes are played from the highest note to the lowest note.
Up+Down	Notes are played from lowest note to highest, then from highest back down to the lowest. The very lowest and the highest arpeggio notes are not repeated. I.e. the arpeggiator will play the lowest note to the second highest note, then the highest note to the second lowest note.
Random	The notes you input will be arpeggiated randomly.

If the Pattern function is active (see "Pattern"), the Direction setting only determines in which direction the steps should advance - regardless of the pitches of the notes in the pattern.

Hold


- **Click the Hold button to keep the arpeggio running even after you release all keys.**
  It will continue to arpeggiate the last notes played until a new note-on is received.
- **If you continue to hold down at least one key when Hold is on, any new notes will be added to the existing arpeggio as opposed to starting a new arpeggio.**

The Display sections



In the display sections you can design your arpeggios/patterns.

Normal (Arpeggio) mode




If none of the switches to the left of the display (Steps, Pattern or Velocity) are activated, the display only shows the orange moving step indicator (if you hold down more than one key on your MIDI Control Keyboard). The rest of the display area is dark.

- **The step indicator travels the same number of steps as the number of notes you play and hold on your MIDI Control Keyboard.**
  So, if you hold down a 5-note chord, the step indicator advances five steps before it starts over again.

Steps

If you want the arpeggio to always play a certain number of steps, regardless of how many keys you hold down, you can activate the Steps function. This is perfect for maintaining a steady "beat" in your song.

1. **Click the Steps switch to activate the Steps function.**
   The default value is 4 steps.
2. **Click or click-hold and drag on the right side of the orange bar on the area above the step indicator, to increase or decrease the number of steps:**



   The arpeggio (or Pattern, see below) will restart after the set number of steps, regardless of how many notes you are playing.

   Range: 1-16 steps.


Pattern

In the default "Arpeggio mode" (Pattern switch off), the arpeggiator(s) work in the standard "monophonic" fashion, where the notes are played back one by one according to the settings you have made in the left section of the device.

With Pattern activated, the arpeggiator turns into a combined pattern player + arpeggiator. Pattern mode allows for up to four-note polyphonic "arpeggios".

Here is how it works:


1. **Click the Pattern switch to activate the Pattern function.**




All currently active pattern steps (green boxes) light up in the display.

The four green boxes in the example above represent the playback pattern if you hold a 4-note chord on your MIDI Control Keyboard. The lowest row in the display represents the lowest held note in the chord you play.


2. **Set the Direction to "Up" (see "Direction"), to make the examples below work as described.**
If you, for example, hold down the keys C4, E4, G4 and B4, the pattern plays back C4 in step 1, E4 in step 2, G4 in step 3 and B4 in step 4. Then the pattern starts over again:



If you hold down fewer keys, the pattern steps gets equally fewer steps and only plays back the new lowest to the new highest notes in the chord:




3. **Click in any of the matrix boxes to edit the pattern:**



Editing the pattern.

- **Each step can have a note that can be 1/3, 2/3 or 1/1 of the step's total length, depending on where in the box you click.**
  This way you could draw in "staccato" notes for desired steps, if you like. If you click the full 1/1 of a step (click in the right area of the box), and then click another consecutive box on the same row, the notes will be tied together (played in legato).

  If you hold down the keys C4, E4, G4 and B4, the pattern above now plays back C4 and B4 in step 1, E4 and B4 in step 2, G4 in step 3 and B4 in step 4. Then the pattern starts over again:



- **Click anywhere on a filled box to delete the note.**
- **To fill several consecutive boxes on the same row with identical note lengths, click and hold on the desired position in the initial box and then drag to the right:**




Adding consecutive notes by click-holding and dragging.

Here are some general rules regarding Pattern Mode:


- **A pattern can be up to 16 steps long (if Steps is activated, see "Steps").**
- **The notes you play are then mapped to the four note positions for each step.**
  If you play a four note chord, some steps may play only the lowest note, others may play a higher note or a combination of notes or all four.
- **If you hold down more than four notes, note 5 and up are ignored completely in the pattern.**
  Note that if the Steps function is not active (see "Steps"), note 5 and up will add additional silent steps in the pattern, making the pattern longer.

- **If you play fewer notes than the number of rows you have programmed in you pattern, this is what happens:**
  Let's take the pattern below (with the Steps function off) as an example:




Pattern Mode with the Steps function off.


If you only hold down key C4, note C4 is repeated (since the pattern length is only one step with one key pressed):




If you hold down C4 and E4, the pattern plays back C4 and E4 alternating (since the pattern length is now two steps with two keys held):



If you hold down C4, E4, and G4 the pattern plays back C4, E4 and G4 alternating (since the pattern length is now three steps with three keys held):




- **If we now do the same procedure with the Steps function on - and set the number of steps to 4 - things work a little differently.**
  This is what happens:




Pattern Mode with the Steps function on.


If you only hold down key C4, note C4 is played back on step 1 and note C5 is played back on step 2. Steps 3 and 4 are silent. In other words, a new note one octave above is automatically generated on the second step:



If you hold down C4 and E4, the pattern plays back note C4 on step 1, note E4 on step 2, note C5 on step 3 and note E5 on step 4. So, the two held notes are played back one octave higher on steps 3 and 4:



If you hold down C4, E4, and G4 the pattern plays back C4 on step 1, E4 on step 2, G4 on step 3 and C5 on step 4. As you can see, the lowest held note is played back one octave higher on step 4:



Velocity

In default mode, when the Velocity function is off, the velocities of the input notes set the velocity of each generated note in the arpeggio/pattern. If you want to define the velocity values and draw them in manually, you can activate the Velocity function.


1. **Click the Velocity switch:**



2. **Click or click-hold and drag the blue Velocity bars to manually set the velocity values.**
   When you play your chords, the input velocity is disregarded and replaced by the values you drew in the display.


   Range: 0-127.

Shift Step




- **Change where in the arpeggio/pattern you want the playback to begin.**
  Range: -16 to + 16 steps.

Transpose



- **Transpose all the generated arpeggio/pattern notes equally, in semitone steps.**
  Range: -24 to + 24 semitones.

Gate Length



- **Change the lengths of the generated arpeggio/pattern notes.**
  Here you can change the "gate/hold" time for the generated arpeggio/pattern notes. 100% means the gate time is exactly one full Step. A Length of 25% results in a gate time of 1/4 of a Step and a Length of 400% means a gate time of four Steps.

  Range: 25%-400%.

Note Echo



Note Echo simulates a MIDI delay effect, by adding repeats of the incoming MIDI notes. The Note Echo device is polyphonic, so you can get repeats of entire chords if you like.

Step Length

The Step Length knob controls the echo time, and consequently also the time between the repeats. The step length range is 0 to 1000 milliseconds. When Tempo Sync (see below) is enabled, the range is 1/128 notes up to ½ note.

- **A Step Length of 0 makes it possible to create chords and clusters, since all steps are played back simultaneously. See "Creating parallel chords" for a practical example.**

Tempo Sync

Switch on to sync the Step Length (see above) to the Reason sequencer tempo.

Repeats

This knob sets the number of repeats, from 1-16. The number of repeats is also shown in the display.

Velocity

The Velocity knob controls the linear increase or decrease of the Note Velocity value for each step.

The range is from 10% to 200%, where 100% means the velocity value is left unchanged throughout the repeats. Values below 100% means a decrease of the velocity values, and values above 100% means increasing velocity with each repeat.

The velocity values are represented by blue bars in the display. The blue line in the bars indicates the 100% value.

Pitch

With the Pitch knob you set how many semitones each step should be transposed relative to the previous step. The function is linear for all repeats. The Pitch values are represented by orange bars in the display.

The range is –12 to +12 semitones. 0 is the default value and means no transposition of the input notes.

! **If you use very high or very low Pitch value settings together with many Repeats, the note range of the associated instrument might be exceeded. If this happens, any remaining repeats will be silent.**

Display

Aside from showing number of Repeats, Velocity and Pitch (transposition) information, the display can also be used if you want to mute individual repeats.

- **Click the desired green circles in the display, to mute the corresponding repeat.**
  This way you can create interesting rhythmic repeats. The first green circle (to the left in the display) represents the incoming "dry" MIDI Note. This can be muted as well, if you like. By default, all repeats are on (unmuted).

Note Tool




The Note Tool Player device can be used for processing MIDI notes in various ways. For example, you could transpose notes, change the Velocity, alter the note length and restrict the polyphony.

Note Tool features two main sections: the Filter and the Adjust sections. The Filter section can filter the incoming MIDI notes, depending on the chosen Note Range and/or Velocity. The Adjust section processes the MIDI notes and then outputs them to the attached instrument device.

Note Tool also has a Mode selector, which lets you route the Filter and Adjust sections before or after one another.

Mode



- **Click the Mode display and select how you want the Filter and Adjust sections to be routed.**
  "Filter > Adjust" puts the Filter before the Adjust section.
  "Adjust > Filter" puts the Adjust section before the Filter.
  "Filter > Adjust (Split)" puts the Filter before the Adjust section, but the notes rejected by the filter (the notes that normally would be removed) are passed on directly to the output. This allows using the Adjust section on certain notes only, and leave the others unaffected.

Filter




The Filter section in "Filter > Adjust" Mode.

The Filter section features settings for Pitch Range and Velocity Range. These can be used either individually or together.

Pitch Range


1. **Click the Pitch Range button to activate the Pitch Range filter.**
2. **Drag the note numbers up/down to set the desired note range:**



- ▶ **Alternatively, drag the blue range handles (or the bar) sideways to set the note range.**
  You can also drag the thin vertical lines in the display to set the note range.
  Range: C-2 to G8
- ▶ **Hold [Shift] and click the handles (or the bar) to flip the note range.**


Velocity Range

1. **Click the Velocity Range button to activate the Velocity Range filter.**
2. **Drag the Lo and Hi Velocity numbers up/down to set the desired velocity range:**



- ▶ **Alternatively, drag the yellow range handles (or the bar) up/down to set the velocity range.**
  You can also drag the thin horizontal lines in the display to set the velocity range.
  Range: 1-127
- ▶ **Hold [Shift] and click the handles (or the bar) to flip the velocity range.**


Filter display



The Filter display shows the notes that come into the Filter section, and their Velocity levels.

- **The blue vertical lines represent notes that are within the note and velocity ranges.**
- **The red vertical lines indicate notes that are being filtered out, due to their being outside of the note or velocity ranges.**
  Depending on which Mode you have selected (see "Mode"), the red notes are either muted (in "Filter > Adjust" mode) or sent unprocessed to the attached instrument device (in "Filter > Adjust (Split)" mode).
- **in "Adjust > Filter" mode, any changes you make in the Adjust section (pitch, velocity, polyphony) will be reflected in the Filter display.**

Adjust



The Adjust section in "Filter > Adjust" Mode.


The Adjust section is where the MIDI notes are processed. The section features settings for six different parameters. These parameters be used either individually or together in all possible combinations.

Pitch



1. **Click the Pitch button to activate the Pitch settings.**
2. **Click the left part of the Pitch display and select if you want the pitch transposition to be an Offset to the input note(s) or a Fixed pitch.**
   Range: Offset or Fixed
3. **Click the right part of the display and drag up/down to select the desired transposition offset - or to set a fixed note number.**
   Range: +/- 24 semitones in Offset mode. C-2 to G8 in Fixed mode.


Octave



1. **Click the Octave button to activate the Octave transposition function.**
2. **Click the - or + buttons to change the transposition down/up one octave at a time.**
   Alternatively, click one of the rectangles to select the desired octave.


   Range: +/- 3 octaves

Velocity



1. **Click the Velocity button to activate the Velocity settings.**
2. **Click the left part of the Velocity display and select if you want the velocity change to be an Offset to the input velocity, a Fixed velocity or Scaled velocity.**
   Range: Offset, Fixed or Scale
3. **Click the right part of the display and drag up/down to select the desired value.**
   Range: +/- 127 in Offset mode, 1-127 in Fixed mode, and 1-800% in Scale mode.

- **Click and drag the velocity curve if you want exponential or logarithmic velocity characteristics instead of the default linear type.**

  Drag the curve up/left to get relatively high velocity even when you play fairly soft.

  Drag the curve down/right to get relatively low velocity even when you play fairly hard.


  Drag the end points up/down to set a narrower velocity range. The Velocity range is also indicated by the numbers to the right in the display.

- **Double click in the velocity display to add one extra point.**
  This makes it possible to create different curves/slopes on either side of the added point:

- **Double click the extra point to delete it, if desired.**

Note Length



1. **Click the Note Length button to activate the Note Length settings.**
2. **Click the left part of the display to select Min, Max or Fixed.**
   This determines if the notes should have a minimum length, a maximum length, or a fixed length of the value selected in the right part of the display (see below).
3. **Click the right part of the display to select the desired note length value.**
   Range: Pulse (a couple of ticks), 1/128, 1/64, 1/32, 1/16T, 1/16, 1/8T, 1/8, 1/4T, 3/16, 1/4, 1/2 and 1/1.

Restrict Poly




1. **Click the Restrict Poly button if you want to restrict the polyphony of the processed notes.**
2. **Click the left part of the display to and drag up/down select the max number of polyphony.**
   Range: 1-16
3. **Click the right part of the display to select how the polyphony restriction should be applied.**
   Select "First Note" to start the restriction, counting from the first played note in the chord/strum.

   Select "Low Note" to restrict only notes played above the lowest note to be restricted. If you have reached the restricted number of polyphony and then play a note below the current lowest note, the new note will sound and the highest note will stop.

   Select "High Note" to restrict only notes played below the highest note to be restricted. If you have reached the restricted number of polyphony and then play a note above the current highest note, the new note will sound and the lowest note will stop.

   Select "Last Note" to always be able to add new notes and automatically silence the first played note in the chord.

Hold




1. **Click the Hold button if you want to keep the note(s) sustaining indefinitely.**
2. **Click the display and choose between "Hold All", "Latch" or "Chord".**
   Select "Hold All" to have all added notes sustain indefinitely, until you click the button to the right of the display.

   Select "Latch" to have a note or chord sustaining until you press a new note or chord, which will then "take over" and keep sustaining. Click the button to the right of the display to stop the last note/chord from sustaining.

   Select "Chord" to have all added notes sustain until you release the last held note in the chord.


In/Out

Note displays




The note displays show the latest note and velocity input values in the top (IN) display and the last processed note and velocity value in the bottom (OUT) display.

Using CV



On the back of Note Tool, you'll find a comprehensive set of CV inputs and outputs.

- **Input: Gate In and CV In**
  Here you can connect the Note CV Out and Gate Out of another device, to have Note Tool process notes sent from another device. For example, connect the Step Sequencer CV Outputs from a Thor to send the step sequencer notes to Note Tool.
- **Reject All Gate In**
  A gate signal sent to this input will make Note Tool reject all notes, overriding the settings in the Filter section. The note rejection is indicated in the Filter display:



- **Note Filter CV Outputs**
  These outputs will send the last rejected or passed notes as Note CV/Gate, for connection to other instrument devices. For example, this lets you send rejected notes to another instrument, using the Filter section as a device splitter.
- **Restrict Poly CV Outputs**
  These outputs will send notes excluded by the Restrict Polyphony setting as Note CV/Gate, for connection to other instrument devices.
- **Pitch, Octave, Velocity, Length and Hold Gate Inputs**
  A gate signal sent to these inputs will turn the corresponding function off or on (depending on whether it is activated on the front panel or not).
- **Pitch Offset, Octave Offset, Velocity Offset, Length Offset and Clear Hold CV Inputs**
  Bipolar CV signals connected to the first four of these inputs will modulate the values of the corresponding Adjust function.

  A positive CV trig signal (a short gate) on the Clear Hold input will clear the Hold function.
- **Gate and CV Outs**
  These outputs send out a Gate and CV value based on the last note output from Note Tool.

Random Tool



The Random Tool device can be used for randomizing various parameters of input MIDI notes. It can change the pitch, velocity and note lengths, or let through notes and chords based on probability. There is also a function for defining which notes/chords will be let through depending on the order you play them.

Conditional



This function lets you set which notes/chords you want to let through, depending on the order you play them (in sequence).


1. **Click the Conditional button to activate the function.**
2. **Click and drag the number up/down to set the number of notes you want to have in your sequence.**
   Range: 2-8
3. **Click an orange rectangular button to de-activate a step and click a dark button to activate the step.**
   An orange button means activated and a dark button means de-activated. When you play notes/chords, an orange dash below the buttons indicates which step is currently played.
4. **Click "Reset on Play" to bring up a menu with the following alternatives:**
   "Reset on Play" means the sequence will restart from step one when main sequencer playback starts.

   Select "Reset 1 sec" or "Reset 5 sec" to automatically reset the sequence to the first step after 1 or 5 seconds respectively.

   "No Reset" mean the sequence will not reset automatically.

- **If the Chord button is on, each chord you play will trigger a single step (i.e. the sequence will stay on the same step as long as any note is held).**

Probability



This function lets you set the probability for notes to be let through.

1. **Click the Probability button to activate the function.**
2. **Click and drag the figure up/down to set the probability for notes to pass through.**
   A hand symbol in the display indicates when notes are being stopped from passing through.

   Range: 0-100%

Random Pitch



This function will randomly change the pitch of the notes.

1. **Click the Random Pitch button to activate the function.**
2. **Click "Between" to bring up a menu with the following alternatives:**
   "Set To" lets you set a specific note to be played back, regardless of the input notes.


   "Octaves +/-" lets you set an octave range between +/-1 and +/-8. The notes you play will then be randomly octave-shifted accordingly.

   "Octaves +" lets you set an octave range between +1 and +8. The notes you play will be randomly octave-shifted (but only to higher octaves)

   "Semitones +/-" lets you set a semitone range between +/-1 and +/-127. The notes you play will then be randomly transposed within the set range. Note, though, that notes might end up outside of the available MIDI Note range, in which case the notes will be limited to the first or last note of the MIDI Note Range.

   "Between" lets you randomize the notes within the set note range, regardless of the original note pitches.
3. **Click and drag up/down to set the desired notes/range.**
4. **Click and drag up/down in the "Chance" area to set the probability for the random pitch function.**
   Range: 0-100%

Random Velocity




This function will randomly change the velocity of the notes.

1. **Click the Random Velocity button to activate the function.**
2. **Click "Offset +/-" to bring up a menu with the following alternatives:**
   "Set To" lets you set a specific Velocity to be played back, regardless of the input notes.
   Range: 1-127

   "Offset +/-" lets you set a Velocity offset between +/-1 and +/-127.

   "Between" lets you randomize the Velocity within the set range (+/-127), regardless of the original note velocities.
3. **Click and drag up/down to set the desired Velocity/Velocity range.**
4. **Click and drag up/down in the "Chance" area to set the probability for the random velocity function.**
   Range: 0-100%

Random Note Length



This function will randomly change the length of the notes.

1. **Click the Random Note Length button to activate the function.**
2. **Click "Set To" to bring up a menu with the following alternatives:**
   "Set To" lets you set a specific note length to be played back, regardless of the input note lengths.
   Range: Pulse (a couple of ticks), 1/128, 1/64, 1/32, 1/16T, 1/16, 1/8T, 1/8, 1/4T, 3/16, 1/4, 1/2 and 1/1.


   "Between" lets you randomize the note lengths within the set range.
3. **Click and drag up/down to set the desired note length/note length range.**
4. **Click and drag up/down in the "Chance" area to set the probability for the random note length function.**
   Range: 0-100%

Sync Chance



- **Click the Sync Chance button to sync the Chance functions of the "Random Pitch", "Random Velocity" and "Random Note Length" sections so that they are triggered at the same time.**
  In this mode, the Chance value will be common for the three functions.

Using CV




On the back of Random Tool, you'll find a comprehensive set of CV inputs and outputs.

- **Input: Gate In and CV In**
  Here you can connect the Note CV Out and Gate Out of another device, to have Random Tool process notes sent from another device. For example, connect the Step Sequencer CV Outputs from a Thor to send the step sequencer notes to Random Tool.
- **Conditional Rejected Gate Out and CV Out.**
  These outputs send out a Gate and Note CV signal for rejected notes in the Conditional section.
- **Probability Rejected Gate Out and CV Out.**
  These outputs send out a Gate and Note CV signal for rejected notes in the Probability section.

- **Pitch, Velocity and Note Length Gate Ins**
  A gate signal sent to these inputs will turn the corresponding function off or on (depending on whether it is activated on the front panel or not).
- **Pitch, Velocity and Note Length CV Ins**
  Bipolar CV signals connected to these inputs will modulate the "Set To" value of the corresponding randomize function.
- **Pitch, Velocity and Note Length CV/Gate Outs**
  These outputs send out CV and Gate for notes changed by the corresponding randomize function. For example, if the pitch of a note is randomly changed, that note will also be sent out from the Pitch CV/Gate outputs.
- **Gate and CV Outs**
  These outputs send out a Gate and CV value based on the last note output from Random Tool.

Scales & Chords



The Scales & Chords device either transposes incoming notes to fit a set scale, or transposes notes and generates chords that fit the desired scale. Scales & Chords has a number of built-in preset scales, and you can also create your own custom scales!

Here are some examples of how you can use it:

- **to get chords from single note inputs.**
- **to get new chord voicings and progressions that feel fresh and inspires your music making.**
- **to experiment with existing note lines, by transforming them to different scales.**
- **to get the notes you play to automatically fit the music.**
- **to easily be able to play chords without using a MIDI Control Keyboard.**
  You could write single MIDI notes in a Note clip and have the Scales & Chords Player generate the chords for you.
- **to get chords that sound right, without knowledge of tonality/scales.**

Scales

In the Scales section you choose which key and scale you want.

▶ **Note that all parameters in the Scales section can be automated, so you could change key and scale anywhere throughout your song if you like!**

Key

▶ **Click to select the desired Key from the list that appears.**
12 Keys are available, from C to B.

Scale

▶ **Click to select the desired Scale from the list that appears.**
13 scales are available, plus a Custom scale that you can create yourself (see below). The preset Scales are:

Major, Minor, Lydian, Mixolydian, Spanish, Dorian, Phrygian, Harmonic Minor, Melodic Minor, Major Pentatonic, Minor Pentatonic, Hemi Pentatonic and Chromatic.

- **The notes that fit the selected Key and Scale are displayed in light blue in the keyboard display in the Scales section:**




The Dorian scale in the key of E.

The notes in the selected Key and Scale are then automatically repeated throughout all octaves of the entire MIDI Note range.

- **Notes you play on your MIDI Control Keyboard/On-screen Piano Keys are indicated in orange in the Scales keyboard display.**

Creating a Custom Scale

▶ **Create a custom Scale by clicking the desired keys in the keyboard display in the Scale section:**



Selected notes are colored light blue. The selected notes are then automatically repeated throughout all octaves of the entire MIDI Note range.


- **You can easily switch between your Custom Scale and any of the preset Scales whenever you want, by clicking the "Scale" display and selecting the desired scale from the list that appears.**
- **Your Custom Scale is automatically saved with the song.**
Your Custom Scale is also saved in the Scales & Chords patch, should you choose to save your settings as a patch.

Filter Notes

- **When the Filter Notes switch is off (default), incoming notes outside the set Scale (see "Scales") are transposed to fit the scale.**
Wrong notes are automatically transposed to the closest correct note. If the wrong note is equally near two correct notes, the wrong note is transposed to the lowest of the correct notes.
- **When the Filter Notes switch is on, incoming notes that are outside the set scale will be filtered out (silent) instead of transposed.**
The display below shows a hand symbol whenever wrong input notes are filtered out (silent).

Chords

▶ **Switch on the Chords function to generate chords out of single notes.**
When you play a note, you will get a chord that fits the set Scale (see "Scales"), and contains the number of notes set with the "Notes" knob. The generated notes are shown in real-time in the keyboard display at the bottom of the Chords section:



! **If you play several notes at the same time you will get several chords, which might be cool or just weird. If notes in the generated chords should coincide, only one instance of the notes are played back (to avoid doubled/layered notes).**


▶ **If you want to create "parallel chords", i.e. chords that contain notes with the same relative intervals, the Note Echo device is better suited for this, see "Creating parallel chords".**

Notes

▶ **Set the desired number of notes in the generated chords.**
Range: 1-5 notes.

Inversion

The Inversion knob defines which note in the generated chord should be the lowest. The function tries to keep the lowest generated note in the chord as close to the played root note as possible. Below is an example of inversions of a generated 4-note chord in the Scale C Major, played from a C note of the MIDI Control Keyboard:



Inversions of a generated 4-note chord played from the (orange) C note.

! **Note that the Inversion function is only relevant if the Inversion number is less than the selected "Notes" value. So, if the Notes value is 4, only a maximum Inversion value of 3 is useful.**

Open Chords

When the Open Chords function is active, some notes in the generated chords are transposed in octave steps, so that the notes are not so close to each other. The transposition is different depending on the "Inversion" and the "Notes" settings.

Add

The Add functions can be used for adding notes to the generated chords:

- **The Add Oct Up function adds a note one octave above the root note.**
- **The Add Oct Down function adds a note one octave below the root note.**

- **The Add Color function adds a note two thirds above the highest note in the tertian chord structure.**
  If the Notes value in the Chord section is 3, you will get a regular triad (e.g. a C major). Adding a sixth above top will mean adding a 9 (e.g. the note D). Similarly, if the Notes value in the Chord section is 4, this will add an 11; if the Notes value in the Chord section is 5, this will add a 13.

▶ **All three Add functions can be used together, simultaneously.**

! **If the added note is already used in the chord (due to inversions, open chord etc), the note is transposed up another octave (or down, in case of Oct Down).**

Alter

The Alter button is a momentary button that turns off as soon as you release the mouse button (like the Trig button on The Echo, for example). It alters the chord slightly so that it goes outside the current scale. The result depends on the Key (as set in the Scale section), whether the current scale is major or minor and what note you play (relative to the Scale Key).

The chord is altered by having one of the chord notes changed. For example, a major chord may be changed to a minor chord, or vice versa.

Tips & Tricks

Generating scale-correct arpeggios from single notes

By chaining a Scales & Chords device with a Dual Arpeggio device you will be able to generate scale-correct arpeggios by playing single notes.

1. **Create an Instrument device.**
   In this example we create an ID8.
2. **Select the ID8 device in the rack and double-click a Scales & Chords device.**
   The Scales and Chords device is automatically attached to the ID8.
3. **Select the ID8 device in the rack and double-click a Dual Arpeggio device.**
   The Dual Arpeggio device is attached between the Scales & Chords device and the ID8 device:
4. **On the Scales & Chords device, select Key and Scale, then switch on the Chords function set the Notes knob to 4.**
5. **Play single notes on your MIDI Control Keyboard (or On-screen Piano Keys) and hear how four-note scale-correct arpeggios are now generated.**

Generating chord arpeggios

By chaining a Dual Arpeggio device with a Scales & Chords device you will be able to generate arpeggiated chords.


1. **Create an Instrument device.**
   In this example we create an ID8.
2. **Select the ID8 device in the rack and double-click a Dual Arpeggio device.**
   The Dual Arpeggio device is automatically attached to the ID8.
3. **Select the ID8 device in the rack and double-click a Scales & Chords device.**
   The Scales and Chords device is attached between the Dual Arpeggio device and the ID8 device:
4. **On the Scales & Chords device, select Key and Scale, then switch on the Chords function set the Notes knob to 3.**
5. **Play chords on your MIDI Control Keyboard (or On-screen Piano Keys) and hear how arpeggiated three-note chords are now generated.**

Creating parallel chords

The Scales & Chords Player is great for generating chords that stay within a set scale, but sometimes you may want chords that keep their *form* when you play different notes. For example, you might want a minor 9th chord that is transposed with the notes you play, but stays a minor 9th chords (like with the Chord Memory function of some synthesizers, for example). This can be called "parallel chords", and is actually best done with the Note Echo device:

1. **Set Step Length to 0.**
2. **Raise the Repeats value to maximum.**
3. **Set the Pitch to +1 semitone.**
   This means that each repeat is 1 semitone higher than the previous - and since Step Length is 0, they are all played at the same time. If you play a note now, you get a dense cluster of notes - not very musical or useful, but let's continue:

4. **Click the Repeat circles in the display to turn off the notes you don't want.**
   This is how you would set up a minor 9th chord for example:




5. **Play different (single) notes on your MIDI Control Keyboard/On-screen Piano Keys to get parallel, transposed chords.**
   You could also add a Dual Arpeggio Player after the Note Echo for cool arpeggios!

▶ **The Note Echo device comes with a number of ready-made chord patches. You find them by clicking the Browse Patch button on the Note Echo device and opening the "Chords" sub-folder in the browser.**

Using a Scales & Chords device as a "MIDI Note monitor"

Sometimes it might be interesting to see in real-time what notes/chords a Player or "Player chain" actually generates.

1. **Add a Chords & Scales device last (at the bottom) in the Player chain.**
2. **Make sure Scale is set to "Chromatic" and that Filter Notes and Chords are Off.**
   When you play through your Player(s) the generated notes/chords are now displayed in the Scales & Chords keyboard display:



The "Creating parallel chords" example monitored in a Scales & Chords device when playing the note C.

Chapter 14
Working with Rack Extensions



About this chapter

This chapter describes the procedures and techniques for managing Rack Extension devices.

What are Rack Extensions?

Rack Extensions are additional rack devices that can be purchased in the Reason Studios web shop at www.reasonstudios.com/shop and used together with the internal devices in the rack. Rack Extensions can be instruments, effects or utility devices, such as mixers and CV processors. Rack Extension devices are developed by Reason Studios as well as by 3rd party companies.

Rack Extension devices integrate fully with the Reason rack:

- **Cables can be connected on the rear panels, just like on the internal rack devices.**
- **CV signals can be routed like on the internal rack devices.**
- **Rack Extension devices are combinable with other Rack Extension and internal devices (see "The Combinator" chapter).**
- **Panel parameters are automatable and remotable.**

Future compatibility

Rack Extensions are Windows and Mac-compatible and will work with any operating system and platform that Reason supports - now and in the future.

Trying and buying Rack Extensions

Trial versions of Rack Extensions

You can try out a Rack Extension by going to the Reason Studios web shop at www.reasonstudios.com/shop and using the "Try" function. This gives you a trial license which will last for 30 days (counted from when you clicked the "Try" button). During this time, the Rack Extension is fully operational, with no limitations.

When the trial license expires, the Rack Extension will be removed from the program menus. However, it will remain installed unless you manually uninstall it. Should you choose to purchase the Rack Extension later on, you don't need to download it again.

You can only try a Rack Extension once (one 30-day period).

Buying Rack Extensions

When you purchase a Rack Extension, a license is automatically written to your Reason Studios user account on the Reason Studios web site. Just like with your Reason license, you can write a Rack Extension license to your authorized computer. You can download and install the Rack Extension on as many computers as you like. However, to use the Rack Extension in Reason you either need your authorized computer or an Internet connection to run with Internet Verification.

! Rack Extension devices are not available when you run Reason in Demo Mode.

If you move to another computer, you can download and install all your Rack Extensions by going to the Devices tab in the Reason Companion app and clicking the "Install all" button. This function is also excellent for making sure you got the latest versions and updates of all your Rack Extensions. Only files that are missing on your computer will be downloaded and installed.

Rack Extensions can be updated, with fixes and additions. Updates are indicated on the Devices tab in the Reason Companion app. Rack Extensions are backwards compatible, meaning that you can open older songs and patches and they will sound the same.

Rent-to-Own Rack Extensions

An alternative to purchasing Rack Extension licenses one at a time is to use the Rent-to-Own program. To utilize Rent-to-Own Rack Extensions, please go to the Reason Studios web shop at www.reasonstudios.com/shop.

Installing and managing Rack Extensions

! **in Reason 12.7 and later, Rack Extension installation and management is handled completely in the Reason Companion app - not by Authorizer, which is now deprecated.**


Whenever you download and install a Rack Extension, from the web shop or your user account, this will be handled by the Reason Companion application. Reason Companion will automatically launch when you Buy, Try or Download a Rack Extension from the Reason Studios web shop.

Reason Companion checks what's already installed on your computer, downloads any missing files and puts them in the correct locations.

! **Reason Companion automatically writes Rack Extension licenses to your computer, when applicable.**

If you want to check what Rack Extensions are installed on your computer, you need to launch Reason Companion:

▶ **Either select Rack Extensions from the Window menu in Reason or locate the Reason Companion application on your computer and launch it manually.**
Reason Companion lists all currently available Rack Extensions on the Devices tab:



The Devices tab in Reason Companion lists the Rack Extension devices currently installed on your computer.

▪ **If you are subscribing to Reason+, the Reason+ Rack Extensions are listed at the top of the Devices tab.**
Further down on the Devices tab your purchased Rack Extensions are displayed in the "My Rack Extensions" section.

▪ **You can search for a Rack Extension, by typing in its name (or the first part of the name) in the Filter Rack Extensions box.**


▶ **Click the Update all button to update all currently installed Rack Extension to the latest versions.**
Note that only the Rack Extensions in the corresponding section (Reason+ Rack Extensions or "My Rack Extensions") are affected.

▶ **Click the Install all button to install all Rack Extensions displayed on the Devices tab.**
Note that only the Rack Extensions in the corresponding section (Reason+ Rack Extensions or "My Rack Extensions") are affected.

▶ **Click the Update/Install/Uninstall buttons to perform the corresponding actions for individual Rack Extensions.**
If you have purchased the Rack Extension (or if it's included in your Reason+ subscription), you can always reinstall an uninstalled Rack Extension at any time.

Using Rack Extensions in Reason


Rack Extensions behave just like internal Reason devices, and are listed together with the Reason Studios devices in the Create menu subgroups and on the Device Palette:



The Complex-1 Rack Extension is available from the Instruments palette in the Device Palette and in the Create menu.

The installed Rack Extension devices are sorted in the appropriate subgroups and are listed, per manufacturer, in alphabetical order. However, Rack Extension devices from Reason Studios are always placed first in the list, below the internal Reason devices.


- **Click the menu button and make sure the "Show Reason devices" box is selected, since this also determines whether or not to show 3rd-party Rack Extensions:**




- **To create a Rack Extension device, either select it in the appropriate subgroup in the Create menu, double click or drag and drop from the Device Palette - or select "Create Instrument..." or "Create Effect..." from the Create menu.** The Rack Extension device is placed in the rack and routed according to the standard rules, see "Creating devices".

If a Rack Extension supports patches, you will find the included patches in the Rack Extension itself. To get there, either click the “Browse patch” button on the Rack Extension device to bring up the Browser. Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and press [F]:

1. **In the Browser, click "Reason Library” and unfold the "Rack Extensions" folder.**
   This lists all available Rack Extensions in alphabetical order:



2. **Scroll down and unfold the desired Rack Extension folder to browse its patch content.**




   If you are browsing patches from a Rack Extension device (by clicking the “Browse patch” button on the device panel), patches and folders for that specific device type are displayed in the Browser list right away.

About missing Rack Extensions

When you open a Reason song from another user, it may have been created with Rack Extensions that you don't have installed - or even own. It might be a song from a friend, or a song that you have made using a Rack Extension with a trial license (that has since expired).

When you open such a song, the following alert appears:



Now, you can choose to open the song without the Rack Extension(s), or go to the Reason Studios web shop and Try or Buy the missing Rack Extension(s). If you click OK, the song opens without the missing Rack Extension(s).

All such missing devices in a song are replaced by generic placeholder devices:



A "Missing Device" placeholder plate for a Rack Extension device, which is currently unavailable on your computer.

The placeholder device itself will be silent. If it's an effect, it will bypass the sound (or be silent, if connected as a send effect).

If you're collaborating with a friend you can safely save the song and send it back. When your friend opens the song, the Rack Extension device will be restored with all settings intact.

Acquiring missing Rack Extensions

If you change your mind and want to hear the song with the Rack Extension(s) included, you could either download a paid version or a trial version from the Reason Studios web shop:

1. **Click inside the "View in Companion" area on the placeholder panel to launch the Companion app and from there get to the Reason Studios web shop and Try or Buy the Rack Extension:**



2. **After you have downloaded the (paid or trial) Rack Extension device(s), restart Reason and open the song again.** Now, the Missing Device placeholders have been replaced by the downloaded Rack Extension(s) and the song will sound as originally intended.

Chapter 15
Working with VST Plugins

About this chapter

This chapter describes the procedures and techniques for working with VST plugins in Reason.

About VST plugins

VST (Virtual Studio Technology) is a software instruments and effects plug-in format designed by Steinberg. Reason 12.5 and later supports 64-bit VST3 and VST2 (2.4) plugins. VST plugins integrate nicely with the Reason rack:

- **A VST Plugin is represented by a Plugin Rack Device in the Reason rack.**
- **Cables can be connected on the rear panels of the Plugin Rack Devices, just like on the internal rack devices.**
- **CV signals can be routed like on the internal rack devices.**
- **Plugin Rack Devices are combinable with other Plugin Rack Devices, Rack Extensions and internal devices (see "The Combinator" chapter).**
- **Panel parameters are automatable and remotable.**

VST compatibility in Reason

- **Reason 12.5 and later supports 64-bit VST3 and 64-bit VST2 (2.4) plugins.**
- **Both Windows and Mac VSTs are supported.**

! **Multitimbrality in VSTs is currently not supported - only one MIDI channel per VST can be used at a time. If you are using a multitimbral VST it will only receive on MIDI Channel 1.**

! **Reason does not support VSTs that output MIDI.**

! **VSTs are NOT supported in Reason Rack Plugin.**

Installing and enabling VST plugins

VST plugins are downloaded and installed individually for each VST, as designed by the VST plugin manufacturer. No special Reason Studios app or functions are required for installing VSTs.

About VST licenses

VST licenses and authorizations are handled by the individual VST manufacturers. VSTs cannot be authorized using the Reason Studios authorization system used for Reason and Rack Extensions.

Installing VST plugins under Windows

At each launch, Reason automatically scans for installed VST plugins in the following folders:

C:\Program Files\VSTplugins\ (VST2 plugins)

C:\Program Files\Steinberg\VSTplugins\ (VST2 plugins)

C:\Program Files\Common Files\Steinberg\VST2\ (VST2 plugins)

C:\Program Files\Common Files\VST3\ (VST3 plugins)

▶ **If you don't have any VST plugins installed on your Windows computer you might have to manually create a folder according to one of the paths listed above.**
When you then install VST plugins later on, instruct the VST Installation program to install the vst3/dll files in the appropriate folder. If there is no installation program for the VST, manually place the vst3/dll files in this folder.

- **It's also possible to define your own custom VST folders on the Folders tab in Settings, see "Defining custom VST folders".**

Installing VST plugins under Mac

On a Mac OS computer Reason automatically scans for installed VST plugins in the following folders at each launch:

Library/Audio/Plug-ins/VST (VST2 plugins)


~/Library/Audio/Plug-ins/VST (VST2 plugins)

Library/Audio/Plug-Ins/VST3 (VST3 plugins)

- ▶ **If you don't have any VST plugins installed on your Mac you might have to manually create a folder according to one of the paths listed above.**
  When you then install VST plugins later on, instruct the VST Installation program to install the files in the appropriate folder. If there is no installation program for the VST, manually place the VST files in this folder.
- ▪ **It's also possible to define your own custom VST folders on the Folders tab in Settings, see "Defining custom VST folders".**


Enabling VST plugins in Reason

- ▶ **To make newly installed VST plugins s available in Reason, simply (re)launch Reason.**
  The available VST plugins are displayed on the corresponding palettes in the Reason Device Palette; VST instruments on the "Instruments" palette and VST effects on the "Effects" palette. VSTs that are internally tagged with "Analysis" are placed on the "Utilities" palette.
- ▪ **The VST plugins appear in the corresponding manufacturer sections, the same way as Rack Extensions are presented:**



VST instruments on the Instruments palette in the Device Palette.

- ▪ **VST3 plugins have a small golden VST3 label at the top left of the device thumbnail - and VST2 plugins have a small blue VST2 label. This is to distinguish them from Rack Extension devices, which don't have any label.**
- ▶ **Click the menu button and make sure the "Show VST2 plugins" and "Show VST3 plugins" boxes are ticked:**




If both the VST2 and VST3 boxes are ticked, you can also choose to hide any VST2 "duplicates" of the same device by ticking the "Hide VST2 Duplicates" box.

- ▪ **Some VST plugins might be represented by a generic device "panel" in the Browser. If this is the case, you can have Reason take a screenshot of the VST plugin panel and automatically replace the generic panel, see "Screenshot".**

Using VST plugins in Reason

VST plugins are listed together with Rack Extensions and Reason devices on the Device Palette and in the Create menu subgroups:



The Arturia ARP 2600 V3 VST2 and VST3 instruments are available on the Instruments Device Palette and from the Create menu.

The VST plugins are sorted in the appropriate subgroups and are listed, per manufacturer, in alphabetical order. Note though, that devices from Reason Studios are always placed first in the list, below the internal Reason devices.

Adding VSTs to the rack

Adding VSTs to the rack is done in exactly the same way as when you add native devices and Rack Extensions.

1. **To create a VST, either select it in the appropriate subgroup in the Create menu, double click or drag and drop from the Device Palette, or select "Create Instrument..." or "Create Effect..." from the Create menu.**
   The Plugin Rack Device is placed in the rack and is auto-routed according to the standard rules. See "About auto-routing of VSTs in the rack" for more details about auto-routing of VSTs.

   Like with other devices, Instrument VST plugins automatically get a sequencer track, whereas effect and utility VSTs don't, by default.

2. **To edit the VST plugin, click the Open button on the Plugin Rack Device (see "The Plugin Rack Device" below).**
   A Plugin Window opens up and displays the VST panel.

The Plugin Rack Device

When you create a VST in Reason it's automatically housed in a Plugin Rack Device. The Plugin Rack Device is a "container" for the VST plugin and represents the VST in the Reason rack. The Plugin Rack Device much resembles a Combinator device and features audio inputs and outputs as well as CV connectors and a CV Programmer section.

If the VST is detected as an instrument the Plugin Rack Device is automatically connected to a Mix Channel device, just like any other instrument device in Reason.

Front panel



A Plugin Rack Device representing an Arturia ARP 2600 V3 VST3 instrument.




A Plugin Rack Device representing a Sonic Charge Permut8 VST2 effect.

A Plugin Rack Device for a VST instrument has Pitch and Mod Wheel controls, whereas a Plugin Rack Device for a VST effect has the standard "Bypass/On/Off" switch (like any other Effect device in the rack).

! **Note that setting the VST effect device in "Off" or "Bypass" will not disable the VST. This means the VST will still affect the CPU/DSP Load.**

- **The center and right sections of the Plugin Rack Device are identical, regardless of if it represents a VST instrument or VST effect.**
- **The Patch Load/Save section works in the same way as for the other device types in Reason (see "Loading patches" and "Saving patches").**
  There are also Next/Previous VST Program buttons to the right of the patch display, where you can step through the programs loaded in the VST plugin itself, see "Selecting VST presets/programs".
- **Above the Patch Load/Save section is the name of the corresponding VST, as well as the manufacturer's name.**
- **Below the Patch Load/Save section is a button for unfolding the CV Programmer (see "The CV Programmer").**
- **The display shows a screenshot of the corresponding VST (or a default logo).**
  At the top left of the display it's also stated if it's a VST2 or VST3 plugin.
- **At the bottom of the display is the Open button. Clicking this (or the image of the VST) brings up the VST in its Plugin Window (see "The Plugin Window").**
- **To the far right are audio input and output level meters, as well as indicators for Note On, Automation data and CV input.**
- **Below the indicators is an On/Off button for enabling/disabling the VST plugin completely.**
  Disabling a VST plugin will also reduce the CPU/DSP Load.

The CV Programmer




The CV Programmer of the Plugin Rack Device.

On the CV Programmer panel you can route CV signals from other (modulation) devices in the rack to parameters of the VST plugin. Each of the eight CV slots can receive a CV signal connected to the corresponding Modulation CV In connector on the rear panel of the Plugin Rack Device (see "Rear panel" below).

Refer to "CV modulation of VST parameters" for information on how to route CV signals to VST parameters.

Rear panel



The rear panel of a Plugin Rack Device representing a VST Instrument, with the CV Programmer unfolded.

The rear panel features Sequencer Control connectors for controlling VSTs from e.g. step sequencers and arpeggiator devices. This section is available only if the Plugin Rack Device represents a VST Instrument. To the right are audio inputs and outputs.

If the Plugin Rack Device represents a VST Effect, Audio Inputs 3-4 (Sidechain) are available at the top right on the upper section of the rear panel, together with the other main inputs and outputs.

On the unfolded CV Programmer/Optional Inputs & Outputs panel are eight CV modulation inputs, for controlling VST parameters from connected CV modulation sources.

To the right on the unfolded panel are optional audio inputs and outputs. If the VST supports the use of multiple audio inputs and/or outputs, the available jacks are indicated by green numbers.

For more details about CV controlling VSTs, see "CV modulation of VST parameters".

About auto-routing of VSTs in the rack

Auto-routing of VST instruments

The auto-routing rules for VST instruments are very straight forward:


- **VST instruments that output a stereo signal are automatically connected from Audio Out 1 (L) and 2 (R) of the Plugin Rack Device to the L and R inputs of a Mix Channel device.**
- **VST instruments that output a mono signal are automatically connected from Audio Out 1 (L) of the Plugin Rack Device to the L input of a Mix Channel device.**

Auto-routing of VST effects

Unlike with native Reason effects and Rack Extension effects, there can be mono VSTs, with mono in/mono out. Also, Reason doesn't know whether a stereo VST effect device is "dual mono" or generates stereo from a mono signal.

There are two cases to be aware of:

- **If you insert a Mono In-Mono Out VST effect in a stereo signal path, only the left output will be connected (resulting in a mono signal path):**



- **If you insert a Stereo VST effect in a mono signal path, Reason will route it as mono in-stereo out (changing the signal path to stereo):**




The Plugin Window

The VST plugin panel is shown in a separate floating window - the Plugin Window - that is kept on top of the song window(s). Several Plugin Windows can be open at the same time.

Opening the Plugin Window

▶ **Open the Plugin Window by clicking the Open button - or the VST image - on the Plugin Rack Device panel:**



The Plugin Window opens up and shows the VST panel:



The MicroTonic VST in its Plugin Window.

General functions in the Plugin Window

- **The title bar of the VST Plugin Window shows the name of the device instance (same as tape strip).**
  This is for helping you finding the correct Plugin Window, especially if there are several instances of the same plugin.


At the top of the Plugin Window are a number of icons:

- **Keep open**
  If you activate the "Keep open" function, the Plugin Window(s) will not be automatically closed when you select another device in the rack. Having the "Keep open" selected on several Plugin Windows makes it possible to have several VST panels open at the same time.
- **Automate**
  Click this button when you want to assign a VST parameter for automation in the Reason sequencer, see "Automating VST parameters".
- **Remote**
  Click this button and then select a VST parameter you want to remote control from your MIDI keyboard/control surface, see "Remote controlling VST parameters".

- **Screenshot**
  Click the camera symbol to take a screenshot of the VST front panel:



The screenshot is then automatically scaled down and placed on the corresponding palette in the Device Palette, and in the Plugin Rack Device display:



The screenshot of the MicroTonic VST is scaled down and displayed in the Browser and in the Plugin Rack Device.

Closing the Plugin Window

The Plugin Window can be closed in a number of different ways:

- **By clicking the Open button on the Plugin Rack Device panel (the same as for opening the Plugin Window).**
  This works regardless of whether the "Keep open" function in the Plugin Window is on or off.
- **By clicking the standard "window close" button in the upper corner of the Plugin Window.**
  This works regardless of whether the "Keep open" function in the Plugin Window is on or off.
- **By selecting another device in the rack.**
  If the "Keep open" function in the Plugin Window is active, selecting another device in the rack will NOT close the Plugin Window (see "Keep open" above).

Editing the VST parameters

Editing a VST is done in the same way as when editing a native device or a Rack Extension device, only VSTs are edited in their Plugin Windows - not in the rack.

! **Note that the standard "Reason" functions, such as holding [Shift] while turning a knob/moving a slider to improve the precision - or holding [Ctrl](Win) or [Cmd](Mac) to reset parameters to their default position/value - won't work for most VSTs. This is because the VST manufacturers define this type of functionality themselves.**

! **If the VST plugin has a built-in on-screen keyboard (etc), this can be used for auditioning sounds but you cannot use it for recording into Reason's sequencer!**

About Undo and Redo

The Undo/Redo functions in Reason also work in most situations when editing VST parameters in the Plugin Window(s).

Automating VST parameters

Automating VST parameters in the Reason sequencer works in a similar way as for native devices and Rack Extension devices. Basically, there are three (or four) ways of automating VST parameters in the Reason sequencer:


▶ **Start recording in the Reason sequencer and then edit the desired VST parameters while recording.**
Each of the edited VST parameters automatically gets their own automation lane on the sequencer track, with clips and automation points recorded. Make sure the Parameter Automation is record-enabled on the track first.

Another alternative is this:


1. **Click the Automate button in the Plugin Window.**



2. **Then, click the parameter you want to automate on the VST panel.**




The automated VST parameter gets an automation lane in the Reason sequencer:



3. **Then, you can draw automation clips and automation points, the same way you would for a native device or a Rack Extension device.**

- **A third alternative is to select the parameter from the Track Parameter Automation popup above the track list in the sequencer, see "Creating/adding parameter automation lanes":**




- **As a fourth alternative, some VSTs let you right click a parameter on the VST panel and select Automate from the context menu.**

CV modulation of VST parameters

There are eight CV inputs on the rear panel of the Plugin Rack Device. These CV inputs can be assigned on the CV Programmer panel of the Plugin Rack Device.

▶ **Click the CV Programmer button on the VST Rack Device panel to unfold the CV Programmer:**



The CV Programmer of the Plugin Rack Device.

For each slot on the CV Programmer panel you can:


- **Select a CV input.**
  Several slots can use the same CV input.
- **Set a bipolar modulation Amount.**
  The range is -100 to 100.
- **Select a VST destination parameter from a drop-down list.**
  This can also be done with Learn function (see below).
- **Set a Base Value.**
  The Base Value is the value the parameter has the time you select it on the VST panel. This is similar to the "Static Value" used when automating parameters on native Reason devices and Rack Extension devices. The exact Base Value is shown in the corresponding value slider.
- **Clear the CV assignment.**

CV controlling VST parameters using the Learn function

1. **Press [Tab] to flip the rack around.**
2. **Connect a CV cable from the device you want to use as control source, to the CV IN 1 input of the Plugin Rack Device.**



3. **Press [Tab] to flip the rack back to the front again.**
4. **Click the topmost Learn button.**




The Learn button lights up and the Plugin Window is opened and brought to front. In the Plugin Window, the text display tells you to move a parameter.

5. **Click a parameter in the VST Plugin Window.**




In this example we click the Fine Tune slider of Oscillator 1 to assign it.

The Fine Tune Osc1 parameter is now assigned in the Parameter column for CV slot 1:




6. **If desired, change the CV (bipolar) modulation amount by clicking the Amount bar and dragging up/down:**



7. **Repeat the procedure for the other CV slots you want to assign.**

- **You can also change the VST parameter's "start" value by clicking the Base Value bar and dragging up/down.**
- **If you want to reassign a VST parameter, just click the Parameter drop-down and select the desired VST parameter from the list:**




Remote controlling VST parameters

It's possible to assign Remote Overrides to VST parameters, to be able to control VST parameters from your connected MIDI Control Keyboard/Surface.

Adding a Remote Override to a parameter

1. **Click the Remote button at the top of the Plugin Window.**




The button is highlighted and a text display tells you to click a parameter.


2. **Click a parameter on the VST panel in the Plugin Window.**



- **In some VSTs you could right click a parameter on the VST panel and select Remote from the context menu.**
  The Remote Override Edit dialog appears for this parameter:



3. **Use the "Learn from control surface input" function and turn a knob on your MIDI Control Keyboard/Surface to assign a physical knob/slider to the VST parameter.**



Knob 8 on the MIDI keyboard assigned to control the DistAmt1 parameter on the MicroTonic VST.


4. **Click OK to close the dialog.**

Removing a Remote Override from a parameter

1. **Click the Remote button at the top of the Plugin Window.**
   The button is highlighted and a text display tells you to click a parameter.
2. **Click the parameter you want to remove from the Remote Override.**
   A context menu appears where you can select "Edit Remote Override Mapping..." (to reassign an override), or "Clear Remote Override Mapping" to remove the override.

Selecting VST presets/programs


VST3 plugins can support "vstpreset" files. Vstpreset files can be browsed by clicking the Browse Patch button on the Plugin Rack Device:



You then select and load the desired vstpreset from the Reason browser, like you would any other patch files.


Programs for VST2 plugins can be selected from the Plugin Rack Device (if the VST2 supports programs). For example, if you load a bank (fxb) using Reason's Browser, the fxb bank may contain a number of different programs, which are then loaded into the VST.

1. **Click the patch name display on the Plugin Rack Device to show the list of programs loaded in the VST plugin.**



2. **Select the desired VST2 program/patch from the list.**

▶ **Alternatively, click the VST Prog up/down selectors to step between and load the VST programs:**



These methods also work if the VST2 has presets that are automatically loaded when you create the device.

! **Note that the VST Prog selector buttons only appear if the plugin has a bank of programs or presets loaded.**

About saving songs that contain VSTs


When you save a Reason song document, all VST preset/patch/program data is automatically embedded in the song document. This means that you can load VST presets/patches/programs, edit them and then save the Reason song without needing to save the edited VST presets/patches/programs separately. This works exactly the same way as for patches in native Reason devices and Rack Extension devices.

Combining VST plugins in Combinator devices

A Plugin Rack Device can be Combined just like any other device types. In the Combi Programmer, all VST parameters are listed. See "The Combinator" for more information.

About missing VST plugins

When you open a Reason song from another user, it might have been created using VST plugins that you don't have. When you open such a song, any missing VSTs are replaced by empty Plugin Rack Devices in the rack:




An empty Plugin Rack Device representing a VST which is currently unavailable on your computer.

- **The empty VST device itself will be silent.**
  If it's an effect, it will bypass the audio (or be silent, if connected as a send effect).
- **If you're collaborating with a friend you can safely save the song and send it back.**
  When your friend opens the song, the missing VST will be restored with all settings intact.

Managing VST plugins

To get an overview of the VST plugins currently installed on your computer - and to be able to disable any malfunctioning VSTs - there is the Manage Plugins window.

▶ **Select "Manage Plugins" from the Options menu.**



The Manage Plugins window.

Here, all VST plugins installed in your VST folder(s) on your computer are listed (see "Defining custom VST folders").

The Manage Plugins window is divided into the following columns:

- **Manufacturer**
  Shows the name of the plugin manufacturer.
- **Plugin Name**
  Shows the name of the plugin.
- **Auto-scale (Windows only)**
  Here you can choose whether Reason or Windows should scale the VST panel. See "Auto-scale (Windows only)" below for more details.
- **Plugin Type**
  Shows whether the plugin is a VST2 or VST3.
- **Device Type**
  Shows whether the plugin is defined as an "Instrument", "Effect" or "Utility" in Reason.
- **Status**
  Shows the current status of the plugin (see "Plugin Status" below).

In the Plugin Management windows you can also:

▶ **Click and drag the column headings to sort the list.**


▶ **Click a plugin to select it.**
Additional info (path to the dll and comments about its status) is then shown in the Details area.

▶ **Click the Disable/Enable button to disable or enable the selected plugin (see "Plugin Status" below).**

Auto-scale (Windows only)


Some VST panels might show up quite small in Reason standalone on Windows computers. This is most likely because they are scaled by Reason's hi-res graphics instead of Windows. In Reason 12.2.4 and later there is a function for scaling up these VST panels.

In this example we have created a VST in the Rack and clicked to open the VST Plugin window:




As you can see the VST panel is small and a little hard to edit.

1. **Select "Manage Plugins" on the Options menu in Reason.**
2. **Select the VST in the list and tick the "Auto-scale (follow Windows display scaling)" check box:**



3. **Close the Manage Plugins window and re-load the VST (e.g. by dragging and dropping the VST from the browser and replacing the current instance in the Rack):**



4. **Click the VST Rack device to open the VST Plugin window:**



Now the VST panel is larger and a lot easier to view and edit.

Plugin Status

A plugin can have four different Status values, with additional texts in the Details area.

Plugin Status: Enabled

- **If the plugin was enabled in a previous session, the plugin is enabled and ready for use.**
- **If the plugin has been enabled during this session, it will be loaded when you restart Reason.**

Plugin Status: Disabled

- **If the plugin was manually disabled in a previous session, it's now disabled.**
- **If the plugin has been manually disabled during this session, it will be disabled when you restart Reason.**

Plugin Status: Could not load


- **If the plugin has the "Could not load" status, the plugin returned an error code and couldn't be loaded.**
  If you enable it, Reason will attempt to load it the next time you restart.

Plugin Status: Crashed

- **If the plugin has the "Crashed" status, it was automatically disabled because it crashed or caused Reason to hang.**
  If you enable it, Reason will attempt to load it the next time you restart.

Defining custom VST folders

It's possible to specify custom VST folders. This can be done on the Folders tab in Settings:



- **Tick the check boxes for the folders you want Reason to scan for VST plugins at launch.**
  You will have to restart Reason for the changes to take effect.
- **Click the Add button to add a custom VST Plugin folder.**
  Note that you will have to create the folder in the computer's file system before you can add it - you cannot create a new folder using the Add function.

  You will then have to restart Reason for the changes to take effect.
- **Click the Remove button to remove a custom VST Plugin folder.**
  Note that you don't delete the folder from the file system of your computer - you only make it unavailable in the list.

  You then have to restart Reason for the changes to take effect.

Chapter 16
Sounds, Patches and the Browser



About this chapter

This chapter deals with the following topics:

- **Handling Patches.**
  See "About patches".
- **Using the Patch Browser.**
  See "Using the Browser".
- **ReFills and Reason file formats.**
  See "About ReFills" and "Reason file formats".

About patches

A patch contains settings for a specific device. Patches can be either separate files on your hard disk or files embedded in a ReFill (see "Using the Browser" for info about ReFills). The devices that use patches are described below. The Mix Channel, Master Section and Audio Track devices can use Insert FX patches saved as Combinator devices. All other Reason devices use either Presets or can only be programmed using the device panel parameters.

Patches and references to samples/REX files

- **Dr. Octo Rex patches contain information about what REX files are loaded in each slot, their settings as well as the parameter settings on the device panel.**
  It is important to note that the Dr. Octo Rex patch doesn't contain the actual REX files - only information about which REX files are used.
- **Mimic, NN19, NN-XT and Grain patches contain information regarding which samples are used, their settings (key mapping, tuning, etc.) and the parameter settings on the device panel. Europa patches and RV7000 MkII patches can also contain references to samples, if the patches use samples.**
  Note that the patch doesn't contain the actual samples - only information about which samples are used.
- **Redrum Drum Computer and Kong Kit Patches patches contain a complete "drum kit", that is, information about which drum samples are used, together with the parameter settings for each drum sound.**
  Again, the actual samples are not included in the patch, only references to files. Also note that Redrum patches are separated from Redrum *patterns* - loading a new patch will not affect the patterns in the device.
- **The Combinator (Combi) patch format saves all settings and file references for each device in the Combi, along with the Combinator's own settings; key/velocity zones, modulation routing etc.**
  Any audio or CV routing from/to devices that are part of the Combi is also saved.

! **Note that patches for devices included in a Combi are not saved individually - e.g. if a Combi includes a Subtractor, and you have tweaked its settings, these settings will be saved with the Combi patch, but will not be saved as a separate Subtractor patch unless you do so from within the Combi - see "Saving patches".**

! **Patches other than Combi patches do not include any cable routing information.**

About the "Load Default Sound in New Devices" setting

On the "Browsing" tab in Settings, there is an option (on by default) to load a default patch when creating a device. If the "Load Default Sound in New Devices" option is off, the device will be loaded with a basic "init sound" (the same sound as after you have right clicked the device and selected "Reset Device" from the context menu).

About the "Browsing starts in default sound folder (for new devices)" preference


On the "Browsing" tab in Settings, there is an option which lets you decide where the Browser should start showing patches when you have created a new device. If the "Browsing starts in default sound folder (for new devices)" option is ticked, the browsing starts in the device's home folder, showing the patches and folders included with the device. Otherwise it starts in "All Locations", showing all patches for that device (including any you have created).



Loading patches

To select and load a patch for a device, use one of the following methods:

- **Click the "Browse Patch" button in the Patch section on the device panel.**
  The Patch section has the same basic layout for all patch devices; a Patch Name display, two "Select Patch" buttons (up/down) for stepping through patches sequentially, a "Browse Patch" button to open the Browser, and a "Save Patch" button to save patches.



The Patch section of the Subtractor device.

! **On the panels of devices that can load samples/REX files, there are also Browse Sample/REX Loop buttons, used for loading samples or REX files. Make sure you click on the button in the Patch section (next to the patch name display) to load patches!**

When you click the Browse Patches button on a device, the device automatically gets "Browse Focus" and the Browser opens. A button at the top of the Browser indicates that only patches for the highlighted device in the rack are shown:



Browse focus for a device is indicated by orange side bars in the rack and on the sequencer track - and that the patch section on the device is colored in orange:



The orange Browse Focus indicators in the rack and in the sequencer.

- **Another way of loading patches is to select "Browse Patches..." from the Edit menu or device context menu of a selected device.**
  Alternatively, hold down [Ctrl](Win) or [Cmd](Mac) and click [B].

▶ **Once you have loaded a patch, you can step between all the patches in the same folder by using the "Select Patch" buttons on the device panel:**



▶ **If you click on the Patch Name display on the device panel, a pop-up menu - the browse list - will appear, listing all patches in the currently selected folder.**
This allows you to quickly load another patch, without having to step through the patches one by one. You can also choose to set browse focus to the device by selecting "Browse..." from the patch display pop-up menu.

When you load a patch in any of the ways described above, the device's parameters will be set according to the values stored in the patch, and the name of the patch is shown in the Patch Name display.

! **Any parameter adjustments you make on the device panel after loading a patch will not affect the actual patch file on the computer. For this to happen, you need to save the patch - see "Saving patches".**

! **For all the patch loading methods described above, you can automatically revert back to the original patch, by clicking the Cancel button in the Browser.**

▶ **You can also load patches from a MIDI Master Keyboard or Control Surface - see "Remote - Playing and Controlling Devices".**

For more details about browsing patches and searching for sounds, please refer to "Browsing patches for a device" and "Filtering in the Browser".

If referenced samples are missing

As described above, patches for the Mimic, Grain, Europa (User Wave sample), Redrum, NN19, NN-XT and Dr. Octo Rex devices contain references to samples or REX files. Just like patches, samples can be independent files on the hard disk or elements within a ReFill. However, if sample files have been moved or renamed after a patch was saved, the sample file references in the patch will not be accurate.

If this is the case when you select a patch, the program will tell you so. You can then choose to either manually locate the missing files, to have the program search for them, or to proceed without the missing sounds. For details, see "Handling Missing Sounds".

! **Proceeding without locating or replacing the missing samples will result in silent patches, drum channels, key zones or loop slots (for the Redrum, NN19/NN-XT, Kong, Grain and Dr. Octo Rex).**

Saving patches

Saving device settings in a song

When you save a Reason song, all settings for all devices are automatically included in the song file - there is no need to save the patches separately.

! **It's important to realize that it's the actual device parameter settings that are saved in the Song - not references to patches on disk. The next time you open the song, all devices will be set as they were when you saved them (regardless of whether you have removed or edited any patches on disk).**

! **Note that device samples are not stored with the Song by default. This means that if you edit any Redrum, Kong, Mimic, Grain, Europa (with a User Wave sample) or NN19/NN-XT samples in an external application and then open a Song containing devices that use these samples, the sound will be different. It's possible, however, to store actual device samples together with the Song using the "Self-Contain" feature. See "About Self-Contained Songs".**

Saving device settings as patches on disk

Even though the device settings are stored with the song, you may want to save any settings you have made for a device as a separate patch file. This allows you to use the patch in other songs, and lets you try out other patches in your song without the risk of losing your original sound. A patch is saved as follows:

1. **Click the "Save Patch" button on the device panel:**



2. **In the Save File dialog that appears, specify a location and name for the patch file and click Save.**
   The first time you save during a Reason session, the Save File dialog defaults to the "User Library" folder in the "Reason Studios" folder in the local Music folder on your computer, but you can of course choose another destination folder if you like.

- **Under both Windows and macOS, the different types of patch files have different file extensions.**
  File extensions are automatically added by Reason when you save. This is useful, especially if you saved the files on a Mac and want to be able to open them on a Windows computer.
- **If you have selected a patch, modified it and want to save it with the modifications, you could either save a separate, modified version of the patch (with a new name) or simply overwrite the old patch file on disk.**
  As usual, you will be asked if you want to replace (overwrite) the existing patch file.

! **Note that you can save a patch under the same name and location without having the save dialog appear by holding down [Alt](Win) or [Option](Mac) and clicking the "Save Patch" button on the device panel. Be aware that this overwrites the original patch!**

! **Note that you cannot save into a ReFill! This means that if you have opened a patch from within a ReFill (like the Factory Sound Bank), modified the patch and want to save it, you need to save it as a separate file in a new location (outside the ReFill). Preferably, you should also rename the modified patch file, to avoid confusion.**

Copying and pasting patches between devices

A quick way to copy device parameter settings between devices of the same type is to use the "Copy Patch" and "Paste Patch" functions. The result is exactly the same as if you had saved a patch from one device and opened it on another device of the same type - this is just a quicker method.

! **Copying and Pasting settings is possible with all device types that can use patches.**

Proceed as follows:

1. **Select a patch, and/or make the desired settings on the source device.**
   Make sure the device remains selected.
2. **Select "Copy Patch" from the Edit menu or from the device context menu.**
3. **Select the destination device of the same type (in the same song or another song).**
4. **Select "Paste Patch" from the Edit menu or from the device context menu.**
   The settings of the source device (including Mimic, Europa, Grain, Redrum, NN19, NN-XT, and Kong sample references and Dr. Octo Rex REX loop references) are automatically applied to the destination device.


! **Note that this operation simply copies the settings from one device to another. Adjusting the settings on one of the devices will not affect the other; neither will the edits affect any patch file on disk.**

Initializing patches and resetting device parameters

Sometimes it is useful to start with a "clean slate" when creating a synth sound, a drum kit or a sampler patch. This is achieved by selecting "Reset Device" from the Edit menu or from the device context menu. This resets all parameters to "default" values. Initializing Mimic, NN19, NN-XT, Dr. Octo Rex, Kong, Grain, Europa (if it uses a User Wave sample) or Redrum devices will also remove all sample/REX file references, allowing you to start from scratch.

Using the Browser

Browser overview




Example of the Browser when using the Browse Patch button/function on a Subtractor device.

The Browser is used when you load patches, samples, audio files, MIDI files and REX files, from regular file folders or from ReFills.

Besides being shown as a separate window, the Browser can also be placed as a side panel to the left in the song window.

- **Click the "Show Browser in Side Panel" symbol to the right on the Browser header to show the Browser in the side panel.**



The Browser is now placed in a side panel to the left in the song window:




The Browser functionality is identical to the separate Browser window - it's only the placement that differs. You can re-size the Browser side panel horizontally by dragging the right edge sideways.

- **Click the "Show Browser in Separate Window" symbol to the right on the Browser side panel header to show the Browser as a separate window again.**



- **If you always want the Browser to open in the side panel in your new songs you can select this on the Browser tab in Reason's Settings:**



This setting also determines how the Browser is shown when you open songs made in older Reason versions.

▶ **Open and close the Browser by pressing [F9], or by holding [Cmd](Mac) or [Ctrl](Win) and pressing [F] - or by selecting Show/Hide Browser from the Windows menu.**
The Browser will open without Browse Focus.

▪ **You can also open the Browser by clicking the Browser button at the top of the Reason document window.**
The Browser will open without Browse Focus.



! **If the Browser is located in the side panel - and you have the Device Palette open - opening the Browser will automatically close the Device Palette (to make room for the Browser).**

▪ **You can close the Browser by clicking the Browser button again.**
This is the same as clicking the Close/Cancel button in the Browser.

▶ **With a patch based device selected in the rack, hold down [Cmd](Mac) or [Ctrl](Win) and press [B].**
This opens the Browser allowing you to browse for and load patches for the selected device.

▶ **With a sample based device selected, select "Browse Samples" on the Edit menu (or click the "Browse Samples" button on the device panel).**
This opens the Browser, where you can browse for, preview and load samples in the supported audio formats.

▶ **With a Dr. Octo Rex Loop Player selected, select "Browse ReCycle/REX Files" on the Edit menu (or click the "Browse Loops" button on the device panel).**
This opens the Browser, allowing you to browse for, preview and load REX loops into the Dr. Octo Rex device.

▶ **With a Kong Drum Designer device selected, select "Browse Drum Patches" on the Edit menu (or click the "Browse Drum Patch" button on the Drum Control Panel on the device).**
This opens the Browser, allowing you to browse for Kong Drum Patches and supported audio files to load into a slot in the Kong Drum Designer device.

▶ **Select "Import Audio File" from the File menu.**
This opens the Browser, allowing you to browse for, preview and load files in the supported audio formats to an audio track in the sequencer. See "Importing audio to the sequencer".

▶ **Select "Import MIDI File" from the File menu.**
This opens the Browser, allowing you to browse for MIDI files to import to instrument tracks in the sequencer. See "Importing Standard MIDI Files".

! **When opening and browsing for Reason song files, the regular OS "Open" window is normally used instead.**

Besides standard file and folder browsing, the Browser offers several useful functions:

▪ **Search for files by name, type, category, and tags - see "Filtering in the Browser".**

▪ **Use "cross-browsing" to search for patches belonging to any type of device.**
For example, set browse focus from a Subtractor device by clicking its Browse Patch button. Instead of limiting the Browser to show only Subtractor patches, you can choose to browse for any type of instrument patch. If you select a patch with a different format than the device you are browsing from, the original device will be replaced by the new device. See "Browsing patches for a device".


▪ **Audition audio samples and REX loops on the fly. See "Previewing samples and REX loops".**

▪ **Save shortcuts to various locations on your local drive(s).**
See "Shortcuts".

▪ **Create Favorite Lists containing shortcuts to your favorite files for instant access.**
See "Favorite Lists".

A note about Browser indexing

To keep track of all your files at all times, the Browser needs to continuously index your files. The first time you open the Browser after having installed Reason, the indexing could take a while, especially if you have a lot of files (samples etc.) on your computer. The following symbols are used to show how the indexing is progressing:



When the indexing is completed, the symbols will disappear.

Important notes about where to store your files so that Reason can find them

To avoid that the Browser should "choke" from scanning a huge amount of irrelevant files, some folders are blacklisted by Reason, i.e. the Reason Browser won't look in those folders.

Blacklisted folders on Mac

The following folders are disregarded by Reason on Mac, so make sure you don't store any Reason related content/files in these:

Macintosh HD/System

Macintosh HD/Applications

Macintosh HD/Library

! **Note! Even though "Macintosh HD/Library" is blacklisted, "Macintosh HD/Library/Audio" is explicitly white-listed, so you can create shortcuts from there.**

~/Music/Propellerhead Content/ (in your personal Music folder, where the old Optional Rack Extensions and ReFills in Reason 12 were located)

Blacklisted folders on Windows

The following folders are disregarded by Reason on Windows, so make sure you don't store any Reason related content/files in these:


C:\Windows

C:\Users\<youruser>\Music\Propellerhead Content (in your personal Music folder, where the old Optional Rack Extensions and ReFills in Reason 12 were located)

Creating a device by browsing patches

If you want a certain sound or effect, the best way is often to add it directly by browsing (instead of first choosing a device and then finding a patch for it).

▶ **To add an instrument device, right-click anywhere in the rack or sequencer track list and select "Add Instrument" (or hold [Cmd](Mac) or [Ctrl](Win) and press [I]).**
This opens the browser in Add Instrument mode, showing only instrument patches:



You can use the category and tag buttons to filter which patches are shown (or type directly into the filter text field to filter by name, category, kind or tag). See "Filtering in the Browser".

1. **Click a patch in the list to create a new device in the background.**
   You can audition it by playing your MIDI keyboard.
2. **Select another patch with the mouse or the computer up/down arrow keys to load it instead.**
3. **Audition sounds this way until you find one you like.**
4. **Press [Return] or click OK to close the Browser, keeping the last loaded patch.**
   Double clicking a patch in the Item List is the same as selecting it and clicking OK, in one move.

▶ **Alternatively, you can press [Esc] or click Cancel to close the browser and remove the created instrument.**

Creating an Effect device by browsing patches

▶ **To add an effect device, select the instrument device in the rack and click the + sign at the bottom of the blue frame.**
Select "Add Effect..." to open the browser in Add Effect mode.
See "Creating devices" for more information.

- **Alternatively, right-click anywhere in the rack or in the sequencer track list and select "Add Effect" (or hold [Cmd](Mac) or [Ctrl](Win) and press [E]).**
  The insertion point of the new effect device is determined by where you right-click; often you want to right-click an existing instrument or effect to add a new effect directly after that device.

  This opens the browser in Add Effect mode, showing only effect patches.

1. **Select a patch to create its device in the background, then load other patches by clicking or using the computer up/down arrow keys until you find the one you want.**
   You can audition the effect by playing the instrument it's connected to.
2. **When you're done, close the browser by pressing [Return] or clicking OK.**
   Alternatively, press [Esc] or click Cancel to close the browser and remove the created effect.

Creating a Player device by browsing patches

- **To add a Player to an instrument, select the instrument device and click the + sign at the top of the blue frame.**
  Select "Add Player..." to open the browser in Add Player mode.
  See "Creating devices" for more information.
- **Alternatively, right-click the instrument in the rack and select "Add Player".**
  This opens the browser in Add Player mode, which works the same way as the other Add modes (see above).


Browsing patches for a device

- **To open the Browser for a specific device, click the "Browse patch" button on the device panel.**
  Alternatively, right-click the device panel and select "Browse Patches" - or select the device and hold [Cmd](Mac) or [Ctrl](Win) and press [B]).



The Patch section of the Subtractor device.

This opens the browser in Patch Browse mode. The orange header shows which device you're browsing for.



What is shown in the Browser depends on the device you started from:

- **If the device had a patch loaded from the Browser (for example with the Add Instrument function), the browser will show the same settings as when the patch was loaded.**
  This includes Location, Categories, Tags and other filtering settings.
- **If the device had no patch loaded (or the default patch), the Browser will show all patches of that kind (e.g. SubTractor Patches).**
  You can use the Patch Type buttons at the top to switch between showing patches for this device type only or for all Instrument Patches - what we call cross-browsing.

! **If you have selected the "Browsing starts in default sound folder (for new devices)" option on the "Browsing" tab in Settings, the Browser will show patches in the device's home folder instead of in All Locations.**

- **In Patch Browse mode you can click patches (or use the computer up/down arrow keys) to load them in the background.**
  When you're happy with what you hear, click OK or press [Return} to close the Browser. Double clicking a patch is the same as selecting it and clicking OK, in one move.

▶ **If you want to browse patches for another device in the rack, click the Browse Patch button on that device. The Browser will then automatically switch to show patches for that device instead. This way you don't have to close the Browser and open it up again.**

▶ **To go back to the original patch instead, click Cancel or press [Esc].**

▶ **Tip: When you are browsing patches for a device, its "Home Folder" will be shown in the Locations list to the left. This is a quick way to get to the patches that come with the device, shown in their original folder structure.**

Browsing samples for a device

▶ **To load a sample, for example in a sample slot on a drum machine device, click its Browse Sample button.**




Browse Sample button on Redrum

This opens the browser in Sample Browse mode. In this mode, the browser will only show samples.

It's often most useful to select a sample category (e.g. Drum Samples) here, since you might not want to go through all instrument multisamples and similar:

▶ **Click the Drum Samples button in the Category section to refine the list in the Item List to drum samples:**



▶ **Click samples in the Item List (or use the computer up/down arrow keys) to load the samples in the background.** When you're happy with what you hear, click OK or press [Return] to close the Browser. Double clicking a sample is the same as selecting it and clicking OK, in one move.

▶ **To go back to the original sample instead, click Cancel or press [Esc].**

Previewing samples and REX loops

▪ **The Audition controls below the Item List lets you preview the selected sample.**
If Auto is on, selecting a sample will automatically play it back:



▶ **Adjust the preview volume with the slider.**

Selecting multiple files

It is possible to select multiple files in the Browser, by using standard [Shift] or [Ctrl](Win) or [Cmd](Mac) selection techniques. This, however, doesn't necessarily mean that the selected files can be loaded. There are a number of instances where selecting several files in the Browser file list is relevant:

- **It is possible to load several drum patches (on consecutive pads) simultaneously into the Kong device.**
  See the "Kong Drum Designer" chapter for details.
- **It is possible to load several samples simultaneously into the NN-XT, NN19 and Kong NN-Nano sampler devices.**
  See "NN-19 Sampler", "NN-XT Sampler" and "NN-Nano Sampler" for details.
- **It is possible to load several REX files simultaneously into the Dr. Octo Rex device.**
  See the "Dr. Octo Rex Loop Player" chapter for details.
- **It is possible to simultaneously import multiple audio files to the sequencer.**
  See "Importing audio to the sequencer" for more info.
- **You can select several files to add them to a Favorites List in one go - see "Favorite Lists". Note that this is only possible if a device does not have Browse Focus, see "Using the browser without Browse Focus".**

! **In situations where several selected files (e.g. patches or songs) cannot be loaded, the Create/Load button in the Browser is grayed out.**

About patch formats and sampler devices

As both the NN-XT and NN19 sampler devices can load patches in the NN19 (.smp) and REX (.rx2/.rcy/.rex) formats, there must be certain rules regarding cross-browsing.

- **The basic rule is that the Browser will load such patches into the original device type (the device you opened the Browser from), whenever possible.**
  Thus, when the patch format is NN19 (.smp) or REX (.rx2/.rcy/.rex) and the NN19 device has browse focus, the patch will be loaded into this device.
- **If you are browsing from any other type of device, these patch types will be loaded into an NN-XT device.**
- **If you are using the "Create Instrument" function, an NN19 (.smp) patch will create a NN19 device and a REX patch will create a Dr. Octo Rex device.**

About browse lists


When you click the Open/Load/Create/Import button to open a file from the Browser, the file and folder list shown at that time is memorized for that device. This is called a "browse list".

For patches (and to a certain extent samples) this list provides a specific functionality:

- **The browse list is what applies when changing patches using the Next/Previous Patch buttons on the front panel of a device (or from patch selectors on a control surface).**
- **The browse list is shown as the patch list when you click in the patch name field for a device.**
- **For samples, the browse list applies when changing samples using the Next/Previous Sample buttons on the front panel of a sampler device.**



Other Browse Focus modes




Browse Focus means the Browser has a specific target (indicated by the orange heading background). The most common examples are already described above, but there are some others:

- **Browsing loops for a Dr Octo Rex or for a Nurse Rex module in Kong will open the Browser in Browse REX Loops mode, showing only REX loops (.rx2 files).**
- **Browsing for a pad on Kong will open the Browser in a special Browse Drums mode, showing both samples and Kong drum patches (.drum files).**
- **Selecting Import Audio File (not available in Reason Rack Plugin) will open the Browser showing only samples and REX loops.**
  Selecting a file and clicking Import will close the browser and import the file to an audio track in the sequencer, at the current song position.
- **Selecting Import MIDI File (not available in Reason Rack Plugin) will open the Browser showing standard MIDI files.**
  Selecting a file and clicking Import will close the Browser and import the file to new instrument tracks in the sequencer.

Using the browser without Browse Focus

▶ **Click the Browser button at the top of the Song window (or press [F9], or hold [Cmd](Mac) or [Ctrl](Win) and press [F]) to open the Browser without a specific Browse Focus (as shown by the gray heading):**



Here you can see any type of item (as set with the Type buttons at the top). In this mode, patches and samples are not automatically loaded in the background when you select them. Instead you have to explicitly load them.

Here are some examples:


- **Select a patch and click the Create button (or double click the patch, or press [Return]) to create a new device.**
- **Select a sample and click the Import button (or double click the sample, or press [Return]) to import it to the selected audio track in the sequencer.**
  Note that this is not available in Reason Rack Plugin.
- **Select a Reason song and click the Open button (or double click the song, or press [Return]) to open it.**
  This is useful if you need to open songs inside Rack Extensions or ReFills (since the regular Open Song dialog cannot open these).

- **Alternatively, you can use drag and drop to drag an item from the Item List to the rack or sequencer.**
  When you drag an item out of the Browser (when it is in a separate window), it will automatically fold up to let you see background. This lets you drop to devices or sample slots that were obscured by the Browser. When you drop the item, the browser reappears.

  If you change your mind before dropping, you can drag the item back to the browser heading to unfold it again.

- **You can use drag and drop from the Browse Focus modes too. For example, if you are browsing piano patches for a device and stumble upon a nice bass sound, you can just drag the bass patch into the rack to create a new device. The Browser will remain in Patch Browse mode for your original piano instrument.**

The Locations list



The Locations list to the left in the Browser provides different ways to get to files and folders.

All Locations


- **All Locations shows all files that Reason knows about, in a flat list.**
  This means all patches, samples and loops in all folders listed in the left column (except the folders under the "Computer" heading). All Locations is often the best starting point for browsing, since you can find all content there, regardless of where the files actually are.

User Library

- **User Library is a subfolder in the Music/Reason Studios folder on your computer.**
  When you save a patch in Reason, this is the default save folder. You can also move existing patches and sounds there, to make sure they are indexed and included in "All Locations".

Reason Library

- **Reason Library shows the built-in sound banks, a subfolder listing all installed Rack Extensions and a ReFills folder:**



ReFills is a subfolder in the Music/Reason Studios folder on your computer. Reason Companion will install the optional Drum Supply and Loop Supply ReFills in this folder, and you are also encouraged to move any ReFills you have downloaded or purchased there. This will ensure that they are indexed and included in "All Locations".

Sound Packs

- **If you are a Reason+ subscriber, you will continuously get new content in the form of Sound Packs.**
  You will find these in the Sound Packs location.

Song Samples

- **The Song Samples folder lists samples used in the current song, including self-contained samples.**

! **Not available in Reason Rack Plugin.**

Shortcuts

- **Shortcuts are aliases to folders and items that you need quick access to.**

▶ **To add an item as a Shortcut, drag it from the Item List and drop it under the Shortcuts heading.**


▶ **To delete a Shortcut, right click the folder icon and select "Delete Location" from the context menu.**

Favorite Lists

- **Favorite Lists are custom collections of patches, samples or loops.**
  There are two ways to add items to Favorite Lists:

▶ **Drag files from the Item List and drop them on a Favorite List to the left.**

▶ **Right-click a file in the Item List and select a Favorite List from the context menu:**



Adding a patch to the user created "Bells" Favorite List.

! **The check mark next to a Favorite List means the item is already part of that Favorite List. Selecting it will remove it from the list.**

▶ **To rename or delete a Favorite List, right click the folder icon and select "Rename Favorite List" or "Delete Favorite List" from the context menu.**


! **We strongly recommend not to put ReFills in Favorite Lists. Instead, use the User Library or Shortcuts Location for ReFills, see "User Library" and "Shortcuts".**

Computer

- **The Computer heading holds links to the User and Desktop folders on your computer.**
  These are not included in "All Locations". Use these for navigating to folders that you want to add as Shortcuts!

Filtering in the Browser

The key to finding what you want in the Browser is using the filtering section above the item list. This is especially powerful when "All Locations" is selected to the left:



The filtering section.

- **You can set up the Browser to show only the Filter text field or the Categories and/or Tags buttons too, using the fold buttons on each section:**



The Filter text field, Categories and Tags sections unfolded.

! **Note that Categories section is not shown if you have selected the "All Types" Type button at the top. However, you can type in the Filter text field and get suggestions of Categories that you could select - it's just that they won't show up as buttons in the Browser.**

The Type buttons




The Type buttons at the top of the Browser.

The Type buttons at the top specify which general type of files are listed. These can be set or limited automatically if the browser is in a Browse Focus mode. For example, if you're browsing patches for an instrument device, you will only be able to switch between Instrument Patches and patches for the current device type (e.g. Europa patches).


! **Note: The MIDI Files type is not available in Reason Rack Plugin.**

The Text (search) field

The Filter text field can be the quickest way to filter the result:




- **Typing something in the Filter text field shows a menu with filter property suggestions.**
  You can use the arrow keys to go down to a suggestion and press Return to select it. This adds that filter property, shown to the right in the filter Filter text field:



The category "Keys: Organ" selected.

- **If you just press Return in the text field (without going down the menu), the browser will show items that match any of the filter properties on the menu.**
  This is indicated by the filter property "Any":



You can continue writing and adding other properties.

▶ **To remove a filter property, click its X button (or use the left/right arrow keys to select it and press [Backspace]).**

The properties available on the menu are as follows:

- **Name**
  The name of the item.
- **Category**
  For example, whether an instrument is a piano or a synth pad, or whether a sample is a Snare Drum or a Sound FX - different Types have different categories.

- **Tag**
  A more subjective description of a sound. All patches and sounds in the Reason Factory Sound library have been manually tagged, to make them easier to search for and filter out.
- **Author**
  This lets you view all items by a certain sound designer.
- **In Sound Pack**
  This lets you view all patches and samples in a certain Sound Pack.
- **In Rack Extension**
  This lets you view all patches built into a certain Rack Extension.
- **In ReFill**
  This lets you view all items within a certain ReFill.
- **In Folder**
  This lets you view all items in a certain folder. If there are multiple folders of the same name, selecting this will show the contents of all these folders.
- **Kind**
  For patches, this is the device type (e.g. “Europa Patch”, “Polytone Patch” etc.).
  For samples, Kind represents the file format: WAV, AIFF, mp3 etc.

! **Adding multiple Names, Categories or Kinds will widen the result.**


For example, if you filter on “Category: Keys” and “Category: Strings”, you will see both Keys and Strings patches.

! **Adding multiple Tags will narrow down the result.**

For example, if you filter on “Tag: Fat” and “Tag: Analog“ you will only see sounds that are tagged both as "Fat" and "Analog".

The Categories buttons

- **The Category buttons will be different depending on which Type button you have clicked.**
  If "All Types" is selected, no Category buttons are shown (but you can still filter on categories using the Filter text field).
- **In most cases, turning on a Category button will show its sub-categories:**



Sub-categories for the “Bass” Category.



Sub-categories for the “Mallets” Category.

- **You can choose whether to filter on the main category only ("Bass", "Mallets", etc) or to specify one or more subcategories.**
  Multiple categories can be activated at the same time.

! **Note: The "Uncategorized" Category shows all items that have no category (yet). That will initially include all your own existing patches and samples as well as patches in 3rd party Rack Extensions and VSTs.**


The Tags buttons

- **The Tags buttons are the same for all Types.**
  They describe the character of a patch or sample and in some cases technical aspects ("Sampled", "Portamento", etc). The "Staff Pick" tag lists sounds that we at Reason Studios think are extra nice!
- **Multiple tags can be activated to narrow down the filtering result.**
- **It's also possible to edit and add your own custom tags, see "Adding User Tags".**

! **Note: Clicking the "Untagged" button will show all items that have no tag(s) (yet). That will initially include all your own existing patches and samples as well as patches in 3rd party Rack Extensions and VSTs.**

Categories and Tags in the Filter text field

- **Any activated Category or Tag buttons will be shown in the Filter text field.**
  You can clear them by clicking their individual X buttons (or clear all by clicking X for the whole text field):



Editing Categories, Tags and Author


You can change or remove the categorization and tagging of items, and also add categories and tags to your own sounds:

Editing Categories and Tags

It's possible to edit (assign and deassign) Categories and Tags for single or multiple files in the Item List.

Here is an example of a single sample assigned to "Sound FX" in the "Misc Samples" Category:


▶ **Right click a file in the Item List and select "Categories >" and the desired sub menu, then click the Category name to assign (or to deassign if already selected):**



- **Assigning/deassigning Tags works the same way, except you select the "Tags >" sub menu instead.**

Here is an example of a selection of samples assigned to different and some common Categories:

▶ **Right click one of the selected files in the Item List and select "Categories >":**




- **If you have selected multiple files, any Category and/or Tag you select will be applied to all selected files.**
- **If any of the selected files are already assigned to one or several Categories and/or Tags, this is indicated by a "-" sign to the left of the Category/Tag name.**
  Selecting such a Category or Tag will assign all selected files to that Category/Tag and the sign will switch to a check mark instead.

▶ **To de-assign a file (or multiple files) from a Category/Tag, right click the file(s), select "Categories >" or "Tags >" and click the check mark for the Category or Tag you want to de-assign.**


Editing Categories, Tags and Author in Edit Info mode

If you want to edit Categories, Tags and Author for one or several selected items in one go, you can do that in Edit Info Mode:

1. **Set up the view to show the items you want to categorize and/or tag.**
   For example, if you want to categorize and tag all patches in a certain folder, navigate there. The items must be part of the indexed locations; if you have custom patches in a folder on your hard drive you need to add that folder as a Shortcut first, see "Shortcuts".
2. **Right click an item (or one of several selected items) in the Item List and select "Edit Info..."**



The Browser switches to Edit Info mode:



Currently set Categories and Tags for the "DS8 Mk IV.thor" patch.

- ▶ **Click in the Author field at the top if you wish to change the name of the Author.**

The Category and Tags buttons show the current categorization and tagging of the selected item.

- ▶ **Click the Categories and Tags buttons (to turn on/off) to add or remove categories and tags.**
- ▶ **Select other items in the view to see and change their respective Categories and Tags.**
- ▪ **You can press [Shift] or [Cmd](Mac)/[Ctrl](Win) and click to select multiple items, and tag them all in one go.**
  If they have conflicting settings, those buttons will be shown with white text.
- ▶ **To keep your changes and leave the edit mode, click Save at the bottom at the bottom right in the Browser.**
  This takes you back to the regular browser view.


Adding User Tags

It's also possible to create and add your own custom Tags - User Tags:


1. **Unfold the Filter text field and the User Tags sections:**



2. **Click the "+ Add..." button, type in a new Tag name and then hit [Enter]:**




3. **To add your custom Tag to sounds/patches, right click the sound/patch in the Item List, select "User Tags >" and then select one of your User Tags:**




Assigning a sample to the "EBM" User Tag.

- **You can also create a new User Tag and assign a sound to it in one go, by right clicking the sound and selecting "User Tags > + Assign New Tag...":**




▶ **To deassign or User Tags, right click the sound in the Item List, select "User Tags >" and click a check mark to deassign - or click the empty area to the left of the User Tag to assign:**




- **If you have selected multiple files in the Item List, these files may have both common and individual Tags assigned to them.**
  In such cases you can edit and reassign according to the description in "Editing Categories and Tags" above.

▶ **To delete or rename a User Tag, right click the User Tag button and select "Delete Tag" or "Rename Tag...":**



! **Note that regular Tags cannot be deleted - only User Tags.**

Other Browser functions




- **Above the Item List, you will find back/forward buttons and a path menu for navigating up in the folder tree.**
- **To the right is a selector for selecting view mode: Flat list or Tree (showing folders).**
  Different locations have different default view modes when you go there. In some cases you cannot change the view mode ("All Locations" is always a Flat list for example, while the folders under "Computer" will always be in Tree mode).

▶ **Right click a file in the Item List (Flat view) and select "Show in Folder" to show the file in its original folder (in Tree view).**

- **You can sort by columns by clicking the column headings.**
- **You can resize the columns by dragging the heading dividers sideways.**
- **The entire Browser window can be resized and moved within the boundaries of the Reason application.**


! **Note: Even though the Browser is shown, you can still edit settings in the rack or sequencer, click transport buttons and so on.**

Back/Forward buttons




These arrow buttons allow you to move back and forth between the Browser locations you have opened during the browsing session, similar to when browsing pages in a web browser.

Path popup menu




This field displays the name of the currently selected root folder.

- **Click in the name field to bring up a popup menu where you can move up in the folder hierarchy.**
  When you're in a top-level location such as All Locations or a Favorite list, the path popup menu cannot be used.
- **Click on the Up button to the right of the root folder list to move up in the hierarchy one level at a time:**



! **When you're in a top-level location such as All Locations or a Favorite list, the path popup menu cannot be used.**

The Info area




The Info area at the bottom to the left in the Browser shows information about the currently selected file in the Item List, including Name, File Type, File Location, Author, Categories (if categorized) and Tags (if tagged).

If the file is a sample or REX loop, there can also be information about Sample/Loop Length and Tempo (if embedded in the file). Length and/or Tempo will then also be displayed in the corresponding Item List columns.

Handling Missing Sounds

Sampler patches, drum machine patches, Dr. Octo Rex patches, and SoundFonts contain references to samples - files on your hard disk. The same is true for songs that contain samples (in sampler or drum machine devices) or REX files. If any of these files have been moved, renamed or removed when you try to open the patch or song, Reason will alert you that files are missing by showing the "Missing Sounds" window. The "Missing Sounds" window also appears if patches in the song are part of a ReFill which has been moved, removed or is not installed on your computer:



The "Missing Sounds" window.

The main display in the Missing Sounds window lists all missing files. The three columns show the following properties:

Column	Description
Device	Shows the name of the device in which the missing sound is used.
Sound	Shows the name of the missing sample or loop.
Part of ReFill/R.E.	If the missing file is part of a ReFill (or a SoundFont within a ReFill) or a Rack Extension device, this column shows the name of the ReFill/SoundFont/Rack Extension.

Below the main display are four buttons (besides the Help button):

Search All Locations

- ▶ **If you have the missing samples somewhere on your computer, put them in a Browser Location (so the Browser can find them), then click the "Search All Locations" button.**
  Reason will automatically search for and find the missing files in any of the Locations present in the Browser.

! **If you have a lot of ReFills and folders in your Browser Locations, the search could take a while.**

Browse to Folder

1. **If you know in which folder your missing sound(s) are, click the "Browse to Folder" button.**
   The Browser opens.
2. **Navigate to the folder in the Browser, select the folder, and click the OK button in the Browser.**


Replace

1. **If you want to replace a missing sound without searching for it, select the missing sound in the list and click the "Replace" button.**
   The Browser opens.
2. **Select the desired sound in the Browser and click OK.**
   If you like, you could replace missing sounds with new sounds - it doesn't have to be the original ones. When you save the Patch or Song later on, the new sounds will permanently replace the previous (missing) sounds.

Download ReFill/RE

- **Select a file in the list and click the "Download ReFill/RE" button to open the Reason Companion app and see if the ReFill can be found on your account.**
  If it can't be found, click the "Search for the ReFill in the Shop" button in the Companion app, to direct your web Browser to the Reason Studios Shop, where you can download (and purchase, if necessary) the ReFill/Rack Extension.
- **Alternatively, close the Missing Sounds window.**
  The song or patch will still work, but with sounds missing. This means that sampler patches, drum machine patches and/or loop players will not play back correctly.

  On the panels of the concerned devices, missing samples are indicated with an asterisk (*) before the file names:



A Redrum device with a missing sample in one of its slots.

- **If you want to continue searching for and replacing missing sounds later on, you can open the Missing Sounds window again by selecting "Show Missing Sounds Window" from the Windows menu.**

About ReFills

A ReFill is kind of a content package for Reason, which can contain sounds and effects patches, samples, REX files, SoundFonts and MIDI files. On your computer, ReFills appear as files with the extension ".rfl".

All sounds included in Reason are embedded in two ReFills named "Reason Factory Sound Bank" and "Orkester Sound Bank", which were copied to the hard disk during installation.

Additional Reason Studios ReFills are available for purchase. You can also purchase ReFills from other sample manufacturers, etc.

- **Samples (Wave and AIFF files) are compressed to about half their original file size when stored in ReFills, without loss of quality.**

In Reason, you can use the Browser to list and access the embedded sounds and other components within the ReFills, just as if the ReFills were folders on your hard disk.

Furthermore, if a song makes use of components from ReFills, Reason will tell you which ReFills are required.



Reason file formats

The following table lists the file formats that you can browse and open using Reason's Browser:

File type	Extension	Description
Combinator Patch	.cmb	The Combinator can store/recall combinations of Reason devices. Combinator patches (Combis) will save all panel settings (as well as sample references if used) for all devices that are part of the Combi. In addition, all routing (audio/CV) between devices in the Combi are included in the patch. Effect Combi patches are also used for Insert FX patches in the Main Mixer.
Subtractor Patch	.zyp	This is a patch for the Subtractor synth device, containing all panel settings. You store your synth sounds by saving Subtractor patches.
Thor Patch	.thor	This is a patch for the Thor synth device, containing all panel settings. You store your synth sounds by saving Thor patches.
Malström Patch	.xwv	This is a patch for the Malström synth device, containing all panel settings. You store your synth sounds by saving Malström patches.
NN19 Sampler Patch	.smp	This is a patch for the NN19 Sampler device, containing references to and settings for all used samples, along with panel settings.
NN-XT Sampler Patch	.sxt	This is a patch for the NN-XT Sampler device, containing references to and settings for all used samples, along with panel settings.
Redrum Patch	.drp	This is a patch for the Redrum drum machine device. It contains information about which drum samples are used, along with all drum sound settings. In effect, a Redrum patch is a stored drum kit.
Dr. Octo Rex Patch	.drex	This is a patch for the Dr. Octo Rex Loop Player device. It contains information about which REX Loops are used, along with all loop and panel parameter settings.
Kong Kit Patch	.kong	This is a patch for the Kong Drum Designer device. It contains information about what drum samples/modules are used, along with all drum sound settings for all 16 channels. In effect, a Kong Kit Patch is a complete stored drum kit.
Kong Drum Patch	.drum	This is a patch for a single Drum channel in the Kong Drum Designer device. It contains information about which drum samples/modules are used, along with all drum sound settings for one single Drum channel.
RV7000 Patch	.rv7	This is a patch for the RV7000 reverb effect, containing all panel settings.
Scream 4 Patch	.sm4	This is a patch for the Scream 4 distortion effect, containing all panel settings.
The Echo Patch	.echo	This is a patch for The Echo delay effect, containing all panel settings.
Pulveriser Patch	.pulver	This is a patch for the Pulveriser effect, containing all panel settings.
Alligator Patch	.gator	This is a patch for the Alligator gate effect, containing all panel settings.
REX files	.rx2, .rcy or .rex	REX files are created in another Reason Studios application, the ReCycle loop editor. REX files contain audio loops chopped into slices, with one slice for each significant beat in the loop. REX files can be imported to Audio Tracks in Reason and are automatically converted to audio files. By loading a REX file into the Dr. Octo Rex Loop Player device, you can play back the loop in virtually any tempo (without affecting the pitch), manipulate individual beats in the loop, extract timing info, etc. Note that you can also load REX files into the samplers, the Redrum drum machine and Kong Drum Designer.

File type	Extension	Description
Audio files and Samples	.wav, .aif, mp3 etc.	Audio files of various formats, resolutions and sample rates can be imported to Audio Tracks in Reason. All sampler devices in Reason can also load and play back samples and audio files in these formats. You can use files of different formats in the same device - one drum sound can be an 8-bit sample, the next a 16-bit sample, etc. The audio file format support differs depending on which computer OS you are using. In macOS, the following audio file formats are supported: .wav (not floating point), .aiff (not floating point), .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4. In Windows, the following audio file formats are supported: .wav (not floating point), .aif (not floating point), .mp3, .aac, .m4a and .wma
SoundFont Bank	.sf2	The SoundFont format was co-developed by E-mu Systems and Creative Technologies and is used with many audio cards and software synthesizers. SoundFont banks store wavetable synthesized sounds, allowing users to create and edit multi-sampled sounds in special Soundfont editing programs. The SoundFonts can then be played back in wavetable synthesizers, typically on audio cards, thereby effectively turning an ordinary sound card into a sampler. The NN-XT and NN19 Samplers and the Redrum drum machine allow you to browse and load SoundFonts. Regardless of which editing program was used to create them, these banks are similarly and hierarchically organized, with folders for instruments, presets, samples etc. The NN-XT, NN19 and the Redrum lets you load individual samples and presets from a SoundFont bank, but *not* the complete SoundFont.
Rack Extension Patch	.repatch	These are patches for Rack Extension devices. All Rack Extension devices use the same file extension but the patch files contain different data depending on which device was used for creating them.
VST Patches	.fxp and .fxb VST2 patches .vstpreset VST3 patches	Reason can read the VST2 patch formats fxp and fxb and the VST3 patch format vstpreset. Provided that the VSTs are installed and detected by Reason, the patches can be opened in the corresponding VSTs.

File types that can be browsed/opened using Reason's Browser.

The following table lists the file formats that you normally browse for and open using the regular (OS) browser:

File type	Extension	Description
Reason Song	.reason or .rns	This is the main document format in Reason. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if you have made the song "self-contained" (see "About Self-Contained Songs"). Opening a Reason Version 5 (or earlier) song will retain the original rack configuration, but will route the signals originally connected to the Out 1 and 2 of the Reason Hardware Interface to a new Mix Channel (see "About opening Reason Version 5 (or earlier) Songs").
Reason Demo Song	.rsndemo	A Reason Demo Song is a factory made song intended to demo the sound and features of the Reason program. Reason Demo Songs, Reason Essentials Demo Songs and Record Demo Songs are the only song file types that can be opened when you run Reason in Demo Mode (without authorization). See "Opening a Reason Demo Song".
Reason Published Song	.rps	A Reason Published Song is a self-contained Reason song (created in Version 5 or earlier) intended for playback only. It can only be opened in Reason and cannot be changed. Its components cannot be extracted and it is only possible to export the song as an audio file if you haven't edited anything. Opening a Reason Published Song song in Reason will retain the original rack configuration, but will route the signals originally connected to the Out 1 and 2 of the Reason Hardware Device to a new Mix Channel (see "About opening Reason Version 5 (or earlier) Songs").
Reason Adapted Song	.rsb	A Reason Adapted Song is a song created in a Reason Adapted version. Opening a Reason Adapted Song song in Reason will retain the original rack configuration, but will route the signals originally connected to the Out 1 and 2 of the Reason Hardware Device to a new Mix Channel (see "About opening Reason Version 5 (or earlier) Songs").



File type	Extension	Description
Record Song	.record	This is the main document format in Propellerhead Record. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if the song is "self-contained" (see "About Self-Contained Songs").
Record Demo Song	.recdemo	A Record Demo Song is a factory made song intended to demo the sound and features of the Propellerhead Record program. Record Demo Songs, Reason Demo Songs and Reason Essentials Demo Songs are the only song file types that can be opened when you run Reason in Demo Mode (without authorization). See "Opening a Reason Demo Song".
Reason Essentials Song	.ree	This is a song created in Reason Essentials. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if the song is "self-contained" (see "About Self-Contained Songs").
Reason Essentials Demo Song	.reedemo	A Reason Essentials Demo Song is a factory made song intended to demo the sound and features of the Reason Essentials program. Reason Essentials Demo Songs can be opened and edited in Reason just like a regular Reason Essentials Song.
Reason Limited Song	.rltd	This is a song created in Reason Limited. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if the song is "self-contained" (see "About Self-Contained Songs").
Reason Intro Song	.rei	This is a song created in Reason Intro. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if the song is "self-contained" (see "About Self-Contained Songs").
Reason Intro Demo Song	.reidemo	A Reason Intro Demo Song is a factory made song intended to demo the sound and features of the Reason Intro program. Reason Intro Demo Songs can be opened and edited in Reason just like a regular Reason Intro Song.
Reason Lite Song	.relt	This is a song created in Reason Lite. It contains the recordings on all audio, instrument and automation tracks - and the device setup in the rack, along with references to any used instrument samples and loops - or it can contain the actual samples and loops if the song is "self-contained" (see "About Self-Contained Songs").
Reason Lite Demo Song	.reltdemo	A Reason Lite Demo Song is a factory made song intended to demo the sound and features of the Reason Lite program. Reason Lite Demo Songs can be opened and edited in Reason just like a regular Reason Lite Song.



Chapter 17
Routing Audio and CV

About this chapter

This chapter describes the various signals used in Reason and how you can route them.

Signal types

The following signal types are used in Reason:

Audio signals

Besides the Spider CV, Matrix Pattern Sequencer and the RPG-8 Arpeggiator, all Reason devices have audio connectors on the back. The audio connectors carry audio signals to or from devices via virtual cables.

- **Audio connectors are shown as large quarter inch jacks.**
- **Audio Effects devices, which are used to process audio, have both audio inputs and outputs.**
- **Instrument devices, which generate audio, have either mono or stereo left/right audio output connectors.**
  You do not have to use both outputs for devices with stereo outputs. Use the left output to use a mono signal from a stereo device.
- **To monitor audio outputs from devices, the signals can be routed, either via the Main Mixer or directly, to the physical outputs of your audio interface via the Reason Hardware Interface (see "Manual audio routing").**
  Typically, if you are using an audio interface with stereo outputs, you will most likely use the Main Mixer to mix the audio signals to the master outputs.
- **To route audio input signals from your audio interface to audio tracks in the sequencer, you just have to select the appropriate input(s) from the Audio Input drop-down list on the corresponding audio track (see "Selecting audio input(s) and defining mono or stereo").**
  This means that you never have to manually patch input signals from the Audio In jacks of the Reason Hardware Interface.

For more information about signal paths in Reason, see "System signal paths".

CV/Gate signals

In the early days of synthesizers, before the MIDI protocol was invented, analog synthesizers could be interconnected using Control Voltage (CV) cables. For example, one cable would be used for controlling pitch while another would send a Gate voltage, basically telling a synth when to play a note and when to stop. The CV signal cables in Reason emulate this analog control system. CV signals are typically used to modulate parameter values, and do not carry audio.

- **CV/Gate connectors are shown as smaller mini jacks.**
- **CV is typically used for modulation purposes.**
  For example, you could modulate a parameter with a CV signal generated by an LFO or an envelope generator on another device.
- **Gate outputs/inputs are typically used to *trigger* events, such as note on/off values, envelopes etc.**
  Gate signals produce on/off values, plus a "value" which could be likened to (and used as) velocity.
- **You can only route CV/Gate signals from an output to an input (or vice versa).**
  You cannot route an input to another input or an output to another output.

P-LAN signals

P-LAN is the internal system used for routing audio signals from Mix Channel and Audio Track devices to the Main Mixer Master Section device - and from Mix Channel/Audio Track devices to other Mix Channel devices that are used as Output Busses (sub-mixers).

P-LAN connections are not indicated by cables or similar in the rack - only by an Audio Output display on the front and rear of Mix Channel and Audio Track devices:



P-Lan signal destinations on Mix Channel and Audio Track devices (front and rear).

If you use the Direct Out jacks on an Audio Track device or Mix Channel device, the internal P-LAN connection is broken. In this case, the audio from the Mix Channel/Audio Track device is not sent to the Master Section.

About MIDI routing

Normally, MIDI (e.g. note and performance data) are sent to devices from their respective sequencer track. No cables are used in the rack to indicate MIDI connections.


For other ways to route MIDI to devices, see the chapters "Remote - Playing and Controlling Devices", "Synchronization and Advanced MIDI" and "MIDI Out Device".

About cables

Cable appearance


If there are many connections in Reason, the cables can sometimes obscure the view, making it difficult to read the text printed on the back panels of the devices. Cables can be displayed in "normal" mode and in "hidden" mode.

▶ **Toggle cable display mode by pressing [K] or by selecting "Hide Cables" on the Options menu:**



- **In "normal" mode, i.e. with the option "Hide Cables" deselected, all cables for all devices are displayed at the back of the rack.**

- **With "Hide Cables" selected, the cable appearance depends on the setting in the "Hide cables function" section on the "User Interface" tab in Settings:**



▶ **Select "Shows for selected devices only" to only display the cables for selected devices.**
All other (non-selected) devices will have "transparent" cables to make it easier to distinguish the cables of selected devices.

▶ **Select "Hides auto-routed cables" to only display manually routed cables.**
All devices with auto-routed cables will have "transparent" cables to make it easier to distinguish the manually routed cables.

▶ **Select "Hides all cables" to hide all auto-routed and manually routed cables.**
All cable connections on devices will be indicated with colored dots in the jacks, and no cables will be displayed.



"Reduce Cable Clutter" selected with the "Hide All Cables" appearance.

- **In "Hide Cables" mode, it's still possible to connect and disconnect cables in the same way as when they are shown.**
See "Manual routing" for a description of routing methods.

Checking and following cable connections

You can always check to which device a jack is connected. This is especially useful if the patch cables are hidden, but it is also practical if you have a lot of cables in your rack, or if the two connected devices are far from each other in the rack:

▶ **Hover with the pointer over a connector and wait a moment.**
A tool tip appears, showing both the device name and connector that the cable is connected to.



About the "Scroll to Connected Device" function


It's possible to scroll directly to a connected device as follows:

1. **Click and hold (or right-click (Win) or [Ctrl]-click (Mac)) on a connector.**
A pop-up menu appears.
2. **Select "Scroll to Connected Device" from the pop-up menu.**
The device in the other end of the cable will be scrolled into view in the rack.

Cable color

To allow for a better overview of the connections in the rack, the cables have different colors:

Green cables indicate effect device connections.



Yellow cables indicate CV connections.

Red cables indicate connections between instrument and mixer devices.

- **Audio connections between instrument and mixer devices are different shades of red.**
- **Connections to and from effect devices are different shades of green.**
- **CV connections are different shades of yellow.**
- **Combinator connections are blue.**

Automatic routing

Auto-routing enables the automatic routing of cables between devices according to certain rules. Auto-routing is performed under the following circumstances:

- **When you create a new (Empty) Song, the Master Out L & R on the Master Section device are by default connected to Outputs 1 & 2 of the Reason Hardware Interface.**
- **When a new device is created.**
- **When moving, duplicating or pasting devices with [Shift] pressed.**
- **When selecting "Auto-route Device" from the Edit or context menu, with one or several devices selected in the rack.**
- **Audio input signals from the Reason Hardware Interface to the audio tracks in the sequencer are automatically routed "in the background".**

When applicable, auto-routing is performed in stereo.

Auto-routing of audio input signals

- **Available audio inputs on your installed audio interface are auto-routed from the Hardware Interface to audio tracks in the sequencer "in the background".**
  This means that no patch cables are necessary for routing audio to audio tracks in the sequencer.

Auto-routing of Instrument devices

Routing to the Main Mixer

- **When you create an instrument device, it is automatically connected to a new Mix Channel device in most situations.** However, if the instrument device is created directly below an unused (no inputs connected) Mix Channel device in the rack, it will be connected to this instead.

Routing to the Mixer 14:2 or Line Mixer

- **If a Mixer 14:2 or Line Mixer 6:2 is selected when you create an Instrument device, or if you create an Instrument just below the mixer device in the rack, the instrument will be auto-routed to the first available inputs on the mixer device.**

Auto-routing of Effect devices

Routing as a Main Mixer insert effect

- **When you have a Mix Channel or Audio Track device selected and create an effect device, it will be automatically connected as an insert effect in the Mix Channel/Audio Track device. See "Adding Insert effects".**


! **The above does not apply to the Master Section device - see below!**

▶ **It's also possible to select Effect Combi patches as insert effects - see "Using Effect Combi patches as insert effects".**

Routing as a Main Mixer Master Section insert effect

Routing an effect device as an insert effect in the Maser Section device can be done in the following ways:

1. **Click the "Show Insert FX" button on the Master Section device and then click inside the Insert FX container.**
   A blue insertion line with a + sign is shown:



2. **Create an effect device from the Create menu, or by selecting it from the device context menu, or by double-clicking on the device in the Device Palette.**
   The device will be automatically connected as an insert effect in the Master Section device.

▶ **By dragging and dropping an effect device from the Device Palette to the open Insert FX container in the Master Section device, it will be automatically connected as an insert effect.**

▶ **It's also possible to select Effect Combi patches as insert effects in the Master Section - see "Using Effect Combi patches as insert effects".**

Routing as a Main Mixer Master Section send effect

- **When you have the Master Section device selected and create an effect device, it will be automatically connected as a send effect to the first available Send FX connectors on the Master Section device. See "Creating Send effects".**

▶ **It's also possible to use the "Add Send FX" function to add effect devices or Effect Combi patches as send effects in the Master Section - see "Creating Send effects".**

Routing directly to another device

- **When you have an instrument device selected and create an effect, that effect will be connected as an "insert" effect between the instrument device and the Mix Channel/mixer device.**
  Examples of effects that work well as insert effects are distortion, compression and modulation effects.

Routing as a send effect to a mixer device

- **When you have a mixer device (the Mixer 14:2 or Line Mixer 6:2) selected in the rack and create an effect device, it will be automatically connected as a send effect (to the first free Aux Send/Return jacks).**

Auto-routing of CV/Gate signals

The Matrix Pattern Sequencer

- **When you have an instrument device (e.g. a Subtractor/Thor/Malström/NN-19/NN-XT/Combinator) selected and create a Matrix Pattern Sequencer, the Note and Gate CV signals will be auto-routed to the instrument device.**
  The Matrix Note and Gate CV outputs are automatically connected to the Sequencer Control CV and Gate inputs on the instrument device, respectively.

The RPG-8 Arpeggiator

- **When you have an instrument device (e.g. a Subtractor/Thor/Malström/NN-19/NN-XT/Combinator) selected and create an RPG-8 Arpeggiator, the Note CV, Gate CV, Mod Wheel and Pitch Bend signals will be auto-routed to the instrument device.**
  The RPG-8 Note CV and Gate CV outputs are automatically connected to the Sequencer Control CV and Gate inputs on the instrument device, respectively. The RPG-8 Mod Wheel and Pitch Bend outputs are automatically connected to the Modulation Inputs Mod Wheel and Pitch Bend inputs on the instrument device, respectively.

Auto-routing devices after they have been created

Some additional rules regarding auto-routing devices that are already in the rack:

▶ **To reroute a device already in the rack, you can select it and choose "Disconnect Device" and "Auto-route Device" from the Edit menu or context menu.**
When you use "Auto-route Device" it will be connected in a logical way according to its current location in the rack.

▶ **If you hold [Shift] and drag a device to a new position in the rack, it will be re-routed (as if you deleted it and created it in its new position).**
This allows you to e.g. change the order of effect devices in a signal chain by Shift-dragging them.

- **If you delete a device connected between two devices, the connection between the two remaining devices is preserved.**
  A typical example might be if you have an effect device connected between an instrument device and a Mix Channel device. If you delete the effect device, the instrument device will be re-routed directly to the Mix Channel device.
- **When you move a device in the rack, the connections are not affected.**



- **When you duplicate devices by dragging and dropping, or using copy and paste, the devices are not auto-routed.** If you would like them to be auto-routed, hold down [Shift] while performing the operation.

! **If you are duplicating a complete Device Group (see "Duplicating devices"), this will often include a Mix Channel. In this case, the Mix Channel will also be duplicated, with no need for further auto-routing.**

Bypassing Auto-Routing

▶ **If you wish to create a new device without any auto-routing taking place, press [Shift] when creating the device.**

About re-routing devices in songs created in Reason Version 5 or earlier

If you open a Reason song, created in Reason Version 5 or earlier, the song will open with the outputs of the Mixer 14:2 connected to the inputs of a single Mix Channel device in Reason Version 13 To make better use of the Main Mixer in Reason Version 13 you will have to re-route all instrument devices in the older Reason song to separate (new) Mix Channels in Reason Version 13. To make this re-routing a little easier, proceed as follows:

1. **Open the older (Version 5 or earlier) Reason song in Reason Version 13.**
2. **Delete the Mixer 14:2. ***
3. **Select "Select All" from the Edit menu to select all devices.**
4. **Select "Auto-route Device" from the Edit menu.**
   This will create a Mix Channel device for each instrument in the old Reason song, keeping any connected effect devices in the signal chain.

* If you have send effects connected to the Mixer 14:2, you will need to re-route them manually to the Main Mixer Master Section device. You might also want to make a note of fader and pan settings on the Mixer 14:2 before deleting it.


Manual routing

To connect devices manually, you need to flip the rack around to see the back. This is done by pressing [Tab], or by selecting "Toggle Rack Front/Rear" from the Options menu, or by clicking the Flip Rack button at the top of the song window.

Note that routing cables can be done regardless of the "Reduce Cable Clutter" setting on the Options menu. This means that you can connect cables even though they are hidden (see "Cable appearance").



On the back of each device you will find connectors of two different types: audio and CV (Control Voltage, used for controlling parameters - see "Using CV and Gate"). Audio inputs and outputs are shown as large quarter inch jacks, while CV input and output jacks are smaller. For now, we'll stick to the audio connections.



Audio and CV connectors.


▶ **When the back of the rack is shown, you can still navigate in the rack by scrolling or by using the computer keyboard.**

There are two ways to route signals from one device to another:

- **By connecting virtual patch cables between inputs and outputs.**
- **By selecting connections from a pop-up menu.**

Connecting cables

1. **Click on the desired input or output jack on one of the devices, and drag the pointer away from the jack (with the mouse button pressed).**
   A loose cable appears.



2. **Drag the cable to the jack on the other device.**
   When you move the cable end over a jack of the correct type (audio/CV, input/output) it will be highlighted to show that a connection is possible.
3. **Release the mouse button.**
   The cable is connected. If both input and output are in stereo and you connect the left channels, a cable for the right channel is automatically added.

! **Dragging a cable to make a connection can be aborted by pressing [Esc] while keeping the mouse button pressed.**


▶ **You can change an existing connection in the same way, by clicking on one end of the cable and dragging it to another connector.**

Connecting cables using pop-up menus

1. **Right-click (Win) or [Ctrl]-click (Mac) on a connector.**
   A pop-up menu appears, listing all devices currently in the rack.

▶ **If the connector is an audio output, the first alternative in the pop-up is to route to a new Mix Channel. This is useful if you want to route separate audio outputs (e.g. in Kong or Redrum) to separate Mix Channels.**

2. **Move the pointer to the device you want to create a connection to.**
   A sub-menu appears, listing all suitable input/output connections. For example, if you clicked on an audio output on a device, the hierarchical sub-menus will list all audio inputs in all other devices.




- **If a device is grayed out on the pop-up menu, there are no suitable connections on the device.**
- **An asterisk (*) next to the connector name on the sub-menu indicates that the connection is already occupied.**
  It's possible, however, to select an occupied connection. Doing so will disconnect the existing connection and replace it.

3. **Select the desired connector from the submenu.**
   The connection is created.

Disconnecting cables

There are two ways of manually disconnecting cables:

- **Click on one end of the cable, drag it away from the jack and drop it anywhere away from a jack.**
- **Click and hold (or right-click (Win) or [Ctrl]-click (Mac)) on a connector and select "Disconnect" from the pop-up menu that appears.**



Disconnecting devices

It's also possible to disconnect all cables from selected devices in one go:

- **Select the device(s) and then choose "Disconnect Device" from the Edit menu or device context menu.**
  All cables on the selected device(s) are now disconnected simultaneously.

Using CV and Gate

CV/Gate is used for modulating and triggering device parameters. Each separate Device chapter lists the available CV/Gate connections and the parameters that can be modulated or used for modulation outputs for that device.

Routing CV and Gate signals

There are not really any hard and fast "rules" applicable to CV/Gate routing. A few points should be mentioned, though:

- **The specific "Sequencer Control" inputs present on e.g. the Subtractor, Thor, Malström, NN-19 and NN-XT sampler devices are primarily intended for controlling these devices as (monophonic) instruments from the Matrix Pattern Sequencer or the RPG-8 Arpeggiator.**
  If your intention is to use the Matrix or the RPG-8 CV/Gate outputs to create melodic patterns using these Instrument devices, you should use the Sequencer Control inputs.

▶ **The Matrix Pattern Sequencer can be used in many other ways, besides creating melodic patterns. For example you could use it to modulate any CV controllable parameter, with the added advantage of the modulation being synchronized to the tempo.**

- **Conversely, if you would like to apply Gate or CV modulation to more than one voice, you should *not* use the Sequencer Control inputs, as these only function monophonically.**
- **Feel free to experiment: Use Gate signals to control parameter values and CV signals to trigger notes and envelopes, if you like.**
  See the chapter "Matrix Pattern Sequencer" for more tips about using CV.

▶ **By routing CV to the rotary controls on a Combinator, you can CV control virtually any parameter on any device - see "CV Connections" in the Combinator chapter.**

About CV Trim knobs

All CV inputs have an associated Trim knob. This is used to set the CV "sensitivity" for the associated parameter. The further clockwise a CV trim knob is set, the more pronounced the modulation effect.

- **Turned fully clockwise, the modulation range will be 100% of the parameter range (0-127 for most parameters).**
- **Turned fully anti-clockwise, no CV modulation will be applied.**



Chapter 18
The Main Mixer

About this chapter

This chapter describes the various procedures, parameters and functions in the Main Mixer as well as the relationship between mixer channels and the Audio Track/Mix Channel devices in the rack. The chapter also covers how to set up and use Insert and Send effects, as well as some advanced routing tips and tricks.

Overview



The Main Mixer is a fully equipped mixer with pro features to meet the most demanding mixing needs. You can have an unlimited number of channels, each with advanced eq and dynamics control.


The mixer can be viewed as a remote control for Audio Track and Mix Channel rack devices. This is where you control levels, make eq and effect settings etc., although the devices themselves "live" in the rack.

The Audio Track, its device and mixer channel strip

Audio Tracks and their associated rack devices are for recording/playing back audio.

When you create a new Audio Track, a corresponding Audio Track device is added to the rack and an Audio Track channel strip is added to the Main Mixer.

The track, device and channel strip all belong together. If you delete the device, the corresponding track and channel strip are also deleted.



An Audio Track in the sequencer with its corresponding rack device and channel strip in the Main Mixer.

- **Audio Track devices have no audio inputs on the back - the audio is fed internally to the Audio Track device from the associated sequencer track.**

The Mix Channel device and channel strip

A Mix Channel device acts as a host to a source device (e.g. an instrument device). When you create an instrument, a Mix Channel device is added automatically to the rack and a corresponding Mix Channel strip is added to the Main Mixer. You can also create Mix Channels manually from the Utilities tab in the Device Palette - or from the Create menu. This is useful if you need to make manual mixer routings - see "Advanced routing tips and tricks" at the end of this chapter.

The Mix Channel device has inputs to which the source (instrument) device is connected. The Mix Channel device and channel strip will automatically be assigned the name of the connected source device, but this can be changed - see "Naming mixer channels".

A Mix Channel device will not automatically have a corresponding track created in the sequencer (but the connected source device will). Mix Channel tracks are created manually and used for automating channel strip parameters - see "Automating mixer parameters".





A Mix Channel device (with an ID8 source device connected) and the corresponding channel strip in the Main Mixer.

The Master Section device and mixer strip

The Master Section device is always present and is fixed in the rack, just below the Reason Hardware Interface. This is where all your Audio Track and Mix channels are summed and mixed to stereo, and where you set up your Send effects and Master Insert effects. For descriptions of how to set up and use effects, see "Insert FX" and "Send FX".

The corresponding Master Section mixer strip is also fixed and is always visible to the right in the Main Mixer.

The Master Section track is used for automating Master Section parameters - see "Automating mixer parameters".



The Master Section device and mixer strip.

Navigating in the Main Mixer

Viewing the Main Mixer area

There are several ways to bring the Main Mixer area into view:

- **By dragging the gray Rack header downwards to reveal the mixer area.**
- **By pressing [F5] on your keyboard.**
- **By clicking the Mixer button in the top bar.**
- **To view the mixer in a separate window, select "Show Mixer in Separate Window" on the View menu.**

Scrolling and navigating in the Main Mixer

The Channel Strip and Mixer scrollbars allow you to navigate between channels in the Main Mixer or to focus on a specific channel strip area:



- **The Mixer scrollbar allows you to scroll between all the channels in the mixer.**
  The Mixer scrollbar will only show and scroll the regular channel strips - the Master Section is always visible and fixed to the right in the Main Mixer area.
- **The Channel Strip scrollbar area allows you to scroll between the various channel strip sections (channel strip sections can also be hidden, see below).**
  All areas of the channel strips and Master Section can be scrolled, except the Channel Header section (the area below the faders) which is always visible at the bottom. If the Main Mixer is in its separate window, the fader section is also always visible at the bottom.
- **Alternatively, you can use a mouse scroll wheel or a trackpad to scroll.**
- **The [left]/[right] arrow keys can be used to move between channels**
- **The [Page Up]/[Page Down] keys can be used to scroll vertically.**
- **The [Home] and [End] keys will scroll the mixer to the leftmost and rightmost channel strip, respectively.**

Showing and hiding channel strip sections

Channel strips are divided into sections, which can be globally shown or hidden in the mixer. This enables you to hide sections that you don't need to tweak or to focus on specific sections. Hiding a section does not alter the mixer functionality in any way, sections are still active when hidden.

Each section has a section name header in the channel strip. The sections are as follows (from the top down): Input, Dynamics, EQ, Inserts, FX Sends and Fader. (See "The channel strip" for descriptions of each section.)

The section headers are always visible even if a section is hidden, as is the channel header (name label) section below the faders. Note that if the Main Mixer is detached from the rack, the fader section cannot be hidden.



Section headers in the channel strip. A red light to the right of the section header name indicates that the section is in use for the channel. Here, all sections are hidden (except the Fader section), so that only the section headers are visible.

To show/hide channel strip sections:

- ▶ **Double-click a section header in the channel strip.**
  This will also show or hide the corresponding section.

- ▪ **Showing/hiding channel strip sections affects all channel strips, including the Master Section strip.**

Differences between the channel strips and the Master Section strip

Showing/hiding mixer strip sections also affects the Master Section strip. There are a few differences in the Master Section and the channel strip sections when using the Show/Hide buttons:

- **There is no Input section in the Master Section. If the Input section is shown, the Master Section will display a blank panel.**
- **The "EQ" Show/Hide button affects the FX Send section in the Master Section.**
- **The "FX Sends" Show/Hide button affects the FX Return section.**

Switching between channels, rack devices and tracks

The RACK and SEQ buttons allow you to go to a channel's rack device or sequencer track directly from the Main Mixer. Both buttons are located in the Channel Header section of the Main Mixer:



If you click the RACK button the following happens:

- **For Audio Track channels, this will bring the Audio Track rack device into view.**
  The rack area will be shown (if hidden) with the channel device in view.
- **For Mix channels, this will bring the Source device (i.e. the instrument device connected to the channel) into view.**
  [Shift]-clicking the RACK button for a Mix channel will instead bring the Mix Channel device into view.

The SEQ button allows you to go to a channel's sequencer track from the mixer. The SEQ button is also located in the Channel Header section. If you click the SEQ button the following happens:

- **For Audio Track channels, this will bring the Audio Track into view.**
  The sequencer area will be shown (if hidden) with the track in view.
- **For Mix channels, this will bring the track for the Source device into view.**
  [Shift]-clicking the SEQ button for a Mix channel will instead bring the Mix Channel automation track into view. If there isn't an automation track, one will automatically be created.
- **If you have previously deleted Mix Channel tracks and/or Audio tracks in the sequencer, clicking the SEQ buttons on the corresponding channel strips in the mixer will automatically create new sequencer tracks.**

To find the mixer channel for a specific track in the sequencer, or for a specific Mix Channel or Audio Track device in the rack, proceed as follows:

1. **Select the track in the sequencer, or select the Mix Channel/Audio Track device in the rack.**
2. **Bring the mixer into view.**
   The channel will get Edit Focus (see "Channel Header section") and be scrolled into view in the Main Mixer. If you have both the sequencer and Main Mixer in view, or the rack and Main Mixer, clicking a track in the Track List, or on a Mix Channel/Audio Track device in the rack, will flash the corresponding channel strip in the Main Mixer.

Managing mixer channels

Creating and deleting channels

Mixer channel strips are automatically created when you create Audio Track and Mix Channel devices. In most situations, a Mix Channel device (with its channel strip) is also automatically created when you create an instrument device (see "Creating devices").

To delete a channel, proceed as follows:

- **Select the channel strip in the Main Mixer, or select its device in the rack, and press [Delete] or [Backspace].**
  Alternatively, select "Delete Channels and Tracks" from the Edit menu or context menu.

  This will delete the channel strip, device and associated track. An alert appears asking you to confirm deletion.

  If there are devices connected to the Mix Channel device you delete, and "Auto-group Devices and Tracks" is selected on the Options menu, the alert will ask if you want to delete only the selected device, or all devices in the Device Group (see "Creating devices" for more information).


Selecting channels

To select channels in the mixer you can use any of the following methods:

- **Clicking anywhere on a channel strip (including parameters) will select the channel.**
  If you are not editing parameters but want to select a channel, the channel header is a good place to click. You could also click anywhere on the channel strip background (where there are no parameters or displays).
- **If the Main Mixer has focus, you can use the left and right arrow keys to select channels.**
  The selection will move to the next adjacent channel (left or right) with each keystroke.
- **It is possible to select several channels, by using standard [Shift], or [Ctrl](Win) or [Cmd](Mac) selection techniques.**
  This allows you to e.g. change the Fader levels of all selected channels simultaneously (see "Changing Fader section parameters on multiple channels simultaneously"), or move or delete several channels in one go. The last selected channel will be given edit focus which is indicated by a red strip in the channel header (see "Channel Header section").
- **To select all channels, use the "Select All Channels" item on the Edit menu or channel strip context menu.**
  The Main Mixer must have focus for this item to be available.

Moving channels

To move channels in the Main Mixer, simply select them and use standard drag and drop method. A red insertion line will show the insertion point, exactly like when moving devices in the rack or tracks in the sequencer.



Moving a channel. The thicker red line indicates where the moved channel will be inserted.

Displaying channels, devices and tracks in the same order

Channel strips in the mixer, Audio Track and Mix Channel devices and tracks can be independently re-ordered. This allows you to set up the main work areas according to your preferences.

Should you wish to display mixer channels, devices in the rack and tracks in the same order, proceed as follows:

1. **Select the area where everything is in the order you want reflected in the other areas.**
   This could either be the Main Mixer, the sequencer or the rack.
2. **Use the "Select All" Edit menu item.**
   This menu item would be "Select All Devices" if the rack is selected, or "Select All Channels" if the mixer is selected. You could also select channels, tracks or devices manually.
3. **Select the "Sort Selected Device Groups" Edit menu item.**
   Channels, devices and tracks will now all be presented in the same order as the area you selected in the first step.

Copying and duplicating channels

Cut, Copy and Paste functions

Selected channels can be moved or copied using the "Cut/Copy/Paste Channels and Tracks" functions on the Edit menu or channel strip context menu. This allows you to copy one or several channels from one Song document to another. The following rules apply:

- **Cut and Copy affects all selected channels, and behaves according to the standard procedures.**
  Cut moves the channels to the clipboard, removing them from the rack, sequencer, and mixer, while Copy creates copies of the channels on the clipboard, leaving the originals as they were.
- **If the "Auto-group Devices and Track" option is activated on the Options menu, this will copy the channel's entire Device Group, including tracks and clips - see "Creating devices".**
- **If no channel is selected when pasting, channels will be added to the left of existing channels in the Main Mixer.**
  If a channel is selected when pasting, the copied channel(s) will be inserted to the right of the selected channel.

Duplicating channels

- **To make a duplicate copy of a mixer channel, with its settings and Insert FX (if any), hold down [Ctrl](Win) or [Option](Mac) and drag the channel to where you want it.**
  Several selected channels can be duplicated. You can also select "Duplicate Channels and Tracks" functions on the Edit menu or mixer context menu.
- **If the "Auto-group Devices and Track" option is activated on the Options menu, this will duplicate the channel's entire Device Group, including tracks and clips - see "Creating devices".**

Copy channel settings

If you wish to copy mixer channel settings from one channel to another you can use this function.

1. **Select the channel you wish to copy settings from.**
   Copy channel settings only works when a single channel is selected, if several (or no) channels are selected the function is not available.
2. **Select "Copy Channel Settings >" on the Edit menu or channel context menu.**
   On the submenu you can select to copy channel settings from a single section (Dynamics, Filters and EQ, Insert FX or FX Sends), or "All", which copies everything including any Insert FX devices with their settings.
3. **To paste the settings, select the channel you wish to copy channel settings to, then select "Paste Channel Settings" on the Edit menu or mixer context menu.**
   The type of settings you copied will be reflected in the paste menu item, e.g. "Paste Channel Settings: EQ" if you only copied the EQ section.

- **The copied channel settings remain on the clipboard (until you cut or copy again) so you can paste them to other channels if you so wish.**
  This can only be done with one selected channel at a time - pasting channel settings is not possible if several channels are selected.
- **Copying channel settings can also be done by selecting an Audio Track or Mix Channel device in the rack.**
  The procedure is the same. You can copy settings from a device to a mixer channel or vice versa.

Resetting channel settings

Resetting channel settings initializes all channel strip parameters to default values and removes any insert effects (see "Insert FX section") from the channel.

- **To initialize a mixer channel (or Mix Channel/Audio Track device), select "Reset All Channel Settings" from the Edit menu or channel/device context menu.**
  Channel settings reset is not possible if several channels are selected.

! **Any Output Bus routings are not affected (see "Output Busses").**

Naming mixer channels

New Audio Tracks will by default be named "Audio Track + number". When creating an Instrument, the Mix channel will take its name from the patch of the connected Instrument device.

- **To enter a new name for a channel, double-click the name in the channel header.**
  A text field opens allowing you to enter a name for the channel.

Channel names are reflected - and can be changed - in all areas; the Track List., the Main Mixer and in the device. Mix Channel source devices and tracks have independent names from the Mix Channel device/channel strip. By default, a Mix channel takes its name from its source device (typically, the instrument device connected to it). If you change the name of the source device, the Mix channel name will change too.



If you want the source device and Mix channel to have different names, change the name of the Mix channel. To return to the default state (and use the source device name for the Mix channel), just delete the Mix channel name.

! **There are special naming conventions when you are using Parallel Channels, see "Naming Parallel Channels".**

Coloring mixer channels

Mixer channels are shown with the same color as their corresponding rack devices and tracks. The color is shown in the channel header and channel strip section headings:



A channel strip with all sections folded, except for the Fader section.

- **You can change the color for a channel by selecting it and using the Channel Color submenu on the Edit menu or context menu. This will also change the color of the corresponding rack device and track (and vice versa).**
- **For Mix Channels connected to a source device (e.g. an instrument), the Channel Color submenu has a special setting called "Mirror Source Track Color". If this is on, any color settings you make will be reflected both in the source device (the instrument device and track) and in the channel strip.**
  This is true regardless of whether you change the color in the mixer, in the rack or in the sequencer.
- **To make independent color settings for Mix Channels, turn off "Mirror Source Track Color" first.**
  For example, this is useful if you have a Redrum with separate outputs connected to different Mix Channels, and want these to have different colors in the mixer.

! **If you change the color of an Output Bus channel, this will be reflected in the Output areas on all other channels connected to that Output Bus, see "Creating an Output Bus".**

The channel strip

The channel strip is divided into sections, each marked with a section header. Mix Channel and Audio Track channel strips have identical parameters. Here is a detailed rundown of the parameters and functions in each section.

Input section




Input Gain

Parameter	Description
Gain	This sets the input gain for the channel. Range is +/- 18 dB. If Gain is set to any other value than the default 0,0 dB or Invert Phase is on (see below), a LED is lit to the right in the section header to indicate the section is active.
INV (Invert Phase)	This inverts the phase of the input signal to correct eventual phase problems. For example, using multiple microphones during recording can sometimes cause phase-cancellation between microphones picking up the same sound source but at slightly different distances. Phase problems are most noticeable when signals are summed to mono. Out of phase signals are indicated by a lack of lower frequencies and a generally "hollow" sound quality.

Signal Path section


The Dynamics, EQ and Insert effect sections will by default process a channel signal in that order, i.e. the order of the sections as shown in the channel strip (from the top down). By using the buttons in this section, the signal path order can be changed internally.

Parameter	Description
Insert Pre	If this button is activated, the Insert effects are placed before the Dynamics and EQ sections in the signal path.
Dyn Post EQ	Activating this button places the EQ before the Dynamics and Insert sections in the signal path.
Insert Pre + Dyn Post EQ	If both buttons are activated, the order will be Insert, EQ and lastly Dynamics.
FILTERS TO DYN S/C	See "About the Filters To Dynamics Sidechain button".



The displays illustrate the selected signal path order of the processing for each channel.

Dynamics section



Each channel strip has a powerful dynamics section featuring compression/limiting and gating/expansion. The upper part of the section (with a white background) is the compressor/limiter, and the lower part (gray background) is the gate/expander. The compressor and gate processing can be independently switched in or out of the circuit.

Compressor/Limiter

Compressors reduce dynamic range by evening out the difference between loud and quiet signals. This makes signal levels easier to balance, and can add punch and sustain to the sound.

The Main Mixer's compressor/limiter is a flexible processor which has soft-knee (a gradual, smooth onset of compression) characteristics but can be switched to peak limiting, where levels above the set threshold are instantly reduced. The compressor also features automatic make-up gain.

The parameters are as follows:

Parameter	Description
Comp "ON" button	Activates/deactivates the compressor.
RATIO	Sets the amount of gain reduction applied to the signal above the set Threshold. The Ratio can be set from 1:1 (no reduction) to Infinite:1.
PEAK button	When activated this changes the signal detection from RMS to Peak, which results in an instant attack time. Peak mode is suitable for compression of sounds with fast attacks like drums.
THRES (Threshold)	This sets the level at which onset of compression occurs. Signals below the Threshold setting are unaffected, but when the level exceeds the threshold, compression kicks in. Range: -52 dB to 0 dB Automatic make-up gain (based on the Ratio and Threshold settings) is applied to compensate for level reduction caused by compression and maintain a steady output level.
REL (Release)	Release determines the time it takes before the compressor lets the sound through unaffected after the signal level drops below the set threshold. Set this to short values for "pumping" compressor effects, or to longer values for a smoother change of the dynamics. Range: 100ms to 1000ms.
FAST button	Attack - the time it takes for the compressor to react when signals rise above the set threshold level. If the FAST button is activated the attack will be fixed at 3ms for 20 dB gain reduction.
Meter	The right LED meter shows the gain reduction applied by the compressor.

Gate/Expander

Gating or expansion will attenuate signals below a set threshold; the opposite of compression. It can be used to reduce or eliminate unwanted background noise that may be present when there is no signal to mask it. Gating is also commonly used to reduce microphone "bleeding", e.g. when recording a close-mic'ed drum kit you can use gating to silence the tom microphones when the toms aren't being played to tighten up the sound, and for special effects like "keying" (see below).

Higher expansion ratios (10:1 and above) are referred to as noise gating, where the channel is completely silenced if the level drops below the set threshold.

The Gate/expander has the following parameters:

Parameter	Description
Gate "ON" button	Activates/deactivates the gate.
RANGE	Sets the amount of gain reduction applied to signals below the set Threshold. The Range can be set from 0dB (no reduction) to -40dB. If the EXP button is on (see below), the RANGE knob sets the expansion amount.
EXP button	When activated this changes the operating mode from Gate to Expansion. The RANGE knob (see above) then sets the expansion amount.
THRES (Threshold)	This sets the level at which the gate opens or closes. Signals below the Threshold setting are gated, but when the level exceeds the threshold, the gate opens. Range: -52 dB to 0 dB Note that the threshold for closing the gate is slightly lower than the threshold for opening the gate. This is to avoid undesirable gate triggering with signal levels close to the set threshold.
REL (Release)	Release determines the time it takes for the gate to go from open to fully closed. Fast release times will fade the signal abruptly once the level falls below the threshold, and longer release times will slowly fade out the signal. Range: 100ms to 1000ms.
FAST button	Attack - the time it takes for the gate to open - is normally1.5ms per 40dB. If the FAST button is activated the attack will be 100µs (microseconds) per 40 dB, which is useful for percussive material were the waveform rises steeply in a very short time.
HOLD	This determines the time the gate stays fully open after the signal falls below the threshold. Hold interacts with the Release parameter such that Release only starts acting after the set Hold time. Range: 0ms to 4000ms.
Meter	The left LED meter shows the gain reduction applied by the gating/expansion.

About the Filters To Dynamics Sidechain button





When this button (found in both the Input and EQ sections) is activated, the Low Pass and High Pass filters can be used to filter the channel sidechain signal before the dynamic processing.

The channel signal itself will not be directly affected by the filters, only the sidechain signal. The filtered sidechain signal is what triggers the dynamic processing, but the dynamic processing is applied to the channel signal. This allows you to use frequency sensitive compression.

By trimming low and/or high frequencies you can specify which frequency range should trigger the compressor or gate. A typical application of frequency sensitive compression is "de-essing" where harsh sibilants in vocal material are reduced or eliminated. This is done by filtering the Sidechain signal so that only high frequencies ("s" noises) will trigger the compressor.

! **When the "Filters To Dyn S/C" is active, the LPF and HPF buttons are not available in the Spectrum EQ Window, see "The Spectrum EQ Window".**

The Key button and the Dynamics Sidechain inputs

You can use external signals to trigger the Dynamics section. This is done by connecting an external signal output to the Sidechain inputs on the back of the Mix Channel or Audio Track rack device.



The Sidechain inputs.

When a cable is connected to the Sidechain inputs the "KEY" button is activated automatically and the Dynamics section for the channel will now be "keyed" i.e. triggered by the external signal instead of the channel signal.

For example, you could use a drum loop to trigger the gate for a channel playing a synth pad to create rhythmic chord effects.

See "Using compression sidechaining" for a description of further uses of sidechaining.

About Gain Reduction CV



The Gain Reduction CV out connector on the back of a Mix Channel or Audio Track rack device can be used to modulate other parameters with the amount of gain reduction applied by the compressor/gate. The gain reduction CV out can be used as an envelope follower as the CV follows the dynamics of the original signal.

For example, try using gain reduction CV to control filter frequency for "auto-wah" effects.

EQ section



This is a four-band EQ with parametric midrange controls and high and low frequency shelving bands. The EQ can be switched between two operating modes, each with slightly different curve characteristics. There is also a filter section with low pass and high pass filters.

The EQ can be placed before or after Dynamics in the signal path - see "Signal Path section".

The parameters are as follows:

Parameter	Description
Spectrum EQ Window button	Click this button to bring up the Spectrum EQ Window where you can edit the EQ and Filter parameters graphically, see "The Spectrum EQ Window".
LPF "ON" button	Activates/deactivates the low pass filter. A low pass filter lets low frequencies pass and cuts out the high frequencies.
HPF "ON" button	Activates/deactivates the high pass filter. A highpass filter is the opposite of a lowpass filter, cutting out lower frequencies and letting high frequencies pass.
LPF Frequency	The Low Pass filter (LPF) removes high frequencies from the signal, making the sound less bright. The LP filter has 12dB/Octave roll-off curve. Range is 100 Hz - 20 kHz.
HPF Frequency	The High Pass filter (HPF) removes low frequencies from the signal, causing a thinner sound. The HP filter slope has a 18 dB/Octave roll-off. Range is 20 Hz - 4 kHz.
FILTERS TO DYN S/C button	See "About the Filters To Dynamics Sidechain button".
EQ "ON" button	Activates/deactivates the EQ. (This does not affect the LPF/HPF filters.)
"E" button	When the "E" button is activated the EQ will have slightly different curve characteristics. In normal mode (E button deactivated), the Gain setting will also affect the bandwidth (Q) for the HMF and LMF EQ sections. The higher the gain, the narrower the bandwidth and vice versa. With E mode activated, bandwidth is constant at all gain settings. (Check out the difference in "The Spectrum EQ Window" if you like.)

Parameter	Description
HF Gain/Frequency	The HF section provides high frequency shelving equalization. Frequencies above the set corner Frequency will be cut or boosted by the set HF Gain amount. The HF Gain control can cut or boost the selected frequency range +/- 20dB and the HF Frequency can be set between 1.5kHz - 22kHz.
HF BELL mode	When this button is activated, the HF EQ will switch to peaking characteristics. This means it works like a regular parametric EQ band, cutting or boosting the signal around the set frequency. Bell mode has a fixed bandwidth or "Q" (see below).
HMF Gain/Frequency/Q	The high medium frequency EQ is fully parametric. HMF Gain is adjustable +/- 20dB. Center frequency range is 600 Hz - 7 kHz. The "Q" parameter adjusts the bandwidth around the set center frequency. Q range is 0.70 - 2.50. The higher the Q value, the narrower the affected frequency range - except in "E" mode (see above).
LMF Gain/Frequency/Q	The low medium frequency EQ is also fully parametric. LMF Gain is adjustable +/- 20dB. Center frequency range is 200 Hz - 2 kHz. The "Q" parameter adjusts the bandwidth around the set center frequency. Q range is 0.70 - 2.50. The higher the Q value, the narrower the affected frequency range - except in "E" mode (see above).
LF Gain/Frequency	The LF section provides low frequency shelving equalization. All frequencies below the set Frequency will be cut or boosted by the set LF Gain amount. The LF Gain control can cut or boost the selected frequency range +/- 20dB and the LF Frequency can be set between 40 Hz - 600 Hz.
LF BELL mode	This works in the same way as described above for the HF filter, but affects the LF filter.

The Spectrum EQ Window

The EQ section can also be displayed and edited "visually". This is done in the Spectrum EQ floating window. Besides the EQ functionality, the Spectrum EQ also features a spectrum analyzer which displays the audio frequency content of the selected mixer channel in real-time. Here is how you can work with the Spectrum EQ:

1. **Select "Show Spectrum EQ Window" from the View menu (or press [F2]), or click the Spectrum EQ Window button on the desired channel strip (see "Spectrum EQ Window button") or on the device in the rack:**
   The Spectrum EQ window shows up and the (pre-Fader) frequency content of the currently selected mixer channel is displayed in gray during playback:



The Spectrum EQ Window with audio playing back.

! **The LPF and HPF buttons are only present when the "FILTERS TO DYN S/C" button is off.**

▶ **Click and drag the Spectrum EQ window frame to resize the window horizontally and vertically as desired.**

▶ **Select the desired mixer channel for the Spectrum EQ by selecting it from the drop-down list at the bottom of the window.**

! **If "Master Section" is selected, no controls are available in the window, since the Master Section lacks these.**

- **If the "Follow Selection" checkbox is ticked, changing sequencer track, Mix Channel/Audio Track device in the rack, channel strip, or editing parameters on other channel strips will automatically change the Spectrum EQ Window focus to show the signal of the corresponding mixer channel.**

2. **Tick the "EQ On" box to activate the EQ in the channel strip and bring up the parameters in the window.**
   You can also activate the HPF and LPF Filters, E Mode, HF Bell mode and LF Bell mode for the selected mixer channel by ticking the corresponding check boxes in the window. The pictures below shows how the different objects in the Spectrum EQ window correspond to the channel strip parameters:



The Spectrum EQ Window with the Filters, EQ, E Mode, Bell Mode and Analyzer functions active during audio playback.



The Spectrum EQ editing objects (points) and what parameter(s) they affect in the mixer channel strip.

- ▶ **Click and drag any of the points in the window to change the frequency (and gain for the EQ points) value(s).** Dragging sideways changes the frequency value and dragging vertically changes the gain (of the EQ points). As you edit the points, the corresponding channel strip parameter(s) are updated in real-time - and vice versa. The white line in the window shows the resulting EQ (and Filter, if activated) curve.
- ▪ **Hold down [Shift] and drag to constrain the movement to vertical and/or horizontal.** This allows you to change either frequency or gain without affecting the other.
- ▶ **[Ctrl]-click (Win) or [Cmd]-click (Mac) on an EQ point to reset its Gain value to 0dB.**
- ▪ **When you hover over a point, its current values are displayed numerically in the Frequency, Gain and Q fields below the graph. The parameter's (or section's) name is also displayed at the bottom left in the window:** (The point remains selected until you touch another point with the mouse or click on the window background.)



The HMF EQ point is selected and highlighted in the window.

- ! **Note that the Analyzer always shows the audio frequencies before the Fader section. This means that any Filter and/or EQ changes you make will affect the displayed frequency content. Also, if you use any Insert FX, these could also affect the frequency content.**
- ▶ **Hold down [Alt](Win)/[Option](Mac) and drag an EQ point vertically to change its Q-value.** This is only valid for the HMF and LMF EQ points, since these are the only ones that have a Q parameter.
- ▶ **It is possible to record parameter automation in the sequencer by dragging the points around in the Spectrum EQ Window during recording. Just make sure you have created a sequencer track for the channel you want to automate. See "Parameter automation recording procedure" for more details.**

Insert FX section



The channel strip Insert FX section allows you to add effect devices to be used as Insert Effects in the channel strip. You add Insert effect devices to the Audio Track or Mix Channel device in the rack. Insert effects process the whole channel signal, as opposed to Send effects where the effect is shared among all channels and the balance is individually adjustable for each channel. Typical insert effects are compression, distortion and modulation effects such as chorus.

The Insert effects can be placed ahead of the Dynamics and EQ sections in the signal path, see "Signal Path section".

- **See "Insert FX" for descriptions of how to create and work with Insert effects.**

The Insert FX section in the channel strip contains the following parameters:

Parameter	Description
Bypass	Bypasses the Insert effect(s).
Edit Inserts	This will bring the channel's rack device into view with its Insert FX container opened, allowing you to edit the effect devices.

FX Sends section



Send effects, which are global for all channels in the Main Mixer, are connected to the Master Section rack device. Up to 8 Send effects can be used simultaneously. For a description of how to use Send effects, see "Send FX".

The FX Sends section contains the following parameters:

Parameter	Description
FX Send On 1-8	Activates the Send for the channel.
Level 1-8	The Send Level knobs control the amount of channel signal that is to be sent to the effect connected to the corresponding Send.
PRE button	Send channel output is normally taken post channel fader, so that changing the channel's volume also changes the send level. By activating the PRE button, the send output is taken pre channel fader. In this mode, the send level is independent of the channel fader.

Fader section



The Fader section is used for controlling the level of the channel and its stereo placement in the mix. The section has the following parameters:

Parameter	Description
Pan L/R	Use this control to set the left/right position of the channel in the stereo field. [Ctrl]-click (Win) or [Cmd]-click (Mac) the Pan knob to reset to the default "0" (center position). The pan law is "-3dB compensated", with "compensated" meaning that the signal becomes +3dB louder when it's panned hard left/right compared to when it's completely centered.
Width	Width will only be available on stereo channels. It allows you to control the width of the stereo field for the channel. Normally this is fully on (value 127) which represents full stereo. By decreasing this value the stereo width is narrowed. Turned fully off the channel output will be in mono.
MUTE/SOLO buttons	**! Note that the Mute and Solo functions in the Main Mixer are NOT the same as Mute and Solo of sequencer tracks (see "Muting tracks" and "Soloing tracks").** Clicking a channel's Mute button silences the output of that channel. Click the button again to unmute the channel. Clicking a channel's Solo button silences all other mixer channels, so that you only hear the soloed channel. Several channels can be soloed at the same time, but if this is the case, note that soloed channels can't be muted with the Mute button. To mute one of several channels in solo mode you simply "un-solo" it. There are also Mute All Off/Solo All Off buttons in the Master Section - see "Master Section Header". If you are using Output Busses (see "Output Busses") and/or Parallel Channels (see "Parallel Channels"), the Solo and Mute functions affect the other concerned channels in an intelligent way, see "Solo, Mute and Send FX logic".
Channel Fader	The channel fader is used to control the output level of each channel. By adjusting the faders, you can set the desired mix (balance) between channels. If a channel is an Output Bus (see "Output Busses"), the Fader section background is colored and the Fader knob is red.
Channel Meter	The meter is a graphical representation of the channel output level. Stereo channels have two level bars and mono channels have one. If the signal level pushes the meter into the red, to avoid distortion try lowering either the output level of the device connected to the channel device or the channel fader itself. The meter is a VU meter, taking into account any VU offset set in the Big Meter of the Reason Hardware Device - see "The Big Meter".
Output Bus Selector	Here you can route the channel to an Output Bus (sub-mixer) instead of to the default Master Section, see "Output Busses".


About Level/Pan CV

On the back of the Programmer section of a Mix Channel or Audio Track device you will find CV inputs for the channel Level and Pan controls. These allow for automatic level and pan control from sources that output CV signals.

▶ **Press [Tab] to flip the Rack around, then click the "Show Programmer" button to access the CV jacks.**

Changing Fader section parameters on multiple channels simultaneously

In the Fader section you can change parameter values in a "ganged" or "linked" fashion on several selected Mix Channels. You can change the Mute, Solo and Level fader parameters this way. The example below shows seven selected channels, where the Level is reduced on the KorgBass channel and the rest of the channels' Faders follow along (with the same amount of level change in dB for each channel):



▪ **If you don't release the mouse button you can change the level back and the other channel faders will follow along as expected.**

! **If you lower the level to minimum (or raise to max) so that all faders reach their end values, and then release the mouse button, changing the level again will move all faders together equally.**

Channel Header section

The Channel Header is always visible at the bottom of the channel strip. It contains the following items:

The Edit Focus indicator - When you select a channel, the horizontal strip at the top of the Channel Header lights up red to indicate Edit Focus. The channel most recently clicked will have edit focus, regardless of how many channels are selected. When using [Ctrl](Win)-click or [Cmd](Mac)-click to deselect previously selected channels, edit focus will be on the most recently deselected channel.

Edit Focus also reflects the last selected track or Mix device, which is useful when moving between work areas because the channel with Edit Focus will always be in view in the Main Mixer. For example, if you select an ID8 track in the sequencer, the Mix channel to which it is connected will be scrolled into view in the Mixer, and will be given Edit Focus.



The top strip is lit to indicate Edit Focus.

- **When you are using the Spectrum EQ Window, and the "Follow Selection" box is ticked, the channel with Edit Focus is displayed in the window, see "The Spectrum EQ Window".**

The Remote Base Channel indicator - To the left in the same horizontal strip area a small yellow arrow symbol can be shown. This is the Remote Base Channel indicator, which shows which channel is considered the first or base channel when using Remote Control - see "Setting the Remote Base Channel".



The Remote Base indicator.

The RACK and SEQ buttons allow you to switch to a channel's rack device or sequencer track directly from the mixer - see "Switching between channels, rack devices and tracks".

The Channel Header area reflects the selected Track Color (see "Coloring mixer channels").

You can rename the channel by double-clicking on the name (see "Naming mixer channels").

Note that the Channel Header is a little shorter if the channel is a Parallel Channel (see "Parallel Channels").

The Master Section strip



The Master Section is where all your audio track and mix channels are mixed down to the Master Out bus. The Master Section strip contains a bus compressor and Insert FX section, both of which process the master bus, as well as send/return master level and pan controls for the eight FX Sends. Any processing applied to the master bus affects all channels that are routed to the Master Section.

Master Compressor section




The Master Compressor is perfect for providing the final "fairy dust" to your mix. It can add punch and cohesion, and generally make the mix sound bigger and more powerful. The compressor is very straightforward in operation and features make-up gain as well as program-adaptive Release.

The Master Compressor can be applied pre or post Master Insert section - see "Master Inserts section".

The parameters are as follows:

Parameter	Description	Range
On button	Activates/deactivates the Master Compressor.	
Meter	The meter shows the amount of gain reduction in dB.	0dB - 20dB
Threshold	This sets the level at which onset of compression occurs. The lower the Threshold, the more compression will be applied.	-30dB to 0dB
Ratio	Ratio specifies the amount of gain reduction applied to signal levels above the set threshold. A 2:1 compression ratio effectively means that a signal level 2dB above threshold will have a signal gain of 1dB.	Fixed Ratios: 2:1 / 4:1 / 10:1
Attack	This governs how quickly the Master Compressor will react when signals rise above the set threshold.	Fixed settings (in ms): 0.1 / 0.3 / 1 / 3 / 10 / 30
Release	When the signal level drops below the set threshold, this determines how long it takes before the compressor lets the sound through unaffected. If set to "Auto", the Release time will be program adaptive, so the Release time is automatically increased following long peaks and decreased following short peaks.	Fixed settings (in s): 0.1 / 0.3 / 0.6 / 1.2 /Auto
Make-Up	Make-Up gain compensates for level reduction caused by compression and helps maintain a steady output level.	-5dB to 15dB
KEY button/External Side Chain	When a cable is connected to the Sidechain inputs on the back of the Master Section device, the KEY button is activated automatically and the Master Compressor will now be triggered by the external signal instead of the master bus signal. When a sidechain source is connected you can turn the KEY button off to monitor the sidechain signal. See "Using compression sidechaining" for a description of how sidechaining can be used.	

FX Send section



This section controls the master levels of the FX Sends. Send effect devices are connected to the Master Section via the eight FX Send and eight FX Return connectors on the back of the rack device.

See "Send FX" for a description of how to set up an use Send FX.

The Send bus can be monitored via the Control Room output - see "Control Room output section".

The section contains the following items:

Parameter	Description
Level 1 - 8	Adjusts the FX Send master level. The master send levels are normally left at default 0dB. if you wish to increase/decrease the effect balance, this is best done by increasing/decreasing the send levels for the individual channels using the effect.
Meter	Shows the signal level of the send bus.
EDIT button	This brings the connected effect device in the rack into view for easy editing of its parameters.
Name label	This automatically shows the name of the connected effect device. If you enter a new name for the label, this overrides the automatic naming. Deleting a manually entered name will bring back the automatic naming.

Master Inserts section



The Master Inserts Section is identical to the Insert FX section in the channel strips, except that it affects the master bus, i.e. the whole mix. Master Insert effects are ideally used to apply mastering effects, such as compression and limiting/maximizing for finalizing the mix.

Master Insert effect devices are added to the Master Section device in the rack.

The Master Insert effects can be placed ahead of the Master Compressor in the signal path. By default, the Master Insert effects are placed after the Master Compressor in the signal path. This makes sense, as you usually add a Maximizer or Mastering Combinator as a Master Insert effect, and this must be last in the signal path to avoid clipping on the output. However, if necessary, you can place the Master Insert effects before the Master Compressor, by activating the "Inserts Pre Compressor" button.

- **See "Insert FX" for descriptions of how to create and work with Insert effects.**

The Inserts section in the Master Section contains the following parameters:

Parameter	Description
Bypass	Bypasses the loaded Insert effect(s).
Edit Inserts	This will bring the Master Section device into view in the rack, with its Insert FX container opened, allowing you to edit the effect devices.
Signal Path button	If activated, the "Inserts Pre Compressor" button will place the Inserts before the Master Compressor in the signal chain. If the Master Insert effects contain a maximizer or limiter, the inserts should normally be last (this button should be left in the off position).

FX Return section



This section controls the master levels of the FX Returns. Send effect devices are connected to the Master Section via the eight FX Send and eight FX Return connectors on the Master Section device. See "Send FX" for a description of Send FX.



Send/Return connectors on the Master Section device.

You can monitor the Return bus via the Control Room output - see "Control Room output section".

The section contains the following items:

Parameter	Description
Level	Adjusts the FX Return master level. The master return levels are normally left at the default value, 0dB. If you wish to increase/decrease the effect balance, this is best done by increasing/decreasing the send levels for the individual channels using the effect. You can, however, use the FX Return level to change the overall balance of a send effect in the mix.
Pan	Pan adjusts the return signal stereo balance.
Meter	Shows the signal level of the return bus.
EDIT button	This brings the connected effect device in the rack into view for easy editing of its parameters.
Mute (M)	This mutes the return signal for the send effect.
Name label	This automatically shows the name of the last effect device in the send signal path. If you enter a new name for the label, this overrides the automatic naming. Deleting a manually entered name will bring back the automatic naming.

Master Fader section



The Master Fader controls the final output level of the mix to be recorded or exported to a file. It should normally be set to 0dB. The Master Fader should never be used to adjust the monitoring level - this is what the Control Room bus is for (see below).

The section contains the following items:

Parameter	Description
Master Fader	Adjusts the level of the Master Out bus.
Meter	Shows the level of the Master Out bus.
Mode	The Mode button switches the meter between VU/Peak/PPM modes - see "The Big Meter".
Reset	This resets the meter, deleting any registered peaks.

Spectrum EQ (Spectrum Analyzer) Window button



Below the Meter is a button for bringing up the Spectrum EQ Window. Since there are no Filter or EQ sections in the Master Section, the Spectrum EQ Window is used only for displaying the frequency content of the Master Section.

Control Room output section

The Control Room outputs are located on the back of the Master Section device. To use the Control Room output section, the outputs have to be connected to your monitor system. This can be done by manually patching cables from the "Ctrl Room Out" connectors to a separate output pair on the Reason Hardware Device - see "Manual audio routing".



The Control Room outputs, which are separate from the Master Out bus, are the outputs that you should monitor (listen) from. This allows you to monitor the main mix and to adjust your monitoring level without affecting the Master Out bus. You can also monitor the FX Send or Return buses in this section.

The section contains the following items:

Parameter	Description
Monitor display/selector for Master/FX Send 1-8/FX Return 1-8	Click the display to bring up a list where you can select what to monitor on the Ctrl Room Out jacks. You can select between Master, FX Send 1-8 and FX Return 1-8. One bus can be monitored at a time.
Control Room Out Level	Adjusts the level of the Control Room Out bus.

Delay Comp

- **Click the Delay Comp button (or display) to activate delay compensation in the Main Mixer.**
  The total delay of the Main Mixer signal (at the Master Out) is displayed below the display. See the "Delay Compensation" chapter for more information about delay compensation in Reason.

Master Section Header



The Header is always visible at the bottom of the Master Section. It contains the following items:

Parameter	Description
SEQ / RACK buttons	The RACK and SEQ buttons allow you to switch to the Master Section rack device or automation track directly from the mixer - see "Switching between channels, rack devices and tracks".
Mute/Solo All Off	This allows you to switch off all channel Mute or Solo buttons in one go.
DIM -20dB	This simply dims the Master Out level -20dB. Use this to temporarily lower the output level when answering the phone, etc.

Automating mixer parameters

Automating mixer parameters works in the same way as for other parameters. Automation is part of the audio track or Mix channel track. See "Recording parameter automation".

- **A quick way to automate a parameter is to right-click (Win) or [Ctrl]-click (Mac) on the parameter and select "Edit Automation" from the context menu.**
  This will create an automation lane (and track if needed) where you can record or draw automation.

- **When you select a sequencer track, the "Record Enable Parameter Automation" button is automatically enabled, allowing for parameter automation to be recorded. However, when recording automation for Audio Track channel strip parameters, you may want to disable the regular Record Enable button to avoid recording audio by mistake.**

Working with effects

Insert FX

By definition, insert effects are inserted in the signal chain and process the whole channel signal, as opposed to Send effects (see "Send FX") where the effect is shared among all channels and the balance is individually adjustable for each channel. Typical insert effects are dynamics, distortion, chorus etc., plus mastering effects for the Master Section.

As mentioned earlier in this chapter, the channel strips and Master Section strip have a "slot" dedicated to insert effects - the Insert FX section. In the Insert FX section, you can create effect devices and use as insert effects.

▶ **A very flexible way of using Insert FX is to have the effects in separate mixer channels and utilize parallel processing, see "Parallel Channels".**

Adding Insert effects

▶ **An easy way to add insert effects is to use the Track Panel, see "Adding devices on the Track Panel".**

To add an insert effect in the Rack, proceed as follows:

1. **Select a channel strip in the Main Mixer, a Mix Channel or Audio Track device in the rack, or an audio track or Mix Channel track in the sequencer.**
2. **Select the desired effect device from the Create menu or from the context menu.**
   The effect device is created and automatically routed in the Insert FX container in the channel's rack device.



A Scream 4 device created as Insert FX in an Audio Track device.

3. **If you need to re-route any connections, press [Tab] to flip the rack around.**



The "To Device" and "From Device" connections in the Insert FX slot in the Audio Track device.

! **Note that the Mix Channel/Audio Track device must be unfolded to show the connections.**

▶ **If desired, re-route the connections according to the standard routing procedures (see "Manual routing").**
The signals always travel from the "To Devices" outputs, via the desired effect devices, to the "From Devices" inputs on the Mix Channel/Audio Track device.


- **When the Show Insert FX button is on, you can add devices directly in the insert FX container area, drag devices in or out, etc. - just like with a Combinator (see "The Combinator").**

! **Note that if you add, load or route insert effects in stereo, and the Mix Channel/Audio Track device (and channel strip) is in mono, the channel will automatically switch to stereo.**

Using Effect Combi patches as insert effects

It's possible to load Effect Combi patches as Insert FX as well. First you either need to create a Combinator device in the Insert FX container of the channel - or drag an Effect Combi patch from the Browser and drop in the Insert FX container.

You could also add several Combinators/Effect Combi patches to the same Insert FX container, e.g. by dragging and dropping. This makes it possible to have multiple Combinators in series, for even more complex effects processing:



Three Effects Combinators serially connected in the Insert FX container.

Bypassing Insert effects

▶ **Click the "Bypass" button at the top of the Insert FX section on the channel strip, or on the device in the rack, to bypass the insert effects for the channel.**



The "Bypass" buttons on the channel strip and on the device.

Deleting Insert effects

Deletion of insert effects can be done either in the rack or with a mixer channel selected in the Main Mixer:

1. **Select a Mix Channel or Audio Track device in the rack or a mixer channel in the Main Mixer.**
2. **Select "Clear Insert FX" from the Edit menu or context menu.**
   This will disconnect and delete all Insert FX devices of the selected channel. The deleted devices will be replaced by an internal straight-through connection.

Another way of deleting Insert FX is by manually removing them from the Insert FX container in the Mix Channel or Audio Track device in the rack:

1. **Unfold the Mix Channel/Audio Track device and click the "Show Insert FX" button.**
2. **In the Insert FX container, select the device(s) you want to remove.**
3. **Press [Backspace] or [Delete], or select "Delete Devices and Tracks" from the Edit or context menu.**
   An alert appears asking you to confirm the deletion. (See "Deleting devices" for more details).

Copying and Pasting Insert effects between mixer channels

To copy the insert effect(s) from one mixer channel and paste to another mixer channel, proceed as follows:


1. **Select the mixer channel which contains the Insert effect(s) you want to copy.**
2. **Select "Copy Channel Settings" from the Edit or context menu and then select "Insert FX" from the sub-menu.**
   If you select the Master Section, the "Copy Insert FX" item will appear directly on the Edit menu or context menu.
3. **Select the mixer channel to which you want to paste the Insert effects and choose "Paste Channel Settings: Insert FX" from the Edit menu or context menu.**
   If you select the Master Section, the "Paste Insert FX" item will appear directly on the Edit menu or context menu.

Send FX

Send effects are routed in parallel with the signal chain, and the effect balance can be adjusted - as opposed to Insert effects, which are inserted in the signal chain and process the whole channel signal (see "Insert FX"). Typical Send effects include reverbs and delays.

The Main Mixer can hold up to eight separate Send effects per Song. These eight Send effects can be used simultaneously by any or all mixer channels in the Song, at individually adjustable levels per mixer channel. The main Send FX controls, which include the FX Send and FX Return sub-sections, are located in the Master Section strip in the mixer. In these sections, you can control the FX Send and FX Return levels to and from all mixer channels, as well as panning for each of the Send effects.

In addition to the "global" Send FX controls in the Master Section, each mixer channel features a Send FX section, where you can control the levels to each of the Send effects for the specific mixer channel.



Creating Send effects


▶ **An easy way to add Send Effects is to use the Track Panel, see "Using Send Effects on the Track Panel".**

Send effects can also be added as follows:

1. **In the Main Mixer, select a channel strip or the Master Section strip.**
2. **Select "Create Send FX..." from the context menu.**
   The Browser appears (if it was hidden) and the Send FX section gets browse focus. Now, you can now browse for and load effect devices. You can also browse for Effects patches and load these into their corresponding devices, e.g. Effect Combinators.


! **If all eight Send effect busses are already in use, the "Create Send FX..." item on the context menu is grayed out.**

- **Each FX Send and FX Return in the Master Section strip has a display that shows the name of the last effect in that send's signal path:**



The names of three added Send effects are displayed in the Master Section strip.

3. **If you need to re-route any connections, press [Tab] to flip the rack around.**



The Send FX connections on the Master Section device.


! **Note that the Master Section device must be unfolded to show the connections.**

As you can see, all Send effects are placed outside the Master Section device - as opposed to Insert effects, which are placed in the Insert FX container of the Master Section device.

- **It's also possible to manually connect devices to the FX Send and FX Return connectors according to the standard routing procedures (see "Manual routing").**
The signals always travel from the "FX Send" outputs, via the desired effect device(s), to the "FX Return" inputs on the Master Section device.

Editing and saving Send effects

▶ **Click the "Edit" buttons in the FX Send or FX Return sections to get to the corresponding Send effect device(s) in the rack.**




The Edit buttons for the Send effects in the FX Send and FX Return sections.

The corresponding Send effect devices are scrolled into view in the rack.

▪ **Send effects can be edited from their device panels according to standard editing procedures.**
Any edits you make will be automatically stored when you save the Song document. If you edit Effect Combi patches, these can also be saved separately as Combinator patches as usual.

Muting Send effects

▶ **Click one of the "M" buttons in the FX Return section to mute the FX Return for the corresponding Send effect.**
All channels that currently use the muted send effect will be affected.



The Mute buttons for the Send effects in the FX Return section.

! **The Mute buttons only mute the FX Return signals. If you should choose to route an FX Send output of the Master Section device to an effect, and then route the effect to a regular Mix Channel instead of an FX Return input, the Mute button will of course not have any effect.**

Deleting Send effects

Deletion of Send effects is done in the rack according to the standard device deletion procedures:

▶ **Select the device(s) you want to delete and press [Backspace] or [Delete] - or select "Delete Devices and Tracks" from the Edit or context menu.**
An alert appears asking you to confirm the deletion. (See "Deleting devices" for more details).

▪ **When a Send effect has been deleted, the name will automatically be removed from the displays in the FX Send and FX Return sections in the Master Section strip.**

Output Busses


Output Busses allow you to create sub-mixers. Sub-mixers can be very useful for pre-mixing a multi-mic'ed drum kit, or a horn section, for example. You can also use a sub-mixer configuration to route several external input signals (from separate microphones, for example) for recording onto a single audio track (see "Recording a sub-mix onto an audio track"). You can have as many mix busses as you like in a Reason song.

▶ **For multiple levels of sub-mixing, it's also possible to create an Output Bus that is fed by an existing Output Bus.**

Creating an Output Bus


The fastest and easiest way of creating an Output Bus for several mixer channels is this:

1. **Select all mixer channel strips that you want to route to the same Output Bus.**
2. **Press [Ctrl]+[G](Win) or [Cmd]+[G](Mac) - or select "Route to > New Output Bus" from the Edit menu or context menu of one of the selected channels.**



A new Output Bus channel, named "Bus 1", is created to the right and the selected channels are automatically routed to it as indicated on the channels' Output labels.


The step-by-step instructions below show how you can assign individual channels to an Output Bus - one channel at a time. The picture shows a number of Audio Tracks in a song with individual recordings of the drums of a drum kit:



Audio Tracks with separate drum recordings routed to the Master Section.


Now, we want to create a sub-mixer which mixes only the individual drum channels. The advantage of doing this is that we can then control the sound and volume of the entire drum kit using only one single Mix Channel:

1. **Click the Output selector (or the gray name tag) on the Kick channel and select "New Output Bus".**




▶ **Alternatively, select the Kick channel strip and press [Ctrl]+[G](Win) or [Cmd]+[G](Mac).**
A new Mix Channel is created in the Main Mixer and its corresponding Mix Channel device is created in the Rack. The Kick channel is now routed to the new Mix Channel via the internal P-Lan network.

The Output selector area on the Kick channel is colored and the name "Bus 1" is displayed to indicate the name of the Output Bus it is routed to:




The Fader section of the new Output Bus channel gets a colored background and a red Fader knob to indicate it is an Output Bus.

2. **Click the Output selector on the Snare channel and select "Bus 1".**



The Output selector area on the Snare channel is now colored in the same color as the Bus 1 channel and the Output Bus name is displayed:



3. **Repeat the procedure for the remaining drum channels in the Main Mixer.**

4. **If you like you could now rename the Output Bus channel, e.g. to Drum Mix, and drag the channel strip to the right of the individual drum channels for better overview:**



The changed Output Bus name is automatically displayed in the colored Output area on all channels routed to that Output Bus channel.

If you look in the rack, you can see that the Audio Output display on the Audio Track devices for the individual drum channel now show “Drum Mix” instead of the default “Master Section”.



Output Bus destinations on the Audio Track devices in the rack (front and rear).

When an Output Bus is created with the “New Output Bus” function, it automatically gets an automation track in the sequencer. Selecting this track will show the bus channel in the Track Panel, making it easy to add insert effects to the bus.

Rerouting channels

- ▶ **If you like you can change the Audio Output destinations - or create new Output Busses - by clicking the Audio Output selector on the device front panel, or in the Audio Output display on the rear panel, or in the Output selector area on the channel strip in the mixer.**

- ! **If you manually deassign all channels from the Drum Mix Output Bus channel, the Output Bus channel automatically becomes a regular Mix Channel. If you want to assign channels to this Mix Channel, and thus make it become an Output Bus channel again, click the Audio Output selector on the front panel, or in the Audio Output display on the rear panel, and select “All Channels > Drum Mix”. These routings can also be made in the Output selector area on the channel strip in the mixer.**


Deleting an Output Bus

- ▶ **To delete an Output Bus channel, select the Output Bus channel strip in the Main Mixer - or the device in the rack - and press [Delete] or [Backspace].**
  When you delete an Output Bus channel which has other mixer channels already routed to it, the source channels will be automatically re-routed to the default Master Section again via P-Lan.

  On the Mix Channel/Audio Track devices in the rack, “Master Section” is now shown in the Audio Output displays to indicate that the channels have been re-routed to the Master Section device.


Recording a sub-mix onto an audio track

The example below shows an Output Bus (sub-mixer) configuration with four microphones connected to one input each on the audio interface and then routed from the Reason Hardware Interface to the Direct Inputs on four Mix Channel devices. The four Mix Channel devices are routed to the "Drums SubMix" Output Bus for sub-mixing:



Direct routing of individual Audio Inputs to Mix Channels which, in turn, are routed to an Output Bus for sub-mixing.

- **To record the sub-mixed signals from the "Drums SubMix" Mix Channel onto Audio Track 1, click the Rec Source button on the "Drums SubMix" Mix Channel device, and then select "Stereo Input" and "Drums SubMix" as Audio Input source on the "Audio Track 1" device:**



The Rec Source button on the Drums SubMix device activated and "Drums SubMix" selected as Audio Input on the Audio Track 1 device.

See "Recording audio from Mix Channel outputs" for more details.

- **In the sub-mixer setups above, each source Mix Channel could also house individual Insert FX. See "Creating an input channel for recording with effects" for tips on how to record with FX.**

Parallel Channels


A very flexible way of working with insert effects is to use parallel channels that host the effects, while keeping the dry signal of the source channel intact. This way you can freely control the levels of the dry signal and the separate effects - and also control the sound of each effect individually from each of the parallel channels.

You could, for example, have one parallel channel with a compressed distortion effect, another parallel channel with a Delay, and so on. Then, you can freely EQ the effects in each of the parallel channels, as well as control their levels individually from each Fader.

Creating Parallel Channels

Parallel channels can be created as follows:

1. **Select the source Mix/Audio Track channel strip in the Main Mixer, or its device in the rack.**




2. **Select "Create Parallel Channel" from the Edit menu or context menu.**
   A new Mix Channel is created and placed to the right of your original channel in the Main Mixer:



A Parallel Channel created for Audio Track 1.


The parallel Mix Channel is automatically named "P1: <source channel name>" and its channel header is colored according to the source mixer channel header. Both the source channel and the parallel channel also get shorter channel headers to indicate they are routed in a parallel configuration.

▶ **If you want to add more parallel channels to your source channel, select the last created parallel channel and select "Create Parallel Channel" from the Edit menu or context menu.**
This adds another parallel channel to your source channel:



Another Parallel Channel created for Audio Track 1.

In the rack, the Parallel out jack(s) of the source Mix Channel/Audio Track device are automatically connected to the Direct Input jack(s) of the first parallel Mix Channel. The second parallel Mix Channel is then connected to the first parallel Mix Channel, and so on:



Parallel Channels 1 and 2 for the Audio Track 1 source channel in the rack.

! **Since the Audio Track/Mix Channel device only has one pair of Parallel out jacks, any additional parallel channels have to be created from the last created parallel channel.**

If your original channel is in mono, only the left parallel output is connected to the left input of the parallel channel.


3. **Now, you can create Insert FX in each of the parallel channels and process the signal of your source channel separately, in parallel.**

▶ **It might also be a good idea to create a separate Output Bus for the source channel and all parallel channels, see "Creating an Output Bus".**

Creating a Parallel Output Bus


Parallel channels can also be created for Output Bus channels, for parallel processing of the entire Bus signal. The following example shows a drum kit, with a channel for each drum, that we want to assign to an Output Bus and apply parallel compression to:

1. **[Shift]-select all drum channels in the mixer.**
2. **Press [Ctrl]+[G](Win) or [Cmd]+[G](Mac) to create a new Output Bus to automatically route the drum channels to.**



A new Output Bus channel, named "Bus 1", is created to the right and the selected channels are automatically routed to it as indicated on the channels' Output labels.

3. **Select the "Bus 1" channel in the mixer and select "Create Parallel Channel" from the Edit menu or context menu.**



A parallel channel, the "P1 : Bus 1" is created and the "Bus 1" Output Bus channel is automatically connected to it.

4. **Activate the Compressor in the "P1: Bus 1" parallel channel and raise the Compression Ratio up high.**



5. **Raise the Level fader on the "P1: Bus 1" channel to gradually introduce the heavily compressed sound (in parallel with the dry signal of the "Bus 1" channel).**

Deleting Parallel Channels

- **To delete a Parallel Channel, select its mixer channel strip - or its device in the rack - and press [Delete] or [Backspace].**
  Confirm the deletion in the alert that appears.

Naming Parallel Channels

When you create a Parallel Channel it is automatically named after its source channel according to: "P1: <source channel name>", where "P" stands for Parallel and "1" for the first parallel channel. If you add on more parallel channels, the following channels are named "P2: <source channel name>" and so on.

If you change the name of the source channel, all the parallel channel are automatically renamed accordingly. You can then manually rename each parallel channel afterwards if you like.

- **To revert to the automatically generated name, double-click the parallel channel's name, press [Delete] or [Backspace] and then [Enter].**

Solo, Mute and Send FX logic

The Solo, Mute and Send FX functions in the channel strips are very straight-forward when you work with mixer channels that are routed straight to the Master Section. However, when you are using Output Busses for sub-mixing and/or Parallel Channels for parallel processing, the Solo, Mute and Send FX functions need to work intelligently to provide the desired result. This has been carefully taken care of in the Main Mixer in Reason.

Solo and Mute logic

The Solo and Mute functions are designed to work intelligently in the following special scenarios:

- **When several mixer channels are routed to an Output Bus.**
- **When a mixer channel has one or more Parallel Channels.**
- **When Output Busses are routed to other Output Busses.**
- **When Output Busses have Parallel Channels.**

Solo and Mute examples

There are two ways a mixer channel can be soloed or muted:

- **Manually, by clicking the corresponding Solo or Mute buttons.**
  In these situations, the buttons light up in green (Solo) or red (Mute).
- **Automatically, according to the state(s) of the other mixer channels.**
  This happens when another mixer channel is affected by a manual Solo/Mute in another mixer channel. Automatically soloed/muted buttons light up in dimmed green (Solo) or dimmed red (Mute) color.


The examples in the figure below show how Solo and Mute work in different mixer channel configurations:



The Snare channel has been manually soloed.

Since the Snare channel is routed to the Drums SubMix Output Bus, the Drums SubMix bus is automatically soloed to let the Snare signal through to the Master Section.

All other mixer channels are automatically muted.




The Snare channel has been manually soloed.

Since the Snare channel is routed to the Drums Clean Output Bus, the Drums Clean Output Bus is automatically soloed to let the Snare signal through.


The Drums Clean Output Bus is routed to the Drums SubMix Output Bus. The Drums Clean channel also has a parallel channel; the Drums Dist, which is also routed to the Drums SubMix Output Bus.

This means that the Drums Clean, Drums Dist and Drums SubMix channels are automatically soloed to let the Snare signal through to the Master Section.

All other mixer channels are automatically muted.




Now, if we manually mute the Drums Clean Output Bus channel from the previous example, its automatic solo is disabled, allowing you to hear the sound of the Drums Dist bus only.



If we start from scratch again and click the Solo button in the Drums SubMix channel, all channels routed to the Drums SubMix Output Bus are automatically soloed.

All other mixer channels are automatically muted.

Below is another example of the Solo and Mute logic:



The Drums Dist parallel channel is manually soloed.

Its output bus, the Drums SubMix, is automatically soloed, as are the Kick, Snare and Overhead channels that are routed to the Drums Dist channel via the parallel connection from the Drums Clean channel.

The Drums Clean channel is automatically muted, as are the other remaining channels in the mixer.

Send FX level and mute logic

If you are using Send FX in your mixer channels, these need to behave intelligently when you are using Output Bus channels and/or Parallel Channels.

Send FX level examples

Since the eight Send FX busses in the Main Mixer are shared between all mixer channels, including Output Bus channels, there has to be a way to compensate the Send FX levels for changes in Output Bus levels. Therefore:


- **If a channel is routed to an Output Bus, its Send FX levels will follow the Output Bus level.**
  One example would be if you have a number of drum channels routed to a "Drums" Output Bus, and add a reverb to the Snare channel using an FX Send. Now, if you raise or lower the Drums Output Bus level fader, the individual Snare reverb Send level will automatically adjust, so that the effect balance is maintained.

! **Note that the automatic Send FX level adjustment is disabled if the Send FX PRE button is on.**

! **Note that the individual FX Send level knobs will not move to reflect the automatic level compensations.**


Send FX mute examples

The example in the figure below shows how the Send FX behave when an Output Bus channel is muted:




The Send FX outputs of all channels that are routed to the Drums SubMix Output Bus are automatically muted if you manually mute the Drums SubMix Output Bus channel.

The examples in the figure below show how the Send FX behave when you mute a Parallel Channel as well as a Parallel Channel plus an Output Bus:



The Drums Clean Output Bus is manually muted.

Since the Drums Clean output bus is connected to an un-muted Parallel Channel, the Drums Dist channel, the Send FX outputs of the Kick, Snare and Overhead channels are not muted. However, if you should manually mute the Drums Dist channel, the Send FX outputs of the Kick, Snare and Overhead channels should be automatically muted.



Now, if you also manually mute the Drums SubMix Output Bus, the Send FX outputs of all channels that eventually end up in the Drums SubMix Output Bus will be automatically muted.

Remote controlling the Main Mixer

There are two ways of Remote controlling the Main Mixer: one channel at a time, for detailed control of the parameters of one mixer channel at a time, or multiple channels simultaneously, for balancing levels etc.

Remote controlling a single mixer channel

You can control a single mixer channel, either by locking your control surface to the mixer channel, or by setting Master Keyboard Input to the mixer channel's track in the sequencer.

For example, if you set Master Keyboard Input to the audio track you're recording on, you will be able to adjust the monitor level and other parameters of the channels you're using when recording.

The extensive Remote control functionality in Reason allows for detailed control of the parameters of one mixer channel at a time.

Remote controlling multiple mixer channels

The typical way of remote controlling the Main Mixer is to control the Master Section (by setting Master Keyboard Input to the Master Section track in the track list, or typically by locking your control surface). This lets you control the Master Section parameters plus mixer parameters for a number of channels (often 8 channels at a time, depending on the control surface). To define what channels to remote control at a given time, you need to set the "Remote Base Channel".

Setting the Remote Base Channel

The first (leftmost) mixer channel controlled by Remote is called the "Remote Base Channel". The current Remote Base Channel is indicated by a yellow arrow symbol in the mixer channel strip Header section:



The Remote Base Channel indicator.

To change the Remote Base Channel, proceed as follows:

- **Select a mixer channel and select "Set Remote Base Channel" from the Edit menu or context menu.**
  The Remote Base Channel indicator will move to the selected mixer channel.
- **Alternatively, change Remote Base Channel via Remote (in steps of 1 or 8 channels).**
  Functions for changing the Remote Base Channel may already be mapped to buttons on your control surface - see the "Control Surface Details" pdf document. If not, you can set this up manually in the Additional Remote Overrides dialog on the Options menu - see "Additional Remote Overrides...".

Remote controlling multiple mixer channels - an example

If you want to remote control several channel strips at once from your control surface, you can proceed as follows:


- **Select the Master Section device in the rack or the Master Section Strip in the Main Mixer.**
  If you want to lock your control surface to the Master Section, select "Lock Xxxxx to This Device" from the Edit menu or context menu. ("Xxxxx" represents the name of your connected control surface.) This way, you can ensure that your control surface will always control the Main Mixer, regardless of where the edit focus is.



Selecting and locking the Master Section to the connected control surface.


Depending on your connected control surface, it may now be possible to control parameters of several channel strips at the same time. In this example, we're using a control surface which has nine sliders. These sliders are configured to control one channel strip Level Fader each, plus the Master Section Level Fader.

In the picture below, the Remote Base Channel is currently set to Audio Track 1. This means we can control the Level Faders of Audio Track 1 through Audio Track 8, plus the Master Section Level Fader, with the nine sliders on the control surface:



Controlling Audio Track 1 through Audio Track 8 and Master Section from the connected control surface.

On our control surface it's possible to select next and previous Remote Base Channel in steps of 8 channels. If we click the "Next" button on our control surface, the Remote Base Channel is set to Audio Track 9 and we can now control Audio Track 9 through Audio Track 12, plus the Master Section:



Controlling Audio Track 9 through Audio Track 12 and Master Section from the connected control surface.

If your control surface doesn't have buttons already assigned for controlling Remote Base Channel selection, you can manually assign controllers for this by using the Remote Override function described in "Remote Override mapping". Alternatively, select a channel strip and select "Set Remote Base Channel" from the Edit menu or context menu.

See "Remote - Playing and Controlling Devices" for more details about remote controlling Reason. See also the "Control Surface Details" pdf document for information about parameter assignments on various common control surfaces.

Advanced routing tips and tricks

Chaining Send effects from Redrum or Mixer devices

The Redrum Drum Module and the Mixer 14:2 and 6:2 devices have separate Send FX connectors where you can add send effects individually for each device. The Redrum and Mixer devices also have separate Send FX level pots for each drum/mixer channel so that you could set the send effect levels individually for each drum/mixer channel in the device.

Let's say you want to add a Redrum device and use two of the Main Mixer's Send FX, but with individual settings for each of the Redrum device's internal channels. In the example below, we're going to chain the two Send Outs from the Redrum device to two send effects in the Main Mixer:

1. **Create two extra Mix Channel devices - one for each of the send effects we're going to chain.**
   In this example we name the Mix Channel devices "FX 1 Chaining" and FX 2 Chaining".
2. **Activate the Send FX bus you want to use in each of the mixer channels and also activate the corresponding Pre-fader button.**
   In this example, we activate the Send FX 1 bus on the FX1 Chaining channel and the Send FX 2 bus on the FX 2 Chaining channel. The Send FX 1 has a reverb connected and the Send FX 2 has a delay connected.


! **The PRE buttons should be activated because we don't want the mixer channel faders to affect the Send levels.**

3. **Lower the "FX 1 Chaining" and "FX 2 Chaining" mixer channel faders to zero.**
   This way, the effect signals won't be mixed with the rest of the Main Mixer channel signals in the mix bus, but are kept isolated in the Send FX busses. Now, our setup should look like this in the rack and in the Main Mixer:



The device setup, plus two new Mix Channel devices added. To the right, the channel strips with activated FX Send busses.

4. **Connect the Send Out 1 and 2 of the Redrum device to the Left inputs of each of the "FX 1 Chaining" and "FX 2 Chaining" Mix Channel devices.**
   Now, you should have a setup that looks something like this:



The Redrum Effect Sends chained to one Send FX bus each of the Master Section, via two new Mix Channel devices.

5. **Set individual Send levels for each of Redrum's internal channels.**



Now, you have individual send levels for each of the Redrum device's internal channels - and are still able to use the Send FXs in the rest of the Main Mixer channels like before.


Using compression sidechaining

Compression sidechaining is a feature which lets you control the Compressor, not from the internal channel signal, but from an external signal. A typical use case would be to let the signal from a kick drum channel control the compression of the bass channel. The result would be that the bass signal is compressed each time the kick drum signal is present on the sidechain input, allowing the kick sound to momentarily suppress the bass sound.

Compression sidechaining from an external channel

The example below shows an audio track with a kick sound that is tapped from the Kick Audio Track device's Parallel output and routed to the Dynamics Sidechain input of the Bass Audio Track device.

- **The Key button is automatically activated when you connect a signal to the Sidechain Input.**
  This will force the Compressor to be controlled from the Sidechain input signal rather than from the internal signal.



Compression Sidechaining of the Bass audio track from the Kick Drum audio track.

About compression sidechaining of several channels from one source channel

If you want to use compression sidechaining of several (destination) channels from a single source channel, there are some options of doing that:

- **If you are already using both Parallel outputs for sidechaining, tap an additional sidechain signal from one of the Insert FX "To Device" outputs of the source channel.**
  This is useful if you are not using both "To Device" outputs for insert effects in the source channel.
- **Use a "Spider Audio Merger & Splitter" device to split the sidechain signal from the Parallel outputs and/or Insert FX "To Device" output into several signals.**
  Each of these signals can then be individually routed to each Sidechain Input of the desired destination Audio Track/Mix Channel devices.
- **Create an Output Bus (sub-mixer) and route all (destination) channels you want to control to this Output Bus. Then, route the sidechain signal from the source channel device to the Sidechain Input of the Output Bus Mix Channel device.**
  See "Output Busses" for information.

About internal compression sidechaining

Another typical application for compression sidechaining is to use the internal signal of the channel, filter it, and then feed to the compressor via "internal" sidechaining. This type of internal sidechaining can be used for de-essing, for example. No additional patching is required for this; you only have to activate the "Filters to Dynamics Sidechain" button in the Filter or EQ sections. See "About the Filters To Dynamics Sidechain button".

Using the Mix Channel and Audio Track devices' Direct Outs

The Mix Channel and Audio Track devices feature Direct Out connectors. By patching cables into these outputs, you break the internal signal chain from the device to the Master Section, and can route the channel output signals directly to the Reason Hardware Device's outputs. This is a very nice feature if you want to use outboard mixing or summing, to route individual channel signals to another application.

The example below shows how to route the Direct Outs of a number of Audio Track devices to separate outputs of the Reason Hardware Interface:



Direct routing of individual channel outputs to individual outputs on the Reason Hardware Interface.

! **Using the Direct Outs will break the internal P-LAN routing to the Master Section device. This is indicated by the red dashes (---) in the Audio Output display on the Audio Track/Mix Channel devices.**

Creating an input channel for recording with effects

When you record on an audio track, the input signal is routed "dry" to the audio track. Then, when you play back the recorded audio, the signal goes via the channel strip, with all its settings and any Insert FX etc. However, there might be situations where you want to record a processed signal to the audio track. For example, if you record an electric guitar, you might want to record it with distortion effects or similar.

The example below shows a typical setup where a separate Mix Channel device is used for processing the input signal before it's routed to the audio track for recording:

1. **Begin by creating an Audio Track device and a separate Mix Channel device.**
   The Mix Channel device is going to be used for housing the effects we're going to record with.
2. **Create the effect(s) you want to use and patch them as Insert FX in the Mix Channel device.**
   In this example, we use a Scream 4 distortion device and an RV7000 reverb device connected in series.

3. **Connect one of the Audio Ins of the Reason Hardware Interface to the "Input L" of the Mix Channel device.**
   This manual patching from the Hardware Interface is made to route the input signal directly to the Mix Channel device, where we have our effects.



Direct routing of an Input signal from the Reason Hardware Device to the Mix Channel device.

4. **Flip the rack around to view the front.**

5. **Click the "Rec Source" button on the Mix Channel device.**
   This makes the Mix Channel device selectable as input source for the Audio Track device.



Rec Source enabled on the Mix Channel device.

6. **Finally, select the Mix Channel device as Input on the Audio Track in the sequencer (or in the Audio Input selector on the Audio Track device in the rack).**
   This will route the signal from the Mix Channel device's output directly to the input of the Audio Track.



The Mix Channel device selected as audio input on the Audio Track in the sequencer.

Now, you can begin recording on the Audio Track according to the standard recording procedures described in "General recording procedure". The signal will be processed by the Insert FX of the Mix Channel device before being recorded on the track.

With this setup, you will always hear the sound of the input processed through the Amp device - just as if you had a real hardware amp turned on and mic'ed in the studio. If you don't want the "Lead Gtr Rec Input" Mix channel to be heard, just mute it in the Main Mixer.

Chapter 19
Delay Compensation

About this chapter

This chapter describes how delay compensation is implemented in Reason.

About Delay Compensation in Reason

Delay compensation is desired because some effect devices have inherent latencies, due to internal processing (re-sampling, FFT, lookahead compression etc). When a signal passes through such a device, it gets delayed and thus "out-of-sync" with other signals. This is especially noticeable if you're using Parallel Channels in the Reason mixer, because both the original channel and the parallel channel(s) carry the same source signal. If the effects on one of these parallel channels delay the signal, this will be heard as comb filtering, phasing, blurring, etc.

Traditionally, Reason hasn't had any delay compensation, mainly because of the totally free routing possibilities. However, as from version 9.5 Reason features delay compensation for its native effect devices, Rack Extension effect devices and VST effect plugins.

Typically, there are two ways to achieve delay compensation:

By inserting "invisible" delays on the other signal paths, so that all paths are delayed equally.

By having the tracks with latency effects in their paths play back earlier.


- **The delay compensation introduced in Reason 9.5 uses the first method only, i.e. inserting delays in the other signal paths.**

Activating the Delay Compensation

The delay compensation can be activated in the Master Section fader section, on the Transport panel, and on the Options menu.



The Delay Compensation button in the Master Section of the Main Mixer.



The Delay Compensation button on the Transport panel.

- ▶ **Click the Delay Comp button to switch on/off the delay compensation.**
  When on, the delay compensation affects all configurations described in "Delay Compensation rules" below.
- **The total signal path latency is displayed (in no. of samples) below the Delay Comp buttons.**
  Hovering over any of these latency figures brings up a tool tip which also displays the latency in milliseconds.

Delay Compensation rules and limitations


Due to the free routing possibilities in Reason, delay compensation could become infinitely complicated. Therefore, we have chosen to keep it fairly simple by imposing some general rules and limitations.

! **The delay compensation aims at getting a coherent mix using the main mixer in a *standard* configuration. If you do unconventional routings, the delay compensation may not work as intended and things might sound off. See "Problematic configurations" for examples of problematic routings.**

Delay Compensation rules


Here are the basic rules for delay compensation in Reason:

- **Delay compensation can be applied to Effect devices that are connected in series between an instrument device and the inputs of a Mix Channel device:**




An ID8 instrument device routed via a Scream 4 effect and an RV7000 Reverb effect in series.

The configuration above can be described schematically in the following picture:




- **Delay compensation can be applied to Effects devices connected in series as Insert FX in the mixer channels (between the "To/From Insert FX" jacks on Audio Track and Mix Channel devices):**




A Scream 4 and an RV7000 effect device routed in series inside a Combinator device in the Insert FX container in a Mix Channel.

The configuration above can be described schematically in the following picture:




- **Delay compensation can be applied to Effect devices that are connected in series between the Parallel Out jacks of a Mix Channel or Audio Track device, to the Input jacks of another Mix Channel device:**



The Parallel Outs of a Mix Channel (ID8 3) routed via a Scream 4 and an RV7000 to another Mix Channel (Mix Channel).

The configuration above can be described schematically in the following picture:



- **Delay compensation can also be applied to combinations of the three examples above.**
  This could be, for example, if an Instrument device is routed in series via Effect devices to a Mix Channel device, and the Mix Channel device has Effect devices in series in its Insert FX section. Then, the latency is summed for all effect devices in the serial signal chain.
- **Delay compensation can be applied to signals that are sent from the mixer channels to the Send FX busses.**
  This means that the signals from the Mix Channels are delay-compensated (if necessary) before they are sent to the Send FX busses.
- **Reason fully depends on getting latency values reported from the Effect devices/plugins.**
  In other words, Reason doesn't measure any latency of the effect devices. However, you can manually adjust the delay compensation if needed (if things sound wrong due to plugins reporting wrong latencies etc.). See "Manually adjusting the latency values" for more details.


Delay Compensation limitations

- **Only signals routed to a channel in Reason's main mixer will be compensated. There is no delay compensation for the channels on a rack mixer, such as Mixer 14:2.**
- **Only signals that pass the Master Section will be compensated (not channels connected using Direct Outs, see "About using the Direct Out connections of the mixer channels").**
- **The delay compensation ignores the latency reported by devices connected as Send Effects (see "About Send FX Returns").**
- **With some non-standard routings (splits, loopbacks, cross-routing etc), delay compensation may not work or may be limited. See "Problematic configurations".**
- **Effects inside an Instrument Combinator are not delay-compensated (but Effect Combis are).**
- **CV, MIDI and automation signals are not delay-compensated.**
- **MIDI Clock sync and Ableton Link are not delay-compensated.**
  However, you can manually adjust the MIDI Clock Sync Offset, see "External synchronization considerations".

How the Delay Compensation works

Delay Compensation in individual mixer channels

As soon as you add an effect device/plugin as Insert FX in a Mix Channel or Audio Track device - or in the Master Section device - the sum of the reported inherent latencies of the effect devices in that channel is displayed (in samples) at the bottom of the Insert FX section on the corresponding channel strip in the main mixer. If you add more effect devices in an Insert FX chain, the latency figures are added and summed to a total latency value, which is then displayed in the respective Insert FX sections:




Latency values (in samples) displayed in the Insert FX sections on the main mixer channel strips.

▶ **Hovering over any of these latency figures brings up a tool tip which also displays the latency in milliseconds.**

What Reason then does to compensate for the inherent latencies in effect devices is to automatically add "invisible delays" to the signals of the *other* mixer channels. The goal for the delay compensation is to have all mixer channel signals arriving at exactly the same time to the Master Section of the main mixer.

In the picture below, four mixer channels with different Insert FX devices are routed to the Master Section of the main mixer. Reason checks which mixer channel has the longest combined inherent latency, by summing the effect device's reported latencies individually for each channel.



Delay compensation principle for a number of mixer channels routed to the Master Section of the main mixer.


Mix Channel 2 has the longest inherent latency in the example above: 2+10=12 samples. The goal now is to add internal "invisible delays" to the signals from the other mixer channels so that the total delay for each channel is 12 samples.

This means that for Mix Channel 1 Reason automatically adds a compensation delay of 8 samples (to add up to '12'). Mix Channel 2, which has the longest inherent latency, doesn't get any delay compensation at all. Mix Channel 3 gets a delay compensation of 2 samples (to add up to '12') and Mix Channel 4 gets a a delay compensation of 9 samples (to add up to '12').

Now, the signals from all Mix Channels have a total delay of 12 samples and are thus perfectly "in sync" with each other when they reach the Master Section.

If you add more effect devices to any of the Mix Channels, the inherent latencies might become longer, and the delay compensation values are automatically recalculated and adjusted.

A more "graphical" way of looking at the delay compensation is shown in the picture below. Here the inherent latencies of the mixer channels and the delay compensation are represented by proportionally sized boxes, which could make it easier to understand the principle:



Delay compensation principle for a number of mixer channels routed to the Master Section of the main mixer.

As you can see in the picture above Mix Channel 2 doesn't get any delay compensation, since it has the longest inherent latency of the four channels.

Manually adjusting the latency values

There might be situations where you want to manually adjust the latency values. This could be, for example, if effect devices should report the wrong latency values and thus cause the audio to sound out of phase or weird in other ways.


On the rear panel of the Audio Track device's and Mix Channel device's unfolded Insert FX section are two displays: the display to the left shows the total inherent latency for the channel (the sum of the reported inherent latencies of the effect devices in the Insert FX signal chain), and the display to the right shows the number of samples you might have manually adjusted the latency value:




! **Note that the Channel Delay figure can never be less than the sum of the reported inherent latencies of the effect devices in the Insert FX signal chain.**

! **Note that manually adjusting the latency is only possible if you have connected your effects as an Insert FX chain (between the To Device and From Device jacks).**

The sum of the reported inherent latencies (Channel Delay) and any manual adjustment is displayed in the respective Insert FX sections on the main mixer channel strips:




The "Total signal path latency" figure displayed on the Transport panel is the sum of the individual channel which has the longest inherent latency, plus the inherent latency of the Master Inserts effect devices:



▶ **Hovering over any of the latency figures in the three pictures above brings up a tool tip which displays the latency in milliseconds.**

Delay Compensation with Busses and Parallel Channels

When using Parallel Channels and Output Busses the same principles apply, i.e. the total latencies for all mixer channels and busses should be the same when the signals reach the Master Section. Also, the latencies of the signals entering the same Output Bus must also be the same, to avoid phasing problems etc. In the picture below, a number of mixer channels, parallel channels and busses are used:



Delay compensation when using Parallel Channels and Busses.

As you can see in the picture above, the signal chain with the longest inherent combined latency is: Mix Channel 3 > Bus 1 > Parallel Bus 1 > Bus 2 > Master Section; this signal chain is therefore not delay-compensated. All other signals are delay-compensated where necessary, which is indicated by the orange circles in the picture.

Delay Compensation to Send FX busses

Since each mixer channel is delay-compensated individually, we need to make sure that any signals from the mixer channels to the Send FX busses reaches the Send FX busses at the same time. To make the signals to each of the Send FX busses come “in sync”, there is also a built-in delay compensation to the eight FX sends of each mixer channel.

About Send FX Returns

Reason doesn't compensate for any inherent delays in the Send Effect devices themselves, as this would make the delay compensation scheme extremely complex. Also, Send FX are traditionally often used for delays and reverbs, where a little extra inherent delay won't matter much.

! **In the situation where you might route the outputs of Send Effects back to separate Mix Channels, no delay compensation is being performed on the “return” Mix Channels.**


About the Master Insert FX

Reason considers all audio signals to pass through the Master Section in the main mixer; this is where all signals eventually should end up in sync. But the Master Section has an Insert FX section too, and effect devices used here can often have a significant inherent latency (maximizers, mastering EQs etc). However, since all signals pass through these effect devices in sync, no delay compensation is performed on the Master Insert FX devices. This is why the Master Section device in the rack lacks Channel Delay and Adjustment displays.

Problematic configurations

The examples below describe a number of “problematic” routings and how Reason handles these regarding delay compensation.


When non-standard routings are detected, the red LED in the Delay Compensation section of the back of the Mix Channel/Audio Track device Programmer section lights up. Hovering over the LED brings up a tool tip, which describes the detected type of problem;



Parallel signal paths within the channel

In these types of configurations Reason uses delay compensation only for the shortest signal path, i.e. the signal path that has the shortest inherent latency between the To Device and From Device connections:






Example of a parallel signal configuration where only the delay for the shortest path is used for delay compensation.

Sub-mixers with Send FX routings within the channel


In these types of configurations Reason uses delay compensation only for the shortest signal path, i.e. the signal path that has the shortest inherent latency between the To Device and From Device connections. If there are send effects in the path, this means that the inherent latency will be the same, or longer with these effects. Therefore, send effects are always disregarded from any delay compensation:




Example of an internal "send fx" routing inside an Insert FX configuration.

Loopback within the channel

In these types of configurations Reason uses Delay compensation only for the shortest signal path, i.e. the signal path that has the shortest inherent latency between the To Device and From Device connections. If there are any feedback connections in the signal path, these will be disregarded from any delay compensation:







Example of a feedback loop, which is disregarded from delay compensation.

External routing from the channel

If there are any connections to devices outside the Insert FX section, and these devices are routed to other mix channels (or to the Master Section), any inherent latencies in the external effect devices will be disregarded from any delay compensation:





Example of an external routing from (any of) the Insert FX devices.


Broken signal path in the channel

If the effects signal path should be broken in the channel, the tool tip “Could not calculate latency. The default value of 0 samples was used” is displayed. This means that the program couldn't follow the signal path, which may be because it's not completely connected, for example:



About using the Direct Out connections of the mixer channels

Since connecting the Direct Outs of a Mix Channel or Audio Track device automatically disconnects it from the Master Section of the main mixer, any delay compensation is also automatically disabled. This is indicated by " - " in the Channel Delay display:



Example of when the Direct Outs are used in a channel.

About the Metronome Click

Reason adds the Metronome Click (if selected) at the Hardware Interface (after the Master Section). This means that if there's a delay in the signal path, the Metronome would be heard before the rest of the audio on playback. Therefore, Reason uses delay compensation also for the Metronome so it always plays back correctly in sync.

Recording with Delay Compensation

When you record audio using External Monitoring (Settings - the User Interface tab), Reason repositions the audio according to the reported audio card latency. Recorded audio is positioned earlier on the track, by Input Latency + Output Latency. When delay compensation is active, the total delay time is then added to the audio repositioning.

Playing and monitoring with Delay Compensation

A problem with delay-based delay compensation is that all signal paths are delayed equally. Even if you have no Insert FXs in the signal path for your track, it might be delay-compensated (depending on what's in the rest of the channels in the mixer). This could make it hard to play instrument devices and monitor through Reason. Some good advice could be to:

- **Record and monitor through Reason with delay compensation Off, and then switch it on after recording.**
- **You could also bypass the Insert FX on the channels with highest latency when recording. Also remember to bypass Master Insert FX when recording or playing.**

About bouncing mixer channels

Delay compensation is taken into account when you bounce mixer channels - both to files on disk and to new tracks in the song - as well as when you use the "Bounce in Place" function.

Chapter 20
Song File Handling



About this chapter

This chapter describes how to open, create and save songs in various ways. It also describes how to save a song as a Template and how to import and export songs as Standard MIDI files.

Opening Songs

Opening a Reason Song

! **To be able to open a Reason Song (or a Reason Essentials/Reason Intro/Reason Lite/Record Song), you need to run Reason in Authorized mode. If you're using Reason in Demo Mode (unauthorized), the "Open" item on the File menu is removed and replaced by "Open Demo Song". This allows you to open only the factory made Reason Demo Songs (see "Opening a Reason Demo Song"). See "Authorizing Reason" for details on how to authorize Reason.**

To open a Reason Song:

▶ **Double click the Song file in Windows Explorer (Win) or in Finder (Mac).**

Or, if you want to open a Song file from within the program:

1. **Hold down [Ctrl](Win) or [Cmd](Mac) and press [O], or select "Open" from the File menu.**
   The standard OS browser appears.
2. **Navigate in the browser to the desired folder on disk or within a ReFill.**
3. **When you have located the Reason (.reason, .rsndemo, .ree, .reedemo, .rei, .reidemo, .relt, .reltdemo, .rltd, .rns, .rps or .rsb), or Record Song file (.record or .recdemo), select it and click "Open" (or double click the file).**
   The song opens in a new document window.

▶ **You can have several Songs open at the same time if you like. This allows you to drag and drop (and copy and paste) patterns, clips and patches between songs. However, all open songs consume some memory and processing power, so you might want to close songs you don't need for the moment.**

▶ **It's also possible to have Reason open the last song you worked on as soon as you launch the program. See "Opening the last Song at program launch" for more information.**

If the "Missing Sounds" window appears

If the song includes samples or REX files, and these have been moved or renamed since the song was saved, the program will inform you that it cannot find all files. You can then choose to either manually locate the missing files, to have the program search for them or to proceed without the missing sounds. For details, see "Handling Missing Sounds" in the "Sounds, Patches and the Browser" chapter.

If "Missing Device" panels appear in the rack

When you open a Reason song made by another user, it may have been created with Rack Extension devices that you don't have. All such missing devices in a song will be replaced by generic "Missing Device" placeholder devices. See "About missing Rack Extensions" for more information.

About opening Reason Version 5 (or earlier) Songs

If you run Reason in Authorized mode, it's also possible to open older Reason (.rns, .rps and .rsb) songs. A Reason Song created in Reason Version 5 or earlier will end up in a separate Song document, just like an ordinary Reason Song. All Rack device and sequencer track configuration will be preserved as well as all cable connections. The only things that will be changed are these:

- **The Main Mixer Master Section will be connected to Outputs 1 and 2 of the Reason Hardware Interface.**

- **The Rack device that was connected to outputs 1 and 2 on the Reason Hardware Interface in the old song will now be connected to a new Mix Channel device, below the Master Section device in the Rack.**
- **If there were any more connections to the Reason Hardware Interface in the song, these will now be connected to new mono Mix Channels.**
- **Below the Mix Channel devices in the Rack, the devices from the Reason song will appear in a single rack column, just like they did in the earlier version of Reason.**

! **If you open a Reason Published Song (.rps), you cannot save etc., and the "Export Audio" and "Bounce Mixer Channels" functions will only work if you haven't manually changed anything in the Song document.**

▶ **If you want to re-route the instrument devices from the 14:2 Mixer in the old Reason Song to separate Mix Channels in the Reason Version 13 Song, there is kind of a semi-workaround for this, see "About re-routing devices in songs created in Reason Version 5 or earlier".**

Opening a Reason Demo Song

Reason Demo Songs are factory made songs that demonstrate how Reason can be used in various musical projects. If you run Reason in "Demo Mode" (unauthorized), you will only be able to open Demo Songs - but not regular Songs. If you run Reason in authorized mode, the Open Demo Song item is available in addition to the regular Open item.

▶ **Select "Open Demo Song" from the File menu and select a Demo Song from the sub-menu.**
You could also select "Download more Demo Songs" from the sub-menu. This will open your default web browser and direct you to the Reason Demo Songs page on the Reason Studios web site. On this page you can download additional Reason Demo Songs to your computer. You will then have to use the "Open Demo Song" command from the File menu to open the downloaded Demo Songs.


▶ **You can also download more Reason Demo Songs by selecting "Download more Demo Songs" from the Help menu.**

▶ **You can have several Demo Songs open at the same time if you like. This allows you to drag and drop (and copy and paste) patterns, clips and patches between songs. However, all open songs consume some memory and processing power, so you might want to close songs you don't need for the moment.**

Opening the last Song at program launch

It's possible to instruct Reason to automatically open the last Song you worked on each time you launch Reason. You select this on the "Browsing" tab in the "Settings" dialog.

1. **Click the Settings button in the top bar, or select "Settings" from the Edit menu (Win) or "Reason" menu (Mac) and then click the "Browsing" tab.**



2. **Tick the "Open last song on startup" checkbox.**
When you launch Reason the next time, the last saved Song will automatically open in a document window.

Closing Songs

- ▶ **To close a Song, hold down [Ctrl](Win) or [Cmd](Mac) and press [W], or select "Close" from the File menu. Alternatively, click the close button in the upper corner of the Song document window.**
  If you have unsaved changes, you will be asked if you want to save the song before closing.

! **Note that when you're closing the last open Song document in the Windows version of Reason, the Reason application will quit.**

Creating Songs


Creating a new Song

- ▶ **To create a new song, hold down [Ctrl](Win) or [Cmd](Mac) and press [N], or select "New" from the File menu.**
  A new Song document window appears. By default, the new Song contains the following:
- ▪ **The Reason Hardware Interface in the Rack.**
- ▪ **The Main Mixer Master Section with its Master Section device in the Rack.**
  The Master Section device's Master Out L & R are connected to the Reason Hardware Interface Audio Out 1 & 2.
- ▪ **The Transport Track at the top of the Sequencer.**
- ▶ **Instead of creating an empty song each time you select "New", it's possible to automatically load an existing song to use as template for your new songs. For example, if you want to start with your own unique selection of devices, you can create and save a song and then instruct Reason to use this song each time you create a new song. See "Setting up a Default Song".**
- ▶ **An alternative to creating a new song is to use the "Create New from Template" command to open one of the factory made Template Songs. See "Creating a new Song from a Template".**

Setting up a Default Song

It's possible to specify a certain Song document which will automatically open as a "template" each time you select "New" from the File menu. The Default Song could be any Song you have created earlier, or a factory made Template Song. You can select this Default Song on the "Browsing" tab in the "Settings" dialog.

1. **Select "Settings" from the Edit menu (Win) or "Reason" menu (Mac) and then click the "Browsing" tab.**



2. **If desired, click the "Device Sorting in new songs" dropdown and select one of the following alternatives:**
   "Rack per Track" (one rack column per sequencer track), "Auto-Group Devices" and "No Grouping".
3. **Click the "Template" radio button in the "Default Song" section.**
4. **Click the Browse button to the right and select the Song you want to use as a template when creating new Songs.**
   The included Template Songs in Reason can be found in your user's Music folder at "Music > Reason Studios > Template Songs".

   Each time you create a new Song (by selecting "New" from the File menu), the selected Song will be loaded and used as a template for your new Song. On Windows platforms, the Song document will be named "Document n" where "n" is an incremental number. On macOS platforms, the document will be named "untitled n" where "n" is an incremental number. You can then save your Song with a new name.

! **Make sure the "Load last song on start-up" checkbox is not ticked, otherwise the last song will be opened instead of the Template song you selected.**

Creating a new Song from a Template

- **To create a new song from a Template, select "New from Template" from the File menu and then select one of the Template Songs that appear in the sub-menu.**
  The selected Template Song appears in a new document window. On Windows platforms, the document will be named "Document n" where "n" is an incremental number. On macOS platforms, the document will be named "untitled n" where "n" is an incremental number. You can then save your Song with a new name.
- **You could also create your own Template Songs and make them appear in the sub-menu. See "Making a Song appear as a Template Song".**
- **You can also download more Reason Template Songs by selecting "Download more Template Songs" from the Help menu.**

Saving Songs

Saving a Song

You will always be able to save your Songs in Reason. It doesn't matter if you're running in authorized or unauthorized (Demo) mode.

The "Save" function

To save a Song, proceed as follows:

1. **Hold down [Ctrl](Win) or [Cmd](Mac) and press [S], or select "Save" from the File menu.**
   If this is the first time you're saving the song, a file dialog will appear where you can specify a name and destination.
2. **Specify a name and destination for the Song and click "Save".**
   Once you have saved a song, selecting "Save" will simply save it under the same name and in the same location, without showing a dialog.

- **It's also possible to automatically include all samples used by the Reason devices and make the Song "self-contained". Refer to "About Self-Contained Songs" for details about how to include your own samples in your songs.**
- **To reduce the file size of your song, you can use the "Save and Optimize" command described in "Saving and optimizing a Song".**
- **It's also possible to include detailed information about your song. Refer to "Including Song Information" for more details.**

The "Save As..." function

To save an existing Song under another name and/or in another location:

1. **Hold down [Ctrl]+[Shift](Win) or [Cmd]+[Shift](Mac) and press [S], or select "Save As..." from the File menu.**
   The "Save As" dialog appears.
2. **Specify a new name and/or new destination for the Song and click "Save".**

- **Using the "Save As..." function will automatically optimize the Song (see "Saving and optimizing a Song").**

Saving and optimizing a Song

When you record audio in the Sequencer, the recordings are stored in your Song document. If you remove recordings in your song while editing, there might be "empty" areas left in the document, similar to a fragmented hard disk. To "defragment" the Song document, and thus reduce the file size, you can use the "Save and Optimize" command on the File menu. Note that the "Save and Optimize" command can only be used on previously saved Song documents.



▶ **Select "Save and Optimize" from the File menu.**
The Song will be optimized and saved at the original location.

! **Note that saving and optimizing a Song could take a while if you have lots of audio recordings in it. Therefore, the best alternative would probably be to use the "Save" command while you're still working with your Song, and then use the "Save and Optimize" command as a final step when you've finished editing.**


▶ **Using the "Save As..." function also automatically optimizes the Song.**

▶ **In some situations, it's possible to reduce the file size even further by deleting any recordings you haven't used in your Song. See "Delete Unused Recordings".**

Including Song Information

Selecting "Song Information" on the File menu opens a dialog in which you can add information about your song. For example, if you plan to send the song to other Reason users, this dialog allows you to add contact information, comments about the song, etc.

▶ **Select "Song Information..." from the File menu.**
The Song Information dialog opens.



The Song Information dialog contains the following items:

- **Text in Window Title:**
The text you add here will be displayed directly after the file name in the song window's title bar.
- **More Information:**
This is where you could add notes and comments about your song.
- **Song Splash:**
This allows you to add a picture to the song. The picture will be displayed when the song is opened.

▶ **To add a splash picture, click the folder button at the upper right corner, locate and open the picture file in the file dialog that appears.**

! **Splash pictures must be JPEG files (Windows extension ".jpg") with a size of 256 x 256 pixels.**

▶ **To remove the splash picture from the song, click the "cross" button at the upper right corner.**

▶ **Tick the "Show splash on song open" check box to make the splash appear every time the song is opened.**

- **Author's Web Page:**
  Here, you can type in your web site URL. When a user opens your song, he/she can go directly to your web site by clicking the Browse button that appears in the splash (provided there's an Internet connection available).
- **Author's Email Address:**
  Here, you can specify your e-mail address if you want other Reason users to e-mail you their comments, etc.


About Self-Contained Songs

The Song is the main file format in Reason. A Song contains the device setup and all settings and connections in the Rack, all Main Mixer Channel settings as well as everything you have recorded in the Sequencer. However, this is not always sufficient. If you want to open your song on another computer, or send it to another Reason user, you will also need to include all samples and REX files used by the Reason devices in the Song. To make this easier, Reason allows you to create "self-contained" songs. A self-contained song contains not only the references to the used samples and REX files, but also the files themselves. You can choose exactly what files should be included in the self-contained song.

▶ **An alternative to self-containing samples and/or REX files could be to bounce Mixer Channels to Audio Tracks. This way, you could "convert" ReFill samples to audio so that your song would always sound the same, no matter on which computer you play it back. See "Bouncing Mixer Channels" for details.**

To specify what files should be included in the self-contained song, proceed as follows:

1. **Select "Song Self-contain Settings..." from the File menu.**
   The "Song Self-Contain Settings" dialog appears, listing all samples and REX files used in the song:



2. **Tick the checkboxes to the left of the "Name" column for the files you want to contain in the song.**
   Note that samples and REX files from ReFills can also be self-contained (but not un-self-contained, see below).

▶ **You can use the "Check All" button to tick all check boxes in one go.**
Similarly, the "Uncheck All" button clears all check boxes.

3. **When you have marked the desired sounds, click "OK" to exit the dialog.**
   The next time you save your Song, the specified sounds will be automatically included in the Song file.

! **Note that a self-contained song file will be larger than the original song file. However, samples included in a self-contained song are automatically compressed by approximately 50% of their original size. Since the compression is lossless, this does not in any way affect the sound quality.**

“Un-self-containing” a Song

If you have a self-contained song which contains one or several sounds embedded in the song file, you may want to extract these sounds and make the song refer to them on disk as usual. This is done in the following way:

1. **Select “Song Self-Contain Settings...” from the File menu.**
   The “Song Self-Contain Settings” dialog appears.
2. **Locate the sounds you want to extract from the song file, and deactivate their checkboxes (or click the “Uncheck All” button).**
3. **Click “OK” to close the dialog.**
   Now, Reason will check for each “extracted” sound file whether it is available (at its original, stored location) or not.

- **If the program finds the sound file at the location stored in the song, it is simply removed from the song file, and the original file reference path is used.**
  This would be the case if you made the song self-contained yourself, and un-self-contain it on your own computer (provided that you haven’t removed the original sound files from disk since you made the song self-contained).
- **If the program doesn’t find the sound file, a file dialog appears, allowing you to select a folder and name for the sound file.**
  The extracted file will be saved in the specified folder, and the path in the song will be adjusted. This would be the case if you were given the self-contained song by another user, for example.

! **Note that it is not possible to un-self-contain samples that originate from ReFills!**

! **If you un-self-contain samples that were modified in the Edit Sample Window and feature Start and End Markers and/or loop crossfades, the Lossy Sample Export dialog appears. The available options are described further down in the “Exporting samples” section in the Sampling chapter. Note that the option you select in the Lossy Sample Export applies to all samples you have deselected in the Song Self-contain Settings dialog!**

Making a Song appear as a Template Song

If you want Songs you have created to appear on the “New from Template” sub-menu, and be available for selection when you use the “New from Template” command (see “Creating a new Song from a Template”), you need only move or copy the Song(s) to the Template Songs folder in the Music folder on your hard drive. The easiest way to get to this folder is by selecting “File > New from Template > Show Template Folder”. This brings up the Template folder in Windows Explorer or Finder on Mac.

A note about saving Songs as audio files

It’s also possible to export your Songs as audio files in WAV, AIFF or MP3 format. Refer to “Exporting Songs or parts of Songs” for more information.

Audio data and Scratch Disk settings

About audio data in Song files


If you record or import audio into an unsaved Song document, the audio is written to the "Scratch Disk folder" on your computer. As soon as you save (and name) the Song document, the audio is moved from the Scratch Disk folder to the Song document. From here on, all new recorded and/or imported audio is stored in the Song document.

Changing Scratch Disk folder location

The Scratch Disk is where Reason stores new, unsaved songs, plus analysis data (waveform data and high-quality time stretch/transposed audio/sample rate conversion data).

By default, Reason places the Scratch Disk folder in the system temp folder in your home directory. You can change the Scratch Disk folder location if you like:

1. **Select "Settings" from the Edit menu (Win) or Reason menu (Mac) and then click the "Folders" tab.**



2. **Click the "Change..." button in the Scratch Disk Folder section.**
   A system folder browser opens where you can select - or create - a new folder.
3. **Select the folder where you want to locate the Scratch Disk Folder and click "OK".**
4. **Restart the computer and relaunch Reason.**

- **If you later want to revert to the default setting, click the "Reset" button on the "Advanced" tab.**
  The custom Scratch Disk Folder setting is removed and is replaced by the default setting. You will then have to restart the computer for the change to take effect.

About unavailable Scratch Disk Folder

If a custom assigned Scratch Disk Folder isn't available when you launch Reason, an alert saying: "The selected Scratch Disk folder isn't available. Reason will use the default scratch disk for this session." is shown. This could happen if you have assigned the Scratch Disk folder to a removable disk and that disk is currently unavailable.

- **Click "OK" to use the default Scratch Disk Folder.**

The next time you launch Reason, it will look for the custom assigned Scratch Disk Folder again, and will do so every time you launch Reason, until you reset the custom assignment by clicking the "Reset" button.

About “Orphan Audio Streams”

If your computer should malfunction (due to power loss etc.) during recording into a previously saved Song document, there is a good chance that your last unsaved audio recordings can be (at least partly) recovered:

1. **Restart your computer and launch Reason.**
2. **Open one of the Song documents that was open during the computer malfunction.**
   If the Song contained unsaved audio recordings, Reason will find these and show an alert saying that the Song contains “orphan audio streams”. You will be given the choice of deleting them or having them appear in new clips on a new audio track, for salvaging.

! **Note that it’s only audio recordings that it’s possible to recover. Any new Instrument Tracks in an unsaved Song will be lost in the case of computer malfunction.**

Importing and exporting Standard MIDI Files

Reason can import and export Standard MIDI Files (SMF). This allows you to transfer MIDI data between Reason and other applications.

Importing Standard MIDI Files

To import a Standard MIDI File to the Reason sequencer, follow these steps:

1. **Create a new, empty Song document.**
2. **Select “Import MIDI File...” from the File menu.**
   The Browser appears (if it was hidden).
3. **Select a Standard MIDI File (.mid) in the Browser and click “Import”.**
   A number of new tracks are created in the Reason sequencer. The tracks will have their original name, with their original MIDI channel added. Each track will be assigned an ID8 device, loaded with a sound that resembles the original sound. These assignments will only serve as a starting point to be able to play back the imported MIDI file. You may want to change sound, or replace the ID8 with another device if you have Reason installed.

- **The Note events in the MIDI file will be imported into one or several Note Clips on a Note Lane on each Track.**
- **If the imported MIDI file is a Type 1 MIDI file, there will be one sequencer track for each track in the MIDI file.**
- **If the imported MIDI file is a Type 0 MIDI file (that is, it contains one track with MIDI events on multiple channels), there will be one sequencer track for each used MIDI channel.**
- **The Tempo setting, any Tempo Automation and any Time Signature automation in the MIDI file will be recognized.**
- **All controller data in the MIDI file is included.**
  This means that standard performance controllers (Pitch Bend, Mod Wheel etc.) are preserved properly and will be included in the note clip, just as when recording in Reason. If there are separate MIDI Controllers in the imported MIDI file, these will be imported to separate Automation Lanes on the Instrument Tracks. There is a chance that some controller data may be imported to alien clips, due to different interpretations of a controller by a device in the rack and the MIDI instrument used to create the MIDI file (see “About alien clips”).



Green frames will appear for automated parameters on the ID8 device panels. This helps you locate any unwanted controller automation.

Exporting Standard MIDI Files

To export all Instrument Tracks and Automation Tracks from the Reason sequencer as a Standard MIDI File (SMF), do like this:

1. **Set the End Marker in the sequencer to where you want your song to end.**
   The MIDI file will contain all MIDI events on all tracks from the start of the song to the End marker.
2. **Select "Export MIDI FIle..." from the File menu.**
   The standard file browser appears.
3. **Type in a new file name (if desired) and select location for the file to be exported. Then, click "Save".**
   The default name for the MIDI File will be the Song's name followed by the ".mid" extension.

   MIDI files exported by Reason will have the following properties:

- **The MIDI file will be of Type 1, with one MIDI track for each track in the Reason sequencer.**
  The tracks will have the same names as in the Reason sequencer.
- **Since the Reason sequencer doesn't use MIDI channels as such, all tracks will be set to MIDI channel 1.**
- **The sequencer Tempo, and any Tempo Automation and/or Time Signature Automation, is included in the MIDI file.**

! **Since an Instrument Track in Reason could consist of different types of devices (plus FX etc.), there is no information about the actual sound in the exported MIDI File. The exported MIDI File only contains information about each instrument track and its MIDI Notes and/or MIDI Controller data laid out on the track. You will have to manually assign appropriate sounds to each track in the importing application.**



Chapter 21
Importing and Exporting Audio



About this chapter

This chapter describes the various techniques you can use to import and export audio to and from Reason.

Importing audio

Audio formats, sample rates and tempo matching

The Reason sequencer supports import of mono and stereo audio files of various formats, sample rates and resolutions. Reason also supports import of REX (ReCycle rcy, rex and rx2) files. You can import several audio files at the same time, with each audio file ending up on a separate Audio Track in the sequencer - or on separate Comp Rows in a selected Audio Clip. You can import files of different formats on the same Audio Track - or even in the same Audio Clip. One audio file could be an 8-bit mono file sampled at 22.05 kHz, the next a 24-bit stereo file sampled at 192 kHz, etc. Reason automatically converts sample rates and resolution with preserved audio quality. If the imported audio file includes tempo data that Reason supports, Reason automatically matches (stretches) the audio file to fit the current Song Tempo, without affecting the pitch.

- **if the imported audio files' sample rates differ from the current audio hardware sample rate, Reason will automatically sample rate convert.**
  This will first be done with a real-time algorithm, allowing for immediate playback. In the background, a high-quality sample rate conversion is performed. This is indicated by the CALC indicator on the transport panel. When done, Reason will automatically switch to playing back the high-quality version and the CALC indicator will go out.




The CALC indicator indicates when Reason performs high-quality stretching of audio.

About tempo matching imported audio to the sequencer

When you import an audio file, which has tempo data that Reason can read, the audio can be automatically stretched to fit the current tempo in the song. However, if the tempo in the imported audio is unknown, you could either let Reason try to detect the tempo, or you could manually tempo match (stretch) the imported audio.

On the "Browsing" tab in Settings is a selector for choosing how you want Reason to treat audio imported to the sequencer:



- **The default setting "Stretch to Song Tempo" works as follows:**
  Reason looks for tempo metadata in the audio file. If none is found, the program attempts to calculate the tempo based on the file length (assuming the length matches a 1, 2, 4 or 8 bar loop in a normal tempo range). This read or calculated tempo is then stored with the audio recording, and used as basis for stretching the audio to tempo: Reason compares the stored tempo with the song tempo, and stretches the audio clip so that they match.
- **The "Import as is, enable stretch on clip" works as follows:**
  The audio is not adapted to the sequencer tempo when imported, but will stretch to follow tempo changes in the sequencer once imported. Slice Edit and Pitch Edit modes are enabled for the imported audio clip.
- **The "Import as is, disable stretch on clip" works as follows:**
  The audio is not adapted to the sequencer tempo when imported, and will not follow any tempo changes in the sequencer once imported. Slice Edit and Pitch Edit modes are disabled for the imported audio clip.

There are also some ways to manually adjust the imported audio to the current sequencer tempo:


- **By using the Scale Tempo "tool" to manually stretch the audio clips, see "Tempo scaling Clips".**
- **By using the Scale Tempo function, see "Scale Tempo".**

Importing audio to the sequencer

! **To minimize the song saving time, we strongly recommend to save the song before you import many or large audio files.**

To import one or several audio files to tracks in the sequencer, proceed as follows:

1. **Select "Import Audio File..." from the File menu, or hold down [Ctrl]+[Shift](Win) or [Cmd]+[Option](Mac) and press [I].**
   The "Import Audio File" function gets Browse Focus:



2. **Browse and select the audio file(s) you want to import.**
   When you select a single audio file, you can preview selected audio file by clicking the "Play" button in the "Audition" section in the Browser.

! **You will not be able to preview the audio files when several files are selected.**

▶ **You can also import samples from the "Song Samples" location in the Browser.**


! **If you select a REX file, this will be rendered to audio when imported and all information about slice positions etc. will be lost. The Song Tempo and any Tempo Automation starting at the Song Position Pointer will be taken into account during the import. After the import, the REX file will behave just like any imported audio file.**

! **If you are going to edit the imported REX file inline, and work with slices, audio quantizing, stretching etc. Reason will automatically detect the transients in the audio and generate new slice markers that might not correspond to the original slice distribution of the imported REX file, see "Editing audio in Slice Edit mode".**

3. **Click "Import" to import the audio file(s).**
   Depending on the where the edit focus was when you selected "Import Audio File" from the Edit menu, the audio file(s) will be placed a little differently. In all scenarios, the imported audio file(s) will be placed at the current song position:


- **If an audio track has edit focus in the sequencer track list and you have selected only a single audio file, the imported audio file will be placed in a new clip on this audio track.**
- **If you selected several audio files when using the Import Audio File command, each audio file will be imported to new audio tracks in the sequencer - in the order the files were selected in the Browser.**
- **If you selected only a single audio file and the edit focus is elsewhere in the application, a new audio track will be created for the imported audio file.**

▶ **You can also drag one or several audio files from the Browser and drop in the sequencer track list.**
The audio files will then be imported to separate audio tracks in the sequencer:



A + sign and a divider indicate where in the track list the imported audio file(s) will be placed.

▶ **You can also drag one or several audio files from the Browser and drop on an audio track on the Arrange Pane.**
The audio files will then be imported as separate audio clips, after one another, on the corresponding audio track. If Snap is active in the sequencer, this will be taken into consideration:



A waveform sign and an insertion point divider indicate where on the audio track the imported audio file(s) will be placed.

Import audio file(s) to an open Audio Clip

It's also possible to import audio files to open Audio Clips in the Comp Editor in the sequencer. Proceed as follows:

1. **Open the Audio Clip you wish to import the audio file(s) to in the Comp Editor.**
2. **Select "Import Audio File..." from the File menu, or hold down [Ctrl]+[Shift](Win) or [Cmd]+[Option](Mac) and press [I].**
   The "Import Audio File" function gets browser focus.
3. **Browse and select the audio file(s) you want to import.**

▶ **You can also import samples from the Song Samples location in the Browser.**


! **If you select REX files, these will be rendered to audio when importing. The Song Tempo and any Tempo Automation starting at the Clip position will also be taken into account.**

4. **Click "Import" to import the selected audio file(s).**
   The audio file(s) will be imported as new recordings on new Comp Rows. The Comp Row(s) for the imported audio file(s) will be named "<filename.extension> (Imported)" where <filename.extension> is the name of the imported audio file with the appropriate extension.

   Depending on if you selected one or several audio files, the following will happen:

- **If you selected a single audio file, it will end up on the topmost Comp Row in the audio clip.**
- **If you selected several audio files, the first selected file will end up on the topmost Comp Row.**

▶ **You can also drag one or several audio files from the Browser and drop it/them in the Comp Row area in the Comp Editor.**
The audio files will then be imported to new separate Comp Rows in the Comp Editor. The horizontal divider indicates where the new Comp Row(s) will be inserted and the vertical divider indicates where the audio will begin. If Snap is active in the sequencer, this will be taken into consideration:



A + sign and a horizontal and a vertical divider indicate where in the Comp Row area the imported audio file(s) will be placed.

▶ **If you like, you could now edit the Audio Clip and comp the recordings on the different Comp Rows according to the description in "Creating a comped audio clip".**

Exporting audio

You can export audio from Reason in some different ways. Besides exporting songs or parts of songs, it's also possible to export (bounce) audio from separate Mixer Channels, with or without the mixer settings. It's also possible to export (bounce) individual Audio Clips. You can choose a variety of sample rates for the exported/bounced audio, and also various audio file formats and resolutions.

Exporting Songs or parts of Songs

There are two ways of exporting the mix of all active sequencer tracks in a song:

- **The "Export Song as Audio File..." on the File menu allows you to save the mix from the start of the song to the End Position Marker.**
- **The "Export Loop as Audio File..." on the File menu allows you to save the mix from the Left Locator to the Right Locator.**


! **When you export a song or a Loop, the signals for the exported audio file are taken from Outputs 1 and 2 of the Hardware Interface device. Any other used outputs on the Hardware Interface will be disregarded.**

Proceed as follows to export the mix of an entire song, or a loop section of a song:

1. **Make sure the End Position Marker is placed where you want the song to end or, if you want to export a Loop, make sure the Left and Right Locators are placed around the Loop you want to export.**

! **Make sure you place the End Marker (when exporting a Song) or Right Locator (when exporting a Loop) so that any sustaining sounds are allowed to decay to silence. Otherwise, there will be an abrupt "cut" in the end of the exported audio file. This is probably not what you want.**


2. **Select "Export Song as Audio File..." or "Export Loop as Audio File..." from the File menu.**
   The "Export Song as Audio File" or "Export Loop as Audio File" dialog appears.
3. **Choose location, File Name and File Format (AIFF, WAV or MP3) for the exported audio file at the bottom of the dialog and click "Save":**



Choose a file name and select file format.

4. **Select "Sample Rate", "Bit Depth" (resolution) and "Dither" in the "Export Audio Settings" dialog and click "OK":**
   If you are exporting at 16-bit Bit Depth you will have the option of applying Dither. Dither means that a type of noise is added to the digital signal to improve low level sound quality when exporting high resolution audio at a lower bit depth. Reason features a new, and very sophisticated, dithering algorithm with noise shaping.

▶ **Tick the "Dither" check box to improve the audio quality of exported audio at 16-bit resolution.**



Select Sample Rate, Bit Depth and Dithering of the audio to be exported.

About Tempo data in exported audio files

In addition to the audio data, tempo data is automatically included in the exported audio file. The tempo data contains information about the song Tempo and any Tempo Automation used in the song/loop. If you import such an audio file into another Reason song, it will automatically stretch to fit the current song tempo.

If the section to be exported contains audio for which high-quality stretching hasn't already been done, this will be calculated before the actual export happens. When Reason performs high-quality stretching, the CALC indicator on the Transport Panel shows a progress bar:



The CALC indicator indicates when Reason performs high-quality stretching of audio.

- **If high-quality stretching is still in progress when you export your audio file, the Export dialog will show a progress bar as well.**
  As soon as the high-quality stretching is finished, the dialog will be closed.

Bouncing Mixer Channels

Bouncing Mixer Channels basically means "recording" the audio outputs from Audio Track Channels and/or Mix Channels and then automatically creating separate audio files. The audio files can then be saved to disk or placed on new Audio Tracks in your song. If you choose to bounce to disk, the audio files will be automatically saved to disk as separate audio files. If you instead choose to bounce to new tracks, the bounced audio files will be automatically placed on new Audio Tracks in the sequencer.


The "bounce to disk" option is ideal if you want to export your sequencer tracks separately for further processing in external applications. The "bounce to track" option is great if you, for example, have instrument tracks with lots of resource consuming Insert FX etc. and therefore want to render them into audio to free up DSP resources in your song.

You can choose to bounce the Mixer Channels, either throughout the entire song, or only between the Left and Right Locators. You can also choose to bounce with or without mixer settings.

! **It's also possible to bounce individual clips to new audio clips on new audio tracks in the sequencer. If this is what you want to do, please refer to the "Bounce in Place" function.**

To bounce Mixer Channels proceed as follows:

1. **Select "Bounce Mixer Channels..." from the File menu.**
   The "Bounce Mixer Channels" dialog appears:



The "Bounce Mixer Channels" dialog.

When you open the “Bounce Mixer Channels” dialog, some channels in the Mixer Channels list might already be checked. This depends on what Mixer Channels (or their corresponding tracks or rack devices) were selected when you opened the dialog. The Master Section and FX Returns are never automatically checked when you open the dialog; you have to do that manually.

2. **Tick the check boxes for the Mixer Channels you want to bounce. Note that you can also bounce the Mixer Master Section and any FX Returns at the same time if you like.**
   The Mixer Channels in the list appear in the order they are placed in the Main Mixer, i.e. not necessarily in numerical or chronological order. The color tags in the list correspond to the Channel Strip colors in the Main Mixer. The Master Section is always listed as “Master Section” in the list and the eight FX Returns are listed as "FX 1 Return (<name>)", where <name> is the FX name shown on the label in the Main Mixer. Selecting FX Returns makes it possible to bounce reverbs and other Send FX you might be using in your song. The FX signal is tapped after FX Return Level/Pan/Mute if “Apply Mixer Settings = All” (see below). Otherwise, the signals will be taken at the FX Return inputs.

- **Click the “Check All” or “Uncheck All” buttons to activate or deactivate all checkboxes in one go.**

3. **Select what channel settings you want to use (or not use) by clicking one of the radio buttons in the “Apply Mixer Settings” section.**

- **Select “All” to bounce the selected Mixer Channels with all its settings, including any Insert FX, Level and Pan.**
  Since the Pan parameter is included, mono Mixer Channels will be bounced as stereo audio files.
- **Select “All except fader section” to bounce the selected Mixer Channels with all Mixer Channel settings, including any Insert FX, but excluding the Level, Pan, Stereo Width and Mute parameters of the Channel Strip.**
  Stereo Mixer Channels will be bounced as stereo audio files whereas mono Mixer Channels will be bounced as mono audio files. For the Master Section, this option means including Insert FX and the Master Compressor, but not the master fader.
- **Select “None” to bounce the selected Mixer Channels before the Mixer Channel Strips, without applying any Mixer Channel parameters or Insert FX.**
  Bounced files will be in stereo if there's any stereo material on the Audio Track (or, for a Mix Channel, if it's connected in stereo). Otherwise, the bounced audio files will be in mono.

4. **Tick the “Normalize” check box to adjust all bounced audio files so the maximum level is 0 dB.**
   Normalizing is useful to get good levels when you proceed to use the bounced audio files in another application, or to avoid clipping.

5. **Select what range to bounce in the “Range to Bounce” section.**

- **Select “Song” to bounce the entire song (from the beginning of the song to the End Marker).**
- **Select “Loop” to bounce the section between the Left and Right Locators.**

! **Make sure you place the End Marker (when bouncing a Song) or Right Locator (when bouncing a Loop) so that any sustaining sounds are allowed to decay to silence. Otherwise, there will be an abrupt “cut” in the end of the bounced audio files.**

6. **Select destination for the bounced Mixer Channel(s) in the “Bounce to:” section.**



▶ **Select “New Tracks in Song” to bounce the Mixer Channels to new Audio Tracks in the song.**
When “New Tracks in Song” is selected, the File Format settings in the dialog are disabled (as is the "Export Tempo Track (.MID)" setting). The audio will be rendered at the current song’s sample rate (i.e. what you have previously set up in the hardware audio interface), at full 32-bit float resolution.

Clicking OK will create a new Audio Track for each selected Mixer Channel, create an Audio Clip on each of these Tracks and render the Mixer Channel audio as a recording on a Comp Row in the Audio Clip.

The new Audio Tracks will get the names and colors of their corresponding (bounced) Mixer Channels. The Audio Clips will get the same color but will not be labeled (named).

The new recordings (on the Comp Rows) will get the name of their source Mixer Channels + "(Bounced)", e.g. "Picked Guitar (Bounced)" if the bounced Mixer Channel’s name is “Picked Guitar”.

Selecting "Mute Original Channels" will mute all bounced Mixer Channels (those selected in the Mixer Channels list) after the bouncing. If there are automation lanes for their Mute buttons, their ON buttons will be turned off.

If you selected “None” in the “Apply mixer settings” section, you will be given the option to copy the original mixer channel settings to the destination channels. To do this, tick the “Copy original channel settings” box.

! **The “Mute Original Channels” setting does not affect the Master Section or the FX Returns.**

▶ **Select “Audio Files on Disk” to bounce the Mixer Channels to audio files on disk.**
When “Audio Files on Disk” is selected, the "Mute Original Channels" option in the dialog is automatically disabled.

Choose File Type, Sample Rate, Bit Depth and any Dither in the “File Format” section.

Clicking OK will bring up a Save dialog which allows you to select a folder, or create a new folder. Clicking Save will then create one audio file per selected Mixer Channel and place in a sub-folder named “Bounced <song name>”. All audio files will have the file type, sample rate and bit depth as defined in the “File Format” section.

The audio files will get the name of the bounced Mixer Channels, plus the File Type extension. If several selected Mixer Channels have the same name, an incremental number (starting with "-01") will be automatically added before the file extension.

The Song Tempo, and any Tempo Automation, is also included in the exported audio files. This means that if you import the audio files into another Reason Song document, they will automatically be stretched to the Song Tempo of that song.

If "Export Tempo Track (.MID)" is activated, the bounce function will also export a separate MIDI file containing the Song Tempo, and any Tempo Automation data. The MIDI file will have the name of the song, with the extension ".MID". This MIDI file can then be imported to the tempo automation lane in another Reason Song document, or to the tempo track in another DAW, to automatically set the song tempo and control any tempo automation in the sequencer.

! **Note that the “Export Tempo Track” option is available only if you have selected “Audio Files on Disk" in the “Bounce to:” section and “Song” in the “Range to Bounce:” section.**

Bouncing Audio Clips


The “Bounce Clip to Disk” function

The “Bounce Clip to Disk” function becomes available when a single Audio Clip is selected (in Arrange Mode or Edit Mode). The function allows you to bounce single Audio Clips, after the Clip Level and Fades but without the Mixer Channel settings, to disk for further processing in an external application, for example. Do like this to bounce an audio clip to disk:

1. **Select an Audio Clip and choose “Bounce Clip to Disk...” from the Edit menu or context menu.**
The “Bounce Clip As Audio File” dialog appears. It looks the same, and has the same functionality, as the “Export Song as Audio File” and “Export Loop as Audio File” dialogs.




2. **Choose location, File Name and File Format (AIFF or WAV) for the bounced audio clip at the bottom of the dialog and click "Save".**
   (The default name in the dialog is the Clip name + extension, or (if there's no name label on the clip) the track name + extension.)



Choose a file name and select file format.

3. **Select "Sample Rate", "Bit Depth" (resolution) and "Dither" in the "Export Audio Settings" dialog and click "OK":**
   If you are exporting at 16-bit Bit Depth you will have the option of applying Dither. Dither means that a type of noise is added to the digital signal to improve low level sound quality when exporting high resolution audio at a lower bit depth. Reason features a new, and very sophisticated, dithering algorithm with noise shaping.

- **Tick the "Dither" check box to improve the audio quality of exported audio at 16-bit resolution.**



Select Sample Rate, Bit Depth and Dithering of the audio clip to be bounced.

The exported audio file will also contain tempo data as described in "About Tempo data in exported audio files".

About the "Bounce Clip to New Sample" function

You can bounce an Audio Clip to a new Song Sample if you like. You could then edit the sample and load into a sampler device for playback.

See "Bounce Clip(s) to New Sample(s)" in the "Audio Editing in the Sequencer" chapter for more details.

About the "Bounce Clip to New Recording" function

You can also bounce an Audio Clip to a new recording on an additional Comp Row in the Audio Clip. This is like a non-destructive "Flatten" operation. It will create a new recording from the clip output - ignoring Clip Level and Clip Fade In/Out settings. The recording will be placed on a new Comp Row at the top of the Comp Row list in the clip. The Audio Clip will then automatically switch to Single Mode.

See "Bounce Clip(s) to New Recording(s)" in the "Audio Editing in the Sequencer" chapter for more details.

About the "Bounce Clip to REX Loop" function

A Single Take clip, which is open for inline editing, features the function "Bounce Clip to REX Loop" on the Edit and context menu. This allows you to generate a REX loop out of the Single Take audio clip. The REX loop can then be used in a Dr Octo Rex device in Reason and/or be exported to disk.

See "Bounce Clip to REX Loop" in the "Audio Editing in the Sequencer" chapter for more details.

Chapter 22
Sampling



About this chapter

This chapter describes how you can sample, edit samples and manage your samples in your songs. For more information about the specific devices that can sample and play back samples, please refer to the "NN-XT Sampler", "NN-19 Sampler", "Redrum Drum Computer", "Kong Drum Designer", "RV7000 Mk II Advanced Reverb", "Europa Shapeshifting Synthesizer", "Grain Sample Manipulator" and "Mimic Creative Sampler" chapters.

Overview

The sampling feature allows you to sample external audio (or internally from the outputs of any device) and use in any of the Reason devices that support sample files.

One-click sampling

The sampling workflow has been designed to be as quick and easy as possible, so you don't lose any inspiration. Regardless which device you use, sampling can be instantly accessed by simply clicking, or by clicking and holding the Sampling button(s) on these devices:




Start Sampling buttons on NN-XT, NN19, Redrum and Kong respectively.

See "Sampling procedure" for more details on how to sample.

The Edit Sample window

All sampling parameters and functions are controlled from one single window - the Edit Sample window. This window is used when you're editing samples in any of the devices described above, See "Editing samples" for more details.



The Edit Sample window with a sample.

About sample format, rate and resolution


Whenever you sample in Reason, the resulting audio files are stored in WAV format. The sample rate is determined by the settings on the Audio tab in Settings (see "Audio settings"). The resolution (bit depth) is fixed at 16 bits.

Reason is totally agnostic about what sample rate you use. If you like, you can change the sample rate at any time without affecting the pitch, playback speed etc. of your samples. What you have once sampled will always sound the same, regardless of the current audio settings.

General sampling functions

Setting up for sampling

If you want to sample external audio, e.g. from a mic or an instrument connected to the audio hardware on your computer, make sure you have set up the desired audio input(s) on the Audio tab in Settings, see "Settings – MIDI". Available audio inputs are indicated with yellow or green LEDs on the Hardware Interface in the rack:



Selecting audio input source(s)

To set up for sampling, you first need to make some connections on the Hardware Interface:

1. **Navigate to the Hardware Interface and press [Tab] to flip the rack around.**
2. **Patch cables to the Sampling Inputs as follows:**

- ▶ **To sample external audio, connect the desired Audio Input connector(s) to the Sampling Input connector(s) to the left on the rear of the Hardware Interface.**
- ▶ **To sample the audio of a device in the rack, connect cables from the audio output(s) of the device to the Sampling Input connector(s) on the Hardware Interface.**
- ▪ **To sample in stereo, connect to both the Left and Right Sampling Input connectors.**
- ▪ **To sample in mono, connect only to the Left or Right Sampling Input connector.**



Audio Inputs 1&2 connected to Sampling Inputs L&R for sampling in stereo.


Setting audio input level

Once you have made the desired connections to the Sampling Input(s) on the Hardware Interface, it's important to check the audio input level to avoid clipping. If you are going to sample external audio via the audio hardware of your computer, you have to adjust the level at the source, i.e. on the pre-amp of the audio hardware (or connected instrument). A good suggestion is to use the Big Meter on the Hardware Interface to be able to monitor the input level(s) more easily.

- ▶ **Adjust the level at the source and make sure the level doesn't exceed 0 dB to avoid clipping.**




- ▶ **If you sample internally, from the output(s) of a device in the rack, adjust the Output Level on the source device and check the levels with the Sampling Inputs selected on the Big Meter:**



Monitoring and Monitor Level

To the left on the Hardware Interface are two buttons and one knob for monitoring the signals on the Sampling Inputs:



- ▶ **Click the Monitor button to activate monitoring of the signals present at the Sampling Inputs.**
  Monitoring will always be active, regardless of if you sample or not.
- ▶ **Click the Auto button to activate monitoring only during sampling.**
  Monitoring will only be active during the actual sampling. When you don't sample, monitoring will be off.
- ▶ **Turn the Monitor knob to adjust the monitor signal level.**

! **The Monitor Level knob does not affect the level of the audio to be sampled - only the monitored signal.**

Sampling

The Sample buttons

The NN-XT, NN19, Redrum, Kong, Grain and RV7000 Mk II devices feature one or several Sample buttons. The Sample buttons are located on the devices as follows:



Sampling buttons on NN-XT, NN19, Redrum and Kong respectively.


Sampling procedure

1. **Make sure you have made the necessary connections and set the levels according to the descriptions in "Setting up for sampling".**
2. **Click the Sample button on the device you want to sample to.**

▶ **Alternatively, click and hold the Sample button depressed for as long as you want to sample.**
When you use the "click and hold" method, sampling will be automatically terminated as soon as you release the mouse button. The sample will then end up in the device and in the Song Samples location in the Browser.

! **If you're sampling into a Redrum, make sure you click/hold the Sample button for the desired drum channel.**


A waveform display shows up with a moving "play head":



3. **Start playing or singing what you want to sample.**
As soon as any audio is present on the Sampling Inputs on the Hardware Interface, the waveform display will indicate this by drawing a wave.

! **The buffer size for sampled audio is 30 seconds. After 30 seconds, the play head will start over again from the beginning and start erasing any previously sampled audio.**

▶ **If you want to restart the sampling manually, click the Restart Sampling button:**




The "Restart Sampling" button.

This will erase any sampled audio and force the play head to restart from the beginning.

! Note that you cannot restart sampling this way if you use the "click and hold" sampling method.

4. When you're satisfied with your recording, click the Stop Sampling button in the waveform display.




The "Stop Sampling" button.

The waveform display closes and the sample automatically ends up in the device, where you can play it back instantly:



By default, the sample is named "Sample 'n'" where 'n' is a serial number. As you will notice, any silence preceding the actual audio in the sample will be automatically disregarded. The entire sample is preserved, but this is done so you won't have to edit the sample start before playback.


Besides ending up in the device, the sample is also placed under the corresponding device icon in the Assigned Samples folder in the Song Samples location in the Browser:



Here, all samples you use in your song are listed (see "The Song Samples location"). Here is also where you can open samples for editing (see "Editing samples").

The Song Samples location

The Song Samples location in the Browser is where all samples in your song are listed and can be accessed for preview and editing purposes. Besides your own samples, all Factory samples and any ReFills samples used in the song are also accessible for previewing and editing!



The Song Samples location in the Browser.

The Song Samples location in the Browser contains the following items:

- **Assigned Samples folder**
  Here, all samples that are assigned to devices in the song are listed. All devices that contain assigned samples are listed as "sub-folders". Each device "sub-folder" shows the samples currently assigned to it. See "Assigned Samples" for more details.
- **Unassigned Samples folder**
  If you remove a sound you have sampled from a device, the sound is automatically moved from the Assigned Samples folder to the Unassigned Samples folder. From here you can load the sample into other devices if you like. See "Unassigned Samples" for more details.
- **All Self-contained Samples folder**
  All sounds you have sampled yourself, plus any duplicated samples from the Factory Soundbank and/or ReFills, automatically becomes self-contained and are always stored with the song. These samples are listed in the All Self-contained Samples folder. See "About self-contained samples" for more details.
- **Import button**
  Click this button to import the selected sample(s) to audio tracks in the sequencer.
- **Play and Auto buttons**
  To audition a sample, select it in the Browser list and click the Play button. If you click the Auto button, simply selecting a sample in the list will automatically play it back.
- **Volume slider**
  Adjust the preview volume of the sample with the slider. This does not affect the samples original volume.

The context menu of a selected sample contains the following functions:


- **Edit Sample**
  Select this to open the sample for editing in the Edit Sample window (see "The Edit Sample window"). If several samples are selected, this item is grayed out.
- **Duplicate Sample(s)**
  Select this to create a duplicate of the selected sample. The duplicated sample is placed in the All Self-contained Samples and Unassigned Samples folders. Several selected samples can be duplicated in one go. See "Duplicating samples" for more details.
- **Export Sample(s)**
  Select this to export the selected sample to disk. A dialog appears where you can select file format. Note that it is not possible to export samples from the Factory Soundbank or from ReFills. Several selected samples can be exported in one go. See "Exporting samples" for more details.
- **Delete Sample(s)**
  Select this to permanently delete the selected sample(s) from the song. Note that samples from the Factory Soundbank and from ReFills will not be deleted from their original locations - only from the song document. Several selected samples can be deleted in one go. See "Deleting samples from a song" for more details. Any samples you have recorded yourself will be permanently erased unless you have previously exported them to disk (see "Export Sample(s)" below).



Editing samples

The Edit Sample window


Any sample present in the All Self-contained Samples folder in the Song Samples location in the Browser can be edited.



- ▶ **Right click a sample in the Item List and select "Edit Sample" to open the sample in the Edit Sample window.**
- ▪ **You can also open a sample for editing by holding down [Alt](Win) or [Option](Mac) and clicking the Start Sampling button on the device panels:**



Start Sampling buttons on NN-XT, NN19, Redrum and Kong respectively.



The Edit Sample window with an open sample.

The Edit Sample window can be resized in all directions by clicking and dragging the window frame. If you resize the window vertically, the displayed waveform will be resized vertically as well.

- **Undo and Redo buttons**
  The Undo and Redo buttons work like the regular undo and redo functions in the main window menu, but these are used locally only for the Sample Edit window. The number of Undo and Redo steps in the Sample Edit window are limited to 10. Once you have clicked the Save button, you can still undo the entire sample editing procedure by using the Undo function in the main window.
- **Crop button**
  Click the Crop button to crop the sample so that only the content between the Start (S) and End (E) locators is preserved. The rest of the sample will be permanently deleted. See "Cropping samples" for more info.
- **Normalize button**
  Click the Normalize button to amplify the entire sample so that the loudest peak touches 0 dB. Note that the entire sample is normalized, regardless of any locator settings. See "Normalizing samples" for more info.
- **Reverse button**
  Click the Reverse button to reverse (play backward) the entire sample. Note that the entire sample is reversed, regardless of any locator settings. See "Reversing samples" for more info.
- **Fade In and Fade Out buttons**
  The Fade In and Fade Out buttons can be used to apply a fade in or fade out of the sample volume. See "Fading in/out samples" for more info.
- **Loop Mode buttons**
  Click one of the Loop Mode buttons to select loop type. The default (leftmost) setting is "no loop". Then follow "Loop Forward" and "Loop Forward + Backward". See "Looping samples" for more info.
- **Waveform pane**
  Here, the currently open sample is displayed as one (mono) or two (stereo) waveforms. The Start (S) and End (E) locators are also displayed. By default the Start locator is placed where the audio begins in the sample. This means that if you have started sampling before there were any audio present, the playback will automatically start where the audio begins. This way you won't have to manually move the Start locator in most situations.
- **Waveform Navigator**
  Below the waveform pane is the horizontal Waveform Navigator. This can be operated in the same way as the Song Navigator in the sequencer (see "Scrolling with the scrollbars and Navigators", "Zooming horizontally in the Sequencer" and "Scrolling and zooming using a wheel mouse").
- **Set Sample Start/End button**
  Set the desired sample playback region by clicking and dragging on the waveform pane. Then, click the Set Sample Start/End button to automatically place the Start and End locators at the beginning and end of the sample region. See "The Set Start/End function" for more info.
- **Snap Sample Start/End To Transients button**
  Click the Snap Sample Start/End To Transients button to make the Start and End locators snap to suitable transients in the sample as you move the locators. This makes it easier to find appropriate start and end locations for the sample playback.
- **Crossfade Loop checkbox**
  Tick the Crossfade Loop box to introduce a crossfade in the loop. Crossfade is useful to even out any clicks in the loop points, especially for sounds with fairly even volume throughout the loop region. See "The Crossfade Loop function" for more info.
- **Set Loop button**
  Set the desired loop region by clicking and dragging on the waveform pane. Then, click the Set Loop button to automatically place the Left and Right Loop locators at the beginning and end of the loop region. See "The Set Loop function" for more info.



- **Play button, Solo checkbox and Volume slider**
  Click the Play button to play back the sample from the current position of the play head until the end of the sample. As soon as playback is started the button switches to display Stop instead, giving you the option of stopping playback. This is especially useful if your sample is looped. As an alternative to clicking the Play/Stop button you can press [Spacebar] to toggle between Play and Stop.


  Tick the Solo checkbox to solo sample playback. This is useful if your song is playing in the background and you only want to listen to the sample.

  Adjust the sample playback volume with the Volume slider to the right.
- **Root Key**
  Set the sample Root Key (pitch) by clicking the spin controls, or by entering the desired note value in the display. If you know what note your sample is, select that note here. When you open the sample in a sampler device, the device will automatically transpose the sample correctly across the keyboard.
- **Name**
  Type in desired name for your sample. Note that this will overwrite the original name of the sample in the Song Samples location in the Browser once you click Save. See "Renaming samples" for more info.
- **Save and Cancel buttons**
  Click Save to save your sample. The sample will appear in the Song Samples location in the Browser. See "Saving edited samples" for more info.

  Click Cancel to exit the Edit Sample window and discard from any edits you've made in the current sample.

Setting Sample Start and End

1. **Open the sample by selecting it in the Browser list and clicking the Edit button - or select "Edit Sample" from the context menu.**
   The sample opens in the Edit Sample window.



   If you have recorded the sample yourself in Reason, the Start (S) locator has been automatically placed at the first significant transient in the sound. The play head is also automatically placed at the Start locator.

2. **If necessary, adjust the Start locator by clicking and dragging it back or forth in the Edit Sample window ruler.**
   Play back the sample by clicking the Play button, or by pressing the [Spacebar].


- **To make it easier to fine adjust the locators, it could be wise to magnify the waveform pane horizontally using the Waveform Navigator. The Waveform Navigator works exactly as the Song Navigator in the Sequencer - see** "Zooming horizontally in the Sequencer" and "Scrolling and zooming using a wheel mouse".
- **Tick the "Snap Sample Start/End To Transients" check box if you want the locators to snap to significant transients in the sample.**

3. **Adjust the End locator by clicking and dragging it back or forth in the Edit Sample window ruler.**

The Set Start/End function


Another way of defining a sample's start and end positions is by using the Set Start/End function:

1. **Set the desired sample playback zone by clicking and dragging on the waveform pane.**



The defined zone is highlighted in blue color.

2. **Click the Set Sample Start/End button.**



The Start and End locators are automatically placed at the beginning and end of the defined playback zone.

3. **Click anywhere on the Waveform pane to remove the highlight.**

Cropping samples

Cropping a sample means deleting parts you don't want to keep, e.g. any silence in the beginning and/or in the end of a sample. The Crop function in the Edit Sample window deletes everything except what's in between the Start and End locators, or everything outside any highlighted part of the sample. To crop a sample, proceed as follows:

1. **Set the Start and End locators where you want them - see "Setting Sample Start and End".**
   Alternatively, click and drag in the Edit Sample window to highlight the section you want to keep.
2. **Click the Crop button in the Edit Sample window.**



- **If you highlighted a section by clicking and dragging in the Edit Sample window, everything except the highlighted part gets permanently deleted.**
- **If you didn't highlight a section of the sample, everything before the Start locator and after the End locator gets permanently deleted.**

Normalizing samples

Normalizing means amplifying the volume of the sample so that the loudest peak in the sound touches 0 dB. The Normalize function normalizes either the entire sample, or the highlighted part of the sample.

1. **Click and drag in the Edit Sample window to highlight the part of the sample you want to normalize.**
   To normalize the entire sample, you don't have to do anything.
2. **Click the Normalize button in the Edit Sample window.**



- **If you highlighted a section of the sample, the highlighted part gets normalized.**
- **If you didn't highlight a section of the sample, the entire sample gets normalized regardless of any Locator settings.**
  Since the entire sample is normalized, this means that any noise present in the sound will also be amplified.


  After the Normalize operation, the waveform is redrawn with the new volume values.

! **Note that normalizing a sample that already use the full headroom (touches 0 dB) won't have any effect.**

Reversing samples

Reversing a sample means playing it backwards, from the end to the start. The Reverse function reverses either the entire sample, or the highlighted part of the sample.

1. **Click and drag in the Edit Sample window to highlight the part of the sample you want to reverse.**
   To reverse the entire sample, you don't have to do anything.
2. **Click the Reverse button in the Edit Sample window.**




- **If you highlighted a section of the sample, the highlighted part gets reversed.**
- **If you didn't highlight a section of the sample, the entire sample gets reversed regardless of any Locator settings.**
  After the Reverse operation, the waveform is redrawn with the reversed shape.

Fading in/out samples

Using short fades is useful if you want to remove clicks or pops in the beginning and/or end of the sample. You can also create longer fades to make a sound fade in and/or out nice and smoothly.

1. **Set the desired Fade In (or Fade Out) zone by clicking and dragging on the waveform pane.**




The defined zone is highlighted in blue color.

2. **Click the Fade In (or Fade Out) button.**



Clicking the Fade In button creates a fade in from complete silence at the beginning of the highlighted zone to the current volume at the end of the highlighted zone:



Clicking the Fade Out button creates a fade out from the current volume at the beginning of the highlighted zone to complete silence at the end of the zone.

After the Fade operation, the waveform is redrawn with the new volume values.

3. **Click anywhere on the Waveform pane to remove the highlight.**

Looping samples


Looping a sample means playing back the sample from the start and then playing back a defined zone in the sample over and over again (usually for as long as a key is depressed on the MIDI master keyboard). In practice, looping samples can be used to create "longer" sounds out of shorter ones. For example, if you have a flute sample you may want to loop the middle part of it so that you could make the sound sustain as for long as you like.

There are two different loop modes available in the Edit Sample window (besides the default non-loop mode):

- **Loop Forward**
  In Loop Forward mode the sample is played back from the Start locator to the Right Loop locator, then playback starts over from the Left Loop locator and continues to the Right Loop locator over and over again.
- **Loop Forward + Backward**
  In Loop Forward + Backward mode the sample is played back from the Start locator to the Right Loop locator, then the playback is reversed from the Right Loop locator to the Left Loop locator and then forward again to the Right Loop locator over and over again.


Adjusting the Loop locators

1. **Click the Loop Forward or Loop Forward + Backward button.**



The Left (L) and Right (R) Loop locators appear on the Waveform pane.

2. **Play back the sample and adjust the Loop locators to your liking.**
   If necessary, zoom in horizontally to more easily find suitable loop positions.




▶ **To make loops sound smoother, try using crossfades as described in "The Crossfade Loop function".**

The Set Loop function


Another way of defining a sample's loop positions is by using the Set Loop function:

1. **Set the desired loop zone by clicking and dragging on the waveform pane.**



The defined zone is highlighted in blue color.

2. **Click the Set Loop button.**
   The Left and Right Loop locators are automatically placed at the beginning and end of the defined zone.



3. **Click anywhere on the Waveform pane to remove the highlight.**

▶ **To make loops sound smoother, try using crossfades as described in "The Crossfade Loop function".**

The Crossfade Loop function

Crossfades are useful for evening out clicks or transients at the loop points, especially in sounds with fairly constant volume throughout the loop zone. The Crossfade Loop function creates smooth volume crossfade around the Loop Locators.

▶ **Tick the Crossfade Loop box to automatically introduce a crossfade in the loop.**




- **When the Crossfade Loop function is active, moving the Left and/or Right Loop Locators will force them to automatically "snap" to suitable loop positions. If you move the Left Loop Locator, the Right Loop Locator will automatically self-adjust to a suitable loop position.**
  This way you will quickly reach a good result.

▶ **Experiment by alternating the Loop Modes between Loop Forward and Loop Forward + Backward. Just changing Loop Mode can make the loop transitions much smoother in many situations.**


▶ **A general tip when trying to create a smooth loop is to locate the loop zone where the volume and timbre is fairly constant over time. Big changes in volume and/or timbre in the loop zone will often result in quite pronounced or strange "pulsating" loops. Also, very short loop zones often tend to sound unnatural and "static".**

Saving edited samples

▶ **Click the Save button in the Edit Sample Window to save your edited sample.**




The sample is saved, complete with all the edits you have made in the Edit Sample Window (Start, End, Loop settings, Name etc.) The sample will appear in the Song Samples location in the Browser, with the new name if this has been changed.



! **If you have opened and edited a ReFill sample, a copy of this sample (including any edits) will be saved with its original name in the All Self-contained Samples folder.**

Renaming samples

1. **Type in the desired name of your sample in the Name field in the Edit Sample Window.**



2. **Click the Save button to save the sample with the new name.**


! **Note that saving a sample under a different name will simply replace the current name - it will not create a copy of the original sample!**

Sample management

About Assigned and Unassigned samples

Assigned Samples


Samples can be assigned to devices that support sample playback, such as the NN-XT, NN19, Redrum and Kong. Samples that are assigned to a device can be found in the Assigned Samples folder in the Song Samples location in the Browser:



The Assigned Samples folder can contain various sub folders, one for each sampler device used in the current song. The song in the picture above contains two sampler devices; the "NN-XT 1" and the "Redrum 1". The instrument folders can be unfolded to display their current sample contents. Sounds you have sampled yourself as well as samples from the Factory Soundbank and from ReFills are displayed with icons.

Unassigned Samples


Samples that have been removed from a sampler device and have not (yet) been assigned to another sampler device are displayed in the Unassigned Samples folder:



Unassigned samples can be assigned to any sampler device by simply loading them into a sampler device - see "Loading samples into a device".

Saving samples in a song

When you have recorded a sample, by clicking a Sample button on a sampler device, the sample is automatically stored in the All "Self-contained Samples" folder in the Song Samples location in the Browser:



The samples you have recorded are automatically named "Sample 'n'" where 'n' is a serial number.

You can rename a sample by right clicking it in the All Self-contained Samples folder, selecting "Edit Sample", and then re-naming it in the Edit Sample Window and then clicking the Save button:



As soon as you save your song, all samples you have recorded will be automatically saved as self-contained samples in the song document. This way you don't have to keep track of any "loose" samples on your computer.

Deleting samples from a song

It's only possible to delete samples you have recorded yourself in a Reason song, i.e. samples that are located in the All Self-contained Samples folder in the Browser. Samples from the Factory Soundbank and from ReFills cannot be deleted because they are contained in ReFills.

- ▶ **To delete a sample in the All Self-contained Samples folder, right click it and select "Delete Sample(s)" from the context menu.**
- ! **Since the selected sample also exists, either in the Assigned Samples folder or Unassigned Samples folder, it will be deleted from there as well. Similarly, if you select and delete a non-Factory Soundbank/ReFill sample from the Assigned Samples folder or Unassigned Samples folder, it will be deleted from the All Self-contained Samples folder as well.**

Loading samples into a device


To load samples into a sampler device (NN-XT, NN19, Redrum, Kong and RV7000 Mk II) proceed as follows:

1. **Click on a Browse Sample button on the device.**




Browse Sample buttons on NN-XT, NN19, Redrum and Kong respectively.

2. **Navigate to the desired location in the Browser.**
   In the picture below, we have clicked the Song Samples location and expanded all folders and subfolders:



3. **Select the sample you want to load into your device.**
   You can select a sample in any of the folders. If you like to audition a sample, click the Play button below the Browser list. To make samples automatically play upon selection, click the Auto button.

4. **Double click the sample to load the selected sample into the device.**
   When the selected sample has been loaded into the device, the Browser closes. If you open the Browser again you will see that the corresponding sample file icon in the Browser has been placed under the device's icon in the Assigned Samples folder. If the loaded sample was originally in the Unassigned Samples folder, it has now been moved from this folder to the Assigned Samples folder:




"Sample 1" has now moved from the Unassigned Samples folder to the NN-XT 1 "folder" in Assigned Samples.

Duplicating samples

If you want to use an existing sample as base for new edits, you can do this by first duplicating the existing sample and then performing the edits on the duplicate. It's even possible to duplicate samples from the Factory Soundbank and from any existing ReFills! However, duplicated samples from the Factory Soundbank or from ReFills cannot be exported to disk as separate files, but can only be saved as self-contained samples inside the song document.


To duplicate a sample, proceed as follows:

▶ **Right click the desired sample in the Song Samples location in the Browser and select "Duplicate Sample(s)" from the context menu.**



Selecting "Sample 5" for duplication.

The duplicated sample appears - with its original name followed by the word "Copy" - in the All Self-contained Samples folder. The sample also appears in the Unassigned Samples folder:



To edit and/or rename the duplicated sample, refer to "Editing samples" and "Renaming samples".


Exporting samples

If you like you can export samples that you have recorded in your song and save them as separate WAV or AIFF files to disk. Proceed as follows:

1. **Select desired sample(s) in the Song Samples location in the Browser.**


! **Note that it is not possible to export samples that originate from the Factory Soundbank or from a ReFill.**

2. **Select "Export Sample(s)" from the context menu.**



Selecting "Sample 5" for export.

- **If your sample(s) are not cropped, or use a Crossfade Loop, the Lossy Sample Export dialog appears:**



The following options are available:

- **Crop selected sample(s) and render loop crossfades**
  This item shows up if you have edited the Start and/or End Markers and use a Loop with Crossfades. The sample will be cropped at the Start and End Markers and the crossfaded loop will be rendered into the sample.


! **This will make the sample sound exactly the same when you import it to a sample playback device/application, but the sample data has been changed compared to the original.**

- **Crop selected sample(s)**
  This item shows up instead of the above item if no Loop is used. The sample will be cropped at the Start and End Markers.

- **Save raw sample(s)**
  The sample will be exported without Start or End Marker position data but with Loop data, if any. If the loop is crossfaded, the crossfade will be removed.

! **This will make the sample sound differently when you import it to a sample playback device/application.**

3. **Click Export to proceed.**
   The "Export Sample as..." dialog appears;




4. **Choose location for your sample file, type in desired name and choose WAV or AIFF file format.**
5. **Click Save to export the sample file to disk.**
   The sample is saved to disk using its original resolution (bit depth) and sample rate. The original self-contained sample in your song will remain intact.

About self-contained samples

All samples you record in a song automatically become self-contained. Self-contained means that the samples are automatically stored within the song when you save it. A great advantage with this is that you never have to keep track of any "loose" custom samples you use in your song - they are always included in the song document.

All self-contained samples in a song can be viewed by unfolding the All Self-contained Samples folder in the Song Samples location in the Browser:



Self-contained samples can also be loaded into any sampler device from the Browser. See "Loading samples into a device" for more details.

Un-self-containing samples

There might be situations where you want to "un-self-contain" your own samples, i.e. export the samples to disk as separate files and at the same time remove them from the song document. This can be done by selecting "Song Self-Contain Settings..." from the File menu - see "About Self-Contained Songs" for more details.



Chapter 23
The ReGroove Mixer

Introduction



The ReGroove Mixer combines all the benefits of quantization, shuffle, and groove templates into a single integrated environment, giving you real-time creative control over the feel and timing of individual note lanes. The ReGroove Mixer, which extends from the top of the Transport Panel puts 32 channels of interactive groove control at your fingertips.

If you're familiar with mixing, you're already well on your way toward understanding the ReGroove Mixer. Think of it as a mixer with 32 busses but, instead of these busses modifying the volume of the input tracks, they modify the feel (or groove) of the input tracks. You can route any note lane to one of ReGroove's 32 channels, and that lane's feel and timing are modified, in real-time, by the channel's settings. Each ReGroove channel can use its own groove template or shuffle amount. In addition, each channel can slide notes forward or backward in time, allowing you to put certain tracks slightly ahead or behind the beat, which greatly alters the feel of your music.


! **Note that ReGroove only works for notes on note lanes.**

▶ **It's also possible to lock a control surface to control the ReGroove Mixer parameters via Remote - see "Locking a surface".**

ReGroove basics

When working with grooves, you'll make use of three interacting sections within Reason's interface:

- **First, in the Sequencer, each note lane can be assigned to any of ReGroove's 32 channels.**
  You assign a note lane to a groove channel by selecting it with the Select Groove pop-up in each note lane.




- **Second is the ReGroove Mixer, which contains both global groove settings and channel-specific ones.**
  This is described on the following pages.
- **Finally, there's the Groove Settings section, which is accessed by clicking a ReGroove channel's Edit button.**
  Groove Settings allow you to set the intensity of various groove patch parameters. This is also where you save your own ReGroove patches. See "Groove Settings".

The ReGroove Mixer

▶ **Open the ReGroove Mixer by clicking the Groove button in the top bar.**



The ReGroove mixer is divided into three sections. On the left are the Global parameters, in the middle are the Channel parameters, and to the right are the Groove Settings parameters:



Global parameters



These parameters operate globally, rather than channel-by-channel.

Channel Banks

The ReGroove mixer consists of 32 channels, grouped into 4 banks (labeled A through D). Click a Channel Bank button to see and edit its corresponding bank of 8 channels.

Anchor Point

Normally, all groove patterns start at Bar 1 and repeat themselves throughout a song. For example, a 4-bar groove pattern will begin at Bar 1 and repeat its pattern every four bars. Many times, however, songs begin with blank measures, pickup measure or, perhaps, a short introduction. In these cases, you probably don't want the groove pattern to begin at Bar 1, but at some later bar. This is the purpose of the anchor point - it tells Reason at which measure it should begin applying the groove settings.

For example, assume you have a song with a 1-bar pickup. Because the song really begins on bar 2, that's where you want your groove to begin. Setting the anchor point to 2 insures that the groove patterns all begin at measure 2.

- **Note: There is one exception to the rule that grooves start playing at their anchor point and repeat indefinitely throughout the song-and that's when they encounter a time-signature change. Grooves always restart at any measure containing a time signature change.**
  You can use this knowledge if, for example, you have a song section with an odd number of bars-inserting a time signature change will force all your grooves to restart at that measure.


Global Shuffle

This knob adjusts Reason's global shuffle amount, and is used by any devices that employ patterns, such as the Dual Arpeggiator Player device, Redrum's internal sequencer, the Matrix pattern sequencer, and the RPG-8 arpeggiator. It also defines the shuffle value for any ReGroove channel for which the Global Shuffle option is activated.

Setting the Global Shuffle to a value of 50% results in a "straight" beat, with no swing applied. Setting the Global Shuffle to a value of 66% results in a perfect sixteenth-note triplet shuffle. Values between 50% and 66% have a less pronounced swing feel, and values greater than 66% are more exaggerated.

- **If you are quantizing notes and/or audio Slices to "Shuffle" in the "Quantize" sections, these are quantized to the current Global Shuffle value.**

Channel parameters



These parameters operate on a per-channel basis. Each of ReGroove's 32 channels (arranged in 4 banks of eight) contains an identical set of parameters.

On Button

This is an On/Bypass button for the channel. When the button is lit, the groove channel is active and any note lane assigned to this groove channel will be affected. When the button is not lit, the channel is disabled and any note lanes assigned to this groove channel will play back straight, without being "grooved."

- **This can be used for comparing the groove with the original, ungrooved beat. You can also do this for individual note lanes, by turning off the "Enabled" item on the Groove Select pop-up menu in the track list - see "Applying grooves to your music".**

Edit Button

Click this button to select the channel for editing in the Groove Settings section to the far right, where you can view and edit additional "Groove Settings" for each channel.

Each ReGroove channel has its own groove settings, so clicking the Edit button in different channels will fill the Groove Settings section with groove settings specific to that channel.

Channel Number

This is a non-editable channel number label. Channels are numbered 1-8 and are grouped into 4 banks (A-D). Channel numbers are named accordingly. For example, A2 is the second channel in Bank A, and B5 is the fifth channel in Bank B.

Groove Patch Name

This shows the name of the groove patch currently loaded into the channel. If no groove patch is loaded, then no name appears. Click this area to bring up a list of the patches in the current folder, just as with patch displays on devices in the Reason rack.


- **To remove a groove patch assignment and reset the channel to its default values, right-click (Win) or [Ctrl]-click (Mac) the Groove Patch name, or anywhere on the ReGroove panel background, and select "Initialize Channel" from the context menu.**

Groove Patch Browser

This allows you to load groove patches and to step between them, just like device patches in the Reason rack. ReGroove patches have a '.grov' file extension. See "ReGroove patches in the Factory Sounds bank", later in this chapter, to learn more about the types of groove patches included with Reason.

Slide

Use this knob to slide notes forward or backward in time. Musicians will frequently add energy and urgency to a track by "rushing" a particular beat or instrument a little. Similarly, they may "drag" a note a little in order to create a more laid back, shuffle-like feel. The Slide knob has a range of ±120 ticks, which allows you to slide notes up to a thirty-second note in either direction. Setting negative values makes notes play earlier in time (rushing the feel). Setting positive values makes notes play later in time (lagging the feel).



For example, if you wanted to create a slightly "in the pocket" groove, you could create a snare lane and assign it to a ReGroove channel with a small amount of positive slide. This would delay the snare track slightly, giving your music a relaxed, laid back feel.

- **If you have a track that you want to rush (set to a negative slide value), you should put an empty bar at the beginning of your sequence, making sure to set the Anchor Point to "2" (see "Anchor Point"). This insures that any notes assigned to Bar 1/Beat 1 will indeed play ahead of the beat (since you created an empty measure into which the early note can shift).**

Shuffle

At its most basic level, this knob adds a sixteenth note "swing" feel to the ReGroove channel. A value of 50% results in a straight (no shuffle) feel, and a value of 66% creates a perfect triplet feel.



Shuffle works by changing the start time of every other sixteenth note.



A shuffle value of 66% delays every other sixteenth note to create a perfect triplet feel.

You can also use this knob to "de-shuffle" a beat by dialing in values below 50%. For example, if you had a recording that was played with a perfect triplet feel, setting the Shuffle value to 34% will make the beat straight again!


Groove Amount

Use this fader to adjust how intensely the selected groove patch should modify your notes. At 0%, the groove patch will have no effect. At 100%, the groove patch will have its maximum effect. Obviously, values between these extremes will produce some amount of groove effect, but less than maximum.

As discussed in "Groove Settings", later in this chapter, several additional parameters are associated with groove patches and how they modify your notes. Specifically, the Groove Settings section contains four "impact" settings (timing, velocity, note length, and randomness), and the Groove Amount fader acts like a "master" fader that scales these four parameters proportionally.



A Groove Amount of 100% modifies notes using all groove settings at their specified amounts.



A Groove Amount of 50% modifies notes using all groove settings at only half their specified amounts.

Pre-Align

Enabling this button causes any incoming notes to be quantized to a rigid, sixteenth note grid prior to having any additional groove modifications applied to them. This quantization, which occurs in real time and is non-destructive, is an easy way to align all incoming notes to a "straight" grid, so that any shuffle, slide, or groove modifications have the expected effect on the notes.

Global Shuffle

Enabling this button causes the ReGroove channel to use the "Global Shuffle" setting, rather than the channel's own shuffle setting. The channel's Shuffle knob will have no effect when a channel uses global shuffle. Using global shuffle is a good way to synchronize notes in a particular channel with those in pattern-based devices, such as Redrum's internal sequencer, the Matrix pattern sequencer, and the RPG-8 arpeggiator, all of which get their shuffle values from the Global Shuffle value.

Copy, Paste and Initialize ReGroove channels

To copy one ReGroove channel configuration into another:

1. **Decide which ReGroove channel you want to copy from, then right-click (Win) or [Ctrl]-click (Mac) on the Groove Patch Name (or anywhere else in that channel, except directly on a parameter).**
2. **Select "Copy Channel" from the context menu.**
3. **Right-click (Win) or [Ctrl]-click (Mac) on the destination channel's Groove Patch Name, then select "Paste Channel" from the context menu.**
   Reason copies all the ReGroove channel settings to this channel.

To initialize a ReGroove channel:

1. **Right-click (Win) or [Ctrl]-click (Mac) on the Groove Patch Name (or anywhere else in that channel, except directly on a parameter) to open a context menu.**
2. **Select "Initialize Channel" from the context menu.**
   Reason resets all channel parameters to their default values.

Groove Settings



A groove patch consists of a groove template, which contains timing and dynamics information extracted from a performance, plus a collection of Impact parameters, which determine how strongly the groove patch applies the template settings. This section discusses the settings in the Groove Settings section to the right of the ReGroove Mixer panel, where all the Groove Patch settings can be viewed and edited.

Groove channel

The Groove Settings display one ReGroove Channel at a time. To select which ReGroove channel is currently displayed, select it by dragging up/down in the Edit Channel display (or click the Edit button for the channel in the ReGroove Mixer).

Groove Patch name

This shows the name of the groove patch currently loaded into the channel. If no groove patch is loaded, then no name appears. Click this area to bring up a list of the patches in the current folder, just as with device patches in the Reason rack. This area duplicates the functionality of the Groove Patch Name area in each channel of the ReGroove Mixer.

Groove patch Load/Save

These buttons allow you to load and/or save groove patches, just like device patches in the Reason rack. ReGroove patches have a '.grov' extension. To learn more about the types of groove patches included with Reason, see "ReGroove patches in the Factory Sounds bank".

Groove patch Length

This displays the groove's length, which is import for determining how often the groove repeats.

- **In general, if you apply different groove patches to different note lanes, you'll want their lengths to be multiples of one another.**
  For example, if one ReGroove channel uses a 4-bar groove, you might want to use 4-bar grooves on other channels or, perhaps, a multiple (such as 1-bar, 2-bar, or 8-bar grooves).
  You can, of course, mix and match grooves with non-standard lengths, but you need to be aware of how these grooves will interact. For example, if one channel used a 3-bar groove and another used a 4-bar groove, the groove pattern would actually repeat every 12 bars (3-bars times 4-bars).

Groove patch Time signature

This displays the groove's time signature and should, in most cases, match the time signature of your sequence.


- **In general, if you apply different groove patches to different note lanes, you'll want them to share a common time signature.**
  You can, of course, mix and match time signatures to create polyrhythmic grooves, but you need to be aware of how these grooves interact. For example a 6/8 groove will shift notes in a radically different way than a 4/4 groove, so applying them simultaneously may or may not sound the way you expect.

Get Grove from Clip

This button converts the notes in a selected clip into a groove patch. The patch can then be used right away in the active ReGroove Mixer Channel or saved to disk as a new groove patch. Clicking this button has the same effect as selecting a clip and choosing "Get Groove From Clip" from the Edit (or context) menu. See "Creating your own ReGroove patches".

Timing Impact

This determines the extent to which timing information embedded in the groove template affects the position of your notes. A 50% setting means that notes are moved halfway to the positions defined in the groove template. 100% means they are moved exactly to the positions in the groove, and 200% means they are moved just as far past the groove template positions.



- **This parameter works in conjunction with the ReGroove Mixer's Groove Amount fader, which can scale back the groove's timing impact.**
  For example, if the Groove Amount fader is set to 100%, then notes are moved by the indicated Timing Impact amount, but if the Groove Amount fader is set to 50%, then notes are moved by only half the Timing Impact amount.

Velocity Impact

This determines the extent to which velocity information embedded in the groove template affects the velocity of your notes. Grooves modify only the relative differences between note velocities, not their absolute values. This way, soft passages remain soft and loud passages remain loud-the groove simply accents the notes differently. A 100% setting means that the feel is more or less exactly transferred from the template to your music. Values below this mean that less of the groove's dynamics affect your notes, and values above 100% dramatically increase the dynamic effect of the groove patch.

- **This parameter works in conjunction with the ReGroove Mixer's Groove Amount fader, which can scale back the groove's velocity impact.**
  For example, if the Groove Amount fader is set to 100%, then velocities are modified by the indicated Velocity Impact amount, but if the Groove Amount fader is set to 50%, then velocities are modified by only half the Velocity Impact amount.

Note Length Impact

This determines the extent to which note length information embedded in the groove template affects the length of your notes. This setting is not always relevant (such as with drum samples, which always play at their full length) and, consequently, most grooves in the Factory Sounds bank do not contain any length information (with the exception of the "Bass-Comp" category).

That said, when working with sustaining instruments, note length can have a dramatic impact on the performance's feel. Grooves modify only the relative differences between note lengths, not their absolute values. This way, legato or staccato passages retain some of their original intent when modified with a groove patch.

- **This parameter works in conjunction with the ReGroove Mixer's Groove Amount fader, which can scale back the groove's note length impact.**
  For example, if the Groove Amount fader is set to 100%, then note lengths are modified by the indicated Note Length Impact amount, but if the Groove Amount fader is set to 50%, then note lengths are modified by only half the Note Length Impact amount.

Random Timing

This determines the extent to which note positions are randomized. This value defines the maximum distance that a note can be randomly shifted (in either a positive or negative direction). You may set an amount between 0 ticks (no randomization occurs) and 120 ticks, which allows notes to shift as much as a thirty-second note in either direction.

The effect is "polyphonic," meaning that any notes originally beginning at the same position will still be moved by different amounts. It is also "semi-deterministic," meaning that if you play a clip several times, without editing anything, all notes will play back at exactly the same positions each time. However, as soon as you edit the clip in any way, all random positions are recalculated.

- **This parameter works in conjunction with the ReGroove Mixer's Groove Amount fader, which can scale back the randomization.**
  For example, if the Groove Amount fader is set to 100%, then notes are randomized by the indicated Random Timing amount, but if the Groove Amount fader is set to 50%, then notes are randomized by only half the Random Timing amount.

Working with grooves

Applying grooves to your music


Follow this example to learn basic ReGroove mixing techniques and hear the effect that various groove parameters have on your music.

1. **If it's not already visible in either the Sequencer or Rack, open the ReGroove Mixer by clicking the Groove button in the top bar:**



2. **Decide which note lane you are going to apply the groove to.**
   For the most obvious effect the track should contain a drumbeat based on straight (as opposed to shuffled) sixteenth notes. A hi-hat lane, for example, might be a good source for experimentation.

3. **Use the Groove Select pop-up on the chosen note lane to route those notes to a specific ReGroove mixer channel.**



- **The "Enabled" item at the top of the pop-up menu allows you to turn ReGroove off for individual note lanes.**
  This is useful for comparing with the original, ungrooved beat. If you want to do this for several note lanes set to a particular ReGroove channel, use the "On" button for the channel in the ReGroove mixer instead (see "On Button").
- **To turn ReGroove off for a note lane, select "No Channel".**

4. **In the ReGroove Mixer, make sure the channel you are using is activated - the On button should be lit.**

5. **To hear some of the different possibilities, start by turning up the channel's Shuffle knob while you play the sequence.**




The music on that note lane (and any other note lane assigned to the same ReGroove channel) will start playing with a shuffle feel.

6. **Turn down Shuffle to its middle position (50%), and turn up the channel's Slide knob to hear its effect.**



- **Note that, because slide shifts all notes by the same amount, you won't hear the results unless you play the track in conjunction with another track whose notes are not being slid (or with Click activated in the sequencer).**

7. **Turn the Slide knob back to its middle position (0 Ticks),**
8. **Click the channel's Browse button to set Browse focus to ReGroove Patches in the Factory Sounds bank.**
9. **Navigate to the "Reason Library > Reason Factory Sound Bank > ReGroove Patches" folder:**



10. **Unfold the Vinyl folder, select the first groove patch in the list and click OK to load the groove patch.**

11. **Pull up the Groove Amount fader on the channel, to about 80%.**



12. **Click the Next Patch button to step through the groove patches in the folder and hear what they do to your music.**
13. **On the ReGroove Mixer channel, click the Edit button to enable that channel's groove settings in the Groove Settings section.**
14. **Edit the various parameters and listen for their effects.**
    Note that none of the patches in the Vinyl folder make use of Note Length, so the Note Length Impact parameter will have no effect.

▶ **There are all sorts of creative and useful ways to apply grooves to your music. See "Groovy tips & tricks", later in this chapter, for some suggested techniques.**

Commit to Groove - making the grooves "permanent"

When you assign a ReGroove channel to a note lane, this will only affect how the notes play back. The notes will still be shown with their original, ungrooved positions if you open the note clip.

If you want to edit grooved notes (e.g. adjust timing and velocity manually), it's useful to first actually move the notes to the grooved positions, permanently. This is done with the "Commit to Groove" function:


1. **Select the track with the grooved note lane(s).**
2. **Select "Commit to Groove" from the Edit menu or the track context menu.**
   All notes on all lanes on the track will be moved to their grooved positions, and the Groove Select pop-up will be reset to "No Channel".

If you play back the track, it will sound exactly the same as before. If you look at the notes in Edit mode, their positions, length and velocity will now match what you hear.

Using Commit to Groove on some lanes only

"Commit to Groove" affects entire tracks, including all note lanes if there are several. If you only want to make the groove permanent for one of the lanes, here's a workaround:

1. **Click the Groove Select pop-up for the note lanes that should remain ReGrooved, and turn off "Enabled".**
   This bypasses the ReGroove channel for those note lanes, but retains the channel selection.



2. **Select "Commit to Groove".**
   Only the note lanes with ReGroove Enabled will be affected.
3. **Select "Enabled" again for the note lanes that should remain ReGrooved.**

Creating your own ReGroove patches

To create your own ReGroove Patch, proceed as follows.

1. **Create a clip containing notes with the desired timing and dynamics (velocity).**
   Alternatively, you could import a MIDI File with the desired effect, or use the "Copy Loop To Track" function on a Dr. Octo Rex device to extract the notes from a REX loop.

- **Note that some MIDI clips will make better grooves than others.**
  To learn some of the characteristics of a good groove-making clip, see "Tips for selecting the best Groove-Making Clips" below.

2. **Select the clip.**
3. **Select an unused Groove Channel in the Track List.**
4. **Select "Get from clip" from the clip context menu.**
5. **In the Groove Settings section, set the various impact parameters as desired.**
   For a good starting point, you can simply leave them at their default settings.
6. **Click the Save Patch button in the Groove Settings section and specify a name and location.**

Your ReGroove patch is now ready to use. As discussed in "Applying grooves to your music", simply route one or more note lanes to the ReGroove channel assigned to your new groove, and pull up the Groove Amount fader on that channel.

Tips for selecting the best Groove-Making Clips

The following tips will help insure that your custom grooves work their best:

- **Include as many sixteenths notes as possible in the source clip.**
  If there are any sixteenth note gaps in your source material, there will be corresponding gaps in your groove patch. This means, when you apply the groove to a note lane, some notes will be grooved and some (those that fall in the gaps) will not.
- **Grooves use the relative differences between note velocities, not their absolute values.**
  If you don't want dramatic shifts in dynamics, avoid having widely varying velocities in your source clip.
- **Groove patches are always an exact number of bars, so if your source clip has an uneven length, the groove will be extended to the next bar.**
  We recommend that you adjust your source clip to an exact number of bars before creating a groove patch.
- **In general, you should use source clips whose length is an even multiple of 2 (for example, 1-bar, 2-bars, 4-bars, etc.)**
  You can create and use grooves that are an odd number in length (3, 7, 13, etc.), but unless you're well organized and plan to use these grooves in specific polyrhythmic pieces, their general effect on most tracks will be somewhat unpredictable.

Groovy tips & tricks

- **Because you can route each note lane to any of the 32 ReGroove channels, the key to creating really dynamic grooves is to spread your instrumentation across multiple note lanes.**
  For instance, where you might normally create a Redrum sequence with kick, snare, and hi-hat all on the same track, putting these elements into different lanes will let you apply different grooves to them. For example, you might have a kick lane routed to a ReGroove channel with a slight shuffle feel, and you might send the snare to a ReGroove channel that slides the notes earlier in time to "push" the backbeat a little. Breaking things into lanes will definitely enable you to create beats that are more loaded with feel and personality than if you simply apply one groove setting to everything.

▶ **See "Extract Notes to Lanes" for tips on how to automatically distribute notes from one note lane to several additional note lanes.**

- **When building a groove, start simple. Experiment with adjusting the slide parameter to move just the snare or hi-hat forward or backward in time.**
  Try applying slightly different amounts of shuffle to different percussion instruments. Small changes can sometimes have a big visceral effect, so use your ears (and not your eyes) when adjusting the various groove settings.
- **Try applying the same groove patch to multiple lanes, but by varying amounts.**
  You are, of course, free to apply different groove patches to different lanes. Though, more often than not, your results might result in something that sounds more clumsy than groovy. The hottest grooves often have the most subtle of humanization.
- **Don't forget to try sending sequenced REX files through the ReGroove mixer.**
  Depending on the material in the file and how it's sliced up, this can create all types of results-ranging from unusable to downright inspiring.
- **If you're doubling instruments - that is two instruments play the exact same part - try sending one of the instruments to a ReGroove channel that has a small amount of random timing applied.**
  Random Timing (which is accessible in the Groove Settings section to the right) will put some separation between the two instruments, making their performance sound more human. For example, if you have a clap doubling a snare, apply a little bit of random timing to the clap track, and it'll stand out more clearly in the mix.
- **As described under the "Anchor Point" heading above, grooves restart whenever a new time signature appears.**
  You can use this knowledge to force a groove to restart, which might be required if your music contains sections of odd lengths. Simply add in a time signature event, with the same type of time signature as you already have in the song. The groove will restart where the event starts.
- **Remember that groove patches have separate timing and velocity impacts and, as such, you can apply them independently.**
  For example, if you already have a track that has just the right groove timing, but you want to experiment with different dynamic feels, you can apply just the velocity portion of a groove by setting its Timing Impact parameter to 0. A groove's timing and velocity impact parameters can be accessed by clicking a ReGroove channel's Edit button, which enables the Groove Settings section.

ReGroove patches in the Factory Sounds bank

Reason ships with a ready-made assortment of groove patches, arranged in a number of different folders:

Bass-Comp, Drummer, and Percussion

Grooves in these categories were created by session musicians. Their performances were captured and analyzed, and the timing and velocity information was then extracted from the performances. The Bass-Comp patches also contain note length information, though the other categories do not.

MPC-60

These grooves were created by analyzing the audio output of an Akai MPC-60. Use these patches to get the same shuffle feeling as an original MPC-60. Note that these patches do not contain any velocity or note length information. There are some additional patches that use the Random Timing feature, which emulates the original MPC-60's behavior when loaded with a lot of information.

Programmed

These grooves were created by a session drum groove programmer. They were hand-crafted to emulate the feel of certain styles, and are divided into two genres: Hiphop and Pop-Rock. These grooves do not contain any note length information.

Vinyl

These grooves were created by sampling snippets from classic groove records, analyzing them with a special signal processing tool, then extracting both timing and velocity information from the samples. These grooves do not contain any note length information.

Chapter 24
Remote - Playing and Controlling Devices



About the various MIDI inputs

This chapter describes how you can use Remote and the Easy MIDI Input function to set up your master keyboard and control surfaces, allowing you to play Reason devices, adjust parameters and control various Reason functions. This is the main way of sending MIDI to Reason, but there are also some additional methods:

- **Using the External Control Bus inputs.**
  The External Control Bus inputs (set up on the "Other Controls" tab in Settings - and in the MIDI In device in the hardware interface) let you send MIDI directly to the individual devices in the rack. This is mainly used if you control Reason from an external sequencer, etc. See "About the External Control Bus inputs".
- **Sending MIDI Clock to Reason.**
  This allows you to synchronize Reason's tempo to other devices. See "Synchronization to MIDI Clock".

About Remote

MIDI from control surfaces (keyboards, remote control units etc.) is handled by a protocol called Remote. The Remote protocol allows for seamless integration between Reason and control surface devices. It is basically a mapping system that provides direct hands-on control of parameters for each Reason device - including transport and sequencer track selection!

At the time of this writing, Reason supports a large number of control surfaces and keyboards - the knobs, faders and buttons on the devices are automatically mapped to parameters on each Reason device.

Remote drivers for more control surfaces will be added continuously. Check the Reason Studios web page in case your model isn't listed on the Settings - MIDI tab.

Remote controlling Reason devices couldn't be made any simpler. Let Reason automatically look for all available MIDI Input ports on your computer and automatically connect your master keyboard. Or, manually set up your control surface for use with Reason - the program handles the rest!




Setting up

Automatic set-up using the Easy MIDI Inputs function

By default Reason automatically scans and detects all available MIDI In port(s) on your computer. If you have a MIDI keyboard or MIDI control surface connected to your computer, Reason automatically connects and lets you use it for controlling Reason. This way you don't have to do any manual set-up but can start controlling Reason right away.

At the bottom of the MIDI tab in Settings all currently available MIDI In Ports are listed:



All available MIDI In Ports on your computer are listed in the Easy MIDI Inputs list.

- **The Easy MIDI Inputs function supports input of MIDI Note On/Off (with Velocity) as well as standard performance controllers, such as Mod Wheel, Pitch Bend and Sustain Pedal.**
  You can also do manual Remote Overrides to assign Reason parameters to knobs/sliders/buttons on your control keyboard/surface, see "Remote Override".

- **Deselect the Enabled box(es) to disable MIDI Ports you don't want to be available for Reason.**
  For example, if you have a drum machine connected via USB to your computer, you might not want it to start sending MIDI Note data to Reason, especially if it's synced to MIDI Clock to Reason's sequencer.


Adding a specific control surface or keyboard

If your specific MIDI keyboard/control surface model is featured in the list of supported surfaces in Reason you will get even more functionality if you add it in the "Remote keyboards and control surfaces" section at the top - with knobs/sliders/buttons already pre-assigned to parameters in Reason.

This is how you add your specific control surfaces - including the master keyboard.


1. **Open the Settings dialog and click the MIDI tab.**
2. **If your control surface is connected via USB (or if you have made a two-way MIDI connection), try clicking the Auto-detect Surfaces button.**
   Reason sends an ID request to all MIDI ports and checks for answers from any connected control surfaces. Note that not all control surfaces support auto-detection.

! **If a MIDI Port of your connected control surface/keyboard is already used by the Easy MIDI Inputs function (see "Automatic set-up using the Easy MIDI Inputs function"), this detection will override this and automatically remove the MIDI In Port from the Easy MIDI Inputs list.**



3. **To add a control surface manually, click the "Add manually" button.**
   This brings up a new dialog.
4. **Select the manufacturer of your control surface from the Manufacturer pop-up menu.**
   If you can't find it on the menu, see below.
5. **Select the model of your control surface from the Model pop-up menu.**
   If you can't find it on the menu, see below.

6. **An image of the selected control surface model is shown, often along with some information text - read this carefully.**
   For some control surfaces, you need to select a specific preset to use the surface with Reason - this is noted here.



7. **Use the MIDI Input pop-up to select the input port to which you have connected the surface.**
   If in doubt, you can click the Find button and then tweak a control or play a key on the control surface to have Reason find the correct input port for you.

- **Some control surfaces may have more than one MIDI Input pop-up menu.**
  You need to select ports on all MIDI Input pop-up menus.
- **Some control surfaces will have a MIDI Output pop-up menu.**
  In some cases this labeled "Optional" - then you don't have to make a selection. In other cases, a MIDI Output is required. This is the case if the control surface uses MIDI feedback - motor fader, displays, etc.
- **Reason only "grabs" the MIDI inputs you are actually using.**
  MIDI inputs not selected here or on the Sync page (see "Advanced MIDI - The External Control Bus inputs") are available to other programs.

! **Note that other MIDI programs may "grab" all MIDI ports in your system when you launch them!**

8. **If you like, you can rename your control surface in the Name field.**
9. **Click OK to add the surface.**

- **Depending on the surface model, alerts may appear, reminding you to select a specific preset etc.**
  In some cases, Reason can restore a preset in the control surface to factory settings for you. In such cases you will be informed about this.

Finally you return to the MIDI tab in Settings, where your added surface is now listed.

If your control surface model isn't listed

If you can't find your control surface listed on the Manufacturer or Model pop-up menus when you try to add it, this means that there's no native support for that model. However, the program supports generic keyboards and controllers. These alternatives might be more useful than the Easy MIDI Input alternative described earlier - if you have a control surface (or keyboard with knobs/buttons/sliders) that you want predefined parameter destinations for. Here's what to do:

▶ **Select "Other" on the Manufacturer pop-up menu and then one of the three options on the Model pop-up menu.**

or, if the Manufacturer is listed but not your specific model:

▶ **Select one of the three "Other" options on the Model pop-up menu:**

In both cases, the options are:

- **MIDI Control Keyboard**
  Select this is you have a MIDI keyboard with programmable knobs, buttons or faders. You need to set up your control keyboard so that the controls send the correct MIDI CC messages, depending on which Reason device you want to control - check out the MIDI Implementation Chart. If your control keyboard has templates or presets for Reason devices, these can be used if you run Reason.
- **MIDI Control Surface**
  Select this if you have a MIDI controller with programmable knobs, buttons or faders (but without keyboard).
  You need to set up your control surface so that the controllers send the correct MIDI CC messages, depending on which Reason device you want to control - check out the MIDI Implementation Chart. If your control surface has templates or presets for Reason devices, these can be used if you run Reason.
- **MIDI Keyboard (No Controls)**
  Select this is you have a MIDI keyboard without programmable knobs, buttons or faders. This is used for playing only (including performance controllers such as pitch bend, mod wheel, etc.) - you cannot adjust Reason device parameters with this type of control surface.
- **MIDI Multichannel Control Keyboard**
  Select this is you have a MIDI keyboard with programmable controls that use multiple MIDI channels (different controls send the same MIDI CC but on different MIDI channels). With this model there is no automatic mapping to device parameters - you need to use Remote Overrides to map each control to a parameter on a device.
- **MIDI Multichannel Control Surface**
  Select this is you have a MIDI control surface with programmable controls that use multiple MIDI channels (different controls send the same MIDI CC but on different MIDI channels). With this model there is no automatic mapping to device parameters - you need to use Remote Overrides to map each control to a parameter on a device.

After selecting a model, proceed with selecting MIDI input port as described above.

About the Master Keyboard

One of the control surfaces can be the Master Keyboard. This is like any other control surface, but it must have a keyboard and it cannot be locked to a specific Reason device (in other words, it always follows the MIDI input to the sequencer). This is the surface you use to play the instrument devices in Reason.

- **The first surface with a keyboard that is added (manually or auto-detect) is automatically selected to be the master keyboard.**
  This is shown in the "Remote keyboards and control surfaces" list on the Settings page.
- **If you want to use another surface as master keyboard, select it in the list and click the "Make Master Keyboard" button.**
  You can only have one surface as master keyboard at a time.
- **If you don't want to use any master keyboard at all, select the current master keyboard surface and click the same button (which is now labeled "Use No Master Keyboard").**

Other functions

- **To edit a surface, double click it in the list (or select it and click Edit).**
  This lets you change its name and MIDI port settings, if needed.
- **To delete a surface, select it in the list and click Delete.**
- **You can turn off a surface by deactivating its "Use with Reason" checkbox.**
  This could be useful if the surface is connected to your system but you only want to use it with another program.

There is also the Sync tab in the Settings. This is only used for External Control MIDI buses and for MIDI Clock Sync settings. All hands-on MIDI control is set up on the MIDI tab.

Example Setups

There are several possible variables when it comes to what type of setup you are using. Please read on.

A single MIDI keyboard with controls

With this setup, the keyboard is your master keyboard, which means it is always routed via the sequencer (it controls the device connected to the sequencer track with Master Keyboard Input). To control another device, you move the Master Keyboard Input (the keyboard symbol in the In column in the track list) to another sequencer track.

You can, however, use Remote Override to control parameters on other Reason devices (or global Reason functions such as transport).

A basic MIDI keyboard and an additional control surface

The keyboard and the control surface should be connected to separate MIDI ports (or use separate USB connections). Here, the basic MIDI keyboard is your master keyboard - it is used for playing and recording via the sequencer. You can have the control surface follow the master keyboard - this lets you tweak the parameters of the device you are playing (just like in the example above).

You can also lock the control surface to another device in the rack - this lets you play one device while adjusting the parameters of another.

A MIDI keyboard with controls plus one or more control surfaces

This is the ideal setup! Again, all keyboards and control surfaces should be connected to separate MIDI ports (or use separate USB connections). The master keyboard is routed via the sequencer track and you can use its controls to tweak the parameters of the device you are playing. The additional control surfaces could be locked to the Main Mixer or to different devices in the rack.

If you have additional MIDI keyboards locked to devices in the rack, you can also play and record on their corresponding sequencer tracks simultaneously. This is perfect if your band has several keyboard players who want to play and record their tracks simultaneously into Reason!

For example, if you lock a control surface to the Main Mixer, you will always have control over levels, pans and additional channel strip parameters - see "Remote controlling the Main Mixer" and "Remote controlling multiple mixer channels". You could also have dedicated controls for transport, Undo/Redo, sequencer track MIDI focus selection, etc.

Remote basics

Parameters and functions for each Reason device are mapped to controls on supported control surface devices. As soon as you have added your control surface(s) in the Settings, you can start tweaking parameters!

- **By default, all connected control surfaces follow the sequencer's current Master Keyboard Input.**
  This means that you set Master Keyboard Input to a track in the sequencer to route the control surface(s) to the track's device in the rack. You can bypass this functionality by locking a control surface to a specific device - see "Locking a surface to a device". Or you can simply use Remote Override mapping (see "Remote Override" for specific parameters - these will then be mapped to the selected controls regardless of Master Keyboard Input.
- **The Reason device associated with the track with Master Keyboard Input will have its parameters standard mapped to logical controls (faders, buttons etc.) on the control surface device.**
  E.g. if a Subtractor has Master Keyboard Input, your control surface will control the most important Subtractor parameters. If you set Master Keyboard Input to a track connected to an NN-XT, the control surface will now control parameters on the NN-XT device, and so on for each device. There are standard mapping variations for most devices as well - see "About mapping variations".
- **Supported control surfaces with dedicated transport controls will be standard mapped to the equivalent transport controls in Reason.**
  If you do not have transport controls on your control surface you can still map transport controls to controllers using Remote Override mapping - see "Remote Override mapping".
- **Other important functions such as switching target track in the sequencer, selecting patches, Undo/Redo can also be remote controlled.**
  See "Additional Remote Overrides...".

About Standard vs Remote Override mapping

Reason parameters are "standard-mapped" to supported control surface devices. There is nothing the user needs to set up to remote control any Reason device. You can, however, use Remote Override mapping to map a specific parameter to a specific control if you should want to.

- **By using standard mapping, the remote mapping for each device will be the same for any new song created in Reason, given you have the same set of control surfaces connected.**
  If you use Remote Override mapping (see "Remote Override"), the overrides will be saved with the current song, but won't be there if you create a new song.
- **Which parameters and functions that are standard mapped for each Reason device depends on the control surface(s).**

The "Control Surface Details" document contains some information about the standard mappings of the different control surface models. But you can also activate Remote Override Edit mode to see which parameters for each device are mapped to your control surface(s) - see "Remote Override".

- **Note that if you have several control surfaces connected, some parameters could be mapped to controls on more than one control surface.**
  This is not a conflict of any kind, but simply a consequence that stems from the fact that all control surfaces by default follow Master Keyboard Input. By using Surface Locking (see below) or Remote Override (see "Remote Override") you have full control over your control surfaces.

About mapping variations

Since there are often more parameters on a device than there are controls on the control surface, there are standard mapping variations available for most devices. When selecting a standard mapping variation, a new set of parameters will be mapped to the controls on your control surface for a selected Reason device.

For example, if you have a control surface with 8 rotary knobs routed to a Subtractor, the knobs may control filter parameters by default. Selecting variation 2 may make the knobs control the oscillator settings, variation 3 may control LFOs and so on.

- **For devices that support keyboard shortcuts, you switch between mapping variations by holding down [Ctrl]+[Alt](Win) or [Cmd]+[Option](Mac) and press the numerical keys [1] to [10] (not the numerical keypad), where [1] selects the default standard mapping.**
  How many mapping variations are available depends on the control surface and the Reason device selected. The variation selected will stay active until you switch MIDI input to another device (or select another variation). If you switch back to the same device it will have its default standard mapping (variation [1]).
- **For control surfaces that have dedicated controls for selecting mapping variations these are used instead of keyboard shortcuts.**
- **Locked devices (see "Locking a surface to a device") can also be locked to a specific mapping variation.**

Locking a surface to a device

You can lock a control surface or an additional MIDI keyboard/controller to a specific device so that it is always "tweakable" and record enabled, regardless of which track has Master Keyboard input in the sequencer. This enables you to play and record notes for several devices simultaneously from multiple control surfaces/keyboards.

For example, you could lock a control surface to control the Main Mixer, so you can always control overall levels while playing/tweaking other devices. See "Remote controlling the Main Mixer" for an example.

- **The master keyboard device cannot be locked!**
  If you select the master keyboard in the Settings, you can de-select the "Master Keyboard" check box. You can then lock this control surface to a device and use its controllers to tweak parameters, but you will not be able to play the device.
- **You can lock several control surfaces to the same device.**
  However, each control surface can only be locked to one device at a time.
- **Info about which devices are locked (and to which control surfaces) is saved with the song.**


! **Control surfaces/keyboards that use the Easy MIDI Inputs function (see "Automatic set-up using the Easy MIDI Inputs function") cannot be locked to devices.**

Locking a surface

There are basically two methods you can use to lock a Surface:


Using the Surface Locking dialog

1. **Select "Surface Locking..." from the Options menu.**
   The Surface Locking dialog opens.




In this picture, the dialog has the master keyboard as the selected control surface - this cannot be locked.

2. **Pull down the Surface pop-up from at the top of the dialog and select the control surface you wish to lock to a device.**




3. **Next, open the "Lock to device" pop-up menu.**
   On this pop-up, all devices in the current song are listed. The "Follow Master Keyboard" item which is selected by default, means that the control surface isn't locked (it instead follows the Master Keyboard Input in the sequencer).



4. **Select the device you wish to lock to the selected control surface from the list.**

▶ **If the selected control surface supports keyboard shortcuts for selecting mapping variations (see "About mapping variations") an additional "Always use Mapping" pop-up appears.**
On this pop-up you can set whether you wish to lock a specific standard mapping variation or whether the device should switch mapping variations according to keyboard shortcuts. If the former is the case, select the mapping variation from the list. If the latter is the case, select "Follow Keyboard Shortcut".




5. **Close the dialog when you are done.**
   The device is now locked to the selected control surface. In Remote Override Edit mode (see "Activating Remote Override Edit mode") a locked device is shown with a lock symbol in the upper left corner of the device panel.



▶ **It's also possible to lock a control surface to the ReGroove Mixer (see "The ReGroove Mixer") to control its parameters via Remote!**

Using the context menu

- **A quick way to lock devices is by right-clicking (Win) or [Ctrl]-clicking (Mac) on a device panel to bring up the context menu.**
  On the context menu, all installed control surfaces (apart from the master keyboard) are listed with the text "Lock to" plus the name of the control surface. Selecting one will lock the device to the control surface. On the context menu the control surface that is currently locked to this device will be ticked.



Unlocking a surface

- **To unlock a locked device, bring up the context menu for the locked device, and untick the "Lock to" item.'**
  This unlocks the device and the control surface will now follow master keyboard input.
- **Another way to unlock a surface is to open the Surface Locking dialog and selecting "Follow Master Keyboard" on the Lock to device pop-up.**

Remote Override

Remote Override allows you to map parameters and functions to controls on your control surface device, overriding the standard mapping. It also allows you to control device parameters from Easy MIDI Inputs (that has no standard mapping).

Activating Remote Override Edit mode

1. **Select "Remote Override Edit Mode" from the Options menu.**
   All unselected devices in the rack are grayed out, indicating Edit mode. Each selected device (including the Transport panel) will show a blue arrow symbol on every parameter that can be mapped to a control on a control surface.



Remote Override Edit mode enabled with the mixer device selected.

To be able to see which parameters are currently mapped for a device, you have to direct Master Keyboard input to the sequencer track it is connected to:

2. **Select a device in the rack and enable Master Keyboard input for its sequencer track.**
   Standard-mapped parameters are tagged with yellow knob symbols.



A Subtractor with standard-mapped parameters.

- **Note that you can select the Transport Panel as well!**
  Most items on the Transport panel can be mapped to controls. Note that by selecting the Transport panel any standard mapping will be shown automatically, unlike other devices where you have to first direct Master Keyboard input to the device from the sequencer.
- **If you point on a standard mapped parameter, a tooltip appears showing which control on the control surface device the parameter is mapped to.**




Remote Override mapping

If Remote Override Edit Mode is enabled you can use the following methods to map a parameter to a control:

Method 1:


1. **Select the parameter you wish to map.**
   The arrow (or knob) changes to orange, indicating it is selected.
2. **Select "Edit Remote Override Mapping..." from the Edit menu.**
   You can also right-click (Win) or [Ctrl]-click (Mac) on the parameter to select the same item from the context menu.

   The "Edit Remote Override Mapping" dialog opens. From here you have two ways to proceed:



- **Either manually select the control surface and the control you wish to map the parameter to from the two corresponding pop-ups.**
  The Control Surface pop-up lists all installed control surface devices, and the Controls pop-up lists all the mappable controls for the selected control surface.
- **Or you can activate "Learn From Control Surface Input" and simply move (or press) the control you want to map the parameter to.**
  The "Control Surface Activity" field momentarily flickers as you turn the knob, and then the dialog shows the control surface and control it is mapped to.
- **If the control surface has a keyboard, you can also select keys as controls.**
  Keys work just like on/off buttons. If "Keyboard" is selected from the Controls pop-up, a Note Number field appears in the dialog.

3. **Click OK to exit the dialog.**
   The mapped parameter now shows a lightning bolt icon, indicating it uses Remote Override mapping. Any overrides are always shown in Remote Override Edit mode. The device does not have to be selected or have Master Keyboard Input in the sequencer.



4. **To exit Remote Override Edit Mode, deselect it from the Options menu.**
   You can also leave this mode by pressing [Esc].

Method 2:

1. **Double-click the parameter you wish to map.**
   A rotating lightning bolt appears for the parameter - this indicates that "Learn From Control Surface" mode is active. You can leave this mode by pressing [Esc].
2. **Now move (or press) the control you want to map the parameter to.**
   The parameter is now mapped to the control.

You do not always have to edit override mapping when Remote Override Edit mode is activated - see below.

Override mapping with Remote Override Edit mode deactivated

If Remote Override Edit Mode is enabled on the Options menu, mapped parameters are "tagged", and the arrow indicators show the assignable parameters. In this mode, however, you cannot operate Reason normally. Remote Override Edit mode is primarily for overview of available parameters and the current assignments.

- **Another way to map parameters is to have "Remote Override Edit Mode" deactivated on the Options menu, and to simply right-click (PC) or [Ctrl]-click (Mac) on the parameter you wish to remote control.**
  This opens a pop-up menu, where one of the options will be "Edit Remote Override Mapping". Selecting this will open the Edit Remote Override Mapping dialog. Thus, you do not have to select Edit mode from the Options menu if you already know that a parameter is free and assignable.

Removing Remote Overrides

This can be done for a selected parameter in the following way:

1. **In Remote Override Edit Mode, select the parameter you wish to remove Remote Override for.**
   The lightning bolt changes to orange, indicating it is selected.
2. **Select "Clear Remote Override Mapping..." from the Edit menu.**
   You can also right-click (Win) or [Ctrl]-click (Mac) on the parameter to select the same item from the context menu. This is always available, regardless whether Remote Override Edit mode is selected or not.

Or you can remove all Remote Overrides for a device in one go:

1. **Select the device you wish to remove Remote Override for.**
2. **Select "Clear All Remote Override Mappings for Device" from the Edit menu.**
   You can also right-click (Win) or [Ctrl]-click (Mac) on the device panel to select the same item from the context menu.

Copying/Pasting Remote Overrides


You can copy Remote Override mappings for a device and paste them into a device of the same type. This works as follows:

1. **With Remote Override Edit mode activated, select the device you want copy Remote Override mappings from, and the select "Copy Remote Override Mappings" from the Edit menu.**
   You can also right-click (Win) or [Ctrl]-click (Mac) on the device panel to select the same item from the context menu.
2. **Select the device you wish to paste the copied mappings to.**
   It has to be the same type of device you copied from. In case you copied Remote Override mappings from the Transport panel you can thus only paste the mappings into another song document.
3. **Select "Paste Remote Override Mappings" from the Edit menu.**

Now the following happens:

- **If you are pasting in the mappings into a device in the same song document, a dialog appears informing that the overrides are already used.**
  You then have the choice of canceling the operation, or to move the existing overrides to the new device.
- **If you are pasting into a device in another song, the copied Remote Override mappings are simply pasted.**
  In this case, the original Remote Override mappings are not affected.

Additional Remote Overrides...



On the Options menu there is an item named "Additional Remote Overrides...". Selecting this opens a dialog with remote functions that cannot be assigned using Remote Override Edit mode, such as switching target tracks, Undo/Redo etc. Although most of the items in this dialog are self-explanatory, some need to be described. These are as follows:

Target Track Delta and Target Previous/Next Track

- **Target track is the track with Master Keyboard Input.**
  Assigning Target Previous/Next Track to two Button controls on a control surface allows you to move the Master Keyboard Input symbol up or down in the Track list.
- **Target Track Delta is meant to be used with Delta wheel controllers (a special control with no min/max range) to switch target track.**
  A Mackie Jog wheel is an example of this type of controller.
- **Select Previous/Next Track can be assigned to standard button controls.**

Select Patch for Target Device and Select Previous/Next Patch for Target Device

The target device is the device connected to the target track.

- **Patch selection is usually standard-mapped to buttons on a control surface.**
  If you wish to override this standard patch selection mapping for devices globally to select patches for any patch device that currently has Master Keyboard Input, you can assign this here.

  For example, you may always want to use the same buttons on a specific control surface for selecting patches.
- **Select Patch for Target Device is also meant to be assigned to a Delta-type control (see above).**
  This allows you to select patches for a device connected to the target track by spinning the wheel clockwise or anti-clockwise.
- **Select Previous/Next Patch can be assigned to standard button controls.**

Select Keyboard Shortcut Variation (Delta)/Select Previous/Next Keyboard Shortcut Variation

By mapping controls to these, you can use your control surface to change which keyboard shortcut variation is selected in Reason.

- **The "Select Previous/Next" functions are typically mapped to buttons, allowing you to step between keyboard shortcut variations.**
- **The Delta function must be mapped to a delta-type control to work.**
- **The keyboard shortcut variation selection is a global setting in Reason. It affects all added control surfaces (if they make use of keyboard shortcut variations and aren't locked to a specific device and variation in the Surface Locking dialog).**

Undo/Redo

You can assign Undo/Redo to controls. This works just like the corresponding items on the Edit menu.

Document Name

This allows you show the name of the song in the display of the control surface. This only works for control surfaces that support this feature.

Assigning Additional Overrides

Assigning overrides in this dialog is similar to assigning standard Remote Overrides:

1. **Select a function/parameter in the list that you wish to assign to a control and click "Edit".**
   This opens the Edit Remote Override Mapping dialog, where you can assign a control to the selected function/parameter. You can also simply double click the item in the list to open this dialog.
2. **Click OK to close the dialog.**

Clearing Additional Overrides

1. **Select "Additional Remote Overrides" from the Options menu.**
   In the Mapping column you can see which parameters/functions use overrides.
2. **Select the item currently assigned override mapping, and click "Clear".**



Keyboard Control

Assigning computer keyboard remote commands does not involve MIDI, so there is no special setting up required. Keyboard commands can be assigned to parameters just as when using Remote Override mapping, but the functionality differs in one central aspect:

- **Keyboard Control commands can only be used to toggle on/off or min/max values for an assigned parameter.**

Hence, if you assign a computer keyboard remote command for a knob, slider or spin control, it will only switch between the minimum and maximum values for that parameter. The only exception to this are the multi-selector buttons used for various parameters such as envelope destination, for example. These will cycle through the available options when using keyboard control.

! **Note that Keyboard Control cannot be used for the ReGroove Mixer parameters.**

Enabling Keyboard Control

To enable Keyboard Control, select "Enable Keyboard Control" from the Options menu.

Editing Keyboard Control

▶ **To get an overview of which parameters are remote controllable select "Keyboard Control Edit Mode" from the Options menu.**
When done, each device you select in the rack will show a yellow arrow symbol beside every parameter that can be assigned a keyboard control.




A section of a Redrum drum machine with Keyboard Control Edit Mode enabled.

! **The Main Mixer channel strip parameters can also be controlled using the Keyboard Control function, but there is no Edit Mode for this. Instead, you have to right-click (Win) or [Ctrl]-click (Mac) on individual channel strip parameters and select "Edit Keyboard Control Mapping" from the context menu.**

- **If you click on an assignable parameter to select it, you can then select "Edit Keyboard Control Mapping" from the Edit menu.**
  This opens a dialog allowing you to select a key command for that parameter.

  You may use any key except the [Space bar], [Tab], [Enter], the Numeric keypad keys (which is reserved for Transport functions) and the function keys (except [F2] and [F3]) - or a combination of [Shift] + any key (with the same afore-mentioned exceptions).



The Keyboard Control dialog.

- **Simply press the key (or Shift-key combination) you wish to use to remote control the parameter.**
  The "Key Received" field momentarily indicates that it is "learning" the keystroke(s), and then the dialog displays the name of the key you have pressed. If [Shift] was used, the box beside the word Shift in the dialog is ticked.

You can also double-click on the arrow for an assignable parameter to set up keyboard control:

- **A rotating yellow rectangle appears, indicating Learn mode. Press the key (or key combination) you wish to use to control the parameter.**
  The rotating stops and the rectangle will now display the key or key combination you used.

About the two Edit Keyboard Control Modes

If Keyboard Control Edit Mode is enabled (ticked) on the Options menu, assigned parameters in the rack are "tagged", showing the remote key for that parameter. In this mode, however, you cannot operate Reason normally. This mode is primarily for overview of available parameters and the current assignments.

- **Another way to assign keyboard remote commands is to have "Keyboard Control Edit Mode" deselected on the Options menu, and to simply right-click (Win) or [Ctrl]-click (Mac) the parameter you wish to remote control.**
  This opens a pop-up menu, where one of the options will be "Edit Keyboard Control Mapping". Selecting this opens the Keyboard Control dialog. Thus, you do not have to enable/disable Edit mode from the Options menu if you know that a parameter is assignable.

! **This is the only way Main Mixer channel strip parameters can be assigned to Keyboard Control.**

Saving Remote Setups

There's no need to save MIDI Remote mapping as the Standard Remote mapping for each Reason device to supported control surfaces is built-in, and is always available. You may, however, wish to save specific Remote Override mappings or Keyboard Control setups as a template:

- **This could be done by saving a song document containing all the devices that are affected by the related Key or Remote Override mappings, but without any sequencer data.**
  This song document could then be used as a starting point for any new song, by simply loading it, and immediately using "Save As" to save it under a new name.

- **A good idea could be to save these types of "Remote Template" songs in the Template Songs folder. See "Making a Song appear as a Template Song" for info on how to do this.**

Chapter 25
Synchronization and Advanced MIDI

About this chapter

This chapter describes how to synchronize Reason to external MIDI Clock or Ableton Link and how to sync external equipment from Reason's internal MIDI Clock. The chapter also describes how to use the External Control Bus inputs for advanced MIDI routing.

Synchronization to MIDI Clock

What is synchronization and MIDI Clock?

Synchronization, in this context, is when you make Reason play at the same tempo as another MIDI device; where both start, stop and can locate to certain positions, together. This is done by transmitting MIDI Clock signals between Reason and the other device. MIDI Clock is a very fast "metronome" that can be transmitted in a MIDI cable. As part of the MIDI Clock concept there are also instructions for Start, Stop and locating to sixteenth note positions.

You can set up synchronization between Reason and hardware devices (tape recorders, drum machines, stand alone sequencers, workstations etc.) and other computer programs running on the same or on another computer.

Host/Device

In a synchronized system there is always one Host and one or more Devices. In our case, the host is the one that controls the tempo. In other words, it is only the tempo setting on the host that is of any relevance, since the devices follow the host's tempo.

- **Reason can act as Host or Device. That is, Reason can transmit MIDI Clock signals and also receive them.**

Using Reason as MIDI Clock Host

Reason can transmit standard MIDI Clock signal. It also sends Start, Stop, Continue and Song Position Pointer (SPP) MIDI messages so that you can also control the transport functions of the synced equipment from the Transport Panel in Reason. To set up Reason as a MIDI Clock host, proceed as follows:


1. **Select the desired MIDI Port from the Sync Output Port drop-down menu in the "MIDI Clock Sync Out" section on the Sync tab in Settings.**




Selecting MIDI clock output port.

2. **Close the Settings window.**

3. **Select "Sync -> Send MIDI Clock" from the Options menu:**




- **Alternatively, click the Send Clock button in the Sync Mode section on the Transport panel:**




Now, you have set up Reason as a MIDI Clock sync master. When you start the Reason sequencer, MIDI Clock is sent out on the selected MIDI Out Port.

- **If your synced MIDI equipment is not in phase with the Reason sequencer, you might have to change the Output Offset in the "MIDI Clock Sync Our" section on the Sync tab in Settings.**



- **If the external MIDI equipment lags, set the Output Offset to a negative value.**
  A negative Output Offset means that the MIDI Clock signal is sent out from Reason earlier to compensate for the lag.
- **If the external MIDI equipment plays ahead of the Reason sequencer, set the Output Offset to a positive value.**

There are also some additional options regarding the MIDI Clock signal that can be selected at the bottom of the MIDI clock sync section:




- **Send MIDI Clock while Sequencer is Stopped.**
  When this box is checked, Reason continues to send out MIDI clock signal also when the sequencer is stopped.
- **Send Song Position Pointer.**
  When this box is checked, Reason sends out MIDI Song Position Pointer information to the device. If the synced device doesn't support Song Position Pointer, turning this setting off can improve synchronization. This is also useful if the synced device is playing a looped pattern and should disregard all positioning.
- **Send Stop/Continue when Repositioning.**
  When this box is checked Reason sends out Stop/Song Position Pointer/Continue messages to the synced device, if the song position locator in the sequencer is moved (either manually or when in Loop mode) when the sequencer is running.

  If unchecked, only Song Position Pointer messages are sent out if the song position locator is moved (or in Loop mode) while the sequencer is running.

Syncing Reason to an external MIDI application or instrument

This example assumes that you have an external device, such as a drum machine, hardware sequencer, another computer, tape recorder etc., that transmits MIDI Clock signals to which you want to synchronize Reason.

1. **Connect the device via USB/MIDI to the computer running Reason.**
2. **Set up the host so that it transmits MIDI Clock signals to the MIDI Out you just connected to the computer running Reason.**
3. **In Reason, pull down the Edit menu (under macOS, the Reason menu) and open the Settings dialog. Click the Sync tab.**



4. **Pull down the Sync Input Port pop-up and select the MIDI Input to which you connected the host.**
5. **Close the dialog.**
6. **Activate MIDI Clock Sync from the Options menu - "Sync" submenu in Reason.**
7. **Activate playback on the host.**
   Reason will start playing in sync with it.

▶ **If the Reason sequencer lags or plays ahead of the host, adjust the Input Offset on the Sync page in Settings, see "Adjusting for Latency".**

Syncing Reason to another program on the same computer

This section describes how to use MIDI Clock to synchronize Reason to another application running on the same computer.

! **Note that synchronization via MIDI Clock makes the two programs play at the same time, that is, they both "run" when you "hit play". It does not mean they can both play audio at the same time.**


Proceed as follows:

1. **Set up the host, so that it transmits MIDI Clock to Reason:**
   Under Windows this is done by selecting one of the MIDI routing utility ports.
2. **In Reason, open the Settings - Sync page.**
3. **Pull down the MIDI Clock Input pop-up and select the corresponding MIDI port.**
4. **Close the dialog.**
5. **Activate MIDI Clock Sync from the Options menu - "Sync" submenu in Reason.**
6. **Activate playback on the host.**
   Reason will start playing in sync with it.

▶ **If the Reason sequencer lags or plays ahead of the host adjust the Input Offset on the Sync page in Settings, see "Adjusting for Latency".**

External synchronization considerations

Adjusting for Latency



Because of MIDI latency problems, you might need to adjust Reason's playback in relation to the sync host, so that they are in perfect time. The tempo will not differ between the two, but Reason might play ahead or behind the other application. You might need to adjust this. However, this is something you only need to do once. The setting is stored with your other preferences, so you don't need to adjust it again.

Proceed as follows:

1. **Set up the other application so that it generates a solid click, on for example quarter or eighth notes, preferably with a special sound on the downbeat.**
   This click can either come from an internal metronome or from a MIDI source. If you use a MIDI source, make sure you pick one that has solid MIDI timing.
2. **Set up Reason so that it plays a similar rhythm as the other application.**
   You might for example use the sequencer Click or a Redrum drum computer for this.
3. **Start the two applications in sync.**
4. **Make sure you hear both applications at approximately equal level.**
5. **Open the Settings dialog in Reason and click the Sync tab.**
6. **Trim the "Input Offset" setting until the "clicks" from the both sources sound at exactly the same time.**
7. **Close the Settings dialog in Reason.**

If Latency Compensation isn't enough

There might be situations where you can't compensate enough in Reason to make two software applications run in sync. This might especially be true if the other application is an audio sequencer, that is if it can record and playback both audio and MIDI.

This problem is an indication of the fact that the other application has not been set up properly and that its audio playback is not in sync with its own MIDI playback.

! **This is not something that you can or should compensate for in Reason. Instead, follow the instruction included with the other application to make sure its MIDI playback and audio playback are correctly locked to each other.**

About the beginning of the Song

Due to the latency phenomenon, described in "About latency", Reason needs some time to correct its playback speed when it first receives the Start command. This can be noted as a small glitch in the audio playback, when the program starts. If this is a problem, you need to insert a couple of empty measures at the beginning of the Song. Proceed as follows:

1. **Set the Left Locator to "1. 1. 1.0" and the right Locator to "3. 1. 1.0".**
2. **Click somewhere in the main sequencer area to move the menu focus to the sequencer.**
3. **Select "Insert Bars Between Locators" from the Edit menu.**
4. **Set up the other device/application, so that it also plays two empty bars at the beginning.**

About MIDI Song Position Pointers

MIDI Clock actually consists of five type of messages: The actual clock (the metronome that establishes the tempo), Start, Stop and Continue commands and Song Position Pointers. This last type of message contains information about positions, so that a program for example "knows" where in a Song to start playback from.

Normally, this ensures that you can locate to any position and activate playback from there. In older devices, Song Position Pointers might not be implemented. This means that you will be able to synchronize properly only if you start both devices from the absolute beginning of the song.

About Tempo and Tempo Changes

Again, due to the latency phenomenon, Reason needs a bit of time to adjust to changes in tempo. If there are abrupt changes in the MIDI Clock, due to drastic tempo changes in the master, you will note that Reason will require up to one measure to adjust itself to the change. How long this actually takes also depends on the precision of the incoming MIDI Clock. The more precise it is, the faster Reason can adjust to it.

If this adjustment is a problem, try to use gradual tempo changes rather than immediate ones.

! **When Reason is synchronized to external MIDI Clock, there is no Tempo readout.**

! **Note that high-quality stretching of audio tracks is automatically disabled when syncing from external MIDI Clock.**

Input Focus and Play Focus

If you activate (external) MIDI Clock sync on the Options|Sync menu, the Transport Panel controls will be disabled, and Reason will not run unless MIDI Sync data is provided from an external device.

The Input Focus (MIDI + Audio) and Play Focus (MIDI Sync) buttons (located on the Reason Hardware Interface) relate to how incoming MIDI and MIDI sync should be handled if there are several open Song documents. If you have two or more Songs opened, and no MIDI sync is used, the currently selected Song (the document "on top") always has Input focus.

If (external) MIDI Clock sync is enabled (which is global for all currently open Song documents), this functionality changes in the following way:

- **If both "Play Focus" and "Input Focus" are activated for a Song, incoming MIDI data, MIDI sync (and Audio) will be sent to this Song, regardless of whether another Song is currently in focus.**
- **If only "Input Focus" is activated for Song, and another Song has "Play Focus", incoming MIDI (and Audio) will be sent to the former and MIDI sync to the latter (i.e this Song will play back), regardless of which Song is currently in focus.**



Synchronization using Ableton Link


About Ableton Link

Link by Ableton is a technology that keeps sequencing/playback devices and applications in sync over a wireless network. By connecting to the same network as other Ableton Link users you will be able to jam in perfect sync with other Ableton Link-enabled applications. Other users may be using apps on iOS devices or similar, but that's perfectly fine, Link works across platforms!

Any of the Ableton Link users can then start and stop their part while others keep playing. Any user in the network can also adjust the tempo in real-time and the rest of the "linked" applications/devices will follow.

Synchronizing Reason's sequencer with Ableton Link

1. **Connect your computer to the wireless network where the other Ableton Link devices/applications are connected.**
   This is done where you configure your network in your computer OS.
2. **Select "Ableton Link" from the Sync Mode selector in the Transport panel - or from the Sync sub-menu in the Options menu.**

   In the Sync Mode section a green progress bar constantly indicates the tempo and the current "position" (phase) within one single Bar.

   The number to the right of the progress bar shows how many other Link users you are connected to (4 in the example above).
3. **Hit Play in the sequencer.**
   The Reason sequencer will start when the green progress bar reaches the current play head position (phase) within the current Bar. This means that the start of the sequencer will always be correct within the Bar and thus in perfect phase-sync with the rest of the Link devices/applications.

▶ **If you change the Tempo in the sequencer, the tempo in all other Link applications will follow accordingly.**
Similarly, if the tempo is changed in any of the other Link applications in the network, Reason's sequencer tempo will change. The tempo is constantly updated and displayed in real-time in the Tempo display on the Transport panel.

▶ **If you switch back to Internal sync from Ableton Link sync, the Tempo in the Reason sequencer will remain at the tempo it had when you switched back.**
If your song has tempo automation, please have a look at "About Tempo Automation when using Ableton Link" for some additional information.

! **Note that high-quality stretching of audio tracks is automatically disabled when using Ableton Link sync.**

About recording in the sequencer when using Ableton Link

It's also possible to record in the sequencer while synchronized to Ableton Link. A couple of important things, tough:

! **We strongly recommend using "External Monitoring" when recording audio in Ableton Link sync mode.**

This is to enable the Recording Latency Compensation function, see "Latency Adjustment".

! **Pre-count in the sequencer is automatically disabled when synchronized with Ableton Link!**

About using different time signatures with Ableton Link

Using a different time signature than the other devices/applications in the Ableton Link network works just fine. The sync progress bar on the Transport panel always shows the sync phase of one single Bar, regardless of selected time signature. Using different time signatures may of course generate interesting rhythmical results, though.

About synchronizing external MIDI instruments while using Ableton Link

It's also possible to synchronize external MIDI instruments from Reason via MIDI Clock, while you are using Ableton Link. This is very useful if you, for example, are using external hardware MIDI instruments and want them to follow the Ableton Link synchronization tempo.

1. **Set up Reason to send MIDI Clock, as described in "Using Reason as MIDI Clock Host".**
2. **Select "Ableton Link" from the Sync Mode selector and then click the Send Clock button in the Transport panel:**



3. **Hit Play in the Reason sequencer.**
   The Reason sequencer will start when the green progress bar reaches the current play head position (phase) within the current Bar. As the sequencer starts, any external MIDI instruments will also be started and synced to Reason's MIDI Clock signal. The MIDI Clock tempo will then automatically follow the Ableton Link tempo.

About Tempo Automation when using Ableton Link

If you use Ableton Link synchronization in a Reason song which has Tempo Automation, the Tempo Automation lane will be automatically muted in the sequencer:



The song will then automatically follow the Ableton Link tempo instead and disregard any tempo automation.

! **As long as Ableton Link synchronization is active it's not possible to manually unmute the Tempo Automation lane!**

▶ **If you switch back to Internal sync from Ableton Link sync, the Tempo in the Reason sequencer will remain at the tempo it had when you switched back.**
The Tempo Automation lane is also automatically unmuted.

The Automation Override indicator on the Transport panel is also lit:



▶ **Click the Automation Override indicator - or press stop in the Reason sequencer - to set the tempo according to the Tempo Automation clip.**

Advanced MIDI - The External Control Bus inputs

About the External Control Bus inputs


The External Control Bus inputs allow you to receive MIDI from external equipment/applications directly to individual Reason devices.

! **MIDI control keyboards/surfaces should NOT be set up using the External Control Bus! Instead, set them up on the MIDI tab, see "Settings – MIDI".**

- **These MIDI inputs are for controlling Reason devices from an external sequencer.**
  This could be an external hardware sequencer or a sequencer application running on another computer.

! **Do NOT use the External Control Bus if you are only going to use Reason's internal sequencer for recording and playback!**

You set up the External Control Bus inputs on the "Other Controls" tab in the Settings dialog:



▶ **Select a separate MIDI port for each bus you plan to use.**
Each bus provides 16 MIDI channels, for a total of up to 64 MIDI input channels. For example, if you have an external sequencer with two MIDI outputs, you connect these to two MIDI inputs on your MIDI interface and select these two inputs for the first two busses on the Other Control tab. You will then be able to send MIDI on up to 32 channels from the external sequencer to Reason.

▶ **Make sure you don't select a MIDI port that is already selected on the Control surfaces tab (or in the MIDI Clock Sync section).**

▶ **To control external MIDI equipment from Reason, you can use the MIDI Out Device. Refer to "MIDI Out Device" for more details.**

Routing MIDI to devices

Each External Control Bus can control up to 16 different Reason devices, one for each MIDI channel. To route a MIDI channel directly to a Reason device, proceed as follows:

1. **Locate the Reason Hardware Interface at the top of the rack and click the ADVANCED MIDI button.**



The Advanced MIDI Device panel is unfolded.

2. **On the Advanced MIDI Device panel, click the Bus Select button for the External Control Bus you want to use (A, B, C or D).**



3. **Below the Bus Select buttons there are fields for the 16 MIDI channels. Click the arrow button for the desired MIDI channel and select a Reason device from the menu that appears.**
   Incoming MIDI data on that bus and channel will now be sent directly to the selected device. In other words, the master keyboard routing in the sequencer is bypassed.

Receiving Controller data via MIDI

It is possible to send controller data from an external sequencer to control Reason parameters. Just set up your external device to transmit the correct MIDI controller messages on the right MIDI port.

To find out which MIDI Controller number corresponds to which control on each device, please see the "MIDI Implementation Charts.pdf" document.

Once you have located the controller numbers and set everything up, you can record and edit the controller data in the external sequencer as you normally do, and the Reason parameters will react correspondingly.

▶ **Do not confuse this with Remote control. Remote does not require any mapping of controller numbers for supported control surfaces! See "About Remote".**

About recording Pattern Changes

As specified in the MIDI Implementation, MIDI Controller #3 can be used to switch patterns in a device. However, pattern changes activated this way occur immediately (not at the end of the bar), which may or may not be what you prefer.

Please, see "Recording pattern automation", "Editing pattern automation" and "Drawing pattern automation" for information on recording and editing pattern changes.

Chapter 26
Optimizing Performance



Introduction

Reason is a program of infinite possibilities. You can create extremely complex songs, with a vast number of audio tracks and rack devices. While this is one of the most exciting properties of the program, it does have a drawback – it means that you must be careful with how you manage your computer processing power.

Each audio track and device you add in your song uses up a bit of computer processing power – the more audio tracks and devices, the faster the computer has to be. However, you can set up your devices to require more or less processing power. For example, a sound on the Subtractor synthesizer that only uses one oscillator and one filter requires less processing power than one using both dual oscillators and dual filters.

Samples used in your songs also require RAM (memory) to load properly. The use of RAM can also be managed, as described at the end of this chapter.

When collaborating on songs with other Reason owners, you should do what you can to reduce the requirements for playing back a certain song, both in terms of processing power and in terms of RAM requirements. Other users may not have as powerful a computer as you do!

Checking overall processing power

To the right on the Transport Panel you will find a meter labeled DSP. This indicates how much processing power is used at any given moment.



The DSP meter on the Transport Panel

The higher this meter goes, the higher the strain on your computer processor. You will note when your processor is heavily loaded that graphics will update slower. Finally, when there's too little power left to generate audio properly, the sound will start to break up.

Checking processing power for individual devices

There is also a function for displaying the processing power of individual devices in the rack. This lets you pinpoint any CPU hogs, letting you possibly replace those devices with less CPU demanding ones if necessary.

- **Select "Show CPU Load for Devices" from the Options menu.**
  The CPU Load for the devices is shown in their upper right corners:



Europa is currently using 1% CPU together with its Mix Channel device, and Dr Octo Rex is using 15% CPU together with its Mix Channel device

- **Each Mix Channel/Audio Track device shows the total CPU sum of their connected devices, including any Insert Effects.**

Optimization and latency reduction

As described in "About latency" in the Audio Basics chapter, you generally want the lowest possible latency, to get the best response when you record and play in Reason in real time. However, selecting too low a latency is likely to result in playback problems (clicks, pops, dropouts, etc.). There are several technical reasons for this, the main one being that with smaller buffers (lower latency), the average strain on the CPU will be higher. This also means that the more CPU-intensive your Reason song (i.e. the more devices and audio tracks you use), the higher the minimum latency required for avoiding playback difficulties.

Therefore, you may need to adjust the latency. This is done differently depending on which audio cards, drivers and operating system you are using.

Making Buffer Size adjustments in the ASIO Control Panel (Windows)


If you are using an ASIO driver (Windows only) specifically written for the audio hardware, you can in most cases make settings for the hardware in its ASIO Control Panel. This panel (opened by clicking the ASIO Control Panel button in the Settings-Audio dialog) may or may not contain parameters for adjusting the latency. Usually this is done by changing the number and/or size of the audio buffers - the fewer and smaller the audio buffers, the lower the latency. Please consult the documentation of your audio hardware and its ASIO drivers for details.

! **Raising the buffer size to eliminate audio artefacts on playback is mainly effective if you are currently using very small buffers, 64 to 256 samples. If the buffers are already big (1024 or 2048 samples) you will not notice much difference.**

Making Buffer Size adjustments in the Reason Settings dialog

If you are running Reason under Windows and are using an ASIO driver, or under macOS and are using a Core Audio driver, you can adjust the input and output latencies in the Settings – Audio dialog.

▶ **This is done by dragging the Buffer Size slider or by clicking the spin controls to the right.**



General procedure for reducing latency

The basic procedure for optimizing the latency is the following:

1. **Open a song and start playback.**
   You want to choose a song that is reasonably demanding, i.e. with more than just a few tracks and devices.
2. **Open the Settings dialog.**
   Under macOS, this is found on the Reason menu; under Windows it's found on the Edit menu.
3. **Click the Audio tab and locate the Buffer Size slider.**

! **If you are making adjustments in the ASIO Control Panel for hardware with an ASIO driver (Windows only), you should make a note of the current buffer settings before changing them.**

4. **While the song is playing, listen closely for pops and clicks and try lowering the latency (Buffer Size).**
5. **When you get pops and clicks, raise the Buffer Size value a bit.**
6. **Close the Settings dialog (and ASIO Control Panel, if open).**

About Latency Compensation

Below the Input Latency and Output Latency rows in the Settings-Audio dialog, you will find an item called Latency Adjustment. This value is used internally in Reason to compensate for latencies when recording audio using external monitoring.

Latency Adjustment

! **Changing the Latency Adjustment parameter is never necessary when you have selected "Automatic" in the Monitoring section on the User Interface tab in Settings - see "Play in background".**

Latency Adjustment is when the program adjusts the position of the recorded audio according to the current latency. Here's how it works:


If you're recording audio and are not monitoring through Reason (e.g. monitoring directly through the audio card or via an external mixer), the audio you record will reach the program slightly late. This is because you play along with background tracks or the metronome - and you hear these delayed by the output latency. Also, the sound you record is sent to the program via the buffers in the audio hardware - it is delayed by the input latency.

Reason compensates for this by moving the recorded audio earlier by the sum of the input+output latencies. This compensation is also done in "Manual Monitoring" mode, if Monitor was Off for the recorded track (when you started recording).

If Monitor is On, there is no latency compensation. This is because the monitored sound will also be delayed, and numerous tests have shown that the performer will actually play slightly ahead to compensate for this. In other words, when monitoring through Reason, the performer is expected to do the latency compensation himself/herself.

If you are monitoring via an external mixer, and have selected "External" in the Monitoring section on the User Interface tab in Settings, there might be situations where you experience that the recorded audio is generally played back too early - or too late - in the song. This could be because your audio card doesn't actually have the latency values it reported to Reason.

If you should experience that your audio recordings are played back too early or too late compared to the instrument tracks in your song, you can adjust this by editing the Latency Adjustment parameter:



▶ **Click the Latency Adjustment spin controls to compensate for early or late playback of audio track recordings**
If the audio appears too early during playback, adjust to a negative (-) value.

If the audio appears too late during playback, adjust to a positive value.


Optimizing your computer system

In this manual we do not have the possibility to give you detailed procedures for optimizing your computer for maximum power. This is a subject that we could write complete books on. However, there are a couple of very useful things to check and adjust.

About Multi-core processors

When you're using a multi-core processor, Reason will take full advantage of this in a very sophisticated way. Similarly, if your computer has several multi-core processors, Reason will use the full capacity of these to enhance the performance.

In the "Max audio threads" drop-down on the Audio tab in Settings you can select the maximum number of audio threads Reason should be allowed use. The "Default" setting equals the total number of physical cores in your computer's CPU (corresponding to the old "Use multi-core audio rendering" option, but without the "Use hyper-threading audio rendering" option in earlier Reason versions). On Apple Silicon computers the Max audio threads setting defaults to the number of Performance Cores.



This preference can also be used to limit the number of threads if you want to leave room for other apps or perhaps multi-core VSTs.


- **If you should experience performance problems in Reason, try selecting another Max Audio Threads number, starting from the highest number and going down one number at a time until you get the best performance.**

▶ **If you are using a dual-core Intel CPU and previously used the "Use multi-core audio rendering" and "Use hyper-threading audio rendering" functions available in earlier Reason versions, select the "3 (HT)" setting to get the equivalent performance.**

About hyper-threading audio rendering

Hyper-threading audio rendering could improve the performance even further. Note that this depends on your computer's CPU and other hardware, so there is no guarantee the performance will improve. If you are experiencing performance problems, try activating or deactivating this to see if the performance improves.

About audio rendering using the audio card buffer size setting



The "Render audio using audio card buffer size setting" function should be selected (ticked) for best plugin performance. When selected, the audio batches are rendered internally according to the set Buffer size (see "Making Buffer Size adjustments in the Reason Settings dialog" above). For example, if you have a Buffer size of 512 Samples, each audio batch will be 512 samples internally. Raising the Buffer size will let Reason process larger audio batches in one go, which is often more efficient. Many plugins are also more efficient when doing larger audio batches. if you are using DSP-heavy VSTs (mastering effects, for example), these will run a lot smoother with this function selected.

! **Note that old songs might sound different with this function selected, if the songs uses feedback routings and CV connections.**

If unchecked (off), all audio batches are rendered internally at a fixed size of 64 samples - regardless of the Buffer size setting. This might be desirable if you are using feedback signal routings and CV connections in your songs, and want the internal latency of those connections to be fixed at a short value all the time. This might result in performance problems for DSP-heavy VSTs, though.

Unchecked will give the same performance as in Reason 10.2 and older versions.

About hard drives

Most state-of-the-art hard drives will work perfectly together with Reason. Generally, the faster hard drive(s) you use, the better. A large hard drive is also highly recommended when working with DAWs like Reason. A single song with a lot of recordings in it could easily reach around 1 GB in final size. During recording and editing, the song file size could be a lot bigger than that, so a hard drive with at least 20 GB space is definitely recommended.

General optimization tips

Finally, we'd like to share a couple of other general optimization tips:

- **Quit other programs that are running at the same time as Reason.**
- **Remove background tasks on your computer.**
  This might be any background utilities you have installed as well as networking, background Internet activities etc.
- **Under Windows, make sure you use the latest and most efficient ASIO driver for your audio card.**
- **Only work on one Reason Song document at a time.**
  Songs that are open in the background do consume some processing power, even though they're not playing.
- **Lower the sample rate setting on the Audio tab in the Settings dialog.**
  This is a very quick and convenient way to try to play a song that your computer otherwise can't handle.
- **Raise the Buffer size on the Audio tab in the Settings dialog.**
  See "Making Buffer Size adjustments in the Reason Settings dialog".



Optimizing Songs

With most of today's computers, processing power is usually not a problem. However, if you should experience excessive CPU load, there are some things you could do to optimize your Reason songs. Below follows things you can check and change to make sure your song uses as little computer processing power and memory as possible:

Global

- **To reduce the Song file size, delete unused recordings on Audio Tracks.**
  This won't affect the processing power but will reduce the Song file size, which might be desirable in many situations. See "Delete Unused Recordings".
- **Use the "Save and Optimize" function when you're finished editing your song.**
  As a final step, after you have recorded and edited your song, use the "Save and Optimize" function on the File menu. This will remove any "empty" disk areas in the song file, making the file as small as possible - see "Saving and optimizing a Song".
- **Bounce Mixer Channels.**
  If you're using a lot of devices in an instrument track, you could bounce the instrument track to an Audio Track. Doing so makes it possible to delete the instrument track afterwards and thus reduce the processing power. See "Bouncing Mixer Channels".
- **Delete unused devices.**
  If a device isn't actually doing anything, delete it from the rack.
- **Use fewer devices.**
  For example, instead of using several similar reverbs as separate insert effects, replace them all with one, set up as a send effect on a Send FX bus in the Main Mixer. By the same token, try to use one sampler playing several different samples instead of numerous samplers playing one sample each.

Main Mixer

- **Make sure you deactivate any channel strip parameters or sections you don't use in your song.**
  This could, for example, be Input Gain and INV, EQ, Filters, Dynamics and Insert FX.
- **Delete any Mix Channel devices and/or Audio Track devices you don't use in your song.**

Sample Players – NN19, NNXT, Dr. Octo Rex, Grain and Redrum

- **Only activate High Quality Interpolation (where applicable) when it is required.**
  Listen to the sound in a context and determine whether you think this setting makes any difference.
- **If you are playing back a sample at a much higher pitch than it was recorded at, consider sample rate converting the actual sample file to a lower sample rate.**
  This will require an external sample editor with good sample rate conversion facilities.

Filters – Subtractor, Thor, Malström, NN19, NNXT, Grain, Europa and Dr. Octo Rex

- **Deactivate filters that are not used.**
  Observe that if the Cutoff is all the way up or the envelope is set to open the filter fully, then the filter doesn't affect the sound. Conserve processing power by disabling the filter altogether.



Polyphonic Devices – Subtractor, Thor, Malström, NN19, NNXT, Grain, Europa, Dr. Octo Rex and Redrum

- **Try making the device play fewer voices.**
  This can be done for example by lowering the release and setting the Polyphony setting to exactly the maximum number of notes played simultaneously by this device.

! **Note that just lowering the polyphony setting has no effect. Unused voices do not consume processing power.**

- **Where applicable, try the Low Bandwidth (Low BW) setting.**
  This will remove some high frequency content from the sound of this particular device, but often this is not noticeable (this is especially true for bass sounds).

Subtractor

- **Try avoiding using Oscillator 2 altogether.**
  If you can create the sound you need with only one oscillator, this saves considerable amounts of processing power.
- **Do not use the oscillator Phase mode if you don't need it.**
  In other words, set the Oscillator Mode switches to "o", not "⋆" or "–".
- **Do not activate Noise unless required.**
- **Do not activate Filter 2 unless required.**
- **Do not use FM unless required.**
  In other words, set the oscillator FM knob to "0" and make sure no modulation source is routed to FM.

Thor

- **In general, unload any filters or oscillators that aren't used.**

Malström

- **If it isn't necessary, refrain from using Osc B at all.**
  If you can produce the desired sound by using Osc A only, this will save a lot of processing power.
- **If one or both Oscillators are routed to one Filter only, and/or the Spread parameter is set to "0", only connect one of the outputs (the one to which the filter is connected) to the mixer, and leave the other one unconnected.**
- **Try to see if you can achieve the desired effect by using only one of the filters, and without using the shaper.**
  Using both of the filters and the shaper in conjunction requires considerably more processing power than using just one of the filters and/or the shaper.

Redrum

- **Do not use the Tone feature available on channels 1, 2 and 9.**
  Make sure the Tone controls and their accompanying Vel knobs are set to "0" ("twelve o' clock" position).

Mixer devices

- **Avoid using stereo inputs when not required.**
  For example, if your sampler or Dr. Octo Rex player is playing mono material, only connect it to the Left input on a mixer channel. Leave the Right input unconnected.
- **Do not activate EQ (Mixer 14:2 only) unless required.**
  If a channel doesn't make use of EQ, make sure it's EQ button is deactivated.



Distortion

- **The D-11 Foldback Distortion will use up less CPU power than the Scream 4 Distortion device.**

Reverb

- **The RV-7 uses much less power than the RV7000.**
  For some applications the RV-7 might do just fine, and will use up much less power.
- **If you are running out of processing power, try the Low Density algorithm for the RV-7.**
  This uses up much less power than other algorithms.

Send Effects

- **When you are using mono effects as send effects, you can connect the effect returns in mono as well (disconnect the cable to Aux Return Right on the Main Mixer).**
  This is true for the following effects:
- **D-11 Distortion**
- **Scream 4 Distortion**
- **ECF-42 Envelope Controlled Filter**
- **COMP-01 Compressor**
- **PEQ-2 Parametric EQ**
- **DDL-1 Delay (provided the Pan parameter is set to center position).**
- **MClass effects; Equalizer, Compressor, Maximizer.**

RAM requirements

Songs not only use up system resources in terms of processing power and hard disk space, they also require RAM (memory) to load at all. The amount of RAM required for loading a song, is directly proportional to the amount of samples used in the song. For example, a song which uses only Subtractors and effects requires very little RAM.

If you are running out of RAM try the following:

- **Close other Song documents.**
  All open songs compete for RAM.
- **Terminate other applications.**
  All running applications compete for the RAM available in the computer.
- **Use mono samples instead of stereo ones.**
  Mono samples require half the amount of RAM.
- **Try sample rate converting sample files to a lower sample rate.**
  Note that this could affect sound quality negatively. Also note that it will require an external sample editor with good sample rate conversion facilities.





Chapter 27
Hardware Interface



Introduction



The Hardware Interface device is where you connect Reason to the "outside world". This is where MIDI is received, and where audio signals are routed from physical inputs and to physical outputs of your audio hardware. The Hardware Interface is always present at the top of the rack, and cannot be deleted. This chapter is meant to serve as a panel reference, describing the various sections of the device. How to set up your audio hardware is described in the "Audio Basics" chapter.

The Hardware Interface is normally unfolded, showing a panel with 2 Sampling Inputs, 16 Audio Inputs and 16 Audio Outputs and a couple of buttons.

- **On the right hand side at the top of the panel are the Input Focus and Play Focus buttons - these are described in "Input Focus and Play Focus".**
- **The Sampling Input, Audio Input and Audio Output sections feature a LED meter for each input and output channel.**

! **Remember that the Hardware Interface is where any possible audio clipping will occur in Reason. Keep an eye on the clipping indicator on the Transport Panel, and also on the individual meters on the Hardware Interface panel. If a channel pushes the meter into the red, the level should be reduced at the source - see "About audio levels" in the "Audio Basics" chapter.**

- **The multi-color LEDs below each channel indicate the following:**
  Green LED: Available and used channel (cable connected to the channel jack on the rear panel).

  Yellow LED: Available but unused channel (no cable connected to the channel jack on the rear panel).


  Red LED: Unavailable channel but with a connected cable on the rear panel. No audio will be present on channels with red LEDs.

  Unlit LED: Unavailable and unconnected channel (no cable connected to the channel jack on the rear panel).
- **By clicking the "ADVANCED MIDI" button at the top on the panel, the Advanced MIDI Device panel is shown:**




Refer to "Advanced MIDI Device" for more information.

- **By clicking the "MORE AUDIO" button at the top on the panel, an additional Audio In and Out panel is shown for a total of 64 inputs and outputs.**



Refer to "More Audio" for more information.

- **By clicking the "BIG METER" button at the top on the panel, a panel with bigger audio level meters is shown:**



Refer to "The Big Meter" for more information.

Sampling Input section



The Sampling section features two audio inputs (L & R) to which you should route the audio signals you want to sample. There is also a Level knob and two Monitor buttons. See "Setting up for sampling" for details on how to sample.

Advanced MIDI Device



! **Do NOT use the Advanced MIDI Device if you are only going to use Reason's internal sequencer for recording and playback!**

This is opened by clicking the "ADVANCED MIDI" button on the Hardware Interface panel. The Advanced MIDI device is only used if you are controlling Reason from an external sequencer, using the External Control Bus inputs. Normally, you send MIDI to a track via the sequencer, by selecting the sequencer track.

You can select MIDI ports for up to four External Control Busses (on the "Other Controls" tab in Settings). Each bus can host 16 MIDI channels, for a total of up to 64 MIDI input channels. The Advanced MIDI Device is where you can route each MIDI channel to a specific device in the Reason rack:

1. **Select one of the External Control Busses by clicking the corresponding Bus Select button at the top of the Advanced MIDI device.**
2. **Pull down the device pop-up menu for a MIDI channel and select a device.**
   The menu lists all devices in the current song.

Now, incoming MIDI data on the selected bus and MIDI channel is sent directly to the selected device, bypassing the Reason sequencer. The name of the device is shown in the name field for that MIDI particular channel.

3. **Try sending MIDI notes from the external sequencer, on the selected bus and MIDI channel.**
   The indicator below the channel's name field should light up.

See also "Advanced MIDI - The External Control Bus inputs" in the Advanced MIDI and Synchronization chapter.

More Audio


Reason supports up to 64 audio input and 64 audio output channels. The additional 48 inputs and 48 outputs can be found on the "More Audio" panel.

▶ **To view inputs 17-64 and outputs 17-64, click the "More Audio" button.**



Each additional input and output features a meter and a multi-color LED indicator which will be lit in different colors depending on current state - see "Introduction".

The Big Meter



To get a better overview of the levels of a particular channel pair you can bring up the Big Meter on the Hardware Interface.

1. **Click the “BIG METER” button on the front panel.**
   The “Big Meter” panel shows up.

2. **Select the Input or Output pairs to view in the Big Meter by clicking on the corresponding Channel Selection button below each Input or Output pairs.**
   Alternatively, select channel by turning the Channel Selection knob.

▶ **It’s also possible to select various Meter Modes, or combinations of Meter Modes, by clicking the Meter Mode button to the far left.**
The available Meter Modes are:

- **VU**
  The VU Mode simulates the behavior of analog meters and shows the RMS (Root Mean Square) value of the signal. Since the RMS value is an "average" of the signal level over time it's not suited for detecting fast transients in the sound. Rather, VU meters are useful for monitoring the overall loudness of the signal.

  In VU Mode, the meter response is 300 ms/20 dB for both attack and release. There is no peak segment in the meter.

▶ **The VU Offset can be set in 2 dB steps between -20 and 0 dB, by turning the VU Offset knob.**
This setting determines how the VU dB scale relates to the Peak dB scale. If you have no specific preference in this matter, you don't need to change the VU Offset.

! **The VU Offset setting will affect the readout of all Meters on the Main Mixer channel strips and on their corresponding Rack devices.**

- **PPM**
  In PPM (Peak Program Meter) Mode, the meter response is 0 ms rise and 2.8 s/24 dB fall. The PPM Mode is perfect for detecting transients in the sound. There is no peak segment in the meter.

- **PEAK**
  In PEAK Mode, the meter response is 0 ms for both rise and fall, which means that this mode provides the most accurate representation of the signal level over time. Since the fall time is 0 ms, it could be quite distracting to the eyes to watch the meters in PEAK mode. If so, the PPM Mode might be more convenient since it's equally fast at responding to transients, but falls more slowly.

  The peak segment (the rightmost LED segment, indicating the highest level) has a fall time according to the Peak Hold parameter setting (5 seconds or infinite). This allows you to more easily spot very brief level peaks.

- **VU+PEAK**
  In VU+PEAK Mode, the meter response is according to the VU Mode, plus a peak segment.

- **PPM+PEAK**
  In PPM+PEAK Mode, the meter response is according to the PPM Mode, plus a peak segment.

If the audio level for the selected is, or have been, too high, the Clip indicators on the Big Meter will stay lit until you click the "Reset" button, or select new audio channels for the Big Meter. See "About audio levels" for more information on how to use and work with the Big Meter.

Chapter 28
Dr. Octo Rex
Loop Player



Introduction



The Dr. Octo Rex Loop Player is the successor to the trusty Dr. Rex Loop Player, introduced in Reason Version 1. The Dr. Octo Rex can hold up to eight different REX loops at once, in eight pattern memories, and allows you to switch between loops and slices in very flexible ways. The Dr. Octo Rex Loop Player is fully backwards compatible with the discontinued Dr. Rex device. This means that all REX loops that previously used Dr. Rex devices in your songs will now open and play back in Dr. Octo Rex devices instead. The loops will sound exactly the same as they did in Dr. Rex.

The Dr. Octo Rex Loop Player is capable of playing back and manipulating files created in ReCycle, another product created by Reason Studios, or bounced from open Single Take audio clips in Reason (see "Bounce Clip to REX Loop"). ReCycle is a program designed especially for working with sampled loops. By "slicing" an audio loop and making separate samples of each beat, ReCycle makes it possible to change the tempo of loops without affecting the pitch and to edit the loop as if it was built up of individual sounds.

ReCycled Loops

To fully understand Dr. Octo Rex you need to understand what it means to ReCycle a drum loop. Imagine that you have a sample of a drum loop that you want to use in a track you are working on. The loop is 144 BPM and your track is 118 BPM. What do you do? You can of course lower the pitch of the loop, but that will make the loop sound very different, and if the loop contains pitched elements they will no longer match your song. You can also time stretch it. This won't alter the pitch, but will make the loop sound different. Usually it means that you loose some "punch" in the loop.

Instead of stretching the sample, ReCycle slices the loop into little pieces so that each drum hit (or whatever sound you are working with) gets its own slice. These slices can be exported to an external hardware sampler or saved as a REX file to be used in Reason. When the loop has been sliced you are free to change the tempo any way you want. You can also create fills and variations since the slices can be moved around in the sequencer.

About REX file formats

Dr. Octo Rex can read REX files in the following formats:

- **REX (.rex)**
  This is the file format generated by previous versions of ReCycle (Mac platform).
- **RCY (.rcy)**
  This is the file format generated by previous versions of ReCycle (PC platform).
- **REX 2 (.rx2)**
  This is the ReCycle file format for both Mac and PC platforms generated internally in Reason (see "Bounce Clip to REX Loop") or by ReCycle version 2.0. One of the differences between the original REX format and REX2, is that the REX2 format supports stereo files.

! **Unlike the Dr. Rex device, Dr. Octo Rex can also load and save the device panel settings in a special Patch format (.drex). The REX file(s) and the Dr. Octo Rex panel settings are also saved in the Song file just like every other patch in the song.**

Loading and saving Dr. Octo Rex patches

Loading and saving Dr. Octo Rex patches is done in the same way as in other patch based devices - see "Loading patches" and "Saving patches".

Dr. Octo Rex patches can consist of up to eight separate REX loops. When you load an Dr. Octo Rex patch, the REX loop(s) will be automatically loaded in the Loop Slots with their names shown in the display(s) below each button.

- **You can also load Dr. Octo Rex patches by dragging them from the Browser and dropping on the device panel.**



About the Dr. Octo Rex patch format

Dr. Octo Rex patches (.drex) contains all panel and synth parameter settings as well as references to all (up to eight) REX loops. The actual REX files are not contained in the patch but must be available separately on the computer.

About opening songs that previously used Dr. Rex devices

Songs created in earlier versions of Reason that used Dr. Rex devices will open just fine in this version of Reason. Any Dr. Rex devices will be replaced by Dr. Octo Rex devices and the corresponding REX loop will load in Loop Slot 1. The original Dr. Rex device settings will be translated as follows:

- **The panel parameter settings are automatically applied to the Dr. Octo Rex device.**
  This makes the loop play back and sound exactly like it did when you created it in Dr. Rex.
- **The Enable Loop Playback button on Dr. Octo Rex will be set to Off.**
- **Any automation for Level and Transpose are converted to Master Level and Global Transpose.**
- **Routing to CV Mod Input Level is routed to Master Volume.**
- **The Dr. Octo Rex is set to "Master Keyboard Input to Slices" Mode, so that it behaves exactly like the old Dr. Rex.**

Playing Loops

1. **Make sure the Enable Loop Playback button is on (lit).**



2. **Click the desired Loop Slot button.**
3. **Play back the loop by clicking the Run button.**
   The loop in the selected Loop Slot will play back repeatedly in the tempo set on the Transport Panel. If you change the tempo, the loop tempo will follow.

- **You can also play the loop once via MIDI, by using the D0 key.**
- **To check out the loop(s) together with other device sequencer data and patterns already recorded, click the sequencer Play button.**
  The loops will automatically play back in perfect sync with the sequencer.


Switching playback between Loop Slots

Switching playback between loops in different Loop Slots is just like switching a Pattern in a Redrum device, for example.

1. **Activate the Enable Loop Playback button on the Dr. Octo Rex device.**
2. **Click the Run button - or start sequencer playback.**
3. **Click another Loop Slot button to switch loop.**
   Selecting Loop Slots that have no loops loaded will result in silence.

The Trig Next Loop function

The Trig Next Loop function determines how long Dr. Octo Rex waits after a Loop Slot button (or a key) is pressed before it actually "gates in" or triggers the loop. This allows for different "precision" when switching between running loops:



- **Activate the Bar button to make the loops switch at the next bar of the current loop.**
- **Activate the Beat button to make the loops switch at the next beat of the current loop.**
- **Activate the 1/16 button to make the loops switch at the next 1/16th note of the current loop.**

Switching Loops using Pattern Automation in the sequencer

Switching between Loop Slots can be automated, by using Pattern Automation in the main sequencer.

! **When using Pattern Automation, the Trig Next Loop function described above is disregarded - the switching between Loop Slots is instantaneous.**

Refer to "Pattern automation recording details" for details about Pattern Automation.


! **When you use the Pencil tool to draw Pattern Automation clips and select Pattern in the Inspector, the Bank selection is of no importance since Dr. Octo Rex doesn't make use of Banks.**

Triggering playback and selecting Loop Slots from a MIDI keyboard

It's also possible to control playback, stop and Loop Slot selection in real-time by pressing different keys on a MIDI keyboard. By pressing the keys E0 to B0 you select Loop Slot 1-8 and start playback of the corresponding loop. The loop(s) will play back continuously, one loop at a time, until you press the D#0 key to stop playback, or click the Run button or Stop in the main sequencer. The time between key press and Loop Slot switching is determined by the Trig Next Loop function, see "The Trig Next Loop function".

! **Note that the Enable Loop Playback button must be on.**

The picture shows what keys should be pressed to select and play Loop Slot and to stop loop playback:



- **To maintain backwards compatibility with Dr. Rex, the D0 key can be used to play back the REX loop in the Loop Slot that currently has Note To Slot focus (see "Note To Slot").**
  The loop is played back once (single-shot) and cannot be stopped during this time.

Adding Loops

To add one or several (max 8) loops into the Dr. Octo Rex Loop Player, proceed as follows:

1. **Unfold the Loop Editor panel.**
2. **Select the Loop Slot you wish to add the (first) REX loop into.**



3. **Open the REX Loop browser by clicking the folder button to the left of the Loop Slot buttons.**
   Alternatively, select "Browse Loops..." from the Edit menu or the device context menu.
4. **In the Browser, locate and select the desired loop(s).**
   You can listen to the loops before loading by using the Preview function in the Browser.

▶ **To select several loops, hold down [Ctrl](Win)/[Cmd](Mac) and click.**
To select a range of loops, hold down [Shift] while clicking the last file.

5. **Click the Load button in the Browser to load the selected file(s) in the Loop Slot(s).**

! **If you have selected and opened several loops, the first loop will load in the selected Loop Slot and the rest will load in consecutive Loop Slots.**

! **Loading new REX files will replace any files currently in the slots.**

▶ **Alternatively, select the REX loop(s) in the Browser and drag and drop it/them on the Loop Editor panel section, or on a Loop Slot button on the Controller Panel.**
If you have selected several loops, the first loop will load in the selected Loop Slot and the rest will load in consecutive Loop Slots.

! **If you drag a single REX loop from the Browser and drop on the Controller Panel (not on a Loop Slot button), the REX loop will load into Slot 1 and all other Slots will be cleared.**

Loading Loops “On the Fly”

Another practical method for checking out loops, is to load them “on the fly”, i.e. during playback. This is especially useful if you want to check out a number of loops against other sequencer data and patterns previously recorded. Proceed as follows:

1. **Activate the Enable Loop Playback button on the Dr. Octo Rex device and start sequencer playback.**
   The REX loops and the sequencer are synced.
2. **Now load a new REX file by using the Browser in one of the usual ways.**
   After a brief silence, the new file is loaded, and sync is maintained.
3. **Repeat step 2 as necessary until you have found a suitable loop.**

▶ **If you are trying out loops within the same folder, the quickest ways to select and load a new loop is to use the arrow buttons next to the loop name display.**
Or, you can click in the loop name display and select a new loop from the pop-up menu that appears.

Removing Loops

▶ **To remove a loop from a Loop Slot, select “Remove Loop” from the Edit menu or device panel context menu.**

Cut/Copy and Paste Loops between Loop Slots

To cut or copy a loop from one Loop Slot and paste into another, proceed as follows:

1. **Click the button of the Loop Slot that contains the loop you want to cut or copy.**
2. **Select “Cut Loop” or “Copy Loop” from the Edit menu or panel context menu.**

! **You have to context-click on the panel (not any button or knob) to access the correct context menu.**

3. **Click the destination Loop Slot button and select “Paste Loop” from the Edit menu or panel context menu.**
   Now, you can edit the slices of the pasted loop as desired, see “Slice handling”.

Playing individual Loop Slices

Besides playing back entire REX Loops using the Run function (or Play in the sequencer), it’s also possible to play individual slices of a loop from a MIDI master keyboard. This way you can use the Dr. Octo Rex almost like a traditional sampler, playing separate slices from separate keys.

The slices are automatically distributed in semitone steps, with the first slice on MIDI note C1, the second slice on C#1 and so on, with one note for each slice. The note range differs depending on how many slices the REX Loop contains.

▶ **Define which REX Loop to control from the MIDI master keyboard by selecting the desired Loop Slot with the Note To Slot knob:**



The range is 1-8 corresponding to Loop Slots 1-8. Selected Slot is indicated with a lit LED.

Creating sequencer notes


The individual slices in a REX loop can be transferred as separate MIDI notes to tracks in the sequencer. This makes it possible to have detailed control over every single sample in a REX loop. Proceed as follows to create sequencer notes from the slices:

1. **Select the sequencer track associated with the Dr. Octo Rex device.**
2. **Set the left and right locators to encompass the section you want to fill with REX notes.**
3. **Select the Loop Slot that contains the REX loop you want to copy to the sequencer track.**
4. **Click the Copy Loop To Track button.**




Now, the program will create clips containing a note for each slice of the REX loop in the selected Loop Slot, positioned according to the timing of the slices. The notes will be distributed in semitone steps, with the first note on C1, the second on C#1 and so on, with one note for each slice.

In addition to the created notes, the Note To Slot parameter (see "Note To Slot") is copied into the clips as a Performance Controller. This way, Dr. Octo Rex will always know which Note Slot the generated notes originated from and will thus automatically play back the loop slices from the correct Loop Slot.




The loop clips in the Arrange Area...



...and in the Edit Area.


5. **Disable the Enable Loop Playback parameter.**



This is because you probably don't want the loop playback to be controlled by the regular Run function but from note playback in the sequencer. If the Enable Loop Playback parameter is on, there will be double notes during playback from the sequencer.


Activating playback in the sequencer will now play back the notes on the sequencer track. These in turn will play back the slices of the REX loop in the Loop Slot defined by the Note To Slot parameter, in the correct order and with the original timing maintained. Now the fun begins!

- **If the space between the Left and Right locators is greater than the length of the REX loop, the clips will be repeated on the note lane.**



The REX loop is 1 bar long and the space between the locators is 4 bars, thus the clip is repeated four times on the note lane.

- **The Copy Loop To Track function always creates an exact number of complete clips, meaning that the last clip may "stick out" after the right locator.**



Here, the REX loop is 4 bars long. Since there are only two bars between the locators, the clip will stick out after the right locator.

! **If you are using the Alt function for slices in the REX loop, these slices will output different note numbers each time you use the Copy Notes To Track function. See "About the Alt parameter" for details.**

▶ **If you like, you can manually resize the clip to two bars by clicking and dragging the right clip handle. The last two bars of the clip will then be masked and won't play (see "Resizing (masking) clips").**

- **You can change the groove in the loop by quantizing or moving notes.**
- **You can transpose notes to change the order of the slices on playback.**
- **You can use the Alter Notes function (see "Alter (Note pitches)") to scramble the loop notes - without destroying the original loop timing.**
- **You can remove and draw new notes, creating any kind of variation.**
- **You can use the User Groove function to apply the rhythmic feel of the loop to notes on other sequencer tracks.**

For details about editing in the sequencer, see the "Note and Automation Editing" chapter.

! **Note that if you have created sequencer notes from a REX file in one Loop Slot, selecting another Loop Slot with another REX loop could make the playback sound awkward. This is because the notes generated from the original REX loop will in most situations not correspond to the slices in the other REX loops. However, in some situations this could produce really interesting results so don't be afraid to experiment.**

- **You can automate Loop Slot selection using the Notes To Slot function, see "Note To Slot".**

You can also export the REX file as a MIDI file, as described in "Export REX as MIDI File...".

Slice handling

Selecting Slices



A selected slice is indicated by being highlighted in the waveform display. To select a slice, use one of the following methods:

- **By clicking in the waveform display.**
  If you hold down [Alt](Win) or [Option](Mac) and click on a slice in the waveform display, it will be played back. The pointer takes on the shape of a speaker symbol to indicate this.
- **By using the "Slice" knob below the waveform display.**
- **Via MIDI.**
  If you activate "Select Slice Via MIDI", you can select and "play" slices using your MIDI keyboard. Slices are always mapped to consecutive semitone steps, with the first slice always being on the "C1" key.



- **If you play back a loop with "Select Slice via MIDI" option activated, each consecutive slice is selected in the waveform display as you play the keys.**
  You can edit parameters during playback.

Editing individual Slices

There are two basic methods you can use to edit individual slices in Reason:

- **In the Waveform display of the Dr. Octo Rex device.**
  This is used for making playback settings for a slice.
- **In the Sequencer.**
  Here you can edit the notes that play the slices. There is a special REX edit lane for editing REX slice notes, with the notes indicated by the slice numbers instead of by pitches. Editing notes in the sequencer is described in the "Note and Automation Editing" chapter.

Editing in the Waveform Display



Here you are able to edit several parameters for each slice, by first selecting the slice and then using the knobs below the waveform display. If you want to edit a single parameter for several slices at once, a more convenient way would be to use the Slice Edit Mode, see "The Slice Edit Mode". The following slice parameters can be set:


Parameter	Description
Pitch	Allows you to transpose each individual slice in semitone steps, over a range of more than eight octaves.
Pan	The stereo position of each slice.
Level	The volume of each slice. The default level is 100.
Decay	Allows you to shorten individual slices.
Rev	Allows you to play back individual slices reversed (backwards)
F.Freq	Allows you to modify the Filter (cutoff) Frequency of individual slices. This value is added to, or subtracted (if negative) from the FREQ value of the synth panel, see "Filter Frequency".
Alt	Allows you to assign slices to an Alternate group (1-4). Slices assigned to any of these four Alt groups will be played pack in a random fashion within each group, see "About the Alt parameter".
Output	Allows you to assign individual slices to separate audio output pairs (1-2, 3-4, 5-6 or 7-8). If you want the slices routed to individual outputs (1-8), select the appropriate output pair and then pan the slice hard Left/Right using the Pan parameter described above.

! If you have made settings to any of the parameters listed above, these will be lost if you load a new REX file into that Loop Slot.

About the Alt parameter

The Alt parameter in the waveform display can be used to create a more "live" feel to your Rex loops by alternating samples within each individual Alt group. For example, if you assign all snare hit slices in the loop to the Alt 1 group, the snare samples will be selected and played back randomly each time these slices appear in the loop. Then, you could assign all hi-hat slices to the Alt 2 group and so on. The result will be a loop that plays back differently every cycle.

In the example below, slices 3 and 6 have been assigned to the same Alt group. Here, we have used the Copy Loop To Track function five times to generate notes from the loop slices, just so you can see the note distribution. As you can see, slices 3 and 6 have been distributed randomly for each loop cycle:



This randomization within each Alt group also occurs when you play back the REX loop using the Run function - and when you use Pattern Automation in the main sequencer.

The Slice Edit Mode

A very convenient way of editing several slices at once is to work in Slice Edit Mode. In Slice Edit Mode, you can edit one parameter at a time for all slices in the loop.

1. **Click the Slice Edit Mode button.**



The waveform display switches to show the REX loop in Slice Edit Mode.

2. **Select the parameter you want to edit by clicking on its name below the REX loop.**
The parameters that can be selected are: Pitch, Pan, Level, Decay, Reverse, Filter Frequency, Alt Group and Output.



Here, we have selected the Pitch parameter.

3. **Edit the Pitch value for each individual slice by clicking, or drawing across several slices, in the display.**



Now, the Pitch parameter can be edited for all slices in a single sweep.

▶ **To reset the selected parameter to its default value for one or several slices, hold down [Ctrl](Win) or [Cmd](Mac) and click on the desired slice(s), or draw across the slices in the waveform display.**

4. **When you are finished with one parameter, select another parameter and repeat the procedure by drawing values for the slices in the waveform display.**

! **If you have made settings to any of the parameters listed above, these will be lost if you load a new REX file into that Loop Slot.**

Dr. Octo Rex panel parameters


Pitch and Mod wheels



The Pitch wheel to the left is used for "bending" the pitch up or down. The Mod wheel can be used to apply various modulation while you are playing the loop(s). Virtually all MIDI keyboards have Pitch Bend and Modulation controls. Dr. Octo Rex also has two "wheels" on the panel that could be used to apply real time modulation and pitch bend should you not have these controllers on your keyboard, or if you aren't using a keyboard at all. The wheels mirror the movements of the corresponding MIDI keyboard controllers.


The Pitch bend range and Mod destination parameters are set on the synth parameter panel, see "Pitch Bend Range" and "Mod. Wheel".

Trig Next Loop



The Trig Next Loop parameter determines the timing when switching between Loop Slots See "The Trig Next Loop function".


Note To Slot



The Notes To Slot knob set to Slot 1

The Note To Slot knob controls which Loop Slot is currently controlled from the MIDI master keyboard, or by any recorded sequencer notes. The Loop Slot which currently has "note input" is indicated with a lit LED.

The Note To Slot parameter can also be automated. This means you could switch between Loop Slots for every single sequencer note if you like. This opens up for very interesting "beat mangling" experiments. In the example below the Note To Slot parameter has been automated to switch between the REX loops in the seven first Loop Slots:



Automation of the Note To Slot parameter to automatically switch between Loop Slots

In the picture above slice 1 is played from Loop Slot 1, slices 2 and 3 from Loop Slot 2, slice 4 and 5 from Loop Slot 3, slice 6 from Loop Slot 2 and so on.

Loop Slot buttons




The eight Loop Slot buttons are located in the center of the front panel. You can load one REX loop per Slot. Loading REX loops are done from the Loop Editor panel, see "Select Loop & Load Slot".

- ▶ **Click a Loop Slot button to select its REX loop for playback.**
  Play back the REX loop in the selected Loop Slot by clicking the Run button (or Play in the main sequencer).

! **Note that selecting a Loop Slot only selects the corresponding REX loop for playback using the Run function (see "Enable Loop Playback and Run") or Play from the main sequencer. Which Loop Slot the master keyboard or sequencer notes control is defined with the Note To Slot button, see "Note To Slot".**

Enable Loop Playback and Run



- **Click the Enable Loop Playback button to make it possible to play back the REX loops using the Run button or Play function in the main sequencer.**
  If the Enable Loop Playback button is off, clicking Run or Play in the sequencer won't play back the loops. This can be useful if you only want to control the individual slices of the REX loops from a master keyboard or from recorded notes in the main sequencer.

Volume



The Master Volume parameter acts as a general volume control for the loops in all Loop Slots.

Global Transpose



Set the global transposition of the loops in all Loop Slots by using the Global Transpose spin control. You can raise or lower the pitch in 12 semitone steps (+/– 1 octave).

- **The Global Transpose value can also be controlled via MIDI Notes, by pressing a key between C-2 and C0 (with C-1 resetting the transpose value to zero).**
  This way you can also record transposition changes in the sequencer.

Dr. Octo Rex synth parameters

The Dr. Octo Rex synth parameters are used for shaping and modulating the sound of the REX loops. These parameters are familiar synth parameters, similar to the ones in the synthesizers; The Subtractor and the Malström, and in the samplers; the NN-19 and the NN-XT. It is important to remember that these parameters do not alter the REX files in any way, only the way they will play back.

! **Most of the synth parameters are global, in the sense that they will affect all slices in the REX files as well as all REX loops in all eight Loop Slots.**

! **All Dr. Octo Rex synth panel settings are stored in the Song (and in the Dr. Octo Rex patch file if you choose to save the settings as a patch).**

Select Loop & Load Slot



▶ **Click any of the eight Select Loop & Load Slot buttons to select a loaded REX loop for editing, or to load a new REX file to.**
If no loop is already present in the selected Loop Slot, the Waveform Display will be blank. Otherwise, the display shows a graphical readout of the REX loop and info (name, original loop tempo, number of bars and signature).

▶ **Click the Follow Loop Playback button to "synchronize" the Select Loop & Load Slot buttons to the Loop Slot buttons on the front panel.**
This way, the currently playing loop will always be displayed in the Waveform Display. If you're using Pattern Automation in the sequencer, where the Slots are switched during playback, you might want to deactivate the Follow Loop Playback function to make it easier to edit a specific loop.

Refer to "Adding Loops" for info on how to load REX files and to "Editing in the Waveform Display" for info about editing the REX loop.

Loop Transpose



▶ **Set the transposition of individual loops in the Dr. Octo Rex by using the Loop Transpose knob to the bottom left on the panel, or by clicking on the keyboard display below the knob.**
You can raise or lower the pitch in 12 semitone steps (+/–1 octave).

▶ **It's also possible to set a global transpose value that affects all REX loops equally, see "Global Transpose".**

Loop Level

- **Set the individual levels for the loops in the Loop Slots with the Loop Level knob.**
  This lets you match the levels of the loops in the 8 Loop Slots.

Oscillator section



For a REX file, the audio contained in the slices are what oscillators are for a synthesizer, the main sound source. The following settings can be made in the Osc Pitch section of the Dr. Octo Rex:

Env. A

This parameter determines to what degree the overall pitch of all the REX files will be affected by the Filter Envelope (see "Filter Envelope"). You can set negative or positive values here, which determines whether the envelope curve should raise or lower the pitch.

Oct and Fine - Setting the overall Pitch

You can change the overall pitch of all REX files in the 8 Loop Slots in three ways:

- **In octave steps.**
  This is done using the Oct knob. The range is 0 - 8, with "4" as default.
- **In semitone steps.**
  This is done by using Global Transpose controls, see "Global Transpose".
- **In cents (hundredths of a semitone).**
  The range is -50 to 50 (down or up half a semitone).

- **To transpose individual REX loops, use the Loop Transpose parameter, see "Loop Transpose".**

! **To tune an individual slice in a REX loop, select it and use the Pitch parameter below the waveform display, see "Editing in the Waveform Display".**

Mod. Wheel



The Modulation wheel can be set to simultaneously control a number of parameters. You can set positive or negative values, just like in the Velocity Control section. The following parameters can be affected by the modulation wheel:

Parameter	Description
F. Freq	This sets modulation wheel control of the filter frequency parameter. A positive value will raise the frequency if the wheel is pushed forward. Negative values invert this relationship.
F. Res	This sets modulation wheel control of the filter resonance parameter. A positive value will increase the resonance if the wheel is pushed forward. Negative values invert this relationship.
F. Decay	This sets modulation wheel control for the Filter Envelope Decay parameter. A positive value will increase the decay if the wheel is pushed forward. Negative values invert this relationship.

Velocity section



Velocity is usually used to control various parameters according to how hard or soft you play notes on your keyboard. A REX file does not contain velocity values on its own. And when you create sequencer track data by applying the "Copy Loop To Track" function, all velocities are set to a default value of "64". As velocity information is meant to reflect variation, having them all set to the same value is not meaningful if you wish to velocity control Dr. Octo Rex parameters.

There are basically two ways you can apply "meaningful" velocity values to REX files:

- **After creating track data, you can edit velocity values in the Velocity Lane in the sequencer.**
- **You can play slices in real time on your keyboard. The resulting data will have velocity values reflecting how the notes were struck when you played.**

When velocity values have been adjusted, you can control how much the various parameters will be affected by velocity. The velocity sensitivity amount can be set to either positive or negative values, with the center position representing no velocity control.

The following parameters can be velocity controlled:

Parameter	Description
F. Env	This sets velocity control for the Filter Envelope Amount parameter. A positive value will increase the envelope amount with higher velocity values. Negative values invert this relationship.
F. Decay	This sets velocity control for the Filter Envelope Decay parameter. A positive value will increase the Decay time with higher velocity values. Negative values invert this relationship.
Amp	This let's you velocity control the overall volume of the file. If a positive value is set, the volume will increase with higher velocity values.

The Filter Section



Filters are used for shaping the overall timbre of all REX files in all 8 Loop Slots. The filter in Dr. Octo Rex is a multimode filter with five filter modes.

▶ **Activate or deactivate the filter completely by clicking the Filter On button.**
The filter is active when the button is lit.

Mode

With this selector you can set the filter to operate as one of five different types of filter. These are as follows:

- **Notch**
  A notch filter (or band reject filter) could be described as the opposite of a bandpass filter. It cuts off frequencies in a narrow midrange band, letting the frequencies below and above through.
- **High-Pass (HP12)**
  A highpass filter is the opposite of a lowpass filter, cutting out lower frequencies and letting high frequencies pass. The HP filter slope has a 12 dB/Octave roll-off.
- **Bandpass (BP 12)**
  A bandpass filter cuts both high and low frequencies, while midrange frequencies are not affected. Each slope in this filter type has a 12 dB/Octave roll-off.
- **12 dB Lowpass (LP 12)**
  This type of lowpass filter is also widely used in classic analog synthesizers (Oberheim, early Korg synths, etc.). It has a gentler slope (12 dB/Octave), leaving more of the harmonics in the filtered sound compared to the LP 24 filter.
- **24 dB Lowpass (LP 24)**
  Lowpass filters lets low frequencies pass and cuts out the high frequencies. This filter type has a fairly steep roll-off curve (24dB/Octave). Many classic synthesizers (Minimoog/Prophet 5 etc.) used this filter type.

Filter Frequency

The Filter Frequency parameter (often referred to as "cutoff") determines which area of the frequency spectrum the filter will operate in. For a lowpass filter, the frequency parameter could be described as governing the "opening" and "closing" of the filter. If the Filter Freq is set to zero, none or only the very lowest frequencies are heard, if set to maximum, all frequencies in the waveform are heard. Gradually changing the Filter Frequency produces the classic synthesizer filter "sweep" sound.

! **Note that the Filter Frequency parameter is usually controlled by the Filter Envelope (see "Filter Envelope") as well. Changing the Filter Frequency with the Freq slider may therefore not produce the expected result.**

Resonance

The filter resonance parameter affects the character of the filter sound. For lowpass filters, raising the resonance will emphasize the frequencies around the set filter frequency. This produces a generally thinner sound, but with a sharper, more pronounced filter frequency "sweep". The higher the resonance value, the more resonant the sound becomes until it produces a whistling or ringing sound. If you set a high value for the resonance parameter and then vary the filter frequency, this will produce a very distinct sweep, with the ringing sound being very evident at certain frequencies.

- **For the highpass filter, the resonance parameter operates just like for the lowpass filters.**
- **When you use the Bandpass or Notch filter, the resonance setting adjusts the width of the band.**
  When you raise the resonance, the band where frequencies are let through (Bandpass), or cut (Notch) will become narrower. Generally, the Notch filter produces more musical results using low resonance settings.


Envelope section

Envelope generators are used to control several important sound parameters in analog synthesizers, such as pitch, volume, filter frequency etc. In a conventional synthesizer, envelopes govern how these parameters should respond over time - from the moment a note is struck to the moment it is released. In the Dr. Octo Rex device however, the envelopes are triggered each time a slice is played back.

There are two envelope generators in the Dr. Octo Rex, one for volume, and one for the filter frequency (and/or pitch). Both have the standard four parameters; Attack, Decay, Sustain and Release


! **Please refer to "Envelopes - General" in the Subtractor chapter for a description of the basic envelope parameters.**

Amplitude Envelope



The Amp Envelope governs how the volume of each slice should change over time, from the time it is triggered (the slice note starts) until the slice note ends. This can be used to make a loop more distinct (by having a snappy attack and a short decay time) or more spaced-out (by raising the attack time).

Filter Envelope



The Filter Envelope can be used to control two parameters for all REX loops in the 8 Loop Slots; filter frequency and overall loop pitch. By setting up a filter envelope you control how the filter frequency and/or the pitch should change over time for each slice.

The Amount parameter determines to what degree the filter frequency will be affected by the Filter Envelope. The higher the Amount setting, the more pronounced the effect of the envelope on the filter.

▶ **Try lowering the Frequency slider and raising Resonance and Envelope Amount to get the most effect of the filter envelope!**

LFO section



LFO stands for Low Frequency Oscillator. LFOs are oscillators in the sense that they generate a waveform and a frequency. However, there are two significant differences compared to normal sound generating oscillators:

- **LFOs only generate waveforms with low frequencies.**
- **The output of the two LFOs are never actually heard. Instead they are used for modulating various parameters.**

The most typical application of an LFO is to modulate the pitch of a (sound generating) oscillator or sample, to produce vibrato. In the Dr. Octo Rex device, you can also use the LFO to modulate the filter frequency or panning.

Waveform

LFO 1 allows you to select different waveforms for modulating parameters. These are, from top to bottom:

Waveform	Description
Triangle	This is a smooth waveform, suitable for normal vibrato.
Inverted Sawtooth	This produces a "ramp up" cycle. If set to control pitch (frequency), the pitch would sweep up to a set point (governed by the Amount setting), after which the cycle immediately starts over.
Sawtooth	This produces a "ramp down" cycle, the same as above but inverted.
Square	This produces cycles that abruptly changes between two values, usable for trills etc.
Random	Produces random stepped modulation to the destination. Some vintage analog synths called this feature "sample & hold".
Soft Random	The same as above, but with smooth modulation.

Destination

The available LFO Destinations are as follows:

Destination	Description
Osc	Selecting this makes LFO control the pitch (frequency) of the REX file.
Filter	Selecting this makes the LFO control the filter frequency.
Pan	Selecting this makes the LFO modulate the pan position of the REX file, i.e. it will move the sound from left to right in the stereo field.

Sync

By clicking the SYNC button you activate/deactivate LFO sync. The frequency of the LFO will then be synchronized to the song tempo, in one of 16 possible time divisions. When sync is activated, the Rate knob (see below) is used for setting the desired time division.

Turn the knob and check the tooltip for an indication of the time division.




Rate

The Rate knob controls the LFO's frequency. Turn clockwise for a faster modulation rate.

Amount

This parameter determines to what degree the selected parameter destination will be affected by the LFO 1, i.e. the amount of vibrato, filter wah or auto-panning.

Pitch Bend Range



The Pitch Bend Range parameter sets the amount of pitch bend when the wheel is turned fully up or down. The maximum range is 24 semitones (=up/down 2 Octaves).

Setting number of voices - polyphony



This determines the polyphony, i.e. the number of voices, or slices, Dr. Octo Rex can play simultaneously. For normal loop playback, it is worth noting that slices sometimes "overlap". Therefore, it is recommended that you use a polyphony setting of about 3-4 voices when playing REX files. If you are "playing" slices via MIDI, the polyphony setting should be set according to how many overlapping slices you want to have.

! **Note that the Polyphony setting does not "hog" voices. For example, if you are playing a file that has a polyphony setting of ten voices, but the file only uses four voices, this doesn't mean that you are "wasting" six voices. In other words, the polyphony setting is not something you need to consider if you want to conserve CPU power - it is only the number of voices actually used that counts.**

Audio Quality settings

Dr. Octo Rex features two parameters that provide ways of balancing audio quality vs. conservation of computer power. The parameters are called “High Quality Interpolation” and “Low Bandwidth” and are located to the right on the rear panel:



High Quality Interpolation

When High Quality Interpolation is active, the loop file playback is calculated using a more advanced interpolation algorithm. This results in better audio quality, especially for loops with a lot of high frequency content.

- **High Quality Interpolation uses more computer power - if you don't need it, it's a good idea to turn it off.** Listen to the loop in a context and determine whether you think this setting makes any difference.

Low Bandwidth

This will remove some high frequency content from the sound, but often this is not noticeable (this is especially true if you have “filtered down” your loop). Activating this mode will save you some extra computer power, if needed.

Connections



On the rear panel of Dr. Octo Rex you will find the connectors. The left part of the panel houses a number of CV/Gate inputs and outputs. Using CV/Gate is described in “Routing Audio and CV”.

Modulation Inputs

These control voltage (CV) inputs (with trim pots), allow you to modulate various Dr. Octo Rex parameters from other devices (or from the modulation outputs of the Dr. Octo Rex device itself). The following CV inputs are available:

- **Master Volume**
- **Mod Wheel**
- **Pitch Wheel**
- **Filter Cutoff**
- **Filter Resonance**
- **Osc Pitch**

Modulation Outputs

The Modulation outputs can be used to voltage control other devices, or other parameters in the Dr. Octo Rex device itself. The Modulation Outputs are:

- **Filter Envelope**
  The Filter Envelopes in Dr. Octo Rex are polyphonic (one per voice). Only the filter envelope of voice 1 is output here.
- **LFO**

Gate Inputs

These inputs can receive a CV/gate signal to trigger the two envelopes. Note that connecting to these inputs will override the "normal" triggering of the envelopes. For example, if you connected an LFO CV output on another device to the Gate Amp input on the Dr. Octo Rex, the amplitude envelope would not be triggered by the incoming MIDI notes to the Dr. Octo Rex device, but by the LFO CV signal. In addition you would only hear the LFO triggering the envelope for the slices that were playing at the moment of the trigger.

- **Amp Envelope**
- **Filter Envelope**

Gate Output

This outputs a gate signal for each triggered slice in the loop.

Slice Outputs

To the right of the modulation inputs and outputs are the eight individual slice audio outputs. You can assign individual slices to any of these outputs as described in "Editing in the Waveform Display".

Main Outputs

To the right are the main left and right audio outputs. When you create a new Dr. Octo Rex device, these are auto-routed to the first available channel on the audio mixer.

Chapter 29
Europa
Shapeshifting
Synthesizer

Introduction



The Europa Shapeshifting Synthesizer is the most advanced and sonically "wide" synthesizer in Reason. Despite being a very advanced synthesizer, it's really easy to create great sounds from scratch. Just a few mouse clicks and knob twists in a Sound Engine section will generate truly impressive and inspiring sounds!


The three powerful and flexible sound engines offer a unique combination of analog/wavetable/spectral/physical modeling/FM synthesis techniques. If you like, you could also draw your own waveforms and filter curves to design your own completely unique sounds. In addition to this you can also load your own sample into Europa and use as a wavetable and/or filter! Each sound engine also has its own Unison module for generating really wide multi-voice stereo chorus effects.

The extensive Envelopes section and Modulation Bus section allow for very detailed and flexible modulation and control. Europa also features a top-notch semi-modular multi-effect section so you could put that final touch on your sounds.

Don't forget to check out the Europa videos here!

Panel overview

The Europa front panel contains the following sections:




The Europa front panel sections.

- **1. MIDI Note On LED.**
- **2. Patch Selector (for browsing, loading and saving patches).**
- **3. Sound Engines section.**
- **4. User Wave and Mixer section.**
- **5. Filter section.**
- **6. Amplifier section.**
- **7. Global output controls.**
- **8. Global performance and "play" controls.**
- **9. Envelopes section.**
- **10. LFO section.**
- **11. Modulation Bus section.**
- **12. Effects section.**

Signal flow

The picture below shows the basic signal flow in Europa:



Europa signal flowchart.

- **The "hearts" of Europa are the three Sound Engines I, II and III.**
- **First in each Sound Engine is an Oscillator, which generates the basic audio signal.**
  The oscillators in Europa are extremely powerful and flexible. Besides all the basic "analog" waveforms, the oscillators can also generate a vast variety of wavetable waveforms, physical modeling signals and other types of unique signals - and also your own samples! The signals can also be continuously transformed into various shapes.
- **The Oscillator signal can be modified by the two Modifiers.**
  The Modifiers feature a huge amount of algorithms that can modify the Oscillator signal in various ways.
- **The signal from the Oscillator is routed to the Spectral Filter.**
  The Spectral Filter affects the partials of the signal. The algorithms could be various types of filters - or special purpose signal processors.
- **The signal from the Spectral Filter can then be routed to the Harmonics processor.**
  The Harmonics processor modulates the harmonics in the signal, for example introducing ensemble or stretch effects.
- **The signal from the Harmonics processor can then be routed to the Unison module.**
  This module can generate various types of unison chorus effects, to make the sound really fat and wide.
- **The signals from the Sound Engines are then routed to the Mixer, where you can set the mix between the three Sound Engine output signals and also pan the signals individually.**
- **The mixed signal is then routed to the Filter, Amp Envelope and then, via the Multi FX section, to the stereo outputs.**
- **The remaining sections in Europa (Envelopes 1-4 and LFOs 1-3) can be freely assigned to modulate destination parameters via the Modulation Bus section.**

Playing and using Europa

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global output controls



Master Volume

This is the main stereo output volume control.

Voices

Here you set the desired maximum polyphony of your patch, from 1 to 16 voices. This control is mainly intended for deliberately restricting the polyphony of a sound. If you just want to play a patch polyphonically you can leave the Voices setting at 16 at all times. The DSP Load won't increase with higher voice number settings - only if you play a lot of notes simultaneously.

- **If you want monophonic playback you could use the "Retrig" and "Legato" modes instead of lowering the Voices parameter to 1.**

Global performance and "play" controls



Key Mode

Here you choose how Europa should respond to MIDI Note data:

- **Poly**
  Select this if you want to play Europa polyphonically. The maximum number of voices is 16. The number of voices is set in the Voices control at the center right of the Europa panel, see "Voices".
- **Retrig**
  Select this if you want to play Europa in monophonic mode and always retrigger the envelopes as soon as you play a new note.
- **Legato**
  The Mono Legato mode is also monophonic. However, if you play a new note without having released the previous one, the envelopes won't start over.

Porta

Portamento makes note pitches glide from previous notes to new ones, at the time set with the Time knob. Portamento can be used in all Key modes (see above).

- **When On in Poly Key Mode (see above), the pitches will glide from any of the available voices.**
  The results will be unpredictable since there is no way of controlling from which note(s) the glide(s) will commence. The effect is very nice, though.
- **When On in Retrig or Legato Key Mode (see above), the pitch will glide between consecutive notes.**
- **In Auto mode, the pitch will glide between consecutive monophonic notes only when you play legato. If you have selected Poly Key Mode (see above), Auto will have no effect at all.**
  If you release the previous key before hitting the new key, there will be no portamento effect.

P.Range

- **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
  Range: +/-24 semitones (+/-2 octaves) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Europa also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "P.Range" control above the Pitch bend wheel.

Mod

The Mod wheel can be used for controlling almost any parameter in Europa. Use the Mod wheel as a Source parameter in any of the Modulation Source boxes in the different sections. Or use it as Source parameter in the Modulation Bus section and then route to the desired Destination parameter(s), see "The Modulation Bus section".



Panel reference

Sound Engines On/Off and Edit Focus section



Engine Select

- **Click the On LED buttons to activate the corresponding Sound Engine.**
- **Click the I, II or III LED radio buttons to select the corresponding Sound Engine for editing.**

The Oscillator section



Here is where you choose oscillator waveform and set the wave shape and pitch for the selected Sound Engine.

On

- **Click the red rectangular LED button to switch the selected Sound Engine on/off.**

Oct

- **Set the pitch in octave steps.**
  Range: 5 octaves.

Semi

- **Set the pitch in semitone steps.**
  Range: 12 semitones (one octave).

Tune

- **Change the pitch in steps of 1 cent.**
  Range: +/- 50 cents (down or up half a semitone).

Kbd

▶ **Set how much the pitch should track incoming MIDI Notes.**
Range: 0% (no tracking (constant pitch)) to 100% (1 semitone per note).

Waveform display

The interactive Waveform display shows the waveform shape in real-time.

- **Clicking and dragging horizontally in the display changes the Shape parameter, see "Shape".**
- **Clicking and dragging vertically in the display changes the Modifier 1 Amount parameter, see "Amount".**

▶ **See "Recording display movements in the sequencer" for tips about automating display movements.**

Waveform selector

▶ **Click the Waveform name box to bring up a menu of the available waveforms.**
The wave shapes are shown in the display above and are updated in real-time according to the current settings and modulations. A great way to understand how the sound actually "looks".

The waveforms are:

- **Basic Analog**
A pure sinewave at Shape=0%, gradually transformed via triangle and square towards a sawtooth wave at Shape=100%.
- **Square-Ramp**
A square wave at Shape=0%, gradually transformed towards a sawtooth wave at Shape=100%.
- **Saw-Triangle**
A negative ramp sawtooth wave at Shape=0%, gradually transformed via triangle towards a positive ramp sawtooth wave at Shape=100%.
- **Pulse Width**
A 0% duty cycle pulse wave (silence) at Shape=0 gradually transformed via a 50% duty cycle square wave towards a 100% duty cycle pule wave (silence) at Shape=100%.

▶ **Modulate the Shape parameter from an LFO to achieve PWM, see "Shape Modulation" below.**

- **Game**
A lo-fi "early computer game" type of signal. Turn the Shape knob to change the overtone contents and the octave transposition.
- **Synced Sine**
A pure sinewave at Shape=0%. As the Shape is increased, the pitch of the synced sinewave oscillator is raised.
- **Formant Sweep**
A cosine window modulated by a sinewave. Turn the Shape knob to change the sinewave frequency and thus sweep through the generated formants.
- **Electro Mechanical**
This is a simulation of an electric piano. A soft/mellow tone at Shape=0% gradually transformed towards an agitated signal at Shape=100%, with natural sound at the 12 o'clock position (50%).
- **Vocal Cord**
A simulation of a vocal cord with a bit of noise modulation. Change the overtone content with the Shape knob.

▶ **Try this together with the Vocal Formants algorithm in the Spectral Filter section to generate "vocal" sounds, see "Vocal Formant".**

- **Karplus-Strong**
A physical model of a "string", generated by sending a short pulse through pitched delay lines. At Shape=0% there is no damping and at Shape=100% there is full damping, which results in just a short clicking sound.

▶ **Try this together with the "Stretch" algorithm in the Harmonics section to create realistic metallic sounds.**



- **Envelope 3-4**
  This is a special mode where you can manually draw your waveforms in the Envelope 3 and Envelope 4 windows and then gradually crossfade between the drawn waveforms using the Shape knob. See "Using the Envelope 3 and Envelope 4 curves as Sound Engine waveforms" for information on how to draw your own waveforms.
- **FM > FM Ratio (1:1, 1:2, 1:8, 2:1)**
  These are frequency modulated sine waves with different frequency ratios between the carrier (C:) and modulator (:M) signals. Set the frequency modulation amount with the Shape knob.
- **FM > FM Feedback**
  A pure sinewave signal at Shape=0% gradually fed back internally at an 1:1 ratio. The feedback signal is filtered before fed back to the carrier signal. If you modulate the Shape parameter from e.g. an LFO you will get a similar result as when using the FM FB Noise waveform without Shape modulation, see "Noise > FM FB Noise" below.
- **Noise > S/H Noise**
  A sample & hold modulated noise. Change the sample & hold rate with the Shape knob. If you play high up on the keyboard at high Shape values, you get a kind of "pitched noise" sound.

▶ **To get white noise, set Shape to max, set Oct to -1 and turn Kbd to 0.**

- **Noise > Perlin Noise**
  A pure sinewave signal modulated by low frequency noise. At Shape=0% the noise has its lowest frequency and at Shape=100% the noise frequency is higher (but still low-frequent). The character of the signal is similar to the Band Noise in the Thor synthesizer.
- **Noise > Bit Noise**
  This generates a random lo-fi "digital" bit noise. At Shape=0% the signal is completely silent and with increasing Shape values the signal is modulated faster and in a wider frequency range.
- **Noise > FM FB Noise**
  A pure sinewave signal at Shape=0% gradually fed back internally at an 1:1 ratio. The feedback signal unfiltered before fed back to the carrier signal which gives the signal a noisy character.

▶ **To get a cleaner FM signal, use the FM Feedback waveform, see "FM > FM Feedback" above.**

- **Noise > Freeze Noise**
  This signal produces a range of noises, from tonal noise up to almost white noise, by amplitude modulating the signal's partials with noise.
- **Wave Tables >**
  The Wave Tables sub-menu contains a selection of very useful wave tables. Each wave table features eight waveforms that you could crossfade between with the Shape knob.
- **User Wave/User Wave Smooth**
  The User Wave options let you use the external sample you have loaded in the User Wave section (see "The User Wave and Mixer section"). The oscillator then generates and plays back wavetables (grains) of that sample. The "User Wave Smooth" algorithm uses a crossfaded loop within each grain, which produces a smoother character to the sound. Set the playback position in the sample with the Shape knob. Modulate the Shape parameter, for example from a negative Envelope ramp, for continuous movement in the sample.

Shape

▶ **Turn the Shape knob to change the shape of the currently selected waveform.**
The wave shapes are shown in the display above and are updated in real-time according to the current Shape settings.

Shape Modulation

▶ **Click the Shape Modulation Source box to bring up a menu of the available modulation sources.**
The "Inverted" sub-menu contains inverted variations of all modulation sources.

▶ **Set the modulation amount with the Shape Modulation Amount knob.**



- ▶ **Turn the Velo knob to control the Shape Modulation Amount from Keyboard Velocity.**
- ▶ **If you want other modulation sources or scaling options, use the Mod Bus, see "The Modulation Bus section".**

Phase Sync

- ▶ **Click the Phase Sync button to force the waveform cycle to always start at the same phase (0 degrees).**
  When active, the sound character will be the same each time you play the same note. When inactive, the sound character will vary more or less each time you play the same note.

The Modifiers section



The two Modifiers can be used for modifying the currently selected waveform in various ways. The two Modifiers are identical in functionality and can be used alone or together (or not at all).

Modifier On/Off

- ▶ **Click the On/Off LED buttons to activate/deactivate the corresponding Modifier.**

Modifier selector

- ▶ **Click the Modifier name box to bring up a menu of the available Modifier types.**
  The available Modifier types are:

- **Faded Sync**
  This is oscillator sync but with a crossfade at the sync positions. This makes the effect a little smoother (less bright) than with regular hard sync, see below.
- **Hard Sync**
  Oscillator hard sync is when one oscillator restarts the period of another oscillator, so that they will have the same base frequency. If you change or modulate the frequency of the synced oscillator you get the characteristic sound associated with oscillator sync. Control the frequency of the synced oscillator (and thereby the overtone spectrum) with the Amount knob.
- **Invert**
  This inverts the waveform phase at a variable position within the waveform cycle. Set the phase angle with the Amount knob.
- **Mirror**
  This mirrors the waveform cycle (in the time line) at a variable position in the waveform cycle. Set the mirroring position in the waveform cycle with the Amount knob. At Amount=50% the waveform is completely symmetric.
- **DownSample**
  This lets you quantize the waveform in time, i.e. reduce the sample rate. Set the sample rate reduction amount with the Amount knob.
- **Quantize**
  This lets you truncate the signal's bit depth, thus making it possible to achieve that noisy, characteristic "8-bit sound" for example. Set the bit-reduction amount with the Amount knob.

- **Phase Distort**
  This distorts the waveform by modulating the start phase of the waveform cycle. This generally creates a brighter tone towards the extremes of the Amount range (0% and 100%). At Amount=50% the signal is unaffected.
- **Self Multiply**
  This multiplies a copy of the waveform with the original waveform. Set the phase angle of the copied waveform with the Amount knob.
- **Noise Mod**
  This modulates the waveform with low frequency noise. Perfect for adding e.g. "breath noise" to a signal. Set the noise modulation amount with the Amount knob.
- **Shaping > Wrap**
  This amplifies the signal above the available headroom and then wraps the peaks down into the available headroom. This adds quite an aggressive distortion to the sound.
- **Shaping > Fold**
  This amplifies the signal above the available headroom and then "mirrors" the peaks down into the available headroom. Fold is similar to the Wrap shaping but is generally less "aggressive".
- **Shaping > Hard Clip**
  This amplifies the signal above the available headroom and then clips the peaks that are above the headroom. Generally, a signal that is clipped to the maximum would result in a pulse/square shaped waveform.
- **Shaping > Soft Clip**
  Soft clip is similar to hard clip described above, but has a smoother shape at the clipping points and thus generates less overtones.
- **Shaping > Sine Shape**
  This generates sine shaping distortion to the signal.
- **Shaping > Glitch 1**
  This distorts the waveform by introducing a short low-frequency noise glitch in the waveform cycle, but only in parts of the waveform that go from zero to positive level.
- **Shaping > Glitch 2**
  This is similar to Glitch 1 described above, but introduces a more high-frequent noise glitch in the waveform cycle.
- **Harmonics > Octave**
  This makes it possible to gradually crossfade between the original signal and a copy of the signal one octave above. Set the crossfade amount with the Amount knob.
- **Harmonics > Fifth**
  This makes it possible to gradually crossfade between "one octave up" and "one octave+one fifth up". As soon as you turn on the Fifth modifier you automatically raise the pitch by one octave. The reason for this is that this is done by multiplying frequencies, i.e. you crossfade between the double and triple of the original frequency. Set the crossfade amount with the Amount knob.
- **Harmonics > 16 Harmonics**
  This makes it possible to gradually crossfade between the original signal and copies of the signal at the 16 first harmonics above the original frequency. Set the position in the harmonic spectrum with the Amount knob.
- **Harmonics > Fund. + 16 Harm.**
  This is the same as "16 Harmonics" described above, except this always keeps the original signal mixed in with the selected harmonic.
- **Harmonics > All 16 Harm.**
  This gradually adds copies of the original signal at the first 16 harmonics. Turning up the Amount knob will add on the harmonics one by one until all 16 harmonics are present in the signal.
- **Harmonics > Ring Harm.**
  This multiplies the waveform with a sinewave signal to generate a ring modulator effect. Set the modulator frequency with the Amount knob.



- **FM > FM Ratio (1:1, 1:2, 1:8, 2:1)**
  These modifiers let you frequency modulate the currently selected Waveform at various ratios. The carrier signal is the currently selected Waveform (C:) and the modulator (:M) is the modifier signal. Set the frequency modulation amount with the Amount knob.
- **FM > FM Feedback**
  Here, an internally fed back sinewave signal at an 1:1 ratio modulates the waveform (same signal type as in the "FM > FM Feedback" Waveform).
- **Detuning > Unison3**
  This simulates 2 copies of the original signal. The Amount knob controls the detuning amount and rate.
- **Detuning > Unison7**
  This simulates 6 copies of the original signal. The Amount knob controls the detuning amount and rate.
- **Detuning > Ensemble**
  This simulates a variable number of copies of the original signal. The Amount knob controls the number of copies, the detuning amount and rate.
- **Detuning > Unison 3Oct**
  This simulates 2 copies of the original signal at +1 and +2 octaves relative to the original signal. The Amount knob controls the detuning amount and rate.
- **Formant**
  This simulates a formant (body) filter, which produces multiple peaks and notches in the frequency spectrum of the signal. The Amount knob controls the formant transposition in the frequency spectrum. At Amount=50% the signal is unaffected. Below 50% the formant is transposed down and above 50% it's transposed up.

  To make the formant static in the frequency spectrum, regardless of which note you play, modulate the Amount parameter using the "-KEY" (inverted) modulation source with a fairly high value (see "Amount Modulation" below). This is especially useful if you are using an acoustic instrument sample as User Wave in the Oscillator section.

Amount

▶ **Turn the Amount knob to change the modification amount of the currently selected Modifier.**
The wave shapes are updated in real-time and shown in the Waveform display.


Amount Modulation

▶ **Click the Modulation Source box to bring up a menu of the available modulation sources.**
The "Inverted" sub-menu contains inverted variations of all modulation sources.

▶ **Set the modulation amount with the Amount Modulation knob.**

▶ **If you want other modulation sources or scaling options, use the Mod Bus, see "The Modulation Bus section".**

The Spectral Filter



The signal from the Oscillator section can then be processed by the Spectral Filter. The Spectral Filter features a wide variety of algorithms that affect the partials of the signal.

Spectral Filter On/Off

▶ **Click the On/Off LED button to activate/deactivate the Spectral Filter.**

Spectral Filter display

The interactive Spectral Filter display shows the filter shape in real-time.

- **Clicking and dragging vertically in the display changes the Freq parameter, see "Freq".**
- **Clicking and dragging horizontally in the display changes the Resonance parameter, see "Reso".**

▶ **See "Recording display movements in the sequencer" for tips about automating display movements.**

Spectral Filter selector

▶ **Click the Spectral Filter name box to bring up a menu of the available filter types.**
The available filter types are:

- **LP 12**
  This simulates a standard 12dB/octave lowpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.
- **LP 24**
  This simulates a standard 24dB/octave lowpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.
- **HP 24**
  This simulates a standard 24dB/octave highpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.
- **BP 12**
  This simulates a standard 12dB/octave bandpass filter. Set the center frequency with the Freq knob and the resonance amount with the Reso knob.
- **Par EQ**
  This simulates a standard single band parametric equalizer with a fixed bandwidth. Set the center frequency with the Freq knob and the gain/attenuation with the Reso knob.
- **Dual Peak**
  This simulates two 12dB/octave bandpass filter routed in parallel. Set the center frequency of the first bandpass filter with the Freq knob and the peak separation with the Reso knob.
- **Vocal Formant**
  This simulates the formants of the vocal tract by using multi-peak+notch filters. Change the formant with the Freq and Reso knobs.
- **LP Variable Slope**
  This simulates a non-resonant lowpass filter with a variable attenuation slope. Set the cutoff frequency with the Freq knob and the attenuation slope with the Reso knob.
- **HP Variable Slope**
  This simulates a non-resonant highpass filter with a variable attenuation slope. Set the cutoff frequency with the Freq knob and the attenuation slope with the Reso knob.
- **Comb +**
  This simulates a multi notch filter, great for phaser types of effects. Set the cutoff frequency of the first notch with the Freq knob and the attenuation amount - and consequently the bandwidth - of the notches with the Reso knob. The difference between "Comb +" and "Comb –" (see below) is in the position of the peaks in the spectrum. The main audible difference is that the "Comb –" version causes a bass cut.



- **Comb -**
  This simulates a comb filter with a positive feedback loop - but without feed forward - ideal for flanger and phaser types of effects. Set the cutoff frequency of the second peak with the Freq knob and the resonance amount with the Reso knob. The difference between "Comb +" (see above) and "Comb –" is in the position of the peaks in the spectrum. The main audible difference is that the "Comb –" version causes a bass cut.
- **Resonator 1,2 and 3**
  The three Resonator algorithms contain formant filter tables that simulate various body resonances (multi-peak+notch filters). Set the position in the formant tables with the Freq knob and the resonance with the Reso knob.
- **Envelope 4**
  This is a special mode where you can manually draw your own filter curve in the Envelope 4 window. You then control the cutoff/center frequency with the Freq knob and the resonance with the Reso knob. See "Using the Envelope 4 curve as a Spectral Filter curve" for information on how to draw your own filter curves.
- **User Wave**
  This utilizes a filter generated from FFT analyses of the external sample you have loaded in the User Wave section (see "The User Wave and Mixer section"). Transpose the formant up/down in the frequency spectrum with the Freq knob and change the filter's position in the sample with the Reso knob.

▶ **To create a classic "vocoder" effect, load a vocal/speech sample in the User Wave section. Then, set the Freq knob to 50%, the Reso knob to 0% and the KBD knob to 0%. Then, have one of the Envelopes modulate the Reso parameter using the Modulation Bus (see "The Modulation Bus section"). Create a positive ramp (inverted sawtooth) envelope and set the Reso modulation amount to 100%.**

Freq

▶ **Set the cutoff/center frequency of the currently selected Spectral Filter type.**

Reso

▶ **Set the resonance amount of the currently selected Spectral Filter type.**

Frequency Modulation

▶ **Turn the Kbd knob to set the keyboard tracking amount.**
At 0% the filter is static and doesn't track the keyboard at all. At 100% the filter tracks the keyboard 1 semitone per note. At values above 0% you can also see the filter curve move sideways in the Spectral Filter Display depending on where on the keyboard you play.

▶ **Click the Frequency Modulation Source box to bring up a menu of the available modulation sources.**
The "Inverted" sub-menu contains inverted variations of all modulation sources.

▶ **Set the modulation amount with the Frequency Modulation Amount knob.**

▶ **Turn the Velo knob to control the Frequency Modulation Amount from Keyboard Velocity.**

▶ **If you want other modulation sources or scaling options, use the Mod Bus, see "The Modulation Bus section".**

The Harmonics section



The Harmonics section offers extensive modulation possibilities of the partials of the signal. For most algorithms the partials' characteristics is displayed in the Spectral Filter display, see "Spectral Filter display".

Harmonics On/Off

▶ **Click the On/Off LED buttons to activate/deactivate the Harmonics section.**

Harmonics selector

▶ **Click the Harmonics name box to bring up a menu of the available harmonic algorithms.**
The available Harmonics types are:

- **Random Gain**
  This alters the gain for each of the partials in the signal in a random fashion. Turn the Pos knob to change the randomization "pattern" and the Amount knob to change the partial gain levels in the "pattern".
- **Harmonic 1-8 Mix**
  This alters the gain/attenuation for the first eight partials in the signal. Turn the Pos knob to crossfade between the partials and the Amount knob to change the partial gain/attenuation level. Amount levels below 50% attenuate all partials but the one selected with the Pos knob. Amount levels above 50% attenuate the partial selected with the Pos knob.
- **Odd-Even**
  This alters the gain/attenuation of the partials in the signal. At Pos=0% the Amount knob controls the mix strictly between the odd and even partials in the signal. At other Pos values, the gain/attenuation is not strictly on odd and even partials. At Amount=50% the Pos value has no effect.
- **Stretch**
  This stretches or squeezes all partials (overtones) - except for the fundamental - in the signal, up or down in the frequency range. Perfect for turning a harmonic signal into a more inharmonic one. Change the stretch amount with the Amount knob. The Pos knob controls the start phase of all the overtones. At Pos=0% all partials start at the same phase. When Amount is set fairly high the Pos parameter have little or no influence on the sound.

▶ **Try this with the Karplus-Strong waveform to create really realistic metallic sounds, see "Karplus-Strong"!**

- **Ensemble**
  This is the perfect algorithm for really dense pad sounds. The Ensemble algorithm simulates a type of chorus effect by utilizing noise modulation of the partials. Set the noise frequency with the Pos knob and the mix level with the Amount knob.
- **Ensemble Sparse**
  The Ensemble Sparse algorithm also utilizes noise modulation of the partials, but here a lot of noise frequency bands are cut out. This makes Ensemble Sparse sound more animated and less smooth than the Ensemble algorithm described above. Set the noise frequency with the Pos knob and the mix level with the Amount knob.
- **HF Noise**
  This amplitude modulates the high frequencies in the signal with (high-frequency) noise, perfect for adding "breath noise" to the signal, for example. Set the noise frequency with the Pos knob and the noise mix level with the Amount knob.
- **Harmonic Lag A-R**
  The Harmonic Lag A-R algorithm is designed especially for use with the User Wave algorithm in the Spectral Filter (see "User Wave") to create vocoder effects. The Harmonic Lag A-R algorithm controls the Spectral Filter - so the Spectral Filter has to be on for this to work!

  Note that the Harmonic Lag A-R algorithm works on the filter partials - not the oscillator's signal partials. Set the Attack time of the filter partials with the Pos knob and the Release time with the Amount knob. These controls work similarly to the Attack and Decay parameters on the BV512 Vocoder device.

Pos

▶ **Turn the Pos knob to change the frequency of the currently selected Harmonics algorithm.**
The frequency spectrum is updated in real-time and shown in the Spectral Filter display.



Amount

▶ **Turn the Amount knob to change the intensity of the currently selected Harmonics algorithm.**
The frequency spectrum is updated in real-time and shown in the Spectral Filter display.

The Unison section



The Unison function generates detuned duplicates of the signal in pairs on either side of the original signal's pitch.

Unison On/Off

▶ **Click the On/Off LED button to activate/deactivate the Unison section.**

Unison display

The Unison display shows the unison characteristics, as set with the controls in the Unison section. Note, though, that this display is not interactive like the Waveform and Spectral Filter displays.

Unison Type selector

▶ **Click the Unison name box to bring up a menu of the available Unison types.**
The available Unison types are:

- **Normal**
  This generates duplicates of the signal on either side of the original signal's pitch.
- **Fourth**
  This generates duplicates of the signal on either side of the fourth above the original signal's pitch.
- **Fifth**
  This generates duplicates of the signal on either side of the fifth above the original signal's pitch.
- **Octave Down**
  This generates duplicates of the signal on either side of the original signal's pitch - one octave down.
- **Phase Only**
  This generates duplicates of the signal on either side of the original signal's pitch. The Detune parameter (see below) now controls the phases of the signal copies, instead of the detuning. This is great for creating wide stereo sounds without lots of detuning.

  If Phase Sync is active in the Oscillator (see "Phase Sync"), all signals in the Unison function get the same relative start phases each time you play the same note. The original signal always has the phase 0 degrees.

Count

▶ **Set the number of desired signals in the unison effect.**
Range: 1-7.
Note that for even numbers, the original signal is represented by two duplicates.

Blend

- **Set the mix between the original signal and the duplicates.**
  For even "Count" numbers (see above), one of the duplicates represents the original signal in the mix.

Detune

- **Set the pitch detuning of the signal duplicates.**
  If the "Phase Only" Unison type is selected (see above), the Detune knob controls the phases of the signal duplicates instead of the pitch detuning.
- **In the "Phase Only" scenario it could also be a good idea to modulate the Detune parameter from an LFO using the Modulation Bus (see "The Modulation Bus section"), to create nice phasing effects.**

Spread

- **Set the stereo spread amount of the signal duplicates.**

The User Wave and Mixer section



The User Wave and Mixer section is where you can sample (or load an external sample) to use in the Oscillators (see "User Wave/User Wave Smooth") and/or in the Spectral Filter (see "User Wave"). In the Mixer you can mix and pan the signals from the three Sound Engines before sending them to the Filter, Amp and Multi FX sections.

Sample Select/Load/Sampling/Edit buttons

- **Load a sample using drag & and drop, or by clicking the Browse sample button, or by using the Up/Down buttons to scroll and load a sample from the currently selected folder.**
- **Alternatively, sample straight into Europa by clicking the Start sampling button.**
  See the "Sampling" chapter for more information about setting up and using Reason for sampling.
- **Click the Edit Sample button to open up the existing sample in the Sample Edit window.**
  See "Editing samples" for more information about editing samples in Reason.

▪ **It's possible to load/sample stereo signals. However, the sample will be automatically converted to mono in Europa.**

! **Like with the other sampler devices in Reason, the Europa patch does not include the actual sample - only a reference to it. Therefore, the sample has to be stored separately (self-contained with the song, or already on disk or in a ReFill on your computer).**

! **If the sample length is a multiple of 2048 samples ("Serum compatible"), no pitch detection is being made. Then, Europa automatically assumes that 2048 samples is one complete waveform cycle (period). If the sample is not an exact multiple of 2048 samples, a pitch detection is being performed by Europa to determine the pitch. Longer samples (with a stable pitch) will render better pitch detection results, so don't use very short samples.**

Level

- **Set the volume of the corresponding Sound Engine signal with the Level slider.**
  Range: -Inf to +6.0dB.

Pan

▶ **Set the panning of the corresponding Sound Engine signal in the stereo panorama.**

The Filter section



Routing buttons

▶ **Click the red LED buttons to route the corresponding Sound Engine signals to the Filter section.**
If deactivated, the signal bypasses the Filter and goes straight to the Amp section, see "The Amplifier section".

Drive

▶ **Turn the Drive knob to amplify and introduce an overdrive type of distortion to the Sound Engine signal(s) in the filter.**

Filter Type selector

▶ **Click the Filter Type name box to select one of the following filter types:**

- **SVF HP 12dB**
  A state variable (SVF) highpass filter with a 12dB/octave slope. This filter is similar to the State Variable Filter in the Thor synthesizer.
- **SVF BP 12dB**
  A state variable (SVF) bandpass filter with 12dB/octave slopes. This filter is similar to the State Variable Filter in the Thor synthesizer.
- **SVF LP 12dB**
  A state variable (SVF) lowpass filter with a 12dB/octave slope. This filter is similar to the State Variable Filter in the Thor synthesizer.
- **SVF Notch**
  A state variable (SVF) notch filter. This filter is similar to the State Variable Filter in the Thor synthesizer.
- **Ladder LP 24dB**
  A ladder-type lowpass filter with a 24dB/octave slope. The resonance peak more narrow in this filter type than in the MFB LP 24dB filter (see below). The filter can be driven to self-oscillate.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

- **MFB LP 12dB**
  A multiple feedback (MFB) lowpass filter with a 12dB/octave slope.
- **MFB LP 24dB**
  A multiple feedback (MFB) lowpass filter with a 24dB/octave slope. The resonance peak is wider in this filter type that in the Ladder filter (see above). The filter can be driven to self-oscillate.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

- **MFB HP 24dB**
  A multiple feedback (MFB) highpass filter with a 24dB/octave slope.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

- **K35 LP 12dB**
  An "early MS-20 type" of lowpass filter with a 12dB/octave slope. The filter can be driven to self-oscillate.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

Reso

▶ **Set the resonance amount.**
In the SVF Notch filter, the Reso knob controls the width of the notch - from wide to narrow.

Freq

▶ **Set the cutoff frequency (for the HP and LP filter types) or the center frequency (for the BP filter type).**

Frequency Modulation

▶ **Turn the Kbd knob to set the keyboard tracking amount.**
At 0% the filter is static and doesn't track the keyboard at all. At 100% the filter tracks the keyboard 1 semitone per note.

▶ **Click the Frequency Modulation Source box to bring up a menu of the available modulation sources.**
The "Inverted" sub-menu contains inverted variations of all modulation sources.

▶ **Use one of the Envelopes (see "The Envelopes section") as modulation source to create a Filter envelope.**

▶ **Set the modulation amount with the Frequency Modulation Amount knob.**

▶ **Turn the Velo knob to control the Frequency Modulation Amount from Keyboard Velocity.**

▶ **If you want other modulation sources or scaling options, use the Mod Bus, see "The Modulation Bus section".**




The Amplifier section



The Amplifier section contains a standard ADSR envelope, which controls the amplitude of the signals from all three Sound Engines equally.

- **To create an "amp envelope" for a separate Sound Engine, have a look at "Creating an individual "pre amp envelope" for a Sound Engine".**

The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

A(ttack)

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the Gain knob (see below). How long this should take, depends on the Attack setting. If the Attack is set to "0", the Gain level is reached instantly. If the Attack value is raised, it will take longer time before the Gain level is reached.

D(ecay)

After the Gain level has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.

S(ustain)

The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Gain level, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Gain level. Note that Sustain represents a level, whereas the other envelope parameters represent times.

R(elease)

The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

Pan

- **Set the panning of the output signal from the Amplifier in the stereo panorama.**
- **Since Pan works individually per voice, you can assign e.g. Keyboard Velocity or an Envelope in the Modulation Bus to control the Pan effect, see "The Modulation Bus section".**

Gain

- **Set the desired maximum level for the Amplifier with the Gain knob.**
  This is the maximum level the envelope will reach after the Attack stage is completed (see above).
- **If you want to create a tremolo effect, assign "Gain" as Destination and an LFO as Source in the Modulation Bus section, see "The Modulation Bus section".**

Velo

- **If you want the Gain level to be controlled from keyboard velocity, turn up the Velo knob.**



The Envelopes section



The Envelopes section features four separate polyphonic (one per voice) general purpose envelope generators, that can be assigned to control selectable parameter(s) in the Modulation Bus section.

The Envelopes are extremely flexible, and you can draw your own custom modulation shapes by clicking and drawing in the display area. There are also a number of preset shapes that you can use as starting points (or use as is). If you use Loop mode, you could turn the envelope into a kind of LFO.

See "The Modulation Bus section" for details on how to assign the Envelopes to the desired destination(s).


Envelope 1, 2, 3 and 4

▶ **Click one of the Envelope 1, 2, 3 or 4 buttons to select which envelope to edit:**




Preset

1. **Click the Preset button to bring up a palette of envelope preset curves:**



2. **Click the desired envelope preset curve to place it on the display.**
   Let's select a standard ADSR style of envelope curve:






Adding a Sustain stage

▶ **Click the Sustain button to add a sustain stage to the envelope:**



The vertical red marker that appears indicates at what level (and where) the envelope will stay sustained until you release the key.

▶ **Drag the sustain marker sideways to move the sustain stage to the desired position:**



▶ **To remove the sustain stage, click the Sustain button.**

Adding and removing envelope points


▶ **Double click, or hold down [Ctrl](win) or [Cmd](Mac) and click in the envelope display to add points to the envelope curve:**



▶ **To remove a point, double click, or hold down [Ctrl](win) or [Cmd](Mac) and click, on an existing point on the envelope curve.**


Changing the envelope curve shape

▶ **Click a line segment (between two points) and drag up/down to change the curve shape:**



Looping the envelope

▶ **Click the Loop button to turn the envelope into a kind of LFO.**
If there was previously a sustain stage in the envelope, this will automatically be disabled when you click the Loop button.




Here we have edited a stepped curve from the Presets. We have also enabled Beat Sync and set the length/rate to 4/4. This means that each step in the curve now represents an 1/8th note.

- **Key Trig means the envelope restarts when you play a note.**
- **You can choose whether the envelope should send out a bipolar value or unipolar one (0-100%).**
- **If Global is on, the envelope will be common for all voices.**


Editing levels only

▶ **To restrict the editing to levels only, without affecting the time positions, click the Edit Y-Pos button:**



In this mode you cannot change the time positions of the envelope points, only their levels (height). This is extra useful with a stepped Preset curve, because dragging up or down will change the value of an entire segment, turning the Envelope into a pseudo-sequencer.

! **To be able to adjust the level of a segment, the two points on either side of the segment have to be on the exact same time positions. Otherwise, only the closest point will be changed. Also, any inclining/declining segment will automatically turn horizontal when edited:**




Adjusting the level of a segment.

Creating “free form” envelope curves

In the Edit Y-Pos mode, you can also draw “free form” curves:

▶ **To continuously add new consecutive points, hold down [Ctrl](win) or [Cmd](Mac) and drag in the envelope display:**



▶ **To erase points, hold down [Shift] and [Ctrl](win) or [Cmd](Mac) and drag in the envelope display.**

Using the Envelope 3 and Envelope 4 curves as Sound Engine waveforms

As a special feature you can use the Envelope 3 and Envelope 4 curves as waveforms for the Sound Engines:

1. **Select Envelope 3 and create/modify a curve in the envelope display:**



2. **Select Envelope 4 and create/modify another curve:**



3. **In the Waveform selector for a Sound Engine, select the "Envelope 3-4" waveform:**



4. **Turn the Shape knob to crossfade between the curves/waveforms of Envelopes 3 and 4:**




Using the Envelope 4 curve as a Spectral Filter curve

Another special feature is that you could use the Envelope 4 curve as a filter curve in the Spectral Filter:

1. **Select Envelope 4 and create/modify a curve in the envelope display:**



2. **In the Filter selector in the Spectral Filter section, select "Envelope 4":**



3. **Turn the Freq knob to change the curve's "cutoff" frequency and the Reso knob to change the curve's "resonance".**
   At Reso=0% the curve is completely flat (no gain or attenuation) and at Reso=100% the resonance corresponds exactly to the Envelope 4 curve.

The LFO section



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of a signal to produce vibrato, but there are countless other applications for LFOs.

The LFO section features three separate general purpose LFOs, that can be assigned to control selectable parameter(s) in the Modulation Bus section, see "The Modulation Bus section".

1. **Select which of the three LFOs you want to edit by clicking one of the LFO 1, LFO 2 and LFO 3 buttons.**
2. **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by click-holding in the display and dragging up or down.**
   Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.
3. **Set the LFO frequency with the Rate knob.**

- **Click the Beat Sync button to sync the LFO to the main sequencer Tempo in Reason.**
  The Rate parameter now controls the time divisions.
- **Click the Key Sync button to restart the LFO at every new Note On.**
- **Click the Global button to make the LFO common for all voices (monophonic).**
- **Turn the Delay knob to introduce a delay before the LFO modulation kicks in after a note is played.**
  Turn clockwise for longer delay times.

The Effects section



The Effects section features six different effect modules that can be freely reordered by dragging & dropping. Most of the effect parameters are also available as destinations in the Modulation Bus, see "The Modulation Bus section".

At the top of the Effects section are six Effect buttons. Click any of these to bring up the control panel for the corresponding effect. Below the Effect buttons are the On/Off buttons for the individual effects. Click these to activate the effects.

Reordering the effects

▶ **To define the order of the effects in the serial chain, click and hold on the desired Effect button and drag sideways to the desired position:**



Moving the Reverb effect to another position in the effects chain.

You can reorder the effects at any time.

Reverb



This is a stereo reverb, routed as a send effect.

- **Decay**
  This governs the length of the reverb effect.
- **Size**
  Sets the emulated room size, from small room to large hall. Middle position is the default room size.
  Lowering this parameter results in a closer and gradually more "canned" sound. Raising the parameter results in a more spacey sound, with longer pre-delay.
- **Damp**
  Raising the Damp value cuts off the high frequencies of the reverb, thereby creating a smoother, warmer effect.
- **Amount**
  Use this parameter to adjust the send level to the Reverb effect.

  If you play a note, have a long delay Decay time and turn down Amount, the reverberation will continue.

Delay



This is a stereo delay, routed as a send effect.

- **Sync**
  Activate Sync to sync the delay time to the main sequencer Tempo.
- **Time**
  This sets the time between the delay repeats. If Sync is active (see above), the Time parameter now controls the time divisions.
- **Ping Pong**
  Activate Ping Pong to have the delay repeats alternating between left and right in the stereo panorama. The effect is also dependent on the Pan parameter (see below).
- **Pan**
  Sets the panning of the delay repeats in the stereo panorama. If Ping Pong is active (see above) the Pan knob controls the panning of the initial delay repeat as well as the total stereo spread of the remaining repeats.
- **FB**
  The FB (feedback) parameter determines the number of delay repeats.
- **Amount**
  Use this parameter to adjust the send level to the Delay effect.

▶ **If you play a note, have a long delay feedback and turn down Amount, the echoes will continue. This allows for automated "triggered delay" fx.**

Distortion



The Distortion effect features six different types of distortion.

▶ **Select distortion type with the switch.**
"Dist" produces a dense, rich analog type of distortion.
"Scream" produces a less bright type of distortion.
"Tube" emulates a tube type of distortion.
"Sine" is a sine shaping distortion.
"S/H" gives the effect of sample rate reduction.
"Ring" is a ring modulator effect.

- **Drive**
  Sets the overdrive/feedback level of the selected distortion.
- **Tone**
  This is a lowpass filter and sets the tone of the selected distortion.
- **Amount**
  Sets the Dry/Wet amount of the distortion.

Compressor



This is a stereo compressor.

- **Attack**
  This governs how quickly the compressor will apply its effect when signals rise above the set threshold. If you raise this value, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds.
- **Release**
  When the signal level drops below the set threshold, this determines how long it takes before the compressor lets the sound through unaffected. Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics.
- **Thres**
  This is the threshold level above which the compression sets in. Signals with levels above the threshold will be affected, signals below it will not. In practice, this means that the lower the Threshold setting, the more the compression effect.
- **Ratio**
  This specifies the amount of gain reduction applied to the signals above the set threshold.

Phaser/Flanger/Chorus



This is a stereo Phaser/Flanger/Chorus.

- ▶ **Select effect type with the Phaser/Flanger/Chorus switch.**
  The selected effect type is displayed on the Effect button.
- **Depth**
  Sets the depth of the selected effect. To get a static sound, set Depth to zero.
- **Rate**
  Sets the rate/speed of the modulation.
- **Spread**
  Sets the stereo width of the effect.
- **Amount**
  Sets the Dry/Wet amount of the effect.

▶ **It's also possible to modulate the start/center frequency of the Phaser/Flanger/Chorus using the "Chorus/Flanger/Phaser > Frequency" destination in the Modulation Bus, see "The Modulation Bus section".**


EQ



The EQ effect is a single band parametric equalizer with adjustable Q-value and Gain.

- **Freq**
  Sets the center frequency of the EQ band.
- **Q**
  Sets the bandwidth of the EQ band, from wide to narrow.
- **Gain**
  Sets the gain/attenuation of the EQ band, from -18dB to +18dB.

The Modulation Bus section



The Modulation Bus section is used for routing a modulation Source to one or two modulation Destinations each. This creates a very flexible routing system that complements the "pre-wired" routing in Europa.

The Modulation Bus section in Europa is derived from the one in the Reason Thor Polysonic Synthesizer device, so if you are familiar with Thor, you will quickly find your way around in Europa's modulation bus.

There are eight "Source –> Destination 1 –> Destination 2 –> Scale" busses, of which the first four have pre-assigned sources. However, these four pre-assigned sources can be easily changed if you like.

A Source parameter can modulate two different Destination parameters per bus (with variable Amount settings). Each bus also has a Scale parameter that affects the relative modulation Amount for both Destinations.

▶ **Note that it is possible to assign the same source parameter as Source in several busses. This allows you to control more than two Destination parameters from the same Source.**

1. Select the desired Source parameter by clicking in the corresponding Source box and selecting from the list.

The following parameters can be used as modulation Sources:

Parameter	Description
Velocity	This applies modulation according to the Keyboard Velocity values (how hard or soft you strike the MIDI keyboard keys).
LFOs (LFO 1, LFO 2 and LFO 3)	This allows you to modulate parameters from LFO 1, LFO 2 and LFO 3 respectively.
Envelopes (Amp Envelope, Envelope 1, Envelope 2, Envelope 3, Envelope 4, Envelope 3 * Envelope 4, Envelope 3 * LFO 3)	This allows you to modulate parameters from any of the Envelopes. As a special feature you can also modulate parameters from the multiplied signal of Envelope 3 and Envelope 4, as well as from the multiplied signal of Envelope 3 and LFO 3.
Mod Wheel	This allows you to modulate parameters from the Mod Wheel.

Parameter	Description
MW Latched	This allows you to modulate parameters based on the current Mod Wheel value at a given Note On.
Pitch Wheel	This allows you to modulate parameters from the Pitch Bend control.
Breath	This allows you to modulate parameters from the Breath performance controller
Expression	This allows you to modulate parameters from the Expression performance controller
Aftertouch	This allows you to modulate parameters from Keyboard Aftertouch (channel aftertouch)
Sustain	This allows you to modulate parameters from a connected sustain pedal. Note that continuous sustain data (0-127) is supported - not just on/off.
Key	This is keyboard tracking. If a positive Amount value is used and the destination is filter frequency, the filter frequency will track the keyboard, i.e. increase with higher notes.
Random	This sends out a random value each time a new note is played.
Key In Octave	This allows you to modulate parameters based on 12 separate note values (within each octave).
Noise	This allows you to modulate parameters from white noise.
Polyphony	This allows you to modulate parameters based on the number of playing voices at a given time.
Last Velocity	This applies modulation according to the latest Keyboard Velocity value (how hard or soft you hit the latest MIDI keyboard key).
CV Input 1/2/3/4	This takes the current value on the CV 1/CV 2/CV 3/CV 4 inputs on the rear panel and sends to the desired destination.
CV Input 1/2/3/4 Latched	This allows you to modulate parameters based on the current CV 1/CV 2/CV 3/CV 4 value at a given Note On.


Modulation Bus Source parameters.

2. **Set the Amount for the first Destination by turning the corresponding Amount knob, or by clicking and dragging vertically in the corresponding Amount box.**

! **Note that the Amount range is +/-100. This means that the Amount value can exceed the modulated parameter's range. When this happens, the modulated parameter simply stays at its extreme value until the Amount value gets within the parameter's range again.**

3. **Select the first Destination parameter by click-holding the red arrow symbol to the right of the corresponding Destination box.**

4. **While click-holding, drag to the desired destination parameter on the panel:**



Assigning LFO 1 Rate as a Destination for Envelope 1.

As you hover over a valid destination control on the panel, the parameter name is automatically displayed in the Destination box in the Modulation Bus.

5. **To assign the currently selected Destination control, release the mouse button.**

▶ **Alternatively, click the desired Destination box and select the Destination parameter from the list.**

The following parameters can be used as modulation Destinations:

Parameter	Description
Engine: Pitch	This affects the (full range) pitch of the Oscillator.
Engine: Shape	This affects the Shape parameter in the Oscillator section.
Engine: Mod 1 Amount	This affects the Modifier 1 Amount parameter in the Sound Engine.
Engine: Mod 2 Amount	This affects the Modifier 2 Amount parameter in the Sound Engine.
Engine: Filter Freq	This affects the Spectral Filter Frequency parameter in the Sound Engine.
Engine: Filter Res	This affects the Spectral Filter Resonance parameter in the Sound Engine.
Engine: Harmonics Pos	This affects the Harmonics Pos parameter in the Sound Engine.
Engine: Harmonics Amount	This affects the Harmonics Amount parameter in the Sound Engine.
Engine: Unison Count	This affects the Unison Count parameter in the Sound Engine.
Engine: Unison Detune	This affects the Unison Detune parameter in the Sound Engine.
Engine: Unison Blend	This affects the Unison Blend parameter in the Sound Engine.
Engine: Unison Spread	This affects the Unison Spread parameter in the Sound Engine.
Mixer: Level	This affects the Sound Engine Level in the Mixer section.
Mixer: Pan	This affects the Sound Engine Pan in the Mixer section
Filter: Drive	This affects the Drive parameter in the Filter section.
Filter: Freq	This affects the Frequency parameter in the Filter section.
Filter: Reso	This affects the Resonance parameter in the Filter section.
Amplifier: Gain	This affects the Gain parameter of the Amplifier section.
Amplifier: Pan	This affects the Pan parameter of the Amplifier section.
Amp Envelope: Attack	This affects the Attack time of the Envelope in the Amplifier section.
Amp Envelope: Decay	This affects the Decay time of the Envelope in the Amplifier section.
Amp Envelope: Sustain	This affects the Sustain level of the Envelope in the Amplifier section.
Amp Envelope: Release	This affects the Release time of the Envelope in the Amplifier section.
LFOs: Delay	This affects the LFO Delay parameters.
LFOs: LFO Rate	This affects the LFO Rate parameters.
Envelopes: Env Rate	This affects the Envelope Rate parameters.
Portamento	This affects the Portamento Time parameter.
CV Outputs: CV1/2/3/4 Out	This sends out the source modulation value(s) on the CV1/2/3/4 Output on the rear panel.
Reverb: Decay	This affects the Decay parameter in the Reverb effect.
Reverb: Amount	This affects the Amount parameter in the Reverb effect.
Delay: Time	This affects the Time parameter in the Delay effect.
Delay: Feedback	This affects the FB parameter in the Delay effect.
Delay: Amount	This affects the Amount parameter in the Delay effect.
Delay: Pan	This affects the Pan parameter in the Delay effect.
Dist: Drive	This affects the Drive parameter in the Dist effect.
Dist: Tone	This affects the Tone parameter in the Dist effect.
Dist: Amount	This affects the Amount parameter in the Dist effect.
Compressor: Release	This affects the Release parameter in the Compressor effect.
Compressor: Ratio	This affects the Ratio parameter in the Compressor effect.
Chorus/Flanger/Phaser: Frequency	This affects the center frequency of the Chorus/Flanger/Phaser effects.
Chorus/Flanger/Phaser: Amount	This affects the Amount parameter of the Chorus/Flanger/Phaser effects.
Par EQ: Frequency	This affects the Freq parameter in the EQ effect.
Par EQ: Gain	This affects the Gain parameter in the EQ effect.

Modulation Bus Destination parameters.



6. **Set the Amount for the second Destination (if desired) by turning the corresponding Amount knob, or by clicking and dragging vertically in the Amount box for the second destination.**
7. **If desired, select a second Destination parameter by click-holding the red arrow symbol to the right of the corresponding Destination box, and dragging to the desired control on the panel.**
8. **If desired, click the Scale box and select a Scale parameter.**
   The available Scale parameters are the same as the Source parameters, see "Modulation Bus Source parameters.".
9. **Turn the Scale Amount knob, or click the Amount box to the left of the Scale box and move the mouse pointer up or down to set a Scale Amount value.**
   Both positive and negative Scale Amount values can be set (+/- 100%). If you, for example, are using the Mod Wheel as Scale parameter and don't want any modulation when the Mod Wheel is set to zero, set the Scale Amount parameter to 100%. Then, there will be no effect when the Mod wheel is set to zero, and full modulation when the Mod Wheel is all the way up.

- **How much modulation will be applied when the Scale parameter is set to maximum is governed by the to Destination Amount parameter(s).**
- **How much the Scale parameter controls the modulation is set with the Scale Amount parameter.**

- **To clear an assigned Source, Destination or Scale parameter, hold down [Ctrl](Win) or [Cmd](Mac) and click the Source/Destination/Scale box. Alternatively, click the Source/Destination/Scale box and select "Off" from the list.**
- **To reset an Amount value to 0, hold down [Ctrl](Win) or [Cmd](Mac) and click the desired Amount box or knob.**
- **To clear an entire modulation assignment (a whole row), click the circular X button to the right of the corresponding Scale box.**



Connections



! **Remember that CV connections are NOT stored in the Europa patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Europa from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

CV Modulation inputs and outputs

These assignable control voltage (CV) inputs and outputs can be used for modulation of and from assigned Source and Destination parameters in the Modulation Bus section, see "The Modulation Bus section".

Audio Output


These are the main audio outputs. When you create a new Europa device, these outputs are auto-routed to the first available Mix Channel in the main mixer. If there is no Mix Channel available, a new one will be automatically created.

Tips and Tricks

Creating an individual “pre amp envelope” for a Sound Engine

There might be situations where you want to control the amplitude envelopes separately for each Sound Engine. Let’s say you have a plucked sound with a fairly long release in Sound Engine 2 and then you want to slowly fade in a pad sound from Sound Engine 1. Since the built-in Amp Envelope controls all three Sound Engines together, you could use the following “workaround”:

1. **Assign “Envelope 1” as Source and “Mixer: Eng1 Level” as Destination in the Modulation Bus.**
   Turn the Amount knob to 100 in the Modulation Bus.




2. **Create your “fading” envelope curve in the Envelope 1 display.**
   Click the Sustain button in the Envelopes display if you want to have a sustain stage in your envelope.



3. **Set the Sound Engine 1 Mixer Level slider to zero.**



4. **As you play the keyboard, Envelope 1 will now fade in the signal from Sound Engine 1, while the signal from Sound Engine 2 is only controlled by the built-in Amp Envelope.**




! **Note that the built-in Amp Envelope’s settings will also affect the “fading pad” sound from Sound Engine 1, since all Sound Engine signals eventually pass through the Amp Envelope.**

Recording display movements in the sequencer

If you are in "experimentation mode" and want to try out some wild waveform and/or Spectral Filter tweaking, you can record automation of your interactive display movements in the sequencer:

1. **Record some notes on the sequencer track in the Reason sequencer and then hit Stop twice.**
2. **Hit Record again in the Reason sequencer and click and drag in the Waveform display during recording:**



3. **Hit Stop in the sequencer twice when you are done recording.**
   Any vertical movements have now been recorded as Shape parameter automation and any horizontal movements have been recorded as Modifier 1 Amount parameter automation.
4. **If you like, hit Record again in the Reason sequencer and click and drag in the Spectral Filter display during recording:**




5. **Hit Stop in the sequencer twice when you are done recording.**
   Any vertical movements have now been recorded as Spectral Filter Resonance parameter automation and any horizontal movements have been recorded as Spectral Filter Frequency parameter automation.



Chapter 30
Grain
Sample Manipulator



Introduction



The Grain Sample Manipulator is a very advanced sampler and granular synthesizer, which offers sonic possibilities far beyond the ordinary. Despite its vast sonic capabilities, Grain has a straight-forward user interface, designed for experimentation.

Grain uses samples as base for sound generation. You could either load a sample from your computer or sample straight into Grain. You can then select various types of sample playback modes and algorithms to manipulate and process the audio. You could also use Grain as a traditional sampler and just play back samples in a regular fashion.


A number of filter and modifier algorithms make it possible to modulate and control the audio further. The extensive Envelopes section and Modulation Bus section allow for detailed and flexible modulation and control. Grain also features a flexible and great-sounding multi-effect to spice up your sounds even more.

Don't forget to check out the Grain videos here!

A few words about granular synthesis

Grain utilizes "granular synthesis" to generate sounds. This synthesis method results in playback of a series of snippets of audio data - grains - "extracted" from an audio sample. The grains could be of a selectable length and spacing, and could be from anywhere in the original sample. The grains could also be played back in a number different ways - with or without crossfades between the grains.

The picture below shows the basic principle of granular synthesis:



An example of a signal generated from 5 grains of a sample.


Here is what happens in the example above:

- **The original sample at the top is used as base for the granular synthesis.**
- **5 grains (of the same lengths and the same distances between them) are "extracted" from the original sample.** The distance between the grains is determined by the current sample playback speed. The grains could contain common audio data in some parts (like in the beginnings and ends in the example above).
- **The 5 grains are then placed after one another, partly overlapping each other.** The distance between the grains is determined by the playback rate.
- **When the grains are played back, big parts of the grains are played back together (since they are overlapping).** In the example above, there are also crossfades between the grains to make the overlaps smoother.

Note that the picture above only describes one basic example of granular synthesis - the "Long Grains" playback algorithm in Grain. Grain uses a number of different granular synthesis and spectral synthesis techniques, with different functionality and characteristics.

Panel overview

The Grain front panel contains the following sections:



The Grain front panel sections.

- **1. MIDI Note On LED.**
- **2. Patch Selector (for browsing, loading and saving patches), Polyphony and Master Volume controls.**
- **3. Sample section (for sample loading/sampling and sample playback functions).**
- **4. Playback Algorithm and Oscillator section.**
- **5. Filter and Amplifier sections.**
- **6. Global performance and "play" controls.**
- **7. Envelopes section.**
- **8. LFO section.**
- **9. Modulation Bus section.**
- **10. Effects section.**

Playing and using Grain

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

! **Like with the other sampler devices in Reason, the patch does not include the actual sample - only a reference to it. Therefore, the sample has to be stored separately (self-contained with the song, or already on disk or in a ReFill on your computer).**

Global performance and "play" controls



Key Mode

Here you choose how Grain should respond to MIDI Note data:

- **Poly**
  Select this if you want to play Grain polyphonically. The maximum number of voices is 12. The number of voices is set in the Voices control at the top right of the Grain panel, see "Voices".
- **Retrig**
  Select this if you want to play Grain in monophonic mode and always retrigger the envelopes as soon as you play a new note.
- **Legato**
  The Mono Legato mode is also monophonic. However, if you play a new note without having released the previous one, the envelopes and sample playback position won't start over.

▶ **Also see the description of the "Global Position" parameter. This describes how to play through a sample in a "non-legato" fashion - or polyphonically - in a "sample playback legato" fashion, where new notes will continue at the current sample playback position (and not restart playback).**

Porta

Portamento makes note pitches glide from previous notes to new ones, at the time set with the Time knob. Portamento can be used in all Key modes (see above).

- **When On in Poly Key Mode (see above), the pitches will glide from any of the available voices.**
  The results will be unpredictable since there is no way of controlling from which note(s) the glide(s) will commence. The effect is very nice, though.
- **When On in Retrig or Legato Key Mode (see above), the pitch will glide between consecutive notes.**
- **In Auto mode, the pitch will glide between consecutive monophonic notes only when you play legato. If you have selected Poly Key Mode (see above), Auto will have no effect at all.**
  If you release the previous key before hitting the new key, there will be no portamento effect.

Range

▶ **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
Range: +/-24 semitones (+/-2 octaves) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Grain also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "Range" control above the Pitch bend wheel.

! **Note that with some playback algorithms, such as Spectral Grains, the audible pitch depends on the formant rather than the pitch settings (see "Spectral Grains"). For pitch bend to have an effect here, you need to add a Pitch Wheel -> Formant routing in the Modulation Bus, see "The Modulation Bus section".**

Mod

The Mod wheel can be used for controlling almost any parameter in Grain. Use the Mod wheel as a Source parameter in the Modulation Bus section and then route to the desired Destination parameter(s), see "The Modulation Bus section".

Global output controls



Voices

Here you set the polyphony of your patch, from 1 to 12 voices.

▶ **If you want monophonic playback you can use the "Retrig" and "Legato" modes instead of lowering the Voices parameter to 1.**


Master Volume

This is the main stereo output volume control.

Panel reference

The Sample section

Here is where you load/sample and configure the audio that should serve as the base for the granular synthesis.



Loading/sampling

- **Load a sample using drag & and drop, or by clicking the Browse sample button, or by using the Up/Down buttons to scroll and load a sample from the currently selected folder.**
- **Alternatively, sample straight into Grain by clicking the Start sampling button.**
  See the "Sampling" chapter for more information about setting up and using Reason for sampling.
- **Click the Edit Sample button to open up the existing sample in the Sample Edit window.**
  See "Editing samples" for more information about editing samples in Reason.

! **It's possible to load/sample stereo signals. However, the waveform will always be displayed as a mono signal, regardless if it's mono or stereo.**

Setting the sample range

First you could decide how much of the original sample you want to use - and where in the sample you want to work:

- **Zoom and/or scroll in the Sample Overview to define the Sample range you want to work in.**
  To scroll, click and drag between the orange sample range markers. To zoom, click and drag any of the sample range markers sideways. The set Sample range is automatically updated and displayed in the waveform display.
- **To work in the entire Sample range, drag the left Sample range marker all the way to the left, and the right Sample range marker all the way to the right, in the Sample Overview.**
- **It's possible to automate the sample range settings, see "Automating sample playback parameters from the sequencer".**

Setting the sample start and end

- ▶ **Drag the green Sample Start marker to where you want the sample to begin playing back.**
- ▶ **Drag the red Sample End marker to where you want the sample playback to end.**
  The green triangular "flag" on the Sample Start marker shows the current playback direction. If the Sample Start marker should be to the right of the Sample End marker, the sample will play back in the opposite direction.
- ! **Note that the Freeze playback motion mode don't have any Sample End Marker, see "Freeze" below.**
- ▶ **It's possible to automate the sample start and end settings, see "Automating sample playback parameters from the sequencer".**

Motion

Motion controls the way the Position marker ("playhead") is played back in the original sample. The Motion modes work in conjunction with the Sample Start/End markers in the waveform.

- ▶ **Click the Motion selector to choose one of the following playback motion modes:**

- **Freeze**
  In Freeze mode, the sample is played back at (and around) the Sample Start marker position. There is no Sample End marker in this mode. Note that if you have selected the Tape algorithm (see "Tape"), there will be no sound.
- **One Shot**
  In One Shot mode, the sample is played back (from the Sample Start marker to the Sample End marker) in its entirety each time you press a key.
- **FW Loop**
  In FW Loop mode, the sample is looped forward (from the Sample End marker to the Sample Start marker) for as long as you hold down a key.
- **FW-BW Loop**
  In FW-BW Loop mode, the sample is looped back and forth between the Sample End marker and the Sample Start marker for as long as you hold down a key.
- **End Freeze**
  In End Freeze mode, the sample is played back once from the Sample Start marker to the Sample End marker and then played back at (and around) the Sample End marker position. Note that if you have selected the Tape algorithm (see "Tape"), there will be no sound after you reached the Sample End marker.
- **Envelope 1**
  In Envelope 1 mode, the sample is played back between the Sample Start marker and the Sample End marker according to the Envelope 1 curve (see "The Envelopes section"). The Sample Start position is represented by the minimum Y value and the Sample End position is represented by the maximum Y value in the Envelope display.

  The Envelope 1 mode is also the mode to use if you want to play back and loop the sample in sync with the Reason sequencer. Use a straight ramp (up) in Envelope 1, activate Beat Sync and set the sync to a suitable bar length, see "Looping the envelope".

Speed

The Speed control determines how fast the play position moves in the waveform.

- ▶ **Set the sample playback speed with the Speed knob.**
  Depending on which Motion mode and Playback Algorithm is currently selected, the sonic result may vary heavily. If you have selected the Tape algorithm (see "Tape"), the Speed knob also affects the pitch. Note that the Speed can be set all the way down to 0%, i.e. "stop". Great for Tape Stop effects, for example.
- ! **Note that the Speed control doesn't have any effect when you use the Envelope 1 motion mode, see "Envelope 1" above.**


Jitter

The Jitter function modulates the sample playback position minutely and randomly. The Jitter function can be great for generating "chorus"-like effects and to make a sound more "alive", depending on the other settings in the sound.

- **Set the playback position deviation with the Jitter knob.**
  At 0%, the timing and playback position is completely accurate and at 100% it is completely random.

Global Position

- **Click the Global Position button to start playback of new voices from the global position, i.e. from where the blue Position marker is currently positioned in the waveform display:**



This function is great for rhythmic and vocoder-like sounds etc.

If not active, new voices will always start playing back from the Sample Start marker.

Root Key


A sample is automatically analyzed for its original pitch at the Sample Start position. The analyzed pitch is displayed in the Analyzed display in the Root Key section. If you move the Sample Start marker, the sample is automatically re-analyzed.

- **Click the "SET" button to use the analyzed Root Key.**
  This will automatically place the analyzed Root Key on the correct note in the keyboard range.
- **Alternatively, define the Root Key manually by dragging up/down in the "Semitone" and "Cents" boxes.**

The Playback Algorithms section


Here is where you select which Playback Algorithm to use for manipulating the sample. Each of the Playback Algorithms produce very different sonic results and have different unique parameters.

! **Note that the common Pitch controls to the upper right could affect the sound differently, depending on the selected algorithm.**



- **Click the Playback Algorithm selector and choose one of the following four algorithms:**

Spectral Grains




The Spectral Grains playback algorithm uses FFT analysis to analyze the frequency content (partials) of the original sample. You can then stretch the generated signal by pitch-shifting the partials, and also filter out inharmonic partials. This way you could continuously transform inharmonic signals into harmonic signals, for example. You can also draw your own formant curves in the spectrum display to give the sounds different pitches/characters.

- **Snap**
  This pitch-shifts inharmonic partials towards the closest harmonic partials. At 0% the sound is almost unaffected and at 100% the sound contains only harmonic partials.
- **Filter**
  Instead of pitch-shifting inharmonic partials towards harmonic ones, as the Snap control above does, the Filter control filters out the inharmonic partials and keeps the harmonic ones. Since the filter slopes are not brickwall shaped some of the inharmonic partials (if any) will remain audible even at 100%.
- **FFT Size**
  This sets the accuracy (and speed) of the frequency analysis. "0" is the fastest detection, but this also leaves out detection of low frequencies. "3" is the most accurate detection. However, it's also slower since it also detects low-frequency material (which takes longer to detect).
- **Curve**
  With the Curve tool you can draw your own formant curves in the frequency spectrum. Drawing above the pink area means the partials are amplified, and drawing below the pink area means the partials are attenuated.
- **Amount**
  Set the gain/attenuation amount of the drawn formant curve (see "Curve" above). At 0% the curve is completely flat.
- **Formant**
  Sets the initial pitch of the sample, together with the Root Key setting (see "Root Key"). If Snap and Filter are both set to 0%, the Root Key and Formant controls the pitch of the signal. This also means that the Pitch parameters (see "Pitch controls") and Pitch wheel (see "Pitch") have no effect. To have the Formant track the keyboard in a musical way, make sure the Formant Kbd parameter (see below) is set to 100%.

  When you raise the Snap or Filter parameters towards 100% the sound gradually adapts to the Pitch settings instead, and the Root Key and Formant parameters now affect the tone color instead.
- **Formant Tune**
  Here you can fine-tune the formant curve to adjust the pitch to the Oscillator pitch (see "The Oscillator section").
- **Formant Kbd**
  Here you set how much you want the formant to track the keyboard. 0% means no keyboard tracking and 100% means full 1:1 keyboard tracking. If the Snap and Filter parameters (see above) are both set to 0%, make sure the Formant Kbd is set to 100% to make the audible pitch track the keyboard one semitone per note.


Grain Oscillator



The Grain Oscillator plays back a mix of two very short grains of the original sample. The grain playback rate corresponds to the oscillator pitch. This means the original pitch (Root Key/Formant) of the sample doesn't affect the pitch of the sound, but the timbre.

- **Pan Spread**
  Here you set how much you want the grains to be panned in the stereo panorama. 0% means the signal will be unaffected and 100% means every other grain will be panned hard left and hard right. Great for nice stereo effects and for the impression of an added stereo sub-oscillator, depending on the settings. Note that the pitch of the panned signal becomes 1 octave lower than the original signal due to the fact that every other grain is panned.
- **Pitch Jitter**
  Changes the pitch of every grain. The pitch modulation character is "smooth random".
- **Grain Length**
  Sets the lengths of the grains and also the crossfade amount. At 0% you get the shortest grains and almost no crossfade at all. This means the sound could be a little gritty at this setting. At 100% you get longer grains, that also overlaps each other with a smooth crossfade.
- **Grain Spacing**
  Sets the spacing in the original sample between the two played back grains. High Spacing values render more even sound character throughout the played notes - almost like a wavetable synth - since a lot of audio data in the original sample is skipped. Less spacing normally creates more varying sound character between each played note.
- **Formant**
  Sets the formant's initial frequency. Turn this knob to change the tone color of the sound. At high Grain Spacing values (see above) the effect of changing the Formant could be similar to the classic "oscillator sync" sound. To have the Formant fully track the keyboard, make sure the Formant KBD parameter (see below) is set to 100%.
- **Formant Tune**
  Here you can fine-tune the formant curve.
- **Formant Kbd**
  Here you set how much you want the formant to track the keyboard. 0% means no keyboard tracking and 100% means full 1:1 keyboard tracking.

Long Grains




The Long Grains playback algorithm plays back fairly long grains of the original sample. This means that it's the original pitch of the sound (Root Key) that affects the pitch, along with the Pitch settings (see "Pitch controls").

The display shows the effects of the Grain Length, Rate and X-Fade settings.

- **Pan Spread**
  Here you set how much you want every other grain to be panned in the stereo panorama. 0% means the signal will be unaffected and 100% means every other grain will be panned hard left and hard right. Great for nice stereo effects!
- **Pitch Jitter**
  Changes the pitch of every grain. The pitch modulation character is "smooth random".
- **Grain Length**
  Sets the lengths of the grains. At 0% you get the shortest grains and towards 100% you get longer grains.
- **Rate**
  This controls the playback rate of the grains.
- **X-Fade**
  Here you set the crossfade between the grains. At 0% there is minimal crossfade, which will give the signal a gritty or "popping" character at the playback start and end of each grain.

Tape



The Tape playback algorithm plays back the sample the old-fashioned "tape-style" way, where playback speed and pitch are linked. If playback speed is zero (in Freeze and End Freeze Motion modes for example), no sound will be heard - but you can drag, modulate or automate the playback position for scrubbing and tape stop effects.

- **Loop X-Fade**
  Sets the crossfade amount if you have selected FW Loop or FW-BW Loop as Motion type (see "Motion")

! **Note that the Loop X-Fade control has no effect if you have selected "Envelope 1" as Motion type.**

! **If you have selected "Envelope 1" as Motion type (see "Envelope 1"), the Speed (see "Speed") and Pitch settings (see "Pitch controls") have no effect. The sample will play back at the same pitch regardless of which note you play.**

Pitch controls



- **OCT**
  Sets the pitch in octave steps.
  Range: 5 octaves.
- **SEMI**
  Sets the pitch in semitone steps.
  Range: 12 semitones (one octave).
- **TUNE**
  Changes the pitch in steps of 1 cent.
  Range: +/- 50 cents (down or up half a semitone).
- **KBD**
  Sets how much the pitch should track incoming MIDI Notes.
  Range: 0% (no tracking (constant pitch)) to 100% (1 semitone per key).

! **In the Spectral Grains playback algorithm (see "Spectral Grains"), the Pitch controls have no effect if Snap and Filter are set to 0%. To get full effect of the Pitch controls, set Snap or Filter to 100%.**

The Oscillator section



The Oscillator can be used in addition to the sample playback. The oscillator features a number of selectable waveforms and a modulation control, which affect the signals differently depending on selected waveform. The oscillator pitch always tracks the keyboard to 100%. This makes it perfect as a pitch reference for the sample signal.

On/Off

- ▶ **Click the On/Off LED button to switch on/off the oscillator.**

Oct

- ▶ **Turn the OCT knob to change the pitch in octave steps.**
  Range: 5 octaves.

Waveform and Mod

- ▶ **Select the desired waveform by dragging up/down in the waveform display, or by clicking the up/down buttons.**
  The waveforms are:

- **Sine**
  A pure sinewave at Mod=0%, gradually transformed towards a sawtooth type signal at Mod=100%.
- **Triangle**
  A triangle wave at Mod=0%, gradually transformed towards a sawtooth type signal at Mod=100%.
- **Sawtooth**
  A lowpass-filtered sawtooth wave at Mod=0%, gradually transformed to a pure sawtooth signal at Mod=100%.
- **Square/Pulse**
  A 50% duty cycle square wave at Mod=0%, gradually pulsewidth-modulated to a 0% duty cycle pulse wave (silence) at Mod=100%.

- ▶ **Modulate the Mod parameter from an LFO (using the Modulation Bus) to achieve PWM.**

- **Noise**
  A level-compensated lowpass-filtered noise at Mod=0%, gradually transformed to white noise at Mod=100%.
- **Band Noise**
  A noise-modulated sinewave. The Mod knob controls noise bandwidth. At Mod=100%, the oscillator produces pure noise. Turning the knob counter-clockwise towards 0% gradually narrows the noise bandwidth until a slightly modulated sinewave is produced.

The Filter section



The signals from the Playback Algorithms section and the Oscillator section can be individually mixed and routed through the Filter section. The Filter section features four different filter types.

Routing buttons

- **Click the red buttons with a triangle pointing to the right, to route the desired signal to the Filter section.**
  To bypass the signals from the Filter section, click the buttons with the triangle pointing upwards or downwards.

Filter type

- **Click the Filter type selector to choose any of the following filter types:**

- **HP 12dB**
  A highpass filter with a 12dB/octave slope.
- **BP 12dB**
  A bandpass filter with 12dB/octave slopes.
- **LP 12dB**
  A lowpass filter with a 12dB/octave slope.
- **LP Ladder 24dB**
  A ladder-type lowpass filter with a 24dB/octave slope.

Freq

- **Set the cutoff frequency (for the HP and LP filter types) or the center frequency (for the BP filter type).**

Reso

- **Set the resonance amount.**

Env 2

- **Set the cutoff/center frequency modulation amount from the Envelope 2.**
  Since this is a "hardwired" connection from Envelope 2 you don't need to use the Modulation Bus for envelope modulating the cutoff/center frequency.

Vel

- **If you want the Envelope 2 amount to be controlled from keyboard velocity, turn up the Vel knob.**

Kbd


- **Set how much you want the filter cutoff/center frequency to track the keyboard.**
  At 0%, the filter frequency is static regardless where on the keyboard you play. At 100% the filter tracks the keyboard 1:1, i.e. one semitone per note.



The Amplifier section



The Amplifier section contains a standard ADSR envelope which controls the amplitude of the signals from the Playback Algorithms and Oscillator sections equally. The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

A(ttack)

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the Gain knob (see below). How long this should take, depends on the Attack setting. If the Attack is set to "0", the Gain level is reached instantly. If the Attack value is raised, it will take longer time before the Gain level is reached.

D(ecay)

After the Gain level has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.

S(ustain)

The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Gain level, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Gain level. Note that Sustain represents a level, whereas the other envelope parameters represent times.

R(elease)

The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

Gain

- **Set the desired maximum level for the Amplifier with the Gain knob.**
  This is the maximum level the envelope will reach after the Attack stage is completed (see above).
- **If you want to create a tremolo effect, assign "Gain" as Destination and an LFO as Source in the Modulation Bus section, see "The Modulation Bus section".**


Vel

- **If you want the Gain level to be controlled from keyboard velocity, turn up the Vel knob.**

Pan

- **Set the panning of the output signal from the Amplifier in the stereo panorama.**
- **Since Pan works individually per voice, you can assign e.g. Keyboard Velocity or an Envelope in the Modulation Bus to control the Pan effect, see "The Modulation Bus section".**

The Envelopes section




The Envelopes section features four separate polyphonic (one per voice) general purpose envelope generators, that can be assigned to control selectable parameter(s) in the Modulation Bus section. The first two envelopes (Envelope 1 and Envelope 2) are also hardwired to the Motion and Filter Frequency destinations respectively.

The Envelopes are extremely flexible, and you can draw your own custom modulation shapes by clicking and drawing in the display area. There are also a number of preset shapes that you can use as starting points (or use as is). If you use Loop mode, you could turn the envelope into a kind of LFO.

See "The Modulation Bus section" for details on how to assign the Envelopes to the desired destination(s).

Envelope 1, 2, 3 and 4


- **Click one of the Envelope 1, 2, 3 or 4 buttons to select which envelope to edit:**




Envelope 1 and Envelope 2 are also hardwired to the Motion and Filter Frequency destinations respectively.


Preset

1. **Click the Preset button to bring up a palette of envelope preset curves:**




2. **Click the desired envelope preset curve to place it on the display.**
   Let's select a standard ADSR style of envelope curve:






Adding a Sustain stage

- **Click the Sustain button to add a sustain stage to the envelope:**



The vertical blue marker that appears indicates where the envelope will stay sustained until you release the key.


- **Drag the sustain marker sideways to move the sustain stage to the desired position:**



- **To remove the sustain stage, click the Sustain button.**

Adding and removing envelope points


- **Double click, or hold down [Ctrl](win) or [Cmd](Mac) and click, in the envelope display to add points to the envelope curve:**



- **To remove a point, double click, or hold down [Ctrl](win) or [Cmd](Mac) and click, on an existing point on the envelope curve.**


Changing the envelope curve shape

- **Click a line segment (between two points) and drag up/down to change the curve shape:**



Looping the envelope

- **Click the Loop button to turn the envelope into a kind of LFO.**
  If there was previously a sustain stage in the envelope, this will automatically be disabled when you click the Loop button.




  Here we have edited a stepped curve from the Presets. We have also enabled Beat Sync and set the length/rate to 4/4. This means that each step in the curve now represents an 1/8th note.

- **Key Trig means the envelope restarts when you play a note.**
- **You can choose whether the envelope should send out a bipolar value or unipolar one (0-100%).**
- **If Global is on, the envelope will be common for all voices.**

Another useful application for looped envelopes is to sync the sample playback to the Reason sequencer when using the Envelope 1 Motion mode (see "Envelope 1"):


1. **Select Envelope 1 (since it is hardwired to the sample playback Motion parameter).**
2. **Select the "Ramp Up" Preset, enable Loop and set the Beat Sync to the desired value:**



  Playing back Reason's sequencer now plays back the sample synced to the sequencer Tempo.


Editing levels only

▶ **To restrict the editing to levels only, without affecting the time positions, click the Edit Y-Pos button:**



In this mode you cannot change the time positions of the envelope points, only their levels (height). This is extra useful with a stepped Preset curve, because dragging up or down will change the value of an entire segment, turning the Envelope into a pseudo-sequencer.

! **To be able to adjust the level of a segment, the two points on either side of the segment have to be on the exact same time positions. Otherwise, only the closest point will be changed. Also, any inclining/declining segment will automatically turn horizontal when edited:**




Adjusting the level of a segment.

Creating “free form” envelope curves

As a special feature in the Edit Y-Pos mode, you can also draw “free form” curves:

▶ **To continuously add new consecutive points, hold down [Ctrl](win) or [Cmd](Mac) and drag in the envelope display:**



▶ **To erase points, hold down [Shift] and [Ctrl](win) or [Cmd](Mac) and drag in the envelope display.**

The LFO section



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of a signal to produce vibrato, but there are countless other applications for LFOs.

The LFO section features three separate general purpose LFOs, that can be assigned to control selectable parameter(s) in the Modulation Bus section.

- **Select which of the three LFOs you want to edit by clicking one of the LFO 1, LFO 2 and LFO 3 buttons.**
- **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by click-holding in the display and dragging up or down.**
  Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.
- **Set the LFO frequency with the Rate knob.**
- **Click the Beat Sync button to sync the LFO to the main sequencer Tempo in Reason.**
  The Rate parameter now controls the time divisions.
- **Click the Key Sync button to restart the LFO at every new Note On.**
- **Click the Global button to make the LFO common for all voices (monophonic).**
- **Turn the Delay knob to introduce a delay before the LFO modulation kicks in after a note is played.**
  Turn clockwise for longer delay times.

The Effects section



The Effects section features six different effect modules that can be freely reordered by dragging & dropping. Most of the effect parameters are also available as destinations in the Modulation Bus, see "The Modulation Bus section".

At the top of the Effects section are six Effect buttons. Click any of these to bring up the control panel for the corresponding effect. Below the Effect buttons are the On/Off buttons for the individual effects. Click these to activate the effects.

Reordering the effects

- **To define the order of the effects in the serial connection, click and hold on the desired Effect button and drag to the desired position:**



Moving the Chorus effect to another position in the effects chain.

You can reorder the effects at any time.

Phaser/Flanger/Chorus



This is a stereo Phaser/Flanger/Chorus.

- ▶ **Select effect type with the Phaser/Flanger/Chorus switch.**
  The selected effect type is displayed on the Effect button.
- **Depth**
  Sets the depth of the selected effect. To get a static sound, set Depth to zero.
- **Rate**
  Sets the rate/speed of the modulation.
- **Spread**
  Sets the stereo width of the effect.
- **Amount**
  Sets the Dry/Wet amount of the effect.

- ▶ **It's also possible to modulate the start/center frequency of the Phaser/Flanger/Chorus using the "Chorus/Flanger/Phaser > Frequency" destination in the Modulation Bus, see "The Modulation Bus section".**

Distortion



The Distortion effect features six different types of distortion.

- ▶ **Select distortion type with the switch.**
  "Dist" produces a dense, rich analog type of distortion.

  "Scream" produces a less bright type of distortion.

  "Tube" emulates a tube type of distortion.

  "Sine" is a sine shaping distortion.

  "S/H" gives the effect of sample rate reduction.

  "Ring" is a ring modulator effect.
- **Drive**
  Sets the overdrive/feedback level of the selected distortion.
- **Tone**
  This is a lowpass filter and sets the tone of the selected distortion.
- **Amount**
  Sets the Dry/Wet amount of the distortion.

EQ



The EQ effect is a single band parametric equalizer with adjustable Q-value and Gain.

- **Freq**
  Sets the center frequency of the EQ band.
- **Q**
  Sets the bandwidth of the EQ band, from wide to narrow.
- **Gain**
  Sets the gain/attenuation of the EQ band, from -18dB to +18dB.

Delay



This is a stereo delay, routed as a send effect.

- **Sync**
  Activate Sync to sync the delay time to the main sequencer Tempo.
- **Time**
  This sets the time between the delay repeats. If Sync is active (see above), the Time parameter now controls the time divisions.
- **Ping Pong**
  Activate Ping Pong to have the delay repeats alternating between left and right in the stereo panorama. The effect is also dependent on the Pan parameter (see below).
- **Pan**
  Sets the panning of the delay repeats in the stereo panorama. If Ping Pong is active (see above) the Pan knob controls the panning of the initial delay repeat as well as the total stereo spread of the remaining repeats.
- **FB**
  The FB (feedback) parameter determines the number of delay repeats.
- **Amount**
  Use this parameter to adjust the send level to the Delay effect.

▶ **If you play a note, have a long delay feedback and turn down Amount, the echoes will continue. This allows for automated "triggered delay" fx.**

Compressor



This is a stereo compressor.

- **Attack**
  This governs how quickly the compressor will apply its effect when signals rise above the set threshold. If you raise this value, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds.
- **Release**
  When the signal level drops below the set threshold, this determines how long it takes before the compressor lets the sound through unaffected. Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics.
- **Thres**
  This is the threshold level above which the compression sets in. Signals with levels above the threshold will be affected, signals below it will not. In practice, this means that the lower the Threshold setting, the more the compression effect.
- **Ratio**
  This specifies the amount of gain reduction applied to the signals above the set threshold.

Reverb



This is a stereo reverb, routed as a send effect.

- **Decay**
  This governs the length of the reverb effect.
- **Size**
  Sets the emulated room size, from small room to large hall. Middle position is the default room size.
  Lowering this parameter results in a closer and gradually more "canned" sound. Raising the parameter results in a more spacey sound, with longer pre-delay.
- **Damp**
  Raising the Damp value cuts off the high frequencies of the reverb, thereby creating a smoother, warmer effect.
- **Amount**
  Use this parameter to adjust the send level to the Reverb effect.

  If you play a note, have a long delay Decay time and turn down Amount, the reverberation will continue.

The Modulation Bus section



The Modulation Bus section is used for routing a modulation Source to one or two modulation Destinations each. This creates a very flexible routing system that complements the pre-wired routing in Grain.

The Modulation Bus section in Grain is derived from the one in the Reason Thor Polysonic Synthesizer device, so if you are familiar with Thor, you will quickly find your way around in Grain's modulation bus.

There are eight "Source –> Destination 1 –> Destination 2 –> Scale" busses, of which the first four have pre-assigned sources. However, these four pre-assigned sources can be easily changed if you like.

A Source parameter can modulate two different Destination parameters per bus (with variable Amount settings). Each bus also has a Scale parameter that affects the relative modulation Amount for both Destinations.

▶ **Note that it is possible to assign the same source parameter as Source in several busses. This allows you to control more than two Destination parameters from the same Source.**

1. Select the desired Source parameter by clicking in the corresponding Source box and selecting from the list.

The following parameters can be used as modulation Sources:

Parameter	Description
Velocity	This applies modulation according to the Keyboard Velocity values (how hard or soft you strike the MIDI keyboard keys).
LFOs (LFO 1, LFO 2 and LFO 3)	This allows you to modulate parameters from LFO 1, LFO 2 and LFO 3 respectively.
Envelopes (Amp Envelope, Envelope 1, Envelope 2, Envelope 3, Envelope 4, Envelope 3 * Envelope 4, Envelope 3 * LFO 3)	This allows you to modulate parameters from any of the Envelopes. As a special feature you can also modulate parameters from the multiplied signal of Envelope 3 and Envelope 4, as well as from the multiplied signal of Envelope 3 and LFO 3.
Mod Wheel	This allows you to modulate parameters from the Mod Wheel.
MW Latched	This allows you to modulate parameters based on the current Mod Wheel value at a given Note On.
Pitch Wheel	This allows you to modulate parameters from the Pitch Bend control.
Breath	This allows you to modulate parameters from the Breath performance controller
Expression	This allows you to modulate parameters from the Expression performance controller
Aftertouch	This allows you to modulate parameters from Keyboard Aftertouch (channel aftertouch)
Sustain	This allows you to modulate parameters from a connected sustain pedal. Note that continuous sustain data (0-127) is supported - not just on/off.
Key	This is keyboard tracking. If a positive Amount value is used and the destination is filter frequency, the filter frequency will track the keyboard, i.e. increase with higher notes.
Random	This sends out a random value each time a new note is played.
Key In Octave	This allows you to modulate parameters based on 12 separate note values (within each octave).
Noise	This allows you to modulate parameters from white noise.
Polyphony	This allows you to modulate parameters based on the number of playing voices at a given time.
Last Velocity	This applies modulation according to the latest Keyboard Velocity value (how hard or soft you hit the latest MIDI keyboard key).
Sample Pitch Curve	As soon as you load a sample in Grain the pitches throughout the entire sample is automatically analyzed and saved as a "Pitch Curve". This allows you to modulate parameters based on the analyzed pitch value at the Position marker's current position in the original sample.

Parameter	Description
Display Y Position	This allows you to modulate parameters based on the mouse pointer's Y position in the sample window. See "Automating sample playback parameters from the sequencer" for an example.
Display Mouse Gate	This allows you to modulate parameters based on the clicking/holding the mouse in the sample window. See "Automating sample playback parameters from the sequencer" for an example.
CV Input 1/2/3/4	This takes the current value on the CV 1/CV 2/CV 3/CV 4 inputs on the rear panel and sends to the desired destination.
CV Input 1/2/3/4 Latched	This allows you to modulate parameters based on the current CV 1/CV 2/CV 3/CV 4 value at a given Note On.


Modulation Bus Source parameters.

2. **Set the Amount for the first Destination by turning the corresponding Amount knob, or by clicking and dragging vertically in the corresponding Amount box.**

! **Note that the Amount range is +/-100. This means that the Amount value can exceed the modulated parameter's range. When this happens, the modulated parameter simply stays at its extreme value until the Amount value gets within the parameter's range again.**

3. **Select the first Destination parameter by click-holding the grey arrow symbol to the right of the corresponding Destination box.**
   The arrow symbol turns blue.

4. **While click-holding, drag to the desired destination parameter on the panel:**



Assigning LFO 1 Rate as a Destination for Envelope 1.

As you hover over a valid destination control on the panel, the parameter name is automatically displayed in the Destination box in the Modulation Bus.

5. **To assign the currently selected Destination control, release the mouse button.**

! **Dragging to the Waveform Display (see "The Sample section") will always assign the playback Position parameter. To assign the sample Start Position or End Position, select the parameter from the list (see below).**

▶ **Alternatively, click the desired Destination box and select the Destination parameter from the list.**

The following parameters can be used as modulation Destinations:

Parameter	Description
Position	This affects the sample "playhead" position in the original sample.
Speed	This affects the Speed control in the sample window.
Jitter	This affects the Jitter control in the sample window.
Start Position	This affects the Sample Start marker position in the original sample.
End Position	This affects the Sample End marker position in the original sample.
Pitch	This affects the pitch of the original sample.
Octave	This affects the Oct control in the Playback Algorithm section.
Formant	This affects the Formant Form control in the Playback Algorithm section (if applicable).

Parameter	Description
Sample Level	This affects the Sample Level control of the Playback Algorithm section.
Grain: Length	This affects the Grain Length parameter on the Grain Oscillator and Long Grains playback algorithms.
Grain: Rate/Spacing	This affects the Grain Spacing parameter on the Grain Oscillator and the Rate parameter on the Long Grains playback algorithms.
Grain: X-Fade	This affects the X-Fade parameter on the Long Grains playback algorithm.
Grain: Pan Spread	This affects the Pan Spread parameter on the Grain Oscillator and Long Grains playback algorithms
Grain: Pitch Jitter	This affects the Pitch Jitter parameter on the Grain Oscillator and Long Grains playback algorithms
Spectral Grain: Harm Snap	This affects the Snap parameter on the Spectral Grains playback algorithm.
Spectral Grain: Harm Filter	This affects the Filter parameter on the Spectral Grains playback algorithm.
Spectral Grain: Curve Amount	This affects the Amount parameter on the Spectral Grains playback algorithm.
Oscillator: Modulation	This affects the Mod parameter on the Oscillator.
Oscillator: Octave	This affects the Oct parameter on the Oscillator.
Oscillator: Pitch	This affects the (full range) pitch of the Oscillator.
Oscillator: Level	This affects the Osc Level parameter of the Oscillator section.
Filter: Freq	This affects the Frequency parameter in the Filter section.
Filter: Reso	This affects the Resonance parameter in the Filter section.
Amplifier: Gain	This affects the Gain parameter of the Amplifier section.
Amplifier: Pan	This affects the Pan parameter of the Amplifier section.
Amp Envelope: Attack	This affects the Attack time of the Envelope in the Amplifier section.
Amp Envelope: Decay	This affects the Decay time of the Envelope in the Amplifier section.
Amp Envelope: Sustain	This affects the Sustain level of the Envelope in the Amplifier section.
Amp Envelope: Release	This affects the Release time of the Envelope in the Amplifier section.
LFO's: LFO1/2/3 Delay	This affects the LFO1/2/3 Delay parameter.
LFO's: LFO1/2/3 Rate	This affects the LFO1/2/3 Rate parameter.
Envelopes: Env1/2/3/4 Rate	This affects the Envelope 1/2/3/4 Rate parameter.
Portamento	This affects the Portamento Time parameter.
CV Outputs: CV1/2/3/4 Out	This sends out the source modulation value(s) on the CV1/2/3/4 Output on the rear panel.
Reverb: Decay	This affects the Decay parameter in the Reverb effect.
Reverb: Amount	This affects the Amount parameter in the Reverb effect.
Delay: Time	This affects the Time parameter in the Delay effect.
Delay: Feedback	This affects the FB parameter in the Delay effect.
Delay: Amount	This affects the Amount parameter in the Delay effect.
Delay: Pan	This affects the Pan parameter in the Delay effect.
Dist: Drive	This affects the Drive parameter in the Dist effect.
Dist: Tone	This affects the Tone parameter in the Dist effect.
Dist: Amount	This affects the Amount parameter in the Dist effect.
Compressor: Release	This affects the Release parameter in the Compressor effect.
Compressor: Ratio	This affects the Ratio parameter in the Compressor effect.
Chorus/Flanger/Phaser: Frequency	This affects the center frequency of the Chorus/Flanger/Phaser effects.
Chorus/Flanger/Phaser: Amount	This affects the Amount parameter of the Chorus/Flanger/Phaser effects.
Par EQ: Frequency	This affects the Freq parameter in the EQ effect.
Par EQ: Gain	This affects the Gain parameter in the EQ effect.
Note Trig	This is mainly intended for use with the Display > Mouse Gate or Display > Y-Position source parameters, e.g. with the Freeze motion mode, to trig/gate the sample without having to play the keyboard. This way you can play back the Root Key of the sample by just clicking/dragging in the Waveform display.

Modulation Bus Destination parameters.



6. **Set the Amount for the second Destination (if desired) by turning the corresponding Amount knob, or by clicking and dragging vertically in the Amount box for the second destination.**
7. **If desired, select a second Destination parameter by click-holding the blue arrow symbol to the right of the corresponding Destination box, and dragging to the desired control on the panel.**
8. **If desired, click the Scale box and select a Scale parameter.**
   The available Scale parameters are the same as the Source parameters, see "Modulation Bus Source parameters.".
9. **Turn the Scale Amount knob, or click the Amount box to the left of the Scale box and move the mouse pointer up or down to set a Scale Amount value.**
   Both positive and negative Scale Amount values can be set (+/- 100%). If you, for example, are using the Mod Wheel as Scale parameter and don't want any modulation when the Mod Wheel is set to zero, set the Scale Amount parameter to 100%. Then, there will be no effect when the Mod wheel is set to zero, and full modulation when the Mod Wheel is all the way up.


- **How much modulation will be applied when the Scale parameter is set to maximum is governed by the to Destination Amount parameter(s).**
- **How much the Scale parameter controls the modulation is set with the Scale Amount parameter.**

- **To clear an assigned Source, Destination or Scale parameter, hold down [Ctrl](Win) or [Cmd](Mac) and click the Source/Destination/Scale box. Alternatively, click the Source/Destination/Scale box and select "Off" from the list.**
- **To reset an Amount value to 0, hold down [Ctrl](Win) or [Cmd](Mac) and click the desired Amount box or knob.**
- **To clear an entire modulation assignment (a whole row), click the circular X button to the right of the corresponding Scale box.**

Modulation example patches

The factory patches for Grain features a folder named "Templates". In this folder you will find a number of patches that show typical modulation examples, to make it easier to get the hang of how to create your own patches.

Connections



! Remember that CV connections are NOT stored in the Grain patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Grain from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

CV Modulation inputs and outputs

These assignable control voltage (CV) inputs and outputs can be used for modulation of and from assigned Source and Destination parameters in the Modulation Bus section, see "The Modulation Bus section".

Audio Output


These are the main audio outputs. When you create a new Grain device, these outputs are auto-routed to the first available Mix Channel in the main mixer. If there is no Mix Channel available, a new one will be automatically created.

Tips and Tricks


Automating sample playback parameters from the sequencer

Besides the extensive modulation capabilities of the Modulation Bus, the sample playback parameters can also be automated in the Reason sequencer. For example, you could automate the Sample Start and/or Sample End markers in the Sample section to have the markers reposition in real-time during playback of the Reason sequencer. Below is a basic example of how you could automate various sample playback parameters:

1. **Record some notes on the Grain sequencer track in the Reason sequencer and then hit Stop twice.**
2. **Hit Record again in the Reason sequencer and drag the Sample Start and Sample End markers during recording:**




3. **Hit Stop in the sequencer twice when you are done recording.**
   If you moved both the Sample Start marker and the Sample End marker you will now have four Parameter Automation lanes with clips on them on the Grain sequencer track:




   The first two Parameter Automation lanes - the Display Y lane and the Display Gate lane - always appear as soon as you have recorded any marker movements in the Sample section display.

- **The clip on the Display Y lane represents the vertical movements you made with the mouse during the recording.** This automation doesn't affect the sample playback in any way but can instead be used as a modulation source in the Modulation Bus, for modulating the desired destination parameter(s).
- **The clip on the Display Gate lane reflects when you clicked (and held) the mouse button during the recording.** This automation doesn't affect the sample playback either but can be used as a modulation source in the Modulation Bus, for modulating/gating the desired destination parameter(s).
- **The clips on the Position and End Pos lanes represent the movements of the Sample Start and Sample End markers respectively.**

▶ **If you like you could also record automation of the Sample Range Zoom and Scroll parameters by dragging the markers in the Sample Overview area:**



After recording the movements of the Sample Range markers, two new Parameter Automation lanes appear on the sequencer track:



- **The clip on the Scroll lane represents the movement of the leftmost Sample Range marker, and thus the movement of the entire sample range.**
- **The clip on the Zoom lane represents the movement of the rightmost Sample Range marker, and thus the zooming (in or/and out) of the sample range.**

▶ **It's also possible to automate the Motion, Speed, Jitter and Global Position parameters.**

▶ **Also, don't forget to check out the modulation example patches, see "Modulation example patches".**

Chapter 31
Humana
Vocal Ensemble

Introduction



Humana Vocal Ensemble features a great selection of male and female vocal samples - perfect for any music style. The multi-sampled vocal sound sets can also be tailored and processed in the high-quality filter, amp, delay and reverb sections.

Panel overview

The Humana front panel contains the following sections:




The Humana front panel sections.

- **1. Patch Selector (for browsing, loading and saving patches).**
- **2. Master Volume.**
- **3. Global performance and "play" controls.**
- **4. Instruments section.**
- **5. Filter section.**
- **6. Amp Envelope section.**
- **7. Delay effect section.**
- **8. Reverb effect section.**

Using Humana

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global performance and "play" controls



Note

The Note LED lights up each time Humana receives a MIDI Note On.

Range

- ▶ **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
  Range: +/-12 semitones (+/-1 octave) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Humana also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "Range" control to the right of the Mod wheel.

Mod

The Mod wheel can be used for controlling the three predefined parameters to the right of the Mod wheel:

- **S. Start**
  Here you set how/if the Mod wheel should affect the Sample Start position of the currently selected instrument. The parameter is bi-polar, with zero modulation at the 12 o'clock position. A negative value moves the sample start back and a positive value moves it forward.

! **Note that if the S.Start parameter in the Instruments section (see "S. Start (Sample Start)") is at 0 ms, the sample start cannot be moved back any further. Similarly, if the S.Start parameter in the Instruments section is at 150 ms, the sample start cannot be moved forward any further.**

- **F. Freq**
  Here you set how/if the Mod wheel should affect the Filter Cutoff parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.

! **Note that if the Cutoff parameter in the Filter section (see "Cutoff") is at 20 Hz, the frequency cannot be lowered any further. Similarly, if the Cutoff parameter in the Filter section is at 25 kHz, the frequency cannot be raised any further.**

- **Level**
  Here you set how/if the Mod wheel should affect the Master Volume parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.

! **The volume can never be modulated louder than the maximum +12 dB limit of the Master Volume control.**

Panel controls

The Instruments section



Instrument selector



▶ **Click the Instrument name selector to bring up a menu of the available instruments - and then select the desired instrument from the menu.**
Alternatively, click and drag up/down in the display above the selector to scroll through the instruments.

! **Depending on the instrument size (in MB), it could take a short moment before the entire instrument is loaded into RAM.**

! **Also note that the note ranges of the instruments extend outside their "natural" ranges, which could produce nice artificial effects.**

The available instruments are:

- **Mars ah**



A male vocal ensemble singing sustained “Ah’s” (forte). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.

- **Mars oo**
  A male vocal ensemble singing sustained “Oo’s” (piano). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.
- **Mars ah Staccato**
  A male vocal ensemble singing staccato “Ah’s” (forte). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.
- **Mars oo Staccato**
  A male vocal ensemble singing staccato “Oo’s” (piano). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.
- **Venus ah**



A female vocal ensemble singing sustained “Ah’s” (forte). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.

- **Venus oo**
  A female vocal ensemble singing sustained “Oo’s” (piano). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.
- **Venus ah Staccato**
  A female vocal ensemble singing staccato “Ah’s” (forte). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.
- **Venus oo Staccato**
  A female vocal ensemble singing staccato “Oo’s” (piano). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Olympus Symphonic Choir.

- **Mercury ah**



A boys' choir singing sustained "Ah's" (forte). Recorded with stage mics (stereo) in a large hall, wet. Conducted by Robert Geary. The samples are from Soundiron's Mercury Symphonic Boys' Choir.

- **Female Soprano ah**



Female soprano Nichole Dechaine singing sustained "Ah's" (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Rapture.

- **Female Alto ah**



Female alto Kindra Scharich singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Rapture.

- **Male Tenor ah**



Male tenor Brian Thorsett singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Rapture.

- **Male Bass ah**



Male bass Joseph Trumbo singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Rapture.

- **Female ah**



Female alto soloist Francesca Genco singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Gaia.

- **Female ah 2**



Female alto soloist Linda Strawberry singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Gaia.

- **Male ah**



Male tenor soloist Brian Lane singing sustained “Ah’s” (forte). Recorded with close mic (mono) in a studio, dry. The samples are from Soundiron's Voices Of Gaia.

S. Start (Sample Start)



- ▶ **Turn the S.Start knob to set where in the sample the playback should start.**
  Note that the effect could be different depending on the selected instrument.

Oct



- ▶ **Set the octave transposition for the instrument.**
  Range: 5 (+/-2) octaves.

! **Note that the note ranges of the instrumentscan be transposed far outside their "natural" ranges, which could produce nice artificial effects.**

Semi



- ▶ **Set the pitch in semitone steps.**
  Range: +/-12 semitones (two octaves).

Fine



- ▶ **Set the pitch in steps of 1 cent.**
  Range: +/- 50 cents (down or up half a semitone).

The Filter section



Filter On/Off



▶ **Click the On/Off LED button to switch on/off the Filter section.**

Filter Type selector



▶ **Click and drag up/down on the Filter Type selector to select one of the available filter types - or step through the filter types by clicking the Up/Down arrow buttons.**
The available filter types are:

- **LP**
  This is a lowpass filter with 12db/octave slope.
- **HP**
  This is a highpass filter with 12db/octave slope.
- **BP**
  This is a bandpass filter with 6db/octave slopes.
- **Comb**
  This is a comb filter for phaser/flanger type of effects.

Cutoff



▶ **Set the cutoff/center frequency with the Cutoff knob.**
The cutoff parameter sets where in the frequency range you want the resonance and attenuation to appear.
Range: 20 Hz to 25 kHz.

Reso



▶ **Set the resonance amount with the Reso knob.**
The resonance parameter amplifies the frequencies at, and around the cutoff/center frequency.

Env



▶ **With the Env knob you set how much you want the Filter Envelope (see below) to affect the Cutoff frequency.**
Range: 0% to 100%.

Filter Envelope



The standard ADSR type envelope controls the filter cutoff frequency modulation over time. The ADSR envelope characteristics are described in detail in "Amp Envelope".

Vel




- **Turn the Vel knob to set how much the cutoff/center frequency should be modulated by Keyboard Velocity.**
  Range: 0% to 100%.

Kbd



- **Turn the KBD (Keyboard Track) knob to set how much the cutoff/center frequency should track incoming MIDI Notes.**
  Range: 0% (no tracking (constant frequency)) to 100% (1 semitone per key).

The Amp section




Vel




- **Turn the Vel knob to set how much the amplitude should be modulated by Keyboard Velocity.**
  Range: 0% to 100%.

Amp Envelope



The Amp Envelope is a standard ADSR envelope which controls the amplitude of the signal over time. The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

- **A(ttack)**
  When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the Master Volume knob. How long this should take, depends on the Attack setting. If the Attack is set to "0", the Volume value is reached instantly. If the Attack value is raised, it will take longer time before the Master Volume value is reached.
- **D(ecay)**
  After the Master Volume value has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

  If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.
- **S(ustain)**
  The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

  If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").


  But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Volume value, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Master Volume value. Note that Sustain represents a level, whereas the other envelope parameters represent times.
- **R(elease)**
  The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

The Delay section



This is a stereo delay which affects all voices globally.

Delay On/Off



- **Click the On/Off LED button to switch on/off the Delay section.**

Time



- **Set the time between the delay repeats.**
  If Sync is active (see below), the Time parameter controls the time divisions.

Feedback



- **Set the number of delay repeats with the Feedback knob.**

Sync



- **Click the Sync button to sync the delay time to the main sequencer Tempo.**
  When active, the Time knob (see above) controls the time divisions.

Ping Pong



- **Activate this to get the delay repeats alternating between the left and right channels.**
  Note that this also doubles the delay tempo.

Damp



- **Raise the Damp value to gradually cut off the high frequencies of the delay repeats.**

Amount



- **Set the delay amount with the Amount knob.**
  Note that the Delay effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a delay effect if you turn up the Amount afterwards (depending on the Feedback setting, see "Feedback").

The Reverb section



This is a stereo reverb which affects all voices globally.

Reverb On/Off



- **Click the On/Off LED button to switch on/off the Reverb section.**

Time



▶ **Set the reverberation duration time.**
In practice this sets the "size" of the reverberation "chamber/room/hall".

Pre-Delay



▶ **Set the pre-delay time of the reverb.**
Range: 0-200 ms.

Hi Damp




▶ **Raise the Hi Damp value to cut off the high frequencies of the reverb and thereby create a smoother, warmer effect.**

Lo Damp




▶ **Raise the Lo Damp value to cut off the low frequencies of the reverb signal, to make the reverb effect less "muddy".**

Amount



▶ **Set the reverb amount with the Amount knob.**
Note that the Reverb effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a reverb effect if you turn up the Amount afterwards (depending on the Time setting, see "Time").

Connections



! **Remember that CV connections are NOT stored in the Humana patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Humana from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

Modulation Inputs

These control voltage (CV) inputs can be used for modulating the Filter Cutoff and Resonance parameters, as well as the Master Volume level.

Audio Out

These are the main audio outputs. When you create a new Humana device, these outputs are auto-routed to the first available Mix Channel in the Reason main mixer. If there is no Mix Channel available, a new one will be automatically created.

Chapter 32
ID8 Instrument Device

Introduction



The ID8 Instrument device is a synth module packed with great sounds - ideal for quickly creating nice complete arrangements. The sounds have been extracted from various Reason devices and ReFills to guarantee supreme audio quality.

The Sounds

The ID8 contains 36 presets divided into nine categories, with four sounds in each category. The categories are these:

- **Piano**
  The Piano category features a grand piano, an upright piano, a dance oriented piano sound and vibes.
- **Electric Piano**
  The Electric Piano category holds two classic electric piano sounds plus a digital FM type piano and a Clav.
- **Organ**
  The Organ category contains two classic tone-wheel organ sounds, one transistor organ sound and a pump organ.
- **Guitar**
  The Guitar category sports an acoustic steel string guitar, a clean electric guitar, a half-acoustic jazz guitar and a dulcimer.
- **Bass**
  The Bass category features one fingered and one picked electric bass, an acoustic upright bass and a synth bass.
- **Strings**
  The Strings category holds orchestral strings, arco strings, a small string section and a choir sound.
- **Brass-Wind**
  The Brass-Wind category features Fat Brass, Brass Section, French Horns and Flute.
- **Synth**
  The Synth category contains two classic monophonic synth lead sounds and two characteristic polyphonic pad sounds, one with fast attack and one with slow.
- **Drums**
  The Drums category sports four extensive combinations of drums and percussion instruments aimed at different musical styles. Each "drum kit" contains between 53 and 65 different instruments, so there is plenty to choose from!

See "Velocity mapping" for information about the velocity mapping of some of the sounds.

The ID8 and Standard MIDI Files

The ID8 device is used by default when you're loading a Standard MIDI File into the Reason sequencer. For every MIDI track in the imported file, you will get an ID8 device loaded with a sound that resembles the original sound. This serves as a starting point to be able to play back the imported MIDI file. However, you could of course change sound, or replace the ID8 with another instrument device afterwards.

Using the ID8

Selecting Sounds


- **Select Category by clicking the Up/Down buttons to the left of the Display.**



- **Select Sound in the selected Category by clicking on any of the A-D buttons, or by clicking on the Sound name in the Display.**



- **Click on the Category name in the ID8 Display to bring up a pop-up where you can select Category or replace the ID8 device with another device.**



At the bottom of the pop-up, you can also choose “Browse Instruments...”. Selecting this allows you to replace the ID8 device with another instrument device and load a new sound in that device.

Controlling Sounds

Parameter knobs



Each of the Sounds in the ID8 have two preset parameters assigned to the Parameter 1 and 2 knobs. The parameter names are shown in the small displays to the right of the corresponding knobs, and are different depending on the selected Sound.

Pitch Bend and Mod Wheel



To the left on the ID8 front panel are the standard Pitch Bend and Mod Wheel. The Pitch Bend range is +/- 2 semitones and is the same for all sounds. The Mod Wheel is assigned a little differently depending on the selected Sound, but usually controls vibrato. In the Drums Category, however, the Mod Wheel has no effect, except on the Electronic Drums where it controls the cutoff frequency of a lowpass filter.

Performance Controllers

The sounds in the ID8 also respond to the standard Performance controllers "Sustain Pedal", "Aftertouch", "Expression" and "Breath Control". The parameter assignments can be a little different depending on selected sound. However, "Sustain Pedal" always controls sustain and "Expression" always controls volume.

Velocity mapping

A lot of the sounds in the ID8 are multi-sampled. They also have several velocity layers to faithfully reproduce the original instruments. Some of the sounds also use different types of samples for the highest velocity layer. This means that instead of just sounding louder, they will also sound different. For example, the Jazz Semi Guitar as well as the Finger, Pick and Upright basses have glissando or sliding notes in the highest velocity layer. The Arco Strings have pizzicato (picked) notes in the top velocity layer.

About saving edited Sounds

Since the ID8 is designed as a "preset" sound module, there is no dedicated function for saving edited Sounds. However, any edits you have made of the parameters in a Sound are automatically stored with the song (document) when you save the song.

- ▶ **You could also include one or several ID8 Instrument devices in a Combinator device and save the Combinator patch. Doing so will automatically store the settings of the ID8 Parameters in the Combinator patch. See "The Combinator" for more details.**

Chapter 33
Klang
Tuned Percussion



Introduction



The Klang Tuned Percussion instrument features an assortment of high-quality multi-sampled tuned percussion instruments - perfect for any music style. Each of the multi-sampled instruments can also be tailored and processed in the high-quality filter, amp, delay and reverb sections.

Panel overview

The Klang front panel contains the following sections:




The Klang front panel sections.

- **1. Patch Selector (for browsing, loading and saving patches).**
- **2. Master Volume.**
- **3. Global performance and "play" controls.**
- **4. Instruments section.**
- **5. Filter section.**
- **6. Amp Envelope section.**
- **7. Delay effect section.**
- **8. Reverb effect section.**

Using Klang

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global performance and "play" controls



Note

The Note LED lights up each time Klang receives a MIDI Note On.

Range

- ▶ **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
  Range: +/-12 semitones (+/-1 octave) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Klang also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "Range" control to the right of the Mod wheel.

Mod

The Mod wheel can be used for controlling the three predefined parameters to the right of the Mod wheel:

- **S. Start**
  Here you set how/if the Mod wheel should affect the Sample Start position of the currently selected instrument. The parameter is bi-polar, with zero modulation at the 12 o'clock position. A negative value moves the sample start back and a positive value moves it forward.

! **Note that if the S.Start parameter in the Instruments section (see "S. Start (Sample Start)") is at 0 ms, the sample start cannot be moved back any further. Similarly, if the S.Start parameter in the Instruments section is at 150 ms, the sample start cannot be moved forward any further.**

- **F. Freq**
  Here you set how/if the Mod wheel should affect the Filter Cutoff parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.

! **Note that if the Cutoff parameter in the Filter section (see "Cutoff") is at 20 Hz, the frequency cannot be lowered any further. Similarly, if the Cutoff parameter in the Filter section is at 25 kHz, the frequency cannot be raised any further.**

- **Level**
  Here you set how/if the Mod wheel should affect the Master Volume parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.

! **The volume can never be modulated louder than the maximum +12 dB limit of the Master Volume control.**

Panel controls

The Instruments section



Instrument selector




▶ **Click the Instrument name selector to bring up a menu of the available instruments - and then select the desired instrument from the menu.**
Alternatively, click and drag up/down in the display above the selector to scroll through the instruments.

! **Depending on the instrument size (in MB), it could take a short moment before the entire instrument is loaded into RAM.**

! **Also note that the note ranges of the instruments extend outside their "natural" ranges, which could produce nice artificial effects.**

The available instruments are:

- **Alto Glockenspiel**



The Alto Glockenspiel was played with hard mallets and was recorded with close mics (stereo) in a large hall, slightly wet. The samples were taken from Soundiron's Alto Glockenspiel library.

- **Bamblong**



This instrument is also known as a bamboo log drum, from Indonesia. It was played with rubber mallets and was recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Bamblong library.

- **Circle Bells Mallet**



This instruments is also known as Blossom Bells. It was played with rubber mallets and was recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Circle Bells library.

- **Cylindrum**



This is an experimental instrument built from large diameter plastic piping, also known as a tubulum. It was played with rubber paddle mallets and was recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Cylindrum library.

- **Imbibaphones**




These are wine glasses played with rubber mallets. They were recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's "Imbibaphones" library.

- **Kalimba**



The Kalimba is also known as an mbira or thumb piano, from Africa. It was recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Kalimba library.

- **Music Box**



This is a music box recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Musique Box library.

- **Noah Bells**



The Noah Bells from India are played with the fingertips and were recorded with close mics (stereo) in a large hall, slightly wet. The samples were taken from Soundiron's Noah Bells library.

- **Steel Tones**



This instrument is also known as a hank drum or propane drum. It was played with felt mallets and was recorded with close mics (stereo) in a room, dry. The samples were taken from Soundiron's Steel Tones library.

- **Whale Drum**



The whale drum is a wooden box slit drum from Africa. It was played with rubber mallets and was recorded with close mics (stereo) in a studio, dry. The samples were taken from Soundiron's Whale Drum library.

S. Start (Sample Start)



▶ **Turn the S.Start knob to set where in the sample the playback should start.**
Note that the effect could be different depending on the selected instrument.

Oct



▶ **Set the octave transposition for the instrument.**
Range: 5 (+/-2) octaves.

! **Note that the note ranges of the instruments can be transposed far outside their "natural" ranges, which could produce nice artificial effects.**

Semi



▶ **Set the pitch in semitone steps.**
Range: +/-12 semitones (two octaves).

Fine




▶ **Set the pitch in steps of 1 cent.**
Range: +/- 50 cents (down or up half a semitone).

The Filter section




Filter On/Off



▶ **Click the On/Off LED button to switch on/off the Filter section.**

Filter Type selector



▶ **Click and drag up/down on the Filter Type selector to select one of the available filter types - or step through the filter types by clicking the Up/Down arrow buttons.**
The available filter types are:

- **LP**
  This is a lowpass filter with 12db/octave slope.
- **HP**
  This is a highpass filter with 12db/octave slope.
- **BP**
  This is a bandpass filter with 6db/octave slopes.
- **Comb**
  This is a comb filter for phaser/flanger type of effects.

Cutoff



▶ **Set the cutoff/center frequency with the Cutoff knob.**
The cutoff parameter sets where in the frequency range you want the resonance and attenuation to appear.
Range: 20 Hz to 25 kHz.

Reso



▶ **Set the resonance amount with the Reso knob.**
The resonance parameter amplifies the frequencies at, and around the cutoff/center frequency.

Env



▶ **With the Env knob you set how much you want the Filter Envelope (see below) to affect the Cutoff frequency.**
Range: 0% to 100%.

Filter Envelope



The standard ADSR type envelope controls the filter cutoff frequency modulation over time. The ADSR envelope characteristics are described in detail in "Amp Envelope".

Vel



▶ **Turn the Vel knob to set how much the cutoff/center frequency should be modulated by Keyboard Velocity.**
Range: 0% to 100%.

Kbd



▶ **Turn the KBD (Keyboard Track) knob to set how much the cutoff/center frequency should track incoming MIDI Notes.**
Range: 0% (no tracking (constant frequency)) to 100% (1 semitone per key).

The Amp section



Vel




- **Turn the Vel knob to set how much the amplitude should be modulated by Keyboard Velocity.**
  Range: 0% to 100%.

Amp Envelope



The Amp Envelope is a standard ADSR envelope which controls the amplitude of the signal over time. The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

- **A(ttack)**
  When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the Master Volume knob. How long this should take, depends on the Attack setting. If the Attack is set to "0", the Volume value is reached instantly. If the Attack value is raised, it will take longer time before the Master Volume value is reached.

- **D(ecay)**
  After the Master Volume value has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

  If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to “0”, the Decay parameter should be set to a medium value and the Sustain level should be set to “0”, so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.
- **S(ustain)**
  The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

  If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack “0”) and stays there (Decay “0”), until the key is released and the sound instantly stops (Release “0”).


  But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Volume value, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Master Volume value. Note that Sustain represents a level, whereas the other envelope parameters represent times.
- **R(elease)**
  The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

The Delay section



This is a stereo delay which affects all voices globally.

Delay On/Off



▶ **Click the On/Off LED button to switch on/off the Delay section.**

Time



▶ **Set the time between the delay repeats.**
If Sync is active (see below), the Time parameter controls the time divisions.

Feedback



▶ **Set the number of delay repeats with the Feedback knob.**

Sync



▶ **Click the Sync button to sync the delay time to the main sequencer Tempo.**
When active, the Time knob (see above) controls the time divisions.

Ping Pong



▶ **Activate this to get the delay repeats alternating between the left and right channels.**
Note that this also doubles the delay tempo.

Damp



▶ **Raise the Damp value to gradually cut off the high frequencies of the delay repeats.**

Amount




▶ **Set the delay amount with the Amount knob.**
Note that the Delay effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a delay effect if you turn up the Amount afterwards (depending on the Feedback setting, see "Feedback").

The Reverb section



This is a stereo reverb which affects all voices globally.

Reverb On/Off



- **Click the On/Off LED button to switch on/off the Reverb section.**

Time



- **Set the reverberation duration time.**
  In practice this sets the “size” of the reverberation “chamber/room/hall”.

Pre-Delay



- **Set the pre-delay time of the reverb.**
  Range: 0-200 ms.

Hi Damp



- **Raise the Hi Damp value to cut off the high frequencies of the reverb and thereby create a smoother, warmer effect.**

Lo Damp



▶ **Raise the Lo Damp value to cut off the low frequencies of the reverb signal, to make the reverb effect less "muddy".**

Amount



▶ **Set the reverb amount with the Amount knob.**
Note that the Reverb effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a reverb effect if you turn up the Amount afterwards (depending on the Time setting, see "Time").

Connections



! **Remember that CV connections are NOT stored in the Klang patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Klang from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

Modulation Inputs

These control voltage (CV) inputs can be used for modulating the Filter Cutoff and Resonance parameters, as well as the Master Volume level.

Audio Out

These are the main audio outputs. When you create a new Klang device, these outputs are auto-routed to the first available Mix Channel in the Reason main mixer. If there is no Mix Channel available, a new one will be automatically created.

Chapter 34
Kong Drum Designer




Introduction

The Kong Drum Designer gives the visual impression of a pattern-based drum machine, like the legendary MPC units. Indeed, it does have a matrix of 4 x 4 pads that are used for playing the sounds, just like the aforementioned classics. There are significant differences, however.

Kong features 16 drum "sound channels" that can host one drum sound each. Each drum sound can consist of a sound module routed through various types of FX and processing modules, allowing for completely open-ended sound design possibilities. Individual drum sounds can be saved as Drum Patches and complete drum kits can be saved as Kit Patches, allowing you to mix and match drum sounds and make up custom kits with ease.

In addition, Kong also has sampling capability. This means that you can sample your own sounds straight into any of the 16 drum channels with just a click of a button!

Overview



The Kong front panel.

Kong is an advanced drum sound synthesizer, sampler/sample player and REX loop/slice player with many unique features. The design could be described as semi-modular, in that the sound, FX and audio processing modules are open slots that allows you to select between an array of different sound generators, FXs and audio processor types.

As a result, Kong is capable of producing an astounding array of drum and percussion sounds - or any type of sound, for that matter. While it offers a lot of scope for serious sound design, it still has a straight-forward and user-friendly interface.

Kong also features audio inputs on the back panel. By connecting the output of another device to these inputs, you can use Kong's audio processing modules to process external sound. You can also route drum sounds for audio processing in external devices.

The Pad Section

The pad section features 16 pads. Each of these pads can be assigned to a separate Drum sound. You can also choose to assign several pads to one and the same Drum sound - or to link pads so that one pad will trigger several other pads as well. To the right of the pads is the Pad Settings area where you can control the pad assignments and behavior. See "Pad Settings".

The Drum Control Panel

The Drum Control Panel at the bottom left of the panel shows the name and "macro parameter" settings for the selected pad in the pad section. From the Drum Control Panel you can also load and save Drum Patches as well as initiate sampling. See "The Drum Control Panel".

The Drum and FX Section

By clicking the Programmer button below at the bottom of the Drum Control Panel you can bring up the Drum and FX Section. Here is where you can edit your drum sounds and combine with various types of sound processors and FX. See "The Drum and FX section".

About using custom backdrops

As with the Combinator device, it is possible to customize the Kong front panel graphics with a user-designed skin. In the Reason Download section at the Reason Studios website is the "Combi and Kong Backdrop Templates" zip file, which can be used as starting point for designing your own Kong panel graphics. See the "Read Me.txt" file in the Backdrops folder for more details. Note that you should use separate backdrops for folded vs. unfolded states.

About file formats

Kong can read the following file types:

Kit Patches

A Kong Kit Patch (Windows extension ".kong") contains all settings for all 16 Drum sound channels, including file references to any used drum samples (but not the actual samples themselves). Switching patches is the same as selecting a new drum kit.

Drum Patches

A Kong Drum Patch (Windows extension ".drum") contains all settings for the selected Drum sound channel, including file references to any used drum samples (but not the actual samples themselves). Switching Drum Patches is the same as selecting a new drum sound.

Drum Samples

The audio file format support differs depending on which computer OS you are using.

The NN-Nano Sampler module in Kong can read and play back sample files of the following formats:

- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFonts (.sf2)**
  SoundFonts are an open standard for wavetable synthesized audio, developed by E-mu systems and Creative Technologies.
- **REX file slices (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). The NN-Nano lets you load separate slices from REX files as individual samples.

- **Any sample rate and practically any bit depth.**

See "NN-Nano Sampler" for details.

REX Files

The Nurse Rex Loop Player module in Kong can read and play back files of the following formats:

- **REX files (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop").

See "Nurse Rex Loop Player" for details.

Using patches

When you create a new Kong device it is loaded with a default kit. If you like you can use the default kit - or you can load another Kong Kit patch (or create one from scratch, by loading individual Drum patches). A Kong Kit patch contains settings for the 16 Drum channels, complete with parameter settings and file references to any samples used.

Loading a Kit Patch

To load a patch, use one of the following methods:

- **Use the browser to locate and open the desired patch.**
  To open the browser, select "Browse Kong Patches" from the Edit menu or device context menu, or click the folder button in the patch section on the device panel.



- **Once you have selected a patch, you can step between all the patches in the same folder by using the arrow buttons next to the patch name display.**
- **If you click and hold on the patch name display on the device panel, a pop-up menu will appear, listing all Kong Kit patches in all currently expanded folders in the Patch Browser.**
  This allows you to quickly select another patch without having to step through each one in turn.
- **Use the drag and drop method to drag Kong Kit Patch files from the Browser and drop on the Kong panel.**
  The Kong panel is dimmed in orange and a Patch Replace symbol appears in the center.


Checking the sounds in a Kit Patch

There are three ways you can listen to the sounds in a patch without using the main sequencer:

- **By clicking the Pad buttons on the front panel.**




! **Note that the vertical click position on the pad determines the Velocity value. If you click towards the bottom of a pad, the velocity is low and at the top of each pad the velocity value is high.**



This will give you a good idea about the dynamics behavior of each drum sound. This also allows you to record in the main sequencer using the full dynamic range of each drum sound, even without a connected MIDI keyboard/control surface.

- **By playing the keys C1 to D#2 or C3 to B6 on your MIDI keyboard or on the On-screen Piano Keyboard.**



In the C1-D#2 range, each MIDI note will trigger one pad each, from Pad 1 to Pad 16. In the C3-B6 MIDI note range each pad can be triggered from three adjacent keys on your MIDI keyboard. C3-D3 trigs Pad 1, D#3-F3 trigs Pad 2 and so on. The C3-B6 note range is perfect if you want to play fast passages by triggering the same pad from several keys on your MIDI keyboard.

Creating a new Kit Patch

To create a patch of your own (or modify an existing patch), use the following basic steps:

1. **Click on the pad for the drum sound you want to load or replace.**
   A blue frame surrounds the selected pad.



2. **Click the folder button on the Drum Control Panel.**



- **Alternatively, right-click (Win) or [Ctrl]-click (Mac) on the Pad and select "Browse Drum Patches..." from the context menu.**
  The Patch Browser opens.

3. **Locate and open a Kong Drum Patch (extension '.drum') or a sample or REX file.**
   You will find a selection of Kong Drum Patches in the Factory Sound Bank (in the Kong Drum Patches folder).

   Loading a sample will automatically open it in an NN-Nano Sampler module (see "NN-Nano Sampler") and loading a REX file will automatically open it in a Nurse Rex Loop Player module (see "Nurse Rex Loop Player").

   You can also sample your own sound into a Drum, see "Sampling in Kong".

- **Alternatively, drag a Kong Drum Patch file, a REX file, a sample or a REX slice from the Browser and drop on the Drum Control Panel - or on any desired drum pad.**
  Depending on if you drop a Drum Patch file, a REX file or a sample/REX slice, the Drum Control Panel or pad is dimmed in orange or blue and a Patch/Sample Replace symbol appears in the center.

! **It is important that you drop REX files either on the Drum Control Panel or on a pad. Dropping it elsewhere will replace the entire Kong device with a Dr. Octo Rex device and load the REX file in this device instead!**

4. **Change some parameter settings for the drum sound channel using the knobs on the Drum Control Panel.**
   These parameters are described in "The Drum Control Panel". Note that the Drum Control Panel parameters are "global" for each Drum channel. Each drum sound can consist of a number of different sound and FX modules, each with their separate set of parameters. Refer to "The Drum modules", "The Support Generator modules" and "The FX modules" for details about all the modules that can be used to build up a complete Drum sound.

5. **Repeat steps 1 and 4 for the other drum sound channels.**

6. **When you're satisfied with the drum kit, you can save the patch by clicking the Floppy Disk button in the patch section on the Drum panel.**
   Note however, that you don't necessarily need to save the Drum patch - all settings are included when you save a Kong Kit Patch (see "Saving Kit Patches") and/or your song.

Creating an empty Kit Patch

To "initialize" the settings in the Kong, select "Reset Device" from the Edit menu or the device context menu. This removes all samples for all drum sound channels, and sets all parameters to their default values.

Saving Kit Patches

Saving patches is done in the same way as with any other Reason device - see "Loading patches" and "Saving patches".

! **Note that you don't have to save any of the 16 individual Drum patches first if you don't want to - all settings for each individual Drum patch are included in the Kong Kit patch.**


Pad Settings

In the Pad Settings section to the right of the Pad section you can perform various assignments and tricks pertaining to how the Drum channels should be controlled from the Pads.


Assigning Drums to Pads

Kong features 16 pads and 16 Drum channels, as described earlier. Each pad can control a separate Drum sound channel. You can also assign several pads to control a single Drum sound channel. This is especially useful if you want to apply different settings, like Hit Types (see "Assigning Hit Type to Pads"), for each pad so that the controlled Drum sound channel responds differently. By default the 16 pads are assigned to their corresponding Drum sound channel; Pad 1 to Drum 1 and so on. If you want to change this assignment, proceed as follows:

1. **Select the desired Drum sound channel by clicking on its corresponding pad - or on the Pad name below the pad if you don't want the pad to trigger the sound.**
   A blue frame surrounds the selected pad and the corresponding Drum is displayed in the Drum section to the left.



2. **Select the other pad you want to control Drum 1 from.**
   In this example, we select Pad 2.



3. **Click on button 1 in the Drum Assignment section to assign Pad 2 to Drum 1.**




   Now, Pad 2 is also assigned to play Drum 1. Below Pad 2 it now says "Drum 1" to indicate the current assignment.

Assigning Drums to Pads using the Quick Edit function

If you want to assign several Drums to several pads quickly, you can do this by using the Quick Edit function.

1. **Click the Quick Edit button in the Drum Assign section.**



   Each Pad now shows the current Drum assignment.

2. **Change the Drum assignment clicking on the desired Drum channel number on each Pad.**
3. **When you are done, click the Quick Edit button or press [Esc] to exit to normal mode.**

Renaming Pads

- **Double click on the Pad name below the corresponding Pad, enter a new name and press [Enter].**

Copying & Pasting Drums between Pads


It's possible to copy a Pad with an assigned Drum and paste into another Pad location:

1. **Select the source Pad.**
2. **Press [Ctrl](Win)/[Cmd](Mac)+[C].**
   Alternatively, select "Copy Drum Patch" from the Edit menu or context menu.
3. **Select the destination Pad.**
4. **Press [Ctrl](Win)/[Cmd](Mac)+[V].**
   Alternatively, select "Paste Drum Patch" from the Edit menu or context menu.

Now, the complete Drum patch has been duplicated to the destination Pad and you can begin editing it as a separate patch.

Assigning Hit Type to Pads

If you have assigned several pads to the same Drum sound channel, you can choose a different Hit Type for each of the pads (where applicable). Depending on Drum sound type, some of the sounds can have up to four pre-defined Hit Types. These Hit Types are shown in the Hit Type display.




For example, a Synth Hi-Hat Drum sound has four Hit Types by default: "Closed", "Semi-Closed", "Semi-Open" and "Open". By selecting a different Hit Type for each of the pads assigned to the same Drum, you can create a very nice and "live" sound.

- **To assign a Hit Type to a pad, select the pad and then select Hit Type by clicking the Hit Type button (or on the name in the display).**
  The Hit Type assignment is saved when you save your Kong Kit Patch and/or song.

Assigning Hit Type to Pads using the Quick Edit function

A quicker way of assigning Hit Type to several pads is by using the Quick Edit function.

1. **Click the Quick Edit button in the Hit Type section.**



   Each Pad now shows the current Hit Type assignment.

2. **Change the Hit Type assignment clicking on the desired Hit Type number on each Pad.**
3. **When you are done, click the Quick Edit button or press [Esc] to exit.**

Muting and Soloing Pads



- **Click the Mute button to mute the assigned Drum for the selected Pad.**
  This will also mute MIDI control of the assigned Drum. Muted pads are displayed in red color.
- **Click the Solo button to solo the assigned Drum for the selected Pad.**
  Soloed pads are displayed in green color. All other pads are automatically muted. This also affects MIDI control of the Drum channels.
- **Click the CLR button to remove all Mute and Solo assignments.**

Muting and Soloing Pads using the Quick Edit function

A quicker way muting and soloing several pads is by using the Quick Edit function.


1. **Click the Quick Edit button at the top of the Pad Settings section.**



   Each Pad will now show a Mute and Solo button.

2. **Click the Mute and/or Solo buttons on the desired Pads.**
3. **When you are done, click the Quick Edit button to exit.**

Working with Pad Groups



Kong features 9 Pad Groups, divided into 3 Mute Groups, 3 Link Groups and 3 Alt Groups. Each Pad can be assigned to one or more of these 9 Pad Groups independently. Pad Groups are useful if you, for example, want to trigger several pads from a single pad, have one pad mute another, or randomly trigger other pads from one pad.

Mute Groups

Mute Groups can be used if you want one pad to automatically mute another sound in the same Mute Group. For example, if you assign an open hi-hat and a closed hi-hat sound to the same Mute Group, playing on one pad will automatically mute the sound assigned to the other pad.

Link Groups

Pads assigned to the same Link Group will play together when you trigger any of the pads in that group.


Alt Groups

If you play pads assigned to the same Alt Group, the pads will be triggered in a random fashion, one by one. It doesn't matter which pad you play in the group, the pad triggering is always random.

Assigning Pads to Pads Groups using the Quick Edit function

A quicker way of assigning several pads to Pad Groups is by using the Quick Edit function.

1. **Click the Quick Edit button in the Pad Group section.**



   Each Pad now shows the current Pad Group assignment.

2. **Edit the Pad Group assignment by clicking on the desired Pad Group letter on each Pad.**



   In the picture above, Pads 9 and 10 are assigned to Alt Group "G", which means they will trigger alternating when you play any of these Pads.

   Pads 11 and 12 are assigned to Mute Group "B", which means that playing Pad 11 will mute Pad 12 and vice versa.

3. **When you are done, click the Quick Edit button or press [Esc] to exit.**

The Drum and FX section



The Drum and FX section in Kong is built up of the Drum Control Panel and the Drum and FX section.

- ▶ **Click the Show Drum and FX button below the Drum Control Panel to unfold the Drum and FX section.**
  The Drum and FX section consists of five slots:

- **The Drum Module Slot.**
- **The FX1 Slot.**
- **The FX2 Slot.**
- **The Bus FX Slot.**
- **The Master FX Slot.**

The Drum, FX1 and FX2 slots are unique to each of the 16 Drum channels in Kong. The Bus FX and Master FX slots are shared between all Drum channels in the Kong device. You can activate/deactivate any of the slots by clicking the On button at the upper left of each slot.

Signal flow

The output signal from a Drum module is sent via the FX1 and FX2 Slots to the Bus FX, Master FX or to a pair of the individual outputs on the back of the Kong panel. There is also an internal Bus FX Send that can be used to send an audio signal from the Drum via the FX1 and FX2 Slots to the Bus FX. The Bus FX Slot can the hold e.g. a reverb module which can be used a send effect for all the Drum channels. As an extra bonus, you can also hook up an external effect device between the Bus FX and Master FX Slots, see "Using external effects with Kong".


The signal routing in the Drum and FX section depends on the Drum Output selector setting at the bottom of the Drum and FX section:



The different signals flows are described in the following paragraphs:

Master FX Drum Output


When the Drum Output is set to "Master FX", the signal flow is according to the picture below. If you are using a Bus FX, this is treated as a Send effect with the Bus FX level controlled by the Bus FX knob on the Drum Control Panel.



Signal flow when Drum Output is set to "Master FX".

Bus FX Drum Output


When the Drum Output is set to “Bus FX”, the signal flow is according to the picture below. Note that the Bus FX is now routed both as an Insert effect and as a Send effect at the same time. Therefore, it might be a good idea to set the Bus FX Send knob on the Drum Control Panel to zero in this configuration.



Signal flow when Drum Output is set to “Bus FX”.

Separate Out Drum Output

When the Drum Output is set to any of the separate output pairs “3-4” to “15-16”, the signal flow is according to the picture below. The signals to the selected separate output pair are taken directly after the FX2 via the Master Level knob. Note that the signal via the Bus FX and Master FX is still available on the Main Out L & R and can be controlled with the Bus FX Send knob on the Drum Control Panel.



Signal flow when Drum Output is set to any of the separate output pairs “3-4” to “15-16”.

The Drum Control Panel



The Drum Control Panel features a set of “macro controls” that affect parameters in each Drum. These controls scale the parameters in the Drum module and FX modules in the Drum and FX section. There are also some standard parameters that are identical for each Drum: Pan, Tone and Level.

- **The Pitch Offset knob affects the Pitch parameters in all Drum modules.**
  No FX modules are affected, even if they feature a Pitch parameter.

- **The Decay Offset knob affects the amplitude Decay or Release parameters in all Drum modules plus any FX modules that feature a Decay parameter.**
  For example, the reverb decay time in the Room Reverb FX module is affected by the Decay Offset parameter.
- **The Bus FX Send knob affects the signal level sent to the Bus FX Slot.**
  Depending on current Drum Output setting, the effect will be a little different - see the examples in "Signal flow".
- **The Aux 1 and Aux 2 Send knobs controls the level to any devices connected to the Aux 1 and Aux 2 Send Outputs on the back of the panel, see "Aux Send Out".**
  The signals to the Aux Send is tapped after the FX1 and FX2 Slots but before the Bus FX and Master FX Slots.
- **The Pan parameter controls the panning of the signal in the stereo panorama.**
  The Pan parameter affects the signal after the FX1 and FX2 Slots but before it is sent to the Bus FX and Master FX Slots.
- **The Tone parameter is a built-in filter (similar to the filter in Redrum).**
  The Tone parameter affects the signal after the FX1 and FX2 Slots but before it is sent to the Bus FX and Master FX Slots.

Editing the Drum Control Panel parameters using the Quick Edit function

A quicker way of editing the Drum Control Panel parameters for several Drum channels at once is by using the Quick Edit function. The Drum Control Panel features four Quick Edit buttons.

1. **Click the Quick Edit button below the Pitch and Decay Offset section.**



   Each Pad now shows the current Pitch and Decay Offset settings for each assigned Drum channel.

2. **Edit the Pitch and Decay Offsets by clicking and dragging the "crosshair" on the desired Pads.**



   The Decay Offset is on the horizontal X-axis and the Pitch Offset is on the vertical Y-axis, as shown in plain text on the big red frame around the Pad section. As you move the crosshair, the corresponding knobs on the Drum Control Panel move as well - and vice versa.

3. **When you are done, click the Quick Edit button or press [Esc] to exit - or click another Quick Edit button to change other sets of parameters.**

Loading and Saving Drum Patches



Loading and Saving Kong Drum patches (".drum") are done in the same way as with any other Reason device - see "Creating a new Kit Patch", "Loading patches" and "Saving patches".

A Kong Drum patch contains all parameter settings on the Drum Control Panel, including modules and parameter settings in the Drums and FX section - with references to any used samples.

It's also possible to load samples and REX loops in the Drum Control Panel section. Loading a sample will automatically open it in an NN-Nano Sampler module (see "NN-Nano Sampler") and loading a REX file will automatically open it in a Nurse Rex Loop Player module (see "Nurse Rex Loop Player").

Sampling in Kong

The sampling procedure is the same for all devices that can sample (Kong, NN-19, NN-XT and Redrum). The sampling and sample editing procedures are described in detail in the "Sampling" chapter.

- **To sample your own sound and automatically load it into an NN-Nano Sampler module in the Drum and FX section, click the Sample button for the desired Drum channel.**



Refer to the "Sampling" chapter for details on how to set up and use the sampling feature.

The Drum Module slot



Each Drum channel in Kong has a main module slot - the Drum Module slot - to which you can load one of 9 different types of drum sound modules for designing drum sounds.

▶ **Select Drum Module type by clicking the button to the right of the On button and selecting the module from the pop-up.**
the following Drum Module types can be selected: NN-Nano Sampler, Nurse Rex Loop Player, Physical Bass Drum, Physical Snare Drum, Physical Tom Tom, Synth Bass Drum, Synth Snare Drum, Synth Tom Tom and Synth Hi-Hat. See "The Drum modules" for details about each Drum module.

! **Note that only four pre-defined parameters per Drum Module can be automated!**

At the bottom below the Drum Slot is the Pitch Bend Range parameter which controls the Pitch Bend Range for the Drum Slot. This parameter is global for all types of Drum Modules but is unique to each of the 16 Drum channels.



The Pitch Bend Range knob for each of the 16 Drum channels

The FX slots



Each Drum channel also has 2 insert effect slots - the FX 1 and FX 2 Slots - to which you can load one of two different types of support sound generators or one of 9 different effect modules.

▶ **Select Module type by clicking the button to the right of the On button and selecting module from the pop-up.**
the following module types can be selected for the FX 1 and FX 2 Slots: Noise generator, Tone generator, Room Reverb, Transient Shaper, Compressor, Filter, Parametric EQ, Ring Modulator, Rattler, Tape Echo and Overdrive/Resonator. See "The Support Generator modules" and "The FX modules" for details about each module type.

! **Note that only two pre-defined parameters per FX/Support Generator Module can be automated!**

▪ **For the Bus FX and Master FX slots, all module types except the Noise and Tone generators can be selected.**

The Drum modules

! **Note that only four pre-defined parameters per Drum Module can be automated!**

NN-Nano Sampler



The NN-Nano Sampler is based on the NN-XT Sampler and was designed to be ideal for drums and percussion sounds.


The NN-Nano can handle samples or sets of samples for each of the four different Hit Types described in "Assigning Hit Type to Pads". Each Hit Type can contain one or several samples which can be layered and/or altered and controlled individually via velocity.

Loading samples

1. **Select the Hit you want to load the sample(s) into by clicking in the display.**



2. **Click the Browse Samples (folder) button and select one or several WAV, AIFF or SoundFont Samples or REX slice files.**
3. **Click the Load button in the Browser.**
   The sample(s) are loaded in the selected Hit.




▶ **Alternatively, drag a sample, a REX slice or a SoundFont file from the Browser and drop on the NN-Nano panel.**
The NN-Nano panel is dimmed in blue and a Sample Replace symbol appears in the center.

If you selected several samples in the Browser, these will be loaded as separate Layers in the selected Hit.

If you like you can load additional samples, either into another Hit or into a new Layer in the same Hit. To load a new sample in a new Layer in the same Hit, proceed as follows:

1. **Select the Hit and then click the Add Layer button.**



An additional space is created in the Hit.

2. **Select the empty Layer in the display and load a new sample according to the description in "Loading samples" above.**

The NN-Nano Sampler module in Kong can read and play back sample files of the following formats:


- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFonts (.sf2)**
  SoundFonts are an open standard for wavetable synthesized audio, developed by E-mu systems and Creative Technologies.
- **REX file slices (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). The NN-Nano lets load separate slices from REX files as individual samples.
- **Any sample rate and practically any bit depth.**

Replacing samples

- **To replace one or several samples, select the sample(s) in the display and then load new samples according to the description in "Loading samples".**
  This way it is possible to e.g. replace three selected samples with three new samples in one go.


Adding and Removing Layers

- **To add a new Layer to a Hit, select the Hit and click the Add Layer button.**



An additional space is created in the Hit for the created Layer.

- **To remove a Layer from a Hit, select the Layer and click the Remove Layer button.**



The Layer is removed together with its sample (if any).

Sampling into the NN-Nano


The sampling procedure is generic for all devices that can sample (Kong, NN-19, NN-XT and Redrum). The sampling and sample editing procedures are described in detail in the "Sampling" chapter.

▶ **To sample your own sound and automatically load it into the NN-Nano, click the Sample button.**



Refer to the "Sampling" chapter for details on how to set up and use the sampling feature.


The Edit Sample button



If you click the Edit Sample button with a sample selected in the display, the sample will open in the generic Edit Sample window. In this window you can edit the sample and save as a self-contained Song Sample. See "The Edit Sample window" in the Sampling chapter for details about editing samples.


Sample parameters

There are a number of parameters that are unique to each individual sample and Hit in the NN-Nano. These parameters are visible in the display for the selected (highlighted) sample:



- **Velocity**
  The Velocity range can be set, either by clicking and dragging the Velocity bar sideways to the right of the sample, or by clicking and dragging the Vel Lo and Hi values vertically at the bottom of the display.
- **Level**
  Set the sample level by clicking and dragging the Level value up or down in the display.
- **Pitch**
  Set the sample pitch by clicking and dragging the Pitch value up or down in the display.
- **Alt**
  Click the Alt box for several samples in the same Hit to make them play back alternating.
- **Hit Name**
  Edit the Hit Name if you like by clicking in the Hit Name box, typing in a new name and then pressing [Enter]. The name will appear in the Hit Type display on the main panel (see "Assigning Hit Type to Pads").

! **It's also possible to select multiple samples and edit them together. If the selected samples have different Level, Velocity, Range and/or Pitch values this is indicated by an "M" (for multiple) symbol next to the parameter:**



If you change the values of any of the "M" parameters, all selected samples will get the exact same value.

Global parameters

The parameters located on the panel, outside the display, are global and affect all samples in all Hit groups equally.



- **Polyphony**
  "Full" is, as the word implies, full polyphony. This means that all Hits can sound with full polyphony. Several Hits can also sound together if controlled from separate Pads that are assigned to different Hit Types.

  "Exclusive Hits" means that when one Hit plays it will automatically mute any other sounding Hits. The polyphony is still full within each Hit, though.

  "Monophonic" is... well, monophonic.
- **Mod Wheel**
  If you want the Mod Wheel to affect the pitch and/or decay of the sound, you can set this with the Mod Wheel -> Pitch and/or the Mod Wheel -> Decay knobs. Both parameters are bipolar (+/-).
- **Velocity**
  In the Velocity section you can control how the velocity should affect a number of parameters. The parameters are: Pitch, Decay, Level, Bend and Sample Start. All parameters are bipolar (+/-).
- **Pitch**
  Here you can set the global Pitch, Pitch Bend Amount and Pitch Bend Time for all samples. The Pitch and Pitch Bend Amount parameters are bipolar (+/-).
- **Osc**
  In the Osc section you can set the global Sample Start and Reverse parameters for all samples in the NN-Nano.
- **Amp Env**
  The Amp Env section contains an Attack-Decay Envelope and the global Level parameter for all samples. There is also an envelope trigger mode selector for choosing between Gate and Trig mode. In Gate mode (the square symbol), the Decay time defines the minimum gate time. If you hold down a key or pad on your MIDI keyboard/control surface, the Decay stage will set in after you released the key/pad.

Nurse Rex Loop Player



The Nurse Rex Loop Player is based on the Dr. OctoRex Loop Player but has been modified to be ideal for playing and triggering drum and percussion sounds.

The Nurse Rex can load standard REX files and play back the loops and/or slices in a variety of ways depending on the selected Hit Type (see "Assigning Hit Type to Pads").

Loading REX files

1. **Click the Browse Samples (folder) button.**



2. **Select a REX file and click the Load button in the Browser.**


- **Alternatively, drag a REX file from the Browser and drop on the Nurse Rex panel.**
  The Nurse Rex panel is dimmed in orange and a Patch Replace symbol appears in the center.

The REX file is loaded in Nurse Rex with the loop shown in the display.

Hit Types (playback modes)

Depending on selected Hit Type, the REX loop will play back differently. The editing possibilities also differs depending on selected Hit Type for the assigned pad.


- **Loop Trig**
  In Loop Trig mode, you trigger the REX loop to play one single cycle every time you hit the assigned pad. Loop Trig can also be used together with the "Stop" mode on another pad to immediately stop the loop playback, see "Stop" below.





A REX loop with "Loop Trig" as Hit Type.


- **Set Start and End slice, either by clicking and dragging the S and E numerical values up/down in the boxes, or by clicking and dragging the handles sideways in the "ruler" above the REX loop in the display.**



Different ways of editing the Start and End Slice values.

- **Chunk Trig**
  In Chunk Trig mode, you can assign several pads to play back shorter sections - chunks - of the REX loop. The number of chunks is determined by the number of pads you have assigned to the REX loop using the Chunk Trig Hit Type. The chunks are distributed in equal sections across the REX loop. Chunk Trig can also be used together with the "Stop" mode on another pad to immediately stop the chunk playback, see "Stop" below.

  In the picture below, we have assigned four pads to the same REX loop and we have selected "Chunk Trig" as Hit Type on all four pads:




Four pads assigned to the same REX loop and Hit Type set to "Chunk Trig".

- **Set the size of the chunks by clicking and dragging the right edges of the "tabs" above the REX loop in the display.** Doing so will automatically move the start position of the subsequent chunk so that the chunks will always be adjacent to each other.



Editing the sizes of the chunks.

▶ **Change the Start position of the first chunk and the End position of the last chunk by changing the REX loop Start and End values.**
In effect, this is the same as setting the overall REX loop start and end position.




Editing the start position of the first chunk and end position of the last chunk.

- **Slice Trig**
In Slice Trig mode, you can assign a pad to play back one single slice of the REX loop - or several slices alternatingly. By default, Slice 1 of any REX loop loaded into the Nurse Rex is set to play back when you have selected "Slice Trig" as Hit Type.



A REX loop with "Slice Trig" as Hit Type.

▶ **Change the slice to play back by first removing the tick in the Trig checkbox and then clicking on another slice in the display and ticking the Trig checkbox for that slice.**



Slice 3 selected for playback in Slice Trig mode.

Another way of assigning a slice for playback, or to assign several slices to play back alternating, is by using the mouse in combination with the [Ctrl](Win)/[Cmd](Mac) key.

▶ **Hold down [Ctrl](Win)/[Cmd](Mac) and click on the slice(s) in the display you want to assign or deassign.**



Slices 3, 5, 8 and 11 selected for playback in Slice Trig mode, forcing them to play back alternating.

Selected slices are displayed with a red background. The currently "focused" slice is displayed with an orange background. Selected slices also get their corresponding Trig checkbox ticked automatically.

- **Stop**
  The fourth Hit Type is named "Stop". The Stop mode can be used if you want to use a pad for immediately stopping the currently playing REX loop or Chunk. The Stop mode should be used in combination with any of the Hit Types "Loop Trig" or "Chunk Trig", otherwise it won't be useful.



"Stop" selected as Hit Type for a pad assigned to a Nurse Rex module.

1. **Assign one pad to a REX loop in Nurse Rex and select any of the Hit Types "Loop Trig" or "Chunk Trig".**
2. **Assign another pad to the same Nurse Rex module and select "Stop" as Hit Type.**
   Now, when you play the first pad, the loop or chunk will play. Once you hit the second pad, the loop/chunk playback will immediately stop.

Combining Hit Types

By combining the different Hit Types for the Nurse Rex module you can create really interesting setups. For example, you could load a REX loop and assign a couple of pads to the "Chunk Trig" Hit Type, one pad to Loop Trig, another one to Slice Trig and another pad to Stop. Playing the different pads can now generate really inspiring results. The picture below shows an example of this type of setup:




Eight pads assigned to the same Nurse Rex module, with the pads set to different Hit Types (in Quick Edit mode).

If we click the Hit Type Quick Edit button, we can see that Pad 1 is set to Loop Trig, Pads 2-6 are set to Chunk Trig, Pad 7 is set to Slice Trig and has four slices set to Trig in the REX loop display for alternate playback. Finally Pad 8 is set to Stop so we could stop the loop and chunks playback whenever we like.

Editing Slice Parameters

In the REX loop display you can edit parameters that are unique to each separate slice:



Slices parameters for a loaded REX loop.

▶ **To select a slice for editing, click on the desired slice in the REX loop display.**
Alternatively, click and drag up/down in the Slice number box or use the Slice Select knob below the Slice item.

The Slice Parameters are:

- **Trig**
  Click the Trig check box for the slices you want to alternate between using the Slice Trig Hit Type.
- **Pitch**
  Set the pitch for each individual slice in the REX loop by clicking and dragging the Pitch value up/down.
- **Level**
  Set the level for each individual slice in the REX loop by clicking and dragging the Level value up/down.
- **Reverse**
  Click the Reverse box for the slices you want to play back backwards.

The Nurse Rex panel parameters


On the Nurse Rex panel you can edit parameters that are common to all slices in the loaded REX loop:



- **Env Type**
  Sets the amplitude envelope type to “Gate” or “ADSR” (Attack, Decay, Sustain, Release). In Gate mode, the gate time is set with the Decay parameter.
- **Attack with Velocity control**
  Sets the attack time for the amplitude envelope when ADSR is selected as Env Type. The attack time can also be velocity controlled according to the sensitivity set with the Vel knob.
- **Decay with Velocity and Modulation controls**
  Sets the decay time for the amplitude envelope when ADSR is selected as Env Type. When Gate is selected as Env Type, the Decay parameter sets the gate time. The decay/gate time can also be velocity controlled according to the sensitivity set with the Vel knob. You can also control the decay/gate time from the Mod Wheel with the amount set with the Mod knob.
- **Sustain**
  Sets the sustain level of the amplitude envelope when ADSR is selected as Env Type. In Gate mode, the Sustain parameter has no effect.


- **Release with Velocity and Modulation controls**
  Sets the release time for the amplitude envelope when ADSR is selected as Env Type. The release time can also be velocity controlled according to the sensitivity set with the Vel knob. You can also control the release time from the Mod Wheel with the amount set with the Mod knob. In Gate mode, the Release parameter has no effect.
- **Pitch with Velocity control**
  Sets the overall pitch of all slices in the REX loop. The pitch can be velocity controlled according to the Vel knob setting. A negative Vel setting will lower the pitch with increasing velocity and a positive setting will raise the pitch with increasing velocity.
- **Level with Velocity control**
  Sets the overall level of all slices in the REX loop. The level can be velocity controlled according to the Vel knob setting. A negative Vel setting will lower the level with increasing velocity and a positive setting will raise the level with increasing velocity.

At the top of the Nurse Rex panel is a button for setting the polyphony:



- **Polyphonic means full polyphony**
  Retriggering the same slice/chunk will keep on adding more voices without muting any sustaining sounds.
- **Monophonic will make any new triggered loop/slice/chunk mute any currently playing/sustaining sound.**

Physical Bass Drum, Snare Drum and Tom Tom



The Physical Bass Drum, Snare Drum and Tom Tom use very faithful mathematical models for generating acoustic drum sounds. The sounds of the PM drums are generated using physical modelling; mathematical real-time calculations of physical acoustic phenomena. The physical modelling technique allows for a lot more creative freedom, and much wider sonic ranges, compared to sample playback.

General parameters

- **Level**
  This controls the overall output level of the Drum module to the FX1 and FX2 Slots (see "Signal flow"). The Level is also affected by velocity.

Drum head and shell parameters

The Physical Modelling Drums feature the following drum head and shell parameters:

- **Pitch**
  Sets the overall pitch of the drum. The Pitch parameter can be considered the total size of the drum and affects all other head and shell parameters.
- **Tune 1 and Tune 2 (PM Bass Drum and PM Tom Tom)**
  The Tune 1 and Tune 2 parameters set the drum's harmonic character, similar to the effect of individually adjusting the rim tension screws of the top drum head.
- **Tune (PM Snare Drum)**
  This controls the top drum head tension and thus affects the harmonic character of the sound.
- **Bend Amount (PM Bass Drum and PM Tom Tom)**
  This sets the dynamic "pitch bend" effect you get when hitting a drum head.
- **Damp**
  This controls the damping of the drum head.
- **Decay**
  The Decay parameter doesn't have any actual counterpart in real life. It simply controls the decay time of the drum sound.
- **Shell Level (PM Bass Drum and PM Tom Tom)**
  This controls how much of the drum shell sound should be present in the sound.
- **Shell Size (PM Tom Tom)**
  This controls the depth ("length") of the shell.
- **Edge Tune (PM Snare Drum)**
  This controls the head tuning when Hit Type 4 (Edge Hit) is selected for the pad (see "Assigning Hit Type to Pads").
- **Snare Tension (PM Snare Drum)**
  This controls the tension of the snare and the distance between the snare and bottom drum head.
- **Bottom Pitch (PM Snare Drum)**
  This controls the pitch of the bottom drum head.
- **Bottom Mix (PM Snare Drum)**
  This controls how much of the bottom head sound should be present in the drum sound.

Beater and Stick parameters

- **Density (PM Bass Drum)**
  This controls the "hardness" of the bass drum pedal beater.
- **Tone (PM Bass Drum and PM Tom Tom)**
  This is a filter which controls the tone of the hit.
- **Beater Level (PM Bass Drum)**
  This controls how much of the beater hit sound should be present in the drum sound.
- **Stick Level (PM Tom Tom)**
  This controls how much of the drum stick hit sound should be present in the drum sound.



Synth Bass Drum, Snare Drum and Tom Tom



The Synth Bass Drum, Snare Drum and Tom Tom use analog modelling to generate classic synth drum sounds. The Synth Tom Tom was faithfully modelled after a famous hexagonal shaped analog drum system from the 80's.

General parameters

- **Level**
  This controls the overall output level of the Drum module to the FX1 and FX2 Slots (see "Signal flow"). The Level is also affected by velocity.

Drum parameters

The Synth Drums feature the following parameters:

- **Pitch**
  This sets the overall pitch of the drum. The Noise pitch is not affected by this parameter.
- **Tone (Synth Bass Drum)**
  This is a filter similar to the one used in Redrum and affects the tone of the drum. The Noise is not affected by this parameter.
- **Attack (Synth Bass Drum)**
  Sets the attack time of the drum sound. This also affects the Noise.
- **Decay**
  Sets the Decay time of the drum sound. This also affects the Noise decay on the Synth Bass Drum and is added to the Noise Decay parameter on the Synth Snare and Synth Tom Tom drums. It is also added to the Harmonic Decay value on the Synth Snare Drum. The Decay time is also affected by velocity.
- **Harmonic Balance (Synth Snare Drum)**
  Sets the level balance between the fundamental tone and the harmonic tone.
- **Harmonic Frequency (Synth Snare Drum)**
  Sets the frequency of the harmonic tone.
- **Harmonic Decay (Synth Snare Drum)**
  Sets the decay time of the harmonic tone. This is also affected by the Decay parameter.
- **Click Frequency (Synth Bass Drum)**
  Sets the frequency of the click sound in the attack.
- **Click Resonance (Synth Bass Drum)**
  Sets the resonance amount of the click sound in the attack.
- **Click Level (Synth Bass Drum and Synth Tom Tom)**
  Sets the level of the click sound in the attack.

- **Bend Time (Synth Bass Drum and Synth Tom Tom)**
  Sets the time it should take to change the pitch from the Bend Amount value (se below) back to the original pitch.
- **Bend Amount (Synth Bass Drum and Synth Tom Tom)**
  Sets the upper pitch to bend from. The Bend Amount is also affected by velocity.
- **Noise Tone (Synth Snare Drum and Synth Tom Tom)**
  This is a filter which sets the frequency content of the noise.
- **Noise Decay (Synth Snare Drum and Synth Tom Tom)**
  This sets the decay of the noise in the sound. The Noise Decay is also affected by the regular Decay parameter.
- **Noise Mix (Synth Snare Drum and Synth Tom Tom)**
  Sets the noise level in the drum sound.

Synth Hi-hat



The Synth Hi-hat uses analog modelling to generate sounds. The Synth Hi-hat can be used for generating the typical hi-hat sounds of the early analog drum machines.

Parameters

- **Pitch**
  This sets the overall pitch of the hi-hat sound.
- **Decay**
  This sets the decay time of the hi-hat sound.
- **Level**
  This controls the overall output level of the Synth Hi-hat module to the FX1 and FX2 Slots (see "Signal flow"). The Level is also affected by velocity.
- **Click**
  This controls the click level in the attack of the hi-hat sound.
- **Tone**
  This is a filter similar to the one used in Redrum and affects the frequency content of the hi-hat sound.
- **Ring**
  Sets the level of the resonance peaks in the sound. The higher the value, the more "metallic" the sound.

The Support Generator modules

There are two types of Support Generator modules in Kong, one for generating noise and another one for generating a tone. The Support Generator modules can be used as companions to any of the Drum modules, or stand-alone. The Support Generators can be loaded into the FX1 and/or FX2 slots.

! **Note that only two pre-defined parameters per Support Generator module can be automated!**

Noise Generator



- **Hit Type buttons**
  These buttons allow you to choose for which Hit Type(s) the Noise generator should be active. By default, the Noise generator is active for all Hit Types (see "Assigning Hit Type to Pads").
- **Pitch**
  This sets the center pitch of the noise.
- **Attack**
  This sets the attack time of the noise.
- **Decay**
  This sets the decay time of the noise.
- **Reso**
  This sets the resonance amount of the noise around the center pitch.
- **Sweep**
  This sets the upper start pitch of the sweep range. The Sweep range is also affected by velocity.
- **Click**
  This sets the level of the click in the attack of the noise.
- **Level**
  This sets the overall level of the Noise generator. The level is also affected by velocity.

Tone Generator



- **Hit Type buttons**
  These buttons allow you to choose for which Hit Type(s) the Tone generator should be active. By default, the Tone generator is active for all Hit Types (see "Assigning Hit Type to Pads").
- **Pitch**
  This sets the pitch of the oscillator.
- **Attack**
  This sets the attack time of the tone.
- **Decay**
  This sets the decay time of the tone.
- **Bend Decay**
  This sets the decay time for the Bend.
- **Bend**
  This sets the upper start pitch of the bend range. The Bend range is also affected by velocity.
- **Shape**
  This sets the tonal character of the sound, from less to more harmonics.
- **Level**
  This sets the overall level of the Tone generator. The level is also affected by velocity.

The FX modules

The FX modules can be used in any of the FX1, FX2, Bus FX and Master FX slots.

! **Note that only two pre-defined parameters per FX Module can be automated!**


Using CV modulation of Bus FX and Master FX parameters

When the FX modules are used in the Bus FX and/or Master FX slots, it is possible to route external CV signals to the first two Effect module parameters for modulation. If you hover with the mouse over the first or second parameter of an FX module loaded in the Bus FX or Master FX slot, a tool tip appears:



The tool tip shows which CV modulation input on the back of the unfolded Kong panel will control that parameter. For FX modules loaded in the Bus FX slot, the tool tip displays “Bus FX P1: nn” for the first FX module parameter and “Bus FX P2: nn” for the second one. For FX modules loaded in the Master FX slot, the tool tip instead reads “Master FX P1: nn” for the first FX module parameter and “Master FX P2: nn” for the second one. The “nn” in the tool tip indicates the current parameter value.

By connecting cables to the CV modulation inputs on the back of the Kong panel, you can modulate the corresponding FX module parameters in the Bus FX and/or Master FX slots.



▶ **Control the FX parameter modulation amounts with the corresponding attenuation knobs.**

If you decide to replace the FX modules in the Bus FX and/or Master FX slots, the modulation routing will be preserved - but the CV signals will now control the first two parameters of the replacement module(s).

Drum Room Reverb



The Drum Room Reverb is a reverb with a room-type reverb algorithm. It's perfect for adding ambience to single drum sounds or to the entire mix of all 16 drum channels. The parameters are as follows:

- **Size**
  This sets the "size" of the room, from small to large.
- **Decay**
  This sets the reverb decay time.
- **Damp**
  This sets the high frequency damping amount of the reverb effect, from none to heavy.
- **Width**
  This sets the stereo effect of the reverb, from mono to wide stereo.
- **Dry/Wet**
  This sets the mix between Dry (no effect) and Wet (reverb) signal.

Transient Shaper



The Transient Shaper is a type of dynamics processor which produces a result that could be compared to that of a compressor. As opposed to a "normal" compressor, the Transient Shaper mainly affects the signal's attack, or transients in the signal, making the signal transients cut through in the mix. The parameters are as follows:

- **Attack**
  A positive Attack value will produce an amplified attack/transient whereas a negative value will reduce the attack/transient volume.

- **Decay**
  This sets the decay time from amplification/attenuation back to normal amplitude level.
- **Amount**
  This controls the amplification amount. A high Amount in combination with a positive Attack value will produce a very pronounced attack/transient in the sound.

Compressor



The Compressor levels out the audio, by making loud sounds softer. To compensate for the volume loss, the Compressor has a make-up gain control for raising the overall level by a suitable amount. The result is that the audio levels become more even and the sounds can get more "power" and longer sustain. The parameters are as follows:

- **Amount**
  This sets the sensitivity of the compressor. A high amount will make the compressor more sensitive and react to weak input signals.
- **Attack**
  This sets how fast the compression should be applied to the incoming signal. A low value will make the compression set in immediately whereas a high value will let the attack/transients through before compression sets in.
- **Release**
  This sets how long it should take before the compressor lets the sound through unaffected again. Set this to short values for more intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics.
- **Make up gain**
  This sets the overall level compensation. A low value will produce a softer output signal whereas a high value will amplify the output signal.

Filter



The Filter is a state variable filter with a switch for selecting Lowpass, Bandpass or Highpass state. It has controls for cutoff/center frequency and resonance amount and can also be controlled from a built-in MIDI controlled envelope generator for sweeping the frequency. When used in the Bus FX Slot, MIDI Note E2 (#52) trigs the envelope. When used in the Master FX Slot, MIDI Note F2 (#53) trigs the envelope. The parameters are as follows:

- **Frequency**
  Sets the cutoff frequency in the LP and HP states and center frequency in the BP state.
- **Resonance**
  This sets the amplification amount of the frequencies around the cutoff/center frequency.
- **LP/BP/HP**
  Sets the state of the filter to either Lowpass, Bandpass or Highpass.
- **MIDI Trig EG Amount**
  This sets the amount of the MIDI controlled filter envelope. The Amount value is bipolar (+/-). Set to a positive value, the envelope will sweep the filter frequency from a high value down to the set Frequency value. Set to a negative Amount, the envelope will sweep the filter frequency from a low value up to the set Frequency value. The Amount is also affected by velocity.
- **MIDI Trig EG Decay**
  This sets the MIDI controlled envelope decay time.

Parametric EQ



The Parametric EQ is a single-band parametric equalizer with controls for center frequency, gain and bandwidth (Q-value). The parameters are as follows:

- **Frequency**
  Sets the center frequency of the equalizer.
- **Gain**
  Sets the amplification (positive Gain value) or attenuation (negative Gain value) around the center Frequency.
- **Q**
  Sets the bandwidth around the center Frequency, from wide to a narrow peak.

Ring Modulator



The Ring Modulator takes the input signal and multiplies it with an internal sinewave signal. The result is often a synthetic metallic sound. The Ring Modulator also features a MIDI controlled envelope generator for sweeping the internal sinewave frequency. When used in the Bus FX Slot, MIDI Note E2 (#52) trigs the envelope. When used in the Master FX Slot, MIDI Note F2 (#53) trigs the envelope. The parameters are as follows:

- **Frequency**
  Sets the frequency of the internal sinewave oscillator. The higher the frequency, the higher the resulting output signal pitch.
- **Amount**
  Sets the level of the internal sinewave oscillator. The higher the level, the more the ring modulation effect.
- **MIDI Trig EG Amount**
  This sets the amount of the MIDI controlled envelope. The Amount value is bipolar (+/-). Set to a positive value, the envelope will sweep the internal sinewave oscillator frequency from a high value down to the set Frequency value. Set to a negative Amount, the envelope will sweep the oscillator frequency from a low value up to the set Frequency value. The Amount is not affected by velocity.
- **MIDI Trig EG Decay**
  This sets the MIDI controlled envelope decay time.

Rattler



The Rattler adds the effect of a snare "attached" to whatever sound is fed through it. Using the Rattler in combination with other types of sounds than "usual" snare drum sounds can produce really interesting results! Ever played a snare bass drum, or a snare hi-hat, for example? The parameters are as follows:

- **Snare Tension**
  This sets the tension of the snare. Note that when the Snare Tension is increased, the effect will actually be less pronounced since the snare will have "less contact" with the sound source.
- **Tone**
  This is a filter similar to the one used in Redrum and affects the frequency content of the output signal.
- **Decay**
  This sets how long the snare will "ring".
- **Tune**
  This sets the snare tuning, from low to high, and affects the frequency content of the signal.
- **Level**
  This sets the overall level of the Rattler. The level is also affected by velocity.

Tape Echo



The Tape Echo is based on the principles of classic tape echo effects. The original tape echo effects were electro-mechanical devices that used an endless magnetic tape in combination with recording and playback heads inside the box. Depending on the speed of the tape, and on which playback heads were used, the echo repetition and echo patterns could be controlled. Later on, a lot of tape echo effects were replaced by digital delay effects. The Tape Echo in Kong simulates the classic tape echo effect and features the following parameters:

- **Time**
  This sets the time between the delays, from short to long.
- **Feedback**
  This sets the number of delay repetitions, from one to... many.
- **Wobble**
  This sets the tape speed wobbling effect. Since it emulates a magnetic tape, a wobbling speed also automatically produces a wobbling pitch of the signal.
- **Frequency**
  This sets the change in frequency of the delay repetitions. For every delay, the frequency content will shift according to the Frequency setting. A low value will make each repetition sound muddier than the previous one, whereas a high value will make each delay sound brighter.
- **Resonance**
  This sets the resonance amount of the delay repetitions. Depending on the Frequency parameter setting above, different frequencies will be amplified.
- **Dry/Wet**
  This is a traditional dry/wet parameter for controlling the relationship between unprocessed and processed signal.

Overdrive/Resonator




The Overdrive/Resonator is a combined distortion and resonator module. It can be used to add a nice distortion to the input signal. There is also a resonator section with a number of selectable characteristics, similar to the Body section in the Scream 4 Sound Destruction Unit. The parameters are as follows:

- **Drive**
  Sets the overdrive distortion amount.
- **Resonance**
  Sets the resonance amount for the resonator.
- **Size**
  Sets the size of the virtual “resonance chamber”, from small to large.
- **Model**
  Click to select one of five different resonator “body” characteristics.

Connections

On the back panel of Kong are a number of connectors. Many of these are CV/Gate related. Using CV/Gate is described in the chapter "Routing Audio and CV".



Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play Kong from another CV/Gate device (typically a Matrix or a Redrum). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Modulation Input

These control voltage (CV) inputs (with associated voltage trim pots), can modulate various Kong parameters from other devices. These inputs can control the following parameters:

- **Volume**
  This controls the Master Level in Kong.
- **Pitch**
  This controls the Pitch Bend wheel in Kong.
- **Mod**
  This controls the Mod Wheel in Kong.

Aux Send Out

The two stereo Aux Send Outputs can be used for connecting external effect devices for external signal processing. The signal levels to these Aux Send Outputs are controlled from the Aux 1 and Aux 2 Send knobs on the Drum Control Panel, see "The Drum Control Panel".

Gate In and Out

- **The Gate Inputs can receive a CV signal to trigger each of the 16 pads individually.**
  You are still able to control the pads from the panel and/or via MIDI even when the Gate Inputs are being used.
- **The Gate Outputs send out a CV Gate signal each time the corresponding pad is played.**
  The Gate signals can be used for triggering sounds in other devices.

Audio Out 3-16


There are 14 separate audio output jacks on Kong's back panel - arranged as seven separate stereo pairs. These outputs are never auto-routed but can be manually connected and selected as individual outputs for any of the Drum channels by using the Drum Output selector in the Drum and FX section, see "Signal flow".

Main Audio Out

These are the main audio outputs. When you create a new Kong device, the Main Audio Output pair is auto-routed to the first available mixer channel.

Using Kong as an effect device

Besides using the wide array of internal sound possibilities in Kong, you can also use it as an external effect device. If you unfold the Drum and FX section and flip the rack around, a set of additional audio jacks are visible at the bottom of the back panel.



These audio jacks can be used for connecting external devices and processing their audio in Kong. As you can see, the signal flow for processing external audio is printed on the back panel. Even if you want to use Kong for processing external signals, you can still play and use its internal Drum channels just like before.

Proceed as follows to connect an external device for audio processing in Kong:

1. **Connect the outputs of your other device (a synth, for example) to the Audio Inputs to the left.**
   If your device only has a mono output, connect it to the Left Audio Input on Kong.
2. **Play a couple of notes on your other device.**
   The audio is now routed via Kong's Bus FX slot and further via the Master FX slot, to the Main Audio Outputs of Kong.


3. **Select suitable FX devices for the Bus FX and Master FX slots in Kong according to the descriptions in "The FX modules" and tweak the parameters to your liking.**

- **By connecting CV signals to the Parameter inputs in the Bus FX and Master FX sections on the back of the panel, you can modulate the first two parameters on the selected FX modules, see "Using CV modulation of Bus FX and Master FX parameters".**
  Attenuate the CV signal with the corresponding knobs next to the modulation jacks.

Using external effects with Kong

It's also possible to hook up an external effect device in the signal chain to process the Kong audio, or to process any external audio routed via the Audio Inputs to the left on the unfolded back panel of Kong.

- **Connect the external effect device to the External Effect Outputs and Inputs.**
  In the picture below, an RV7000 Reverb is connected to Kong's External Effect section allowing the RV7000 to process the signal between Kong's internal Bus FX and Master FX slots:



An RV7000 Reverb connected to Kong for processing the Kong audio signals

! **Note that if you have selected "Master FX" or "Separate Out" as output in the Drum Output selector, the BUS FX Send knob on the Drum Control Panel controls the signal level also to the External Effect, see "Signal flow".**

Chapter 35
Malström Synthesizer

Introduction

The Malström is a polyphonic synthesizer with a great number of different routing possibilities. It is based on the concept of what we call "Graintable Synthesis" (see below), and is ideally suited for producing swirling, sharp, distorted, abstract special effect types of synthesizer sounds. In fact, you could go so far as to say that the Malström can produce sounds quite unlike anything you've ever heard from a synthesizer.

For a complete run-down of the principles behind it and thorough explanations of the controls, read on...

Features

The following are the basic features of the Malström:

- **Two Oscillators, based on Graintable Synthesis.**
  See "The Oscillator section" for details.
- **Two Modulators, featuring tempo sync and one-shot options.**
  See "The Modulator section".
- **Two Filters and one Shaper.**
  A number of different filter modes in combination with several routing options and a Waveshaper makes it possible to create truly astounding filter effects.
- **Three Envelope generators.**
  There is one amplitude envelope for each oscillator and a common envelope for both filters. See "The amplitude envelopes" and "The Filter Envelope" for details.
- **Polyphony of up to 16 voices.**
- **Velocity and Modulation control.**
  See "The Velocity controls".
- **A number of CV/Gate Modulation possibilities.**
  See "Modulation Input".
- **A variety of Audio Input/Output options.**
  You can for instance connect external audio sources for input to the Malström, and you can also control its output. See "Audio Input" for more details.

Theory of operation

There are a number of different synthesis methods for generating sound, e.g. subtractive synthesis (which is used in the Subtractor), FM synthesis, and physical modelling synthesis to mention but a few.

To give you a clear understanding of the inner workings of the Malström, it might be in order with a brief explanation of what we call Graintable Synthesis.

What we refer to as graintable synthesis is actually a combination of two synthesis methods, granular synthesis and wavetable synthesis.

- **In granular synthesis, sound is generated by a number of short, contiguous segments (grains) of sound, each typically from 5 to 100 milliseconds long.**
  The sound is varied by changing the properties of each grain and/or the order in which they are spliced together. Grains can be produced either by a mathematical formula or by a sampled sound. This is a very dynamic synthesis method capable of producing a great variety of results, although somewhat hard to master and control.
- **Wavetable synthesis on the other hand, is basically the playback of a sampled waveform.**
  An oscillator in a wavetable synth plays back a single period of a waveform, and some wavetable synths also allow for sweeping through a set of periodic waveforms. This is a very straightforward synthesis method, easily controlled, but somewhat more restricted in results. The Malström combines these two into a synthesis method that provides a very flexible way of synthesizing sounds with incredible flux and mutability.

The Malström combines these two into a synthesis method that provides a very flexible way of synthesizing sounds with incredible flux and mutability.

It works like this:

- **The oscillators in the Malström play back sampled sounds that have been subjected to some very complex processing and cut up into a number of grains.**
- **A set of these periodic waveforms (grains) are spliced together to form a Graintable, which may be played back to reproduce the original sampled sound.**
- **A Graintable may be treated just like a wavetable; e.g., you may choose to sweep through it, to move through it at any speed without affecting pitch, to play any section of it repeatedly, to select from it static waveforms, to jump between positions, etc., etc.**
- **It is also possible to perform a number of other tricks, all of which are described further on in this chapter.**

Loading and Saving Patches

Loading and saving patches is done in the same way as with any other Reason device - see "Loading patches" and "Saving patches".

The Oscillator section



The two oscillators (osc:A and osc:B) of the Malström are the actual sound generators, and the rest of the controls are used for modulating and shaping the sound. The oscillators actually do two things; they play a graintable and generate the pitch:

- **A graintable is several short, contiguous segments of audio (see above).**
- **Pitch is the frequency at which the segments are played back.**


When creating a Malström patch, the fundamental first building block is usually to select a graintable for one or both of the oscillators.

▶ **To activate/deactivate an oscillator, click the On/Off button in the top left corner.**
When an oscillator is activated, the button is lit.



An activated oscillator.

▶ **To select a graintable, either use the spin controls or click directly in the display to bring up a pop-up menu with the available graintables.**
The graintables are sorted alphabetically into a number of descriptive categories, giving a hint as to the general character of the sound. Note that the categories are only visible in the pop-up menu, not in the display.



Selecting a graintable by clicking in the Oscillator display.

Setting oscillator frequency


You can change the frequency - i.e. the tuning - of each oscillator by using the three knobs marked “Octave”, “Semi” and “Cent”.



- **The Octave knob changes the frequency in steps of one full octave (12 semitones).**
  The range is -4 – 0 – +4 where 0 corresponds to middle “A” on your keyboard at 440 Hz.
- **The Semi knob changes the frequency in steps of one semitone.**
  The range is 0 to +12 (one full octave up).
- **The Cent knob changes the frequency in steps of cents, which are 100ths of a semitone.**
  The range is -50 – 0 – +50, i.e. down or up by up to half a semitone.

Controlling playback of the graintable

Each oscillator features three controls that determine how the loaded graintables are played back. These are: The “Index” slider, the “Motion” knob and the “Shift” knob.



- **The Index slider sets the playback starting point in the graintable.**
  By dragging the slider, you set which index point in the graintable should be played first when the Malström receives a Note On message. Playback will then continue to the next index point according to the active graintable. With the slider all the way to the left, the first segment in the graintable is also the one that will be played back first.

! **Note that the Malström’s Graintables are *not* all of the same length, and that the range for the Index slider (0-127) does not reflect the actual length of the graintables. I.e. regardless of whether a graintable contains 3 or 333 grains, the Index slider will always span the entire graintable even though the slider range says 0-127.**

- **The Motion knob controls how fast the Malström should move forward to play the next segment in the graintable, according to its motion pattern (see below).**
  If the knob is kept in the middle position the speed of motion is the normal default. Turning the knob to the left slows it down and turning it to the right results in higher speed. If the knob is set all the way to the left, there will be no motion at all, which means that the initial segment, as set with the Index slider, will play over and over as a static waveform.
- **The Shift knob changes the timbre of the sound (the formant spectrum).**
  What it actually does is change the pitch of a segment up or down by re-sampling. However, since the pitch you *hear* is independent of the actual pitch of the graintable (see above), pitch-shifting a segment instead means that more or less of the segment waveform will be played back, resulting in a change of harmonic content and timbre.

About motion patterns


Each graintable has a predefined motion pattern and a default motion speed.

When a graintable is looped (i.e. if the Motion knob is *not* set all the way to the left), it follows one of two possible motion patterns:

- **Forward**
  This motion pattern plays the graintable from the beginning to the end, and then repeats it.
- **Forward - Backward**
  This motion pattern plays the graintable from the beginning to the end, then from the end to the beginning and then repeats it.

The motion speed can be changed with the Motion knob, as described above, but it is *not* possible to alter the motion pattern of a graintable.

The amplitude envelopes



Each oscillator features a standard ADSR (Attack, Decay, Sustain, Release) envelope generator, and a Level control. These are used for controlling the volume of the oscillator. One thing that makes the Malström different from many other synths though, is the fact that the amplitude envelopes are placed *before* the filter and routing sections in the signal path.

The amplitude envelopes control how the volume of a sound should change from the moment you strike a key on your keyboard to the moment that you release it again.

Vol

The Volume knobs set the volume level out from each oscillator.

! **For an overall description of the general envelope parameters (Attack, Decay, Sustain, Release), please refer to the Subtractor chapter.**

The Modulator section



The Malström features two Modulators (mod:A and mod:B) These are in fact another type of oscillators, called LFOs (Low Frequency Oscillators). They each generate a waveform and a frequency, much like osc:A and osc:B. However, there are a couple of important differences:

- **Mod:A and mod:B do not generate sound. They are instead used for modulating various parameters to change the character of the sound.**
- **They only generate waveforms of low frequency.**

Furthermore, both modulators are tempo syncable and possible to use in one shot mode, in which case they will actually work like envelopes.

Modulator parameters

The two Modulators have a few controls in common, but there are also some differences. Both the common parameters and the ones that are unique for each Modulator (the destinations) are described below.

▶ **To activate/deactivate a Modulator, click the On/Off button in the top left corner.**
When a Modulator is activated, the button is lit.



An activated Modulator.

Curve

This lets you select a waveform for modulating parameters. Use the spin controls to the right of the display to cycle through the available waveforms. Some of these waveforms are especially suited for use with the Modulator in one shot mode (see below).

Rate

This knob controls the frequency of the Modulator. For a faster modulation rate, turn the knob to the right.

The Rate knob is also used for setting the time division when synchronizing the Modulator to the song tempo (see below).

One Shot

To put the Modulator into one shot mode, click this button so that it is lit.

Normally, the Modulators will repeat the selected waveforms over and over again, at the set rate. However, when one shot mode is activated and you play a note, the Modulator will play the selected waveform only once (at the set rate) and then stop. In other words, it will effectively be turned into an envelope generator!

Note that even though all waveforms can be used with interesting results, some waveforms are explicitly well suited for use in one shot mode. For example, try using the waveform with just one long, gently sloping curve.

Sync

Clicking this button so that it is lit synchronizes the Modulator to the song tempo, in one of 16 possible time divisions.

! **When sync is activated, the Rate knob is used for selecting the desired time division. Turn the Rate knob and observe the tool tip for an indication of the time division.**

A/B selector



This switch is used for deciding which oscillator and/or filter the Modulator should modulate - A, B or both. With the switch in the middle position, both A and B will be modulated.

Destinations

The following knobs are used for determining what each of the two modulators should modulate.

- **Note that these knobs are bi-polar, which means that if a knob is in the middle position, no modulation is applied. If you turn a knob either to the left or to the right, an increasing amount of modulation is applied to the parameter. The difference is that if you turn a knob to the left, the waveform of the modulator is inverted.**

Mod:A



Mod:A can modulate the following parameters of either oscillator:

- **Pitch**
  Use this if you want Mod:A to offset the pitch of osc:A, osc:B, or both (see "Setting oscillator frequency").
- **Index**
  Use this if you want Mod:A to offset the index start position of osc:A, osc:B, or both (see "Controlling playback of the graintable").
- **Shift**
  Use this to have Mod:A affect the harmonic content of osc:A, osc:B, or both (see "Controlling playback of the graintable").


Mod:B



Mod:B can modulate the following parameters of either oscillator:


- **Motion**
  Use this if you want Mod:B to affect the motion speed of osc:A, osc:B, or both (see "Controlling playback of the grainable").
- **Vol**
  Use this if you want Mod:B to change the output level of osc:A, osc:B, or both (see "Vol").
- **Filter**
  Use this if you want Mod:B to offset the cutoff frequency of filter:A, filter:B, or both (see "Filter controls").
- **Mod:A**
  Use this if you want Mod:B to change the total amount of modulation from Mod:A.

The Filter section



The filter section lets you further shape the overall character of the sound. Contained herein are two multimode filters, a filter envelope and a waveshaper.

The Filters



Both filter:A and filter:B have the exact same parameters, all of which are described below.

- **To activate/deactivate a filter, click the On/Off button in the top left corner.**
  When a filter is activated, the button is lit.




An activated filter.

Filter types


To select a filter type, either click the Mode button in the bottom left corner or click directly on the desired filter name so that it lights up in yellow:

- **LP 12 (12 dB lowpass)**
  Lowpass filters let low frequencies through and cut off high frequencies. This filter type has a roll-off curve of 12dB/Octave.
- **BP 12 (12 dB bandpass)**
  Bandpass filters cut both high and low frequencies, leaving the frequency band in between unaffected. Each slope in this filter type has a 12 dB/Octave roll-off.


- **Comb + & Comb –**
  Comb filters are basically delays with very short delay times with adjustable feedback (in Reason controlled with the Resonance knob). A comb filter causes resonating peaks at certain frequencies.
  The difference between "+" and "–" is in the position of the peaks, in the spectrum. The main audible difference is that the "–"-version causes a bass cut.
  The Resonance parameter in both cases controls the shape and size of the peaks.




Comb + Low Resonance.



Comb + High Resonance.



Comb – Low Resonance.



Comb – High resonance.

- **AM**
  AM (Amplitude Modulation) is often referred to as Ring Modulation. A Ring Modulator works by multiplying two signals together. In the case of Malström, the filter produces a sine wave which is multiplied with the signal from osc:A or osc:B. Resonance controls the mix between the clean and modulated signals. The Ring Modulated output will then contain added frequencies which are generated by the sum of, and the difference between the two signals. This can be used for creating complex, non-harmonic sounds.

Filter controls

Each filter contains the following four controls:

- **Kbd (keyboard tracking)**
  By clicking this button so that it is lit, you activate keyboard tracking. If keyboard tracking is activated, the frequency of the filter will change according to the notes you play on your keyboard. That is, if you play notes higher up on the keyboard, the filter frequency will increase and vice versa. If keyboard tracking is deactivated, the filter frequency will remain at a fixed value regardless of where on the keyboard you play.

- **Env (envelope)**
  If you click on this button so that it is lit, the cutoff frequency (see below) will be modulated by the filter envelope. If you leave this deactivated, the Filter Envelope will have no effect.
- **Freq (frequency)**
  The function of this parameter depends on which filter type you have selected:


  With all filter types except AM, it is used for setting the cutoff frequency of the filter. In the case of the lowpass filter for example, the cutoff frequency determines the limit above which high frequencies will be cut off. Frequencies below the cutoff frequency will be allowed to pass through. The farther to the right you turn the knob, the higher the cutoff frequency will be.

  If you have selected AM as filter type, this will instead control the frequency of the signal generated by the filter. The same control range applies though; the farther to the right you turn the knob the higher the frequency will be.
- **Res (resonance)**
  Again, the function of this parameter depends upon which filter type is selected:

  If the selected filter is any other type than AM, it sets the filter characteristic, or quality. For the lowpass filter for example, raising the filter Res value will emphasize the frequencies around the set filter frequency. This generally produces a thinner sound, but with a sharper, more pronounced filter frequency "sweep". The higher the filter Res value, the more resonant the sound becomes until it produces a whistling or ringing sound. If you set a high value for the Res parameter and then vary the filter frequency, this will produce a very distinct sweep, with the ringing sound being very evident at certain frequencies.

  In the case of the AM filter type though, this control instead regulates the balance between the original signal and the signal resulting from amplitude modulation. The farther to the right you turn the knob, the more dominant the AM signal will be.

The Filter Envelope



This is a standard ADSR envelope with two additional controls; inv and amt. The filter envelope is common for both filter:A and filter:B, and controls how the filter frequency should change over time.

Inv (inverse)

This button toggles inversion of the envelope on and off. The Decay segment of the envelope will for instance normally lower the frequency, but if the envelope is inverted it will instead raise the frequency.

Amt (amount)

This controls to which extent the filter envelope affects the filters, or rather - the set filter cutoff frequencies. For example; if the cutoff frequency is set to a certain value, the filter will already be opened by this amount when you hit a key on your keyboard. The amount setting then controls how much more the filter will open from that point. Turn the knob to the right to increase the value.

! **For an overall description of the general envelope parameters (Attack, Decay, Sustain, Release), please refer to the Subtractor chapter.**


The Shaper



Before filter:A is an optional waveshaper. Waveshaping is a synthesis method for transforming sounds by altering the waveform shape, thereby creating a complex, rich sound. Or, if that's more to your taste, truncating and distorting the sound to lo-fi heaven!

A guitar distortion box could be viewed as a type of waveshaper for example. An unamplified electric guitar produces a sound with fairly pure harmonic content, which is then amplified and transformed by the distortion box.

▶ **To activate/deactivate the Shaper, click the On/Off button in the top left corner.**
When the Shaper is activated, the button is lit.




The Shaper activated

Mode

You can select one of five different modes for shaping the sound, each with its own characteristics.

To select a mode, either click the Mode button in the bottom left corner or click directly on the desired mode name so that it lights up in yellow.

- **Sine**
  This produces a round, smooth sound.
- **Saturate**
  This gives a lush, rich character to the sound.
- **Clip**
  This introduces clipping - digital distortion - to the signal.
- **Quant**
  This lets you truncate the signal by bit-reduction, thus making it possible to achieve that noisy, characteristic 8 bit sound for example.
- **Noise**
  This is actually not strictly a shaper function. Instead it multiplies the sound with noise.



Amt (amount)

This controls the amount of shaping applied. By turning the knob to the right you increase the effect.


Routing

The Malström puts you in total control of how the signal should be routed from the oscillators, through the filters and on to the outputs. Below is first a general description of the routing options, followed by examples of how to route the signal in order to achieve a certain result.

▶ **Click on a button so that it is lit, to route the signal correspondingly.**
See below for descriptions.

If this button is lit, the signal from osc:A is routed to filter:A via the shaper. If neither this nor the other routing button from osc:A (to filter:B) is lit, the signal will go straight to the outputs.

If this button is lit, the signal from osc:A is routed to filter:B. If neither this nor the other routing button from osc:A (to filter:A/shaper) is lit, the signal from osc:A will go straight to the outputs.




If this button is lit, the signal from osc:B is routed to filter:B. If this is not lit, the signal from osc:B will go straight to the outputs.

If this button is lit, the signal from filter:B is routed to filter:A via the shaper. The signal from filter:B can originate from either osc:A, osc:B or both. If this is not lit, the signal from filter:B will go straight to the outputs.

! **Note that the result depends both on the routing buttons and on whether the filters and shaper are activated or not!**


Routing examples

One or both oscillators without filters




With this configuration, the signals from the oscillators will bypass the filters and the shaper and go directly to the respective output. Using both oscillators allows you to use the Spread parameter to create a true stereo sound.

One or both oscillators to one filter only




Both oscillators routed to filter:B only.



Both oscillators routed to filter:A only.


With these configurations, the signal from osc:A and/or osc:B will go to either filter:A or filter:B and then to the outputs. This is essentially a mono configuration and hence Spread should probably be set to “0”.

Both oscillators to one filter each



With this configuration, the signals from osc:A and osc:B will go to filter:A and filter:B respectively, and then to the outputs. Again, this configuration allows you to work in true stereo.


Oscillator A to both filters in parallel




With this configuration, the signal from osc:A will go to both filter:A and filter:B, with the filters in parallel.

! **This configuration is only possible with osc:A. Osc:B can be routed to both filters as well, but only in series (see below).**

One or both oscillators with both filters in series



Osc:A routed through both filters in series.





Osc:B routed through both filters in series.

With these configurations, the signal from osc:A and/or osc:B will go to both filter:A and filter:B, with the filters in series (one after the other).

Adding the shaper

The signal from one or both oscillators can also be routed to the shaper. The signal will then pass through the shaper to the outputs, with or without also passing through the filters.





In the left figure, the signal from osc:A is routed to the shaper and then directly to the outputs. In the right figure, the signal from osc:B is routed to filter:B, then to the shaper and then to filter:A.

The output controls



These two parameters control the output from the Malström in the following way:

Volume

This knob controls the master volume out from the Malström.

Spread

This controls the stereo pan-width of the outputs from Osc:A/B and Filter:A/B respectively. The farther to the right you turn the knob, the wider the stereo image will be. In other words, the signals will be panned further apart to the left and right.

! If you are only using one output (A or B), it is strongly recommended that you set Spread to "0".

The play controls



To the far left on the Malström's "control panel" are various parameters that are affected by how you play, and lets you apply modulation by MIDI controls. The following is a description of these controls.

Polyphony - setting the number of voices



This lets you set the polyphony for the Malström. Polyphony is the number of voices it can play simultaneously. The maximum number is 16 and the minimum is 1, in which case the Malström will be monophonic.

! **The number of voices you can play depends of course on the capacity of your computer. Even though the maximum number is 16 it doesn't necessarily mean that your system is capable of using that many voices. Also note that voices do not consume CPU capacity unless they are really "used". That is, if you are using a patch that plays two voices but have polyphony set to four, the two "unused" voices do not consume any of your system resources.**

Porta (portamento)



This is used for controlling portamento. This is a parameter that makes the pitch glide between the notes you play, rather than changing the pitch instantly as soon as you hit a key on your keyboard. By turning this knob you set how long it should take for the pitch to glide from one note to the next as you play them.

With the knob turned all the way to the left, portamento is disabled.

Legato



By clicking this button you activate/deactivate Legato. Legato in Malström is unique in that it allows you to control whether the sound is monophonic or polyphonic by using your playing style:

- **If you play legato (hold down a key and then press another key without releasing the previous), the sound is monophonic.**
  Also note that the pitch changes, but the envelopes do not start over. That is, there will be no new "attack".
- **If you play non-legato (separated notes), with polyphony set to more voices than 1, each note will decay separately (polyphonic).**
  This will be most apparent with longer release times.

The Pitch Bend and Modulation wheels




- **The Pitch Bend wheel is used for bending the pitch of notes, much like bending the strings on a guitar or other string instrument.**
- **The Modulation wheel can be used for applying modulation while you are playing.**

Virtually all MIDI keyboards have Pitch Bend and Modulation controls. The Malström does not only feature the settings for how incoming MIDI Pitch Bend and Modulation wheel messages should affect the sound, but also two functional wheels that can be used for applying real time modulation and pitch bend if you don't have these controllers on your keyboard, or if you aren't using a keyboard at all. The wheels on the Malström also mirror the movements of the wheels on your MIDI keyboard.

Pitch Bend Range

The Range parameter sets the maximum amount of pitch bend, i.e. how much it is possible to change the pitch by turning the wheel fully up or down. The maximum range is 24 semitones (2 Octaves). You change the value by clicking the spin controls to the right of the display.

The Velocity controls



Velocity is used for controlling various parameters according to how hard or soft you play notes on your keyboard. A typical use of velocity control is to make sounds brighter and louder if you strike a key harder. By using the knobs in this section, you can control how much the various parameters will be affected by velocity.

! **All of the velocity control knobs are bi-polar, which means that the amount can be set to either positive or negative values, while keeping the knobs in the center position means that no velocity control is applied.**

The following parameters can be velocity controlled:

- **Lvl:A**
  This lets you velocity control the output level of osc:A.
- **Lvl:B**
  This lets you velocity control the output level of osc:B.

- **F.env**
  This sets velocity control for the Filter Envelope Amount parameter. Positive values will increase the envelope amount the harder you play, and negative values will decrease the amount.
- **Atk (attack)**
  This sets velocity control for the Amp Envelope Attack parameter of osc:A and/or osc:B. Positive values will increase the Attack time the harder you play, and negative values will decrease it.
- **Shift**
  This lets you velocity control the Shift parameter of osc:A and/or osc:B.
- **Mod**
  This lets you velocity control all modulation amounts of mod:A and/or mod:B.

! **Note that you can set the last three parameters (Atk, Shift and Mod) to be velocity controlled for either or both of oscillator/modulator A and B. This is done with the A/B selector switch.**

The Modulation wheel controls



The Modulation wheel can be set to control a number of parameters. You can set positive or negative values, just like in the Velocity Control section (see above).

The following parameters can be affected by the modulation wheel:


- **Index**
  This sets modulation wheel control of the currently active graintable's index (see "Controlling playback of the graintable") for osc:A and/or osc:B. Positive values will move the index position forwards if the modulation wheel is pushed forward. Negative values will move it backwards.
- **Shift**
  This sets modulation wheel control of the Shift parameter of osc:A and/or osc:B (see "Controlling playback of the graintable").
- **Filter**
  This sets modulation wheel control of the Filter Frequency

  parameter (see "Filter controls"). Positive values will raise the frequency if the

  wheel is pushed forward and negative values will lower the frequency.
- **Mod**
  This sets modulation wheel control of the total amount of modulation from mod:A and/or mod:B. Positive values will increase the settings if the wheel is pushed forward and negative values will decrease the settings.

! **You can set whether these parameters on either or both oscillator/modulator/filter A and B will be affected by the modulation wheel. This is done with the A/B selector switch.**

Connections



Flipping the Malström around reveals a wide array of connection possibilities. Most of these are CV/Gate related. Using CV/Gate is described in the chapter "Routing Audio and CV".

Audio Output

These are the Malström's audio outputs. When you create a new Malström device, they are auto-routed to the first available channel on the audio mixer:

- **Shaper/Filter:A (left) & Filter:B (right)**
  These are the main stereo outputs. Each of the two filters are connected to a separate output, and by connecting both, you can have stereo output. Whether the output really will be in stereo however, is determined by the routing and the Spread parameter. See "Routing" for details about this.
- **Osc:A & osc:B**
  These make it possible to output the sound directly after the Amp Envelope of each oscillator, bypassing the filter section. Connecting one or both of these to a channel on the audio mixer will break the Malström's internal signal chain. That is, it is not possible to process the sound by using the filters and the shaper of the Malström. the sound instead goes directly to the mixer.

▶ **Note also that you can connect the outputs Osc:A & Osc:B to the Audio Inputs on the Malström for some interesting effects - see "Routing external audio to the filters".**

Audio Input

- **Shaper/Filter:A**
- **Filter:B**

These inputs let you connect either other audio sources, or the Malström's own internal signal directly to the filters and the shaper - see "Routing external audio to the filters".

Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play the Malström from another CV/Gate device (typically a Matrix or a Redrum). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

! **For best results, you should use the Sequencer Control inputs with monophonic sounds.**

Gate Input

These inputs can receive a CV signal to trigger the following envelopes:

- **Amp Envelope**
- **Filter Envelope**

! **Note that connecting to these inputs will override the normal triggering of the envelopes. For example, if you connected a Modulation output to the Gate Amp in-put, you would not trigger the amp envelope by playing notes, as this is now controlled by the Modulator. In addition you would only hear the Modulator triggering the envelope for the notes that you hold down.**

Modulation Input

These control voltage (CV) inputs (with associated voltage trim pots and A/B selector switches), can modulate various Malström parameters from other devices, or from the modulation outputs of the same Malström device. These inputs can control the following parameters:

- **Oscillator Pitch**
- **Filter Frequency**
- **Oscillator Index offset**
- **Oscillator Shift**
- **Amp Level**
- **Mod Amount**
- **Mod Wheel**

Modulation Output

The Modulation outputs can be used to voltage control other devices, or other parameters in the same Malström device.

The Modulation Outputs are:

- **Mod:A**
- **Mod:B**
- **Filter Envelope**

Routing external audio to the filters



The audio inputs on the back of the Malström allows you to connect any audio signal to the filters and Shaper.

To use this feature, it's important to understand the following background:

Normally the Malström behaves like any regular polyphonic synthesizer, in that each voice has its own filter. The filter settings are the same, but each filter envelope is triggered individually when you play a note.

However, when you connect a signal to the audio inputs, it is routed to an "extra" filter. The envelope for this filter is triggered each time any of the other filter envelopes is triggered. In other words, the "extra" filter envelope is triggered each time you play a note on the Malström.

There are two different uses for the audio inputs:

Connecting an external signal source


Connecting an audio signal from another device in the rack to the audio input allows you to process the signal through the filters and/or Shaper of the Malström. The processed signal will then be mixed with the Malström's "own" voices (if activated) and sent to the outputs.

The result depends on the following:

- **To which jack you connect the signal.**
- **Whether the filters and/or Shaper are activated on the front panel.**
- **The routing button for filter:B.**
  If this is activated and you connect a signal to the Filter:B input, the signal will be processed in filter:B and then sent to the Shaper and filter:A (just as when routing Malström's own oscillators on the front panel).

Note again that the filter envelope is triggered by all voices. To make use of the filter envelope, you either need to play the Malström or use gate signals to trigger it or the filter envelope, separately.

Connecting the signals from the Malström itself



If you connect one or both oscillator outputs to the audio input(s), the internal signal path from the oscillators to the filters is broken. In other words, no signals will pass internally from the oscillators to the filters, and the three routing buttons for the oscillators are ignored.

This may seem pointless at first, but there are several uses for this:

- **When you play the Malström in this mode, the filter envelope will be triggered for each note you play, affecting all sounding notes.**
  This is due to the monophonic "extra" filter described above. On older synthesizers, this feature is called "Multiple triggering".
- **Since all notes you play are mixed before being sent into the filter, the result of using the Shaper will be totally different (if you play more than one note at a time).**
  This is similar to playing a guitar chord through a distortion effect, for example.
- **You can patch in external effects between the oscillators and the filters.**
  Just connect an oscillator output to the input of the effect device, and the effect output to the Malströms's audio input.
- **You can use combinations of connections and routing. You could for instance connect an external audio signal to one of the inputs, one of the Malström's oscillators to the other input and then use the routing options on the front panel for the other oscillator. All of these signals will then be mixed and sent to the Malström's main outputs.**

Chapter 36
MIDI Out Device

Introduction



The MIDI Out Device is designed for controlling external MIDI instruments, i.e. instruments that live outside of Reason. These could be other software synths or external hardware instruments that are hooked up to a MIDI interface on your computer.

The MIDI Out Device is treated like any other instrument device in the Reason sequencer, including Note Lanes and automatable controls. One exception, though, is that the MIDI Out Device does not produce any sound of its own; it has to be routed via MIDI Out to an external MIDI instrument.

Using the MIDI Out Device

Setting up for controlling an external MIDI instrument

! **To be able to control external MIDI instruments from Reason it is required that you have installed a MIDI interface on your computer. Refer to the documentation of your specific MIDI interface for installation instructions.**

1. **Connect your external MIDI instrument to the MIDI interface on your computer: MIDI Interface MIDI Out to MIDI instrument's MIDI In.**
   If you want to play and/or record MIDI from your MIDI instrument to Reason, connect your instrument's MIDI Out to your computer's MIDI In as well, see "Recording MIDI Controller automation from the controlled MIDI instrument".

! **If you are using the same MIDI instrument also as MIDI Master Keyboard for Reason, you will need to set it to "MIDI Local Off". Otherwise you will get doubled notes when you play your MIDI instrument.**

▶ **To be able to hear your external MIDI instrument in Reason, connect your instrument's audio output(s) to the desired audio input(s) of your audio interface. Then, create an Audio Track, select the appropriate audio inputs and make sure the Monitor button on the Audio Track in the sequencer is on.**



2. **Create a MIDI Out Device from the "Instruments >" sub-menu in the Create menu or from the Instruments palette in the Browser.**
   The device is created in the rack and a track is automatically created in the sequencer.

! **Make sure that the MIDI instrument controlled by the MIDI Out Device device does NOT transmit the MIDI data back to Reason (e.g. via "MIDI soft through" or "MIDI throughput"). This could cause MIDI feedback loops that could result in MIDI overflow in Reason.**

   Refer to the user manuals for your MIDI instruments for information on how to set the instruments to MIDI Local Off and how to prevent MIDI feedback loops.

3. **Select the desired MIDI Port from the drop-down list to the right of the display.**



   All MIDI Ports that are currently available for Reason on your computer are displayed in the list.

4. **Click the up/down MIDI Channel arrow buttons to select the MIDI Channel your external MIDI instrument is set to receive on.**



The selected MIDI Channel number is shown in the display.

5. **Select the MIDI Out Device track in the sequencer.**
Now, you should be able to play your external MIDI instrument from your Master Keyboard.

! **If you get problems with "hanging" notes, press [!] to send out an "All Notes Off" command on the MIDI port.**

The "MIDI: Send All Notes OFF" command can also be found in the Options menu.

Controlling the sound of your external MIDI instrument



Besides the keyboard note control, you can also control the sound of your external MIDI instrument by using the Pitch (bend) and Mod (wheel) controls, as well as Keyboard Velocity and Aftertouch.

How your sound responds to these controls is totally dependent on how the sound was programmed in your external instrument. For example, Pitch Bend range, Mod Wheel modulation destination, Velocity and Aftertouch modulation need to be defined on your external MIDI instrument.

Using MIDI Program Change

The Program Change MIDI message is used for selecting the desired sound/program/preset on MIDI instruments that have memory locations for stored sounds. The MIDI Out Device has a dedicated control for this, the Program control.

1. **Click the On button to activate the MIDI Program Change function.**



2. **Click the up/down arrow buttons to select the Program number that corresponds to the sound you want to recall on your external MIDI instrument.**



As soon as you load your Reason song, the MIDI Out Device will automatically send out the selected MIDI Program Change message on the set MIDI Port. This ensures that your connected instrument will play the correct sound/program/preset.

Automating MIDI Program Change

If you like, you can automate the Program parameter to change sound/program/preset of your external instrument during playback of your Reason song.

1. **Right-click the Program up/down buttons, or the display, and select "Edit Automation".**
   This creates a separate Program Change automation lane in the sequencer track.
2. **Now, you can edit the Program Change lane in the sequencer and insert Program Change automation points wherever you like in your song.**

! **It's recommended to place the Program Change automation points slightly before the positions where you want the new sound/program/preset to appear in your song. This is to allow for the time it takes to load the new sound in your external instrument.**

A note about MIDI Bank Select

The MIDI Bank Select message is used for selecting specific banks of sounds/programs/presets in MIDI instruments that feature several sound banks.

There is no specific panel control for MIDI Bank Select in the MIDI Out Device. However, you can use the regular MIDI Controller automation described below for inserting Bank Select automation points. MIDI Bank Select normally uses MIDI CC #0 and/or #32. Refer to the MIDI documentation of your specific instrument for details.

! **Note that MIDI instruments that have several banks of sounds usually expect a Bank Select message to be immediately followed by a Program Change message in order to change the bank and program/preset. In these situations, sending only a Bank Select message - without a subsequent Program Change message - will not change anything.**

! **Note that Reason only sends out MIDI CC data when they actually change. This means that you might have to send a different "temporary" MIDI CC value just before you send the actual MIDI CC value. For example, if you want to resend the value "1" for MIDI CC#32, first send another value (e.g. "0" or "2") and then send the value "1" immediately afterwards. You can do this by adding and/or moving automation points in the automation clip for MIDI CC#32 in the sequencer, see "Editing parameter automation".**


Recording MIDI Controller automation

Besides automation of the panel controls, the MIDI Out Device allows you to record automation of MIDI Controllers 0-119. Each recorded MIDI CC# shows up on separate automation lanes in the sequencer and can be edited in the same fashion as regular "internal" parameter automation.


Recording MIDI Controller automation from the MIDI Out Device

To record MIDI CC# automation from the MIDI Out Device, proceed as follows:

1. **Select the desired MIDI CC# by dragging up/down in the CC display.**




2. **Click Record in the sequencer and record the automation by turning the Offset knob.**



An automation lane, named according to the selected MIDI CC#, is created on the sequencer track and automation points are inserted as you turn the Offset knob. When you stop the sequencer, the Offset knob displays a green automation frame.

3. **To record automation of another MIDI CC# parameter, select the desired MIDI CC# by dragging up/down in the CC display (the same display as in Step 1 - or the display below it).**



The green automation frame around the Offset knob disappears as soon as you select a non-automated MIDI CC#. If you drag back to the automated MIDI CC#, the automation frame appears again around the Offset knob.


4. **Repeat steps 1-2 for every new MIDI CC# you want to record.**
A new parameter automation lane is added on the sequencer track for every new MIDI CC# you record.

- **You could also draw parameter automation points in parameter automation clips the same way as with internal Instrument devices in Reason, see "Automation editing".**


Recording MIDI Controller automation from a Remote control surface

If you have a MIDI keyboard or control surface with knobs or sliders, you can use these to control parameters on your MIDI instrument and record automation. This is done using Remote Override Mapping:


1. **Select the first MIDI CC# you want to control by dragging up/down in the CC display.**



2. **Right-click the Offset knob and select Edit Remote Override Mapping... .**




3. **Move a knob or slider on your controller.**
   Reason automatically detects which knob/slider you move and assigns this to the selected MIDI CC#:



Knob 1 on the control surface assigned to MIDI CC#7.

4. **Click OK.**
   You have now mapped that knob or slider to the MIDI CC# you selected in step 2.
5. **Repeat the procedure from Steps 1-4 to assign more MIDI CC# to other knobs/sliders of your keyboard controller.**
   This way you can map all the controls on your keyboard or control surface to different MIDI CC# if you like.

! **Note that dragging in the same display to select a new MIDI CC# will not erase the previous assignment(s) - only add an additional MIDI CC#:**




When you're done mapping, you can record parameter automation by clicking Record in the sequencer and moving the assigned knobs and sliders on your MIDI keyboard/control surface.

Recording MIDI Controller automation from the controlled MIDI instrument

If your MIDI instrument has a panel with knobs/buttons/sliders etc. that can send MIDI Controller data, you might want to record the MIDI CC# automation from that panel instead of from Reason or from your control surface. To be able to do this, you have to add your MIDI instrument as a MIDI Control Keyboard in Reason. This can be done as follows:

1. **If you haven't already, connect a MIDI cable from your MIDI instrument's MIDI Out to a MIDI In jack on your computer's MIDI interface.**
2. **Make sure you have set your MIDI instrument to "MIDI Local Off" as well as disabled any MIDI "soft thru" so that you don't get any MIDI feedback loop.**
   Refer to the documentation of your MIDI instrument on how to do this.
3. **Open the Settings dialog and click the MIDI tab.**
4. **Click the Add Manually button.**

5. **Select <Other> from the Manufacturer drop-down list:**




Selecting "<Other>" as Manufacturer automatically activates the generic MIDI map, which is designed to detect standard MIDI Note and Controller data, regardless of instrument model.

- **If your MIDI instrument has a keyboard, select "MIDI Control Keyboard" from the Model: drop-down list.**
  This way, you will be able to play MIDI Notes from your instrument as well as sending MIDI Controller data.
- **If your MIDI instrument is a rack instrument (without a keyboard), select "MIDI Control Surface" instead.**


6. **Select the appropriate MIDI Input from the "MIDI Input" drop-down list.**
   Alternatively, click the "Find" button and turn a knob on your MIDI instrument. Reason will then auto-detect the correct MIDI In port and automatically select it.

7. **Click OK.**
   Now, your MIDI instrument is shown in the "Remote keyboards and control surfaces:" list along with your other assigned control surfaces (if any).

! **Make sure the "Enabled" and "Master Keyboard" check boxes are selected and that the check marks are present.**



8. **Now, select the MIDI Out Device track in the sequencer and click the Record button on the Transport Panel.**
   If you turn or press a panel control (knob, slider, button, etc.) on your MIDI instrument during recording, each parameter will automatically create a new automation lane and record the corresponding MIDI CC data in a parameter automation clip, just like when you record parameter automation from an internal instrument device:



Parameter automation recording from three knobs on the MIDI Out Device panel.

! **You might have to edit the parameter automation clips afterwards and set appropriate Static Values etc., see "Editing parameter automation in the Edit Area".**

Modulating MIDI Controllers from CV signals

The MIDI Out Device features eight CV inputs for routing modulation signals from the rack to MIDI CC# of your choice.

1. **Flip the rack around and connect some modulation sources to the desired CV inputs:**




2. **Flip the rack back to the front and click the On button to activate the CV IN section:**




CV signals routed to any of the four CV IN pairs are indicated by lit LEDs:




3. **Click to select which CV IN pair to edit:**




4. **Drag up/down to select the desired MIDI CC# to route the CV modulation signals to:**



5. **Turn the Scale knobs to change the modulation range, from static (0-0) to full (0-127):**



6. **Turn the Offset knobs to change the modulation offset (0-127):**



The modulation level(s) are shown in the CC Output displays:



7. **Repeat steps 3-6 to assign and set up the other CV IN pairs.**

- **CV can be bipolar (have negative or positive values) but MIDI CC values are always positive. Any negative CV values will be truncated to zero when converted to MIDI CC. To preserve the shape of e.g. a modulation LFO, you can use the Scale and Offset controls to convert the bipolar CV (going between -127 and +127) to a MIDI CC going between 0 and 127. In that case, set both Scale and Offset halfway up.**
- **You can also use the Offset knobs for manually setting MIDI CC values without anything connected to the CV inputs.**

- **The CV Input ON button enables CV inputs. Turn this off if you want to make manual settings, select MIDI CCs etc, without the values being modulated by CV.**

Connections



Sequencer Control

The Sequencer Control CV In and Gate In inputs allow you to play the MIDI Out Device from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV In controls the note pitch, while the signal to the Gate In delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and ModWheel parameters.

CV In to MIDI CC Out

These eight CV inputs can be used for modulating the desired MIDI CC#. The affected MIDI CC#s are defined on the front panel, see "Modulating MIDI Controllers from CV signals".


Tips & Tricks

Audio recording of MIDI controlled external instruments


At some point you will probably want to record the audio from your MIDI controlled instrument onto an audio track in the Reason sequencer. The example below assumes that you have already recorded the note clips that control your MIDI instrument on an MIDI Out Device track in the sequencer.

! **Depending on how you are monitoring the audio when you are recording, there will be different audio latency times, see "Latency Adjustment".**

1. **If you haven't already, connect your MIDI instrument's audio output(s) to the desired audio input(s) on the audio interface you are using with Reason.**
2. **Create an Audio Track in the sequencer.**
3. **Select the appropriate audio interface input(s) in the "Select Audio Input" drop-down list in the sequencer track list:**




4. **Play back the song and adjust the audio level on your external MIDI instrument and/or the audio interface gain.**
   To be on the safe side, leave around 12dB of headroom below the clipping level (first yellow LED lit on the Input Level Meter on the Audio Track):



- **You might also have to move (or nudge) the MIDI clips on the MIDI Out Device track back slightly to compensate for any MIDI latency. Alternatively, you could slide all the notes in the clip back using the ReGroove Mixer, see "Using the ReGroove Mixer for MIDI latency compensation".**
- **If you don't want to adjust the MIDI notes beforehand to compensate for MIDI latency, you could move all Slice Markers in the audio clip after recording (see the tip below) or try quantizing the audio clips.**
  MIDI latency mainly occurs in the MIDI interface and in the connected MIDI instruments and is nothing Reason can automatically compensate for. Refer to "Moving clips" for more information.

5. **Make sure the Audio Track is enabled for recording and then click Record in the sequencer to start recording the audio from your MIDI instrument.**



6. **When you are finished with the audio recording, click Play to play back the recorded audio.**

! **If you are monitoring your external instrument externally, you will want to mute the MIDI Out Device track so that you don't get double notes or phasing problems during playback.**

If you are monitoring your external instrument only internally in Reason, there is no need to mute the MIDI Out Device track. During playback, the monitor function on the audio track is automatically disabled, and only the recorded audio on the audio track is output.

- **If you are experiencing problems with MIDI latency, i.e. the audio is recorded a little late in the audio clips, a good thing to try is to quantize the audio clips after recording, see "Quantizing audio".**
- **If quantizing the audio clip isn't applicable (e.g. due to playing style or type of sound), open the clip inline, select all Slice Markers and move them slightly to the left in the clip (with Snap off) so that the first note/beat aligns with the clip start. See the last example in "Selecting Slices and Slice Markers" for info about selecting and moving Slice Markers.**

Using the ReGroove Mixer for MIDI latency compensation

If you are experiencing MIDI latency when playing back recorded MIDI notes to your external instrument, you can compensate for this by using the Slide function in the ReGroove Mixer. This way you won't have to move or nudge the note clip(s) back before recording your external instrument onto an audio track in Reason.


1. **Set up your external instrument according to the descriptions in steps 1-4 in "Audio recording of MIDI controlled external instruments".**
2. **Make sure the Monitor button on the audio track is on.**




3. **Assign a ReGroove channel to the MIDI Out Device track.**
   In this example we use ReGroove channel A1.



4. **Make sure Click is on in the sequencer.**



5. **Play back the song and turn the Slide knob in channel A1 of the ReGroove Mixer counter-clockwise until your external instrument plays back in sync with the sequencer click.**




! **Note that the Ticks value you set with the Slide knob is tempo dependent. This means that if you raise the Tempo in the sequencer you will have to set the Slide knob to a lower (more negative) value to maintain the sync - and vice versa.**

6. **Before you begin recording onto the audio track there is one important thing to keep in mind:**

! **If there are MIDI notes present exactly on the note clip start position you have to begin the audio recording before the note clip's start position.**

Since all notes in the note clip have been (invisibly) slided back by the ReGroove Mixer, it means that the first notes could be located before (outside) the note clip. To be able to record also these first notes, the audio recording have to begin before the note clip's start position. If your MIDI Out Device note clip is placed at the very beginning of the song you will have to move all clips forward in the sequencer, so that the audio recording can begin earlier.

7. **Record your instrument onto the audio track.**
After recording, the audio should be on the track with perfect timing.



Chapter 37
Mimic Creative Sampler

Introduction



The Mimic Creative Sampler is a powerful yet very straight-forward sampler, tailor-made for quick and easy triggering, chopping and manipulation of samples. It features eight sample slots, where each slot can hold one sample. Each slot also has its own complete synth parameters setup, with pitch controls, filter, envelopes, LFO and effects.

You could either load a sample from your computer or sample straight into Mimic (Reason stand-alone only). You can then select various sample playback modes and high-quality stretch algorithms to manipulate and process the audio. You could also use Mimic as a traditional sampler and just play back samples in a regular "tape-style" fashion.

Mimic also features a great-sounding "lo-fi style" multi-effect to spice up your sounds even more.

Don't forget to check out the Mimic video tutorial here!

Panel overview


The Mimic front panel contains the following sections:



The Mimic front panel sections.

- **1. MIDI Note On LED.**
- **2. Patch selector (for browsing, loading and saving patches).**
- **3. Master Volume controls.**
- **4. Playback Mode section.**
- **5. Slot selector.**
- **6. Sample section (for sample loading/sampling and sample playback functions).**
- **7. Playback Start Position, Speed, Stretch and Slices sections.**
- **8. Performance and "play" controls.**
- **9. Pitch section.**
- **10. Filter section.**
- **11. Envelopes section.**
- **12. LFO section.**
- **13. Amp section.**
- **14. Compressor, Effects and EQ sections.**

Signal flow




Mimic signal flowchart.

- **Mimic features eight Slots, where each Slot holds a complete configuration of sample parameters and panel parameter settings.**
  Each Slot features a Sample section, where you can load your sample - or sample your own (Reason stand-alone only). You can then select if you want to play back the sample as Slices or Pitched (chromatically). You can also choose among various sample Stretch algorithms. The signal is then routed through a complete configuration of synth parameters, such as Pitch, Filter, Amp and Effects.
- **Depending on the selected Slot Mode, the signals from the Slots are be routed a bit differently.**
  In Pitch Mode and Slice Mode, only one single Slot can be played back at a time.

  In Multi Slot Mode and Multi Pitch Mode you can play back up to eight Slots simultaneously.
- **The synth sections in Mimic's eight Slots are described in "Panel reference".**

Playing and using Mimic

Loading and saving patches



A Mimic patch contains the parameter settings for all used Slots, i.e. up to eight complete parameter setups. Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

! **Like with the other sampler devices in Reason, the patch does not include the actual sample - only a reference to it. Therefore, the sample has to be stored separately (self-contained with the song, or already on disk or in a ReFill on your computer).**

Global output controls



Master Volume

This is the main stereo output volume control and controls the volume of all eight Slots together.

Slot Mode




Mimic has four Slot Modes, which defines how the sample of each Slot should play back - and also if you can use one or several Slots simultaneously:

Pitch Mode



In Pitch Mode you select one of the eight Slots for melodic playback (playing the sample from the start to the end locators). The sample can then be played chromatically pitched over the entire keyboard range.


Slice Mode



In Slice Mode you select one of the eight Slots for playback, and slice a (longer) sample, manually and/or automatically. The slices are then triggered from the keyboard (chromatically, with the leftmost slice playing back from note C1) without affecting the original pitch of the sample. See "Slices" for more details.

Multi Slot Mode


In Multi Slot Mode different keys (C-G in each octave) triggers Slots 1-8 (from the start to the end locators), drum-machine style - without affecting the sample pitches. This is displayed in the Note/range indicator as follows (the currently selected Slot is high-lighted on the keyboard - the others are dark blue):



Multi Slot Mode with samples loaded in Slots 1-4.


▶ **Multi Slot Mode works great with pad controllers.**

Multi Pitch Mode



Multi Pitch Mode with samples loaded in Slots 1-4, played back in a layered fashion.

In Multi Pitch Mode you can play back up to eight samples (one sample per Slot) simultaneously, for melodic playback (playing the sample from the start to the end locators). You can set different keyboard ranges (overlapping and/or adjacent) for the eight Slots and then play back the samples chromatically pitched. You can set the desired keyboard range in the Note/range indicator as follows (the currently selected Slot is high-lighted on the keyboard - the others are dark blue):



Setting the key range for the currently selected Slot.

1. **Click the desired Slot button (see "Slot Select" below) to select it.**
2. **Drag the left and right note range markers to set the desired note range.**
   The minimum "range" for a Slot is one note.
3. **Click another Slot button and set a new desired note range.**

▶ **Note that Slots can have overlapping note ranges (also completely overlapping so that you could play all eight Slots together in a layered fashion).**

Slot Select



Mimic has eight Slots, which can hold one sample each. Each Slot also has a complete parameter setup on the Mimic front panel, so each slot can have its own unique parameter configuration.

▶ **Click the desired Slot Select button to bring up all parameters for that slot, including the sample and its settings.**

! **Note that in Pitch Mode and Slice Mode (see above), only one single Slot can play back its sample at a time (as indicated by the grayed out waveforms below the other Slot Select buttons).**

Performance and "play" controls

Each of the eight Slots has their own individual set of performance/play controls on the front panel:



Porta

Portamento makes note pitches glide from previous notes to new ones, at the time set with the Time knob. Portamento can be used in all Key modes (see above).

- **When On in Poly Key Mode (see below), the pitches will glide from any of the available voices.**
  The results will be unpredictable since there is no way of controlling from which note(s) the glide(s) will commence. The effect is very nice, though.
- **When On in Mono Retrig or Mono Legato Key Mode (see below), the pitch will glide between consecutive notes.**
- **In Auto mode, the pitch will glide between consecutive monophonic notes only when you play legato. If you have selected Poly Key Mode (see below), Auto will have no effect at all.**
  If you release the previous key before hitting the new key, there will be no portamento effect.

Key Mode

Here you choose how Mimic should respond to MIDI Note data:

- **Poly**
  Select this if you want to play Mimic polyphonically.
- **Mono Retrig**
  Select this if you want to play Mimic in monophonic mode and always retrigger the envelopes as soon as you play a new note.

- **Mono Legato**
  The Mono Legato mode is also monophonic. However, if you play a new note without having released the previous one, the envelopes and sample playback position won't start over.

▶ **Also see the description of the "Global Position", which allows new notes to continue playing at the current sample playback position (and not restart playback).**

Pitch Range

▶ **Set the desired Pitch Bend range for the "Pitch Bend" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
Range: +/-24 semitones (+/-2 octaves) in steps of +/-1 semitone.

Pitch Bend

The Pitch Bend wheel can be used for bending note pitches up and down. Mimic also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch Bend Range with the "Pitch Range" control above the Pitch Bend wheel.

! **Note that if you have selected the Tape Stretch algorithm (see "Tape"), pitch bending the sample will also affect its playback speed.**

Mod Wheel

The Mod Wheel can be used for modulating a number of parameters in the eight Slots of Mimic. Use the Mod Wheel as a source parameter for the panel parameters that feature modulation source drop-down selectors.


LFO Scale

The LFO Scale knob can be used for scaling the LFO amount with the Mod Wheel - perfect for gradually introducing Vibrato effects, for example. If the LFO Scale knob is set to 100% the LFO Amount will be 0 when the Mod Wheel is at 0. See "The LFO section" for more details about the LFO.

Panel reference

The Sample section

Here is where you load/sample the audio for the currently selected Slot. The Waveform display differs somewhat, depending on which Slot Mode you have selected (see "Slot Mode").



A sample loaded in a Slot with Slice Mode selected.

Loading/sampling

- **Load a sample using drag & and drop, or by clicking the Browse sample button, or by using the Up/Down buttons to scroll and load a sample from the currently selected folder.**
- **Drag a sample from the browser and drop on a Slot Select button, to load the sample in the desired Slot.**
- **Alternatively, sample straight into Mimic by clicking the Start sampling button (Reason stand-alone only):**



See the "Sampling" chapter for more information about setting up and using Reason for sampling.

! **It's possible to load/sample stereo signals. However, the waveform will always be displayed as a mono signal, regardless if it's mono or stereo.**

Root Key

A sample is automatically analyzed for its original pitch at the Sample Start position. The analyzed pitch is displayed in the Root Key section. If you move the Sample Start marker, the sample is automatically re-analyzed.

- **Click the "SET" button to use the analyzed Root Key.**
  This will automatically place the analyzed Root Key on the correct note on the keyboard, as indicated by an orange key in the Note/range indicator below the Waveform display.

▶ **Alternatively, set the Root Key manually by dragging up/down in the "Root" and "Tune" (cent) boxes:**




! **Note that the Root Key function only works in Pitch Mode and Multi Pitch Mode.**

Setting the sample range

First you could decide how much of the original sample you want to use - and where in the sample you want to work:


▶ **Zoom and/or scroll in the Sample Overview to define the Sample range you want to work in.**



To scroll, click and drag sideways between the dark yellow sample range markers. To zoom, click and drag any of the sample range markers sideways. The set Sample range is automatically updated and displayed in the waveform display.

▶ **To work in the entire Sample range, drag the left Sample range marker all the way to the left, and the right Sample range marker all the way to the right, in the Sample Overview.**


Zooming in the Waveform Display



▶ **Click and hold the mouse button anywhere in the waveform display, then drag down to zoom in, and up to zoom out in the waveform.**

▶ **Dragging sideways in the Waveform Display will scroll left/right.**

Setting the sample start and end



▶ **Drag the Start and End marker handles to where you want the sample to begin and stop playing back.**
Note that the Start and End markers cannot be set in reversed order. If you want to play the sample backwards, from the End marker to the Start marker, click the Reverse button (see "Reverse").

- **If you drag and move the Start/End marker up into the Slice Marker area above the waveform, the Start/End marker will snap to the closest slices. This works in all modes, not just in Slice Mode:**



- **Alternatively, double click in the Waveform Display to position the Start marker. Hold down [Shift] and double click to position the End marker.**

Previewing samples

- **Preview the sample by holding down [Option]/[Alt] and clicking at the desired position in the Waveform Display.** The sample will play back for as long as the mouse button is depressed.
- **It's possible to automate the sample start and end settings, see "Automating the sample Start and End markers".**

Loop and Loop Length



It's also possible to loop (Forward Loop) samples - or slices in Slice Mode. The loop always happens at the end of the sample/slice. In all modes except for Slice Mode the Loop Length is visually indicated with a transparent red region in the Waveform Display, so you can see exactly where the loop is.

- **Enable Loop by clicking the Loop LED.**
- **Adjust the Loop Length by turning the Length knob, or by holding down [Command]/[Ctrl] and clicking/dragging sideways in the waveform display:**



If you are playing back the sample reversed (see "Reverse") the looped region originates from the Start Marker instead and is displayed in transparent blue.

! **In Slice Mode the looped region is not indicated visually in the Waveform Display.**


Start Position



The Start Position section contains controls for determining where the sample/slice playback should begin, and in which direction the sample/slices should be played back.

Global Position

- ▶ **Click the Global Position LED to start the playback of new/additional voices from the global position, i.e. from where the red Position marker is currently positioned in the Waveform Display:**



This function is great for polyphonic rhythmic sounds, where you want to have all the voices synced in time.

If not active, new/additional voices will always start playing back from the blue Sample Start marker.

Reverse

- ▶ **Click the Reverse LED to have the sample/slices play back backwards, from the end to the start.**

Start Position Mod

- ▶ **Turn the Mod knob to set a modulation amount for the sample/slice playback start position.**
  Note that the Mod amount is bipolar (-/+) so that you can modulate the start position either earlier or later than the default start position.
- ▶ **Select a Modulation source from the drop-down selector, to modulate the sample/slice start position.**
- ! **The Start Position Modulation behavior also depends on the "Snap to Slices" setting described below.**

Snap to Slices

- ▶ **Click the Snap to Slices LED to always start the playback from a Slice Marker (and not from somewhere in between Slice Markers).**
- ! **Note that this function is only useful in when modulating the Start Position (see above) in Pitch Mode, Multi Slot Mode and Multi Pitch Mode, since the Start Position always snaps to slices in Slice Mode (see "Slice Mode").**

Speed and Speed Mod



The Speed control determines how fast the play position ("playhead") moves in the waveform.

Speed

- **Set the sample playback speed with the Speed knob.**
  Depending on which Stretch type (see "Stretch") is currently selected, the sonic result will vary. If you have selected the Tape Stretch type (see "Tape"), the Speed knob also affects the pitch. Note that the Speed can be set all the way down to 0%, i.e. "stop". Great for Tape Stop effects in Tape mode and for static playback in other Stretch types, for example.

Speed Mod

- **Modulate the Speed with the Mod knob.**
- **Assign a modulation source from the drop-down selector next to the Mod knob.**
  For example, selecting an Envelope as a modulation source could cause the playback speed to start fast and gradually slow down when you hold a note - or vice versa.

Stretch



Mimic features five different Stretch types, which can be selected from the drop-down selector. Depending on the selected Stretch type, there are also some additional controls to modify the sample characteristics.

Tape



This is the good old "tape recorder" type, where speed and pitch are coupled. This means that to achieve a higher pitch you simply increase the playback speed of the sample/slices - and vice versa.

With the Tape stretch type selected, there is a Loop X-Fade knob present. This controls the crossfade amount when the Loop function is active for the sample/slices (see "Loop and Loop Length").

If Loop is off, the Loop X-Fade knob has no effect.

Advanced



This is a high-quality stretch algorithm suitable for most type of polyphonic and complex audio material.

With the Advanced stretch type selected, there is a Preserve Transients button present. Transients are regions in the sample where the level quickly goes from quiet to loud, for example in percussive hits and other types of "attacks".

- **Click the Preserve Transients button to preserve any transients in the sample/slices.**
  When off, any transients will be "smeared out" and less prominent, which might be desired in some situations.

Melody




This is the Melody stretch type used for audio in the Reason sequencer, i.e. a high-quality stretch algorithm suitable for monophonic audio material.

With the Melody stretch type selected, there is a Preserve Transients button present.

- **Click the Preserve Transients button to preserve any transients in the sample/slices.**
  When off, any transients will be "smeared out" and less prominent, which might be desired in some situations.
- **The Melody stretch type is well suited if you are using the Loop function (see "Loop and Loop Length"), since it usually reduces clicks/pops at the loop point.**

Vocal



This is the Vocal stretch type used for audio in the Reason sequencer, i.e. a high-quality stretch algorithm suitable for monophonic vocal audio material.

With the Vocal stretch type selected, there are two additional controls present:

- **Turn the Formant knob to change the formant of the sample/slices.**
  Turning this up will be like creating a smaller "body" for the sound, and turning it down will be like creating a larger body. If you are using a vocal sample, changing the Formant would be like changing the character from "adult" to "child" like.
- **Click the Fixed Pitch button to "auto-tune" the sample/slices to the currently played (note) pitch.**
  This is really cool for creating processed vocals that you could pitch from the keyboard.


Granular

This is a "vintage" type of digital pitch shift/stretch method, where grains of the sample are being looped and crossfaded.



The Granular stretch type utilizes playback of a series of snippets of audio data - grains - "extracted" from the sample. The grains could be of a selectable length and overlap. The grains could then be played back in a number different ways - with or without crossfades between the grains.

The picture below shows the basic principle of the Granular Stretch type:



An example of a signal generated from 5 grains of a sample.

Here is what happens in the example above:

- **The original sample at the top is used as base for the granular stretch.**
- **5 grains (of the same lengths and the same distances between them) are “extracted” from the original sample.** The distance between the grains is determined by the current sample playback speed. The grains could contain common audio data in some parts (like in the beginnings and ends in the example above).
- **The 5 grains are then placed after one another, partly overlapping each other.** The distance between the grains is determined by the playback rate.
- **When the grains are played back, big parts of the grains are played back together (since they are overlapping).** In the example above, there are also crossfades between the grains to make the overlaps smoother.

With the Granular stretch type selected, there are four additional controls present:

- **Control the grain lengths with the Length knob.** This sets the lengths of the grains. At 0% you get the shortest grains and the sound could be a little gritty at this setting. At 100% you get the longest grains.
- **Control how much the grains should overlap each other with the Overlap knob.** This sets how much the grains should overlap each other and also the crossfade amount. At 0% you get no overlap and almost no crossfade at all. At 100% you get the longest overlaps and also smooth crossfades between the grains.

- **Set the playback position deviation with the Jitter knob.**
  The Jitter function modulates the sample playback position minutely and randomly. The Jitter function can be great for generating "chorus"-like effects and to make a sound more "alive", depending on the other settings in the sound. At 0%, the timing and playback position is completely accurate and at 100% it is completely random.
- **Set how much you want the grains to be panned in the stereo panorama with the Spread knob.**
  0% means the signal will be unaffected and 100% means every other grain will be panned hard left and hard right. Great for nice and wide stereo effects!

Slices



This section is mainly useful when you are working in Slice Mode (see "Slice Mode").

- **Even though slices are the core of Slice mode, they are available in the other modes too. They can be used for snapping the Start position (see "Setting the sample start and end") - either when you drag it manually or when you modulate or automate it.**

Sensitivity

Slices are added automatically at transients according to the Sensitivity knob setting.

- **Turn the Sensitivity knob to increase or decrease the number of automatically detected slices.**
  Automatically generated slice markers are indicated in yellow.
- **In Slice Mode the number of available keys changes according to the number of slices in the loop. For example, if there are 10 slices in the loop, the first 10 notes (counted upwards from C1) are used. If the loop contains 15 slices, the first 15 notes are used, and so on:**



- **Note that the maximum number of slices that can be detected and used is 92 (from C1 to G8). If you are using a very long sample and a high Sensitivity setting, the detected slices might not cover the entire sample - only the first part. If you want to access slices further into the sample you might therefore have to move the Sample Start marker (or reduce the Sensitivity setting).**

Moving, adding and removing Slice markers

▶ **Drag the Slice markers sideways to move them:**



▶ **Add slices manually by double clicking in the Slice Marker lane directly above the waveform:**



! **Any manually moved/added slice markers are automatically indicated in a different color, which also means they are no longer affected by the Sensitivity knob.**

▶ **You can also click on a slice marker handle (without moving it) to deactivate it from the Sensitivity knob.**

▶ **Delete slice markers by double clicking the slice marker handles in the Slice Marker lane.**

Reset

▶ **Click the Reset button to restore the slices to the ones auto-generated by transient detection/Sensitivity.**
Any manually added slice markers will be removed.

Play Thru

▶ **Click the Play Thru LED to force the playback to continue beyond the following slice markers, for as long as the notes sustain.**
When Off, the playback will automatically stop at the next slice marker, even if you have sustaining notes.

Pitch



Semi

▶ **Set the pitch in semitone steps.**
Range: +/-24 semitones (+/-2 octaves).

! **Note that if you are using the Tape Stretch type (see "Tape"), the pitch settings also affect the playback speed.**

Tune

- **Changes the pitch in steps of 1 cent.**
  Range: +/- 50 cents (down or up half a semitone).

LFO

- **Sets how much the pitch should be affected by the LFO (see "The LFO section").**
  Range: +/- 100%.
- **By using the LFO Scale function (see "LFO Scale"), you can gradually introduce the LFO modulation amount by using the Mod Wheel.**

Pitch Mod

- **Sets how much the pitch should be modulated by the source assigned in the drop-down selector to the right.**
  Range: +/- 100%.


The Filter section



The Filter section features eight different filter types.


Filter Type selector

- **Click the Filter type drop-down selector to choose any of the following filter types:**
- **LP 24**




This is a standard 24dB/octave lowpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.

- **HP 24**




This is a standard 24dB/octave highpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.

- **LP 12**




This is a standard 12dB/octave lowpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.

- **BP 12**




This is a standard 12dB/octave bandpass filter. Set the center frequency with the Freq knob and the resonance amount with the Reso knob. Note that raising the resonance also makes the passband narrower.

- **HP 12**




This is a standard 12dB/octave highpass filter. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob.

- **Notch**




A notch filter (or band reject filter) could be described as the opposite of a bandpass filter. It cuts off frequencies in a narrow midrange band, letting the frequencies below and above through. Set the center frequency with the Freq knob and the notch width with the Reso knob. The higher the Resonance, the narrower the notch.

- **Comb -**



This is a comb filter with a positive feedback loop - but without feed forward - ideal for flanger and phaser types of effects. Set the cutoff frequency with the Freq knob and the resonance amount with the Reso knob. The difference between "Comb +" (see below) and "Comb –" is in the position of the peaks in the spectrum. The main audible difference is that the "Comb –" version causes a bass cut.

- **Comb +**



This is a multi notch filter, great for phaser types of effects. Set the cutoff frequency with the Freq knob and the attenuation amount - and consequently the bandwidth - of the notches with the Reso knob. The difference between "Comb +" and "Comb –" (see above) is in the position of the peaks in the spectrum. The main audible difference is that the "Comb +" version lets through more bass frequencies.

Freq

▶ **Set the cutoff frequency (for the HP and LP filter types) or the center frequency (for the BP and Notch filter type).** Range: 37.0 Hz to 16.00 kHz.

Reso

▶ **Set the resonance amount.**

Drive

- **Set the amount of overdrive distortion in the filter.**

Kbd

- **Set how much you want the filter cutoff/center frequency to track the keyboard.**
  At 0%, the filter frequency is static regardless where on the keyboard you play. At 100% the filter tracks the keyboard 1:1, i.e. one semitone per note.

Vel

- **If you want the Filter Envelope amount to be controlled from keyboard velocity, turn up the Vel knob.**

Env

- **Set the cutoff/center frequency modulation amount from the Filter Envelope (see "The Filter Envelope and Amp Envelope sections").**
  Range: +/- 100%.


Freq Mod

- **Select a modulation source, for modulating the filter cutoff/center frequency, from the drop-down selector.**
- **Set the desired modulation amount with the Mod knob.**
  Range: +/- 100%.

The Filter Envelope and Amp Envelope sections



The Filter Envelope and Amp Envelope feature standard ADSR envelopes that control the modulation amounts of the respective destinations (the Filter Freq and the Amp Gain). The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

A(ttack)

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the maximum frequency value (Filter Envelope) or Gain level (Amp Envelope). How long this should take, depends on the Attack setting. If the Attack is set to "0", the maximum Freq/Gain value is reached instantly. If the Attack value is raised, it will take longer time before the maximum Freq/Gain value is reached.

D(ecay)

After the maximum Freq/Gain value has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.

S(ustain)

The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the frequency/volume of the sound is never lowered.

If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to the maximum Freq/Gain value, then gradually decreases to finally land to rest on a level somewhere in-between zero and the maximum Frequency/Gain value. Note that Sustain represents a level, whereas the other envelope parameters represent times.

R(elease)

The Release parameter works just like the Decay parameter, except it determines the time it takes for the Freq/Gain to drop back to zero (or to the set Freq value) after you release the key.

The LFO section



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of a signal to produce vibrato, but there are countless other applications for LFOs.

The LFO section features one general purpose LFO, which can be assigned to control selectable parameter(s) in other sections on the front panel.

- **By using the LFO Scale function (see "LFO Scale"), you can gradually introduce the LFO modulation amount by using the Mod Wheel.**

Wave

- **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by click-holding in the display and dragging up or down.**
  Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.

Rate

- **Set the LFO frequency with the Rate knob.**

Key Sync

- **Click the Key Sync button to restart the LFO at every new Note On.**

Beat Sync

- **Click the Beat Sync button to sync the LFO to the main sequencer Tempo.**
  The Rate parameter now controls the time divisions.

Delay

- **Turn the Delay knob to introduce a delay before the LFO modulation kicks in after a note is played.**
  Turn clockwise for longer delay times.

The Amp section



Gain

- **Set the desired maximum level for the Amplifier with the Gain knob.**
  This is the maximum level the envelope will reach after the Attack stage is completed (see "A(ttack)".).

Vel

- **If you want the Gain level to be controlled from keyboard velocity, turn up the Vel knob.**

Gain Mod

- **Assign a modulation source in the drop-down selector to the right. Then, control the modulation amount with the Mod knob.**
- **If you want to create a tremolo effect, select the LFO as Source in the drop-down selector.**

Pan

- **Set the panning of the output signal from the Amplifier in the stereo panorama.**

Pan Mod

- **Assign a modulation source in the drop-down selector to the right. Then, control the modulation amount with the Mod knob.**
- **Since Pan works individually per voice, you can assign e.g. Keyboard Velocity, an Envelope or "Random" as source to create cool panning effects.**

The Compressor



This is a Compressor, which can be used for compressing the signal and evening out the signal levels.

- **Turn the Squeeze knob to set the compression amount.**
  The red LED above the knob indicates the signal compression.

The Effect section



The Effect section features seven types of distortion/modulation effects, to spice up your sound.

- **Select the desired Effect algorithm from the drop-down selector.**
  "Noise" adds noise to the signal (when a signal is present).

  "Reso Noise" adds resonant noise to the signal (when a signal is present).

  "Ring Mod" is a ring modulator effect.

  "Bitrate" gives the effect of sample rate reduction.

  "Lowres" combines sample rate reduction with bit depth reduction.

  "Sine Fold" is a sinewave shaping distortion.

  "Scream" produces a less bright type of distortion.

Effect Mod

- **Set the character of the selected effect algorithm.**

Mix

- **Set the mix between the dry signal and the effect signal.**

The EQ section



This is a Lo Cut and Hi Cut filter, which lets you cut out bass (lo cut) and treble (hi cut) frequencies from the sound.

Lo Cut

- **Turn up the Lo Cut knob to cut out bass frequencies from the signal.**
  Range: 20.0 Hz to 4 kHz.

Hi Cut

- **Turn down the Hi Cut knob to cut out treble frequencies from the signal.**
  Range: 200 Hz to 20 kHz.

The Send section



The Send knobs can be used for tapping the output signal of the Slot to the corresponding FX Send Out jacks on the rear panel (see "FX Send Out"). You could then route the signals to external effect devices and then further to a separate mixer/audio channel.

- **Control the Send output levels with the corresponding Send knobs.**

Connections



! **Remember that CV connections are NOT stored in the Mimic patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Mimic from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

CV In 1-4

These four assignable control voltage (CV) inputs can be used for modulating parameters on the Mimic front panel, by selecting "CV In" in the Mod drop-down selector for the desired parameter.

Slot Out 1-8

These outputs are breakout jacks for each individual Slot. Connect these to have the audio from the desired Slot(s) routed to its own stereo output pair.

! **Connecting any of the Slot Outs will automatically remove the corresponding Slot from the Master Audio Outs.**

FX Send Out

Here you can route the audio from all eight Slots to external effect devices for further processing. Since there are no FX Return jacks on Mimic, route the processed signal to a separate mixer/audio channel. You can control the Send level of each Slot with the respective Send knobs (see "The Send section").

Audio Output

These are the main audio outputs. When you create a new Mimic device, these outputs are auto-routed to the first available Mix Channel in the main mixer. If there is no Mix Channel available, a new one will be automatically created.

Tips and Tricks

Optimizing performance/DSP Load

Under some circumstances Mimic could be quite DSP demanding. If you experience any excessive DSP Load or playback problems, please check the following:

- **Try another Stretch Type (see "Stretch").**
  Especially the "Advanced" Stretch Type can be quite DSP consuming.
- **If you are playing high-pitched notes using a low-pitched sample, the stretch function has to calculate a lot. To reduce the workload, try loading a higher pitched sample (which has a higher Root Key) and use that instead.**
- **Try to avoid having a lot of notes decaying at the same time. Try shortening the Release time of the Amp Envelope (see "The Filter Envelope and Amp Envelope sections") and/or deactivating Play Thru in Slice Mode (see "Play Thru").**

Creating a "velocity layered" instrument

A neat way to simulate a velocity layered instrument is to sample the same note repeatedly, of let's say a bass or piano, and then modulate which of the recorded notes should play back. This will give you a more "live" and organic sound when you play. In this example we have sampled the same note of a bass guitar eight times in a single recording, played with a little different nuances between the eight picks:



1. **Make sure Pitch Mode is selected.**
2. **Click the "Snap to Slices" LED in the Start Position section.**
   Do this to ensure that the playback will start from a slice marker (and not from in between slice markers).
3. **Select "Velocity" in the Start Position Mod drop-down list and turn up the Start Position Mod amount.**
   We are now controlling which "slice" should play back from Keyboard Velocity. You can of course choose another modulation source (e.g. Mod Wheel) if you want to control the start position using the Mod Wheel instead.

- **Make sure you set the Amp Envelope "Release" time so that the consecutive "slice" doesn't play back.**

Extending the sample “tail” (without looping)

Sometimes it could be useful to extend the tail of a sample (a drum sample, for example), to have it decay longer than the original sample length. An easy way of doing this is by modulating the “Speed” parameter as follows:



1. **Turn down the “Speed” knob close to minimum.**
2. **Turn up the “Speed Mod” knob and select “Filt Env” as Speed Mod source.**
3. **Select the “Advanced” stretch type in the Stretch section.**
4. **Raise the Filter Envelope (D)ecay slider to the desired value.**
   When you play and hold a key down, the Speed will quickly raise and then slow down in the sample tail, making the playback time extend.

Automating the sample Start and End markers


Besides the regular modulation capabilities in Mimic, you could also automate and modulate the sample Start and End markers from the main sequencer, to have them reposition in real-time during sequencer playback. This could be useful if you have a longer recording/sample that you want to alter the playback position in:

1. **Record some notes on the Mimic sequencer track in the sequencer and then hit Stop twice.**
2. **Hit Record again in the sequencer and drag the Sample Start and Sample End markers during recording:**



- **If you like, drag and move the Start/End marker up into the Slice Marker area above the waveform, to have the Start/End marker snap to the closest slices. This works in all modes, not just in Slice Mode.**

3. **Hit Stop in the sequencer twice when you are done recording.**
   If you moved both the Sample Start marker and the Sample End marker you will now have two Parameter Automation lanes with clips on them on the Mimic sequencer track:



- **The clips on the Start Pos and End Pos lanes represent the movements of the Sample Start and Sample End markers respectively.**

Chapter 38
Monotone
Bass Synthesizer

Introduction



The Monotone Bass Synthesizer is a great little monophonic bass synthesizer, designed for seamless integration of Reason Compact projects. Despite its fairly small size, it's very versatile can produce really fat and punchy bass synth sounds.

Monotone features two oscillators, a 24 dB lowpass ladder filter, amp envelope and chorus and delay effects. It also has an LFO and an additional envelope for modulation purposes.

Panel overview

The Monotone front panel contains the following sections:




The Monotone front panel sections.

- **1. MIDI Note On LED.**
- **2. Patch Selector (for browsing, loading and saving patches).**
- **3. Master Volume.**
- **4. Voicing section and global controls.**
- **5. Oscillator section.**
- **6. Filter section.**
- **7. Amplitude Envelope.**
- **8. Chorus section.**
- **9. Delay section.**
- **10. Modulation section.**

Signal flow

The picture below shows the basic signal flow in Monotone:



Monotone signal flowchart.

- **The "heart" of Monotone is the Oscillator section, which generates the basic audio signal.**
  There are two oscillators in Monotone, that can produce a number of traditional "analog" waveforms - plus a Noise generator, which produces white noise. The two oscillators can be detuned, to create a fatter sound. Oscillator 2 can also frequency modulate Oscillator 1, for metallic/bell type sounds.
- **The signal from the Oscillator section is routed to the Filter.**
  The Filter in Monotone is a classic 24 dB/octave lowpass ladder filter, with overdrive control.
- **The signal from the Filter is routed to the Amplifier.**
  The Amplifier is controlled by a standard ADSR (Attack-Decay-Sustain-Release) envelope.
- **The signal from the Amplifier is then routed to the Chorus module.**
  This module generates a chorus effects, to make the sound fat and wide.
- **The signal from the Chorus is then routed to the Delay module.**
  Here you can add audio delay effects.
- **The remaining section in Monotone (Envelopes and LFO) can be used for modulating some Oscillator and Filter parameters.**

Playing and using Monotone

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global output controls



Master Volume

This is the main stereo output volume control.

Global performance and "play" controls



Portamento

Portamento makes the note pitch glide from the previous note to the new one, at the time set with the Portamento knob.

- **When On, the pitch will always glide between consecutive notes.**
- **In Auto mode, the pitch will glide between consecutive notes only when you play legato.**
  If you release the previous key before hitting the new key, there will be no portamento effect.

Retrig

- **Click the Retrig button if you want to play Monotone and always retrigger the envelopes as soon as you play a new note.**
  When Off, the envelopes will retrigger only if you have released the previous note before playing the new note.

Range

- **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
  Range: +/-24 semitones (+/-2 octaves) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Monotone also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "Range" control above the Pitch bend wheel.

Mod

The Mod wheel can be used for controlling the Filter Frequency and LFO intensity in Monotone.

- **Raise the FILT knob above the Mod wheel to set the Filter Frequency modulation amount.**
- **Raise the LFO knob above the Mod wheel to set the LFO intensity modulation amount.**
  Note that for the LFO modulation to work you need to already have some LFO modulation set in the Oscillator (see "LFO") and/or Filter (see "LFO") sections.

Panel reference

The Oscillator section



Here is where you choose oscillator waveforms and set the pitches for the two oscillators. You can also add noise and frequency modulate Oscillator 1 from Oscillator 2.

Waveform selector

- **Turn the Wave knob to select one of four wave shapes.**

The wave shapes are:

- **Ramp**
  Also known as sawtooth. Generates a rich tone with both even and odd harmonics (overtones).
- **Square (Pulse in Oscillator 2)**
  The square wave has a symmetric square shape and contains only odd harmonics. The Pulse wave is basically a square wave with non-symmetrical shape, i.e. a duty cycle that is not 50%. The Pulse wave generally sounds a little thinner than a perfect square wave.

- **Triangle**
  The Triangle wave also only contains odd harmonics, but at lower intensities than the square wave overtones. Every other harmonic is also phase-shifted by 180°. This makes it sound a little "rounder" and with less bite than the square wave.
- **Sine**
  The Sine wave doesn't contain any overtones - only the fundamental. This makes it sound dull and makes it perfect as a sub bass an octave or two below another waveform in the other oscillator.

Oct

▶ **Set the pitch in octave steps.**
Range: 5 octaves.

Osc Mix

▶ **Set the mix of the Oscillator 1 and 2 signals.**

Noise

▶ **Turn up the Noise knob to introduce white noise to the oscillator signal mix.**

Detune

▶ **Change the pitch in steps of 1 cent (in opposite directions for the two oscillators).**
Range: +/- 50 cents (down or up half a semitone).

LFO

▶ **Turn the LFO knob to introduce pitch modulation to both oscillators from the current setting of the LFO section (see "The LFO section").**

FM Env

▶ **Turn the knob to have the oscillator 2 signal frequency modulate the oscillator 1 signal according to the current Envelope settings (see "The Envelope section").**
Range: 0% (no tracking (constant pitch)) to 100% (1 semitone per note).

Osc 2 Semi


▶ **Set the pitch of Oscillator 2 in semitone steps.**
Range: +/-12 semitones (two octaves).

The Filter section



The Filter in Monotone is a classic 24 dB/octave lowpass ladder filter. If you raise the Resonance high enough, the filter will start to self-oscillate.

The picture below shows the lowpass filter's basic characteristics at four different resonance levels:



Drive


▶ **Turn the Drive knob to amplify and introduce an overdrive type of distortion to the signal fed into the filter.**

Freq

▶ **Set the cutoff frequency for the filter.**
The cutoff frequency is where the filter starts to cut out/dampen the higher frequencies of the signal.

Resonance

▶ **Set the resonance amount.**
This controls the resonance peak level at the currently set cutoff frequency (see "Freq" above).
The picture below shows a ramp oscillator signal lowpass-filtered at three different Resonance levels:



! **Be careful when using high Resonance values as this could generate quite loud audio levels!**

Env

- **Turn the Env knob to set the frequency modulation amount from the current settings of the Envelope (see "The Envelope section").**

Key

- **Turn the Kbd knob to set the keyboard tracking amount.**
  At 0% the filter cutoff frequency is static and doesn't track the keyboard at all.
  At 100% the filter cutoff frequency tracks the keyboard 1 semitone per note.

LFO


- **Turn the LFO knob to set the frequency modulation amount from the current settings of the LFO (see "The LFO section").**

The Amplifier section



The Amplifier section contains a standard ADSR envelope, which controls the amplitude of the audio signal.

The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

A(ttack)

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to max level. How long this should take, depends on the Attack setting. If the Attack is set to "0", maximum level is reached instantly. If the Attack value is raised, it will take longer time before the maximum level is reached.

D(ecay)

After maximum level has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.

S(ustain)

The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to max level, then gradually decreases to finally land to rest on a level somewhere in-between zero and maximum level. Note that Sustain represents a level, whereas the other envelope parameters represent times.

R(elease)

The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

Vel

- **Turn up the Vel knob if you want the maximum level to be controlled from Keyboard Velocity.**
  The harder you play, the louder the maximum volume.

Chorus



This is a stereo Chorus effect, which can be used for generating a fatter and wider sound.

Amount

- **Set the Dry/Wet amount of the chorus effect.**
  Set to 0% for a completely dry (unprocessed) signal.

Rate

- **Set the rate/speed of the chorus modulation.**

Spread

- **Set the stereo width of the chorus effect.**
  Set to 0% for a if you want the signal to be in mono.

Delay



This is a stereo delay, which generates delayed copies of the original signal.

Amount

- **Use this parameter to adjust the send level to the Delay effect.**
  Set to 0% for a completely dry (unprocessed) signal.

Time

The delay time is synced to the main sequencer tempo.

- **Set the sync division to the main sequencer tempo with the Time knob.**
  Range: 1/16, 1/8T, 1/8, 2/8T, 3/16, 1/4, 5/16, 4/8T, 7/16 and 2/4.

Feedback

- **Set the number of delay repeats.**

Ping Pong

- **Activate Ping Pong to have the delay repeats alternate between left and right in the stereo panorama.**

The LFO section



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of a signal to produce vibrato, but there are also other applications for LFOs. The LFO section features an LFO which can be set to control Oscillator pitch (see "LFO") and/or Filter frequency (see "LFO").

Rate

- **Set the LFO rate/speed.**
  Range: 0.06-94.0 Hz

Shape


- **Turn the Shape knob to select one of three LFO wave shapes.**
  The wave shapes are: Sine, Triangle and Square.

The Envelope section



The Envelope section features a standard ADSR envelope, which can be used for controlling Oscillator Frequency Modulation (see "FM Env") and/or Filter Frequency (see "Env").

The various envelope stages work exactly like those of the Amplifier, see "The Amplifier section".



The ADSR envelope stages.

A(ttack)

- **Set the time it should take to reach from zero to maximum level.**

D(ecay)

- **Set the time it should take to go from maximum level to the Sustain level (see below).**

S(ustain)

- **Set the level the envelope should rest at, after the Decay stage (see above).**


R(elease)

- **Set the time it should take to go from the Sustain level back to zero, after you have released the note.**

Vel

- **Turn up the Vel knob if you want the maximum level to be controlled from Keyboard Velocity.**
  The harder you play, the higher the maximum level.

Connections



! Remember that CV connections are NOT stored in the Monotone patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Monotone from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

Modulation inputs

These control voltage (CV) inputs and can be used for modulating the corresponding parameters from external modulations sources.

Audio Output

These are the main audio outputs. When you create a new Monotone device, these outputs are auto-routed to the first available Mix Channel in the main mixer. If there is no Mix Channel available, a new one will be automatically created.

Chapter 39
NN-XT Sampler

Introduction

The basic functions of the NN-XT are very similar to those of its sampler companion in the Reason rack - the NN-19 (see "NN-19 Sampler"). Just like the NN-19, NN-XT lets you load samples and create multi-sample patches by mapping samples across the keyboard. The sound can then be modified by a comprehensive set of synth-type parameters. There are however some major differences between the two. The NN-XT has:

- **Support for SoundFonts.**
  Presets and samples from SoundFont banks can be loaded and used in the NN-XT (see "Loading SoundFonts").
- **8 stereo output pairs.**
  This makes it possible to route different samples to different mixer channels for individual effect processing (see "Out").
- **The possibility to create layered sounds.**
  This is done by mapping several samples across the same keyboard range (see "Creating layered sounds").
- **The possibility to create sounds that only play over certain velocity ranges, velocity switched key maps and velocity crossfading.**
  See "Setting velocity range for a Zone".
- **Key maps with individual synth parameter settings for each sample.**
  See "Synth parameters".

Even though the NN-XT is a more advanced sample player than NN-19, it should not be considered as a successor to the NN-19, but rather as a complement to it. The NN-19 will for example probably still be the sampler of choice for those of you who want to be able to quickly load a couple of samples and start playing, since that particular aspect takes a little more doing with the NN-XT.

Sampling in NN-XT

The sampling procedure is generic for all devices that can sample (NN-19, NN-XT, Redrum and Kong). The sampling and sample editing procedures are described in detail in the "Sampling" chapter.

- **To sample your own sound and automatically load it into the NN-XT device, click the Sample button.**



Refer to the "Sampling" chapter for details on how to set up and use the sampling feature.

Panel overview

The main panel

When the NN-XT is added to the rack, you will initially only see the main panel.



The NN-XT main panel.

The main panel is where you load complete sample patches. It also contains the "global controls". These are controls that affect and modify the sound of entire patches rather than the individual key zones.

The Remote Editor panel

To show/hide the remote editor panel, use the fold/unfold arrow at the bottom left.



The remote editor panel is where you load individual samples, create key maps, modify the sound of the samples with synth parameters etc.

! **The main panel of the NN-XT can be folded like any other Reason device. Note that folding the main panel will also fold the remote editor regardless of its current state.**

Loading complete Patches and REX files

As previously alluded, you can load complete sample patches as well as individual samples into the NN-XT.


- **A patch is a complete "sound package". It contains information about all the samples used, assigned key zones, associated panel settings etc. Loading a sample patch is done by using the patch browser on the main panel, and works in the same way as with any other Reason device.**



The Browse Patch button on the main panel.

For general instructions on how to load and save patches, please see "Loading patches" and "Saving patches".

- **Loading separate samples is done in a similar way, but via the sample browser on the remote editor panel. If you load samples, map them across keyboard ranges and set up the sound the way you want it, you can save your settings as a Patch for easy access later.**



The Browse Sample button on the remote editor.

More about loading samples later in this chapter.

Loading NN-XT Patches

NN-XT Patches are patches made specifically for the NN-XT. Reason ships with a large number of NN-XT Patches, some in the Factory Sound Bank but most in the Orkester Sound Bank. NN-XT Patches have the extension ".sxt".

1. **Click the Browse Patch button on the front panel to set browse focus to the NN-XT device.**
2. **Navigate to the folder that contains the NN-XT patch you wish to load, select it and click Load in the Browser.**

▶ **Alternatively, drag an NN-XT patch from the Browser and drop it on the NN-XT device in the rack.**
The panel is dimmed in orange and the Patch Replace symbol appears in the center.

Loading NN-19 Patches

NN-19 Patches have the extension ".smp". Note that when loading NN-19 patches into the NN-XT, some parameters will not be applicable since the NN-19 and the NN-XT to some extent differ from each other in terms of controls. In these cases, the concerned parameters will either be ignored by the NN-XT or mapped to the most equivalent control.

1. **Click the Browse Patch button on the front panel to set browse focus to the NN-XT device.**
2. **Navigate to the folder that contains the NN-19 patch you wish to load, select it and click Load in the Browser.**

▶ **Alternatively, drag an NN-19 patch from the Browser and drop it on the NN-XT device in the rack.**
The panel is dimmed in orange and the Patch Replace symbol appears in the center.

Loading SoundFonts

The SoundFont format was developed by E-mu systems in collaboration with Creative Technologies. It is a standardized data format containing wavetable synthesized audio and information on how it should be played back in wavetable synthesizers - typically on audio cards. The SoundFont format is an open standard so there is a vast amount of SoundFont banks and SoundFont compatible banks developed by third parties.

Loading SoundFonts is no different from loading NN-XT Patches. As with NN-19 Patches, the NN-XT does its best to map all the SoundFont settings to NN-XT parameters.

You can load SoundFont presets by using the patch browser, and single SoundFont samples by using the sample browser.

Loading complete REX files as Patches

REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). In Reason, REX files are primarily used in the Dr. Octo Rex loop player, but they can be used in the NN-XT as well. Possible extensions are ".rx2", ".rcy" and ".rex".

1. **Click the Browse Patch button on the front panel to set browse focus to the NN-XT device.**
2. **Navigate to the folder that contains the REX loop you wish to load, select it and click Load in the Browser.**

- **Alternatively, drag a REX loop from the Browser and drop it on the NN-XT device in the rack.**
  The panel is dimmed in orange and the Patch Replace symbol appears in the center.

  When loading a REX file, each slice in the file is assigned to one key, chromatically, starting from C1. All parameters are set to their default settings.

When using REX files in the Dr. Octo Rex loop player, it is possible to make a track play the slices in order to recreate the original loop. To do the same in the NN-XT requires a few extra steps.

1. **Use the Browser to load the REX file into an NN-XT sampler.**
2. **Create a Dr. Octo Rex loop player and load the same REX file into a Loop Slot of this device.**
3. **Use the Copy Loop To Track feature on the Dr. Octo Rex to create playback data (a group) on the track assigned to the Dr. Octo Rex.**
4. **Move that group to the track that plays the NN-XT and play it back from there.**
5. **Delete the Dr. Octo Rex loop player.**

Using the main panel

All of the controls on the main panel are used for globally modifying certain parameters for *all* of the samples in a patch, by the same amount.

! **Movements of the parameters on the main panel can be recorded as automation. However, controls on the remote editor panel (described later) can not!**

The following is a description of the controls and parameters on the main panel.

The Pitch and Modulation wheels



Most MIDI keyboards come equipped with Pitch Bend and Modulation wheels. The NN-XT features settings for how incoming MIDI Pitch Bend and Modulation wheel messages should affect the sound. The wheels on the NN-XT will also mirror the movements of the wheels on your MIDI keyboard.

If you don't have Pitch Bend or Modulation controls on your keyboard, or if you aren't using a keyboard at all, you can use the two fully functional wheels on the NN-XT to apply real time modulation and pitch bend.

- **The Pitch Bend wheel is used for "bending" the played notes up and down to change their pitch - much like bending the strings on a guitar or other string instrument. The Pitch Bend Range is set on the remote editor panel (see "Pitch Bend Range").**
- **The Modulation wheel can be used for applying modulation to the sound while you're playing. It can also be used for controlling a number of other parameters, as described in "The Modulation controls".**

The External Control wheel



This section can be used in three ways:

Receiving MIDI controller messages from external sources

NN-XT can receive common MIDI controller messages, and route these to various parameters. You use the "Source" selector switch to determine which type of message should be received:

- **Aftertouch (Channel Pressure)**

- **Expression Pedal**
- **Breath Control**

If your MIDI keyboard is capable of sending aftertouch messages, and/or if you have connected an expression pedal or a breath controller to it, you can use these to modulate NN-XT parameters. Which parameters should be modulated is set in the remote editor panel (see "The Modulation controls").

Recording MIDI controller messages with the wheel

The wheel in the external control section can be used for recording any or all of the three MIDI controller message types into the Reason sequencer. If your MIDI keyboard isn't capable of sending aftertouch messages or you don't have access to an expression pedal or a breath controller, you can use the wheel instead.

This is done just as with any other automation recording, see "Recording performance controller automation".

High Quality Interpolation



This switch turns High Quality Interpolation on and off. When it is activated, the sample pitch is calculated using a more advanced interpolation algorithm. This results in better audio quality, especially for samples with a lot of high frequency content.

- **High Quality Interpolation uses more computer power - so if you don't need it, it's a good idea to turn it off! Listen to the sounds in a context and determine whether you think this setting makes any difference.**

Global Controls



All of these knobs change the values of various parameters in the remote editor panel and affect *all* loaded samples. Thus they can be used for quickly adjusting the overall sound.

The knobs are bi-polar, which means that when they are centered, no parameter change is applied. By turning them to the right you increase the corresponding value, and by turning them to the left, you decrease the value.

Again, the movements of these parameters can be recorded as automation. This is done just as with any other automation recording, see "Recording parameter automation".

The controls are, from left to right:

Filter

These two knobs each control a parameter of the filter (see "The Filter section"). Note that the filter must be on for these to have any effect.

- **Frequency**
  This changes the cutoff frequency of the filter.
- **Resonance**
  This changes the resonance parameter of the filter, meaning - the filter characteristic, or quality.

Amp Envelope

These three knobs control the Amplitude Envelope (see "The Amplitude Envelope") in the following way:

- **Attack**
  This changes the Attack value of the Amplitude Envelope. That is, how long it should take for the sound to reach full level after you press a key on your keyboard.
- **Decay**
  This changes the Decay value of the Amplitude Envelope. Decay determines how long it should take for the sound to go back to the sustain level after it has reached full value (see "The Amplitude Envelope") and the key that triggered the sound is still being pressed.
- **Release**
  This changes the Release value of the Amplitude Envelope. Release works just like Decay with the exception that it determines how long it should take for the sound to become silent after the key has been *released*.

Mod Envelope

This knob controls the Decay value of the Modulation Envelope (see "The Modulation Envelope"). Also see above for a brief description of Decay.

Master Volume


This controls the main volume out from the NN-XT. Turn the knob to the right to increase the volume.

Overview of the Remote Editor panel

It is in the Remote Editor Panel that the main NN-XT action is going on, especially if you're creating your own patches. The remote editor is dominated by the key map display, and this is also the part on which we will concentrate to begin with.

The Key Map display

The key map display consists of a number of separate areas that let you do different things. To help you navigate the key map display, these areas are described below.



The Info area

This displays the following information about the currently selected sample: Sample rate, mono/stereo information, bit resolution and file size.

The Sample area

This area displays the names of the samples in each zone. It also allows you to change the order of the zones by clicking and dragging them up and down.

The Group area

This area does not show any information. However, by clicking in it, you can instantly select all the zones that belong to a certain group. See "Working with Grouping" for information on how to create groups.

The Keyboard area

Aside from the fact that is a guideline for setting up key ranges, it is also used for setting the root keys of, and auditioning loaded samples. See "About the Root Key" and "Auditioning samples" respectively for more information.

The Tab Bar area

This area gives you a visual indication of the key range of a selected zone. By clicking and dragging the "handles" at the key range boundaries, you can resize the key ranges, and by clicking in between the handles, you can move the key ranges without changing their length.

The Key Range area

This area in the middle of the key map display is where you keep track of all the zones and the relationship between them. You can also move and resize the zones just like in the Tab Bar area, as described above.

The Scrollbars

There are both horizontal and vertical scrollbars that work just like regular scrollbars. Whenever there is more information in the key map display than what fits on a "single screen", you can use the scrollbars to reveal it. Either click on the arrows or click and drag the scrollbar handles.

Sample parameters



This area shows the current values of basic parameters you can set for zones, such as root key, play mode, output etc. The parameters are changed by using the knobs directly below the key map display.

Group parameters



These parameters are adjusted on a per group basis (see "Group parameters" for more information on groups). Most of them relate to performance or playing style.

Synth Parameters



The bulk of the parameters on the remote editor are used for adjusting the sound of the samples by applying filtering, envelope shaping, modulation (like vibrato and tremolo) and so on. We call these the synth parameters, since they are to a large extent identical to those on a regular synthesizer.

About Samples and Zones

For a clear understanding of the terminology used when describing the various operations that can be performed in the key map display, it is important to clarify the distinction between a *sample* and a *zone*:

- **A Sample is a piece of audio that can be loaded into the NN-XT and played back.**
- **A Zone could be viewed as a "container" for a loaded sample.**

All loaded samples are placed in "Zones" in the key map display. You can then organize the zones as you please, and make various settings such as key- and velocity ranges separately for each zone.

In other words, the settings you make are actually performed on the zones, but affect the samples in them. Hence, when we talk about making settings for a zone, it is synonymous with making settings for a sample - the sample that the zone contains.


- **Two or more zones can play the same sample, but with different parameter settings, making them sound completely different.**
- **A zone can be empty, playing no sample at all.**

Selections and Edit Focus


Almost all operations in the remote editor are performed on one or more selected zones or on the zone with edit focus. Several zones can be selected at once, but only one zone at a time can have edit focus.

This is important since:


- **Editing operations that can be performed on several zones (like deleting), always apply to the selected zones.**
- **Editing operations that can be performed on one zone only, always apply to the zone with edit focus.**
- **The front panel always shows the settings for the zone with edit focus.**



Here no zone is selected.



Here the middle zone is selected but does not have edit focus.



Here the middle zone has edit focus but is not selected. Notice the thicker border and the additional handles in the key range area.



Here the middle zone is selected and has edit focus.



Here, all three zones are selected, but the middle one has edit focus.


Selecting Zones

- **To select a zone, click on it.**
  Clicking on a zone will also automatically give it edit focus.


You can also select multiple zones in several ways:

- **By holding down [Shift], or [Ctrl](Win) or [Cmd](Mac) and clicking on the zones you wish to select.**
  This way you can select several non-contiguous zones. You can also deselect a selected zone by clicking on it again.
- **By holding down [Ctrl](Win) or [Cmd](Mac) and pressing [A].**
  This will select all of the zones in the key map display. To deselect all zones, click in an unoccupied area in the Sample column or the key map area.
- **By clicking and dragging a selection box in the key map area.**

Making a selection box like this....




...will select these zones:




Note that the zones don't have to be completely encompassed by the selection box. The selection box only have to intersect parts of the zones to include them in the selection.

Selecting zones via MIDI

You can also select zones via your MIDI keyboard. By clicking the button marked “Select zones via MIDI” above the key map display so that it lights up, you enable selection via MIDI.



This way, you can select a zone and give it edit focus by pressing a key that lies within the zone’s key range (see later in this chapter for information about setting up key ranges).




In this case, this zone can be selected by pressing any key between C2 - C3 on your MIDI keyboard.

Note also, that selection via MIDI is velocity sensitive. Zones may have specific velocity ranges. This means that they won't be played unless the key that triggers the zone is played with a certain velocity. The same rules apply when selecting via MIDI, only zones that meet the velocity criteria will be selected. Read more about setting up velocity ranges on “Setting velocity range for a Zone”.


Selecting All Zones in a Group

The concept of zone groups is fully introduced on “Working with Grouping”. For now we will only describe how to select all samples that belong to the same group:

Clicking in the Group column...



...selects all zones in the group



Moving Edit Focus

Moving Edit Focus

Moving Edit Focus

A zone can be given edit focus independently of selection:

- **When you click on an unselected zone, it both gets selected and gets edit focus.**
- **When you select several zones using [Shift], or [Ctrl](Win) or [Cmd](Mac), the one you select last always gets edit focus.**
- **To set edit focus to a zone when several zones are already selected, click on it without holding down any modifier keys.**
  This way, you can move edit focus between the selected zones freely without deselecting any of them.

Adjusting parameters

Adjusting Synth parameters

The synth parameters are the ones that occupy the bulk of the remote editor panel (see "Synth Parameters"). Changes you make to synth parameters always apply to all selected zones.

- **The panel always shows the settings for the zone with edit focus.**
  More about this below.
- **To make adjustments to one zone, select it (which also gives it edit focus) and adjust the parameter on the front panel.**
- **To set *several* zones to the same value, select them and adjust the parameter.**
  All zones will be set to the same value for the parameter you adjusted.

Adjusting Group parameters

Group parameters apply to a group. That is, they are settings that are shared by all zones in a group.

- **To make adjustments to one group, select one or more zones that belong to the group, and adjust the parameter on the front panel.**
- **To set several groups to the same value, select at least one zone in each group you want to adjust, and adjust the parameter.**
  All groups will be set to the same value. More about this below.

About "Conflicting" parameters

Often you will find yourself in a situation where you select multiple zones and parameter settings differ between them. This is quite normal. For example, you will often find yourself making adjustments to for example level and filtering to balance the sound between several samples across the keyboard. However, if you have multiple selections this can sometimes lead to confusion: Enter the NN-XT's "conflicting parameters" indication:

Whenever two or more *selected* zones have conflicting parameter settings, NN-XT will notify you about this by showing a small "M" (for multiple) symbol, next to the parameter.



In this example, Level and Spread have conflicting settings.

- **The controls on the panel always show the setting for the zone with edit focus.**
- **By clicking your way through the zones within the selection, you can see the settings for each zone.**
- **If you adjust a parameter, all selected zones will be set to the same value for this parameter.**

You can put this functionality to good use when checking how a patch has been created and when checking that your own settings are consistent through the various zones.

Sample parameters

The Sample parameters allow you to specify various properties for one or several selected zones, such as tuning, key and velocity ranges.



- **To set several zones to the same value, select them and adjust the parameter.**
  All zones will be set to the same value for the parameter you adjusted.

Copying parameters between zones

You can easily copy parameter settings from one zone to any number of other zones. Proceed as follows:

1. **Select all the zones you want to involve in the operation.**
   By this we mean the zone with the settings you wish to copy, and the zone(s) to which you want to copy the settings.
2. **Make sure the zone that contains the settings you want to copy has edit focus.**
3. **Pull down the Edit menu or the NN-XT context menu and select "Copy Parameters to Selected Zones".**
   All the selected zones will now get the exact same parameter settings.

! **Observe that this only applies to the synth parameters (see "Synth parameters"). Sample parameters (root key, velocity range etc.) can not be copied.**


Managing Zones and Samples

Creating a Key Map

When you add an NN-XT sampler to the rack and select "Reset Device" from the context menu or Edit menu, its key map display becomes empty. That is, it contains no samples.

To create a new key map, proceed as follows:

1. **Either click the Browse Samples button, select Browse Samples from the Edit menu or select Browse Samples from the NN-XT's context menu.**
   The NN-XT device gets browse focus.




The Browse Samples button.

2. **Select the sample or samples that you want to load in the browser and click the "Load" button in the Browser.**
   The selected sample(s) are loaded into the NN-XT.

▶ **Alternatively, drag one or several sample files from the Browser and drop it on the NN-XT device in the rack.**
The panel is dimmed in blue and a Sample Replace symbol appears in the center.

When new samples are loaded into the NN-XT they have the following properties:

- **Each sample is placed in its own zone.**
- **Each zone spans a key range of five octaves on the keyboard - C1 to C6.**
- **All the newly added sample(s)/zones are automatically selected.**
- **The first added zone gets edit focus.**



A key map with four newly added samples.

Setting Root Notes and Key Ranges

The next step after loading the samples is most likely to adjust the key range, root note and tuning of the samples, so that they play sensibly across the key range. There are many ways of doing this, described in "Working with Key Ranges" and onwards. However, we will here briefly describe a procedure for quickly creating a complete key map out of a set of loaded samples.

This example assumes that the samples you load is a set of multisamples for a pitched instrument (like guitar, piano, flute etc.).

1. **Load the samples.**
2. **Use "Select All" on the Edit menu to select all the loaded samples.**
3. **Use "Set Root Notes from Pitch Detection" to automatically set up the root notes (pitches) for the samples.**

4. **Select "Automap Zones" from the Edit menu.**

All selected zones are automatically arranged into a basic key map. You can now proceed with adjusting the synth parameters on the front panel to shape the sound!

About file formats and REX slices

The audio file format support differs depending on which computer OS you are using.

The NN-XT can read audio files in the following formats:

- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFont samples**
  This is a standardized data format containing wavetable synthesized audio and information on how it should be played back in wavetable synthesizers - typically on audio cards. SoundFont banks are hierarchically organized into different categories: User Samples, Instruments, Presets etc. The NN-XT lets you load single samples from within a Soundfont bank.
- **REX file slices**
  A slice is a snippet of sound in a REX File (see "Loading complete REX files as Patches"). To import a REX slice, browse to a REX file and open it as if it was a folder. The browser will then display the slices as files inside that "folder". In the rest of this manual, when we refer to importing samples, all that is said applies to REX slices as well.
- **Any sample rate and practically any bit depth.**

Adding more samples to the Key Map

You can add additional samples to an existing key map way described above.

1. **Make sure that no already loaded sample has edit focus.**
   If you don't, there's a risk that the selected sample will be replaced, see below. To remove the edit focus, click in an unoccupied area in the Sample column or the key map area.
2. **Open the Sample Browser.**
3. **Select the sample(s) you want to load in the browser and click the "Load" button in the Browser.**

▶ **Alternatively, drag one or several sample files from the Browser and drop it on the NN-XT device in the rack.**
The panel is dimmed in blue and a Sample Replace symbol appears in the center.

The new sample(s) are added to the key map.

Replacing a sample

To replace the sample in a zone, proceed as follows:

1. **Make sure the zone has edit focus and do one of the following:**

▶ **Click the Browse Samples button.**

▶ **Select Browse Samples from the Edit menu or the NN-XT context menu.**

▶ **Double click in the zone.**
Any of these methods will set browse focus and open the standard file browser in which you can select new samples for the zone.

2. **Select one and only one sample in the Sample Browser.**
   If you select more than one sample in the browser the samples you load will not replace the one with edit focus. They will instead be added below it.
3. **Click the Load button in the Browser.**

- **Alternatively, drag a sample file from the Browser and drop it on the NN-XT device in the rack.**
  The panel is dimmed in blue and a Sample Replace symbol appears in the center.

Quick browsing through samples

If you want to quickly browse through a number of samples, for example to see which one of them would fit best in a certain context, proceed as follows:

1. **Set up the zone as desired and make sure it has edit focus:**
2. **Use the arrow buttons in the Browse Samples section to select the next/previous sample in the directory.**

Removing samples

- **To remove a sample from a zone, select it by clicking on it and then select "Remove Samples" from the Edit menu or the NN-XT context menu.**
  This will remove the sample from the zone, leaving it empty. Note that you can remove the samples from several selected zones at the same time.

Auditioning samples

You can audition the loaded samples in two ways:

- **By pressing [Alt](Win) or [Option](Mac) and clicking a sample in the sample column.**
  The mouse pointer will take on the shape of a speaker symbol when you move it over the sample column.

  Clicking a sample will play it back at its root pitch (see "About the Root Key"). Furthermore, the sample will play back in its unprocessed state. That is, without any synth-parameters applied (see "Synth parameters").

- **By pressing [Alt](Win) or [Option](Mac) and clicking a sample in the keyboard column.**
  The difference here is that you will hear the sample at the pitch corresponding to the key you clicked and with any and all processing applied. The click mimics a key played with velocity 100. Also note that this may trigger several samples, depending on whether they are mapped across the same or overlapping key ranges, and the velocity range settings (see "Setting up Key Ranges" and "Setting velocity range for a Zone" respectively).

Adding empty Zones

You can add empty zones to a key map. Empty zones are treated just like zones containing samples, in that they are automatically selected, gets edit focus and are assigned a five octave key range when they are first created. However, you can only add one zone at a time. It is also possible to resize, move and edit empty zones in the same way as zones containing samples.

- **To add an empty zone, pull down the Edit menu or the NN-XT context menu and select "Add Zone".**
  An empty zone is added below any existing zones in the key map. An empty zone is indicated with the text "**No Sample**".

After you have added an empty zone, you can assign a sample to it, just as when Replacing a Sample, or when Quick Browsing, as described above.

Duplicating Zones

You can duplicate any number of already existing zones (containing samples or empty).

1. **Select the zone(s) you want to copy.**
2. **Pull down the edit menu or the NN-XT context menu and select "Duplicate Zones".**
   The selected zones will now be copied and automatically inserted below the last one in the key map display.

The duplicated zones will contain references to the same samples as the original zones. They will also have the exact same key ranges and parameter settings.

Using Copy and Paste

The Copy Zones function on the Edit menu allows you to copy all selected zones to the clipboard. Selecting Paste Zones from the Edit menu will paste the zones into the selected NN-XT device, below the existing zones.

This is a handy way to transfer zones (complete with all settings) from one NN-XT device to another.

Removing Zones

To remove one or several zones, select them and do one of the following:

- **Press [Delete] or [Backspace] on the computer keyboard.**
- **Select "Delete Zones" from the Edit menu or the NN-XT context menu.**

When removing zones, you will remove any samples in them as well.

Rearranging Zones in the List

- **To move a zone to another position in the list, click on it in the samples column and drag up or down.**
  An outline shows you where the zone will appear when you release the mouse button.

Working with Grouping

About Groups

Grouping has two purposes:

- **To allow you to quickly select a number of zones that "belong together."**
  For example if you have created a layered sound consisting of piano and strings, you could put all string samples in one group and all piano samples in one group. Then you can quickly select all piano samples and make an adjustment to them by trimming a parameter.
- **To group zones that need to share group settings together.**
  For example, you may want to set a group to legato and monophonic mode and add some portamento so that you can play a part where you slide between notes.


Note that there is always at least one group, since the zones you create are always grouped together by default.

Creating a Group


1. **Select the zones you want to group together.**
   The zones don't have to be contiguous in order to be grouped. Regardless of their original positions in the samples column, they will all be put together in succession.

2. **Select "Group Selected Zones" from the Edit menu or the NN-XT context menu.**
   The zones are grouped.

   Selecting these zones and grouping them...




   ...will create these two groups instead of the original one large group.



Moving a Group to another position in the List

- **Click on the group in the Groups column and drag up or down with the mouse button pressed.**
  An outline of the group you move is superimposed upon the display to help you navigate to the desired position.



Dragging a group to a new position.


3. **Release the mouse button at the desired position.**
   The group and all its zones appear at the new position.

Moving a Zone from one Group to another


This is done just as when rearranging samples in the list, as described on the previous page. The only difference is that you drag the zone from one group to another.

Selecting a Group and/or Zones in a Group

- **Clicking on a group in the groups column selects the group and all the zones in the group.**



- **Clicking on a zone in the samples column selects the group (and that zone).**



The Group Parameters

There are a few parameters on the front panel that apply specifically to groups. see "Group parameters" for details.

Working with Key Ranges

About Key Ranges

Each zone can have its own separate key range, the lowest and the highest key that will trigger the sample.

A good example of use for this is when sampling a certain instrument. Sampling of a piano for example is usually performed by making several recordings of different notes at close intervals, and then mapping these samples to separate, contiguous, fairly narrow key ranges. This concept is called multi-sampling.

The reason for this is that if one single sample is played across the entire keyboard, it will most likely sound very unnatural when played too far from its original pitch, since the amount you can transpose a sound without negatively affecting its timbre is very limited.

Setting up Key Ranges


You can adjust the key range of zones in a number of ways:

By Dragging the Zone Boundary Handles


1. **Select the zone in the Key Range area.**
2. **Point and click on one of the handles that appear at each end.**

3. **Drag the handle left/right.**
   Dotted lines extend from the edges of the zones up to the keyboard area. These lines give you a visual indication of which keys the key range will encompass. There is also an alphanumerical indication at the bottom left of the display.

Clicking and dragging the high key boundary handle of a zone with the default key range of C1 - C6...



...to change the key range to C1 - C2.



4. **Repeat the procedure with as many zones as you wish, to create a complete key map.**

By using the Lo Key and Hi Key controls

Directly below the key map area you will find the sample parameters. These are used for changing various parameters that affect how the zones are played back. They can affect single or multiple selected zones. In the middle of the sample parameters area are two knobs called “Lo Key” and Hi Key”.




These can be used for setting the low key and the high key of a zone's key range.

1. **Make sure the zone which you want to set the key range for is selected.**
2. **Use the Lo Key/Hi Key knobs to change the key range.**
   Check the display right above the knobs for an indication of the key. You can also keep an eye on the lines extending from the zone edges to the keyboard area.

Setting key ranges for multiple zones

You can set key ranges for multiple selected zones simultaneously. This can only be done by using the Lo and Hi Key controls. It works as follows:


- **If you have three selected zones that each have different high keys and then turn the Hi Key knob, they will all automatically get the same High Key value as the zone with edit focus.**
  In other words, if the selected zone with edit focus has the high key set to C4, and you change this to D4 by turning the Hi Key knob, all other selected zones will also be extended to D4 as the High Key.



- **If any selected zone's low key setting is higher than the edit focused zone's high key before turning the Hi Key knob, the zone range will be scaled down to one semitone, starting from the low key setting.**
  The high key can naturally never be set to a value lower than one semitone above its low key setting - the zone would otherwise disappear!
- **The inverse is also true - i.e. turning the Lo Key knob for several selected zones will apply the edit focused low key setting to all selected zones.**
  A low key can never be set higher than one semitone below the high key in a zone, so if the edit focused zone has a low key above the high key of another zone, the other zone will be scaled to the minimum semitone range.

By Dragging the Zone Boundary Handles on the Tab Bar

As previously described, the area directly below the keyboard area is called the tab bar. This shows the key range for the currently selected zone, and also contains boundary handles.



Dragging a boundary handle on the tab bar.

These handles can be used much to the same effect as when dragging the boundary handles in the key map display. However, the handles on the tab bar can change the key range of multiple zones at the same time.

The following applies:


- **The tab bar shows the key range for the zone with edit focus.**

- **Dragging the boundary handles for that zone will also simultaneously change the key range for a number of surrounding zones if:**

▶ **The high key or low key (depending on which handle you drag) of the other zones are the same as the zone with edit focus.**


▶ **The other zones are adjacent to the zone with edit focus.**

! **Note that it doesn't matter whether the other zones are selected or not. They will be affected anyway.**




In the example in the picture above, the zone in the middle has edit focus. Its left handle (the low key) is placed differently from any of the other zones, but all of the zones have the same high key setting. This means that...


- **Dragging the left handle will only move the low key position of the zone with edit focus (the pictures show before and after dragging).**





- **Dragging the right handle will move the high key position for all of the zones at the same time, since they all have the same high key position (again, the picture shows before and after dragging).**






Moving Zones by Dragging the Zone Boxes

You can also move entire zones horizontally, thereby changing their key ranges.

1. **Select all the zones you want to move.**
   You can move several zones simultaneously.
2. **Point on any of the selected zones, and press the mouse button.**
3. **Drag left/right and release the mouse button.**




Dragging multiple zones.


Moving Zones by Dragging in the Tab Bar

You can also move a zone by dragging anywhere between the zone boundary handles on the tab bar. When you do, the surrounding zones will be affected just as when dragging the boundary handles in the tab bar (see above).

This can be used to "slide" a zone in relation to its surrounding zones, as the picture example below shows (before and after dragging).




About the Lock Root Keys function



Normally, when you move zones (as described above), the root note of the zone(s) you move will change accordingly. In other words, the zone(s) will be transposed. If this is not desired, you can activate the Lock Root Keys function prior to moving the zone(s) by clicking on the button above the key map display.

Moving zones without changing their root notes can be used for some interesting effects, since it will completely change the timbre of the sample(s) as they are played back.

About the Solo Sample function



The Solo Sample function lets you play a selected sample over the entire keyboard and disregarding any velocity range assigned to the sample. All other loaded samples are temporarily muted.

This is useful if you for example want to check how far up and down from its root key a sample can be played on the keyboard before starting to sound "unnatural". The solo sample function can therefore be useful as a guide for setting up key ranges, as described in "Setting up Key Ranges".


1. **Select one and only one zone, or - if you have a selection of multiple zones - make sure the one you want to hear has edit focus.**
2. **Activate Solo Sample by clicking on the button so that it lights up.**
3. **Play the MIDI keyboard**

Sorting Zones by Note

The Edit menu and the NN-XT context menu contains an item called “Sort Zones by Note”. This option lets you automatically sort the selected zones in descending order according to their key ranges.

When you invoke this option, the selected zones will be sorted from top to bottom in the display starting with the one with the lowest range.

Note however, that the sorting is done strictly on a group basis. That is, only zones that belong to the same group can be sorted in relation to each other.



Before sorting and after.

If two zones have the same key range, they are sorted by velocity range.

Setting Root Notes and Tuning

About the Root Key

All instrument sounds have an inherent pitch. When playing a sample of such a sound on the keyboard, the keys you play must correspond to that pitch. For example, you may have recorded a piano playing the key "C3". When you map this onto the NN-XT key map, you must set things up so that the sampler plays back the sample at original pitch when you press the key C3.

This is done by adjusting the root note.

- **Many samples files from different sources already have a set root key in the file. If they do, the root key will be correctly set automatically when you load the sample into a zone.**
- **However if the sample doesn't have a root note stored in the file, (if you for example have recorded it yourself) you will need to adjust it**


Setting the Root Note manually

To set the root key for a zone, proceed as follows:

- **Make sure the zone has edit focus (for example by clicking on it), and do one of the following:**
- **Use the knob marked "Root" in the sample parameter area below the display.**
  Turning it to the right will raise the pitch of the root key. The selected key is displayed alphanumerically directly above the knob, and you can also look at the keyboard area for a visual indication (see below).



- **Press [Ctrl](Win) or [Cmd](Mac) and click on the desired root key in the keyboard area.**
  The set root key is shaded so you can easily distinguish it.



Tuning samples manually

In addition to setting the root note, you may need to fine tune your samples, in order for them to match other instruments and/or each other:

- **Make sure the zone has edit focus (for example by clicking on it).**
- **Use the knob marked "Tune" in the sample parameter area.**
  This allows you to tune each sample in a key map by +/– half a semitone (-50 – 0 – 50).



Setting the Root Note and Tuning using pitch detection

The NN-XT features a pitch detection function to help you set the root keys. This is useful if you for example load a sample that you haven't recorded yourself, and you don't have any information about its original pitch.

Proceed as follows:

1. **Select all the zones you want to be subject to pitch detection.**
2. **Pull down the Edit menu or the NN-XT context menu and select "Set Root Notes from Pitch Detection".**
   The samples in all the selected zones will now be analyzed, and the detected root keys will automatically be set for you.

! **Note that for this to work properly, the samples must have some form of perceivable pitch. If it is sampled speech, or a snare drum for example, it probably doesn't have any discernible pitch.**

About changing the pitch of samples

The procedures above should be used to make sure the samples are consistently pitched across the keyboard, and that they all match an absolute reference (for example A 440 tuning).

If you need to tune the samples to match other material, or to get a certain effect (for example detuning two sounds against each other for a chorus effect) you should use the Pitch section among the synth parameters, not the sample tuning parameters.

Using Automap

The automap function can be used as a quick way of creating a key map, or as a good starting point for further adjustments of a key map.

Automap works under the assumption that you intend to create a key map for a complete instrument, for example a number of samples of a piano, all at different pitches.

1. **Load the samples you want to Automap.**
   Now you have three options:

- **Trust that the root note information in the files is already correct.**
- **Manually adjust the root notes (and tuning) for all the samples.**
- **Use "Set Root Notes from Pitch Detection" to automatically set up the root notes.**

2. **Select all zones you want to automap.**
3. **Select Automap Zones from the Edit menu or the NN-XT context menu.**

All the selected zones will now be arranged automatically in the following way:

- **The zones will be sorted in the display (from top to bottom - lowest key first) according to the root keys.**
- **The zones will be assigned key ranges according to the root keys.**
  The key ranges are set up so that the split between two zones is exactly in the middle between the zones' root notes. If two zones have the same root key they will be assigned the same key range.


Automapping zones chromatically

- **This Edit menu item will give each zone a key range of one semitone (i.e. one key), starting from C2 and upwards.**
  The function does not take root key into account. It simply places each selected sample on successive keys according the position in the sample list (from the top down).

Layered, crossfaded and velocity switched sounds

Creating layered sounds

You can set things up so that two or more zones have overlapping key ranges - either completely or partially. This way you can create layered sounds, i.e. different samples that are played simultaneously when you press a key on your keyboard.



In the picture above, you can see a set of piano samples at the top, mapped across the key range.

Below these are a set of string samples that also span the entire key range.

Whenever you play a key within this keyboard range, the sound produced will be a combination of the piano and the string sample.

In addition, in the example above, the user has arranged the piano samples into one group and the string samples in another. This is convenient since it allows for quick selection of the entire piano map, for example for balancing its level against the strings.

About velocity ranges

When zones are set up so that their key ranges overlap – completely or partially – you can use velocity switching and crossfading to determine which zones should be played back depending on how hard or soft you play on your MIDI keyboard.

This is done by setting up velocity ranges, with or without crossfading.


Each time you press a key on your MIDI keyboard, a velocity value between 1-127 is sent to Reason. If you press the key softly, a low velocity value is sent and if you press it hard, a high velocity value is sent.

This velocity value determines which samples will be played and which will not.

Let's say for example that you've mapped three different zones across the same key range:

- **Zone 1 has a velocity range from 1-40.**
  This means that the sample in it will be triggered by velocity values between 1-40.
- **Zone 2 has a velocity range of 41-80.**
  The sample in this zone will be played back by velocity values between 41-80.


- **Zone 3 has a velocity range of 81-127.**
  The sample in this zone will be triggered by all velocity values above 80.



Overlapping velocity ranges

Let's change the values above slightly:

- **Zone 1 has a velocity range from 1-60.**
- **Zone 2 has a velocity range of 41-100.**
- **Zone 3 has a velocity range of 81-127.**




Now, velocity values between 41 and 60 will trigger samples from both Zone 1 and Zone 2. Likewise, velocity values between 81 and 100 will trigger sounds from Zone 2 and Zone 3.

About full and partial velocity ranges

You can see which zones have modified velocity ranges in the key map display:

- **Zones with a full velocity range (0 - 127) are only shown with an outline.**
- **Zones with any other velocity range are shown as striped.**



The top zone has a full velocity range (1-127), and the lower zone has a partial velocity range (any other range), which is indicated by stripes

Sorting Zones by velocity values

The Edit menu and the NN-XT context menu contain an item called "Sort Zones by Velocity". This option lets you automatically sort the selected zones in the display in descending order according to their set low or high velocity values.

When you invoke this option, the selected zones will be sorted from top to bottom starting with the one with the highest "Lo Vel "value.

Note however, that the sorting is done strictly on a *group* basis. That is, only zones that belong to the same group can be sorted in relation to each other.

If two zones have the same velocity range, they are sorted by key range.

Setting velocity range for a Zone

To set up a velocity range for a zone, proceed as follows:

1. **Select one or more zones that you want to adjust.**
2. **Use the knobs marked "Lo Vel" and "High Vel" in the sample parameter area to set the desired low- and high velocity values.**



Adjusting the "Lo Vel" value for a zone.

"Lo vel" is the lowest velocity value that should trigger the sample in the zone - i.e. if a key is pressed so softly that the velocity is lower than this value, the sample will not be played.

"Hi vel" is the highest velocity value that should trigger the sample, which means that if a key is pressed so hard that the velocity is higher than this value, the sample will not be played.


About Crossfading Between Zones

At the bottom right in the sample parameter area are two knobs marked "Fade In" and "Fade Out". These are primarily used for setting up velocity crossfades for smooth transitions between overlapping zones. In order to set up crossfades you adjust the fade out and fade in values for the overlapping zones.

Crossfading Between two Sounds

An example:


- **Two zones are both set to play in the full velocity range of 1-127.**
- **Zone 1 has a fade out value of 40.**
  This means that this zone will play at full level with velocity values below 40, With higher velocity values, it will gradually fade out.
- **Zone 2 has a fade in value of 80.**
  This has the effect that as you play velocity values up to 80, this zone will gradually fade in. With velocity values above 80, it will play at full level.



Another example:

Crossfading can be used to only fade in or fade out a certain sound. One common example is to set things up so that one sound plays the entire velocity range and another is faded in only at high velocity values.

- **Zone 1 is set to play the entire velocity range with no crossfade.**
- **Zone 2 is set to play the velocity range 80 to 127, with a fade in value of 110.**
  This means that this zone will start fading in from velocity values 80 and will play at full level in the velocity range 110 to 127.



This can be used for example to add a rimshot to a regular snare sound or a harder attack to a softer violin sample.

Setting crossfading for a Zone

Manually

To set up a crossfade for a zone, proceed as follows:

1. **Select one or more zones that you want to adjust.**
2. **Use the knobs marked "Fade In" and "Fade Out" in the sample parameter area, to set the desired values.**



- **You can change the values with finer precision by pressing [Shift] while turning the knobs, and you can reset the standard values by pressing [Command] (Mac)/[Ctrl] (Windows) and clicking on the knobs.**

Automatically

If you find it tedious to manually set up crossfades between zones, NN-XT can do it for you! The Edit menu and the NN-XT context menu contain an item called "Create Velocity Crossfades".

1. **Set up the zones so that their velocity ranges overlap, as desired.**
2. **Select the zones.**
   You can select as many zones as you wish, not just one pair of overlapping zones.
3. **Select "Create Velocity Crossfades" from the Edit menu.**
   NN-XT will analyze the overlapping zones and automatically set up what it deems to be appropriate fade in and fade out values for the zones.

- **This operation will not work if both zones have full velocity ranges.**
  At least one of the zones must have a partial velocity range (see "About full and partial velocity ranges").
- **This operation will not work if the zones are completely overlapping.**

Using Alternate

About the Alternate function



At the bottom right in the sample parameters area is a knob marked "Alt". It only has two states - On and Off. This is used for semi-randomly alternating between zones during playback.

There are several practical uses for this. Here follows two examples:

- **Layering several recordings of the same snare drum. By alternating between them you get a more natural repetition.**
- **Layering string up- and down strokes. By alternating you get the realistic effect of switching between the two directions of the stroke.**

You can layer as many sounds as you will and the algorithm switches between them in a way that provides as little repetition as possible.

To set up an alternating set of zones, proceed as follows:

1. **Set up the zones so that they overlap completely or partially.**
2. **Select them all.**
3. **Set "Alt" to On for all the zones.**
   Now, the program will automatically detect how to alternate between the zones, depending on their overlap.

Sample parameters



The Sample parameter area is found below the screen. They allow you to adjust parameters for one or several selected zones. Adjusting a parameter with multiple zones selected, will set the parameter to the same value for all selected zones. Below follows a run-down of the various parameters:

Root Note and Tune

These parameters are described in "Setting Root Notes and Tuning".

Sample Start and End

By turning the knobs you offset the start and end positions, so that they will play back more or less of a sample's waveform. Typical examples of use for this would be:

- **Removing unwanted portions from samples.**
  This could be anything from noise to "dead air" at the beginning or end of a sample.
- **To create variations out of a single sample.**
  These controls can be used to pick out any section of a recording for use as a sample.
- **Together with velocity sample start control.**
  You can for example increase Sample Start and then apply negative velocity modulation to Sample Start. Then, the harder you play the more you will hear of the attack portion of the sound.

▶ **If you hold down [Shift] when adjusting these parameters, the adjustment is in single frames (samples).**

Loop Start and End

A sample, unlike the cycles of an oscillator for example, is a finite quantity. There is a sample start and end. To get samples to play for as long as you press down the keys on your keyboard, they need to be looped. For this to work properly, you have to first set up two loop points which determine the part of the sample that will be looped.

The instrument samples in the sound banks included with Reason are already looped. The same will be true for most commercial sample libraries. However, if you need to, you can use these controls to adjust the looping.

- **The size and position of the loop – in the sample – is determined by two parameters, Loop Start (the beginning of the loop) and Loop End (the end point of the loop).**
- **The NN-XT then keeps repeating the section between the Loop Start and Loop end until the sound has decayed to silence.**

Play Mode

By using this knob you can select one of the following loop modes for each zone:

- **FW**
  The sample in the zone will play only once, without looping.
- **FW-LOOP**
  The sample will play from the sample start point to the loop end point, jump back to the loop start point and then loop infinitely between the start and end loop points. This is the most common loop mode.
- **FW - BW**
  The sample will play from the sample start point to the loop end point, then from the loop end point to the loop start point (backwards), and then loop infinitely forwards-backwards between the start and end loop points.
- **FW-SUS**
  This works like FW-LOOP with the exception that it will only loop as long as the key is held down. As you release the key, the sample will play to the absolute end of the sample, that is beyond the boundaries of the loop.

  This means that the sound may have a short natural release even if the release parameter is raised to a high value (which is not true for "FW-LOOP", where the release parameter always controls the length of the sound after the key is released).
- **BW**
  The sample will play only once - from the end to the beginning - without looping.

Lo Key and Hi Key

These parameters are described in "Setting up Key Ranges".

Lo Vel and Hi Vel

These parameters are described in "About velocity ranges".

Fade In and Fade Out

These parameters are described in "About Crossfading Between Zones".

Alt

This parameter is described in "About the Alternate function".

Out

The NN-XT features eight separate stereo output pairs (see "Audio Output"). For each zone, you can decide which of these output pairs to use. Thus, if you have created a key map consisting of eight zones, each of these can have a separate stereo output from NN-XT, and can then be routed to a separate mixer channel if you so wish.

▶ **To select which output a selected zone should be directed to, use the knob marked "Out" in the sample parameter area.**
The output pairs are indicated above the button.

! **Note that you still have to route the outputs the way you want them on NN-XT's back panel. If you assign a zone to an output pair other than 1-2 (which is the default) no connections or auto routing are made. You have to do that manually.**

A Stereo example

One possible way of utilizing this would be to create a drum kit. In this case you could load up to eight different stereo drum samples, assign them to separate outputs, route each to a separate mixer channel and then use the mixer to set levels and pan, add send effects etc.

Using a stereo output as two mono outputs

If, on the other hand, you are using mono samples, you can use one stereo pair as a two separate outputs, effectively giving you a total of 16 separate outputs.

1. **Assign two zones to the same output.**
2. **Us the Pan control to pan one of the zones hard left and the other hard right.**
3. **Connect each of the two outputs in the stereo pair to a separate mixer channel.**

Group parameters



The group parameters are located at the top left on the remote editor panel. These are parameters that in various ways are directly related to playing style.

Group parameters apply to a group, that is they are settings that are shared by all zones in a group.

- **To make adjustments to one group, select one or more zones that belong to the group, and adjust the parameter on the front panel.**
- **To set several groups to the same value, select at least one zone in each group you want to adjust, and adjust the parameter on the front panel.**

Key Poly

This setting determines the number of keys that you can play simultaneously (the polyphony). The maximum number is 99 and the minimum is 1, in which case the group will be monophonic.

Users of other samplers may want to note that the polyphony often means setting the number of *voices* that should be able to play. The NN-XT is different in this aspect, since the polyphony setting instead determines the number of *keys,* regardless of how many voices each key plays.

The Group Mono button

The Group Mono button beside the Key Poly section can be used to quickly set a group to play monophonically regardless of the polyphony setting. E.g. if you have a group with open and closed hi hats, you can switch this on so that an open hi hat is automatically muted when you play a closed hi hat.

Group Mono overrides the Key Poly setting - except when playing the same note.

So you can play your open hi-hat repeatedly without the sound cutting itself off. When you play the closed hi-hat, this cuts off the open hi-hat.

Note that activating this button is not the same as setting polyphony to 1. E.g., it can not be used for Legato or mono Retrig (see "Legato and Retrig").

Legato and Retrig

Legato

Legato works best with monophonic sounds. Set Key Poly (see above) to 1 and try the following:

- **Hold down a key and then press another key without releasing the previous.**
  Notice that the pitch changes, but the envelopes do not start over. That is, there will be no new "attack".
- **If Key Poly is set to more voices than 1, Legato will only be applied when all the assigned keys are "used up".**
  For example, if you had a polyphony setting of "4" and you held down a 4 note chord, the next note you played would be Legato. Note, however, that this Legato key will "steal" one of the keys in the 4 note chord, as all the assigned keys were already used up!

Retrig

Retrig is the "normal" setting for playing polyphonic patches. That is, when you press a key without releasing the previous, the envelopes are triggered, like when you release all keys and then press a new one. In monophonic mode, Retrig has an additional function; if you press a key, hold it, press a new key and then release that, the first note is also retriggered.

LFO 1 Rate

This is used for controlling the rate of LFO 1 if it is used in "Group Rate" mode. In that case, this knob will take precedence over the rate parameter in the LFO 1 section. See "The LFOs" for detailed information about this.

Portamento

This is used for controlling portamento - a parameter that makes the pitch glide between the notes you play, rather than changing the pitch instantly as soon as you hit a key on your keyboard. By turning this knob you set how long it should take for the pitch to glide from one note to the next as you play them.

In legato mode, there will only be any portamento when actually playing legato (tied) notes.

With the knob turned all the way to the left, portamento is disabled.

Synth parameters

The Modulation controls



As previously described, the Modulation wheel (and the External Control wheel) can be used for controlling various parameters. These controls allow you to define which parameters the wheels should modulate and to what extent.

- **Below each of the knobs are the letters "W" and "X".**
  These are used for selecting the source that should control the parameter, and represent the "Modulation Wheel" and the "External Control wheel" respectively.
- **By clicking on any of the letters, you decide which source should control the parameter.**
  You can select either, both or none. When a letter is "lit", the corresponding source is set to control the parameter.
- **By turning the knobs, you decide how *much* the modulation and/or external control wheel should modulate the corresponding parameter.**

Note that all of the control knobs are bi-polar, which means that they can be set to both positive and negative values. Positive values are set by turning the knobs to the right, and negative values are thus set by turning the knobs to the left:

- **Setting them to positive values means that the value of the controlled parameter will be raised if the source wheel is pushed forward.**
- **Setting them to negative values means that the value will be lowered when a wheel is pushed forward.**
- **Keeping the knobs in the center position means that no modulation control is applied.**

There is one exception to these rules, and that is the LFO 1 Amt control, which works in a slightly different way. See below for more information about this.

The following parameters can be modulated:

F.Freq

This sets modulation control of the Filter's cutoff frequency (see "The Filter section").

Mod Dec

This sets modulation control of the Decay parameter in the Modulation Envelope (see "The Modulation Envelope").

LFO 1 Amt

This determines how much the amount of modulation from LFO 1 is affected by the Modulation wheel and/or the External Controller wheel. It does this by "scaling" the amounts set with the three destination knobs in the LFO 1 section (Pitch, Filter and Level, see "The LFOs"). We'll explain this with an example:

To use the Modulation Wheel to *increase* pitch modulation (vibrato), proceed as follows:

1. **Turn the Mod Wheel all the way down, so that no modulation is applied.**
2. **Activate the "W" button for LFO 1 Amt in the Modulation section.**
3. **Set the corresponding knob to "12 o'clock" (zero).**
4. **Set up LFO 1 so that as much vibrato is applied as you want it to be when the Modulation wheel is turned all the way up.**
5. **Increase LFO 1 Amt until you hear as much vibrato as you want it to be when the wheel is turned all the way down.** If you turn LFO 1 Amt all the way up, there will be no vibrato at all when the wheel is all the way down.

To instead use the Modulation wheel to *decrease* vibrato, process as follows:

1. **Turn the Mod Wheel all the way down, so that no modulation is applied.**
2. **Activate the "W" button for LFO 1 Amt in the Modulation section.**
3. **Set the corresponding knob to "12 o'clock" (zero).**
4. **Set up LFO 1 so that as much vibrato is applied as you want it to be when the Modulation wheel is turned all the way down.**
5. **Turn the Modulation wheel all the way up.**
6. **Decrease LFO 1 Amt until you hear as much vibrato as you want it to be when the wheel is turned all the way up.** If you turn LFO 1 Amt all the way down, there will be no vibrato at all when the wheel is all the way up.

F.Res

This sets modulation control of the Resonance parameter in the Filter (see "The Filter section").

Level

This sets the amount of amplitude envelope modulation of each zone's level. The level set here will be the level of the highest point of the Amp Envelope.

LFO 1 Rate

This sets modulation control of the Rate parameter in LFO 1 (see "The LFOs").

The Velocity controls



Velocity is used for controlling various parameters according to how hard or soft you play notes on your keyboard. A typical use of velocity control is to make sounds brighter and louder if you strike a key harder. By using the knobs in this section, you can control if and how much the various parameters will be affected by velocity.

Just like the modulation controls, all of the velocity control knobs are bi-polar, and can be set to both positive and negative values.

- **Setting them to positive values means that the value of the controlled parameter will be raised the harder you play.**
- **Setting them to negative values means that the value will be lowered the harder you play.**
- **Keeping the knobs in the center position means that no velocity control is applied.**

The following parameters can be velocity controlled:

F.Freq

This sets velocity control of the Filter's cutoff frequency (see "The Filter section").

Mod Dec

This sets velocity control of the Decay parameter in the Modulation Envelope (see "The Modulation Envelope").

Level

This sets velocity control of the Amp Envelope.

Amp Env Attack

This sets velocity control of the Attack parameter in the Amplitude Envelope (see "The Amplitude Envelope").

Sample Start

This sets velocity control of the Sample Start parameter (see "Sample Start and End"), so that it will be offset forwards or backwards, according to how hard or soft you play.

This allows you to control how much of the attack portion of the sample you hear when playing harder or softer.

To be able to make use of negative values for this parameter, you must increase the sample parameter Sample Start.

The Pitch section



This section contains various parameters related to controlling the pitch, or frequency, of the zones.

Pitch Bend Range

This lets you set the amount of pitch bend, i.e. how much the pitch changes when your turn the pitch bend wheel fully up or down. The maximum range is +/- 24 semitones (2 Octaves).

Setting the pitch

Use the three knobs marked “Octave”, “Semi” and “Fine” to change the pitch of the sample(s):

- **Octave**
  This changes the pitch in steps of one full octave. The range is -5 – 0 – 5.
- **Semi**
  This lets you change the pitch in semitone steps. The range is -12 – 0 – 12 (2 octaves).
- **Fine**
  This changes the pitch in cents (hundredths of a semitone). The range is -50 – 0 – 50 (down or up half a semitone).

K. Track

This knob controls Keyboard Tracking of the pitch.

- **In the center position, each key represents a semitone This is the normal setting.**
- **When turned all the way down, all keys play the same pitch. This can be useful for percussion like timpani where you might want to play the same pitch from a range of keys.**
- **When turned all the way up, each key on the keyboard shifts the pitch one octave.**

The Filter section



Filters can be used for shaping the character of the sound. The filter in NN-XT is a multimode filter with six different filter types.

- ▶ **To activate/deactivate the filter, click the On/Off button in the top right corner.**
  When the filter is activated, the button is lit.

Filter mode

To select a filter mode, either click the Mode button in the bottom right corner or click directly on the desired filter name so that it lights up:

- **Notch**
  The notch filter is used for cutting off frequencies in a narrow frequency range around the set cutoff frequency, while letting the frequencies below and above through.

- **HP 12**
  This is a highpass filter with a 12 dB/Octave roll-off slope. A highpass filter cuts off low frequencies and lets high frequencies pass. That is, frequencies below the cutoff frequency are cut off and frequencies above it pass through.
- **BP 12**
  This is a bandpass filter with a 12 dB/Octave roll-off slope. A bandpass filter could be viewed as the opposite of a notch filter. It cuts off both the high and the low frequencies, while frequencies in the band range pass through.
- **LP 6**
  This is a lowpass filter with a gentle, 6 dB/Octave slope. A lowpass filter is the opposite of a highpass filter. It lets the low frequencies through and filters out the high frequencies. This filter has no Resonance.
- **LP 12**
  This is a lowpass filter with a 12 dB/Octave roll-off slope.
- **LP 24**
  This is a lowpass filter with a fairly steep roll-off slope of 24 dB/Octave.

Filter controls

The following filter controls are available:

- **Freq**
  This is used for setting the filter cutoff frequency. The cutoff frequency determines the limit above or below which frequencies will be cut off depending on the selected filter type. In the case of a lowpass filter for example, frequencies below the cutoff frequency will be allowed to pass through, while frequencies above it will be cut off. The farther to the right you turn the knob, the higher the cutoff frequency will be.

▶ **It is very common to modulate filter frequency with the modulation envelope, as described in "The Modulation Envelope".**

- **Res**
  Technically, this knob controls feedback of the output signal from the filter, back to its input. Acoustically it emphasizes frequencies around the cutoff frequency. For a lowpass filter for example, increasing Res will make the sound increasingly more hollow until the sound starts "ringing". If you set a high value for the Res parameter and then vary the filter frequency, this will produce a classic synthesizer filter sweep.

  For the notch and bandpass filter types, the Resonance setting instead adjusts the width of the band. That is, the higher the resonance setting, the narrower the band will be where frequencies are cut off (notch) or let through (Bandpass).

- **K. Track**
  This lets you activate and control keyboard tracking of the filter frequency. If keyboard tracking is activated, the set cutoff frequency of the filter will change according to the notes you play on your keyboard. That is, if you play notes higher up on the keyboard, the filter frequency will be raised and vice versa.

  When the knob is set to its center position, filter frequency is adjusted so that the harmonic content remains constant across the keyboard.

  Keyboard tracking is deactivated by default (the knob all the way to the left). This means that the filter frequency will remain unchanged regardless of where on the keyboard you play.

The Modulation Envelope



The Modulation Envelope parameters let you control how certain parameters, or destinations, should change over time - from the moment a note is struck to the moment it is released again.

The destinations you can use are:

- **Pitch**
- **Filter frequency**

Parameters

The following are the available controlling parameters:

- **Attack**
  When you press a key on your keyboard, the envelope is triggered. The attack parameter then controls how long it should take before the controlled parameter (pitch or filter) reaches the maximum value, when you press a key. By setting attack to a value of "0", the destination parameter would reach the maximum value instantly. By raising the attack parameter, the value will instead slowly "slide" up to its maximum.
- **Hold**
  This is used for deciding how long the controlled parameter should stay at its maximum value before starting to decrease again. This can be used in combination with the Attack and Decay parameters to make a value reach its maximum level, stay there for a while (hold) and then start dropping gradually down to the sustain level.
- **Decay**
  After the maximum value for a destination has been reached and the Hold time has expired, the controlled parameter will start to gradually drop down to the sustain level. How long it should take before it reaches the sustain level is controlled with the Decay parameter. If Decay is set to "0", the value will immediately drop down to the sustain level.
- **Sustain**
  The Sustain parameter determines the value the envelope should drop back to after the Decay. If you set Sustain to full level however, the Decay setting doesn't matter since the value will never decrease.

  A combination of Decay and Sustain can be used for creating envelopes that rise up to the maximum value, then gradually decrease to, and stay on a level somewhere in-between zero and maximum.
- **Release**
  This works just like the Decay parameter, with the exception that it determines the time it takes for the value to fall back to zero *after* the key is released.
- **Delay**
  This is used for setting a delay between when a note is played and when the effect of the envelope starts. That is, the sound will start unmodulated, and the envelope will kick in after you have kept the key(s) pressed down for a while. Turn the knob to the right to increase the delay time. If the knob is set all the way to the left, there will be no delay.
- **Key To Decay**
  By using this, you can cause the value of the Decay parameter (see above) to be offset depending on where on your keyboard you play. If you turn the knob to the right the decay value will be raised the higher up you play, and turning the knob to the left will lower the decay value the higher up you play. With the knob in the center position, this parameter is deactivated.

Destinations

The following are the available Mod Envelope destinations:

- **Pitch**
  This will make the envelope modulate the pitch, as set in the Pitch section (see "The Pitch section"). Turn the knob to the right to raise the pitch and to the left to lower the pitch. In the middle position, pitch will not be affected by the envelope.
- **Filter**
  This will make the envelope modulate the cutoff frequency of the Filter (see "The Filter section"). Turn the knob to the right to increase the frequency and to the left to lower the frequency. In the middle position, the envelope will have no effect on the cutoff frequency.

The Amplitude Envelope



The Amplitude Envelope parameters let you control how the volume of a sound should change over time - from the moment a note is struck to the moment it is released again.

Parameters

Most of the Amplitude Envelope parameters are identical to those of the Modulation Envelope. So for a detailed description of the following parameters, please refer to the modulation envelope section in "The Modulation Envelope":

- **Attack**
- **Hold**
- **Decay**
- **Sustain**
- **Release**
- **Delay**
- **Key To Decay**

The following are the parameters that are unique for the Amp Envelope section:

- **Level**
  This knob sets the level of the zone. Turn it to the right to raise the level.
- **Spread and Pan modes**
  These two parameters are used for controlling the stereo (pan) position of the sound. The Spread knob determines the sound's width in the stereo image (how far left – right the notes will be spread out). If this is set to "0", no spread will take place. The Mode selector switch is used for choosing which type of spread you want to apply:

Mode	Description
Key	This will make the pan position shift gradually from left to right, the higher up on the keyboard you play.
Key 2	This will make the pan position shift from left to right and then back again from right to left in a sequence of eight keys. Playing 4 adjacent semitones thus makes the pan position gradually go from left to right. The next 4 higher semitone notes will then change the pan position from right to left in the same way, and this cycle will then be repeated.
Jump	This will make the pan position jump between left and right each time a note is played.

- **Pan**
  This controls the stereo balance of the output pair to which a zone is routed. In the middle position, the signal appears equally strong on the left and right channel in a stereo pair. By turning the knob to the left or right, you can change the stereo balance.

Note that if you for instance turn the Pan knob all the way to the left, you cause the signal to be output from the left channel of the stereo pair only.

You can use this to treat a stereo output as two independent mono outputs, if required.

See "Out" for information on routing zones to output pairs.

The LFOs



NN-XT features two Low Frequency Oscillators - LFO 1 and LFO 2. "Normal" oscillators generate a waveform and a frequency, and produce sound. *Low frequency* Oscillators on the other hand, also generate a waveform and a frequency, but there are two major differences:

- **LFOs only generate sounds of a low frequency.**
- **LFOs don't produce sound, but are instead used for modulating various parameters.**

The most typical use of an LFO is to modulate the pitch of a sound (generated by an oscillator or - in the case of NN-XT - a sample), to produce vibrato.

About the Difference between LFO 1 and LFO 2

There are two fundamental differences between LFO 1 and LFO 2:

- **LFO 2 is always key synced, that is, each time you press a key, the LFO waveform starts over from scratch. LFO 1 can be switched between key synced and non-key synced modes.**
- **LFO 2 only has one waveform, triangle.**

The following parameters are available for the LFOs:

Rate (LFO 1 and 2)

This knob controls the frequency of the LFO. For a faster modulation rate, turn the knob to the right. The Rate knob of LFO 1 is also used for setting the timedivision when synchronizing the LFO to the song tempo (see below).

Delay (LFO 1 and 2)

This can be used for setting a delay between when a note is played and when the LFO modulation starts kicking in (gradually). This way, you can make the sound start unmodulated, and then have the LFO modulation start after you have kept the key(s) pressed down for a while.

Turn the knob to the right to increase the delay time.

Mode (LFO 1 only)

This lets you set the "operation mode" for the LFO. Click the button to switch between the available modes:

- **Group Rate**
  In this mode, the LFO will run at the rate set for its group in the group section, rather than at the rate set here (see "Group parameters"). This way, all zones in the group will have the exact same modulation rate.
- **Tempo Sync**
  In this mode, the LFO will be synchronized to the song tempo, in one of 16 possible time divisions.

! **When tempo sync is activated, the Rate knob is used for selecting the desired timedivision. Turn the Rate knob and observe the tool tip for an indication of the timedivision.**

- **Free Run**
  In free run mode, the LFO simply runs at the rate set with the Rate parameter. Furthermore, if Key Sync is deactivated, the modulation cycle will not be retriggered each time you press a key - it will run continuously.

Waveform (LFO 1 only)

Here, you select which type of waveform should be used for modulating the destination parameters.

Click the button to switch between the following waveforms:

Waveform	Description
Triangle	This is a smooth waveform, suitable for normal vibrato.
Inverted Sawtooth	This produces a "ramp up" cycle. If applied to an oscillator's frequency, the pitch would sweep up, after which the cycle immediately starts over.
Sawtooth	This produces a "ramp down" cycle, the same as above but inverted.
Square	This produces cycles that abruptly change between two values, usable for trills etc.
Random	Produces random stepped modulation to the destination. Some vintage analog synths called this feature "sample & hold".
Soft Random	The same as above, but with smooth modulation.

! **LFO 2 always uses a triangle waveform.**

Key Sync (LFO 1 only)

By activating key sync, you "force" the LFO to restart its modulation cycle each time a key is pressed.

! **Note that LFO 2 always uses Key Sync.**

Destinations for LFO 1

The following parameters can be modulated by LFO 1:

- **Pitch**
  This will make the LFO modulate the pitch, for vibrato, trills, etc. It can be set to -2400 – 0 – 2400 cents which equals 4 octaves. The set pitch will change up and down by this amount, with each modulation cycle. Turning the knob to the right will make the modulation cycle start above the set pitch, while turning it to the left will invert the cycle. Keeping this in the middle position means that the pitch will not be affected by the LFO.
- **Filter**
  This will make the LFO modulate the cutoff frequency of the Filter, for auto-wah effects, etc. The positive/negative effect is the same as for pitch.
- **Level**
  This will make the LFO modulate NN-XT's output level, for tremolo effects, etc. The positive/negative effect is the same as for pitch.

Destinations for LFO 2

The following parameters can be modulated by LFO 2:

- **Pan**
  This makes the LFO modulate the pan position of a zone. The sound will move back and forth in the stereo field. Turning the knob to the left makes the sound move from left to right, and turning it to the right thus makes it move from right to left. The middle position provides no modulation at all.
- **Pitch**
  Just like for LFO 1 (see above), this makes LFO 2 modulate the pitch. The range is also the same as for LFO 1.

Connections

On the back panel of NN-XT are a number of connectors. Many of these are CV/Gate related. Using CV/Gate is described in the chapter "Routing Audio and CV".



Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play the NN-XT from another CV/Gate device (typically a Matrix or a Redrum). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Modulation Input

These control voltage (CV) inputs (with associated voltage trim pots), can modulate various NN-XT parameters from other devices. These inputs can control the following parameters:

- **Oscillator Pitch**
- **Filter Cutoff Frequency**
- **Filter Resonance**
- **LFO 1 Rate**
- **Master Volume**
- **Pan**
- **Modulation Wheel**
- **Pitch Wheel**

Gate Input

These inputs can receive a CV signal to trigger the following envelopes:

- **Amplitude Envelope**
- **Modulation Envelope**

Note that connecting to these inputs will override the normal triggering of the envelopes. For example, if you connect a Matrix Gate Out to the Gate In Amp Envelope, you would not trigger the amp envelope by playing notes, as this is now controlled by the Matrix Gate Out. In addition you would only hear the Gate Out triggering the envelope for the notes that you hold down.

Audio Output

There are 16 audio output jacks on the NN-XT's back panel - eight separate *stereo pairs*. When you create a new NN-XT device, the first output pair (1L & 2R) is auto-routed to the first available channel on the audio mixer.

The other output pairs are never automatically routed. If you wish to use any of the other output pairs, you have to manually connect them to the desired device - typically a Mix Channel device. The basics on Routing is described in "Routing Audio and CV".

! **Note that when you use any other output pair than the first, you also have to route one or more zones to it if you want it to actually output sound, since all zones by default are routed to outputs 1 & 2. How to route zones to other outputs is described in the "Out" section.**

Chapter 40
NN-19 Sampler

Introduction

A sampler could be described as a device capable of recording and reproducing audio material, like a tape recorder. Unlike a tape or hard disk based recorder, samplers allows you to "play" the recorded sound via MIDI, using a keyboard for example. This way, any reproducible sound can be integrated into the MIDI environment, and be controlled from sequencers etc. like synthesizers.

The NN-19 is a sampler capable of recording and reproducing - but not editing - sound files.

The program comes with numerous ready-made sample patches, covering all kinds of instrument types. In addition to this there are plenty of single samples that can be used for creating your own patches.

If you want to sample and edit your own sounds, you can use the Sampling function, described in the "Sampling" chapter.

There are also plenty of relatively inexpensive (and even free) audio editing software for both the Windows and the macOS platforms, that will allow you to both record audio (via your computers or audio cards audio inputs), and to edit the resulting audio file. Virtually every software that is capable of this, can create sound files which can be loaded directly into the NN-19.

Also, there are thousands of high quality sample libraries available, covering every conceivable musical style or direction ranging from professionally recorded orchestral samples to esoteric electronic noises.

General sampling principles

Background

Before a sound can be used by a sampler, it must be converted to a digital signal. Hardware samplers and computer audio cards provide audio inputs that can convert the analog signal to digital, by the use of an "A/D Converter" (analog to digital). This "samples" the signal at very short time intervals and converts it to a digital representation of the analog signal's waveform. The sample rate and the bit depth of this conversion determines the resulting sound quality. Finally the signal is passed through a digital to analog converter (D/A) which reconstructs the digital signal back to analog, which can be played back.

Multisampling vs. single samples

Most of the included NN-19 patches are made up of a collection of several samples. This is because a single sampled sound only sounds natural within a fairly narrow frequency range. If a single sample is loaded into an empty NN-19, the sample will be playable across the whole keyboard. The pitch (frequency) of the original sample (called root-key) will be automatically placed on the middle C key (C3).

Note that this has nothing to do with the actual pitch the sample itself produces! It may not even have a pitch as such, it could be the sound of someone talking for example.

If you play any single sample about two octaves above or below its root key, it will most likely sound very "unnatural". In the case of it actually being a sample of someone talking, playing two octaves up will make the talking voice sample sound squeaky, short and most likely unintelligible. Two octaves down the voice will sound something like a drawn-out gargle.

Thus, the range that most samples can be transposed without sounding unnatural is limited. To make a sampled piano, for example, sound good across the whole keyboard, you need to first have made many samples at close intervals across the keyboard, and then define an upper and lower range for each sample, called a Key Zone. All the keyzones in the piano sample patch then make up a Key Map.

How to create key zones is described in "About Key Zones and samples".

To sample real instruments accurately requires a lot of hard work. Firstly, you need the original instrument, which should be in perfect working order. For acoustic instruments you need a couple of good microphones, a mixer or other device with high quality microphone preamps, and a room with good acoustics. You need to be meticulous when recording the different samples, so that levels are smooth and even across the range etc.

Fortunately Reason provides a wide range of high quality multisampled instruments, so much of this hard work has already been done for you.

In our experience, most people don't use samplers only for playing sampled versions of "real" instruments. Very often, single "stand alone" or single samples are used. Maybe you wish to use different sounds for every key zone. Or you could have complete chorus and verse vocals plus variations assigned to several "one note" key zones. Or use samples of different chords that play rhythmic figures to the same tempo, and use these to build song structures etc. The possibilities are endless. When you use samples in this way, the keys on your keyboard that play the samples do not necessarily correspond to pitch at all, the keys are simply used to trigger the samples.

About audio file formats

The audio file format support differs depending on which computer OS you are using.

The NN-19 can read audio files in the following formats:

- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFonts (.sf2)**
  SoundFonts are an open standard for wavetable synthesized audio, developed by E-mu systems and Creative Technologies.
- **REX file slices (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). The NN-19 lets you either load REX files as patches or separate slices from REX files as individual samples.
- **Any sample rate and practically any bit depth.**

About the Sample Patch format

Reason's Sample Patch format (.smp), is based on either Wave or AIFF files, but includes all the NN-19 associated parameter settings as well.

- **The audio files may be stereo or mono. Stereo audio files are shown with a "S" symbol beside its name in the display.**

Loading a Sample Patch

When you create a new NN-19 device, it is automatically loaded with a default patch. If you want to start from scratch, with no samples loaded, you can select "Reset Device" from the context menu or Edit menu. For NN-19 to produce sound, you need to load either a sample patch, or a sample - or sample a sound yourself using the Sampling function (see "Sampling").

A patch contains "everything". All the samples, assigned key zones, and associated panel settings will be loaded. Loading a sample patch is done using the Browser, just like in all other devices that use Patches.

1. **Click the Browse Patch button on the front panel to set browse focus to the NN-19 device.**
2. **Navigate to the folder that contains the NN-19 patch you wish to load, select it and click Load in the Browser.**

▶ **Alternatively, drag an NN-19 patch from the Browser and drop it on the NN-19 device in the rack.**
The panel is dimmed in orange and the Patch Replace symbol appears in the center.

Loading REX Files as Patches

REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). In Reason, REX files are primarily used in the Dr. Octo Rex loop player, but they can be used in the NN-19 as well. Possible extensions are ".rx2", ".rcy" and ".rex".

1. **Click the Browse Patch button on the front panel to set browse focus to the NN-19 device.**
2. **Navigate to the folder that contains the REX loop you wish to load, select it and click Load in the Browser.**

▶ **Alternatively, drag a REX loop from the Browser and drop it on the NN-19 device in the rack.**
The panel is dimmed in orange and the Patch Replace symbol appears in the center.

When loading a REX file, each slice in the file is assigned to one key, chromatically, starting from C1. All parameters are set to their default settings.


When using REX files in the Dr. Octo Rex loop player, it is possible to make a track play the slices in order to recreate the original loop. To do the same in the NN-19 requires a few extra steps.

1. **Use the Browser to load the REX file into an NN-19 sampler.**
2. **Create a Dr. Octo Rex loop player and load the same REX file into o Loop Slot of this device.**
3. **Use the "Copy Loop To Track" feature on the Dr. Octo Rex to create playback data (a group) on the track assigned to the Dr. Octo Rex.**
4. **Move that group to the track that plays the NN-19 and play it back from there.**
5. **Delete the Dr. Octo Rex loop player.**

Sampling in NN-19

The sampling procedure is generic for all Reason devices that can sample (NN-19, NN-XT, Redrum and Kong). The sampling and sample editing procedures are described in detail in the "Sampling" chapter.

▶ **To sample your own sound and automatically load it into the NN-19 device, click the Sample button.**




Refer to the "Sampling" chapter for details on how to set up and use the sampling feature.

About Key Zones and samples

Loading a Sample into an empty NN-19

1. **Create an NN-19 device and select "Reset Device" from the context menu or from the Edit menu.**
2. **Click on the Browse Sample button.**
   This is located above the keyboard display to the left.



- ▶ **When you browse samples, you can preview them before loading using the Play button in the Browser. If you select the "Autoplay" function, the samples play back once automatically when selected.**

3. **Select a sample in the Browser and click the Load button in the Browser to load it.**

- ▶ **Alternatively, drag a sample file from the Browser and drop it on the NN-19 device in the rack.**
  The panel is dimmed in blue and a Sample Replace symbol appears in the center.

When you load the first sample into an empty NN-19, this will be assigned a key zone that spans the entire range of the keyboard, and the default Init Patch settings will be used.

Below the keyboard, the range, sample name, root key, tuning, level and loop status of the current key zone is displayed, each with a corresponding knob.



The light blue strip above the keyboard indicates the currently selected key zone, which is in this case the full range of the keyboard.

The inverted note on the keyboard indicates the "root key" of the sample. All samples contain a root key, tuning and level setting. If NN-19 is empty, a sample will have its root key placed on the middle "C" (C3) key.

4. **If desired, click on the keyboard to change the root key.**

- ! **You can audition a loaded sample patch or sample by holding down [Option] (Mac)/[Alt] (Windows) and clicking on a key in the Keyboard display. The mouse will take on the shape of a speaker symbol to indicate this.**

Loading SoundFont samples

The SoundFont format was developed by E-mu systems in collaboration with Creative Technologies. It is a standardized data format containing wavetable synthesized audio and information on how it should be played back in wavetable synthesizers - typically on audio cards. The SoundFont format is an open standard so there is a vast amount of SoundFont banks and SoundFont compatible banks developed by third parties.

The samples in a SoundFont are stored hierarchically in different categories: User Samples, Instruments, Presets etc. The NN-19 allows you to browse for and load single SoundFont samples, but *not* entire soundfonts.

1. **Click the Browse Sample button, select a SoundFont file (.sf2) in the Browser and open it.**
   The Browser opens the SoundFont and displays the folders within it.
2. **Select the folder "Samples" and open it.**
   This folder contains a number of samples which can be loaded like any other sample.
3. **Select the desired sample and load it by clicking the Load button in the Browser.**
   The sample is loaded and assigned a key zone range that spans the entire keyboard. You can now make settings for it as with any other sample.

- **Alternatively, drag a sample file from the Browser and drop it on the NN-19 device in the rack.**
  The panel is dimmed in blue and a Sample Replace symbol appears in the center.

Loading REX slices as samples

A slice is a snippet of sound in a REX File.

1. **To import a REX slice, click the Browse Sample button (see above), browse to a REX file and open it as if it was a folder.**
   The Browser will then display the slices as files inside that "folder".
2. **Select the desired REX slice and load it by clicking the Load button in the Browser.**
   The REX slice is loaded and assigned a key zone range that spans the entire keyboard. You can now make settings for it as with any other sample.

- **Alternatively, drag REX slice from the Browser and drop it on the NN-19 device in the rack.**
  The panel is dimmed in blue and a Sample Replace symbol appears in the center.

In the rest of this manual, when we refer to importing samples, all that is said applies to REX slices as well.


Creating Key Zones

A "key zone" is a range of keys, that plays a sample. All key zones together make up a "key map".

To create a new key zone, the following methods can be used:

- **Select "Split Key Zone" from the Edit or context menus.**
  This splits the currently selected key zone in the middle. The new zone is the upper half of the split, and is empty. The dividing point has a "handle" above it, see "Setting the Key Zone Range" below for a description.

- **By [Alt]/[Option]-clicking at a point just above the key zone strip, a new empty key zone is created.**
  The point where you click becomes the lower limit (or boundary) for the original key zone, and the upper limit for the new key zone.



The new empty key zone gets selected upon creation.

Selecting Key Zones

Only one key zone can be selected at a time. A selected key zone is indicated by a light blue (as opposed to dark blue) strip above the keyboard in the display. There are two ways you can select key zones:

- **By clicking on a non-selected key zone in the display.**
- **By activating the "Select Key Zone via MIDI" button.**
  Playing a note belonging to a non-selected key zone from your MIDI keyboard, will select the key zone it belongs to.


Setting the Key Zone Range

! **Key zones cannot overlap.**

When you adjust the boundaries of a key zone, the surrounding boundaries are automatically adjusted accordingly.

You can change the key zone range in the following ways:

- **By dragging the "handle(s)" which divides the key zones, you can change the range of the selected key zone.**
  In the case of having two key zones split in the middle, you could thus change the lower limit for the upper (new) key zone and the upper limit for the original key zone.



▶ **By using the "Lowkey" and "Highkey" knobs to set a lower and upper range, respectively.**



Deleting a Key Zone

▶ **To delete a key zone, select it and then select "Delete Key Zone" from the Edit menu.**

About Key zones, assigned and unassigned samples

When you load samples and rearrange your key mapping, you will often end up with samples that are not assigned to any key zone. In the following texts we refer to the samples as follows:

- **Assigned samples are samples that are currently assigned to one ore more key zones.**
- **Unassigned samples are samples that reside in the sample memory, but that are currently not assigned to any key zone.**

Adding sample(s) to a Key Map

If the sample hasn't been loaded yet

1. **Select a key zone.**
   This can be empty, or contain a sample - it doesn't matter for now.
2. **Use the Browser to add one, or several (see below), sample(s).**

The following will happen:


▶ **If the zone contained a sample prior to loading, this will be *replaced*, both in the zone and in the sample memory, unless the sample was also used by *another* key zone, in which case it will be kept.**

▶ **If you loaded several samples, one of the samples will be assigned to the key zone, and the other samples will be loaded but remain unassigned.**

If the sample is already loaded but unassigned

1. **Select a key zone.**
   This can be empty, or contain a sample - it doesn't matter for now.

2. **Use the Sample knob to dial in the sample you want the key zone to play.**



The Sample knob.

Setting the Root Key

Once you have defined a key zone, and added a sample, you should set the root key for the sample.

- **Select the key zone the sample belongs to, and click on the key you wish to set the root key to.**
  Which key to select is normally determined by the pitch of the sample. For example if the sample plays a F#2 guitar note, click on F#2.
- **Note that it is possible to select a root key outside the key zone, if required.**

Removing sample(s) from a Key Map

- **To remove a sample, select the zone it belongs to, and then select "Delete Sample" from the Edit or context menus.**
  The sample is removed from the zone and from sample memory.
- **To remove a sample from a key zone/map, *without* removing it from memory, you can either select "No Sample" with the Sample knob for that zone, or simply replace it with another sample in the same way.**

Removing all unassigned samples

- **To remove all samples that are not assigned to any key zone, select Delete Unused Samples from the Edit menu.**

Rearranging samples in a Key Map

There is no specific function for rearranging or trading places between samples and key zones. Simply select a key zone and change the current sample assignment with the Sample knob.

Setting Sample Level

For each key zone you can set a volume level, using the Level button below the display. If the transition between two key zones causes a noticeable level difference, this parameter can be used to balance the levels.

Tuning samples

Sometimes you might find that the samples you wish to use in a key map are slightly out of tune with *each other*. This parameter allows you to tune each sample in a map by +/– half a semitone.

- **Select the key zone(s) that contains the out of tune sample(s), and use the Tune knob below the keyboard display.**
- **If all samples originate from different sources, and all or most of them are pitched slightly different (a not uncommon sampling scenario), you could first tune them so that they all match each other, and then, if necessary, use the Sample Pitch controls in the Osc section to tune them globally to the "song" you wish to use the samples in.**

▶ **Note that if all the samples were slightly out of tune *by the same amount* in relation to the song you intend to use the samples in, it would be much simpler to use the Sample Pitch controls in the Osc section directly.**

Looping Samples



A sample, unlike the cycles of an oscillator for example, is a finite quantity. There is a sample start and end. To get samples to play for as long as you press down the keys on your keyboard, they need to be *looped*.

For this to work properly, you have to first set up two loop points which determine the part of the sample that will be looped, and make this a part of the audio file. You cannot set loop points in the NN-19, this has to be done in the Edit Sample window (see "Looping samples") or in an external sample editor.

All included samples already have set loop points (if needed).

For each sample (or key zone), you can select the following Loop modes by using the Loop knob below the keyboard display:

▶ **OFF**
No looping is applied to the sample.

▶ **FWD**
The part between the loop points plays from start to end, then the cycle is repeated. This is the most common loop mode.

▶ **FWD - BW**
The part between the loop points plays from start to end, then from end to start, and then repeats the cycle.

! **For samples without any loop points, the whole sample will be looped.**

About the Solo Sample function

The Solo Sample button will allow you to listen to a selected sample over the entire keyboard range.

▶ **Select the key zone the sample is assigned to, and then activate Solo Sample.**
This can be useful for checking if the root key is set correctly or if the current range is possible to extend etc.

! **For Solo Sample to work, "Select Key Zone via MIDI" must be disabled!**

Automap Samples

If you have a number of samples that belong together, but haven't mapped them to key zones you can use the "Automap Samples" function on the Edit menu. This is used in the following way:

1. **Select all samples that belong together and load them in one go, using the sample browser.**
   One of the samples will be assigned to a key zone spanning the whole range, and the rest will be loaded in to memory but remain unassigned.
2. **Select Automap Samples from the Edit menu.**

Now all samples currently in memory (assigned or unassigned) will be arranged automatically so that:

- **Each sample will be placed correctly according to its root note, and will be tuned according to the information in the sample file.**
  Most audio editing programs can save root key information as part of the file.
- **Each sample will occupy half the note range to the next sample's root note.**
  The root key will always be in the middle of each zone, with the zone extending both down and up in relation to the root position.

Mapping samples without Root Key or Tuning information

Some samples may not have any information about root key or tuning stored in the file. If the file names indicate the root key you can manually set it for each sample using the method described below. In a worst case scenario, i.e. no tuning or root key information whatsoever, you can still make use of the Automap function:

1. **Select all samples that belong together and load them in one go, using the sample browser.**
   One of the samples will be assigned to a key zone spanning the whole range, and the rest will be loaded in to memory but remain unassigned.
2. **Manually set the root key, and adjust the tune knob if the sample needs fine-tuning.**
   Without any information stored in the file, or if the file name doesn't indicate the root key, you will have to use your ears for this step. Play the sample and use another instrument or a tuner to determine its pitch.
3. **Select the next sample using the Sample knob, and repeat the previous step.**
   Proceed like this until you have set a root key for all the samples in memory.
4. **Select "Automap Samples" from the edit menu.**
   The samples will be mapped according to their set root key positions!

How Mapping Information is saved

All information about key zones, high and low range, root key etc. is stored as part of the Sampler Patch. The original sample files are never altered!

NN-19 synth parameters

The NN-19 synth parameters are used to shape and modulate samples. These are mostly similar to the parameters used to shape the oscillators in Subtractor - you have envelope generators, a filter, velocity control etc. Again, it is important to remember that these parameters do not alter the audio files in any way, only the way they will play back.

! **These parameters are global, in the sense that they will affect all samples in a sample patch.**

The Oscillator Section



For a sample patch, the actual samples are what oscillators are for a synthesizer, the main sound *source*. The following settings can be made in the Osc section of the NN-19:

Sample Start

This changes the start position of samples in a sample patch. Turning the knob clockwise gradually offsets the samples' start position, so that they will play back from a position further "into" the samples' waveform. This is useful mainly for two things:

- **Removing "air" or other unwanted artefacts from the start of less than perfect samples.**
  Occasionally (although not in any samples supplied with Reason) you may come across samples where the start point of the sample is slightly ahead of the start of the actual sound. There may be noise or silence in the beginning which was not intended to be part of the sample. By adjusting the sample start position, this can be removed.
- **Changing the start point as an effect.**
  For example, if you had a sample of someone saying "one, two, three", you could change the start position so that when you played the sample it would start on "three".
- **You can also assign velocity sample start allowing to use your playing to determine the exact sample start. See later in this chapter.**

Setting Sample Pitch - Octave/Semitone/Fine

By adjusting the corresponding knobs you can change the pitch of all samples belonging to a patch, in three ways:

- **Octave steps**
  The range is 0 - 8. The default setting is 4.
- **Semitone steps**
  Allows you to raise the frequency in 12 semitone steps (1 octave).
- **Fine steps (100th of a semitone)**
  The range is -50 to 50 (down or up half a semitone).

! **Note that the controls in this section cannot be used to tune samples against each other, as all samples will be affected equally. To tune individual samples, you use the Tune parameter below the keyboard display (see "Tuning samples").**

Keyboard Tracking

The Osc section has a button named "Kbd. Track". If this is switched off, the sample's pitch will remain constant, regardless of any incoming note pitch messages, although the oscillator still reacts to note on/off messages. This could be useful if you are using non-pitched samples, like drums for example. You could then play a sample in a zone using several keys, allowing for faster note triggering if you wanted to play a drum roll, for example.

Osc Envelope Amount

This parameter determines to what degree the overall pitch of the samples will be affected by the Filter Envelope (see "Filter Envelope"). You can set negative or positive values here, which determines whether an envelope parameter should raise or lower the pitch.

The Filter Section



Filters are used for shaping the overall timbre of the sound. The filter in NN-19 is a multimode filter with five filter types.

Filter Mode

With this selector you can set the filter to operate as one of five different types of filter. These are as follows:

- **24 dB Lowpass (LP 24)**
  Lowpass filters lets low frequencies pass and cuts out the high frequencies. This filter type has a fairly steep roll-off curve (24dB/Octave). Many classic synthesizers (Minimoog/Prophet 5 etc.) used this filter type.
- **12 dB Lowpass (LP 12)**
  This type of lowpass filter is also widely used in classic analog synthesizers (Oberheim, TB-303 etc.). It has a gentler slope (12 dB/Octave), leaving more of the harmonics in the filtered sound compared to the LP 24 filter.
- **Bandpass (BP 12)**
  A bandpass filter cuts both high and low frequencies, while midrange frequencies are not affected. Each slope in this filter type has a 12 dB/Octave roll-off.
- **High-Pass (HP12)**
  A highpass filter is the opposite of a lowpass filter, cutting out the lower frequencies and letting the high frequencies pass. The HP filter slope has a 12 dB/Octave roll-off.
- **Notch**
  A notch filter (or band reject filter) could be described as the opposite of a bandpass filter. It cuts off frequencies in a narrow midrange band, letting the frequencies below and above through.

Filter Frequency

The Filter Frequency parameter (often referred to as "cutoff") determines which area of the frequency spectrum the filter will operate in. For a lowpass filter, the frequency parameter could be described as governing the "opening" and "closing" of the filter. If the Filter Freq is set to zero, none or only the very lowest frequencies are heard, if set to maximum, all frequencies in the waveform are heard. Gradually changing the Filter Frequency produces the classic synthesizer filter "sweep" sound.

! **Note that the Filter Frequency parameter is usually controlled by the Filter Envelope (see "Envelope Section" below) as well. Changing the Filter Frequency with the Freq slider may therefore not produce the expected result.**

Resonance

The filter resonance parameter (sometimes called Q) is used to set the Filter characteristic, or quality. For lowpass filters, raising the filter Res value will emphasize the frequencies around the set filter frequency. This produces a generally thinner sound, but with a sharper, more pronounced filter frequency "sweep". The higher the resonance value, the more resonant the sound becomes until it produces a whistling or ringing sound. If you set a high value for the Res parameter and then vary the filter frequency, this will produce a very distinct sweep, with the ringing sound being very evident at certain frequencies.

- **For the highpass filter, the Res parameter operates just like for the lowpass filters.**
- **When you use the Bandpass or Notch filter, the Resonance setting adjusts the width of the band. When you raise the Resonance, the band where frequencies are let through (Bandpass), or cut (Notch) will become narrower. Generally, the Notch filter produces more musical results using low resonance settings.**

Envelope Section


Envelope generators are used to control several important sound parameters in analog synthesizers, such as pitch, volume, filter frequency etc. Envelopes govern how these parameters should respond over time - from the moment a note is struck to the moment it is released.

Standard synthesizer envelope generators have four parameters; Attack, Decay, Sustain and Release (ADSR).

There are two envelope generators in the NN-19, one for volume, and one for the filter frequency.


! **Please refer to the Subtractor chapter for a description of the basic envelope parameters.**

Amplitude Envelope



The Amp Envelope is used to adjust how the volume of the sound should change from the time you press a key until the key is released. By setting up a volume envelope you sculpt the sound's basic shape with the four Amplitude Envelope parameters, Attack, Decay, Sustain and Release. This determines the basic character of the sound (soft, long, short etc.). The Level parameter acts as a general volume control for the sample patch.

Filter Envelope



The Filter Envelope can be used to control two parameters; filter frequency and sample pitch. By setting up a filter envelope you control the how the filter frequency and/or the sample pitch should change over time with the four Filter Envelope parameters, Attack, Decay, Sustain and Release.

Filter Envelope Amount

This parameter determines to what degree the filter will be affected by the Filter Envelope. Raising this knob's value creates more drastic results. The Envelope Amount parameter and the set filter frequency are related. If the Filter Freq slider is set to around the middle, this means that the moment you press a key the filter is already halfway open. The set Filter Envelope will then open the filter further from this point. The Filter Envelope Amount setting affects how much further the filter will open.

Filter Envelope Invert

If this button is activated, the envelope will be inverted. For example, normally the Decay parameter lowers the filter frequency, but after activating Invert it will instead raise it, by the same amount. Note that Invert does not affect the Osc pitch parameter (this can be inverted by setting positive or negative values).

LFO Section



LFO stands for Low Frequency Oscillator. LFOs are oscillators in the sense that they generate a waveform and a frequency. However, there are two significant differences compared to normal sound generating oscillators:

- **LFOs only generate waveforms with low frequencies.**
- **The output of the two LFOs are never actually heard. Instead they are used for modulating various parameters.**

The most typical application of an LFO is to modulate the pitch of a (sound generating) oscillator or sample, to produce vibrato.

The LFO section has the following parameters:

Waveform

LFO 1 allows you to select different waveforms for modulating parameters. These are (from the top down):



Waveform	Description
Triangle	This is a smooth waveform, suitable for normal vibrato.
Inverted Sawtooth	This produces a "ramp up" cycle. If applied to an oscillator's frequency, the pitch would sweep up to a set point (governed by the Amount setting), after which the cycle immediately starts over.
Sawtooth	This produces a "ramp down" cycle, the same as above but inverted.
Square	This produces cycles that abruptly changes between two values, usable for trills etc.
Random	Produces random stepped modulation to the destination. Some vintage analog synths called this feature "sample & hold".
Soft Random	The same as above, but with smooth modulation.

Destination

The available LFO Destinations are as follows:

Destination	Description
Osc	Selecting this makes LFO control the pitch (frequency) of the sample patch.
Filter	Selecting this makes the LFO control the filter frequency.
Pan	Selecting this makes the LFO modulate the pan position of samples, i.e. it will move the sound from left to right in the stereo field.

Sync

By clicking this button you activate/deactivate LFO sync. The frequency of the LFO will then be synchronized to the song tempo, in one of 16 possible time divisions. When sync is activated, the Rate knob (see below) is used for setting the desired time division.

Turn the knob and check the tooltip for an indication of the time division.



Rate

The Rate knob controls the LFO's frequency. Turn clockwise for a faster modulation rate.

Amount

This parameter determines to what degree the selected parameter destination will be affected by the LFO. Raising this knob's value creates more drastic results.

Play Parameters

This section deals with two things: Parameters that are affected by how you play, and modulation that can be applied manually with standard MIDI keyboard controls.

These are:

- **Velocity Control**
- **Pitch Bend and Modulation Wheel**
- **Legato**
- **Portamento**
- **Polyphony**
- **Voice Spread**
- **External Controllers**

Velocity Control



Velocity is used to control various parameters according to how hard or soft you play notes on your keyboard. A common application of velocity is to make sounds brighter and louder if you strike the key harder. By using the knobs in this section, you can control how much the various parameters will be affected by velocity. The velocity sensitivity amount can be set to either positive or negative values, with the center position representing no velocity control.

The following parameters can be velocity controlled:

Destination	Description
Amp	This let's you velocity control the overall volume of the sound. If a positive value is set, the volume will increase the harder you strike a key. A negative value inverts this relationship, so that the volume decreases if you play harder, and increases if you play softer. If set to zero, the sound will play at a constant volume, regardless of how hard or soft you play.
F. Env	This sets velocity control for the Filter Envelope Amount parameter. A positive value will increase the envelope amount the harder you play. Negative values invert this relationship.
F. Dec	This sets velocity control for the Filter Envelope Decay parameter. A positive value will increase the Decay time the harder you play. Negative values invert this relationship.
S.Start	This sets velocity control for the Sample Start parameter. A positive value will increase the Start Time amount the harder you play. Negative values invert this relationship.
A. Attack	This sets velocity control for the Amp Envelope Attack parameter. A positive value will increase the Attack time the harder you play. Negative values invert this relationship.

Pitch Bend and Modulation Wheels

The Pitch Bend wheel is used for "bending" notes, like bending the strings on a guitar. The Modulation wheel can be used to apply various modulation while you are playing. Virtually all MIDI keyboards have Pitch Bend and Modulation controls. NN-19 also has two functional wheels that could be used to apply real time modulation and pitch bend should you not have these controllers on your keyboard, or if you aren't using a keyboard at all. The wheels mirror the movements of the MIDI keyboard controllers.

Pitch Bend Range

The Range parameter sets the amount of pitch bend when the wheel is turned fully up or down. The maximum range is "24" (=up/down 2 Octaves).

Modulation Wheel

The Modulation wheel can be set to simultaneously control a number of parameters. You can set positive or negative values, just like in the Velocity Control section. The following parameters can be affected by the modulation wheel:

Destination	Description
F. Freq	This sets modulation wheel control of the Filter Frequency parameter. A positive value will increase the frequency if the wheel is pushed forward. Negative values invert this relationship.
F. Res	This sets modulation wheel control of the Filter Resonance parameter. A positive value will increase the resonance if the wheel is pushed forward. Negative values invert this relationship.
F. Dec	This sets modulation wheel control for the Filter Envelope Decay parameter. A positive value will increase the decay if the wheel is pushed forward. Negative values invert this relationship.
LFO	This sets modulation wheel control of the LFO Amount parameter. A positive value will increase the Amount if the wheel is pushed forward. Negative values invert this relationship.
Amp	This sets modulation wheel control for the Amp level parameter. A positive value will increase the level if the wheel is pushed forward. Negative values invert this relationship.

Legato

Legato works best with monophonic sounds. Set Polyphony (see "Setting Number of Voices - Polyphony") to 1 and try the following:

- **Hold down a key and then press another key without releasing the previous.**
  Notice that the pitch changes, but the envelopes do not start over. That is, there will be no new "attack".
- **If polyphony is set to more voices than 1, Legato will only be applied when all the assigned voices are "used up".**
  For example, if you had a polyphony setting of "4" and you held down a 4 note chord, the next note you played would be Legato. Note, however, that this Legato voice will "steal" one of the voices in the 4 note chord, as all the assigned voices were already used up!

Retrig

This is the "normal" setting for playing polyphonic patches. That is, when you press a key without releasing the previous, the envelopes are retriggered, like when you release all keys and then press a new one. In monophonic mode, Retrig has an additional function; if you press a key, hold it, press a new key and then release that, the first note is also retriggered.

Portamento (Time)

Portamento is when the pitch "glides" between the notes you play, instead of instantly changing the pitch. The Portamento knob is used to set how long it takes for the pitch to glide from one pitch to the next. If you don't want any Portamento at all, set this knob to zero.

Setting Number of Voices - Polyphony

This determines the polyphony, i.e. the number of voices a patch can play simultaneously. This can be used to make a patch monophonic (=a setting of "1"), or to extend the number of voices available for a patch. The maximum number of voices you can set a patch to use is 99.

! **Note that the Polyphony setting does not "hog" voices. For example, if you have a patch that has a polyphony setting of ten voices, but the part the patch plays only uses four voices, this won't mean that you are "wasting" six voices. In other words, the polyphony setting is not something you need to consider if you want to conserve CPU power - it is only the number of voices *actually used* that counts.**

Voice Spread

This parameter can be used to control the stereo (pan) position of voices. The Spread knob determines the intensity of the panning. If this is set to "0", no panning will take place. The following pan modes can be selected:

Mode	Description
Key	This will shift the pan position gradually from left to right the higher up on the keyboard you play.
Key 2	This will shift the pan position from left to right in 8 steps (1/2 octave) for each consecutive higher note you play, and then repeat the cycle.
Jump	This will alternate the pan position from left to right for each note played.

Low Bandwidth

This will remove some high frequency content from the sound, but often this is not noticeable (this is especially true if you have "filtered down" samples). Activating this mode will save you some extra computer power, if needed.

Controller Section

NN-19 can receive common MIDI controller messages, and route these to various parameters. The following MIDI messages can be received:

- **Aftertouch (Channel Pressure)**
- **Expression Pedal**
- **Breath Control**


If your MIDI keyboard is capable of sending Aftertouch messages, or if you have access to an Expression Pedal or a Breath controller, you can use these to modulate NN-19 parameters. The "Source" selector switch determines which of these message-types should be received.

These messages can then be assigned to control the following parameters:

F. Freq	This sets external modulation control of the filter frequency parameter. A positive value will increase the frequency with higher external modulation values. Negative values invert this relationship.
LFO 1	This sets external modulation control of the LFO Amount parameter. A positive value will increase the LFO amount with higher external modulation values. Negative values invert this relationship.
Amp	This let's you control the overall volume of the sound with external modulation. If a positive value is set, the volume will increase with higher external modulation values. A negative value inverts this relationship.

Connections

On the back panel of the NN-19 you will find the connectors, which are mostly CV/Gate related.



Audio Outputs

These are the main left and right audio outputs. When you create a new NN-19 device, these are auto-routed to the first available channel on the audio mixer.

Mono Sequencer Control

These are the main CV/Gate inputs. CV controls the note pitch. Gate inputs trigger note on/off values plus a level, which can be likened to a velocity value. If you want to control the NN-19 from a Matrix Pattern Sequencer for example, you would normally use these inputs. The inputs are “mono”, i.e. they control one voice in the sampler.

Modulation Inputs

! **Remember that CV connections will not be stored in the sample patch, even if the connections are to/from the same NN-19 device!**

These control voltage (CV) inputs (with associated voltage trim pots), can modulate various NN-19 parameters from other devices, or from the modulation outputs of the same NN-19 device. These inputs can control the following parameters:

- **Osc (sample) Pitch**
- **Filter Cutoff**
- **Filter Resonance**
- **Amp Level**
- **Mod Wheel**

Modulation Outputs

The Modulation outputs can be used to voltage control other devices, or other parameters in the same NN-19 device. The Modulation Outputs are:

- **Filter Envelope**
- **LFO**

Gate Inputs

These inputs can receive a CV signal to trigger the envelopes. Note that connecting to these inputs will override the "normal" triggering of the envelopes. For example, if you connected a LFO output to the Gate Amp input, you would not trigger the amp envelope by playing notes, as this is now controlled by the LFO. In addition you would only hear the LFO triggering the envelope for the notes that you hold down.

- **Amp Envelope**
- **Filter Envelope**

Chapter 41
Pangea
World Instruments

Introduction



Pangea World Instruments features a unique assortment of rare instruments from all over the world - perfect for spicing up any music style. Each of the multi-sampled instruments can also be tailored and processed in the high-quality filter, amp, delay and reverb sections.

Panel overview

The Pangea front panel contains the following sections:




The Pangea front panel sections.

- **1. Patch Selector (for browsing, loading and saving patches).**
- **2. Master Volume.**
- **3. Global performance and "play" controls.**
- **4. Instruments section.**
- **5. Filter section.**
- **6. Amp Envelope section.**
- **7. Delay effect section.**
- **8. Reverb effect section.**

Using Pangea

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global performance and "play" controls



Note

The Note LED lights up each time Pangea receives a MIDI Note On.

Range

- ▶ **Set the desired Pitch Bend range for the "Pitch" wheel with the up/down buttons, or by click-holding on the display and dragging up/down.**
  Range: +/-12 semitones (+/-1 octave) in steps of +/-1 semitone.

Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Pangea also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You set the desired Pitch bend Range with the "Range" control to the right of the Mod wheel.

Mod

The Mod wheel can be used for controlling the three predefined parameters to the right of the Mod wheel:

- **S. Start**
  Here you set how/if the Mod wheel should affect the Sample Start position of the currently selected instrument. The parameter is bi-polar, with zero modulation at the 12 o'clock position. A negative value moves the sample start back and a positive value moves it forward.

! **Note that if the S.Start parameter in the Instruments section (see "S. Start (Sample Start)") is at 0 ms, the sample start cannot be moved back any further. Similarly, if the S.Start parameter in the Instruments section is at 150 ms, the sample start cannot be moved forward any further.**

- **F. Freq**
  Here you set how/if the Mod wheel should affect the Filter Cutoff parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.

! **Note that if the Cutoff parameter in the Filter section (see "Cutoff") is at 20 Hz, the frequency cannot be lowered any further. Similarly, if the Cutoff parameter in the Filter section is at 25 kHz, the frequency cannot be raised any further.**

- **Level**
  Here you set how/if the Mod wheel should affect the Master Volume parameter. The parameter is bi-polar, with zero modulation at the 12 o'clock position.


! **The volume can never be modulated louder than the maximum +12 dB limit of the Master Volume control.**

Panel controls

The Instruments section



Instrument selector



▶ **Click the Instrument name selector to bring up a menu of the available instruments - and then select the desired instrument from the menu.**
Alternatively, click and drag up/down in the display above the selector to scroll through the instruments.

! **Depending on the instrument size (in MB), it could take a short moment before the entire instrument is loaded into RAM.**

! **Also note that the note ranges of the instruments extend outside their "natural" ranges, which could produce nice artificial effects.**

The available instruments are:

- **Acoustic Saz**



This is a 5-string electro-acoustic hybrid saz baglema from Turkey, also known as Turkish guitar. It was played with a hard pick and the strings were recorded with external close mics (stereo) in a studio, dry. The samples are from Soundiron's Acoustic Saz library.

- **Angklung**



This is an18-piece tuned bamboo rattle instrument from Indonesia. It was recorded with close mics (stereo) in a large hall. The samples are from Soundiron's Angklung library.

- **Bizarre Sitar**



This is a small 8-string sitar from India. It was played with a hard pick and was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Bizarre Sitar library.

- **Harp Guitar**



This is a custom instrument designed by Brad Hoyt. It was played with a hard pick and was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Brad Hoyt Harp Guitar library.

- **Kinderklavier**



This is a children's toy steel tine piano from Germany. It was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Kinderklavier library.

- **Lakeside Pipe Organ**



This is a large church pipe organ recorded with close mics (stereo) in a large hall, wet. The samples are from Soundiron's Lakeside Pipe Organ library.

- **Little Wooden Flutes**



This is a Native American walnut 6-hole flute. It was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Little Wooden Flutes library.

- **Little Pump Reeds**



This is a pumped reed instrument related to a harmonium, from India. It was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Little Pump Reeds library.

- **Struck Grand Piano**



This is a grand piano, with the strings being struck with a small metal hammer. It was recorded with close mics (stereo) in a large hall. The samples are from Soundiron's Struck Grand Piano library.

- **Traveler Organ**



This is a mechanically operated antique organ, also known as a traveling organ. It is operated by pumping in air using the two pedals and then playing the keyboard. It was recorded with close mics (stereo) in a studio, dry. The samples are from Soundiron's Traveler Organ library.

- **Zitherette**



This is an 8 string fretless zither played with a hard pick. It was recorded with a close mic (mono) in a studio, dry. The samples are from Soundiron's Zitherette library.

S. Start (Sample Start)



▶ **Turn the S.Start knob to set where in the sample the playback should start.**
Note that the effect could be different depending on the selected instrument.

Oct



▶ **Set the octave transposition for the instrument.**
Range: 5 (+/-2) octaves.

! **Note that the note ranges of the instruments can be transposed far outside their "natural" ranges, which could produce nice artificial effects.**

Semi



▶ **Set the pitch in semitone steps.**
Range: +/-12 semitones (two octaves).

Fine




▶ **Set the pitch in steps of 1 cent.**
Range: +/- 50 cents (down or up half a semitone).

The Filter section




Filter On/Off



▶ **Click the On/Off LED button to switch on/off the Filter section.**

Filter Type selector



▶ **Click and drag up/down on the Filter Type selector to select one of the available filter types - or step through the filter types by clicking the Up/Down arrow buttons.**
The available filter types are:

- **LP**
  This is a lowpass filter with 12db/octave slope.
- **HP**
  This is a highpass filter with 12db/octave slope.
- **BP**
  This is a bandpass filter with 6db/octave slopes.
- **Comb**
  This is a comb filter for phaser/flanger type of effects.

Cutoff



- **Set the cutoff/center frequency with the Cutoff knob.**
  The cutoff parameter sets where in the frequency range you want the resonance and attenuation to appear.
  Range: 20 Hz to 25 kHz.

Reso



- **Set the resonance amount with the Reso knob.**
  The resonance parameter amplifies the frequencies at, and around the cutoff/center frequency.

Env



- **With the Env knob you set how much you want the Filter Envelope (see below) to affect the Cutoff frequency.**
  Range: 0% to 100%.

Filter Envelope



The standard ADSR type envelope controls the filter cutoff frequency modulation over time. The ADSR envelope characteristics are described in detail in “Amp Envelope”.

Vel



- **Turn the Vel knob to set how much the cutoff/center frequency should be modulated by Keyboard Velocity.**
  Range: 0% to 100%.

Kbd



- **Turn the KBD (Keyboard Track) knob to set how much the cutoff/center frequency should track incoming MIDI Notes.**
  Range: 0% (no tracking (constant frequency)) to 100% (1 semitone per key).

The Amp section




Vel




- **Turn the Vel knob to set how much the amplitude should be modulated by Keyboard Velocity.**
  Range: 0% to 100%.

Amp Envelope



The Amp Envelope is a standard ADSR envelope which controls the amplitude of the signal over time. The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

- **A(ttack)**
  When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the Master Volume knob. How long this should take, depends on the Attack setting. If the Attack is set to "0", the Volume value is reached instantly. If the Attack value is raised, it will take longer time before the Master Volume value is reached.
- **D(ecay)**
  After the Master Volume value has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

  If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.
- **S(ustain)**
  The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

  If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").


  But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Volume value, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Master Volume value. Note that Sustain represents a level, whereas the other envelope parameters represent times.
- **R(elease)**
  The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

The Delay section



This is a stereo delay which affects all voices globally.

Delay On/Off



▶ **Click the On/Off LED button to switch on/off the Delay section.**

Time



▶ **Set the time between the delay repeats.**
If Sync is active (see below), the Time parameter controls the time divisions.

Feedback



▶ **Set the number of delay repeats with the Feedback knob.**

Sync



▶ **Click the Sync button to sync the delay time to the main sequencer Tempo.**
When active, the Time knob (see above) controls the time divisions.

Ping Pong



- **Activate this to get the delay repeats alternating between the left and right channels.**
  Note that this also doubles the delay tempo.

Damp



- **Raise the Damp value to gradually cut off the high frequencies of the delay repeats.**

Amount




- **Set the delay amount with the Amount knob.**
  Note that the Delay effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a delay effect if you turn up the Amount afterwards (depending on the Feedback setting, see "Feedback").

The Reverb section



This is a stereo reverb which affects all voices globally.

Reverb On/Off



- **Click the On/Off LED button to switch on/off the Reverb section.**

Time



▶ **Set the reverberation duration time.**
In practice this sets the "size" of the reverberation "chamber/room/hall".

Pre-Delay



▶ **Set the pre-delay time of the reverb.**
Range: 0-200 ms.

Hi Damp



▶ **Raise the Hi Damp value to cut off the high frequencies of the reverb and thereby create a smoother, warmer effect.**

Lo Damp



▶ **Raise the Lo Damp value to cut off the low frequencies of the reverb signal, to make the reverb effect less "muddy".**

Amount



▶ **Set the reverb amount with the Amount knob.**
Note that the Reverb effect is routed as a "send effect", with the Amount knob working as an "effect return" control. This means that if you play a short note with the Amount knob set to zero, you might still get a reverb effect if you turn up the Amount afterwards (depending on the Time setting, see "Time").

Connections



! **Remember that CV connections are NOT stored in the Pangea patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play Pangea from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity. There are also inputs for modulating the Pitch Bend and Mod Wheel parameters.

Modulation Inputs

These control voltage (CV) inputs can be used for modulating the Filter Cutoff and Resonance parameters, as well as the Master Volume level.

Audio Out

These are the main audio outputs. When you create a new Pangea device, these outputs are auto-routed to the first available Mix Channel in the Reason main mixer. If there is no Mix Channel available, a new one will be automatically created.

Chapter 42
Polytone Dual-Layer Synthesizer

Introduction



Polytone Dual-Layer Synthesizer is a synth-lover's synth. Inspired by the great analog poly synths of the past, we designed Polytone Dual-Layer Synthesizer so that you could quickly create the warm analog sounds you know and love. With a familiar and immediate interface, you'll feel right at home.

However, it wouldn't be a Reason Studios instrument if we didn't tweak the formula a little. The oscillators include waveshaping and unique flavors of noise for more tonal variety than the classics. Best of all, Polytone Dual-Layer Synthesizer has two layers that can be stacked or morphed between for super fat and evolving sounds.

Polytone Dual-Layer Synthesizer is more than just a replica of the past. It's a loving tribute!

Panel overview

The Polytone Dual-Layer Synthesizer front panel contains the following sections:




The Polytone Dual-Layer Synthesizer front panel sections.

- **1. Patch selector (for browsing, loading and saving patches).**
- **2. Age and Master Volume controls.**
- **3. Layer controls.**
- **4. Layer specific Keyboard, Mod Wheel and Pitch Bend controls.**
- **5. Layer specific Oscillator and Noise section.**
- **6. Layer specific Filter section.**
- **7. Layer specific Amplifier section.**
- **8. Layer specific Modulation LFO section.**
- **9. Layer specific Modulation Envelope section.**
- **10. Layer specific Filter Envelope section.**
- **11. Layer specific Amplifier Envelope section.**
- **12. Global controls, LFO and Effects sections for both layers.**

Signal flow

The picture below show the signal flow in Polytone Dual-Layer Synthesizer:



Polytone Dual-Layer Synthesizer signal flowchart.

Playing and using Polytone Dual-Layer Synthesizer

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Global output controls



Age

This controls the "age" of the synthesizer and simulates the "degradation" of the analog components. This degradation could result in pitch and filter fluctuations, for example, and is a little different for each individual voice. Pitch fluctuation was never a desired behavior of course, but has later become kind of a "nostalgic" effect. Use it if you like!

Range: 2024 to 1970

Volume

This is the main stereo output volume control.

Global performance and "play" controls



Pitch

The Pitch bend wheel can be used for bending note pitches up and down. Polytone Dual-Layer Synthesizer also responds to Pitch Bend MIDI data from a connected MIDI master keyboard. You can then set the desired Pitch Bend Range with the "P.Bend Range" control individually for each layer.

Mod

The Mod wheel can be used for controlling FM Amount, Filter Frequency and LFO Depth individually for each layer in Polytone Dual-Layer Synthesizer.

Voices

Here you set the desired maximum polyphony of your patch, from 1 to 20 voices. This control is mainly intended for deliberately restricting the polyphony of a sound. If you just want to play a polyphonic patch you can leave the Voices setting at 20 at all times. The DSP Load won't increase with higher voice number settings - only if you play a lot of notes simultaneously.


▶ **If you want monophonic playback you could use the "Retrig" and "Legato" modes instead of lowering the Voices parameter to 1.**

Key Mode

Here you choose how Polytone Dual-Layer Synthesizer should respond to MIDI Note data:

- **Poly**
  Select this if you want to play Polytone Dual-Layer Synthesizer polyphonically. The maximum number of voices is 20. The number of voices is set in the Voices control at the center right of the Polytone Dual-Layer Synthesizer panel, see "Voices".
- **Retrig**
  Select this if you want to play Polytone Dual-Layer Synthesizer in monophonic mode and always retrigger the envelopes as soon as you play a new note.
- **Legato**
  The Mono Legato mode is also monophonic. However, if you play a new note without having released the previous one, the envelopes won't start over.

Layer controls



Like the name suggests Polytone Dual-Layer Synthesizer consists of two individual layers - Layer A and Layer B. Each layer has the same configuration and features the same parameters.

You can edit Layer A and Layer B separately and then define how you want the layers to play back: individually, mixed together, or by morphing between the layers.

Mixing the layers opens up for really nice and fat sounds, whereas morphing between the layers can generate really complex evolving sounds. The mixing/morphing can be controlled from the Mod Wheel, Keyboard Velocity, Global LFO, or from a fader on the front panel. The mix/morph balance can also be controlled from the "Mix/Morph" CV input on the rear panel.

A/B




▶ **Click the A or B button to select which layer to edit (or play, depending on the "Mode" setting).**
When Layer A is selected, the front panel has a blue background and when Layer B is selected the background is red:





Layer A selected (to the left) and Layer B (to the right)

Mode




▶ **Select how the layers should play back.**
In Single mode each layer plays back individually, depending on if you have clicked the A or B button (see above).

In Mix mode the layers play back mixed together. The mix relation is defined by the "Mix/Morph" setting.

In Morph mode all the settings of the layer-specific parameters in each layer are morphed between, depending on the "Mix/Morph" setting. In practice, morphing means that the parameters continuously move between the values they have in the two layers.

In the picture below the Reso, Freq and Type parameters in the Filter section have different values in Layer A and B. At a Morph value of 50% these parameters have morphed halfway to the values of the other Layer:



Three parameters with different values in Layer A and Layer B, and the (50%) morphed result in the image to the right.

Mix/Morph



Here you select how the layers should play back when Mix or Morph mode has been selected (see "Mode").

- **Select Wheel to control the layer mix/morph relation from the Mod Wheel.**
  A low Mod Wheel value will play back more of Layer A and vice versa.
- **Select Vel to control the layer mix/morph relation from Keyboard Velocity.**
  Low Keyboard Velocity values will play back more of Layer A and vice versa.
- **Select G. LFO to control the layer mix/morph relation from the Global LFO, see "The Global LFO section".**
  When mixing/morphing, the Global LFO always uses the full LFO range, independently of the Global LFO Level.
- **Select Fader to control the layer mix/morph relation from the fader to the right of the buttons.**
  The center position of the fader represents a 50/50 Mix/Morph of Layer A and B.

Copy



Here you choose if you want to copy or swap all the layer-specific parameter settings of a layer to/with the other layer.

- **Click the desired button to copy or swap the layer(s).**
  If you should accidentally hit the wrong button, there is always the [Cmd]/[Ctrl]+[Z] (Undo) function to the rescue.

Panel reference

! **Note that all sections below that have pictures with blue panel color describe parameters and functions that are individual for each of the two Layers.**

Glide



Glide (portamento) makes note pitches glide from previous notes to new ones, at the time set with the Time knob. Glide can be used in all Key Modes (see "Key Mode").

- **When On in Poly Key Mode, the pitches will glide from any of the available voices.**
  The results will be unpredictable since there is no way of controlling from which note(s) the glide(s) will commence. The effect is very nice, though.
- **When On in Retrig or Legato Key Mode, the pitch will glide between consecutive notes.**
- **If Auto is selected, the pitch will glide between consecutive monophonic notes only when you play legato. If you have selected Poly Key Mode, Auto will have no effect at all.**
  If you release the previous key before hitting the new key, there will be no glide effect.

Wheels



- **With the FM AMT knob you control how much the Mod Wheel should affect the "FM Amt" parameter in the Oscillator section.**
- **With the FILTER FREQ knob you control how much the Mod Wheel should affect the "Freq" parameter of the Filter.**
- **With the LFO DEPTH knob you control how much the Mod Wheel should scale the MOD parameters - if they are set to a value in the "LFO range".**
  The MOD parameters can be found in the Oscillator and Filter sections:



! **To have any effect, the MOD knobs have to be set somewhere in the "LFO range", i.e. turned counter-clockwise from the 12 o'clock position.**

If you set the LFO DEPTH knob to maximum and have some other MOD knobs set to an "LFO range" value, the Mod Wheel will gradually introduce the LFO modulation the further you move it. With the Mod Wheel at zero, there will be no LFO modulation at all.

See "The Mod LFO section" for more information about the LFO.

P.Bend Range



▶ **Set the desired range for the Pitch Bend wheel (see "Pitch") with the up/down buttons, or by dragging up/down in the display.**
Range: +/-24 semitones (+/-2 octaves) in steps of +/-1 semitone.

The Oscillator section



The Oscillator section consists of two separate Oscillators, plus a Noise oscillator and a Mixer. The two Oscillators can also be cross-modulated (Oscillator 2 frequency modulates Oscillator 1) or synced (Oscillator 1 is synced to Oscillator 2).

The parameter configuration is identical for the two Oscillators.

KBD

- **Set how much the pitch should track incoming MIDI Notes.**
  Range: 0% (no tracking (constant pitch)) to 100% (1 semitone per note).

Fine

- **Change the pitch in steps of 1 cent.**
  Range: +/- 50 cents (down or up half a semitone).

Pitch

- **Set the pitch of the respective Oscillator with the Pitch knob.**
  Range: +/-24 semitones (+/-2 octaves) in steps of 1 semitone.

Pitch Mod

- **Set a desired pitch modulation amount with the Mod knob.**
  Turning the knob counter-clockwise from the 12 o'clock position will make the MOD LFO modulate the pitch. Turning the knob clockwise from the 12 o'clock position will modulate the pitch from the MOD ENV.

  Range: 100-0% LFO modulation and 0-100% MOD ENV modulation.

Waveform selector

- **Click the spin control buttons, or click the display to select the desired oscillator waveform.**
  You can then change the waveform shape with the "Shape" knob.

The following waveforms are available:

- **Saw-Pulse**
  A sawtooth wave at Shape=0 gradually transformed to a 50% duty cycle square wave at Shape=100%.
- **Pulse**
  A ~5% duty cycle pulse wave at Shape=0 gradually transformed via a 50% duty cycle square wave towards a ~95% duty cycle pule wave at Shape=100%.
- **Triangle**
  A pure triangle (odd partials only) wave at Shape=0 with gradual introduction of even partials up to 50%, then gradual reduction of the odd partials, resulting in only even partials (one octave up) at Shape=100%.

- **Sine**
  A pure sine wave at Shape=0. Increasing the Shape value will sweep through the harmonic overtones, resulting in a pure sine wave 3 octaves above the root note at Shape=100%.
- **Digital**
  A selection of very nice and useful wave tables which you could crossfade between with the Shape knob.
- **Band Noise (Oscillator 1 only)**
  Noise, where Shape controls the bandwidth. With Shape at 0% the result is close to a sine wave, while higher Shape settings adds progressively more noise.
- **Chaos (Oscillator 2 only)**
  This produces a wide range of noises and heavily modulated signals, great for adding a bit of chaos to the sound!

Shape

▶ **Turn the Shape knob to transform the Oscillator waveforms, as described above.**

Shape Mod

▶ **Set a desired Shape modulation amount with the Shape Mod knob. Turning the knob counter-clockwise from the 12 o'clock position will make the MOD LFO modulate the Shape. Turning the knob clockwise from the 12 o'clock position will modulate the Shape from the MOD ENV.**
Range: 100-0% LFO modulation and 0-100% MOD ENV modulation.

FM Amt

▶ **Set the amount of linear frequency modulation of Oscillator 1 by Oscillator 2 with the FM Amt knob.**


FM Amt Mod

▶ **Set a desired FM Amt modulation amount with the FM Amt Mod knob.**
Turning the knob counter-clockwise from the 12 o'clock position will make the MOD LFO modulate the FM Amt. Turning the knob clockwise from the 12 o'clock position will modulate the FM Amt from the MOD ENV.

Range: 100-0% LFO modulation and 0-100% MOD ENV modulation.

Osc Sync

▶ **Click the Osc Sync button to have Oscillator 2 sync the restart of Oscillator 1.**
Oscillator sync is when one oscillator will restart the period of another oscillator, so that they will have the same base frequency. In Polytone Oscillator 2 is the syncing oscillator, and thus controls the pitch. If you change or modulate the pitch of the synced oscillator (Oscillator 1 in Polytone) you get that characteristic sound associated with oscillator sync. To hear the sync effect, make sure you listen to Oscillator 1.



Syncing oscillator

(Oscillator 2)

Synced oscillator

(Oscillator 1)

▶ **Modulate the pitch of Oscillator 1 to get the characteristic "sync sound", see "Pitch Mod".**

The Mixer



The Oscillator Mixer is where you mix and set the signal level from the Oscillator section. You can also add Noise to the signal.

1-Mix-2

- **Set the mix between the Oscillator 1 and 2 signals.**

Level

- **Set the level of the mixed oscillator signals.**
  High level settings will overdrive the Filter input, as indicated by the Drive LED in the Filter section (see "Drive").

Noise


- **Set the level of white noise you want to add to the mixed oscillator signals.**
  White noise contains all frequencies at equal energy levels.

The Filter section




The Filter section features a very advanced (continuous) state variable filter. The filter types are:


- **24 dB/Oct Lowpass**




- **12 dB/Oct Lowpass**




- **12 dB/Oct Bandpass**



- **12 dB/Oct Highpass**



- **24 dB/Oct Highpass**




The really clever thing with the Polytone filter is that you can continuously sweep through all filter types, i.e. the filter types "morph" into each other seamlessly from 24 dB LP to 24 dB HP.

Drive

- **The Drive LED lights up when the signal in the Filter is overdriven (e.g. by a high "Level" and/or by a high "Reso" setting).**

Reso

▶ **Set the resonance amount with the Reso knob.**
A high Resonance setting will amplify the signal level around the cut-off Frequency, as described in this picture:



! **Be careful when using high Resonance values as this could generate quite loud audio levels!**

Freq

▶ **Set the cutoff frequency (or center frequency for the Bandpass filter type) with the Freq knob.**

Filter type

▶ **Select the desired filter type with the knob.**
Range: continuous between 24 dB LP and 24 dB HP

Env

▶ **Set how much you want the Filter Envelope to affect the filter cutoff Frequency.**
Range: -100 (inverted modulation) to 100 (positive modulation)

Vel

▶ **Set how much you want the Filter Envelope Amount to be affected by Keyboard Velocity.**
Range: 0-100%


KBD

- **Set how much the cutoff Frequency should track incoming MIDI Notes.**
  Range: 0% (no tracking (constant Frequency)) to 100% (1 semitone per note).

Freq Mod

- **Set a desired cutoff Frequency modulation amount with the Freq Mod knob.**
  Turning the knob counter-clockwise from the 12 o'clock position will make the MOD LFO modulate the cutoff Frequency. Turning the knob clockwise from the 12 o'clock position will modulate the cutoff Frequency from the Oscillator 2 signal, resulting in the popular "Filter FM" effect found on some great analog synths from the past.

  Range: 100-0% LFO modulation and 0-100% Oscillator 2 modulation.




The Filter Envelope section



The Filter Envelope can be used for modulating the Filter cutoff frequency over time. You set the modulation amount with the "Env" knob in the Filter section. It features the standard Attack, Decay, Sustain and Release parameters of an ADSR envelope.

The various envelope stages work exactly like those of the Amp Envelope, see "The Amp Envelope section".



The ADSR envelope stages.

A(ttack)

- **Set the time it should take to reach from the set "Freq" value to the maximum Filter Frequency value.**

D(ecay)

▶ **Set the time it should take to go from maximum Filter Frequency value to the Sustain value (see below).**

S(ustain)

▶ **Set the Filter Frequency value the envelope should rest at, after the Decay stage (see above).**

R(elease)

▶ **Set the time it should take to go from the Sustain level back to the set "Freq" value, after you have released the key.**

The Amp section



The Amp section is where you control the output gain of the signal, as well as any Keyboard Velocity and stereo Spread.

Gain

▶ **Set the desired maximum level for the Amplifier with the Gain knob.**
This is the maximum level the Amp Envelope will reach after the Attack stage is completed (see Amp Envelope).

Vel

▶ **If you want the Gain level to be controlled from Keyboard Velocity, turn up the Vel knob.**

Spread

▶ **Set the desired stereo spread of the output signal from the Amplifier.**
Spread pans each alternate voice left-right (with Spread controlling the amount of panning). This means that if you play a chord, the individual notes in the chord will be panned differently.

In Mix mode, the Spread panning will be mirrored for Layer A and B. By mixing two detuned or slightly different layers with Spread, you can create a really wide stereo sound.


! **Note that the Spread function doesn't work in Legato mode, see "Legato".**

The Amp Envelope section



The Amp Envelope section contains a standard ADSR envelope, which controls the amplitude of the signal.

The picture below shows the various stages of the ADSR envelope:



The ADSR envelope stages.

A(ttack)

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the value set with the "Gain" knob in the Amp section. How long this should take, depends on the Attack setting. If the Attack is set to "0", the Gain level is reached instantly. If the Attack value is raised, it will take longer time before the Gain level is reached.

D(ecay)

After the Gain level has been reached, the level starts to drop. How long this should take is governed by the Decay parameter.

If you want to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0", the Decay parameter should be set to a medium value and the Sustain level should be set to "0", so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you raise the Sustain parameter.

S(ustain)

The Sustain parameter determines the level the envelope should rest at, after the Decay stage. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.

If you want to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to the Gain level, then gradually decreases to finally land to rest on a level somewhere in-between zero and the Gain level. Note that Sustain represents a level, whereas the other envelope parameters represent times.

R(elease)

The Release parameter works just like the Decay parameter, except it determines the time it takes for the volume to drop back to zero after you release the key.

The Mod LFO section



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of a signal to produce vibrato, but there are also other applications for LFOs.

The Mod LFO is used for modulating parameters in the selected Layer that feature MOD knobs with an LFO sector, i.e. the Oscillator and Filter sections. Here is also where you set the desired modulation amount for the parameters, by turning the MOD knobs counter-clockwise from the 12 o'clock positions:



▸ **You can also gradually introduce the LFO modulation amount by using the Mod Wheel, see "Wheels".**

Waveform selector

▸ **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by click-holding in the display and dragging up or down.**
Besides the standard waveforms (sine, triangle, pulse, etc.) there are stepped and smooth random waveforms. The shape of the waveforms are shown in the display.

! **Note that the MOD LFO waveforms are switched between - not continuously morphed between - in Morph Mode.**

Rate

▸ **Set the LFO frequency with the Rate knob.**
Range: 0.16-57.0 Hz

Delay

▸ **Turn the Delay knob to introduce a delay before the LFO modulation kicks in after you play a note.**
Range: 0-2.0 s


The Mod Envelope section



The Mod Envelope section consists of a simple AR (Attack, Release) envelope, which can be used for modulating parameters in the selected Layer that feature MOD knobs with an ENV sector, i.e. the Oscillator section. Here is also where you set the desired modulation amount for the parameters, by turning the MOD knobs clockwise from the 12 o'clock positions:



The Mod Envelope has two stages - Attack and Release, according to the following principle:



The ADSR envelope stages.

As you can see in the picture above, Key Down triggers the envelope, but the Key Up doesn't matter if it happens after the envelope has finished its two stages.

If Key Up happens before the Attack stage has finished, the Release stage takes over at the current Level.

Attack

▶ **Set the time it should take to reach from zero to the maximum modulation value.**

Release

▶ **Set the time it should take to go from maximum modulation value back to zero.**
if Release if set to max, it will be infinite, acting as sustain.

Vel

▶ **Turn up the Vel knob if you want the Mod Envelope level to be controlled from Keyboard Velocity.**

The Global LFO section



The Global LFO affects parameters in both Layers globally. It can also be used for modulating the Mix or Morph between the Layers. Note that the Global LFO is also global for all voices, meaning it modulates all voices equally and simultaneously.

Waveform selector

- **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by clicking the display and dragging up or down.**
  Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.

Rate

- **Set the LFO frequency with the Rate knob.**
  Range: 0.16-57.0 Hz

Sync

- **Click the Sync button to have the Rate synced to time divisions of the main sequencer tempo.**

1-Shot

- **Click the 1-Shot button to have the LFO only run one single cycle of the waveform.**
  This is useful if you want the LFO to work as kind of an "extra" envelope generator for controlling a desired target parameter.

  When Polytone is in Retrig Mode (see "Key Mode"), the LFO will retrigger with each new note, regardless of how you play. In all other Key Modes, the LFO will require that you release all notes before it can retrigger (it will not retrigger if you play legato).

Level

- **Set the desired modulation amount with the Level knob.**

Target selector

- **Select the desired target (destination) parameter for the LFO modulation, by clicking the spin controls to the right of the waveform display, or by clicking the display and selecting from the pop-up menu.**
- **Note that you can also control the Morph "position" from the Global LFO. You can set this up by clicking the G. LFO button in the "Mix/Morph" section.**

The Chorus section



The Chorus section features a stereo chorus effect with two selectable speeds, and a fixed-speed stereo flanger effect.

- **Set the effect level with the Amount knob.**
- **Click one of the buttons for the desired effect.**


The Reverb section



The Reverb section features a stereo echo effect and two types of stereo reverbs.

- **Set the echo/reverb level with the Amount knob.**
- **Set the echo/reverb decay time with the Decay knob.**
- **Click one of the buttons to select the desired effect type.**

Connections



Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play Polytone Dual-Layer Synthesizer from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Mix/Morph

This CV input allows for control of the Mix/Morph balance.

CV Modulation inputs

These control voltage (CV) inputs and can be used for modulating the corresponding parameters from external modulations sources. All inputs also have a corresponding attenuation knob for adjusting the input CV level.

Audio Output

These are the main audio outputs.

Wheels

These are CV inputs for modulating the Pitch Bend and Mod Wheel parameters. The inputs also have a corresponding attenuation knob for adjusting the input CV signal level.

Chapter 43
Radical Piano

Introduction



Radical Piano is designed to be a straightforward, awesome sounding and very flexible piano. Radical Piano combines sample playback technology with physical modeling to give you great sound quality and seamless dynamic response as well as great freedom to tweak your sounds.

The combination of sample playback and physical modeling also makes it possible to keep each piano sound set down to a minimum size. This allows for very quick loading times when you switch between instruments.

Radical Piano also features sympathetic resonance, which means that any undamped strings will ring along with the played notes (strings), just like on acoustic pianos. This makes Radical Piano sound extremely realistic and alive. There are also a number of other controls for further shaping the sound the way you want it.


As a bonus, we also included an audio input so you can route external audio and process it in Radical Piano!

The pianos

Radical Piano holds complete sound sets recorded from these three pianos:

- **Home Grand**
  A Bechstein grand piano with a nice “not perfectly tuned” home grand character.
- **Deluxe Grand**
  A Steinway Model D grand piano - one of the greatest grand pianos out there. This particular one belongs to Sveriges Radio (Swedish Radio Ltd).
- **Upright**
  A Futura upright piano with a distinct “living room” character.

The microphone configurations



The microphone configurations for the grand pianos and the upright piano respectively.

The pianos were recorded using up to nine microphones per instrument, placed at various critical positions inside and outside of the pianos. The different microphone recordings were then stored in Radical Piano as separate sound sets.

The following microphone configurations were used:

- **Vintage Mono**
  A single microphone placed outside the waist of the grand piano (or behind the upright piano). For the Steinway grand piano we used an old school mono ribbon mic with vintage characteristics and a narrow frequency response with the emphasis in the mid range. For the Futura upright piano we used a vintage tube microphone.
- **Ambience**
  Two microphones in AB configuration* placed quite far away from the piano to capture the room ambience.
- **Floor**
  Two pressure zone microphones that lay flat on the floor just behind the front legs of the grand piano (and behind the upright piano). They add depth and richness to the sound and are best used as a complement to the other mics.
- **Jazz**
  Two microphones in AB configuration* placed just outside/in front of the piano. This gives a full bodied sound with a wide stereo image and a less pronounced attack.
- **Close**
  Two microphones in XY configuration** placed close to the hammers. The close mics produce a distinct sound with a sharp attack, ideal for uptempo pop/rock.

* AB configuration: Two mics in stereo configuration placed several feet apart and tilted slightly away from each other.

** XY configuration: Two mics in stereo configuration placed close together in 'V' shape at a 90° coincidence.

Using Radical Piano

Loading and saving patches

Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Selecting piano sound sets


A patch in Radical Piano can consist of a mix between two piano sound sets. The mix could be between two sound sets from the same piano, or from different pianos. You could, for example, blend a Close mic'ed upright piano with the Floor microphones from a grand piano to create your own custom piano sound. The piano sound sets can be selected in the Piano Select section:



The Piano Select section.

1. **Select desired piano sound set(s) by clicking the corresponding LED button(s).**
   You can select one sound set to the left of the Blend knob and one to the right.
2. **Set the mix between the sound sets with the Blend Microphones knob.**
   If you only want to use a single sound set for your sound, set the Microphone Blend knob to min or max.

Character



▶ **Set the character of the sound with the Character knob.**
Range: Subdued to Agitated, in 24 steps, with natural sound at the 12 o'clock position.
Subdued produces a warm and mellow tone whereas Agitated generates a brighter and significantly more pronounced tone.

! **Changing the Character value temporarily mutes the audio outputs.**

Volume



The master volume control for Radical Piano.

Velocity Response



Most sample-based piano instruments and sound libraries on the market use a predefined number of velocity layers. Depending on how soft or hard you play the keys, samples from a specific velocity layer play back. Due to memory limitations, the number of velocity layers aren't often that many. This can make the velocity response feel and sound unnatural. Thanks to the combination of samples and physical modeling in Radical Piano, all sound sets feature very wide and completely seamless velocity ranges.

With the Velocity Response knobs you can tailor the dynamic response of your piano sound.

- **With the High knob you set the timbre for the highest velocity.**
  Note that the High parameter can go far beyond the natural range of an acoustic piano, which is great for experimental sounds.
- **With the Low knob you set the timbre for the lowest velocity.**
  With the Low knob set to zero (marked with an 'S') playing really soft won't play back any sound at all. This can be useful if you, for example, want to hold down a chord and then play other keys to introduce the sympathetic resonance effect, see "Resonance".
- **With the Curve knob you set the shape of the velocity curve - from exponential, via linear to logarithmic.**
  Set this parameter where it feels the best to play. There is no "perfect" position since most MIDI keyboards respond differently to velocity.

▶ **If you want a natural dynamic range, set the Low knob to around the 9 o'clock position and the High knob to around the 12 o'clock position. Adjust the Curve setting to your liking.**

▶ **If you want a dynamic range that stretches beyond the range of an acoustic piano, set the Low knob to zero and the High knob past the 12 o'clock position.**

▶ **If you want a static response (with the same timbre no matter how soft or hard you play), set the Low knob to max and the High knob to zero. Note that there will still be some velocity sensitivity left for controlling the volume.**

Tune



Cent

▶ **Set the overall master tune of your sound with the Cent knob.**
Range: +/-1 semitone (+/-100 cents).

Drift

The Drift parameter can be used for introducing a slow irregular pitch variation to your sound. It's perfect for adding kind of a "scary" or melancholic touch to your piano sound.

Sustain



The Sustain parameter is a special feature in Radical Piano. It lets you control the piano sustain continuously from pedal up to pedal down. As on acoustic pianos, the sustain pedal is not either "on" or "off - it can be "somewhere in between" as well. The Sustain function in Radical Piano simulates this behavior.

The Sustain parameter can be controlled either from the Pedal LED strip control on the front panel or from a Sustain pedal connected to the Sustain Pedal input of your MIDI master keyboard.

- **When you use a standard (switch type) sustain pedal connected to a standard sustain pedal input on your MIDI keyboard, this will control the Sustain function in Radical Piano as either Off ('0') or On ('127').**
  You could record using the standard sustain pedal and then manually edit the Sustain Pedal performance controller data in the note clip in Reason afterwards and adjust the "in between" Sustain levels.

! **The Sustain parameter value (and LED bar) will always adjust to the latest incoming Sustain Pedal data, be it from the Pedal LED strip control or from a sustain pedal connected to your MIDI keyboard.**

Resonance



Sympathetic resonance is a physical phenomenon that can occur in acoustic instruments, like in pianos for example. It means that any undamped strings will ring along with the played strings. For example, if you play a key with the sustain pedal down, all other strings in the piano will also vibrate at various intensities. Similarly, if you hold down a number of keys (so that the dampers are off the strings) and then play additional keys, the strings for the held keys will resonate.

With the Resonance controls you set the amount of sympathetic resonance in your piano sound.

Level

- **Set the amount of overall sympathetic resonance in your sound.**

Release Time

- **Set the time it should take for the sympathetic resonance to fade to silence.**

Envelope



Radical Piano features a special type of envelope generator which is used for shaping the character of the piano sound.

Attack

- **Set the attack time for the piano sound, from immediate to (unnaturally) slow.**
  The range is 0-200 ms.

Decay Curve

- **Set the shape of the decay curve.**
  This control determines how the sound should decay when you play and hold the keys.
  The range is from exponential, via linear, to logarithmic. Exponential settings will make the sound decay faster, which simulates a piano with little body sustain. Logarithmic settings makes the sound sustain more slowly and simulates a piano with a lot of body sustain.

Release

- **Set the time it should take for the sound to fade to silence once you release the keys.**
  This simulates the behavior of the dampers. For example, worn out dampers could result in somewhat longer release times.

Mechanics



The Mechanics section features controls for the mechanical noise.

Key Down

- **Key Down controls the level - and character - of the noise that occurs when the keys are pressed/hit.**
  At the 12 o'clock position the noise is the most natural. Above the 12 o'clock position the noise is more pronounced and below the 12 o'clock position the noise is suppressed.

Key Up

- **Key Up controls the level of the noise that occurs when the keys are released and the hammers and dampers return to their initial positions.**
  At the 12 o'clock position the noise level is natural. Above the 12 o'clock position the noise is louder and below the 12 o'clock position the noise is quieter.

Pedal

- **Pedal controls the level of the noise that occurs when you press and release the sustain pedal.**
  At the 12 o'clock position the noise level is natural. Above the 12 o'clock position the noise is louder and below the 12 o'clock position the noise is quieter.

EQ



The built-in equalizer is a powerful 3-band EQ with gain controls for the Low, Mid and High bands. The EQ characteristics have been fine tuned and optimized for piano sounds. The gain range is +/-18dB for each of the bands, which makes it easy to quickly achieve great sonic results.

The EQ can be switched on/off by clicking the LED button at the top.

Ambience



The Ambience section features four different reverb types and a Level control. The reverb types are:

- **Small Room**
  This simulates the acoustic reflections in a small room.
- **Large Room**
  This simulates the acoustic reflections in a large room.
- **Hall**
  This simulates the acoustic reflections in a medium size hall.
- **Theater**
  This simulates the acoustic reflections in a large hall/theater.

Output



Comp(ression)

This controls the amount of compression of your piano sound.


Width

This lets you set the stereo width of the piano sound.

! **Note that the Width control does not have any effect on the sound if you use only the "Vintage Mono" piano sound set(s), see "Selecting piano sound sets".**

Connections

! **Remember that CV connections will not be stored in the Radical Piano patch!**



Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play Radical Piano from another CV/Gate device (typically a Matrix or an RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Modulation In

These control voltage (CV) inputs (with associated trim pots) can modulate following parameters in Radical Piano:

- **Pitch**
  The Pitch can be modulated at a maximum range of +/-1 octave.

! **Note that +/- 1 octave is the maximum range a piano sound can be pitch shifted in Radical Piano. This assumes that no Pitch Bend performance controller is used (see "Pitch Bend") and that the Character knob is set to Natural (see "Character").**

- **Master Volume**

Audio In

Route an external audio signal to this input to process it with the Resonance, EQ, Ambience and Compression effects in Radical Piano.

▶ **Routing a vocal signal and processing it with the sympathetic resonance effect (with the sustain pedal down) could generate really interesting results. It would be like singing into a piano body!**

Audio Out

These are the main audio outputs. When you create a new Radical Piano device, these outputs are auto-routed to the first available Mix Channel in the main mixer. If there is no Mix Channel available, a new one will be automatically created.

Additional external control

The Radical Piano responds to the following standard Performance Controllers:

- **Pitch Bend**
  Radical Piano responds to Pitch Bend data from the pitch bend control of your MIDI master keyboard.
  The range is fixed at +/-7 semitones.

! **Note that the Character setting (see "Character") as well as any Pitch CV modulation (see "Pitch") can reduce the Pitch Bend range.**

- **Sustain Pedal**
  If you have a standard (switch type) sustain pedal connected to a standard Sustain Pedal input of your MIDI master keyboard, this can be used for controlling Sustain On/Off. You can then edit the Sustain values in your note clips in the sequencer afterwards and set continuous values all the way between 0-127, see "Sustain" for more details.

Chapter 44
Redrum Drum Computer

Introduction



At first glance, Redrum looks styled after pattern-based drum machines, like the legendary Roland 808/909 units. Indeed, it does have a row of 16 step buttons that are used for step programming patterns, just like the aforementioned classics. There are significant differences, however. Redrum features ten drum "channels" that can each be loaded with an audio file, allowing for completely open-ended sound possibilities. Don't like the snare - just change it. Complete drum kits can be saved as Redrum Patches, allowing you to mix and match drum sounds and make up custom kits with ease.

In addition, Redrum also has sampling capability. This means that you can sample your own sounds straight into each of the ten drum channels with just a click of a button!

Sampling in Redrum

The sampling procedure is generic for all devices that can sample (NN-19, NN-XT, Redrum and Kong). The sampling and sample editing procedures are described in detail in the "Sampling" chapter.

- **To sample your own sound and automatically load it into a drum channel in the Redrum device, click the Sample button for the desired drum channel.**



Refer to the "Sampling" chapter for details on how to set up and use the sampling feature.

About file formats

Redrum reads two basic types of files:

Redrum Patches

A Redrum patch (Windows extension ".drp") contains all settings for all ten drum sound channels, including file references to the used drum samples (but not the actual drum samples themselves). Switching patches is the same as selecting a new drum kit.

Drum Samples

The audio file format support differs depending on which computer OS you are using.

Redrum can read audio files in the following formats:

- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFonts (.sf2)**
  SoundFonts are an open standard for wavetable synthesized audio, developed by E-mu systems and Creative Technologies.
- **REX file slices (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). Redrum lets you load separate slices from REX files as individual samples.
- **Any sample rate and practically any bit depth.**

Using patches

When you create a new Redrum device it is loaded with a default kit. If you like you can program a pattern and play back using the default kit - or you can load another Redrum patch (or create one from scratch, by loading individual drum samples). A Redrum patch contains settings for the ten drum sound channels, complete with file references to the drum samples used.

! **Redrum patterns are not part of the patch! If you want to save Redrum patches complete with patterns, create a Combinator containing the Redrum and save the Combi patch.**

Loading a patch

To load a patch, use one of the following methods:

- **Use the Browser to locate and load the desired patch.**
  To open the browser and set browse focus to the Redrum device, select "Browse Redrum Patches" from the Edit menu or device context menu, or click the folder button in the patch section on the device panel.



- **Once you have selected a patch, you can step between all the patches in the same folder by using the arrow buttons next to the patch name display.**
- **If you click on the patch name display on the device panel, a pop-up menu will appear, listing all patches in the current folder.**
  This allows you to quickly select another patch in the same folder, without having to step through each one in turn.
- **Drag a Redrum (.drp) patch from the Browser and drop on the device panel.**
  The panel is dimmed in orange and a Patch Replace symbol appears in the center.

Checking the sounds in a patch

There are two ways you can listen to the sounds in a patch without programming a pattern:

- **By clicking the Trigger (arrow) button at the top of each drum sound channel.**



- **By playing the keys C1 to A1 on your MIDI keyboard.**
  C1 plays drum sound channel 1 and so on. See also "Using Redrum as a sound module".

Both these methods play back the drum sample for the corresponding drum sound channel, with all settings for the sound applied.

Creating a new patch

To create a patch of your own (or modify an existing patch), you use the following basic steps:

1. **Click the folder button for a drum sound channel.**
   The Redrum sample browser opens.



2. **Locate and load a drum sample.**
   You will find a large number of drum samples in the Factory Sound Bank (in the folder Redrum Drum Kits/xclusive drums-sorted). You can also load other samples in any supported format.

▶ **Alternatively, drag a sample file from the Browser and drop on the desired sound channel section.**
The sound channel is dimmed in blue and a Sample Replace symbol appears in the center.

3. **Make the desired settings for the drum sound channel.**
   The parameters are described in "Redrum parameters".

4. **Repeat steps 1 and 3 for the other drum sound channels.**

5. **When you're satisfied with the drum kit, you can save the patch by clicking the Floppy Disk button in the patch section on the device panel.**
   Note however, that you don't necessarily need to save the patch - all settings are included when you save the song.

Loading REX file slices

Loading slices from within a REX file is done much in the same way as loading "regular" samples:

1. **Open the Browser as described above.**

2. **Browse to a REX file.**
   Possible extensions are ".rx2", ".rex" and ".rcy".

3. **Unfold the REX file.**
   The browser will now display a list of all the separate slices within the REX file.

4. **Select the desired slice and click the Load button in the Browser.**
   The slice is loaded into the Redrum.

▶ **Alternatively, drag a REX slice file from the Browser and drop on the desired sound channel section.**
The sound channel is dimmed in blue and a Sample Replace symbol appears in the center.

Creating an empty patch

To "initialize" the settings in the Redrum, select "Reset Device" from the Edit menu or the device context menu. This removes all samples for all drum sound channels, and sets all parameters to their default values.

Programming patterns

Pattern basics


Redrum contains a built-in pattern sequencer. Unlike the main sequencer in Reason, the Redrum sequencer repeatedly plays back a pattern of a specified length. The typical analogy in the "real world" is a drum machine which plays drum patterns, usually one or two bars in length.

Having the same pattern repeat throughout a whole song may be fine in some cases, but most often you want some variations. The solution is to create several different patterns and program pattern changes (automatic switching from one pattern to another) at the desired positions in the song.

How the Redrum pattern sequencer integrates with the main sequencer

The built-in pattern sequencer in the Redrum interacts with the main Reason sequencer in the following ways:

- **The tempo set on the transport panel is used for all playback.**
  If the Tempo track (see "Recording tempo automation") is used, Redrum will follow this.
- **If you start playback for the main sequencer (on the transport panel), the Redrum will automatically start as well (provided the pattern sequencer hasn't been disabled - see below).**
- **You can mute and solo Redrum tracks in the sequencer.**
  If the Redrum has a track in the sequencer and you mute this track, Redrum will automatically be muted as well. This is indicated by a Mute indicator on the device panel. If there are several note lanes on the Redrum track, their respective mute status will not be indicated on the device panel.



This Redrum device is muted.

- **You can also run Redrum separately (without starting the main sequencer) by clicking the Run button on the device panel.**
  This starts the built-in pattern sequencer in the device. To stop playback, click the Run button again or click the Stop button on the Transport panel.



The Run button on the Redrum.

- **If you are running Redrum separately and start playback of the main sequencer, the pattern device will automatically restart in sync with the sequencer.**

- **Pattern changes can be controlled by pattern change events in the main sequencer.**
  In other words, you can record or create pattern changes in the main sequencer, and have them occur at the correct position on playback.
- **The sound sources can also be played by the main sequencer, or via MIDI.**
  You can combine the built-in pattern playback with playback from the main sequencer or via MIDI. For example, this allows you to add variations or fills to a basic pattern.
  It is also possible to disable the pattern sequencer totally, converting the device to a pure sound module. This is done by deactivating the Enable Pattern Section switch.



Selecting patterns

The Redrum has 32 pattern memories, divided into four banks (A, B, C, D).



The Bank and Pattern buttons for the Redrum pattern sequencer.


- **To select a pattern in the current bank, click on the desired Pattern button (1-8).**
  If you like, you can assign computer key commands and/or MIDI messages to pattern selection.
- **To select a pattern in another bank, first click the desired Bank button (A, B, C, D) and then click the Pattern button.**
  Nothing happens until you click the Pattern button.
- **If you select a new pattern during playback, the change will take effect on the next downbeat (according to the time signature set in the transport panel).**
  If you automate pattern changes in the main sequencer, you can make them happen at any position - see "Recording pattern automation".
- **Note that you cannot load or save patterns - they are only stored as part of a song.**
  However, you can move patterns from one location to another (even between songs) by using the Cut, Copy and Paste Pattern commands.

Pattern tutorial

If you are unfamiliar with step programming patterns, the basic principle is very intuitive and easy to learn. Proceed as follows:

1. **Load a Redrum patch, if one isn't already loaded.**
2. **Make sure an empty pattern is selected.**
   If you like, use the Clear Pattern command on the Edit menu or device context menu to make sure.

3. **Make sure that the "Enable Pattern Section" and the "Pattern" buttons are activated (lit).**



4. **Press the "Run" button.**
   There will be no sound, as no pattern steps have been recorded yet. But as you can see, the LEDs over the Step button light up consecutively, moving from left to right, and then starts over. Each Step button represents one "step" in the Pattern.

5. **Select a Redrum channel, by clicking the "Select" button at the bottom of the channel.**
   The button lights up, indicating that this channel and the drum sound it contains is selected.



6. **While in Run mode, press Step button 1, so that it lights up.**
   The selected sound will now play every time Step 1 is "passed over".

7. **Clicking other Step buttons so they light up will play back the selected sound as the sequencer passes those steps.**
   Clicking on a selected (lit) step button a second time removes the sound from that step and the button goes dark again. You can click and drag to add or remove steps quickly.

8. **Select another Redrum channel to program steps for that sound.**
   Selecting a new sound or channel also removes the visual indications (static lit buttons) of step entries for the previously selected sound. The step buttons always show step entries for the currently selected sound.

9. **Continue switching between sounds, and programming steps to build your pattern.**
   Note that you can erase or add step entries even if Run mode isn't activated.

Setting pattern length

You may want to make settings for Pattern length, i.e the number of steps the pattern should play before repeating:



- **Use the "Steps" spin controls to set the number of steps you wish the pattern to play.**
  The range is 1 to 64. You can always extend the number of steps at a later stage, as this will merely add empty steps at the end of the original pattern. You could also make it shorter, but that would (obviously) mean that the steps "outside" the new length won't be heard. These steps aren't erased though; if you raise the Steps value again, the steps will be played back again.

About the "Edit Steps" Switch

If you set the pattern length to more than 16 steps, the pattern steps following after the 16th won't be visible, although they will play back. To view and be able to edit the next 16 steps, you have to set the Edit Steps switch to 17-32. To see and edit steps beyond 32 you set the switch to 33-48, and so on.

Setting pattern resolution



Redrum always follows the tempo setting on the transport panel, but you can also make Redrum play in different "resolutions" in relation to the tempo setting. Changing the Resolution setting changes the length of each step, and thereby the "speed" of the pattern.

Step dynamics

When you enter step notes for a drum sound, you can set the velocity value for each step to one of three values: Hard, Medium or Soft. This is done by setting the Dynamic switch before entering the note.



The color of the step buttons reflect the dynamics for each step. Soft notes are light yellow, Medium notes are orange and Hard are red.

- **When the Medium value is selected, you can enter Hard notes by holding down [Shift] and clicking.**
  In the same way, you can enter Soft notes by holding down [Option] (Mac) or [Alt] (Windows) and clicking. Note that this doesn't change the Dynamic setting on the device panel - it only affects the notes you enter.
- **When you use different dynamics, the resulting difference in the sound (loudness, pitch, etc.), is governed by the "VEL" knob settings for each drum channel (see "Redrum parameters").**
  If no velocity amount is set for a drum channel, it will play back the same, regardless of the Dynamic setting.
- **To change the dynamics for an already programmed step, set the switch to the dynamic value you wish to change it to and click on the step.**

! **Note that if you are triggering Redrum via MIDI or from the main sequencer, the sounds will react to velocity like any other audio device. The Dynamic values are there to offer velocity control when using the built-in pattern sequencer.**

Pattern Shuffle

Shuffle is a rhythmic feature, that gives the music a more or less pronounced swing feel. It works by delaying all sixteenth notes that fall in between the eighth notes. You can activate or deactivate shuffle individually for each Redrum pattern by clicking the Shuffle button on the device panel.



The amount of shuffle is set globally with the Global Shuffle control in the ReGroove Mixer - see "The ReGroove Mixer".



Flam




A flam is when you double-strike a drum, to create a rhythmic or dynamic effect. Applying flam to a step entry will add a second "hit" to a drum sound. The flam amount knob determines the delay between the two hits.

To add a flam drum note, proceed as follows:

1. **Activate flam by clicking the Flam button.**
2. **Click on a step to add a note (taking the Dynamic setting into account as usual).**
   A red LED is lit above the step to indicate that flam will be applied to that step.
3. **Use the Flam knob to set the desired amount of flam.**
   The flam amount is global for all patterns in the device.

- **To add or remove flam to or from an existing step note, click directly on the corresponding flam LED.**
  You can also click and drag on the LEDs to add or remove several flam steps quickly.
- **Applying flam to several consecutive step entries is a quick way to produce drum rolls.**
  By adjusting the Flam knob you can create 1/32 notes even if the step resolution is 1/16, for example.

The Pattern Enable switch




If you deactivate the "Pattern" button the pattern playback will be muted, starting at the next downbeat (exactly as if you had selected an empty (silent) pattern). For example, this can be used for bringing different pattern devices in and out of the mix during playback.

- **You can also mute Redrum devices in the sequencer using the Mute button for the track connected to the Redrum. If you do so, this will mute the Redrum output instantly, and the Mute indicator on the Redrum panel lights up. Note that all tracks connected to this Redrum device must be muted for this to work.**



The Mute indicator

The Enable Pattern Section switch



If this is off, Redrum will function as a pure "sound module", i.e. the internal Pattern sequencer is disengaged. Use this mode if you wish to control Redrum exclusively from the main sequencer or via MIDI (see "Using Redrum as a sound module").

Pattern functions

When a Redrum device is selected, you will find some specific pattern functions on the Edit menu (and on the device context menu):

Function	Description
Shift Pattern Left/Right	These functions move all notes in the pattern one step to the left or right.
Shift Drum Left/Right	The Shift Drum functions move all notes for the selected drum channel (the channel for which the Select button is lit) one step to the left or right.
Randomize Pattern	Creates a random pattern. Random patterns can be great starting points and help you get new ideas.
Randomize Drum	Creates a random pattern for the selected drum sound only - the notes for the other drum sound channels are unaffected.
Alter Pattern	The Alter Pattern function modifies the selected pattern by "shuffling" the current pattern notes and redistributing them among the drum sounds at random. This creates a less chaotic pattern than the "Randomize Pattern" function. Note that there must be something in the pattern for the function to work on - using an Alter function on an empty pattern will not do anything.
Alter Drum	Works like the "Alter Pattern" function, but affects the selected drum sound only.

Chaining patterns

When you have created several patterns that belong together, you most probably want to make these play back in a certain order. This is done by recording or inserting pattern changes into the main sequencer. See "Recording pattern automation".

Converting Pattern data to notes in the main sequencer


You can convert Redrum Patterns to notes in the main sequencer. This allows you to edit the notes freely, create variations or use Groove quantizing.

The "Copy Pattern to Track" function

This function is useful when you have created a single pattern in the Redrum device and want to render individual note events on the sequencer track. You could also use this if you e.g. have created a drum pattern and want to have the pattern play back some other type of device.

Proceed as follows:


1. **Set the Left and Right Locators to encompass the section you want to "fill" with the notes in the pattern.**
   You may want to make sure that the space between the locators is a multiple of the pattern length, to avoid "cutting off" the pattern.
2. **Select the device in the rack and select "Copy Pattern to Track" from the Edit menu or the device context menu.**
   The pattern is converted to a single note clip on the track (see the notes below). If the space between the locators is greater than the pattern length, the pattern will be repeated in the clip to fill up the space.



An internal Redrum drum pattern converted to note events on the track

When you use the "Copy Pattern to Track" function with the Redrum, you should note the following:

- **The notes will have the pitch of the corresponding drum sound (see "Using Redrum as a sound module") and the velocity depending on the "Dynamic" parameter value in the device.**
  "Soft" notes get velocity 30, "Medium" notes get velocity 80 and "Hard" notes get velocity 127.
- **You probably want to turn off the "Enable Pattern Section" switch on the Redrum device panel.**
  Otherwise, the drum sounds will be double-triggered during playback (by the pattern section itself, and by the rendered notes on the sequencer track).



The "Convert Pattern Automation to Notes" function

If you have recorded or drawn pattern changes on a Redrum track, you can have the whole track converted to notes, in the following way:

1. **Select the track with the pattern automation.**
2. **Select "Convert Pattern Automation to Notes" from the Edit menu or the context menu for the track.**
   For each pattern clip, the corresponding pattern is converted to note clips on the track (following the same rules as for the "Copy Pattern to Track" function). The track will play back just the same as when you played the pattern device with the pattern changes.

▶ **After the operation, the Pattern Select lane is switched off.**
The "Enable Pattern Section" button on the device is automatically turned off.

Redrum parameters

Drum sound settings

Redrum features ten drum sound channels that can each be loaded with a Wave or AIFF sample or a sample from a SoundFont bank. Although they are basically similar, there are three "types" of drum sound channels, with slightly different features. This makes some channels more suitable for certain types of drum sounds, but you are of course free to configure your drum kits as you like.

On the following pages, all parameters will be listed. If a parameter is available for certain drum sound channels only, this will be stated.


Mute & Solo



At the top of each drum sound channel, you will find a Mute (M) and a Solo (S) button. Muting a channel silences its output, while Soloing a channel mutes all other channels. Several channels can be muted or soloed at the same time.

You can also use keys on your MIDI keyboard to mute or solo individual drum sounds in real time.

- **The keys C2 to E3 (white keys only) will mute individual drum channels starting with channel 1.**
  The sounds are muted for as long as you hold the key(s) down.
- **The keys C4 to E5 (white keys only) will solo individual drum channel, starting with channel 1.**
  The sounds are soloed for as long as you hold the key(s) down.



This is a great way to bring drum sounds in and out of the mix when playing Reason live. You can also record the drum channel Mutes in the main sequencer, just like any other controller (see "Recording parameter automation").

The Effect Sends (S1 & S2)



On the back panel of Redrum you will note two audio connections labeled "Send Out" 1 and 2. When you create a Redrum device, these will by default be auto-routed to the first two "Chaining Aux" inputs on the Mixer device (provided that these inputs aren't already in use).

This feature allows you to add effects to independent drum sounds in the Redrum.

- **Raising the S1 knob for a drum sound channel will send the sound to the first send effect connected to the mixer.** Similarly, the S2 knob governs the send level to the second send effect in the mixer.
- **Note that there must be send effects connected to the AUX Sends and Returns in the mixer for this to work.**
- **Also note that if Redrum is soloed in the Mixer the effect sends will be muted.**
- **Another way to add independent effects to drum sounds is to use the independent drum outputs.** See "Connections".

Pan



Sets the Pan (stereo position) for the channel.

- **If the LED above the Pan control is lit, the sound uses a stereo sample.** In that case, the Pan control serves as a stereo balance control.

Level and Velocity



The Level knob sets the volume for the channel. However, the volume can also be affected by velocity (as set with the Dynamic value, or as played via MIDI). How much the volume should be affected by velocity is set with the "Vel" knob.

- **If the Vel knob is set to a positive value, the volume will become louder with increasing velocity values.** The higher the Vel value, the larger the difference in volume between low and high velocity values.
- **A negative value inverts this relationship, so that the volume decreases with higher velocity values.**
- **If the Vel knob is set to zero (middle position), the sound will play at a constant volume, regardless of the velocity.** When Vel is set to zero, the LED above the knob goes dark.

Length and the Decay/Gate switch



The Length knob determines the length of the drum sound, but the result depends on the setting of the Decay/Gate switch:

- **In Decay mode (switch down), the sound will decay (gradually fade out) after being triggered. The decay time is determined by the Length setting.** In this mode, it doesn't matter for how long a drum note is held (if played back from the main sequencer or via MIDI) - the sound will play the same length for short notes as for long notes. This is the traditional "drum machine" mode.

- ▶ **In Gate mode (switch up), the sound will play for the set Length, and then be cut off.**
  Furthermore, if a sound set to Gate mode is played from the main sequencer, from a CV/Gate device or via MIDI, the sound will be cut off when the note ends or after the set Length, depending on which comes first. Or in other words, the sound plays for as long as you hold the note, but the Length setting serves as the maximum length for the sound.
  There are several uses for the Gate mode:
- ▪ **For "gated" drum sounds, when the tail of the sound is abruptly cut off as an effect.**
- ▪ **For when you want to use very short sounds, and don't want them to "lose power" by being faded out.**
- ▪ **For when you play the Redrum from the sequencer or via MIDI, with sounds for which the length is important (e.g. when using the Redrum as a sound effects module).**
- ! **Audio samples sometimes contain a "loop", which is set by editing the audio in a sample editor. This loop repeats a part of the sample to produce sustain as long as you hold down a note. Drum samples usually don't contain loops, but who is to say that Redrum should only play drum samples?**
  Note that if a sample contains a loop, and Length is set to maximum, the sound will have infinite sustain, in other words it will never become silent, even if you stop playback. Decreasing the Length setting solves this problem.

Pitch



Sets the pitch of the sound. The range is +/- 1 octave.

- ▶ **When the pitch is set to any other value than 0, the LED above the knob lights up to indicate that the sample isn't played back at its original pitch.**

Pitch Bend



By setting the Bend knob to a positive or negative value, you specify the start pitch of the sound (relative to the Pitch setting). The pitch of the sound will then be bent to the main Pitch value. Thus, selecting a positive Bend value will cause the pitch to start higher and bend down to the original Pitch, and vice versa.

- ▶ **The Rate knob determines the bend time - the higher the value, the slower the bend.**
- ▶ **The Vel knob determines how the Bend amount should be affected by velocity.**
  With a positive Vel value, higher velocity results in wider pitch bends.
- ▶ **The Bend and Vel knobs have LEDs that light up when the functions are activated (i.e. when a value other than zero is selected).**
- ! **Pitch bend is available for drum sound channels 6 and 7 only.**

Tone



The Tone knob determines the brightness of the drum sound. Raising this parameter results in a brighter sound. The Vel knob determines whether the sound should become brighter (positive Vel value) or darker (negative Vel value) with higher velocity.

- ▶ **The Tone and Vel knobs have LEDs that light up when the functions are activated (i.e. when a value other than zero is selected).**
- ! **The Tone controls are available for drum sound channels 1, 2 and 10 only.**

Sample Start



The Start parameter allows you to adjust the start point of the sample. The higher the Start value, the further the start point is moved "into" the sample. If you set the Start Velocity knob to a positive amount, the sample start point is moved forward with higher velocities. A negative Start Velocity amount inverts this relationship.

- ▶ **When Start Velocity is set to any other value than zero, the LED above the knob lights up.**
- ▶ **A negative Start Velocity amount is only useful if you have set the Start parameter to a value higher than 0.** By raising the Start value a bit and setting Start Velocity to a negative value, you can create rather realistic velocity control over some drum sounds. This is because the very first transients in the drum sound will only be heard when you play hard notes.
- ! **The Sample Start settings are available for drum sound channels 3-5, 8 and 9.**

Global settings

Channel 8 & 9 Exclusive



If this button is activated, the sounds loaded into drum channels 8 and 9 will be exclusive. In other words, if a sound is played in channel 8 it will be silenced the moment a sound is triggered in channel 9, and vice versa.

The most obvious application for this feature is to "cut off" an open hi-hat with a closed hi-hat, just like a real one does.

High Quality Interpolation



When this is activated, the sample playback is calculated using a more advanced interpolation algorithm. This results in better audio quality, especially for drum samples with a lot of high frequency content.


- **High Quality Interpolation uses more computer power - if you don't need it, it's a good idea to turn it off!** Listen to the drum sounds in a context and determine whether you think this setting makes any difference.

Master Level

The Master Level knob in the top left corner of the device panel governs the overall volume from Redrum.

Using Redrum as a sound module


The drum sounds in Redrum can be played via MIDI notes. Each drum sound is triggered by a specific note number, starting at C1 (MIDI note number 36):



This allows you to play Redrum live from a MIDI keyboard or a MIDI percussion controller, or to record or draw drum notes in the main sequencer. If you like, you can combine pattern playback with additional drum notes, such as fills and variations. However:

! **If you want to use Redrum purely as a sound module (i.e. without pattern playback) you should make sure that the "Enable Pattern Section" button is deactivated (see "The Enable Pattern Section switch"), otherwise the Redrum pattern sequencer will start as soon as you start the main sequencer.**

Connections



On the back of the Redrum you will find the following connections:

For each drum sound channel:

Connection	Description
Audio Outputs	There are individual audio outputs for each drum sound channel, allowing you to route a drum sound to a separate channel in the mixer, possibly via insert effects, etc. For mono sounds, use the "Left (Mono)" output (and pan the sound using the Pan control in the mixer). When you use an individual output for a sound, the sound is automatically excluded from the master stereo output.
Gate Out	This sends out a gate signal when the drum sound is played (from a pattern, via MIDI or by using the Trigger button on the device panel). This lets you use the Redrum as a "trig sequencer", controlling other devices. The length of the gate signal depends on the Decay/Gate setting for the sound: In Decay mode, a short "trig pulse" is sent out, while in Gate mode, the gate signal will have the same length as the drum note.
Gate In	Allows you to trigger the sound from another CV/Gate device. All settings apply, just as when playing the drum sound conventionally.
Pitch CV In	Lets you control the pitch of the drum sound from another CV device.

Other

Connection	Description
Send Out 1-2	Outputs for the send signals controlled with the S1 and S2 knobs.
Stereo Out	This is the master stereo output, outputting a mix of all drum sounds (except those for which you use individual outputs).

Chapter 45
Rytmik Drum Machine


Introduction



The Rytmik Drum Machine device is an eight-channel drum sample player, designed for seamless integration of Reason Compact projects. Rytmik features a Distortion effect and a Low Cut + Hi Cut filter per drum channel. There are also two send effects - Reverb and Delay - that are shared among the eight drum channels, plus a master section with a Master Compressor, Master Pitch and a Master Filter.

Panel overview

The Rytmik front panel contains the following sections:




The Rytmik front panel sections.

- **1. Patch selector (for browsing, loading and saving patches).**
- **2. Sample playback and editing section (for the currently selected Drum Channel).**
- **3. Distortion and Low Cut + Hi Cut Filter (for the currently selected Drum Channel).**
- **4. Drum Channel sections (for playing back samples and for selecting Drum Channel to edit).**
- **5. Send Effects and Compressor section (global for all eight Drum Channels).**

Signal flow

The picture below shows the basic signal flow in Rytmik:



Rytmik signal flowchart.

- **Rytmik features eight Sample Playback engines (one per Drum Channel).**
  Each Sample Playback engine features a Sample section, where you can select any of the built-in samples. Here, you can also set the Sample Start, Sample End, Pan, Pitch, Fade In and Fade Out parameters.
- **The audio from the Sample Playback engines are then routed to a Distortion insert effect (one per Drum Channel).**
- **The signal is then routed to a Filter section (one per Drum Channel).**
  The signal can then be processed with a Low Cut and Hi Cut filter.
- **The signal from each Drum Channel can then be panned in stereo - and have its own individual volume.**
- **Each Drum Channel can also use the two global Send Effects (Reverb and Delay).**
  The signal levels to each of these send effects can be set individually for each Drum Channel.
- **Finally, the signals of all eight Drum Channels, plus the Send Effects are mixed and output as a stereo signal via a Master Compressor and a Master Filter.**
  It's also possible to output the desired Drum Channel signals individually via separate audio outputs - if you want to process the signals outside of the Rytmik device. If you do that, the signal will be output after the Filter section of the Drum Channel, bypassing the Send Effects and the Master FX.

Global controls

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

The Drum Channel sections



Auditioning samples

▶ **Click a Drum Channel button to play back the sample of the corresponding Drum Channel.**
By clicking the Drum Channel button you also automatically select the Drum Channel (see below).



- **If you are using a MIDI Keyboard/On-screen Piano Keys you can play back the samples of the Drum Channels from Key C0 to G0.**

Selecting a Drum Channel

▶ **Click a Drum Channel button to select the desired Drum Channel:**



Muting and soloing Drum Channels

▶ **Click the M(ute) or S(olo) button in a Drum Channel to mute or solo the desired Drum Channel:**



Setting the Drum Channel volumes

▶ **Drag the Volume slider up/down - or just click - to set the volume of a Drum Channel:**




Setting the Send Effect levels

- **Turn the Delay and Reverb knobs to set the send levels from the Drum Channel to the respective Send Effect:**
  See "The Master FX section" for more information about the Send Effects.



The Sample Playback section



The Sample Playback section contains all sample related controls and parameters for the currently selected Drum Channel. The currently selected Drum Channel is indicated by the lit Drum Channel selection button (see "Selecting a Drum Channel").

The Sample Playback section features the following parameters and controls:


Selecting Samples



- **Select and load a sample either by clicking the triangular arrow buttons on either side of the sample name - or by clicking the sample name and selecting from the pop-up menu.**
  The pop-up menu features eight sub-groups with different types of samples.


! **All samples in Rytmik are embedded in the device itself, so when you save a Rytmik patch the samples are always included (as opposed to other sampler devices in Reason).**

Setting the Sample Start and End



- **Click and drag the Sample Start handle sideways to change the where in the sample playback should begin.**
- **Click and drag the Sample End handle sideways to change the where in the sample playback should stop.**

Setting the Panning



- **Click and drag up/down in the Pan box to place the sample in the stereo panorama.**
  Range: 100L to 100R.

Setting the Pitch




- **Click and drag up/down in the Pitch box to set the pitch of the sample.**
  Range: +/- 1200 cents.

Setting Fade In and Fade Out




▶ **Click and drag up/down in the Fade In and/or Fade Out boxes to apply a fade in/out of the sample.**
Any fade in/out is shown graphically in the sample display.

The Insert Effects section



The Insert Effects section consists of a Distortion effect and a Low Cut and Hi Cut Filter.

Distortion




The Distortion effect is a transistor type of distortion.

▶ **Click and drag up/down in the Distortion box to adjust the input gain to the distortion effect.**
A high value will overdrive the pre-amp and generate more distortion.

Range: 0-100%, where “0” is completely dry/off.

Low Cut and Hi Cut Filter



The Filter features a Low Cut (Highpass) and a Hi Cut (Lowpass) filter. Perfect for removing any rumble (Lo Cut) and/or hiss (Hi Cut), for example.

- **Click and drag up/down in the Low Cut box to set the cutoff frequency for the highpass filter.**
  Alternatively click the left part of the filter curve in the display and drag sideways.


  Range: 20 Hz to 25 kHz.

- **Click and drag up/down in the Hi Cut box to set the cutoff frequency for the lowpass filter.**
  Alternatively click the right part of the filter curve in the display and drag sideways.

  Range: 20 Hz to 25 kHz.

! **Note that the Low Cut and Hi Cut cutoff frequencies can also be on opposite sides of each other, which means that the level of the sample could eventually drop to zero with extreme settings.**

The Master FX section




The Master FX section features controls for the Delay and Reverb send effects, as well as for the master bus Compressor. The Send Effects can be used by all Drum Channels simultaneously, and the effects are active simultaneously.

Delay




This is a delay with two different modes - Stereo and Ping Pong. The delay repeats are tempo synced and you can select the desired time division.

Mode



- **Click the Mode box and select the desired mode from the pop-up.**
  "Stereo" repeats the delay in stereo in a fixed centered position.
  "Ping Pong" repeats the delays, alternating between the left and right channels.


Time



- **Click and drag the Time box up/down to set the time division of the tempo-synced delay repeats.**
  The tempo is hard-wired to the main sequencer tempo.

  Time divisions: 1/1, 1/2D, 1/1T, 1/2, 1/4D, 1/2T, 1/4, 1/8D, 1/4T, 1/8, 1/16D, 1/8T and 1/16


Feedback



- **Click and drag the Feedback box up/down to set the number of delay repeats.**
  Alternatively, click and drag in the display to set the Feedback amount.


  Range: 0-100%, where "0" is one single delay repeat.

Reverb



This is a stereo reverb with six different Modes (reverb algorithms).

Mode




▶ **Click the Mode box and select the desired reverb algorithm from the pop-up.**

The following reverb types can be selected:

- **Room**
- **Large Room**
- **Culvert**
- **Plate**
- **Gated**
- **Hall**


Decay



▶ **Click and drag the Decay box up/down to set the length of the reverb effect.**
Alternatively, click and drag in the display to set the decay length.

The Decay amount is also shown graphically in the display.

Low Cut and Hi Cut




This is essentially a combination of a highpass and a lowpass filter.

- ▶ **Raise the Low Cut value to cut the low frequencies of the reverb signal and make the reverb effect less "muddy".**
  Range: 20 Hz to 25 kHz.
- ▶ **Lower the Hi Cut value to cut off the high frequencies of the reverb, thereby creating a smoother, warmer effect.**
  Range: 20 Hz to 25 kHz.

! **Note that the Low Cut and Hi Cut cutoff frequencies can also be on opposite sides of each other, which means that the reverb level could eventually drop to zero with extreme settings.**

Compressor



This is a stereo compressor, which acts on the total mix of all Drum Channels. It is always active, but if you don't want any compression effect you can set the controls so that no compression is produced. The gain reduction is shown by the meter.


Threshold



This is the threshold level above which the compression sets in. Signals with levels above the threshold will be affected, signals below it will not. In practice, this means that the lower the Threshold setting, the more the compression effect.

- ▶ **Click and drag the Threshold box up/down to set the threshold level.**
  Range: -60 dB to 0 dB
- ▶ **For no compression effect at all, set the Threshold to "0 dB".**

Ratio




This specifies the amount of gain reduction applied to the signal above the set threshold. A high Ratio value makes the sound less dynamic and more "even" in level.

- **Click and drag the Ratio box up/down to set the compression ratio.**
  Range: 1:1 to 20:1
- **For no compression effect at all, set the Ratio to "1.00".**

Attack


This governs how quickly the compressor applies the gain reduction when signals rise above the set Threshold (see above). If you raise the Attack value, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds.



- **Click and drag the Attack box up/down to set the compressor attack time.**
  Range: 0-200 ms

Release

When the signal level drops below the set Threshold (see above), this determines how long it takes before the compressor lets the sound through unaffected. Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics.



- **Click and drag the Release box up/down to set the compressor release time.**
  Range: 0-200 ms

Master Pitch



▶ **Turn the Master Pitch knob to adjust the pitches of all Drum Channels equally.**
Range: +/-1200 cents.

Master Reverb



▶ **Turn the Master Reverb knob to adjust the Reverb return level.**
Range: +/-100%.

! **Note that this control is bipolar, i.e. you could attenuate or amplify the reverb return level. This means that if any of the Reverb Amount knobs for the Drum Channels are < 0 dB, raising the Master Reverb knob to a positive value will increase the Reverb level for these Drum Channels. The level can never exceed 0 dB, though.**

Master Filter



The Master Filter is a combined highpass and lowpass filter, which can be used for cutting out low or high frequencies in the total mix signal. At the default 0% setting the output signal is completely unaffected (not filtered at all).


▶ **Turn the Master Filter knob to adjust the Low Cut and Hi Cut effect.**
Range: +/-100%.

Master Volume



- **Drag the Master Volume slider up/down - or just click - to set the output volume of the total mix.**
  Range: -inf to 6.00 dB

Connections



! **Remember that CV connections are NOT stored in the Rytmik patches! If you want to store CV connections between devices, put them in a Combinator device and save the Combi patch.**

Drum Gate In/Out

The Drum Gate inputs allow you to play Rytmik from another CV/Gate device. The Drum Gate inputs respond to "Note On/Off" along with Velocity.

The Drum Gate outputs allow you to control other CV/Gate equipped devices from Rytmik. The Drum Gate outputs send out "Note On/Off" along with Velocity.

Separate Outputs

The separate outputs can be used for routing individual Drum Channels to external destinations, for further processing.

! **Note that Drum Channels routed via separate outputs are automatically disconnected from the Master FX section. Note, though, that the signal could still be sent to (and heard via) the Send Effects (Delay and Reverb) on the Main Outputs.**

Main Output L & R

These are the main audio outputs. When you create a new Rytmik device, these outputs are auto-routed to the first available Mix Channel in the Reason main mixer. If there is no Mix Channel available, a new one will be automatically created.

Chapter 46
Subtractor Synthesizer



Introduction

Subtractor is an analog-type polyphonic synthesizer based on subtractive synthesis, the method used in analog synthesizers. This chapter will go through all parameters of each section of Subtractor. In addition to the parameter descriptions, the chapter also includes a few tips and tricks to help you get the most out of the Subtractor synthesizer.

! **It is recommended that you start with default settings (an "Init Patch") if you intend to follow the examples in this chapter, unless otherwise is stated. An Init Patch is created by selecting "Reset Device" from the device's context menu, or from the Edit menu. If you wish to keep the current settings, save them before initializing.**

The Subtractor has the following basic features:

- **Up to 99 Voice Polyphony.**
  You can set the number of voices for each Patch.
- **Dual Filters.**
  A combination of a multimode filter and a second, linkable, lowpass filter allows for complex filtering effects. See "The Filter Section".
- **Two Oscillators, each with 32 waveforms.**
  See "The Oscillator Section".
- **Frequency Modulation (FM).**
  See "Frequency Modulation (FM)".
- **Oscillator Phase Offset Modulation.**
  This is an unique Subtractor feature that generates waveform variations. See "Phase Offset Modulation".
- **Two Low Frequency Oscillators (LFO's)**
  See "LFO Section".
- **Three Envelope Generators.**
  See "Envelopes - General".
- **Extensive Velocity Control.**
  See "Velocity Control".
- **Extensive CV/Gate Modulation possibilities.**
  See "Connections".

Loading and Saving Patches

Loading and saving patches is done in the same way as with any other Reason device - see "Loading patches" and "Saving patches".

The Oscillator Section



Subtractor provides two oscillators. Oscillators are the main sound generators in Subtractor, the other features are used to shape the sound of the oscillators. Oscillators generate two basic properties, waveform and pitch (frequency). The type of waveform the oscillator produces determines the harmonic content of the sound, which in turn affects the resultant sound quality (timbre). Selecting a oscillator waveform is usually the starting point when creating a new Subtractor Patch from scratch.

Oscillator 1 Waveform



Oscillator 1 provides 32 waveforms. The first four are standard waveforms, and the rest are "special" waveforms, some of which are suitable for emulating various musical instrument sounds.

- **It is worth noting here that all waveforms can be radically transformed using Phase offset modulation (see "Phase Offset Modulation").**
- **To select a waveform, click the spin controls to the right of the "Waveform" LED display.**
  The first 4 basic waveforms are shown as standard symbols, and the special waveforms are numbered 5 - 32.

Here follows a brief description of the Subtractor waveforms:

! **Please note that the descriptions of the waveforms sound or timbre is merely meant to provide a basic guideline, and shouldn't be taken too literally. Given the myriad ways you can modulate and distort a waveform in Subtractor, you can produce extremely different results from any given waveform.**

Waveform	Description
Sawtooth 	This waveform contains all harmonics and produces a bright and rich sound. The Sawtooth is perhaps the most "general purpose" of all the available waveforms.
Square 	A square wave only contains odd number harmonics, which produces a distinct, hollow sound.
Triangle 	The Triangle waveform generates only a few harmonics, spaced at odd harmonic numbers. This produces a flute-like sound, with a slightly hollow character.
Sine 	The sine wave is the simplest possible waveform, with no harmonics (overtones). The sine wave produces a neutral, soft timbre.
5	This waveform emphasizes the higher harmonics, a bit like a sawtooth wave, only slightly less bright-sounding.
6	This waveform features a rich, complex harmonic structure, suitable for emulating the sound of an acoustic piano.
7	This waveform generates a glassy, smooth timbre. Good for electric piano-type sounds.
8	This waveform is suitable for keyboard-type sounds such as harpsichord or clavinet.
9	This waveform is suitable for electric bass-type sounds.
10	This is a good waveform for deep, sub-bass sounds.
11	This produces a waveform with strong formants, suitable for voice-like sounds.
12	This waveform produces a metallic timbre, suitable for a variety of sounds.
13	This produces a waveform suitable for organ-type sounds.
14	This waveform is also good for organ-type sounds. Has a brighter sound compared to waveform 13.
15	This waveform is suitable for bowed string sounds, like violin or cello.
16	Similar to 15, but with a slightly different character.
17	Another waveform suitable for string-type sounds.
18	This waveform is rich in harmonics and suitable for steel string guitar-type sounds.
19	This waveform is suitable for brass-type sounds.
20	This waveform is suitable for muted brass-type sounds.
21	This waveform is suitable for saxophone-like sounds.
22	A waveform suitable for brass and trumpet-type sounds.
23	This waveform is good for emulating mallet instruments such as marimba.
24	Similar to 23, but with a slightly different character.
25	This waveform is suitable for guitar-type sounds.
26	This is a good waveform for plucked string sounds, like harp.
27	Another waveform suitable for mallet-type sounds (see 23-24), but has a brighter quality, good for vibraphone-type sounds.
28	Similar to 27, but with a slightly different character.

Waveform	Description
29	This waveform has complex, enharmonic overtones, suitable for metallic bell-type sounds.
30	Similar to 29, but with a slightly different character. By using FM and setting the Osc Mix to Osc 1, this and the following two waveforms can produce noise.
31	Similar to 30, but with a slightly different character.
32	Similar to 30, but with a slightly different character.

Setting Oscillator 1 Frequency - Octave/Semitone/Cent



By clicking the corresponding up/down buttons you can tune, i.e. change the frequency of Oscillator 1 in three ways:

- **In Octave steps**
  The range is 0 - 9. The default setting is 4 (where "A" above middle "C" on your keyboard generates 440 Hz).
- **In Semitone steps**
  Allows you to raise the frequency in 12 semitone steps (1 octave).
- **In Cent steps (100th of a semitone)**
  The range is -50 to 50 (down or up half a semitone).

Oscillator Keyboard Tracking



Oscillator 1 has a button named "Kbd. Track". If this is switched off, the oscillator pitch will remain constant, regardless of any incoming note pitch messages, although the oscillator still reacts to note on/off messages. This can be useful for certain applications:

- **When Frequency Modulation (FM - see "Frequency Modulation (FM)") or Ring Modulation (see "Ring Modulation") is used.**
  This produces enharmonic sounds with very varying timbre across the keyboard.
- **For special effects and non-pitched sounds (like drums or percussion) that should sound the same across the keyboard.**

Using Oscillator 2



You activate Osc 2 by clicking the button next to the text "Osc 2". Setting oscillator frequency and keyboard tracking is identical to Oscillator 1.

Adding a second oscillator enables many new modulation possibilities which can produce richer timbres. A basic example is to slightly detune (+/– a few cents) one of the oscillators. This slight frequency offset causes the oscillators to "beat" against each other, producing a wider and richer sound. Also, by combining two different waveforms, and adding frequency or ring modulation, many new timbres can be created.

Oscillator Mix



The Osc Mix knob determines the output balance between Osc 1 and Osc 2. To be able to clearly hear both oscillators, the "Osc Mix" knob should be set somewhere around the center position. If you turn the Mix knob fully to the left, only Osc 1 will be heard, and vice versa. [Command]/[Ctrl]-clicking the knob sets the Mix parameter to center position.

Oscillator 2 Waveform

The waveform alternatives for Oscillator 2 are identical to those of Oscillator 1.

However, the Noise Generator provides a third sound generating source (in addition to the two oscillators) in Subtractor, and could be regarded as an "extra" waveform for Oscillator 2, as it is internally routed to the Oscillator 2 output. See below for a description of the Noise Generator.

Noise Generator



The Noise Generator could be viewed as an oscillator that produces noise instead of a pitched waveform. Noise can be used to produce a variety of sounds, the classic example being "wind" or "rolling wave" sounds, where noise is passed through a filter while modulating the filter frequency. Other common applications include non-pitched sounds like drums and percussion, or simulating breath noises for wind instruments. To use the Noise Generator, select an Init Patch and proceed as follows:

1. **Turn Osc 2 off.**
2. **Click the button (in the Noise Generator section) to activate the Noise Generator.**
   If you play a few notes on your MIDI instrument you should now hear Osc1 mixed with the sound of the Noise Generator.
3. **Turn the Mix knob fully to the right, and play a few more notes.**
   Now just the Noise Generator will be heard.

▶ **Thus, the output of the Noise Generator is internally routed to Osc 2.**
If you switch Osc 2 on, the noise will be mixed with the Osc 2 waveform.

There are three Noise Generator parameters. These are as follows:

Parameter	Description
Noise Decay	This controls how long it takes for the noise to fade out when you play a note. Note that this is independent from the Amp Envelope Decay parameter, allowing you to mix a short "burst" of noise at the very beginning of a sound, i.e. a pitched sound that uses oscillators together with noise.
Noise Color	This parameter allows you to vary the character of the noise. If the knob is turned fully clockwise, pure or "white" noise (where all frequencies are represented with equal energy) is generated. Turning the knob anti-clockwise produces a gradually less bright sounding noise. Fully anti-clockwise the noise produced is an earthquake-like low frequency rumble.
Level	Controls the level of the Noise Generator.

Phase Offset Modulation

A unique feature of the Subtractor oscillators is the ability to create an extra waveform within one oscillator, to offset the *phase* of that extra waveform, and to modulate this phase offset. By subtracting or multiplying a waveform with a phase offset copy of itself, very complex waveforms can be created. Sounds complicated? Well, the theory behind it might be, but from a user perspective it is just a method of generating new waveforms from existing waveforms.

A seasoned synth programmer using Subtractor for the first time may wonder why the Subtractor oscillators (seemingly) cannot provide the commonly used pulse waveform and the associated pulse width modulation (PWM). Or oscillator sync, another common feature in analog synthesizers. The simple answer is that Subtractor can easily create pulse waveforms (with PWM) and oscillator sync-sounds, and a lot more besides, partly by the use of phase offset modulation.




Each oscillator has it's own Phase knob and a selector button. The Phase knob is used to set the amount of phase offset, and the selector switches between three modes:


- **Waveform multiplication (x)**
- **Waveform subtraction (–)**
- **No phase offset modulation (o).**

When phase offset modulation is activated, the oscillator creates a *second* waveform of the same shape and offsets it by the amount set with the Phase knob. Depending on the selected mode, Subtractor then either subtracts or multiplies the two waveforms with each other. The resulting waveforms can be seen in the illustration below.


1. The two offset waveforms:



2. The result of subtraction:



3. The result of multiplication:



- **In example 1, we see two sawtooth waves with a slight offset.**
- **Example 2 shows that subtracting one slightly offset sawtooth wave from the other, produces a pulse wave. If you modulate the Phase offset parameter (with for example an LFO), the result will be pulse width modulation (PWM).**
- **Example 3 shows the resulting waveform when multiplying the offset waves with each other. As you can see (and hear if you try it), multiplying waveforms can produce very dramatic and sometimes unexpected results.**

Using phase offset modulation can create very rich and varied timbres, especially when used along with LFO or Envelopes to modulate the phase offset.

▶ **To get a "feel" for this concept, you could study Patches that use phase offset modulation, and maybe tweak some of the Phase Offset parameters to find out what happens. Try "SyncedUp" in the Polysynth category in the Factory Soundbank for an example of osc sync or "Sweeping Strings" (in the Pads category) for an example of PWM.**

! **Note that if you activate waveform subtraction with a Phase offset set to "0" for an oscillator, the second waveform will cancel out the original waveform completely, and the oscillator output will be silent. If you set the Phase Offset knob to any other value than zero, the sound returns.**

Frequency Modulation (FM)



In synthesizer-speak, Frequency Modulation, or FM, is when the frequency of one oscillator (called the "carrier") is modulated by the frequency of another oscillator (called the "modulator"). Using FM can produce a wide range of harmonic and non harmonic sounds. In Subtractor, Osc 1 is the carrier and Osc 2 the modulator. To try out some of the effects FM can produce, proceed as follows:

1. **Select an Init Patch by selecting "Initialize Patch" from the Edit menu.**
2. **Activate Osc 2.**
   As you need both a carrier and a modulator to produce FM, turning the FM knob will not produce any effect unless you first activate Osc 2. For classic FM sounds, use sine wave on oscillator 1 and triangle wave on oscillator 2.
3. **Use the FM knob to set the FM amount to a value of about 50.**
   As you can hear, the timbre changes, but the effect isn't very pronounced yet.
4. **Turn the Osc Mix knob fully to the left, so that only the sound of Osc 1 is heard.**
   The modulator (Osc 2) still affects Osc 1, even though the Osc 2 output is muted.
5. **Now, hold down a note on your MIDI keyboard and tune Osc 2 a fifth up from the original pitch by setting the Osc 2 frequency "Semi" parameter to a value of 7.**
   As you can hear, for each semitone step you vary the Osc 2 frequency, the timbre changes dramatically. Setting Osc 2 frequency to certain musical intervals (i.e. fourth, fifth or octave semitone steps) produces harmonic, rich timbres, almost like tube distortion. Setting Osc 2 to non-musical intervals usually results in complex, enharmonic timbres.

▶ **Experiment with different oscillator parameters such as phase offset modulation, changing the waveforms etc. and listen to how they affect the sound of frequency modulation.**

Using the Noise Generator as the Modulator source

As explained earlier, the Noise Generator is internally routed to the Osc 2 output. Hence, if you deactivate Osc 2, and activate the Noise Generator while using FM, the noise will be used to frequency modulate Osc 1.

▶ **With the Noise Generators default settings, this will sound much like colored noise. But by changing (lowering) the Noise Generator Decay parameter, so that the noise modulates only the attack portion of the sound can produce more interesting results. You could also use a combination of noise and Osc 2.**


Ring Modulation



Ring Modulators basically multiply two audio signals together. The ring modulated output contains added frequencies generated by the sum of, and the difference between, the frequencies of the two signals. In the Subtractor Ring Modulator, Osc 1 is multiplied with Osc 2 to produce sum and difference frequencies. Ring modulation can be used to create complex and enharmonic, bell-like sounds.

1. **Select an Init Patch by selecting "Initialize Patch" from the Edit menu.**
   Save any current settings you wish to keep before initializing.
2. **Activate Ring Modulation with the button in the lower right corner of the oscillator section.**
3. **Activate Osc 2.**
   You need to activate Osc 2 before any ring modulation can happen.
4. **Turn the Osc Mix knob fully to the right, so that only the sound of Osc 2 is heard.**
   Osc 2 provides the ring modulated output.
5. **If you play a few notes while varying the frequency of either oscillator, by using the Semitone spin controls, you can hear that the timbre changes dramatically.**
   If the oscillators are tuned to the same frequency, and no modulation is applied to either the Osc 1 or 2 frequency, the Ring Modulator won't do much. It is when the frequencies of Osc 1 and Osc 2 differ, that you get the "true" sound of ring modulation.

The Filter Section




In subtractive synthesis, a filter is the most important tool for shaping the overall timbre of the sound. The filter section in Subtractor contains two filters, the first being a multimode filter with five filter types, and the second being a low-pass filter. The combination of a multimode filter and a lowpass filter can be used to create very complex filter effects.

Filter 1 Type


With this multi-selector you can set Filter 1 to operate as one of five different types of filter. The five types are illustrated and explained on the following pages:

- **24 dB Lowpass (LP 24)**
  Lowpass filters lets low frequencies pass and cuts out the high frequencies. This filter type has a fairly steep roll-off curve (24dB/Octave). Many classic synthesizers (Minimoog/Prophet 5 etc.) use this filter type.




The darker curve illustrates the roll-off curve of the 24dB Lowpass Filter. The lighter curve in the middle represents the filter characteristic when the Resonance parameter is raised.

- **12 dB Lowpass (LP 12)**
  This type of lowpass filter is also widely used in analog synthesizers (Oberheim, early Korg synths etc.). It has a gentler slope (12 dB/Octave), leaving more of the harmonics in the filtered sound compared to the LP 24 filter.




The darker curve illustrates the roll-off curve of the 12dB Lowpass Filter. The lighter curve in the middle represents the filter characteristic when the Resonance parameter is raised.

- **Bandpass (BP 12)**
  A bandpass filter cuts both high and low frequencies, while midrange frequencies are not affected. Each slope in this filter type has a 12 dB/Octave roll-off.




The darker curve illustrates the roll-off curve of the Bandpass Filter. The lighter curve in the middle represents the filter characteristic when the Resonance parameter is raised.

- **Highpass (HP12)**
  A highpass filter is the opposite of a lowpass filter, cutting out lower frequencies and letting high frequencies pass. The HP filter slope has a 12 dB/Octave roll-off.



The darker curve illustrates the roll-off curve of the Highpass Filter. The lighter curve in the middle represents the filter characteristic when the Resonance parameter is raised.

- **Notch**
  A notch filter (or band reject filter) could be described as the opposite of a bandpass filter. It cuts off frequencies in a narrow midrange band, letting the frequencies below and above through. On its own, a notch filter doesn't really alter the timbre in any dramatic way, simply because most frequencies are let through. However, by combining a notch filter with a lowpass filter (using Filter 2 - see "Filter 2"), more musically useful filter characteristics can be created. Such a filter combination can produce soft timbres that still sound "clear". The effect is especially noticeable with low resonance (see "Resonance") settings.



The darker curve illustrates the roll-off curve of the Notch Filter. The lighter curve in the middle represents the filter characteristic when the Resonance parameter is raised.

Filter 1 Frequency

The Filter Frequency parameter (often referred to as "cutoff") determines which area of the frequency spectrum the filter will operate in. For a lowpass filter, the frequency parameter could be described as governing the "opening" and "closing" of the filter. If the Filter Freq is set to zero, none or only the very lowest frequencies are heard, if set to maximum, all frequencies in the waveform are heard. Gradually changing the Filter Frequency produces the classic synthesizer filter "sweep" sound.

! **Note that the Filter Frequency parameter is usually controlled by the Filter Envelope (see "Filter Envelope") as well. Changing the Filter Frequency with the Freq slider may therefore not produce the expected result.**

Resonance

The filter resonance parameter is used to set the Filter characteristic, or quality. For lowpass filters, raising the filter Res value will emphasize the frequencies around the set filter frequency. This produces a generally thinner sound, but with a sharper, more pronounced filter frequency "sweep". The higher the filter Res value, the more resonant the sound becomes until it produces a whistling or ringing sound. If you set a high value for the Res parameter and then vary the filter frequency, this will produce a very distinct sweep, with the ringing sound being very evident at certain frequencies.

- **For the highpass filter, the Res parameter operates just like for the lowpass filters.**
- **When you use the Bandpass or Notch filter, the Resonance setting adjusts the width of the band. When you raise the Resonance, the band where frequencies are let through (Bandpass), or cut (Notch) will become narrower. Generally, the Notch filter produces more musical results using low resonance settings.**

Filter Keyboard Track (Kbd)

If Filter Keyboard Track is activated, the filter frequency will increase the further up on the keyboard you play. If a lowpass filter frequency is constant (a Kbd setting of "0") this can introduce a certain loss of "sparkle" in a sound the higher up the keyboard you play, because the harmonics in the sound are progressively being cut. By using a degree of Filter Keyboard Tracking, this can be compensated for.

Filter 2

A very useful and unusual feature of the Subtractor Synthesizer is the presence of an additional 12dB/Oct lowpass filter. Using two filters together can produce many interesting filter characteristics, that would be impossible to create using a single filter, for example formant effects.


The parameters are identical to Filter 1, except in that the filter type is fixed, and it does not have filter keyboard tracking.

- **To activate Filter 2, click the button at the top of the Filter 2 section.**
  Filter 1 and Filter 2 are connected in series. This means that the output of Filter 1 is routed to Filter 2, but both filters function independently. For example, if Filter 1 was filtering out most of the frequencies, this would leave Filter 2 very little to "work with". Similarly, if Filter 2 had a filter frequency setting of "0", all frequencies would be filtered out regardless of the settings of Filter 1.



- **Try the "Singing Synth" patch (in the Monosynth category of the Factory Sound Bank) for an example of how dual filters can be used.**

Filter Link



When Link (and Filter 2) is activated, the Filter 1 frequency controls the frequency offset of Filter 2. That is, if you have set different filter frequency values for Filter 1 and 2, changing the Filter 1 frequency will also change the frequency for Filter 2, but keeping the relative offset.

- **Try the "Fozzy Fonk" patch (in the Polysynth category of the Factory Sound Bank) for an example how linked filters can be used.**


! **Caution! If no filter modulation is used, and the filters are linked, pulling down the frequency of Filter 2 to zero will cause both filters to be set to the same frequency. If combined with high Res settings, this can produce *very* loud volume levels that cause distortion!**

Envelopes - General

Envelope generators are used to control several important sound parameters in analog synthesizers, such as pitch, volume, filter frequency etc. Envelopes govern how these parameters should respond over time - from the moment a note is struck to the moment it is released.

Standard synthesizer envelope generators have four parameters; Attack, Decay, Sustain and Release (ADSR).

There are three envelope generators in the Subtractor, one for volume, one for the Filter 1 frequency, and one modulation envelope which has selectable modulation destinations.



The ADSR envelope parameters.

Attack

When you play a note on your keyboard, the envelope is triggered. This means it starts rising from zero to the maximum value. How long this should take, depends on the Attack setting. If the Attack is set to "0", the maximum value is reached instantly. If this value is raised, it will take time before the maximum value is reached.

For example, if the Attack value is raised and the envelope is controlling the filter frequency, the filter frequency will gradually rise up to a point each time a key is pressed, like an "auto-wha" effect.

Decay

After the maximum value has been reached, the value starts to drop. How long this should take is governed by the Decay parameter.

If you wanted to emulate the volume envelope of a note played on a piano for example, the Attack should be set to "0" and the Decay parameter should be set to a medium value, so that the volume gradually decreases down to silence, even if you keep holding the key down. Should you want the decay to drop to some other value than zero, you use the Sustain parameter.

Sustain

The Sustain parameter determines the level the envelope should rest at, after the Decay. If you set Sustain to full level, the Decay setting is of no importance since the volume of the sound is never lowered.


If you wanted to emulate the volume envelope of an organ, you theoretically only really need to use the Sustain parameter set to full level, as a basic organ volume envelope instantly goes to the maximum level (Attack "0") and stays there (Decay "0"), until the key is released and the sound instantly stops (Release "0").

But often a combination of Decay and Sustain is used to generate envelopes that rise up to the maximum value, then gradually decreases to finally land to rest on a level somewhere in-between zero and maximum. Note that Sustain represents a *level*, whereas the other envelope parameters represent times.

Release


Finally, we have the Release parameter. This works just like the Decay parameter, except it determines the time it takes for the value to fall back to zero *after* releasing the key.

Amplitude Envelope



The Amplitude Envelope is used to adjust how the volume of the sound should change from the time you press a key until the key is released. By setting up a volume envelope you sculpt the sound's basic shape with the four Amplitude Envelope parameters, Attack, Decay, Sustain and Release. This determines the basic character of the sound (soft, long, short etc.).

Filter Envelope



The Filter Envelope affects the Filter 1 Frequency parameter. By setting up a filter envelope you control the how the filter frequency should change over time with the four Filter Envelope parameters, Attack, Decay, Sustain and Release.

Filter Envelope Amount


This parameter determines to what degree the filter will be affected by the Filter Envelope. Raising this knob's value creates more drastic results. The Envelope Amount parameter and the set Filter Frequency are related. If the Filter Freq slider is set to around the middle, this means that the moment you press a key the filter is already halfway open. The set Filter Envelope will then open the filter further from this point. The Filter Envelope Amount setting affects how much further the filter will open.

Filter Envelope Invert



If this button is activated, the envelope will be inverted. For example, normally the Decay parameter lowers the filter frequency, but after activating Invert it will instead raise it, by the same amount.

Mod Envelope



The Mod Envelope allows you to select one of a number of parameters, or Destinations, to control with the envelope. By setting up a modulation envelope you control the how the selected Destination parameter should change over time with the four Mod Envelope parameters, Attack, Decay, Sustain and Release.

The available Mod Envelope Destinations are as follows:

Destination	Description
Osc 1	Selecting this makes the Mod Envelope control the pitch (frequency) of Osc 1.
Osc 2	Same as above, but for Osc 2.
Osc Mix	Selecting this makes the Mod Envelope control the oscillator Mix parameter. Both oscillators must be activated for this to have any effect.
FM	Selecting this makes the Mod Envelope control the FM Amount parameter. Both oscillators must be activated for this to have any effect.
Phase	Selecting this makes the Mod Envelope control the Phase Offset parameter for both Osc 1 and 2. Note that Phase Offset Modulation (Subtraction or Multiplication) must be activated for this to have any effect.
Freq 2	Selecting this makes the Mod Envelope control the Frequency parameter for Filter 2.

LFO Section



LFO stands for Low Frequency Oscillator. LFO's are oscillators, just like Osc 1 & 2, in that they also generate a waveform and a frequency. However, there are two significant differences:

- **LFOs only generate waveforms with low frequencies.**
- **The output of the two LFO's are never actually heard. Instead they are used for modulating various parameters.**

The most typical application of an LFO is to modulate the pitch of a (sound generating) oscillator, to produce vibrato. Subtractor is equipped with two LFO's. The parameters and the possible modulation destinations vary somewhat between LFO 1 and LFO 2.

LFO 1 Parameters

Waveform

LFO 1 allows you to select different waveforms for modulating parameters. These are (from top to bottom):

Waveform	Description
Triangle	This is a smooth waveform, suitable for normal vibrato.
Inverted Sawtooth	This produces a "ramp up" cycle. If applied to an oscillator's frequency, the pitch would sweep up to a set point (governed by the Amount setting), after which the cycle immediately starts over.
Sawtooth	This produces a "ramp down" cycle, the same as above but inverted.
Square	This produces cycles that abruptly changes between two values, usable for trills etc.
Random	Produces random stepped modulation to the destination. On some vintage synths, this is called "sample & hold".
Soft Random	The same as above, but with smooth modulation.

Destination

The available LFO 1 Destinations are as follows:

Destination	Description
Osc 1&2	Selecting this makes LFO 1 control the pitch (frequency) of Osc 1 and Osc 2.
Osc 2	Same as above, but for Osc 2.
Filter Freq	Selecting this makes the LFO 1 control the filter frequency for Filter 1 (and Filter 2 if linked).
FM	Selecting this makes the LFO 1 control the FM Amount parameter. Both oscillators must be activated for this to have any effect.
Phase	Selecting this makes the LFO 1 control the Phase Offset parameter for both Osc 1 and 2. Note that Phase Offset Modulation (Subtraction or Multiplication) must be activated for this to have any effect.
Osc Mix	Selecting this makes the LFO 1 control the oscillator Mix parameter.

Sync

By clicking this button you activate/deactivate LFO sync. The frequency of the LFO will then be synchronized to the song tempo, in one of 16 possible time divisions. When sync is activated, the Rate knob (see below) is used for setting the desired time division.

Turn the knob and check the tooltip for an indication of the time division.



Rate

The Rate knob controls the LFO's frequency. Turn clockwise for a faster modulation rate.

Amount

This parameter determines to what degree the selected parameter destination will be affected by LFO 1. Raising this knob's value creates more drastic results.

LFO 2 Parameters

LFO 2 is polyphonic. This means that for every note you play, an *independent* LFO cycle is generated, whereas LFO 1 always modulates the destination parameter using the same "cycle". This can be used to produce subtle cross-modulation effects, with several LFO cycles that "beat" against each other. This also enables LFO 2 to produce modulation rates that vary across the keyboard (see the "Keyboard Tracking" parameter below).

Destination

The available LFO 2 Destinations are as follows:

Destination	Description
Osc 1&2	Selecting this makes LFO 2 modulate the pitch (frequency) of Osc 1 and Osc 2.
Phase	Selecting this makes the LFO 2 modulate the Phase Offset parameter for both Osc 1 and 2. Note that Phase Offset Modulation (Subtraction or Multiplication) must be activated for this to have any effect.
Filter Freq 2	Selecting this makes the LFO 2 modulate the filter frequency for Filter 2.
Amp	Selecting this makes the LFO 2 modulate the overall volume., to create tremolo-effects.

LFO 2 Delay

This parameter is used to set a delay between when a note is played and when the LFO modulation "kicks in". For example, if Osc 1 & 2 is selected as the destination parameter and Delay was set to a moderate value, the sound would start out unmodulated, with the vibrato only setting in if you hold the note(s) long enough. Delayed LFO modulation can be very useful, especially if you are playing musical instrument-like sounds like violin or flute. Naturally it could also be used to control more extreme modulation effects and still retain the "playability" of the sound.

LFO 2 Keyboard Tracking

If LFO keyboard tracking is activated, the LFO rate will progressively increase the higher up on the keyboard you play. Raising this value creates more drastic results.

▶ **If the LFO is set to modulate the phase offset, LFO keyboard tracking can produce good results. For example, synth string pads and other sounds that use PWM (see "Phase Offset Modulation") can benefit from this.**

Rate

The Rate knob controls the LFO's frequency. Turn clockwise for a faster modulation rate.

Amount

This parameter determines to what degree the selected parameter destination will be affected by LFO 2. Raising this knob's value creates more drastic results.

Play Parameters

This section deals with two things: Parameters that are affected by how you play, and modulation that can be applied manually with standard MIDI keyboard controls.

These are:

- **Velocity Control**
- **Pitch Bend and Modulation Wheel**
- **Legato**
- **Portamento**
- **Polyphony**

Velocity Control



Velocity is used to control various parameters according to how hard or soft you play notes on your keyboard. A common application of velocity is to make sounds brighter and louder if you strike the key harder. Subtractor features very comprehensive velocity modulation capabilities. By using the knobs in this section, you can control how much the various parameters will be affected by velocity. The velocity sensitivity amount can be set to either positive or negative values, with the center position representing no velocity control.

The following parameters can be velocity controlled:

Destination	Description
Amp	This let's you velocity control the overall volume of the sound. If a positive value is set, the volume will increase the harder you strike a key. A negative value inverts this relationship, so that the volume decreases if you play harder, and increases if you play softer. If set to zero, the sound will play at a constant volume, regardless of how hard or soft you play.
FM	This sets velocity control for the FM Amount parameter. A positive value will increase the FM amount the harder you play. Negative values invert this relationship.
M. Env	This sets velocity control for the Mod Envelope Amount parameter. A positive value will increase the envelope amount the harder you play. Negative values invert this relationship.
Phase	This sets velocity control for the Phase Offset parameter. This applies to both Osc 1 & 2, but the relative offset values are retained. A positive value will increase the phase offset the harder you play. Negative values invert this relationship.
Freq 2	This sets velocity control for the Filter 2 Frequency parameter. A positive value will increase the filter frequency the harder you play. Negative values invert this relationship.
F. Env	This sets velocity control for the Filter Envelope Amount parameter. A positive value will increase the envelope amount the harder you play. Negative values invert this relationship.
F. Dec	This sets velocity control for the Filter Envelope Decay parameter. A positive value will increase the Decay time the harder you play. Negative values invert this relationship.
Osc Mix	This sets velocity control for the Osc Mix parameter. A positive value will increase the Osc 2 Mix amount the harder you play. Negative values invert this relationship.
A. Attack	This sets velocity control for the Amp Envelope Attack parameter. A positive value will increase the Attack time the harder you play. Negative values invert this relationship.

Pitch Bend and Modulation Wheels



The Pitch Bend wheel is used for "bending" notes, like bending the strings on a guitar. The Modulation wheel can be used to apply various modulation while you are playing. Virtually all MIDI keyboards have Pitch Bend and Modulation controls. Subtractor features not only the settings for how incoming MIDI Pitch Bend and Modulation wheel messages should affect the sound. Subtractor also has two functional wheels that could be used to apply real time modulation and pitch bend should you not have these controllers on your keyboard, or if you aren't using a keyboard at all. The Subtractor wheels mirror the movements of the MIDI keyboard controllers.

Pitch Bend Range

The Range parameter sets the amount of pitch bend when the wheel is turned fully up or down. The maximum range is "24" (=up/down 2 Octaves).

Modulation Wheel

The Modulation wheel can be set to simultaneously control a number of parameters. You can set positive or negative values, just like in the Velocity Control section. The following parameters can be affected by the modulation wheel:

Parameter	Description
F. Freq	This sets modulation wheel control of the Filter 1 Frequency parameter. A positive value will increase the frequency if the wheel is pushed forward. Negative values invert this relationship.
F. Res	This sets modulation wheel control of the Filter 1 Resonance parameter. A positive value will increase the resonance if the wheel is pushed forward. Negative values invert this relationship.
LFO 1	This sets modulation wheel control of the LFO 1 Amount parameter. A positive value will increase the Amount if the wheel is pushed forward. Negative values invert this relationship.
Phase	This sets modulation wheel control of the Phase Offset parameter for both Osc 1 and 2. Note that Phase Offset Modulation (Subtraction or Multiplication) must be activated for this to have any effect.
FM	This sets modulation wheel control of the FM Amount parameter. A positive value will increase the FM amount if the wheel is pushed forward. Negative values invert this relationship. Both oscillators must be activated for this to have any effect.

Legato

Legato works best with monophonic sounds. Set Polyphony (see below) to 1 and try the following:

- **Hold down a key and press another key without releasing the previous.**
  Notice that the pitch changes, but the envelopes do not start over. That is, there will be no new "attack".
- **If polyphony is set to more voices than 1, Legato will only be applied when all the assigned voices are "used up".**
  For example, if you had a polyphony setting of "4" and you held down a 4 note chord, the next note you played would be Legato. Note, however, that this Legato voice will "steal" one of the voices in the 4 note chord, since all the assigned voices were already used up!

Retrig

This is the "normal" setting for playing polyphonic patches. That is, when you press a key without releasing the previous, the envelopes are retriggered, like when you release all keys and then press a new one. In monophonic mode, Retrig has an additional function; if you press a key, hold it, press a new key and then release that, the first note is also retriggered.

Portamento (Time)

Portamento is when the pitch "glides" between the notes you play, instead of instantly changing the pitch. The Portamento knob is used to set how long it takes for the pitch to glide from one pitch to the next. If you don't want any Portamento at all, set this knob to zero.

Setting Number of Voices - Polyphony



This determines the polyphony, i.e. the number of voices a Subtractor Patch can play simultaneously. This can be used to make a patch monophonic (=a setting of "1"), or to extend the number of voices available for a patch. The maximum number of voices you can set a Subtractor Patch to use is 99. In the (unlikely) event you should need more voices, you can always create another Subtractor!

! **Note that the Polyphony setting does not "hog" voices. For example, if you have a patch that has a polyphony setting of ten voices, but the part the patch plays only uses four voices, this won't mean that you are "wasting" six voices. In other words, the polyphony setting is not something you need to consider much if you want to conserve CPU power - it is the number of voices actually used that counts.**

About the Low Bandwidth button

This can be used to conserve CPU power. When activated, this function will remove some high frequency content from the sound of this particular device, but often this is not noticeable (this is especially true for bass sounds).

External Modulation



Subtractor can receive common MIDI controller messages, and route these to various parameters. The following MIDI messages can be received:

- **Aftertouch (Channel Pressure)**
- **Expression Pedal**
- **Breath Control**


If your MIDI keyboard is capable of sending Aftertouch messages, or if you have access to an Expression Pedal or a Breath controller, you can use these to modulate parameters. The "Ext. Mod" selector switch sets which of these message-types should be received.

These messages can then be assigned to control the following parameters:

Destination	Description
F. Freq	This sets External modulation control of the Filter 1 Frequency parameter. A positive value will increase the frequency with higher external modulation values. Negative values invert this relationship.
LFO 1	This sets External modulation control of the LFO 1 Amount parameter. A positive value will increase the LFO 1 amount with higher external modulation values. Negative values invert this relationship.

Destination	Description
Amp	This let's you control the overall volume of the sound with external modulation. If a positive value is set, the volume will increase with higher external modulation values. A negative value inverts this relationship.
FM	This sets External modulation control of the FM Amount parameter. If a positive value is set, the FM amount will increase with higher external modulation values. A negative value inverts this relationship. Both oscillators must be activated for this to have any effect.

Connections



Flipping the Subtractor around reveals a plethora of connection possibilities, most of which are CV/Gate related. Using CV/Gate is described in the chapter "Routing Audio and CV".

Audio Output

This is Subtractor's main audio output. When you create a new Subtractor device, this is auto-routed to the first available channel on the audio mixer.

Sequencer Control

The Sequencer Control CV and Gate inputs allow you to play the Subtractor from another CV/Gate device (typically a Matrix or a Redrum). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

! For best results, you should use the Sequencer Control inputs with monophonic sounds.

Modulation Inputs

! **Remember that CV connections will not be stored in the Subtractor patch, even if the connections are to/from the same Subtractor device!**

These control voltage (CV) inputs (with associated voltage trim pots), can modulate various Subtractor parameters from other devices, or from the modulation outputs of the same Subtractor device. These inputs can control the following parameters:

- **Oscillator Pitch (both Osc 1 & 2).**
- **Oscillator Phase Offset (both Osc 1 & 2).**
- **FM Amount**
- **Filter 1 Cutoff**
- **Filter 1 Res**
- **Filter 2 Cutoff**
- **Amp Level**
- **Mod Wheel**

Modulation Outputs

The Modulation outputs can be used to voltage control other devices, or other parameters in the same Subtractor device. The Modulation Outputs are:

- **Mod Envelope**
- **Filter Envelope**
- **LFO 1**

Gate Inputs

These inputs can receive a CV signal to trigger the following envelopes. Note that connecting to these inputs will override the normal triggering of the envelopes. For example, if you connected an LFO output to the Gate Amp input, you would not trigger the amp envelope by playing notes, as this is now controlled by the LFO. In addition you would only hear the LFO triggering the envelope for the notes that you hold down. The following Gate Inputs can be selected:

- **Amp Envelope**
- **Filter Envelope**
- **Mod Envelope**

Chapter 47
Thor Polysonic Synthesizer

Introduction



Thor is an advanced synthesizer with many unique features.

The design could be described as semi-modular, in that the oscillator and filter sections are open slots that allow the user to select between various different oscillator and filter types, each with a distinct character. Some of these designs were inspired by selected vintage equipment.

As a result, Thor is capable of producing an astounding array of sounds.

While it offers a lot of scope for serious sound modeling, it still has a basically simple and user-friendly interface.

In the extensive Modulation bus routing section both audio and control signals (CV) co-exist, and more or less any routing combination can be assigned. Use audio to modulate a CV signal or vice versa - Thor's modulation capabilities are virtually limitless.

Thor also features an advanced step sequencer which can be used for creating melody lines or purely as a modulation source.

There are also audio inputs on the back panel. By connecting the output of another device to these inputs, you can use Thor's filters, envelopes etc. to process the sound, or you can use the external audio source to modulate a Thor parameter.

About basic synthesizer terminology

This chapter assumes familiarity with common synth terminology like oscillators, waveforms, filters and envelopes. If you are new to Reason (or these terms), you may want to read the "Subtractor Synthesizer" chapter first, where these elements and how they interact are described from a more basic point of view.

Loading and Saving Patches

Loading and saving patches is done in the same way as with any other Reason device - see "Loading patches" and "Saving patches".

Thor elements

In the picture below an unfolded Thor device is shown.



Thor's user interface consists of the following elements (from the top down):

- **The Controller panel, which is always shown if Thor is unfolded.**
  See "The Controller panel".
- **The main Programmer panel contains all the synth parameters.**
  The Programmer can be shown/hidden by clicking the "Show Programmer" button on the Controller panel. See "Using the Programmer".
- **The Modulation bus routing section.**
  See "Modulation bus routing section".
- **The Step Sequencer section, where you can program up to 16 steps to produce short melody lines/grooves or use it as a modulation source.**
  See "Step Sequencer".

The Controller panel



The Controller panel contains standard Master Volume and Pitch and Mod controls, Keyboard Mode/Note Triggering sections and four virtual (freely assignable) controls. The panel also has a patch display and standard Select/Browse/Save patch buttons (these are always shown even if Thor is folded).

The Keyboard Mode section

In this section you make basic keyboard related settings for a patch. It has the following options:

Function	Description
Polyphony	This setting determines the number of voices that you can play simultaneously when Polyphonic mode is selected. The maximum number of voices is 32.
Release Polyphony	This governs the number of voices that are allowed to naturally decay/ring out (in the release phase of the envelope) when new notes are triggered and Polyphonic mode is selected. E.g. if you set this to "0", any new note(s) will cut off the release of any previously triggered notes.
Mono Legato	Mono Legato mode is monophonic regardless of the Polyphony setting. It works as follows: ▶ **Hold down a key and then press another key without releasing the previous.** Notice that the pitch changes, but the envelopes do not start over. That is, there will be no new "attack".
Mono Retrig	Mono Retrig is also monophonic and this mode means that when you press a key the envelopes are always retriggered.
Polyphonic	This is the standard polyphonic play mode - you can play the number of voices set with the Polyphony parameter.
Portamento On/Off/Auto	The knob is used for controlling portamento - a parameter that makes the pitch glide between the notes you play, rather than changing the pitch instantly as soon as you hit a key on your keyboard. By turning this knob you set how long it should take for the pitch to glide from one note to the next as you play them. There are three basic portamento modes: ▪ **In Auto mode, there will only be any portamento when playing more than one note. If any of the Mono modes is selected, portamento will only affect the legato notes.** ▪ **When set to On, portamento is applied to all notes.** ▪ **Off means no portamento.**

Note Triggering section

Using the buttons in this section you can select in what way Thor will respond:

- **Via note input only.**
- **Via the Step Sequencer only (see "Step Sequencer").**
- **Or both.**

The section also has a standard Note On indicator.

About the assignable controls

- **The rotary knobs and buttons in the Controller panel are assignable controls that can be assigned to multiple parameters and functions in Thor.**
- **You assign parameters to the knobs and buttons in the Modulation Routing panel (these are located on the "Modifiers" sub-menu - see "Modulation bus routing section").**
- **Movements of the assignable controls can be recorded as automation.**
- **Each control can be assigned to any number of parameters.**
- **Clicking on the label for a Rotary or Button lets you type in an appropriate name for it.**

About the button key note function

To the right of the two assignable buttons there are corresponding spin controls and displays. These can be used to assign a key for turning the button on momentarily, as long as the key is held down.

- **Use the spin controls (or click in the display and move the mouse up or down) to assign a key for the button status.** The assigned key will now turn the function(s) assigned to the button on for as long the key is held down.
- **Note that the key note function can only switch from off to on, not the other way around, so make sure the button is deactivated if you wish to use this function.** An assigned key will not trigger a note, only the button status. Also note that the button will not light up when you press the assigned key.

The Pitch Bend and Modulation wheels

- **The Pitch and Mod wheels on the Controller panel will mirror the corresponding actions on your master keyboard.**
- **The Range parameter (like for all instrument devices) sets the range of the Pitch Bend action.**
- **Pitch Bend is pre-wired to the pitch parameter of the three oscillators, but you can of course use it to control any parameter you like. If you don't want Pitch Bend to affect oscillator pitch, simply set the Range parameter to "0".**

Master volume

This is the main volume control for outputs 1 & 2.

Using the Programmer

The Programmer contains the main synth parameters.

- **To show the Programmer panel, click the "Show Programmer" button on the Controller panel.**
  The Programmer appears below the Controller panel.





- **The Programmer panel is divided into two sections; the Voice section to the left and the Global section to the right. The Global section has a separate brown panel to differentiate it from the Voice section.**
  The Voice section contains the basic synth parameters and the parameters are "per-voice", i.e. all envelope and LFO cycles are triggered individually for each voice. The Global section to the right contains global parameters that affect all voices.

- **There are three open Oscillator slots, a Mixer, two open Filter slots, a Shaper, three Envelope generators, an LFO and an Amplifier in the Voice section.**
  The open Oscillator and Filter slots allow you to select between different types of oscillators and filters.

- **The Global section contains a second LFO, a Global Envelope, a third open Filter slot and Chorus and Delay effects.**

Basic connections - a tutorial

There are certain pre-defined connections available between the Oscillator 1-3 slots and the Mixer, Filter 1/Shaper, Filter 2 and Amp sections. On the panel itself, lines with arrows are shown to indicate the standard signal paths.


- **Note that you can also connect sections using the Modulation bus section (see "Modulation bus routing section"). You are not in any way limited to the pre-defined routings, but they do provide a quick and convenient way to connect the basic synth "building blocks" together.**

In the following tutorial we will create a standard setup using two oscillators and two filters to demonstrate Thor basics and the (standard) signal path:

1. **Select "Reset Device" from the context menu or from the Edit menu.**
   The "Init patch" is a basic setup with an Analog oscillator in Oscillator slot 1 and a Ladder LP filter in Filter slot 1 loaded. A connection between Oscillator 1, Filter 1 and the Amp section is already activated, so you get a sound when you play.


Below the Oscillator 1 slot in the upper left corner are two more slots, currently empty. These are the Oscillator 2 and 3 slots, respectively. The three Oscillator slots are basically identical in that they can each be loaded with one of 6 oscillator types.

2. **Click the arrow pop-up in the upper left corner of the Oscillator 2 slot, and select a second oscillator from the pop-up that appears.**
   The following oscillator types are available; Analog, Wavetable, Phase Modulation, FM Pair, Multi and Noise. For a description of the various oscillator types, see "The Oscillator section".



Selecting oscillator type.

With a basic connection setup, the Oscillator outputs are internally connected to the “Mix” section. To pass the output signal onwards in the signal chain, you first have to activate a connection. This is done using the two vertical rows of routing buttons labelled 1, 2 and 3 to the right of the Oscillator section.



- **The upper row of routing buttons determine which of the Oscillators 1 to 3 are routed to Filter 1, and the lower row which of the Oscillators 1 to 3 are routed to Filter 2.**
  All three oscillators can be simultaneously routed to both filters, serially or in parallel (or any combination of these variations). This is explained later in this tutorial.

By activating one or more of these buttons means that the oscillator (1 to 3) is routed to the corresponding Filter. Currently, Oscillator 1 is connected to Filter 1 slot (which is pre-loaded with a Ladder LP filter).

This is indicated by the “1” routing button being lit. The Filter 2 slot is currently not active, which is indicated by a blank panel.

3. **Click the “2” button to the left of the Filter 1 section so that it lights up to activate a connection for Oscillator 2.**
   Now if you play a few notes you should hear both Oscillator 1 and Oscillator 2, via the Filter 1 section.



- **The Filter 1 output passes via the Shaper (currently not activated), on to the Amp section, and finally to the Main Outputs.**
  Actually, the Amp section output is routed via the Global section before being sent to the Main Outputs, but as currently nothing is activated in the Global section the signal passes through unprocessed.

4. **Next, click the arrow pop-up in the upper left corner of the Filter 2 slot.**
   A pop-up menu with the four available Filter types appears. For a description of the filter types, see "Filter slots".



5. **Select a type of filter, e.g. a Comb filter for the Filter 2 slot.**
   Now that the Filter 2 slot in the Voice section is active, you can connect the oscillators to it by using the lower row of routing buttons.
6. **Click the routing buttons "1" and "2" to the left of the Filter 2 slot so that the buttons are lit.**
   Now the two oscillators are connected to Filter 2.
7. **Make sure the arrow routing button that points to the Amp section just above the Filter 2 section is activated.**
   Now if you play a few notes, both oscillators are routed via both filter sections in parallel. You could of course select to pass only one of the oscillators via one filter and both oscillators via the other - any combination is possible.



You can also connect the Filter 1 and 2 sections serially, meaning that the output of Filter 1 is passed through Filter 2 before reaching the Amp section. This is done as follows:

8. **Switch off the routing buttons "1" and "2" to the left of the Filter 2 slot.**
   If you leave them on the oscillators will pass through Filter 2 twice; both via Filter 1 and directly. This is also perfectly "allowable", but to make things clearer in this tutorial we will use a standard serial filter setup.
9. **Click the Arrow "left" button below the Shaper.**
   Now the filters are connected serially, with the output of Filter 1 (via the for now inactive Shaper) being connected to the Filter 2 input. Both oscillators are processed by both filters connected in series.



That concludes this tutorial on how the pre-wired connections in the Voice section can be used, but note that you can also use the Modulation bus to make connections - see "Modulation bus routing section".

Other pre-defined routing assignments

There are other sections in Thor which are pre-defined and can be used without having to make any prior assignments:


- **The Amp Envelope and the Filter Envelope control the volume level and frequency of the Filters (1 & 2), respectively.**
  The amount of filter envelope control is controllable by using the "Env" parameter in each Filter section.
- **The effects (Delay/Chorus) in the Global section are part of the signal chain and can simply be switched on and used.**

The Oscillator section



Oscillators generate the basic raw sound (pitch and waveform) that can in turn be processed by the other parameters. The Oscillator section contains three open slots which can each be loaded with one of six oscillator types. The three Oscillator slots are numbered 1-3, with the top slot housing Oscillator 1, the middle slot Oscillator 2 and the bottom slot Oscillator 3.

- **The Arrow button in the top left corner of each slot opens a pop-up menu where an oscillator type can be selected for the corresponding slot.**



There are six Oscillator types available:

- **Analog**
- **Wavetable**
- **Phase Modulation**

- **FM Pair**
- **Multi Oscillator**
- **Noise**

You can also select Off mode (no oscillator).

Common parameters

The specific parameters of the various oscillator types are described separately, but there are also common parameters that apply to all oscillator types. These are:

- **Octave (OCT) knob - this changes the pitch of the oscillator in octave steps.**
  The range is ten octaves.
- **The Semi knob changes the pitch of the oscillator in semi-tone steps.**
  The range is 12 semitone steps (1 octave).
- **The Tune knob fine tunes the pitch of the oscillator in cent steps.**
  The range is +/- 50 cents (down or up half a semitone).
- **Keyboard Track (KBD) - this knob sets how much the oscillator pitch tracks incoming note data.**
  Turned fully clockwise the pitch tracks the keyboard normally, i.e. a semitone per key.
- **All oscillators also have waveform selectors and a modifier parameter. How the waveform selection works, and what parameter is the modifier varies according to the selected oscillator type.**
- **Important to note is that if you have made a modulation routing to an oscillator parameter e.g. the modifier, and then change the oscillator type, the modulation will be transferred to the corresponding parameter in the new oscillator.**
  The same goes for all common parameters (tuning and tracking). If you switch oscillator type, all common parameters are left unchanged.
- **Oscillators can be synced - see "About Oscillator Sync".**
- **Any oscillator type loaded into the Oscillator 1 slot can also be amplitude modulated by Oscillator 2 - see "About Amplitude Modulation (AM)".**

Analog oscillator



This is a classic analog oscillator with 4 standard waveforms. The waveform selector button is in the lower left corner of the oscillator panel, but you can also click directly on the waveform symbols to switch waveform. The four available waveforms are from the top down (as displayed on the panel): Sawtooth, Pulse, Triangle and Sine.

- **The Mod parameter (PW) controls pulse width and only affects the pulse waveform.**
  By modulating the PW parameter the width of the pulse wave changes, allowing for PWM (Pulse Width Modulation) which is a standard feature in most vintage analog synths.

- **For a perfect square wave, set pulse width (PW) to 64.**

Wavetable oscillator



Wavetable oscillators has been the basis of several vintage synths (PPG, Korg Wavestation and many others).

- **With the Wavetable oscillator, you select between 32 wavetables, where each wavetable contains several (up to 64) different waveforms. By using an envelope or a LFO you can sweep through a wavetable to produce timbre variations.**

The parameters are as follows:

- **Position is the modifier (Mod) parameter and controls the position within the selected wavetable, i.e. which waveform is active at a given time.**
  By modulating the Position you can sweep through the waveforms in the selected wavetable. You can of course also use a single static waveform in a wavetable if you so wish, by not applying any modulation to this parameter.
- **The X-Fade button determines whether the change between waveforms in a wavetable should be abrupt (X-Fade off), or smooth (X-Fade on).**
  If set to on, the waveform transitions are cross-faded.
- **There are 32 wavetables that can be selected using the up/down buttons or by clicking in the Wavetable display.**

Some of the wavetables have waveforms that sequentially follow the harmonic series, i.e. each following waveform adds a harmonic. Others have waveform series that produce a sound similar to oscillator sync when swept, and other wavetables are simply mixed waveforms. The last 11 wavetables are based on wavetables used in the original PPG 2.3 synthesizer.

Phase Modulation oscillator



The Phase Modulation oscillator is inspired by the Casio CZ series of synthesizers. Phase modulation is based on modulating the phase of digital waveforms to emulate common filter characteristics.

- **You have a First and Second waveform which can be combined. Instead of mixing the two waveforms they are played in series, one after the other.**
  This adds a fundamental one octave below the pitch of the original sound.
- **The PD parameter (Mod) changes the shape of the wave, much like a filter does.**

The following waveforms (sequentially from the first) are available as the First waveform:

- **Sawtooth**
- **Square**
- **Pulse**

- **Pulse and Sine**
- **Sine and flat (half sine)**
- **Saw x Sine**
- **Sine x Sine**
- **Sine x Pulse**

The last three waveforms could be described “resonant”, as these originally were meant to simulate filter resonance. They didn’t really do this very accurately, but nevertheless constituted an important part of the sound.

The Second waveform has the same available waveforms except the last three, and it can also be bypassed altogether. You can combine waveforms freely, except it is not possible to combine two “resonant” waveforms.

FM Pair oscillator



As the name implies, this oscillator generates FM, where one oscillator (Carrier) is frequency modulated by a second oscillator (Modulator). Although very simple to use (unlike most hardware FM synths), this oscillator can produce a very wide range of FM sounds.

- ▶ **The Carrier and Modulator selector buttons set the frequency ratio between these two oscillators (the range is 1-32).**
  The frequency ratio is what determines the basic frequency content, and thus, the timbre of the sound.
- ▶ **The FM knob sets the amount of frequency modulation.**
  This is also the Modifier parameter. If FM amount is set to zero, there is no FM and the output will be a pure sine wave.
- **If you set FM Amount to zero and step through the values of the Carrier oscillator, you can hear that the pitch is changed according to the harmonic series.**
- **Stepping through the Mod oscillator values will change the pitch in the same way, although FM Amount has to be set to a value other than zero to be able to hear it.**

Thus, 2:2 is the same wave shape as 1:1 but one octave higher in pitch, 3:3 is the same wave shape as 2:2 but a fifth higher in pitch and so on.

Multi oscillator



This versatile oscillator can simultaneously generate multiple detuned waveforms (of a set type) per voice. It is great for producing complex timbres e.g. to simulate cymbal or bell sounds, but can also generate a wide range of harmonic sounds.

- **The following basic waveforms are available: Sawtooth, Square, Soft Sawtooth, Soft Square, Pulse.**
  You switch waveforms using the button in the lower left corner, or by clicking directly on the waveform symbol.
- **The Amount (AMT) parameter governs the amount of detune.**
  Turn clockwise for more detune. This is also the modifier (Mod) parameter. Using low Amount settings can produce subtle detune variations that makes the sound shift and move endlessly, like an advanced chorus effect, whereas higher Amount settings can produce wild, detuned timbres.
- **The Detune Mode parameter sets the basic operational mode of the detuning.**
  If Amount is set to 0, only the "Octave" and "Fifth" Detune modes actually change the sound, as these modes start off with dual waveforms tuned one octave and a fifth apart, respectively. The "Fifth Up" and "Oct UpDn" modes detune waveforms as the names imply between zero to full Amount settings. "Linear" will change the amount of detune according to where on the keyboard you play; in lower keyboard ranges the amount of detune is stronger than in higher keyboard ranges and vice versa. The other modes (Interval and Random) basically add multiple waveforms and detune them in various ways that will produce different results.

Noise oscillator



The Noise oscillator can not only produce white and colored noise, but can also be used either as a pitched oscillator or as a modulation source.

It has the following basic parameters:


- **There is a single Noise parameter (apart from the standard tuning and kbd track knobs).**
  This is the Noise modifier parameter, that controls different parameters depending on the selected Oscillator mode, see below.
- **The Waveform selector button in the bottom left corner is used to set the Oscillator mode.**
  The following modes are available:'

Mode	Description
Band	In this mode, the Oscillator knob controls bandwidth. Turned fully clockwise, the oscillator produces pure noise. Turning the knob counter-clockwise gradually narrows the bandwidth until a pitch is produced. The pitch will track the keyboard normally if the keyboard (KBD) knob is set fully clockwise.

Mode	Description
S/H	S/H stands for "sample and hold", which is a type of random generator. The Oscillator knob controls the rate of the sample and hold. With high Oscillator knob settings, it produces colored noise with a slightly "phased" sound quality. With lower rate settings you can use the oscillator as a modulation source like a LFO with random values. For example, if you modulate the pitch of another oscillator using S/H with a low Rate setting as the source, you will get stepped random modulation of the pitch.
Static	As the name implies, this can generate the sound of static interference if you use low Oscillator settings. The Oscillator parameter controls Density, i.e. the amount of static. High Density settings generates noise.
Color	This produces colored noise, which is basically noise where certain frequency areas are filtered, i.e. cutting or boosting certain frequency areas in the noise. The Oscillator knob controls Color. With a maximum Color setting you get white noise, and lower settings produces noise emphasizing lower frequencies.
White	This produces pure white noise, where all frequencies have equal energy. There is no associated Oscillator parameter for White noise.

About Oscillator Sync

Oscillator sync is when one oscillator will restart the period of another oscillator, so that they will have the same base frequency. If you change or modulate the frequency of the synced oscillator you get the characteristic sound associated with oscillator sync.



Syncing oscillator

Synced oscillator

In Thor, oscillator 1 is always the syncing oscillator, i.e. oscillator 1 controls the base pitch of oscillators 2 and 3, which are the synced oscillators.

- **Switch Oscillator Sync on or off by activating the Sync buttons to the left of Oscillator slots 2 and 3.**



- **The Sync "BW" sliders to the left of Oscillator slots 2 and 3 allows you to adjust the sync bandwidth.**
  This allows you to change the character of the oscillator sync. The parameter basically sets how abrupt the reset is - high bandwidth settings produces a more pronounced sync effect and vice versa. The picture above illustrates high bandwidth reset - if lower bandwidth settings are used the synced osc curve will be more rounded at the reset points.

About Amplitude Modulation (AM)

AM (Amplitude Modulation) is often referred to as ring modulation. AM works by multiplying two signals together.

- **In Thor, Oscillator 2 amplitude modulates Oscillator 1.**
  The Ring Modulated output will then contain added frequencies which are generated by the sum of, and the difference between the two signals. This can be used for creating complex, enharmonic sounds.
- **The amount of AM is set using the slider to the left of the Oscillator 1 slot.**



Mix section



The Mix section allows you to adjust the levels and the relative balance of the three oscillators.

- **The two sliders controls the output levels of oscillators 1-2 and oscillator 3, respectively.**
- **The Balance knob sets the balance between oscillator 1 and 2.**
  The Balance parameter is also a modulation destination, allowing you to modulate the balance of the two oscillators with e.g. an LFO. Note that the oscillators have to be connected to the filter(s) via the numbered routing buttons for the Mix section settings to have any effect.

Filter slots



Thor has three open Filter slots, two in the Voice section (which act per-voice) and one in the Global section which is global for all voices (see "Global Filter slot").

- **You select (or change) filter type for a slot by clicking the arrow button in the top left corner of a slot.**
  On the pop-up you can select between 4 filter types and bypass mode. Available filter types are Ladder LP, State Variable, Comb and Formant, each described separately below.

The following general rules apply:

- **Filters are pre-wired to the Filter Envelope (see "Filter Envelope").**

- **Filters 1 & 2 can be used serially (i.e. the output of Filter 1 goes (via the Shaper) to the input of Filter 2, or in parallel (meaning that one signal goes to Filter 1 and another to Filter 2).**

The pre-defined routings of the three oscillators into the Filter 1-2 sections is described in the "Basic connections - a tutorial" passage.

Common parameters

As with the open oscillator slots, there are certain parameters which are common for all filter types.

These are as follows:

- **All the filter types have large knobs for the filter frequency (FREQ) parameter and the filter resonance (RES) parameter.**
  This works slightly differently for the Formant filter - see "Formant filter".
- **The "KBD" parameter sets how the filter frequency tracks incoming note pitch data.**
  Some filter types (Ladder/State Variable/Comb) can "self oscillate" and be used as extra oscillator sources.
- **The "ENV" parameter sets how much the filter frequency responds to the Filter Envelope.**
- **The "VEL" parameter sets how much incoming note velocity affects the Filter Envelope Amount.**
  In other words, for this parameter to have any effect it requires that the "ENV" parameter is set to a value other than zero.
- **The "INV" button inverts how the filter frequency responds to Envelope settings.**
- **The "Drive" parameter allows you to adjust the input gain to the filter.**
  By driving the filter harder you can add further character to the sound.
- **Any parameter settings, as well as any modulation assigned to parameters, will be kept even if you change the filter type.**

Ladder LP Filter



The Ladder LP filter is a low-pass filter inspired by the famous voltage controlled filter patented by Dr. Robert Moog in 1965. The name originates from the ladder-like shape of the original transistor/capacitor circuit diagram.

The original filter also had certain non-linear characteristics which contributed to the warm, musical sound it is renowned for. These characteristics are faithfully reproduced in the Ladder LP filter.

There is also a built-in shaper in the feedback (self-oscillation) loop. If self-oscillation is activated (see below), the shaper will distort the sound to produce these non-linear characteristics. To adjust the intensity of this distortion you use the Drive parameter.

- **There are 4 different Filter slopes available; 24, 18, 12 and 6 dB/oct.**
  24dB slope comes in two different types:
- **Type I - The shaper (controlled with the Drive parameter) is placed at the filter output but before the feedback loop.**
- **Type II - The shaper (controlled with the Drive parameter) is placed at the filter input after the feedback loop.**

Note that "Self Osc" (see below) must be activated for the shaper to operate.

- **This filter can self-oscillate and will produce a playable note pitch with high Resonance settings if this is activated.**
  Self-oscillation can be switched on or off by using the "SELF OSC" button. The "KBD" knob governs how the frequency tracks the keyboard, turned fully clockwise will produce 12 semitones/octave tracking.

State Variable Filter



This is a multi-mode filter which offers 12 dB/octave slope Lowpass (LP), Bandpass (BP), Highpass (HP), plus Notch and Peak filter modes which are sweepable between HP/LP states, similar to the vintage Oberheim SEM filter.

The filter modes are as follows:

- **LP 12 (12 dB lowpass)**
  Lowpass filters let low frequencies through and cut off high frequencies. This filter type has a 12dB/Octave slope.
- **BP 12 (12 dB bandpass)**
  Bandpass filters cut both high and low frequencies, leaving the frequency band in between unaffected. Each slope in this filter type is 12 dB/Octave.
- **HP 12 (12 dB highpass)**
  Highpass filters let high frequencies pass and cut off low frequencies. This filter type has a 12dB/Octave slope.
- **The "Notch" and "Peak" filter modes employ a combination of two outputs from the same filter combining LP and HP set to the same the filter frequency.**
  The "LP/HP" knob associated to these two filter modes can modulate the state of the filter from low-pass to high-pass. If the knob is in the mid-position, you get a Peak or Notch filter slope (depending on the mode). The HP/LP parameter can be assigned as a modulation destination.
- **This filter can self-oscillate and will produce a pitch with high Resonance settings if this is activated.**
  Self-oscillation can be switched on or off by using the "SELF OSC" button. The "KBD" knob governs how the frequency tracks the keyboard, turned fully clockwise will produce 12 semitones/octave tracking.

Comb filter



The Comb filter can add subtle pitch variations and phasing-like effects to sounds.


- **Comb filters are basically very short delays with adjustable feedback (controlled with the Resonance knob).**
  A comb filter causes resonating peaks at certain frequencies. Comb filters are used in various signal processing devices like flangers, and produces a characteristic swooshing sound when the frequency is swept.
- **The difference between the "Comb +" and "Comb –" modes is the position of the peaks in the spectrum.**
  The main audible difference is that negative Comb mode causes a bass cut.
- **The Resonance parameter in both cases controls the shape and size of the peaks.**
  This filter will produce a pitch with high Resonance settings combined with low frequency settings.

Formant filter



The Formant filter type can produce vowel sounds. There are no Frequency or Resonance parameters, instead you have a horizontal "X" parameter slider and a vertical "Y" parameter slider that operate together to produce the various filter formant characteristics.

- **You can alter the settings of both the "X" and "Y"parameters simultaneously by moving the "dot" inside the gray rectangle on the filter panel.**
  Horizontal movement changes the "X" parameter, and vertical movement the "Y" parameter.



- **The ENV-VEL-KBD knobs affect the "X" parameter.**
  The parameter can be CV controlled.
- **The "Gender" parameter changes the basic timbre of the vowel generation between male (low Gender settings) and female (high Gender settings) voice characteristics.**
  Gender can also be CV controlled.

Shaper

Waveshaping is a synthesis method for transforming sounds by altering the waveform shape, thereby introducing various types of distortion. The Shaper can radically transform the sound or just add a little warmth, depending on the mode and other settings.

- **The Shaper input is taken from the Filter 1 output.**
- **The Shaper is activated with the button in the top left corner of the section.**



- **The Drive parameter sets the amount of waveshaping.**
  Tip: By raising the Filter 1 Drive parameter you can add even more grit and distortion to the Shaper output.
- **The Shaper has 9 modes, selectable with the spin controls or by clicking in the Mode display, all which distort the waveform in various different ways.**
  These modes are; Soft and Hard clip, Saturate, Sine, Bipulse, Unipulse, Peak, Rectify and Wrap. Exactly how the various modes affect the sound depends on many factors, and there is a slightly random element to the resulting distortion. We recommend simply trying the different modes to hear what happens - many interesting types of distortion of the original signal are guaranteed!

Amp section



The Amp (amplifier) section has two inputs (from Filter 1 & 2) and one output that is routed to the Global section (and on to the Master Level and the Main Outputs).

- **The Gain knob controls the level and the Velocity knob controls the Gain modulation, i.e. how much velocity affects the level - positive values means that you get higher level the faster you strike a key.**
- **The Pan knob controls the relative stereo position of the individual voices.**
  By applying modulation to this parameter, you can make individual voices appear in different stereo positions when you play.

LFO 1



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. A typical example is to have an LFO modulate the pitch of an oscillator to produce vibrato, but there are countless other applications for LFOs.

- **LFO 1 will apply modulation polyphonically.**
  I.e. if LFO 1 modulation of a parameter is assigned, an individual LFO cycle will be triggered for each note you play.
- **You select a LFO waveform by using the spin controls beside the waveform display, or by clicking in the display and moving the mouse up or down.**

The following parameters are available for LFO 1:

Parameter	Description
Rate	This sets the frequency or rate of the LFO.
Waveform	This sets the LFO waveform. Apart from standard waveforms (sine, square etc.) there are various different random, non-linear and stepped waveforms. The shape of the waveforms are shown in the display, and these shapes basically reflect how a signal is affected.
Delay	This introduces a delay before the LFO modulation onset after a note is played. Turn clockwise for longer delay.
KBD Follow	This determines if (or how much) the Rate parameter is affected by note pitch. If you turn the knob clockwise, the modulation rate will increase the higher up on the keyboard you play.
Key Sync	As explained previously, LFO 1 is polyphonic and will produce a separate LFO cycle for each note played. If Key Sync is off, the cycles are free running, meaning that when you play a note the modulation may start anywhere in the LFO waveform cycle. If Key Sync is on, the LFO cycles are reset for each note played.
Tempo Sync	If this is on, the Rate will be synced to the sequencer tempo.

Envelope sections



There are three Envelope generators in the Voice section. These are the Amp envelope, the Filter envelope and the Mod envelope. Each voice played has a separate envelope. There is also an additional Global Envelope which is described separately - see "Global Envelope".

- **The Filter envelope is pre-wired to control the frequency of Filter 1 and 2.**
  Note that envelope control of filter frequency can be switched off in each Filter section (the Env parameter can be set to 0), so the Filter Envelope can be used to control other parameters as well.
- **The Amp Envelope is pre-wired to control the amplitude (volume).**
  Similarly, the Amp envelope can also be used to control other parameters, but in the Voice section you cannot switch off or bypass the Amp Envelope - if no voice is active (i.e. if there is no gate trigger input to the Amp envelope) there will be no output from oscillators or any external audio source routed to the Voice section.
- **The Mod Envelope can be freely assigned to control parameters.**
  This is done in the Modulation section.

Filter Envelope

The Filter Envelope is a standard ADSR envelope as used in the Subtractor.

- **By setting up a filter envelope you control the how the filter frequency or some other parameter should change over time with the four parameters, Attack, Decay, Sustain and Release.**
  Please refer to the Subtractor chapter for a description of these parameters.
- **The "Gate Trig" button can be used to switch off the envelope triggering from notes (which is the normal mode) and allow the envelope to be triggered by some other parameter.**
  "Gate Trig" should normally be activated.
- **The time ranges of each step are as follows:**
  Attack: 0 ms - 10,3 s / Decay and Release: 3 ms - 29,6 s. Sustain is not set as a time but as a level (from Off to 0dB).

Amp Envelope

The Amp Envelope is also a standard ADSR envelope.

- **By setting up a Amp envelope you control the how the amplitude or some other parameter should change over time with the four parameters, Attack, Decay, Sustain and Release.**
  Please refer to the Subtractor chapter for a description of these parameters.
- **The "Gate Trig" button can be used to switch off the envelope triggering from note input (which is the normal mode) and allow the envelope to be triggered by some other parameter.**
  "Gate Trig" should normally be activated.
- **The ranges of each step are the same as for the Filter envelope.**

Mod Envelope

This is a general purpose ADR (Attack, Decay, Release) envelope with a pre-delay stage before the Attack phase. The Delay to Decay phase can also be looped. Apart from standard Attack, Decay and Release stages the Mod Env has the following parameters:

Parameter	Description
Delay	This can set a delay before the onset of the envelope.
Loop	If this is activated, the envelope phase from Delay to Decay will continuously loop.
Tempo Sync	If this is on, each stage will have a length that corresponds to beat increments of the current sequencer tempo. E.g. you can have a 1/4 delay before a 1/16 attack phase followed by a 1/8 decay. Each stage can be set a range from 1/32 to 4/1 (4 bars). If this is off, the envelope times are free running and can be set in seconds (same time ranges as for the Filter Envelope).
Gate Trigger	The "Gate Trig" button can be used to switch off the envelope triggering from notes (which is the normal mode) and allow the envelope to be triggered by some other parameter. "Gate Trig" should normally be activated.

Global section



The Global section contains parameters that affect all voices. It contains two effects, an open filter slot, the Global Envelope and LFO 2.

Effects section

There are two global mono in/stereo out effects, a Delay and a Chorus. These effects affect all voices coming from the Amp section equally if activated. The effects are placed after the Global Filter in the signal chain.

- **There are controls for standard Delay/Time and Feedback parameters.**
  Chorus vs. Delay differ only in the delay time range - Chorus is for chorus effects, i.e. short delays, whereas Delay produces echo effects.
- **Delay Time can be Tempo Synced.**
  This is set with the Tempo Sync button - if on the delay time is set in beat resolutions synced to the main sequencer tempo.
- **The Delay and Chorus effects can also be pitch modulated by a built in LFO (the "Mod" parameters).**
  "Rate" controls LFO speed and "Amount" the Stereo width.
- **Dry/Wet governs the balance between the unprocessed (dry) signal and the effect (wet) signal.**

Global Filter slot

This is the Filter 3 slot which can be loaded with one of the filter types. Filter 3 is basically set up as the other filter slots. The difference is that all voices are mixed together before entering the filter. The "ENV" parameter governs modulation by the Global Envelope. If you play one note the filter envelope will trigger. Adding new notes while a note is still held down (legato) will not trigger the filter envelope.

See "Filter slots" for a description of the filter types.

Global Envelope

The Global Envelope 4 is an advanced envelope that is free to use for whatever purpose, but remember it is "single trigger" so it will not retrigger legato notes as explained above. It is an ADSR envelope with a pre-delay stage and a hold stage before the decay phase. You can make it Loop and Sync the time settings to the song tempo.

Apart from standard ADSR parameters, the Global Envelope has the following parameters:

Parameter	Description
Delay	This can set a delay before the onset of the envelope.
Loop	If this is activated, the envelope phase from Delay to Decay will continuously loop.
Hold	This allows you to set a "hold" phase before the Decay.
Tempo Sync	If this is on, each stage will have a length that corresponds to beat increments of the current sequencer tempo. E.g. you can have a 1/4 delay before a 1/16 attack phase followed by a 1/8 decay. Each stage can be set a range from 1/32 to 4/1 (4 bars). If this is off, the envelope times are free running and can be set in seconds (same time ranges as for the Filter Envelope).
Gate Trigger	The "Gate Trig" button can be used to switch off the envelope triggering from notes and allow the envelope to be triggered by some other parameter. This button is normally activated.


LFO 2

- ▶ **The LFO 2 is a standard LFO but is not polyphonic like LFO 1. It is not assigned to any parameter in an "Init" patch so you have to use the Modulation Routing section to use it.**
- ▪ **Also the LFO 2 "Delay" and "Key Sync" parameters are single trigger, i.e. the LFO will not retrigger these parameters for legato notes.**
- ▶ **You select a LFO waveform by using the spin controls beside the waveform display, or by clicking in the display and moving the mouse up or down.**

The following parameters are available for LFO 2:

Parameter	Description
Rate	This sets the frequency or rate of the LFO.
Waveform	This sets the LFO waveform. Apart from standard waveforms (sine, square etc.) there are various different random, non-linear and stepped waveforms. The basic shape of the waveforms are shown in the display, and illustrate how a signal is affected.
Delay	This introduces a delay before the LFO modulation onset after a note is played. Turn clockwise for longer delay.
Key Sync	If Key Sync is off, the LFO cycle is free running, meaning that when you play a note the modulation may start anywhere in the LFO waveform cycle. If Key Sync is on, the LFO cycle is reset for each note played.
Tempo Sync	If this is on, the Rate will be synced to the sequencer tempo in beat increments (4/1 to 1/32).

Modulation bus routing section



A modulation bus is used to connect a modulation source to a modulation destination. Both audio signals and control (CV) parameters are available. This creates a flexible routing system that complements the pre-wired routing in the Voice panel.

Basic operation - simple tutorial

To illustrate the basic operation of the modulation bus section, let's set up a simple source to destination modulation assignment:

! If you currently have unsaved settings you wish too keep, don't forget to save them first.


1. Select "Reset Device" from the Edit menu.

The Init patch is a simple 1 oscillator/1 filter setup, which produces sound when you play, and will serve the purpose of this tutorial.

- ▪ **The left half of the modulation section contains 5 columns, Source, Amount, Dest, Amount and Scale.**
  Below the column headers there are 7 rows. Each row is a modulation bus where you can have a Source to Destination modulation assigned.

2. Click in the top row of the leftmost Source column.
A pop-up menu appears listing all available Source modulation parameters.

The upper half of the menu contains Voice section source parameters, and the lower half contains various global play and performance-oriented source parameters and the Global Envelope, as well as the Step Sequencer, CV and Audio inputs.




3. Select "LFO 1" from the pop-up.

This means that LFO 1 is the modulation Source, and this can now be assigned to modulate a Destination parameter.

4. Pull down the "Dest" column pop-up in the top row.

A pop-up menu appears listing all available modulation Destinations. The upper half of the menu contains Voice section destinations, and the lower half contains Global section destinations, as well as the Step Sequencer, CV and Audio outputs.

5. Select "Osc 1" from the menu and then "Pitch" from the submenu.



This means that Osc 1 pitch is now assigned to be modulated by LFO 1. Next step is to set the amount of modulation to be applied.

6. Click in the top row Amount column to the right of the Source column, and move the mouse pointer up and down to set an Amount value.
Both positive and negative Amount values can be set (+/- 100%).


▶ **If you now play a few notes you can hear the oscillator pitch being modulated by the LFO to produce vibrato.**
But the vibrato will be constant, which you probably don't want. This is solved by assigning a Scale parameter, which allows you to assign another parameter to control the modulation Amount.

7. Pull down the "Scale" column pop-up in the top row.

A pop-up menu appears listing all available Scale parameters. The upper half of the menu contains Voice section parameters, and the lower half contains various play and performance-oriented parameters and the Global Envelope, as well as the Step Sequencer, CV and Audio inputs.

A typical controller for vibrato is the Mod wheel.

8. **Select "Performance" from the menu and then "Mod wheel" from the submenu.**



This means that Osc 1 pitch is now assigned to be modulated by LFO 1, and the amount of modulation is controlled by the Mod wheel. How much the Scale parameter controls the Amount is set using the "Amount" column for the top row (to the left of the Scale column).

9. **Click in the top row Amount column and move the mouse pointer up and down to set an Amount value.**
   Both positive and negative Scale Amount values can be set (+/- 100%). To fully control the LFO modulation so that there is no vibrato when the Mod wheel is set to zero, set the Amount to 100%.



10. **The modulation routing is now complete!**
    You now have full control over the vibrato modulation by using the Mod wheel.

- **How much modulation will be applied when the Scale parameter is set to maximum is governed by the Source to Destination Amount parameter.**
- **How much the Scale parameter controls the modulation is set with the Scale Amount parameter.**
- **To clear any assigned modulation routing you can use the "CLR" button to the right of the corresponding bus.**

About the three modulation routing types

As described in the tutorial, the principal operators of the Modulation bus routing system are as follows:


- **You have Modulation Source, Modulation Destination and Modulation Amount parameters.**
- **Optionally, you have a Scale parameter controlling the Modulation Amount, and a Scale Amount that governs how much the Scale parameter controls the Modulation Amount.**

There are three different types of modulation routing busses available in Thor:

- **You have seven "Source –> Destination –> Scale" routing busses.**
  These are the seven rows in the left half of the Modulation section, as covered in the tutorial.



- **There are four "Source –> Destination 1 –> Destination 2 –> Scale" busses.**
  These are the four top rows in the right half of the Modulation section. This works after the same principle but the Source parameter can affect two different Destination parameters (with variable Amount settings) and a Scale parameter that affects the relative modulation Amount for both Destinations.



- **Lastly, there are two "Source –> Destination –> Scale 1 –> Scale 2" busses.**
  This means that a modulation Amount can use two Scale parameters.

  An example: You have the Mod Envelope as Source and Oscillator Pitch as the Destination (Amount set whatever you like). As the first Scale parameter we use the Mod Wheel (Amount set to 100 so that no modulation is applied when the Mod wheel is at zero), and LFO 1 as the second Scale parameter (Amount set to whatever you like). When you move the Mod wheel, the pitch modulation amount will be modulated by both the Mod Envelope and LFO 1 simultaneously.



Modulation Sources - Voice section

The following parameters can be used as Voice section modulation Sources:

Parameter	Description
Voice Key	Voice Key lets you assign modulation according to notes. There are 4 modes selectable from the sub-menus: ▪ **Note - this is keyboard tracking. If a positive Amount value is used and the destination is filter frequency, the filter frequency will track the keyboard, i.e. increase with higher notes.** ▪ **Note2 - this works similarly to Note but within a repeated octave range. E.g. if Note2 modulates Amp Pan the pan position will move from left to right within an octave range then start over. If you play chords normally over the keyboard the effect will be that notes are randomly spread across the stereo field.** ▪ **Velocity - this applies modulation according to velocity (how hard or soft you strike the keys).** ▪ **Gate - this is Gate on/off. E.g. if applied to oscillator pitch you will get one pitch value (set by Amount) when a key is pressed, and another value (the unmodulated pitch) when the key is released.**
Osc 1/2/3	This allows you to route the audio output from the oscillators to a destination.
Filter 1/2	This is the audio output of the filters. All filter parameters affect the destination.
Shaper	This is the audio output of the Shaper module. Note that anything connected to the Shaper, e.g. Filter 1, affects the Shaper output, and thus the resulting modulation.
Amp	This is the audio output of the Amp Gain section.
LFO 1	This allows you to modulate parameters with LFO 1.
Filter Envelope	This allows you to modulate parameters with the Filter Envelope.
Amp Envelope	This allows you to modulate parameters with the Amp Envelope.
Mod Envelope	This allows you to modulate parameters with the Mod Envelope.

Modulation Sources - Global

The following parameters can be used as Global section modulation Sources:

Parameter	Description
Global Envelope	This allows you to modulate parameters using the Global Envelope.
Voice Mixer	This allows you to modulate parameters using the Left and Right Mixer inputs.
Last Key	This will apply modulation according to the last note played (monophonic), either via MIDI, or from the Step Sequencer. For example, you can use Last Key to make a filter's frequency track notes played by the Step Sequencer.
MIDI Key	This applies modulation according to notes globally, not per-voice so in other words it is monophonic. E.g. if you use MIDI Note as Source and a self-oscillating filter's frequency as the destination, the filter will track but you will only be able to play one voice at a time. MIDI Note is handy for transposing Step patterns in real time. There are 3 modes selectable from the sub-menus: ▪ **Note - this is keyboard tracking. If a positive Amount value is used and the destination is filter frequency, the filter frequency will track the keyboard, i.e. increase with higher notes.** ▪ **Velocity - this applies modulation according to velocity (how hard or soft you strike the keys).** ▪ **Gate - this is Gate on/off. E.g. if applied to oscillator pitch you will get one pitch value (set by Amount) when a key is pressed, and another value (the unmodulated pitch) when the key is released.**
LFO 2	This allows you to modulate parameters with LFO 2.
Performance parameters	On this sub-menu you can assign the one of the standard Performance controllers to modulate/scale parameters; Mod Wheel/Pitch Bend/Breath/AfterTouch/Expression.
Modifiers	This is where you assign parameters and functions to be controlled with the virtual 2 Rotary and 2 Button controls on the Controller panel.
Sustain Pedal	This allows you to assign the Sustain Pedal as a modulation source.
Polyphony	This allows you to apply modulation according to how many notes you play. E.g. you could have a short envelope attack when you play single notes, and a long attack when you play chords.
Step Sequencer	This allows you to apply modulation according to the settings for each step in the Step Sequencer. On the sub-menu you can chose to apply modulation according to Gate/Note/Curve 1 and 2/Gate Length/Step Duration settings for each step. In addition you have Start and End Trig, which sends a gate trigger at the start and end of the Step sequence, respectively.
CV Inputs 1-4	These are CV inputs on the back panel which facilitates the use of external modulation sources, (e.g. the Matrix) in Thor. If connected you can freely assign the external CV to any modulation destination in Thor.
Audio Inputs 1-4	These are Audio inputs on the back panel which allows you to connect external audio signals and process these using Thor parameters, or use them as modulation sources. See "About using the Audio inputs".

Modulation Destinations - Voice section

The following parameters can be used as Voice section modulation Destinations:

Parameter	Description
Osc 1	There are four modulation destinations available on the Osc 1 sub-menu: ▪ **Pitch - this will affect oscillator pitch (frequency).** ▪ **FM - this will frequency modulate the oscillator.** The difference between Pitch and FM is that if a high frequency audio signal (i.e. an oscillator or an external audio signal) is the source, FM will not alter the basic pitch of the source, only the timbre. If Pitch is used both the pitch and the timbre will be affected. ▪ **There is also a modifier parameter, which differs depending on what oscillator type is selected. See "The Oscillator section" for details.** ▪ **Osc 2 AM Amount - this will control AM modulation amount from Osc 2. See "About Amplitude Modulation (AM)".**
Osc 2/ Osc 3	Oscillator slots 2 and 3 have the same Destination parameters as Osc 1, except that there is no AM.
Filter 1/ Filter 2	The following destinations are available on the Filter 1 and 2 sub-menus: ▪ **Audio In - this allows you to connect an audio source (e.g. an oscillator or an external audio signal) to the filter input.** ▪ **Frequency - this controls the filter frequency.** ▪ **Frequency (FM) - this will apply filter frequency modulation.** The difference between Frequency and FM is that if a high frequency audio signal (i.e. an oscillator or an external audio signal) is the source, FM will not alter the basic frequency of the source, only the timbre. If Frequency is used both the pitch and the timbre will be affected. ▪ **Resonance - this controls filter resonance.** ▪ **Drive - this controls the filter's Drive parameter.** ▪ **Gender - this controls the Gender parameter (Formant filter only).** ▪ **LPHPMix - this controls the LP/HP parameter (State Variable filter only).**
Shaper Drive	This will control the Shaper Drive parameter.
Amp	The Amp section has three destinations on the sub-menu: ▪ **Input - this allows you to connect a source (e.g. an oscillator or an external audio signal) to the Amp input.** ▪ **Gain - this controls the Amp Gain.** ▪ **Pan - this controls the Pan for each voice. Modulating this parameter with for example LFO 1 means that the Pan position will modulate differently for each voice you play.**
Mix	The Mixer has three destinations on the sub-menu: ▪ **Osc 1+2 Level - this controls the level of both oscillator 1 and 2.** ▪ **Osc 1:2 Balance - you can modulate the level balance between oscillator 1 and 2, e.g. to sweep from one oscillator to the other.** ▪ **Osc 3 Level - this controls the level of oscillator 3.**

Parameter	Description
Filter Envelope	The Filter Envelope mod destinations are as follows: ▪ **Gate - this is the gate input of the envelope. A gate signal applied to this input will trigger the envelope.** ▪ **Attack - this controls the Attack of the envelope.** ▪ **Decay - this controls the Decay of the envelope.** ▪ **Release - this controls the Release parameter.**
Amp Envelope	This has the same destination parameters as the Filter Envelope.
Mod Envelope	This has the same destination parameters as the Filter Envelope.
LFO 1 Rate	This allows you to control the LFO 1 Rate parameter.

Modulation Destinations - Global

The following Global modulation destinations are available:

Parameter	Description
Portamento	This allows you to control the Portamento time parameter.
LFO 2 Rate	This allows you to control the LFO 2 Rate parameter.
Global Envelope	The Global Envelope mod destinations are as follows: ▪ **Gate - this is the gate input of the envelope. A gate signal applied to this input will trigger the envelope.** ▪ **Attack - this controls the attack time of the envelope.** ▪ **Decay - this controls the decay time of the envelope.** ▪ **Release - this controls the release time of the envelope.**
Filter 3	The following destinations are available on the Filter 3 sub-menu: ▪ **Left/Right In - this allows you to connect a source to the filter input.** ▪ **Frequency - this controls the filter frequency.** ▪ **Frequency (FM) - this will apply filter frequency modulation.** ▪ **Resonance - this controls filter resonance.** ▪ **Drive - this controls the filter's Drive parameter.** ▪ **Gender - this controls the Gender parameter (Formant filter only).** ▪ **LPHPMix - this controls the LP/HP parameter (State Variable filter only).**
Chorus	The Chorus effect has the following destinations: ▪ **DryWet balance** ▪ **Delay (time)** ▪ **ModRate** ▪ **ModAmount** ▪ **Feedback**

Parameter	Description
Delay	The Delay effect has the following destinations: ▪ **DryWet balance** ▪ **Time** ▪ **ModRate** ▪ **ModAmount** ▪ **Feedback**
Step Sequencer	This allows you to control various parameters belonging to the Step Sequencer. ▪ **Trig - this enables control over the Step Sequencer Run on/off status.** ▪ **Rate - this enables control over the Step Sequencer Rate.** ▪ **Transpose - this enables control over the Step Sequencer base pitch. E.g. if you apply MIDI Note as a source to this parameter you can transpose the sequence by playing notes.** ▪ **Velocity - this enables control over the Step Sequencer Velocity response.** ▪ **Gate Length - this enables control over the Step Sequencer Gate Length response.**
CV Output 1-4	This will allow you to send signals to the CV outputs on the back of the device. Note that you can send CV signals to audio outputs and vice versa.
Audio Output 1-4	This will allow you to send signals to the audio outputs on the back of the device. Note that you can send CV signals to audio outputs and vice versa.

Scale parameters

The available scale parameters are the same as the Source parameters.

About using the Audio inputs

The 4 Audio inputs on the back panel can be used to connect external audio sources and process them with Thor's parameters.

Note that when routing audio to the Voice section, the following things apply:

- **There are only mono inputs in the Voice section.**
- **You need to send a gate trigger for the audio signal to be heard. This can be done in three ways; by playing notes, via notes played by the Step sequencer or from CV gate signals.**

▶ **Routing audio to Global destinations does not require a gate trigger and stereo inputs are provided.**

▶ **The external audio sources can also be used purely for modulation, e.g. you can modulate an oscillators pitch with an audio signal.**
This way you can use the audio input source to modulate any available destinations.

Step Sequencer



Thor's Step Sequencer is a further development of the step sequencers which were often present in vintage analog modular systems. It can be used for programming arpeggios or short melody sequences. Alternatively, it can be used purely as a modulation source.

You can have up to 16 steps, and each step can be programmed with various values such as Note pitch, Velocity, Step Duration etc.

Basic operation

The main parameters and functions are as follows:

- **The row of 16 buttons are used to program each step's on or off status.**
  A lit button means that the step is active, and a dark button means that the step will be a rest (silent).
- **Each step button has a knob above it, which is used to set values for the corresponding step.**
- **The Edit knob determines what value you set with the step knobs.**
  The available Edit values are Note (pitch), Velocity, Gate length, Step duration and Curve 1 and 2.
- **The Run button starts/stops the step sequencer.**

What exactly happens when you press Run depends on the Run mode - see below.

Setting the Run mode



The Run mode is set with the lever beside the Run button. The set mode governs how the step sequencer is played back when you press Run. The options are as follows:

- **Repeat mode - this will repeat the sequence continuously.**
  Click the Run button again or use the Transport to stop.
- **1 Shot mode - this will play the sequence once then stop.**
- **Step mode - the Run button steps the sequencer forward one step at a time.**
- **Off - the step sequencer is inactive.**

Setting the direction



The Direction parameter is used to set the direction of the step sequence. The following options are available:

- **Forward - plays the sequence from the first step to the last.**
- **Reverse - plays the sequence from the last step to the first.**
- **Pendulum 1 - plays the sequence from the first step to the last, then from the last step to the first.**
  I.e. the last and first step is played twice when the sequencer reverses direction.
- **Pendulum 2 - plays the sequence from the first step to the last, then from the second last step to the first, i.e. without repeating the last/first step when reversing direction.**
- **Random - plays the steps in a random order.**

Programming step note pitch

To program step note pitch, you proceed as follows:

1. **Make sure that the Step Seq Trigger button is activated in the Controller panel.**



2. **Set the Run mode to "Repeat".**
   You don't have to use Repeat mode but it makes it easier to follow the following steps.
3. **Start the step sequencer by pressing the Run button.**
   You should now hear a sequence of repeated notes, each with the same pitch (C3). The current step is indicated by a yellow LED above the step buttons.
4. **Make sure that the Edit knob is set to Note.**



5. **Turn one of the step knobs above one of the steps.**
   A tooltip shows you what current note pitch the knob is set to, and when the sequencer repeats you should be able to hear the change in pitch for that step. Turn clockwise to raise the pitch in semitone increments. Turn counter-clockwise to lower the pitch.



- **You can set the knob's note range by using the Octave lever to the left of the step buttons.**
  Available note ranges are 2 Octaves (i.e. one octave up and down from the middle knob position (C3), 4 Octaves (i.e. two octaves up and down from the middle position (C3), or Full (-C2 to G8).
- **Note that the octave range can be set independently for each step. Each step memorizes the current octave range when the pitch is set for that step, and will keep this octave range until you change the pitch for the step with a different octave range setting.**
- **You can either program steps "on the fly" (with the Step sequencer running) or step by step (Step mode).**
  In Step mode, you press Run to forward the step number one position so you can set step parameters for one step at a time.

By using this general method you can continue to enter note pitch for other steps.

Inserting rests

To make step sequences more rhythmically interesting, you can program rests for steps.

- **This is simply done by pressing one or several step buttons so they go dark.**
  Dark steps will be rests.
- **Note that the Step Duration value still "counts" for rests.**

Setting the number of steps

- **You can set how many steps a sequence should have before starting over using the Steps knob at the far right on the panel.**
  Up to 16 steps can be used. The lit LEDs above each step button show the number of steps currently used. You can also change number of steps by clicking on a LED directly - the sequencer will then stop/start over at the selected step.



Setting Rate

The Rate knob determines the rate of the step sequence.

- **You can either use "free running" rates (i.e. not synced to main sequencer tempo) or synced tempo.**
  This is set with the Sync button on/off status. If Sync is active you can set the tempo in various beat resolutions.

Setting other values for steps

For each step you can also program other parameters with the step value knobs apart from note pitch. You use the Edit knob to set one the following:

- **Velocity - if this is selected as the Edit mode you can set a velocity value for each step.**
  Default value is 100, range is 0-127.
- **Gate Length - if this is selected as the Edit mode you can set a Gate Length value for each step.**
  Default is 75%. Gate Length determines the length of the note played for that step.
- **Step Duration - if this is selected as the Edit mode you can set a Step duration value for each step.**
  This parameter determines the total length of the step, which is a factor related to the sequencer rate. Range is 1/4 to 4. E.g. if Rate is 1/16, "1" means a 1/16-note will be played, a "4" means a 1/4-note will be played, and so on.
- **The Curves 1 and 2 allow you to set values for each step that can be sent to control parameters of your choice.**
  This is done in the Modulation bus routing section, where these two independent Curves are selectable as Source controllers.
- **You can compare these curves to the Curve CV output of the Matrix - they simply represent a series of values which can be applied to anything.**

Step Pattern functions

You will find some specific Step pattern functions on the Edit menu (and on the device context menu). These are as follows:

Function	Description
Randomize Sequencer Pattern	The Randomize Pattern function creates random patterns. The function only randomizes the selected Edit value (e.g. if set to Note, only the note pitch values are randomized, not velocity, gate length etc.).
Shift Pattern L/R	The Shift Pattern functions move the pattern one step to the left or right. All parameters (rests, note pitch, velocity etc.) are shifted one step.

Connections

The following Audio and CV connectors can be found at the back of Thor:

Sequencer Control Inputs

The Sequencer Control CV and Gate inputs allow you to play Thor from another CV/Gate device (e.g. a Matrix or the RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Modulation Inputs

- **The Rotary control voltage (CV) inputs (with associated voltage trim pots), can modulate the two virtual Rotary controls.**
  Thus, any parameter(s) assigned to a Rotary control can be modulated by CV.
- **The Filter 1x allows for CV control of the Filter 1 frequency.**
  If the Formant filter is used this is the "X" parameter - see "Formant filter".
- **The four CV Inputs can receive CV from external sources that will be available as Sources in the Modulation bus.**

Modulation Outputs

Here you can find CV outputs from the Global Envelope and LFO 2, as well as the 4 user assignable CV outputs.

Audio Inputs

The Audio inputs can be used to connect audio outputs from other Reason devices. When connected, you can route the Audio inputs as a Modulation source to for example one of the filters and process the external signal. See "About using the Audio inputs".

Audio Outputs

Thor has 4 outputs:

- **1 Left (Mono)/2 Right - these are the main stereo outputs.**
- **2 additional outputs (3 and 4), which can be assigned in the Modulation section.**



Chapter 48
Alligator
Triple Filtered Gate



Introduction



The Alligator is a three-channel gate effect with a built-in pattern player. It can chop up audio in a wide variety of ways and process it with three parallel filters, distortions, a phaser and a delay. The Alligator can be used for processing sustaining sounds like strings and pads, adding rhythms and accents. It can also be used on loops and other rhythmic material, changing the feel and sound. Applied to a whole mix, the Alligator can be a powerful remix tool, totally reshaping the material.

About the Patch format


Alligator patches have the file extension ".gator". The Factory Sound Bank contains a number of Alligator effect patches for use as is or as starting points for further tweaking. Patches are loaded and saved using the standard procedures.

- **Don't forget that you can also save Alligator settings as part of a Combinator patch. Combining an instrument device with an Alligator is a quick way to create gated, rhythmic pads.**

Overview and signal flow

The Alligator may seem overwhelming at first - it's got quite a few knobs and buttons on its front panel. However, once you've understood the basic signal flow it's actually pretty straightforward. Read through the description below and get familiar with the basics - it will help you a lot when working with the Alligator.

Here is a simplified diagram of how the Alligator works:




You normally connect the Alligator as an insert effect, so that all of the audio signal passes through the effect device. The incoming signal is split into three, parallel channels. For each channel, there is a separate gate - when that gate is open the signal passes through and when it's closed, the channel is silent. The gates can be opened in four ways:

- **By the built-in patterns.**
  There are 64 patterns, each with three "tracks" independently controlling the three gates.
- **By clicking the Manual Gate buttons on the front panel.**
- **By sending the MIDI notes F#1, G#1 and A#1 from a keyboard to the Alligator track in the sequencer.**
  This way you can play the Alligator live, with velocity control over the gate levels, see "Playing the Alligator live".
- **By connecting CV cables to the Gate inputs on the back of the Alligator and sending Gate signals, e.g. from a Matrix or Redrum.**


When a gate is open, the signal passes through a filter. The three channels have different types of filters: High Pass, Band Pass and Low Pass, respectively. This means the channels will have different sound characteristics.

Finally, the three channels are mixed together again and sent to the main output.

That's the signal flow in its most basic form. Looking at the front panel, you can see the signal split and the three channels with their gates and filters:



However, as you can see, there are quite a few other settings as well. Let's take a closer look at one of the channels (the band pass filter, in this example):



In this, more detailed diagram, we see that the gate isn't a simple on/off switch - there is actually an amplitude envelope controlling the volume of the channel. When the gate is opened, the envelope is triggered and the sound is let through according to the envelope settings. You can use the amp envelope to soften the attack, to make the notes shorter and more snappy, etc. The gate also triggers a filter envelope, so that each note can get an articulated filter contour. The filter can also be modulated by a global LFO.

Next in the channel are FX settings: a distortion unit, a swirling phaser and a send to a built-in delay unit. Since these settings are independent for the three channels, they can give you a lot of variations.

Finally, there are Pan and Volume controls. Even a function as basic as stereo panning can make for really interesting, spatial effects - especially since you can pan the three channels, the dry signal and the delay independently!

Parameters

Common effect device parameters

Like all effect devices, Alligator features a Bypass/On/Off switch and an input level meter. These are described in "Common effect device features".

Pattern section



Pattern On

When this is on, the built-in pattern player will run in sync with the song tempo, controlling the three gates. Turn it off if you want to control the gates manually or with MIDI/CV.

Shuffle

Shuffle on the Alligator works in the same way as shuffle on the Redrum and Matrix devices. It will delay every second 1/16th note in the playing pattern according to the Global Shuffle Amount setting in the ReGroove mixer, creating a shuffle or swing feel.

Note that Shuffle will work best when Resolution is set to 1/16.

Pattern selector

This is where you select which one of the 64 built-in patterns should play back, controlling the gates. There is a guide to the patterns in "The built-in patterns".


Resolution

When this is set to 1/16 (default) the built-in patterns will be based on 1/16th notes. Changing the Resolution setting allows you to scale the patterns, making them play back faster or slower in relation to the song tempo.

Shift

This will offset the pattern relative to the song playback, moving it "sideways". The range is ±16 steps, with the step length determined by the Resolution parameter. For example, if you set Shift to -1 with Resolution at 1/16, the pattern will be moved one sixteenth note to the left. This means the pattern will play one sixteenth note "early" (the start of the pattern will occur a sixteenth note before the downbeat in the song).

Gate and Amp Envelope



Manual Gate Trig buttons

Clicking one of the Manual Trig buttons will open the corresponding gate. It will remain open for as long as you keep the mouse button pressed. However, the sound may fade out slowly or quickly depending on the amplitude envelope settings.

While the gate is held open manually, it won't be affected by the built-in pattern. This means you can use the buttons to override the pattern, holding a channel open (if Amp Env Decay is long) or muting it (if Amp Env Decay is short).

Gate indicators

These light up when the gates are open.

Amp Env Attack



When a gate is opened, the Amplitude Envelope is triggered. This controls the input level to the corresponding filter. Amp Env Attack sets how long it takes for the level to reach its maximum after the gate opens. Normally, this is kept at a low value for quick, snappy attacks. Raising the Attack parameter will make the notes fade in, blurring the patterns.

Amp Env Decay



Directly after the attack phase, the input level will fade down to zero again. The time this takes is set with the Amp Env Decay parameter. Setting the Decay knob to its maximum value will set the decay time to infinity, which will result in a maximum "sustain" level. Lowering the Decay setting will make the pattern notes shorter.

Amp Env Release



This determines how quickly the sound fades out after the gate is closed. If you raise this setting, the sound will never fade out completely between gates, and the pattern will become blurred and more pad-like.

Filters and Modulation



The three channels have identical settings, even though their filters are of different types. Below, all descriptions apply to all three channels, if not explicitly stated.

Filter On button

When this is on, the channel's signal passes through the filter. Turning this off bypasses the filter. Note though that the Gate, Amp Envelope, effects and other settings are still active.

LFO Amount

Determines how the filter frequency should be affected by the global LFO (see below). This is a bipolar control, allowing for positive or negative modulation of the filter frequency.

Frequency

▶ **For a general introduction to different filter types, see "The Filter Section" in the Subtractor chapter.**

- **For the high pass filter, this is the cutoff frequency.**
  Frequencies below this will be removed from the signal. Turning this parameter up will gradually remove more and more of the signal, leaving only the highest frequencies.
- **For the band pass filter, this is the center frequency.**
  Lower and higher frequencies will be removed from the signal.
- **For the low pass filter, this is the cutoff frequency.**
  Frequencies above this will be removed from the signal. Turning this parameter down will gradually remove more and more of the signal, leaving only the lowest bass frequencies.

Resonance

The filter resonance emphasizes the frequencies around the set filter frequency. Turning this up will make the filter sound more pronounced and ringing.

Envelope Amount

This determines how the filter frequency is affected by the Filter Envelope (see below). This is a bipolar control, allowing for positive or negative modulation of the filter frequency.

LFO Waveform



The global LFO offers nine different waveforms, ranging from sine, triangle and square to random and various stepped forms.

LFO Frequency



Sets the rate of the LFO, used for continuous modulation of the filters. If LFO Sync is activated, the LFO Frequency is expressed as a note value relative to the song tempo; if not, the LFO Frequency is free.

LFO Sync



Turn this on to synchronize the LFO to the song tempo.

Filter Env Attack



Like the amplitude envelope, the filter envelope is triggered by the gates. There are in fact three individual envelopes, one for each filter, but they share the same controls. For the filter envelopes to have any effect on the sound, you need to set the Env Amount parameters to negative or positive values for one or more filter channels.

The Filter Env Attack determines how quickly the filter envelope rises to its maximum value when the gate is opened.

Filter Env Decay



Directly after the attack phase, the filter envelope signal will fall to zero again. The time this takes is set with the Filter Env Decay parameter.

Filter Env Release



This determines how quickly the filter envelope signal falls to zero after the gate is closed. To fully hear the effect of this parameter, you need to raise the Amp Env Release parameter - otherwise the level will drop to zero directly when the gate closes and you won't hear any filter changes.

Effects



The three channels have identical effect parameters. Distortion and phaser effects are separate for the three channels (although the phasers have common controls). The delay is a global effect, working much like a send effect in a mixer.

Drive Amount



Sets the amount of distortion for the channel.

Phaser Amount



Sets the amount of phaser effect for the channel.

Delay Amount



This works like an effect send, determining how much of the signal should be sent to the built-in delay effect. The send is post-volume: If you lower the volume for a channel, the signal sent to the delay will be lowered as well.

Delay Time



This is a standard delay unit with a maximum delay time of 2/4 (when synced to the song tempo) or 1 second.

Delay Sync



Turn this on to set the delay time in musical values relative to the song tempo.

Delay Feedback



This determines the number of delay repeats.

Delay Pan



Sets the stereo panning of the delay repeats.

Phaser Rate



The rate of the phaser sweep.

Phaser Feedback



This is similar to the resonance control on a filter. Raise the feedback to get a more pronounced, “singing” phaser effect.

Mix controls



These parameters determine the signal mix being sent to the main outputs on the back. There are also individual outputs for the three gate/filter channels. If you connect these outputs, the corresponding channel signals will be removed from the main mix, leaving only the delay return signal and the dry signal.

Channel Pan



Sets the stereo pan/balance of the channel.

Channel Volume



The volume of the channel.

Dry Ducking



The Ducking parameter will apply the Amp Envelope to the dry signal - but inverted. This means that whenever the Amp Envelope is “high”, the dry signal will be lowered in volume or “ducked”. The result is a sort of mirror to the sound from the three gated channels.

! Note that this is only audible if the Dry Volume has been raised.

Dry Pan



Sets the stereo pan/balance of the dry, unprocessed signal.

Dry Volume



Sets the volume of the dry, unprocessed signal. Mixing in a bit of the dry sound is useful for subtler processing, e.g. when you just want to animate a pad rather than chop it up.

Master Volume



This is the master volume of the mixed signals. The signals from the separate channel outputs on the back won't be affected by this.

Audio connections




Main Inputs and Outputs

The Alligator is normally connected as a stereo in-stereo out effect. Should you connect a mono input signal, the output will still be in stereo due to the pan controls.

Separate Outputs

These output the signals from the individual gate/filter channels. Connecting one of these outputs will remove the corresponding channel signal from the main output. The separate output signals are taken after the Channel Volume controls but are unaffected by the Master Volume.

CV connections



Gate inputs

These are used for controlling the gates from other devices, using CV. When a gate input receives a CV value of 7 or higher, the gate will be opened. Higher values result in higher input level for the gate channel (i.e. the gates are velocity sensitive).

- **If you select an Alligator device and create a Matrix Pattern Sequencer, its gate output will be auto-routed to the first available Gate input. Also, the Matrix Curve CV output will be auto-routed to the corresponding CV Freq input on the Alligator.**
  You can create up to three Matrix Pattern Sequencers with the Alligator selected and the Matrix devices will be auto-routed to separate Gate and CV Freq inputs on the Alligator.

! **Note: If you want the gates to be controlled by CV only, you need to turn off the Pattern player on the front panel. Otherwise, the gate sources will be combined.**

CV Modulation inputs

These jacks allow you to modulate the filter frequencies of the three filters, as well as the global LFO rate.


Gate Outputs

The three Gate outputs simply send out the current Gate values, regardless of whether these are controlled by the built-in pattern player, the buttons on the front panel, MIDI or CV. You can use these to trigger other sounds and effects in time with the gates.

LFO CV Out

This is the output of the built-in LFO, for modulating parameters in other devices.

The built-in patterns



This is an overview of the 64 built-in patterns. The black dots signify open gates with gate 1 (high pass filter) at the top. Most patterns are two bars long, but some are shorter. All patterns will repeat continuously when the Pattern function is on.

Methods and Tips

Playing the Alligator live

The three gates in the Alligator can be triggered by the MIDI notes F#1, G#1 and A#1, with the lowest note controlling the low pass filter channel and so on. This can be very useful when playing live:

1. **Create and connect an Alligator as an insert effect for the audio material you want to process.**
   This could be a recorded pad, a loop or even the full mix.
2. **Make sure the Alligator is selected and select "Create Track for Alligator" from the Edit menu.**
   This creates a track with a note lane for the Alligator.

▶ **If you like, turn off the Pattern section on the Alligator.**

3. **Start playback and use the keys F#1, G#1 and A#1 to play the gates.**
   Remember that the gates are velocity sensitive and that the Amp Envelope settings affect the gated sound.

Playing the gates from Matrix patterns

While the 64 built-in patterns are rather versatile, sometimes you might want to create your very own patterns. The easiest way to achieve this is to connect Matrix Pattern Sequencers:

1. **Select the Alligator device.**
2. **Create a Matrix from the Create menu or Device palette.**
   It is automatically connected to one of the Gate inputs on the backside. The Curve CV output on the Matrix is automatically connected to the corresponding CV Freq input on the Alligator.
3. **Repeat these two steps twice, to create two more Matrix devices.**
   Note that you need to select the Alligator for the Matrix to be auto-routed to the Gate and CV Freq inputs. Now you have three Matrix devices, one for each gate/channel.
4. **Turn off the Pattern player in the Alligator.**
5. **Use the Gate section in the Matrix display to program custom gate patterns.**
   The Curve can be used for controlling the Filter Frequency of the corresponding frequency band in the Alligator.

▶ **Another interesting trick is to load a rhythmic loop into a Dr Octo Rex device and connect its Slice Gate Output to a Gate input on an Alligator. This makes the slices in the REX loop trigger the gate.**

Controlling other sounds and effects

The gate outputs on the Alligator back panel allow you to control other stuff with the built-in Alligator patterns. Here's an example:

1. **Create an instrument with a sustaining sound, such as a pad.**
2. **Turn on loop mode in the main sequencer and record some chords.**
3. **Create an Alligator and select a suitable pattern.**
   You might want to tweak the sound as well, change the filter settings, adjust fx and pan, etc.

With some tweaking, the filtered pattern can sound a bit like a drum beat or percussion loop. Then it can be nice to add some punch and bottom to the Low Pass channel, making it feel more like a kick drum or bass line:

4. **Create a Kong Drum Designer.**
5. **Load a punchy bass drum sound into Pad 1.**
6. **Flip the rack around and route a CV cable from Gate 3 Out on the Alligator to the Gate input for Kong's pad 1.**
   Now the bass drum sound is triggered along with Gate 3, played by the Alligator's pattern player.
7. **Adjust the Kong level to taste.**
8. **If you like, add other sounds for Gate 1 and 2 in the same way.**

Chapter 49
Audiomatic
Retro Transformer



Introduction



The Audiomatic Retro Transformer Rack Extension effect device was designed mainly with focus on spicing up dull mixes. The Audiomatic Retro Transformer is inspired by the Hipstamatic picture editing app - but designed for audio.

By selecting one of the 16 presets you can instantly change the character of your sound - almost like applying a "magic skin".

At moderate levels the Audiomatic Retro Transformer can breathe life into your individual tracks, as well as into your final mixes, by adding a subtle "shimmer" to your sound. Used to its extremes, it can provide hard-edge and aggressive sounds as well. You can easily control the mix between dry and processed signal with the Dry/Wet knob on the front panel.

In Reason the Audiomatic Retro Transformer Rack Extension device can be found on the Effects palette.

Using Audiomatic Retro Transformer

The Audiomatic Retro Transformer is designed to be used mainly as an insert effect, on individual tracks as well as in the Master Inserts section. Another very nice application is to use the Audiomatic Retro Transformer as an insert effect in Parallel Channels in the Reason Mixer. Then, you can sculpt the effect sound even further using the channel EQ and Compressor, for example. Refer to "Parallel Channels" for information about working with Parallel Channels.

The front panel layout is very simple and straight-forward: the device features 16 Preset buttons, a Transform knob, an input Gain knob and a Dry/Wet knob.

Gain



- **Set the input level Gain.**
  Range: - INF to + 12 dB.

! **Use the Gain control cautiously when using Audiomatic Retro Transformer on the whole mix. It is easy to get unwanted distortion in some of the Presets, e.g. Tape, when the input signal is loud.**

- **Don't be afraid to push the gain up - especially in presets that feature built-in compression! High input Gain settings can also render very interesting distorted sonic results. You can always compensate the level by lowering the Volume, see "Volume".**

The Presets



The 16 Preset buttons are arranged in a four by four matrix. The upper row of presets contains subtle effects, the second row a little less subtle and so on all the way down to the fourth row, which contains the most far out effects.

The display shows a picture which reflects the selected effect Preset.

The following Presets are available:

Tape

This simulates the character of an analog tape recorder.

Hi-Fi

This simulates the classic Loudness compensation function, which was very popular in numerous consumer class hi-fi systems in the 70s and 80s.

Bright

This preset adds brightness to the sound, and removes bass.

Bottom

This preset tightens up and enhances the low frequencies in the sound.

Spread

This preset is a spatial effect, which spreads the stereo width of the sound and also changes the frequency characteristics.

Radio

This simulates a small transistor radio.

VHS

This simulates sound recorded with a VHS camera.

Vinyl

This simulates the background sound and noise from a somewhat scratchy vinyl record.

MP3

This simulates the sound of a poorly encoded/decoded MP3 file.

Psyche

A psychedelic sound experience. “Turn on, tune in, drop out”, sort of.

Cracked

The effect of a broken speaker with lots of distortion.

Gadget

A hollow “robotic” type of effect.

Circuit

A “circuit-bending” type of effect with bit-crushing on top.

Wash

A washing machine on sound check at an open air venue?

PVC

A pretty far out sci-fi preset.

Eerie


A very nice and scary waterphone effect.

Transform



- **Transform the effect with the Transform knob.**
  The knob usually controls a combination of different (hidden) parameters in each of the Presets. This makes it behave more like a “morph” control rather than an “amount” control.

Dry/Wet



- **Set the balance between the dry input signal and the transformed (effect) signal with the Dry/Wet knob.**
- **If you want only subtle effects, turn the Dry/Wet knob more towards the Dry position. For more prominent effects, turn the Dry/Wet knob towards the Wet position.**

Volume



- ▶ **Set the output volume with the Volume knob.**
  Range: - INF to + 12 dB.
- ▶ **Use the Volume knob in combination with the "Gain" knob, to compensate for high input Gain settings.**

Connections



CV Modulation In

Transform

A bipolar CV signal patched here modulates the Transform parameter (see "Transform"). A positive signal increases the Transform parameter amount and a negative signal decreases it.

- ▶ **Patch an LFO signal here and use with the PVC Preset, for a nice sweeping sound!**
- ! **Note that the default Transform parameter range can not be exceeded.**

Dry-Wet

A bipolar CV signal patched here modulates the Dry/Wet front panel control (see "Dry/Wet"). Zero modulation means that the current Dry/Wet knob setting is valid.

Input L&R

- ▶ **Patch the audio signals you want to process here.**
  If your signal is in mono, connect only to the L (left) input.


Output L&R

These are the stereo audio outputs.

- ▪ **The signal routing (stereo/mono/dual mono) is Preset dependent.**

Chapter 50
BV512 Vocoder

Introduction



The BV512 is an advanced vocoder device with a variable number of filter bands. It also has a unique 1024-point FFT vocoding mode (equivalent of 512-band vocoding) for very precise and high quality vocoded speech. By connecting the BV512 to two instrument devices, you can produce anything from vocoded speech, singing or drums to weird special effects.

Even if you have worked with a vocoder before, please read the following section. Knowing the basic terms and processes will make it much easier to get started with the BV512!

How does a vocoder work?

Carrier and modulator

A vocoder accepts two different input signals, a "carrier" and a "modulator". It analyzes the modulator signal, applies its frequency characteristics to the carrier signal and outputs the resulting "modulated" carrier signal.

In the most typical case, the carrier signal is a string or pad sound and the modulator signal is speech or vocals - the result will be a talking or singing synth sound. The modulator could also be drums or percussion (for rhythmically modulated sounds and effects) or any sound with changing frequency content.

Filter bands

Technically, a vocoder works in the following way: The modulator signal is divided into a number of frequency bands by means of bandpass filters (called the "modulator filters" or "analyzing filters"). The signal in each of these bands is sent to a separate envelope follower (which continuously analyzes the level of the signal). The carrier signal is sent through the same number of bandpass filters (the "carrier filters"), with the same frequency ranges as the filters for the modulator signal. The gain of each bandpass filter is controlled by the level from the corresponding envelope follower, and the filtered signals are combined and sent to the vocoder's output.

In this way, the carrier is filtered to have roughly the same frequency characteristics as the modulator. If the modulator signal has a lot of energy in one of the frequency bands, the gain of the corresponding filter band for the carrier signal will be high as well, emphasizing those frequencies in the output signal. If there is no signal at all within a frequency band in the modulator signal, the corresponding band in the output signal will be silent (as the gain will be zero for that filter).

There are several factors determining the quality of the vocoder sound, but the most important is the number of filter bands. The larger the number of filter bands, the closer will the output signal follow the modulator's frequency characteristics. The BV512 offers 4, 8, 16 or 32-band vocoding.

- **Even if a high number of bands will make the sound more precise and intelligible, this isn't always what's desired! Vocoding with a lower number of bands can give results that sound different, fit better in a musical context, etc.**

FFT vocoding

The BV512 has an additional FFT mode, in which the vocoding process isn't based on bandpass filters as described above. Instead, FFT (Fast Fourier Transform) analysis and processing is used. This equals 512 "conventional" frequency bands and results in a very precise and detailed vocoder sound. Note:

- **The FFT mode is best suited for vocoding speech or vocals, giving crystal clear and highly intelligible results.**
  It is not so well suited for vocoding drums and percussion, since the FFT process is inherently "slower" than the regular filtering and doesn't respond as quickly to transients, and also there will be a slight delay added to the signal (in the region of 20ms). A workaround solution to this would be to move the modulator signal slightly ahead to compensate for the delay.
- **Where the conventional filter bands are distributed logarithmically (i.e. the same number of filter bands per octave), the 512 bands in the FFT mode are distributed linearly.**
  This means a lot of the bands will be in the high frequency range - this is one of the reasons for the clear sound but it is also something to keep in mind when making settings for the vocoder in FFT mode.

Setting up for basic vocoding

This tutorial describes how to connect and use a typical vocoder setup. We assume here that you have a MIDI keyboard connected. For details on the parameters, see "BV512 parameters".

Vocoding vocals in real-time

The most common usage for a vocoder is probably the typical "singing" or "talking synth" sound, using vocals or speech as modulator. Since Reason supports live audio input you can sing and play in real time. This is a basic example of how to route your signals:

1. **Create the instrument device you want to use for the carrier signal.**
   This could typically be a synth or a sampler. In this example we choose a Subtractor synthesizer.
2. **Set up the carrier device (Subtractor) for a sustaining, bright sound.**
   It's important to have high frequencies (a lot of harmonics) in the carrier. On the Subtractor, a simple but effective carrier sound would be based on a sawtooth wave, with the filter fairly open. For more about choosing carrier sounds, see "Choosing a carrier sound".
3. **Select the carrier device (Subtractor) and create a BV512 Vocoder.**
   If you flip the rack around you will see that the Vocoder is automatically routed as an insert effect for the carrier device (using the Carrier Input jacks).




4. **Connect a microphone to your audio interface and manually patch the appropriate Audio in jack on the Reason Hardware Interface to the Modulator Input on the BV512.**
5. **Make sure the Master Keyboard Input is set to the carrier device track.**
6. **Also make sure the "Dry/Wet" knob on the BV512 Vocoder is turned to "Wet" (fully clockwise).**


7. **Play some notes or chords on your MIDI keyboard and sing through the microphone.**
   The result will be the classic vocoded vocal sound.



8. **Try the different filter band options and note the difference in sound.**



9. **You can also adjust the vocoder sound by clicking and dragging the bars in the lower display.**
   Each bar corresponds to a frequency band, with low frequencies to the left and high frequencies to the right. You adjust the level of a band by dragging its bar up or down. Clicking and dragging across the bars allow you to change the levels of several bars, much like drawing an eq curve.



The upper display shows the spectrum of the modulator signal, for display only.

- **To reset a band to ±0 dB, press [Ctrl](Win) or [Cmd](Mac) and click on it.**
  You can also reset all bands to zero by bringing up the context menu for the Vocoder device and selecting "Reset Band Levels".

10. **If the vocoder sound is "muddy" or indistinct, try raising the "HF Emph" knob on the Vocoder.**
    This parameter (High Frequency Emphasis) boosts the high frequencies in the carrier signal.
11. **Try out the other parameters if you like.**
    See "BV512 parameters" for details.

Recording the vocoded audio

If you want to record the vocoded audio in the example above on an audio track in the sequencer, you can do like this:

1. **Create an audio track.**
2. **Click the "Rec Source" button on the Vocoder Mix Channel device in the rack.**
3. **Select the Vocoder Mix Channel as input in the Audio Input selector on the audio track in the sequencer.**
4. **Select the carrier device (Subtractor) track in the sequencer and deselect its "Record Enable" button.**
5. **Click the "Record Enable" button on the audio track in the sequencer (but don't select the audio track!).**
6. **Click the "Rec" button on the Transport Panel to start recording.**
   The vocoded audio is now recorded on the audio track as you sing through the microphone and play the keyboard.


Refer to "Recording audio from Mix Channel outputs" for more details on how to record Mix Channel outputs.

Vocoding an existing audio track

If you want to apply vocoding to an existing audio track, but also keep the original sound, a flexible way is to do like this:

1. **Create the carrier device (a Subtractor, for example).**
2. **Select the carrier device and create a BV512 vocoder.**
3. **Patch a cable from the left Insert FX "To Device" connector of the audio track device to the Modulator Input on the BV512.**
4. **Set Master Keyboard Input to the carrier track.**
5. **Click "Play" in the sequencer and play some notes or chords on your MIDI keyboard.**
   The result will be the classic vocoded vocal sound.

- If you don't want the original sound of the audio track to sound, click the Mute button on the channel strip in the Main Mixer (or lower the Level Fader to silence).



6. **At this point you may want to record the notes or chords you play for the carrier device.**
   As Master Keyboard Input is already set to the carrier device track, all you need to do is start recording and play along.

Using the BV512 as an equalizer


The BV512 has a unique equalizer mode, in which the device works purely as an insert effect (the modulator input isn't used). This allows you to use the processing filters of the vocoder as a kind of graphic equalizer.

Setting up

1. **Select the device that you want to process through the BV512.**
2. **Create a BV512 device.**
   It is automatically connected as an insert effect, using the Carrier Input jacks.
3. **Set the switch to the left of the displays to "Equalizer".**



In use



In equalizer mode, you cut or boost frequencies by clicking and dragging in the lower display - just as with a regular graphic equalizer. The usage and results differ depending on which mode is selected:

- **4 - 32 band mode**
  As in vocoder mode, the number of bars in the display conforms to the number of bands selected (4, 8, 16 or 32). With a higher number of bands you get a more detailed control over the frequency response. However:

▶ **In these modes, the equalizer will "color" the sound even if all bands are set to ±0 dB!**
This is due to phase interaction and overlap between the bandpass filters.

Therefore you probably want to use the 4 - 32 band mode for coloring and mutating sounds - not for subtle, "clean" equalizing.

- **FFT (512) mode**
  In FFT (512) mode you still get 32 bars in the display, but the each bar may control several frequency bands (remember that there are 512 bands in FFT mode). Since the frequency bands are distributed linearly in FFT mode, bars to the left in the display control few frequency bands while bars to the right control many frequency bands.

▶ **In FFT (512) mode, setting all bands to ±0 dB is the same as bypassing the equalizer - the sound will not be affected.**
This makes FFT mode suitable for "clean" equalizing, where you want to boost or cut some frequencies without changing the basic sound character.

▶ **However, FFT mode equalizing is not suited for very drastic frequency cuts or boosts, as this may give audio artefacts due to the workings of FFT processing.**
Still: as always, there are no hard and fast rules. Let your ears judge!


▶ **Keep in mind that FFT mode also introduces a slight delay to the signal.**

BV512 parameters

On the front panel of the BV512 Vocoder, you will find the following parameters and displays:

Parameter	Description
Bypass/On/Off switch	In Bypass mode, the carrier signal passes through the device unaffected and the modulator signal is disregarded. In On mode, the device outputs the vocoded or equalized signal. Off mode cuts the output, silencing the device.
Level meters	Show the signal level of the carrier and modulator signals, respectively.
Band switch	Selects the number of filter bands (4, 8, 16 or 32) or FFT (512) mode.
Equalizer/Vocoder switch	Determines whether the BV512 should work as a vocoder or an equalizer. In Equalizer mode, the Modulator input is disregarded.
Modulation level display	The upper display shows the spectrum of the modulator signal.
Frequency band level adjust	The lower display allows you to adjust the level of each filter frequency band, by clicking and dragging the corresponding bar. In vocoder mode this affects the vocoded sound. In equalizer mode, this is where you cut or boost frequencies. To reset a band to ±0 dB, press [Command] (Mac) or [Ctrl] (Win) and click on its bar in the display. To reset all bands, select "Reset Band Levels" from the device context menu. Note: when FFT (512) mode is selected, each of the 32 bars in the display corresponds to several frequency bands, with bars to the right in the display controlling progressively more bands (due to the FFT bands being linearly distributed over the frequency range).
Hold button	Clicking this button "freezes" the current filter settings. While the button is lit, the modulator signal doesn't affect the sound - the carrier signal is filtered with the settings as they were the moment you activated Hold. Click the button again to turn off Hold. Hold is also automatically reset (turned off) when you stop sequencer playback - just like the pitch bend and modulation wheels on synth devices. This function can be controlled via CV or MIDI, for sample and hold-like effects. The Hold button is not available in Equalizer mode.
Attack	This is a global attack time control, affecting all envelope followers (see "Filter bands"). Normally you probably want this set to zero, to make the vocoder react as quick as possible. Raising the Attack time can be useful for "smearing" sounds, creating pads, etc. Not available in Equalizer mode.
Decay	Similarly, this controls the decay time for all envelope followers, i.e. how quick the filter band levels drop. Adjust this according to taste and context. Not available in Equalizer mode.
Shift	Shifts the carrier filters up or down in frequency, drastically changing the character of the vocoded (or equalized) sound. This parameter can be controlled via CV, for phaser-like sweeps and special effects.
HF Emph (High Frequency Emphasis)	Boosts the high frequencies in the carrier signal. This is sometimes desired to get a clearer vocoded sound. The reason is that a carrier signal should theoretically contain roughly equal energies in all frequency ranges for best results - in a typical synth sound the high frequencies are often weaker than the low frequencies. Raising the HF Emph control will rectify this. Not available in Equalizer mode.
Dry/Wet	Determines the balance between modulator sound (dry) and vocoded sound (wet). To get the pure vocoder sound, set this to wet (turned fully right). Not available in Equalizer mode.

Connections



The back panel of the BV512 offers the following connections:

Individual band levels

These are CV outputs and inputs.

- **The upper row outputs CV signals generated by the envelope followers for each frequency band.**
- **The lower row are CV level inputs to the individual bandpass filters through which the signal is processed (the "vocoder filters").**
  Connecting a CV signal to one of the inputs breaks the internal signal path from the corresponding envelope follower (in other words, that frequency band is now controlled by the CV signal you've connected - not by the corresponding frequency band in the modulator signal).
- **If 16 band mode is selected, each output/input pair corresponds to a separate frequency band.**
  In 8 band or 4 band mode, only the 8 first or 4 first output/input pairs are used. In 32 band mode, each output is a mix of two adjacent frequency bands and each input controls two bands. Finally, in FFT (512) mode each output/input pair corresponds to several frequency bands.

There are several interesting uses for the Individual band levels connectors: you can cross-patch frequency bands so that e.g. low frequencies in the modulator signal controls high frequency bands in the vocoder, you can extract CV signals for controlling synth parameters in other devices, you can base the vocoding on CV signals from other devices rather than on a modulator signal, etc. See "Using the individual band level connections" for details.


Other CV connections

Connection	Description
Shift (CV in)	This allows you to control the Shift parameter from an external CV source. A sensitivity knob determines how much the Shift setting is affected by the CV signal.
Hold (Gate in)	When a gate signal is sent to this input, the Hold function is activated (see "Hold button"). Hold remains on until the gate signal "goes low" (falls to zero). By connecting e.g. a Matrix to this input, you can create "stepped" vocoder sounds, sample and hold-like effects, etc.

Audio connections


Connection	Description
Carrier input	This is where you connect the instrument device that provides the carrier signal (or the device to be processed in Equalizer mode) - typically a synth or sampler device. The vocoder can handle mono or stereo carrier signals.
Modulator input	This is where you connect the instrument device that provides the modulator signal, in mono. This connection is not used in Equalizer mode.
Output	In Vocoder mode, the outputs carry a mix between the vocoded signal and the modulator signal (as set with the Dry/Wet control on the front panel). In Equalizer mode the output is the carrier signal, processed through the equalizer filter. Note that the output will be in mono if the Carrier input is in mono, and vice versa - the BV512 does not process mono into stereo.

Automation



All parameters on the front panel can be automated in the standard manner. The individual band levels (the bars in the lower display) will be edited on separate lanes in the sequencer. Note:

- **As with the other effect devices, you have to manually create a sequencer track for the BV512.**
- **Although the band level adjustments can be edited individually, they are treated as one automatable parameter on the device panel.**
  This means that if any single band level control is automated, there will be a frame around the whole lower display on the device panel. Right-clicking (Win) or [Ctrl]-clicking (Mac) in the lower display and selecting "Clear Automation" will remove the automation for all bands. Similarly, selecting "Edit Automation" will open the sequencer with lanes for all band levels shown.



The frame indicates that one or more band level controls are automated.

Tips and tricks

Choosing a carrier sound

As always, which carrier sound to choose is a matter of taste and musical context. However, here are a few guidelines to help you get a good result:

- **The carrier sound should preferably have a lot of harmonic content (brightness) - dark or muffled sounds will not "give the vocoder much to work with".**
- **Often, you want the carrier sound to sustain at an even level (i.e. it shouldn't "die out" when you hold a chord). Similarly, you most often want a reasonably fast attack (although not with a distinct, sharp click or edge).**
- **You may want a sound that is rather static over time, without drastic envelope control of filter cutoff for example.**
- **If you want to play vocoded chords, the carrier sound must of course be polyphonic.**

Here are some hands-on suggestions for carrier sounds:

▶ **A simple Subtractor pad based on a sawtooth waveform.**
You could simply start with the initial patch (as set up when you create a new Subtractor device). Open the filter, turn off envelope modulation of the cutoff frequency and raise the Amp Envelope Sustain.
If you want a classic, rich chorus-like sound, use two detuned oscillators - or better still, add a UN-16 Unison device as an insert effect between the Subtractor and the vocoder!



A simple but effective carrier sound setup.

▶ **A similar fat carrier sound can be obtained using a Malström device with a patch based on the "Sawtooth*16" graintable.**
With the Malström you can get a stereo carrier signal with no extra devices: simply select the "Sawtooth*16" graintable for both oscillators, detune the oscillators slightly with the Cent controls and raise the Spread parameter to the desired stereo width. No filter routings are necessary.

▶ **For a more distinct and precise sound, try using a narrow pulse waveform.**
You get this by selecting e.g. a sawtooth wave on the Subtractor, setting the Phase Mode selector to "–" and turning the Phase knob to the left until you get the desired sound. This type of carrier sound lends itself well to monophonic vocoder lines in the lower registers.

▶ **Use noise as a carrier.**
Try using pure noise (possibly filtered down a bit) for robotic voices, whispering and special effects. It's also very useful to add a bit of noise to a sawtooth or pulse sound - this makes vocoded speech clearer and more intelligible.

- **Use sampled strings or choir sounds.**
  A rich drawbar organ sample can also be a cool carrier sound.
- **For unusual vocoder sounds, try using the Malström as carrier device, e.g. with a glassy, digital pad sound selected.**
  Try turning up the Attack and Decay controls on the BV512, for smeared, rhythmic or pseudo-random modulation of a pad.

Choosing a modulator sound

The modulator sound should typically have varying level and harmonic content. As we've already mentioned, the most typical modulator sounds are vocals or speech and drums or percussion.

- **To use your own voice as modulator sound, refer to "Using the BV512 as an equalizer".**
- **The quickest way to get an "internal" modulator sound is to use a rhythmic loop in the Dr. Octo Rex device.**
  This way you don't have to program a rhythm pattern. On the other hand, using a Redrum as modulator allows you to create exactly the rhythm you want and fine-tune the sounds and the groove.

Using the modulator as carrier

You can get cool special effects by using the same device both as carrier and as modulator. For example, try processing a Redrum device in the following way:

1. **Create a Redrum device and set up the desired patch and pattern.**
2. **Create a Spider Audio Merger & Splitter device.**
3. **Create a BV512 Vocoder.**
4. **Flip the rack around and connect the devices in the following way:**



The output of the Redrum goes into the splitter section of the Spider, and is split into two signals. One signal goes into the carrier input of the vocoder, the other goes into the modulator input.

This is essentially the required connections, but for best results it's a good idea to add some distortion and/or compression to the carrier signal - this increases the amount of high frequencies in the carrier signal:

5. **Press [Shift] and create a Scream 4 distortion device.**
6. **Connect the distortion device as an insert effect between the Spider and the carrier input of the vocoder.**
   Now, the carrier signal will be processed in the distortion device, but not the modulator signal.
7. **Play back the pattern and experiment with the settings on the vocoder and distortion device.**

- ▶ **This technique can also be used to process vocals and speech.**
- ▶ **Try adjusting the Shift parameter for new effects and sounds.**
  Remember that you can route CV to the Shift parameter on the back of the BV512 - use e.g. a Matrix or an LFO output on a synth device!

Controlling the Hold function


As described in "Hold button", pressing the Hold button on the front panel "freezes" the current filter spectrum until you deactivate it again. This can be used for creating sample & hold-like effects, stuttering or garbled vocoder sounds:

- ▶ **Connect e.g. the Gate output on a Matrix device to the Hold input on the back of the BV512.**
  By playing back a gate pattern on the Matrix, the Hold function will repeatedly be turned on and off according to the programmed rhythm in the pattern. Hold will be active for the length of each gate signal.
- ▶ **Automate the Hold function with the main sequencer, either by recording it or by drawing in its controller lane.**
- ▪ **If you route MIDI to the BV512 you can control the Hold function in two ways by default: By pressing a damper pedal connected to your MIDI controller or by playing the note C4.**
  In both cases, the Hold function will be momentary - Hold is on until you release the pedal or key.

Using the individual band level connections

As described in "Individual band levels", the individual band level connectors on the back are CV output and input jacks. The upper row sends out the CV signals from the envelope followers for the different frequency bands, while the lower jacks are CV inputs for controlling the individual bandpass filters (breaking the internal connection from the envelope followers). There are several interesting things you can do with these connections:

Crosspatching frequency bands



By connecting outputs to inputs in alternative configurations, you can drastically change the result of the vocoding. For example, you could have low frequencies in the modulator signal give high frequencies in the vocoded sound and vice versa. Note:

- ▪ **In 4 band and 8 band mode, only the 4/8 first output/input pairs are used.**
- ▪ **In 32 band mode and FFT (512) mode, each connection corresponds to two or several frequency bands.**
  This means that connecting an output to the input with the same number is not the same as using the internal signal path (no CV cable connected). You can hear this quite clearly in FFT (512) mode: connect all outputs to the corresponding inputs and gradually remove the CV cables while listening to the vocoder sound - the sound will progressively get more detailed.

Extracting CV from the vocoder


You can connect an individual band level output to any CV input on any device. This means you can use the vocoder as an envelope follower, having elements in the modulator sound control a parameter in another device, e.g. an effect. Note:

- **The Attack and Decay settings on the BV512 panel affect the envelope followers, and thus the rise and fall times of the CV signals from the individual band level outputs.**
- **If you are using the vocoder in a mode with many bands, but want a broader frequency range to generate the CV signal, you can merge several band outputs into one CV signal - use a Spider CV Merger & Splitter device.**

Controlling vocoder bands from an external source

Connecting a CV source to an individual band input breaks the internal connection from the corresponding envelope follower. This way you can "manually" control the vocoder filters. Some applications:

- **Connect the CV outputs for one or more envelopes in the carrier device to individual band inputs.**
  When you play the carrier instrument, one or more of the bandpass filters in the vocoder will automatically open, adding an extra attack to the sound. Useful if you really want to "play" the carrier, rather than just hold a chord.
- **Connect the gate outputs on a Redrum to individual band level inputs.**
  With this connection (and no device connected to the Modulator input), the Redrum will serve as a pattern sequencer, opening and closing different filter bands. To adjust the gate times, set the drum sounds to Gate mode and use the Length parameter. The result is totally different from using the audio signal of the Redrum as modulator.



The vocoder bands are now solely controlled by the gate signals from the drum channels - the modulator input isn't used. Note that you can use a Spider CV Merger & Splitter device to split a gate signal, sending it to several bands. Also, note that the velocity of the programmed drum notes govern the level of the corresponding filter bands.

"Playing" the vocoder from a MIDI keyboard

If you have routed MIDI to the BV512, playing notes from C1 and up will control individual filter bands. For example, in 16 band mode, C1 controls band 1, C#1 band 2 and so on up to D#2 (which controls band 16).

- **The level of the bands is proportional to key velocity (how hard you play).**
- **A band will be "open" until you release the corresponding key.**
- **Bands to which you have connected a CV signal (using the individual band level inputs on the back panel) will not respond to MIDI keys.**

Note that with this function, you "play the modulator bands". However, you still need both a carrier and a modulator signal to get any sound. Typically, you would first record the notes or chords for the carrier device in the sequencer, then create a sequencer track for the vocoder and "play" it from your MIDI keyboard while playing back the recorded carrier notes and at the same time inputting a signal on the Modulator input.

▶ **An interesting application of this is to patch the vocoder as an insert effect for the whole mix (the output of the main mixer connected to the carrier input), and "play the vocoder" while inputting a signal on the Modulation input. Only the frequency bands for which you press keys will be attenuated. Use the FFT (512) mode for best results.**

Using the BV512 as a reverb

This is a very special trick which can be quite cool. Proceed as follows:


1. **Create a Redrum device.**
   The "vocoder-reverb" is best suited for drums, even though nothing stops you from using it on other sounds.
2. **Create a Subtractor and a vocoder.**
   The Subtractor will automatically be routed to the carrier input. We don't need a dedicated modulator device in this setup.
3. **Flip the rack around and connect Aux send 1 on the Mixer to the modulator input on the vocoder.**
4. **While you're there, re-route the vocoder output to Aux return 1.**
   This way, our vocoder-reverb will be connected as a regular send effect.



5. **Set the vocoder to FFT (512) mode, turn the Decay knob to between 6 and 7 and turn the Dry/Wet control to "wet" (fully right).**
6. **On the Subtractor, set up a noise sound as follows:**

▶ **Turn the Oscillator Mix knob fully to the right.**

- **Turn on the Noise section (but make sure Osc 2 is off).**
- **In the Noise section, turn Color to around twelve o'clock.**
- **Open the filter fully and make sure resonance is set to 0.**
- **Make sure Filter Envelope Amt is 0 (and turn off velocity modulation).**
- **Raise the Sustain to full in the Amp Envelope section.**



Now we want the Subtractor to play a continuous noise. You could just route MIDI to it, play a note and keep it pressed, but that will probably wear you out in the long run. Better to use a Matrix:

7. **Create a Matrix and route it to the Subtractor.**
   We really only need the Gate connection - the note number isn't important with the noise patch.
8. **Set up a one step pattern with a tied gate (press [Shift] and draw the gate) and start playback on the Matrix.**
   Now the vocoder gets a continuous noise signal as carrier.
9. **Create a suitable drum pattern on the Redrum and start pattern playback.**
10. **Gradually turn up send 1 for the Redrum channel in the mixer.**
    This now serves as a balance control between the dry drum sound and the reverb, generated by the voccoded noise! Set it to a suitable reverb level.
11. **Use the Decay control on the vocoder to adjust the reverb decay time.**
12. **Use the Noise Color control on the Subtractor to make the reverb darker or brighter.**
    You could use the filter cutoff for this as well.

That's it - a pretty good reverb sound with a lot of control. Although the settings above give the most natural sound, you can vary the sound and create special-FX reverb in the following ways for example:

- **Switch the vocoder to a lower band mode.**
- **Lower the cutoff and add some resonance in the Subtractor filter.**
- **Modulate the Subtractor filter with a fast LFO.**
- **Set the Subtractor filter to HighPass mode to remove the bottom end from the reverb.**
- **Turn off the Matrix controlling the Subtractor and "play" the noise patch yourself (or from the sequencer). This way you can create gated reverb effects, etc.**

Creating a stereo reverb

What you've got above is a mono reverb. Here's how to make it stereo:

1. **Select the Subtractor and create a Spider Audio Merger & Splitter device.**
2. **Create a DDL-1 delay.**
3. **Connect the devices in the following way:**
   The Subtractor output should be routed to a Splitter input on the Spider. One split output should be routed to one of the carrier inputs on the vocoder, the other split output should be routed to the delay. The delay output (mono) should be routed to the other carrier input on the vocoder.



The vocoder will now get a "fake-stereo" noise carrier signal.

4. **Make sure the output from the vocoder is connected in stereo to the Aux return on the Mixer.**
5. **Finally turn down the Feedback on the delay, set it to all "wet" and set the decay time to a second or so.**

When you now start playback on the Redrum, the reverb will be in stereo!

Chapter 51
Channel Dynamics
Compressor & Gate

Introduction



Channel Dynamics Compressor & Gate is the rack version of the Dynamics section in Reason's Main Mixer. The rack version is mainly intended for use in the VST3 plugin version of Reason, since it lacks the Main Mixer. However, you can of course use it wherever you like - also in the stand-alone Reason program. The Channel Dynamics Compressor & Gate device has identical specifications compared to the channel strip version, with the addition of Input Gain and Dry/Wet Mix controls.

Panel reference

Global controls

Input Gain



- ▶ **Adjust the input gain to the Channel Dynamics device.**
  Range: +/- 18.00 dB

! **The Input Gain knob controls the input signal, regardless if the Compressor and/or Gate is on or not.**

Mix



- ▶ **Set the mix between dry and processed signal with the Mix knob.**
  By setting a mix of <100% you can use the Channel Dynamics device for "parallel processing", i.e. the dry and effect signals are being output together.

The Compressor section



Compressors reduce dynamic range by evening out the difference between loud and quiet signals. This makes signal levels easier to balance, and can add punch and sustain to the sound.

The compressor/limiter in Channel Dynamics is a flexible processor which has soft-knee (a gradual, smooth onset of compression) characteristics but can be switched to peak limiting, where levels above the set threshold are instantly reduced. The compressor also features automatic make-up gain. The parameters are as follows:

On

- **Click the On button to activate the Compressor section.**

Peak

- **Activate to change the signal detection from RMS to Peak, which results in an instant attack time.**
  Peak mode is suitable for compression of sounds with fast attacks like drums.

Fast

- **Click this to make the compressor react to signals above the set Threshold level in a fixed time of 3 ms for 20 dB gain reduction.**

Ratio

- **Set the amount of gain reduction applied to the signal above the set Threshold (see below).**
  Range: 1:1 (no reduction) to Infinite:1

Threshold

- **Set the level at which onset of compression should occur.**
  Signals below the Threshold setting are unaffected, but when the level exceeds the threshold, compression kicks in. Automatic make-up gain (based on the Ratio and Threshold settings) is applied to compensate for level reduction caused by compression, to maintain a steady output level.

  Range: -52 dB to 0 dB

Release

- **Set the time it should take before the compressor lets the sound through unaffected - after the signal level drops below the set threshold.**
  Set this to short values for "pumping" compressor effects, or to longer values for a smoother change of the dynamics.

  Range: 100 ms to 1000 ms

Compressor Gain Reduction Meter

The LED meter shows the gain reduction applied by the compressor.

The Gate/Expander section



Gating or expansion will attenuate signals below a set threshold; the opposite of compression. It can be used to reduce or eliminate unwanted background noise that may be present when there is no signal to mask it. Gating is also commonly used to reduce microphone "bleeding", e.g. when recording a close-mic'ed drum kit you can use gating to silence the tom microphones when the toms aren't being played to tighten up the sound, and for special effects like "keying" (see below).

Higher expansion ratios (10:1 and above) are referred to as noise gating, where the channel is completely silenced if the level drops below the set threshold.

The Gate/expander has the following parameters:

On

- **Click the On button to activate the Gate/Expander section.**

Exp

In Expander mode, the Range (gain reduction) is not as severe as in Gate mode, but more gradual around the Threshold. Also, the gain reduction is not attenuated by a certain dB but is scaled. The major difference compared to the Gate function is that instead of muting the signal once it drops below the Threshold (gate), the Expander still lets some signal through but at a lower level, resulting in a signal of lower volume. You could think of an Expander as an "inverted" compressor, i.e., it expands the dynamic range of the input signal.

- **Click the Exp button to change the operating mode from Gate to Expansion.**
  The Range knob (see below) then controls the expansion amount.

Hold

- **Set the time the gate should stay fully open after the signal falls below the Threshold.**
  Hold interacts with the Release parameter such that Release only starts acting after the set Hold time.
  Range: 0 ms to 4000 ms

Fast

The normal attack time for the Gate is normally1.5 ms per 40 dB.

- **Click the Fast button to lower the attack time to 100µs (microseconds) per 40 dB.**
  This can be is useful for percussive material were the waveform rises steeply in a very short time.

Range

- **Set the amount of gain reduction applied to signals below the set Threshold.**
  The Range can be set from 0 dB (no reduction) to -40 dB. If the Exp button is on (see above), the Range knob controls the expansion amount.

Threshold

- **Set the level at which the gate opens or closes.**
  Signals below the Threshold setting are gated, but when the level exceeds the threshold, the gate opens.
  Range: -52 dB to 0 dB

! **Note that the threshold for closing the gate is slightly lower than the threshold for opening the gate. This is to avoid undesirable gate triggering with signal levels close to the set threshold.**

Release

- **Set the time it should take for the gate to go from open to fully closed.**
  Fast release times will fade the signal abruptly once the level falls below the threshold, and longer release times will slowly fade out the signal.

  Range: 100 ms to 1000 ms

Gate Gain Reduction Meter

The LED meter shows the gain reduction applied by the gating/expansion.

External Sidechain



You can use external signals to trigger the Compressor and/or the Gate/Expander. This is done by connecting an external signal to the Sidechain Inputs on the back of Channel Dynamics.



The Sidechain inputs.

When a cable is connected to the Sidechain Input(s) the "Connected" LED is lit on the front panel:



- **Click the Sidechain button to "key" (trigger) Channel Dynamics from the external signal instead of the channel signal.**
  For example, you could use a drum loop to trigger the gate for a channel playing a synth pad to create rhythmic chord effects.

Connections



CV Outputs

These two CV modulation outputs can be used for controlling other devices that feature CV modulation inputs. The modulation parameters are:

- **Compressor Gain Reduction (see "Compressor Gain Reduction Meter")**
- **Gate Gain**
  This CV signal is high when the gate is open and goes low when the gate closes.

Sidechain Input Left & Right

- **Patch an external audio signal to be used as sidechain signal here.**
  See "External Sidechain" for more information.

Input Left & Right

- **Patch the audio signals you want to process here.**
  If your input signal is in mono, connect only to the L (left) input.

Output Left & Right

These are the audio outputs.

Chapter 52
Channel EQ Equalizer

Introduction



Channel EQ Equalizer is the rack version of the EQ section in Reason's Main Mixer. The rack version is mainly intended for use in the VST3 plugin version of Reason, since it lacks the Main Mixer. However, you can of course use it wherever you like - also in the stand-alone Reason program. The Channel EQ device has identical specifications compared to the channel strip version.

Panel reference

Global controls



Gain

- **Adjust the Channel EQ gain with this knob.**
  This is useful for level-compensating when doing drastic boosts or cuts.
  Range: +/- 18.00 dB

  The signal level is shown in the meter.

The Filter section



The Filter section contains a 12 dB/octave low pass filter and an 18 dB/octave high pass filter.

The parameters are as follows:

HPF On

- **Click the On button to activate the high pass filter.**

HPF Freq

The High Pass filter (HPF) removes low frequencies from the signal, resulting in a thinner sound. The HP filter slope has a 18 dB/Octave roll-off.

- **Set the desired cutoff frequency for the high pass filter.**
  Range: 20 Hz - 4 kHz

LPF On

- **Click the On button to activate the low pass filter.**

LPF Freq

The Low Pass filter (LPF) removes high frequencies from the signal, making the sound less bright. The LP filter has 12 dB/Octave roll-off curve.

- **Set the desired cutoff frequency for the low pass filter.**
  Range: 100 Hz - 20 kHz.

The Equalizer section



The Equalizer section features a four-band EQ with parametric midrange controls and high and low frequency shelving bands. The EQ can be switched between two operating modes, each with slightly different curve characteristics.

The Equalizer has the following parameters:

LF Gain

The LF section provides low frequency shelving equalization. All frequencies below the set LF Frequency will be cut or boosted by the set LF Gain amount.

- **Set the LF Gain/Attenuation amount.**
  Range: +/- 20 dB

LF Frequency

- **Set the LF Frequency.**
  Range: 40 Hz - 600 Hz

LF Bell

- **Click the LF Bell button to switch the LF EQ to peaking characteristics.**
  This means it works like a regular parametric EQ band, cutting or boosting the signal around the set LF Frequency. Bell mode has a fixed bandwidth or "Q" value.

LMF Gain

The low medium frequency EQ is fully parametric.

- **Set the LMF Gain/Attenuation amount.**
  Range: +/- 20 dB

LMF Frequency

- **Set the LMF (center) Frequency.**
  Range: 200 Hz - 2 kHz

LMF Q

The "Q" parameter adjusts the bandwidth around the set center LMF Frequency. The higher the Q value, the narrower the affected frequency range - except in "E" mode (see "E Mode").

- **Set the Q value for the LMF EQ.**
  Range: 0.70 - 2.50

E Mode

- **Click to switch to E Mode.**
  When the E Mode button is activated the EQ will have slightly different curve characteristics. In normal mode (E button deactivated), the Gain setting will also affect the bandwidth (Q value) for the LMF and HMF EQs. The higher the Gain, the narrower the bandwidth and vice versa.

  With E Mode activated, the bandwidth is constant at all Gain settings.

HMF Gain

The high medium frequency EQ is fully parametric.

- **Set the LMF Gain/Attenuation amount.**
  Range: +/- 20 dB

HMF Frequency

- **Set the HMF (center) Frequency.**
  Range: 600 Hz - 7 kHz

HMF Q

The "Q" parameter adjusts the bandwidth around the set center HMF Frequency. The higher the Q value, the narrower the affected frequency range - except in "E" mode (see "E Mode").

- **Set the Q value for the LMF EQ.**
  Range: 0.70 - 2.50

HF Gain

The HF section provides high frequency shelving equalization. Frequencies above the set corner Frequency will be cut or boosted by the set HF Gain amount.

- **Set the HF Gain/Attenuation amount.**
  Range: +/- 20 dB

HF Frequency

- **Set the HF Frequency.**
  Range: 1.5 kHz - 22 kHz

HF Bell

- **Click the HF Bell button to switch the HF EQ to peaking characteristics.**
  This means it works like a regular parametric EQ band, cutting or boosting the signal around the set HF Frequency. Bell mode has a fixed bandwidth or "Q" value.

Connections



CV Inputs

These six CV modulation inputs, with associated trim pots, can be used for controlling the following parameters from CV modulation sources:

- **HPF Frequency (see "HPF Freq")**
- **LPF Frequency (see "LPF Freq")**
- **HMF Gain (see "HMF Gain")**
- **HMF Frequency (see "HMF Frequency")**
- **LMF Gain (see "LMF Gain")**
- **LMF Frequency (see "LMF Frequency")**

Input Left & Right

▶ **Patch the audio signals you want to process here.**
If your input signal is in mono, connect only to the L (left) input.

Output Left & Right

These are the audio outputs.

Chapter 53
Master Bus Compressor

Introduction



The Master Bus Compressor is the rack version of the Master Bus Compressor in Reason's Main Mixer. The rack version is mainly intended for use in the VST3 plugin version of Reason, since it lacks the Main Mixer. However, you can of course use it wherever you like - also in the stand-alone Reason program.

The Master Compressor is perfect for providing the final "fairy dust" to your mix. It can add punch and cohesion, and generally make the mix sound bigger and more powerful. It's perfect for use on a drum channel or in a mixer bus. The compressor is very straightforward in operation and features make-up gain as well as program-adaptive Release.

The Master Bus Compressor device has identical specifications compared to the Master Section version, with the addition of Input Gain and Dry/Wet Mix controls.

Panel reference

Global controls



Mix

- **Set the mix between dry and processed signal with the Mix knob.**
  By setting a mix <100% you can use the Master Bus Compressor for parallel processing, i.e. the dry and effect signals are being output together.

Compression controls



Compressors reduce the dynamic range by evening out the difference between loud and quiet signals. This makes signal levels easier to balance, and can add punch and sustain to the sound, as well as "glue" together a final mix.
The parameters are as follows:

Input Gain

- **Adjust the input gain to the Master Bus Compressor.**
  Range: +/- 18.00 dB

Threshold

- **Set the level at which onset of compression should occur.**
  The lower the Threshold, the more compression is applied.
  Range: -30 dB to 0 dB

Ratio

Ratio specifies the amount of gain reduction applied to signal levels above the set Threshold. A 2:1 compression ratio effectively means that a signal level 2dB above threshold will have a signal gain of 1dB.

- **Set the amount of gain reduction applied to the signal above the set Threshold.**
  Range: 2:1, 4:1 and 10:1

Attack

- **Set the time it should take before the compressor should react to signals above the set Threshold.**
  Range: 0.1 ms, 0.3 ms, 1 ms, 3 ms, 10 ms and 30 ms.

Release

- **Set the time it should take before the compressor lets the sound through unaffected - after the signal level drops below the set Threshold.**
  If set to "Auto", the Release time will be program adaptive, so the Release time is automatically increased following long peaks and decreased following short peaks.
  Range: 0.1 s, 0.3 s, 0.6 s, 1.2 s and "Auto".

Make Up

Make-Up gain compensates for level reduction caused by compression and helps maintain a steady output level.

- **Adjust the output gain from the Master Bus Compressor device.**
  Range: - 5 dB to + 15.00 dB

Compressor Gain Reduction Meter

The meter shows the gain reduction amount in dB applied by the compressor.

External Sidechain



You can use external signals to trigger the Master Bus Compressor. This is done by connecting an external signal to the Sidechain Inputs on the back of the Master Bus Compressor.



The Sidechain inputs.

When a cable is connected to the Sidechain Input(s) the "Connected" LED is lit on the front panel:



- **Click the Sidechain button to "key" (trigger) Master Bus Compressor from the external signal instead of the channel signal.**
  For example, you could use a kick drum pattern to trigger the sidechain function, to achieve a rhythmic pumping effect.

Connections



Comp Gain Reduction

This CV output sends out the gain reduction as a CV signal (see "Compressor Gain Reduction Meter").

Sidechain Input Left & Right

- **Patch an external audio signal to be used as sidechain signal here.**
  See "External Sidechain" for more information.

Input Left & Right

- **Patch the audio signals you want to process here.**
  If your input signal is in mono, connect only to the L (left) input.

Output Left & Right

These are the audio outputs.

Chapter 54
The MClass Effects



The MClass effects


The MClass effects package consists of four effect devices, which are available as separate devices from the Create menu and on the Effects palette in the Browser. There are also a number of Mastering Combi patches available in the Effects folder in the Factory Sound Bank. These mastering patches consist of all four MClass device types, patched together and organized as Combinator patches. The Mastering Combis are perfect to use as Master Insert FX in the Main Mixer to process the final mix. The individual MClass effects are as follows:

- **The MClass Equalizer - this has low and high shelving bands, two fully parametric bands and a low cut "anti-rumble" switch. See "The MClass Equalizer".**
- **The MClass Stereo Imager - this can be used to control the stereo width for the high and low frequency ranges separately. See "The MClass Stereo Imager".**
- **The MClass Compressor - this single band compressor features sidechain input and program-adaptive release. See "The MClass Compressor".**
- **The MClass Maximizer is a special limiter tailored for loudness maximizing without risk of clipping. See "The MClass Maximizer".**

Common effect device parameters

While the specific parameters for the MClass effect devices are described below, some features and procedures are common to all effect devices. Please, refer to "Common effect device features" for information about the Input meter, the Bypass/On/Off switch and Signal Flow Graphs on the effect devices.

The MClass Equalizer



The MClass Equalizer consists of two independent, fully parametric bands plus high and low shelving bands and a lo cut switch.

This is most often used as an insert effect, in mono or stereo.

Activating the separate EQ bands

The separate bands are organized as vertical strips on the panel, in the following order (from left to right): Lo Cut/Lo Shelf/Parametric 1/Parametric 2/Hi Shelf.

You activate the separate bands by clicking the button at the top of each strip (none of the bands are activated by default).

Lo Cut

The Lo Cut switch will simply cut frequencies below 30 Hz (by 12 dB/Octave). This is useful for removing low frequency "rumble".

- **When you are using the MClass Equalizer with a compressor or Maximizer, activating the Lo Cut switch prevents subsonic sound from "topping" the compressor/limiter, and allows them to operate as efficiently as possible.**

Parametric 1-2 parameters

A parametric equalizer will boost or cut frequencies around the selected frequency. The following parameters are available for both the parametric bands:

Parameter	Description
Frequency	This determines the center frequency of the EQ, i.e. at which frequency the level should be decreased or increased. The range is 39 Hz to 20 kHz.
Gain	Specifies how much the level of the selected frequency range should be boosted or cut. The gain range is ±18 dB.
Q	This governs the width of the affected area around the set center frequency. The higher the value, the narrower the affected frequency range.

Lo/Hi Shelf parameters

A shelving equalizer will boost or cut frequencies below or above the selected frequency.

The following parameters are available for the Lo/Hi Shelf bands:

Parameter	Description
Frequency	Frequencies below (Lo Shelf) or above (Hi Shelf) the selected frequency will be boosted or cut. • The Lo Shelf range is 30 Hz to 600 Hz. • The Hi Shelf range is 3 kHz to 12 kHz.
Gain	Specifies how much the level should be boosted or cut. The gain range is ±18 dB.
Q	This governs the slope of the shelving curve. The higher the value, the steeper the curve slope. High Q settings will also produce a "bump" in the opposite cut/boost direction at the set frequency.

About the graphic display

The graphic display to the left in the device panel shows the frequency response curve as set by the EQ parameters. This gives a visual feedback and helps you tailor the EQ settings.

The MClass Stereo Imager



The MClass Stereo Imager splits the signal into two frequency bands; "Hi" and "Lo" and allows you to widen or narrow the stereo image of each band. A typical application of the Stereo Imager is to widen the higher frequencies and narrow the lower frequencies. This will make the bass end "tight" whilst "opening up" the higher frequencies.

This is most often used as an insert effect in stereo.

! **The MClass Stereo Imager does not create stereo from mono input! For the device to work properly it must connected with stereo in/out, and the input signal must contain a stereo audio signal.**

Parameters

The following parameters are available:

Parameter	Description
X-Over Frequency	This determines the crossover frequency between the Hi and Lo band. Range is 100 Hz - 6 kHz. Frequencies below this will be affected by the Lo Width setting; frequencies above will be affected by the Hi Width setting.
Lo Width	This adjusts the stereo width for the Lo band. Turn anti-clockwise to narrow the stereo width (i.e. to make it more "mono"), and clockwise to widen the stereo image. Center position means no change from original signal. The "Active" LED indicates whether Low Width is activated or not. Note that for the Lo band, it is more common to narrow the stereo image, as the low frequency content in a mix is usually mixed center and can become less defined if widened.
Hi Width	This adjusts the stereo width for the Hi band. Turn anti-clockwise to narrow the stereo width (i.e. to make it more "mono"), and clockwise to widen the stereo image. Center position means no change from original signal. The "Active" LED indicates whether Hi Width is activated or not.
Solo switch	This allows you to listen to the Lo and Hi bands separately, for reference purposes. "Normal" is the standard operating mode.

Connections



Apart from standard L/R inputs and outputs, there are also "Separate" L/R outputs on the back panel. The Separate outputs can either carry the Lo or Hi band output, which is set by the switch beside the outputs. These outputs can be used to apply processing separately to either the Lo or Hi band.

- **If you set the Solo switch to "Lo" and the Separate output switch to "Hi", the device will operate as a basic crossover filter, delivering the Lo band signal from the main output and the Hi band signal from the Separate out.**

The MClass Compressor



This is a single-band compressor capable of everything from subtle compression to aggressive pumping effects. Like all dynamics processors it is best used as an insert effect.

The features include "soft-knee" compression for more musical and unobtrusive compression, program-adaptive release time and a sidechain input for de-essing and other dynamics processing. Additionally, you have a CV output, allowing you to have the amount of gain reduction control other Reason parameters.

Parameters:

Parameter	Description
Input Gain	The Input Gain controls the "drive" of the compression. This determines how much compression the signal will have in conjunction with the Threshold. Range: ±12 dB.
Threshold	This sets the level at which onset of compression occurs. When the input level is below the Threshold setting the signal is unaffected. When the input level exceeds the threshold, compression kicks in. In practice, this means that the lower the Threshold setting (and the higher the Input Gain), the more compression will be applied. Range: -36 dB to 0 dB
Soft Knee	Normally signals above the threshold will be compressed immediately at whatever ratio is set. This can be very noticeable, especially when using high compression ratios. When Soft Knee is activated, the onset of compression will be more gradual, producing a less drastic result.
Ratio	This lets you specify the amount of gain reduction applied to the signals above the set threshold. The Ratio can be set from 1:1 (no reduction) to ∞:1 (Infinite).
Gain meter	This shows the amount of gain reduction (in dB).
Solo Sidechain	This allows you to monitor the signal connected to the sidechain input (see below).
Attack	This governs how quickly the compressor will apply its effect when signals rise above the set threshold. If you raise this value, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds. Range: 1ms to 100ms.
Release	When the signal level drops below the set threshold, this determines how long it takes before the compressor lets the sound through unaffected. Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics. Range: 50ms to 600ms.
Adapt Release	When this is used, set Release to the time you want for short peaks - when longer peaks occur, the Release time is automatically increased.
Output Gain	This controls the output gain and can be used to compensate for the gain reduction caused by compression. Range: ±12 dB.

About the Sidechain inputs

- **When a signal is connected to the Sidechain inputs, it is this signal that will trigger the compression.**
  This signal is not passed to the compressor output, and will thus not be heard (unless Sidechain Solo is activated).
- **The signal connected to the normal L/R inputs is the signal that will be processed by the compressor (as usual).**

Here follows two examples of how you can use sidechain processing:

Example 1 - using the Sidechain inputs to create ducking effects

"Ducking" is when the level of one signal is reduced by the presence of another signal. A typical application is to automatically lower the level of a musical bed when a voice-over starts, and to automatically bring the level up when the voice-over stops. To set this up, we can name the musical bed in the example "Device A", and the voice-over "Device B". Proceed as follows:

1. **Connect Device A and Device B to separate channels on a mixer device.**
   In this example the signal produced by Device A should be continuous, and the signal produced by Device B should be intermittent, i.e. it should contain both silent passages and signal passages.
2. **Select Device A and then select an MClass compressor from the Create menu.**
   The effect will be auto-routed as an insert effect to Device A.
3. **Connect a Send on the mixer device to the Sidechain inputs on the MClass compressor.**
   As soon as anything is connected to the Sidechain inputs, the "Active" indicator lights up on the device panel. The compressor will no longer react to the signal produced by Device A.



4. **Turn up the corresponding AUX Send level for Device B on the mixer.**
   This means that the Device B signal now feeds both the mixer's input, and the sidechain input on the compressor, which in turn triggers the gain reduction.
5. **If you now start playback of both devices, the level of Device A will be lowered whenever Device B sounds, and be raised again when Device B stops.**
   The amount of gain reduction, how quickly it lowers the level, and the time it take for the level to return to normal again is determined by the corresponding Gain/Threshold/Ratio and Attack/Release parameters.

Example 2 - using the Sidechain inputs to create frequency sensitive compression

By inserting an equalized signal to the sidechain inputs you can make the compression more or less sensitive to a certain frequency range. A typical application of this is "de-essing" - where harsh "S"-sounds in vocal material is reduced or eliminated.

Frequency sensitive compression is set up as follows:

1. **Hold down [Shift] and create an instrument device.**
   Pressing [Shift] means no auto-routing connections to/from the device are made.
2. **Hold down [Shift] and create a MClass Equalizer.**
3. **Hold down [Shift] and create a MClass Compressor.**
4. **Create a Spider Audio Merger and Splitter device.**
5. **Connect the outputs of the instrument device to the A and B inputs on the Spider.**
6. **Route one pair of the split outputs of the Spider to the MClass Equalizer inputs.**

7. **Route the Equalizer outputs to the Sidechain inputs on the MClass Compressor.**
8. **Route another pair of the split outputs of the Spider to the MClass Compressor.**
   Now, the compressors normal audio inputs are fed the unprocessed signal, and the sidechain inputs are fed the equalized signal.



9. **Next, route the outputs of the Compressor to inputs on a mixer device.**
10. **Activate the Solo Sidechain button on the compressor's front panel.**
    You will now only hear the equalized signal.
11. **Now use the parameters on the MClass Equalizer to boost the frequencies you wish should trigger the gain reduction and cut the frequencies you wish to avoid triggering the gain reduction.**
    You can use rather extreme eq settings - the signal will not be heard when Solo Sidechain is deactivated anyway. E.g. for de-essing you should separate and boost the offending "S" frequencies as much as possible.
12. **Deactivate Solo Sidechain when you have finished tweaking the equalizer.**
    Now, the compressor will be more sensitive to the frequency area you tuned in with the equalizer, and thus react more to these frequencies. Note, however, that the whole signal will still be compressed - not just the boosted frequencies - so in case of de-essing you should usually use fast Attack and Release settings so that the gain reduction does not affect the rest of the program too much.

CV Outs

On the back of the MClass Compressor you can find a "Gain Reduction" CV out connector. This can be used to modulate other parameters with the amount of gain reduction applied by the compressor. This means that the compressor works as an envelope follower. You could for example have the audio signal level control pan in a mixer or a synth parameter.

The MClass Maximizer



This is a loudness maximizer, a special type of limiter which can significantly raise the perceived loudness of a mix without risk of hard clipping distortion. Features include a 4 ms look ahead function for "brick wall" limiting and a Soft Clip function.

The MClass Maximizer should be used as an insert effect, and is designed to be placed at the end of the signal chain between the mixed final output and the Hardware Interface.

Parameters

Parameter	Description
Input Gain	The Input Gain sets the basic volume of a mix. If this is set very high, you should use Look Ahead mode or the Soft Clip function to eliminate the risk of hard clipping distortion. Range: ±12 dB.
Limiter On/Off	This turns the Limiter section on or off.
Look Ahead On/Off	If activated, this will introduce a very short delay (4 ms) to the signal. This delay is used to detect peaks in the signal before they actually occur. If high peaks are detected the limiter is "ready for them" and gain reduction is applied to transparently control the peaks.
Attack (Fast/Mid/Slow)	This governs how quickly the Limiter will apply its effect. If set to Fast with Look Ahead activated (and the Output Gain is set to 0 dB) you will get "brick wall" limiting - no signal peaks over 0 dB will pass.
Release (Fast/Slow/Auto)	This determines how long it takes before the Limiter lets the sound through unaffected. If Auto is activated, the Release time will automatically adapt to the program material.
Output Gain	This controls the output gain and should normally be set to 0 dB.
Soft Clip On/Off	If this is activated, it also acts a 0 dB brick wall limiter but in a slightly different way. The signal will be "soft-clipped" which adds a pleasant, warm sounding distortion to the signal. It can be used simply to get this effect, or as a safeguard against hard clipping distortion if Look Ahead with Mid or Slow attack settings are used (or if Look Ahead is deactivated).
Soft Clip Amount	This controls the amount of soft-clipping distortion. Note that if Soft Clip is on but the Amount is set to zero, the distortion will be like hard clipping, and thus less pleasing to the ear.
Output level meter (Peak/VU)	This is a more detailed meter than found on the mixer. You can switch the meter characteristics between Peak (faster response to peaks) and VU mode (average levels).

Chapter 55
Neptune Pitch Adjuster and Voice Synth

Introduction



The Neptune Pitch Adjuster and Voice Synth device is a combined monophonic vocal pitch corrector, pitch shifter and polyphonic voice synth. Neptune was designed with focus on high-quality vocal processing but can also be used on other material. However, due to the signal characteristics of other types of audio (complex inharmonic instrument sounds, polyphonic material etc.) the result of the pitch adjustments might not be what you would expect. Don't hesitate to experiment, though!

Used as a pitch corrector, Neptune can automatically correct flat monophonic input signals and output corrected notes in real-time. The pitch correction can be adjusted from totally transparent to hard, robot-like. The correction can be controlled from predefined scales, from input MIDI notes or from a combination of both!

When used as a pitch shifter, Neptune performs overall pitch-shifting of incoming monophonic audio in real-time and transposes the output to a defined value within a ±1 octave range.

The Voice Synth section in Neptune allows you to add additional voices - harmonies - to a monophonic vocal input signal and to control the voices via MIDI - from sequencer notes or by playing on your MIDI master keyboard.

Neptune also features controls for adjusting formants and for adding pitch bend and vibrato to the processed signal.

▶ **It's also possible to correct and edit monophonic pitches graphically in Audio Pitch Edit Mode in the Reason sequencer, see "Editing audio in Vocal Edit mode".**


Typical use cases

Neptune can be used in a variety of ways and situations. Here are some examples:

- **Pitch correction of a vocal track**
  Neptune is used as an Insert Effect on the vocal audio track, with the Pitch Adjust's Scale set to desired scale. Set the Correction Speed parameter to a moderate value for transparent pitch correction - or set the Correction Speed parameter to max value and the Preserve Expression parameter to minimum for a hard "robotic" character.
- **Octave dub**
  Neptune is used as a Send Effect. The Pitch Adjust section is turned off and the Transpose section is activated. The Semi parameter is set to +12 to transpose up 1 octave. The Send FX control on the mixer is used for balancing the level of the octave-shifted voice. The Formant Shift control is used for making the transposed voice sound more natural (or unnatural, if that's desired).
- **Create backing harmonies on a vocal track**
  Neptune is used as an Insert Effect on the vocal audio track and MIDI Input is routed to the Voice Synth via the Neptune sequencer track. Play some notes on your MIDI master keyboard and use the Voice Synth breakout jacks connected to a separate Mix Channel for further processing.
- **Pitch shift drums (non-pitched input)**
  The Pitch Adjust section is turned off and the Transpose section is activated. The Transpose parameters are set to desired values.
- **It is also possible to perform other tricks, as described in "Pitch adjustment tips and tricks".**

Overview and basic concepts


Sections overview



The Neptune panel is divided into three main sections that are connected in series:

- **The Pitch Adjust section.**
  Here is where you control the pitch correction settings, including scale, correction speed etc. Here is also where you find the big display where you can view Input Pitch, Target Note and Catch Zone etc. See "Using pitch correction". for more details.
- **The Transpose section.**
  Here is where you control the pitch shifting parameters. See "Using pitch shifting (Transpose)" for details.
- **The Formant section.**
  Here is where you can control and adjust formants. See "Using Formant control" for details.

These three main sections can be used separately, or in combinations, by clicking the ON/Off button of the respective section:




The first section in the signal chain is the Pitch Adjust section. To get a realistic result out of the pitch correction, you will probably want to use it in combination with the Formant section - especially if you control the target pitch via MIDI and the target pitch differs a lot from the input pitch.

The Transpose section can be used stand-alone when you only want to perform stiff pitch shifting of the input audio. If you want to pitch-shift atonal audio, you should use the Transpose section stand-alone, or in combination with the Formant section, for best result. You can also use the Transpose section together with the Pitch Adjust section for transposing pitch corrected audio by a defined amount.

The Formant section can be used stand-alone if you only want to change the character of the input audio - without affecting the pitch. Used on vocals or speech, the Shift knob lets you control the "gender" of the voice.

Besides these three main sections, there are also additional parameters for defining audio input characteristics (see "Input signal type"), MIDI control (see "MIDI Input") and output level control (see "The Output Mixer section").

The display



The big display in the center of the Neptune panel shows the following information:

- **The Input Pitch of the incoming audio signal.**
  The detected Input Pitch is displayed as a yellow vertical line above the keyboard.
- **The Target Note to which Neptune corrects the output signal.**
  The Target Note is displayed as a green vertical line above selected notes on the keyboard.
- **An orange horizontal line between the Input Pitch and the Target Note.**
  The orange line shows the distance and direction from Input Pitch to Target Note.
- **The Catch Zones, i.e. the pitch "window" which determines to what Target Note to correct the Input Pitch.**
  The Catch Zones are displayed as red horizontal boxes above each selected key on the virtual keyboard. As soon as a detected Input Pitch lies within a Catch Zone, the Catch Zone box above the corresponding Target Note switches to green. See "Setting Catch Zone Size".
- **The virtual keyboard, where you can select your own notes or custom scale to correct the audio to.**
  See "Setting Root Key and Scale".

Setting up for pitch processing

The examples below describe how to connect and use Neptune in typical pitch adjustment situations. We assume here that you have a MIDI keyboard connected, or use the On-screen Piano Keyboard (see "On-screen Piano Keys").

Setting up for pitch processing of recorded audio tracks

The most flexible method of performing pitch adjustments is to apply it to already recorded audio tracks in the sequencer. Doing so will give you total freedom to edit and change the pitch adjustment settings afterwards without needing to re-record any audio.

To set up Neptune for pitch adjustments of recorded audio tracks, proceed as follows:

1. **Select the Audio Track in the sequencer for the track you want to pitch-adjust.**
2. **Create a Neptune device.**
   The Neptune device will be created as an insert effect in the Audio Track device and will be automatically connected to the appropriate connectors.

▶ **If you want to control the pitch adjustment via your MIDI keyboard, create a sequencer track for the Neptune device and select the Neptune track in the Track List.**

Now, you are all set for pitch adjustments of the audio on the Audio Track. For information about pitch correction, see "Using pitch correction", for information about pitch-shifting, see "Using pitch shifting (Transpose)", and for info about creating additional vocal harmonies, see "Using the Voice Synth".

Setting up for pitch processing of “live” audio

Neptune can of course also be used for performing pitch adjustments in real-time. This is great for live performances and can also be used for recording pitch-processed audio on an audio track.

To set up Neptune for pitch adjustments in real-time, proceed as follows:

1. **Create a Mix Channel device.**
2. **Create a Neptune device, ether by double clicking the Neptune device icon on the Device Palette in the Effects location in the Browser, or by selecting it from the Create menu.**
   The Neptune device will be created and routed as an insert effect in the Mix Channel device.
3. **Connect a microphone to your audio interface and manually patch the appropriate Audio in jack on the Reason Hardware Interface to the Left Input on the Mix Channel device.**

- **If you want to control the pitch adjustment via your MIDI keyboard, create a sequencer track for the Neptune device and select the Neptune track in the Track List.**
- **To make the tracking of the Input Pitch faster you could try and activate the “Live Mode” button.**
  This will reduce the latency even further, but could in some situations make the pitch tracking a little unstable.

Now, you are all set for live pitch adjustments. For information about pitch correction, see “Using pitch correction”, for information about pitch-shifting, see “Using pitch shifting (Transpose)”, and for info about creating additional vocal harmonies, see “Using the Voice Synth”.

If you want to record your processed audio on an audio track in the sequencer, perform the following additional steps:

4. **Create an Audio Track.**
5. **Click the Rec Source button on the Mix Channel device you use for the Neptune.**
6. **Select the Mix Channel device as input source in the Input Selector on the Audio Track in the sequencer.**
   This will route the pitch-processed audio from the Mix Channel to the Audio Track. This setup is identical to what you would use when recording with effects, as described in “Creating an input channel for recording with effects”.

Using pitch correction

Pitch correction is great if you, for example, have a vocal track in your song that contains flat notes. Instead of having to overdub the flat parts on the audio track, you can automatically adjust the pitches of the flat notes using Neptune. You can also sing through the Neptune in real-time and get a beautifully pitched voice!

There are two basic ways of using pitch correction in Neptune:

- **Automatic pitch correction using Scales, see “Using automatic pitch correction”.**
- **Manual pitch correction using MIDI note input, see “Using manual pitch correction”.**

You can also combine the two methods if you like. First of all, though, you will need to make some basic settings:

Basic settings for pitch correction

Proceed as follows to set up the panel parameters for pitch correction:

1. **Set up the Neptune device as desired according to the descriptions in "Setting up for pitch processing".**
2. **Make sure the "Pitch Adjust" button is activated and that the "Transpose" button is off.**



- **Whether the Formant button should be on or off depends on the situation.**
  For very small pitch corrections, you might want to leave this off; for more substantial pitch changes you will get the most natural sound when this is activated.

3. **Define the Input signal type by using the "Low Freq", "Wide Vibrato" and "Live Mode" buttons:**



- **Activate "Low Freq" for low-frequency material such as a deep voice etc.**
  The "Low Freq" mode will make Neptune detect low frequency notes in a more precise way. Note that the latency will become longer due to the fact that low frequencies have longer cycle times.
- **If the input voice contains a lot of vibrato, it might be a good suggestion to activate the "Wide Vibrato" button.**
  If your input audio has a heavy vibrato, this can cause Neptune to detect the wrong pitches. The result can be wobbling notes, unwanted swoops and glides etc. Activating the Wide Vibrato button will make the pitch detection ignore any vibrato in the input audio, eliminating the problems. Note however that the vibrato can still be retained in the processed sound, by raising the Preserve Expression parameter (see "About the Preserve Expression parameter").
- **If you are going to use pitch correction by singing through Neptune in real-time, try activating the "Live Mode" button.**
  This will reduce the latency of the pitch correction to a minimum, which might be preferable if you want to monitor the corrected signal as you sing. Note, however, that the audio quality may be lower in Live Mode.

4. **Make sure the "MIDI" button is set to "To Pitch Adjust".**




This will enable the pitch correction to be controlled also via MIDI (see "Using manual pitch correction").

Using automatic pitch correction

With the Root and Scale functions you can define what notes you want the incoming audio to be corrected to. The input audio will then be automatically corrected to the defined scale, without further user interaction. With the Catch Zone, Correction Speed and Preserve Expression parameters you can set the character of the adjusted signal.

- **It's also possible to manually override the automatic settings via MIDI at any time, see "Using manual pitch correction".**

About the Scale Memory



There are four Scale Memory slots in the Pitch Adjust section. The purpose of Scale Memories is to allow for automation of different Root Key, Scale and Catch Zone settings. A selected Scale Memory slot automatically stores which Root Key and Scale notes are active (see "Setting Root Key and Scale"), just like a Redrum stores what 16th note buttons are selected in a pattern. The Scale Memory slots also store Catch Zone settings (see "Setting Catch Zone Size"). By using automation of the Scale Memory slots from the Neptune sequencer track, you can easily switch characteristics throughout the song. The Scale Memory settings are automatically saved with the document when you save your Song.

! **Before you perform any edits of the Root Key, Scale and/or Catch Zone parameters, make sure you have selected a Scale Memory slot that you want to overwrite.**

Setting Root Key and Scale


! **Any Root Key and/or Scale settings changes you make are automatically stored in the currently selected Scale Memory slot in real-time, see "About the Scale Memory".**

Define the Root Key and Scale parameters as follows:


1. **Set the Root Key with the Root spin controls.**
   The key can be chosen between C and B in a one octave span, covering each key in the western 12-tone scale.




2. **Set desired scale with the Scale spin controls.**
   The Scale parameter can be set to any of the following preset scales, as indicated in the Scale display:




Chromatic




Major with C as Root Key




Natural Minor with C as Root Key



Harmonic Minor with C as Root Key




Dorian with C as Root Key



Mixolydian with C as Root Key

! *** When Chromatic is selected, the Root display will switch to show "--" since all notes in the 12-tone scale are included and the root key is of no importance here.**

▶ **You can also define your own custom scale by clicking on the keys in the display.**
Selected notes in your custom scale will be indicated with green LEDs:




A custom scale containing the notes D, G and A.

When you set your own scale both the Root Key and Scale displays will switch to show "--".

- **The set Key and Scale is automatically repeated for every octave throughout the entire note range.**

! **Note that this doesn't necessarily need to be an actual scale - sometimes you may only need to activate one or two notes, passing the other notes through, uncorrected.**


Setting Catch Zone Size



The Catch Zone Size parameter defines what pitches in each octave should be "caught" and adjusted towards the closest Target Notes.

! **Any Catch Zone Size settings changes you make are automatically stored in the currently selected Scale Memory slot in real-time, see "About the Scale Memory".**

The Catch Zones are shown as boxes above each selected note in the keyboard display:




The Catch Zones for the notes in a custom scale with notes D, G and A selected.

- **The Catch Zone size is set with the Catch Zone Size knob.**
The range is ±20 to ±600 cent, set in 20 cent steps. The range is always centered around the selected notes in the scale and the default value is ±100 cents.


! **Pitches outside or in-between Catch Zones are not caught and adjusted, but let through unprocessed.**

- **Catch Zones cannot overlap each other. If the Catch Zone Size is increased so that adjacent zones touch each other, they will stop expanding in that direction and meet "half ways".**
  The Catch Zone size in the picture below is set to ±150 cents. As you can see, the Catch Zones for notes G and A have "collided" and therefore met half ways in the center of the G# note. If the Catch Zone size should be increased further, the G Catch Zone would expand only downwards and the A Catch Zone only upwards.



The Catch Zones for the selected notes D, G and A in a custom scale.

- **If the Catch Zones should extend on either side of the 12-note keyboard range, they will "wrap around".**
  In the picture below, notes C and G are selected in a custom scale. The Catch Zone Size is set to ±250 cents. Since the Catch Zone for the C note extends also to the left outside the display, the Catch Zone "wraps around" visually and continues from the B note down to the A# note. Since the Scale is repeated downwards and upwards for every octave, the result of this setting is that the Catch Zone for the C note will cover the B and A# notes in every octave.



The Catch Zones for the selected notes C and G in a custom scale, with the C note Catch Zone "wrapped around" to cover also notes B and A#.

Setting Correction Speed



The Correction Speed parameter controls how fast the Input Pitch should be adjusted to the Target Note. The range is from Slow (knob turned fully counter-clockwise) to Fast (knob turned fully clock-wise).

- **For a natural, transparent correction, a setting around the 12 o'clock position is ideal in most situations.**
- **A very fast correction speed will create almost a "stepped" correction.**
  This is the setting of choice for creating the infamous "robot voice" effect known from numerous radio hits.
- **A slow correction speed will make the pitch correction almost unnoticeable during fast passages in the music.**
  This is because the correction won't have time to set in before new incoming pitches are detected.

About the Preserve Expression parameter



The Preserve Expression parameter controls how much vibrato in the input audio should be let through when you use a fast Correction Speed setting (see "Setting Correction Speed").

- **With a minimum Preserve Expression value and a fast Correction Speed there will be almost no natural vibrato left in the pitch corrected voice.**
- **With max Preserve Expression value and a fast Correction Speed the original vibrato is still preserved.**
- **With max Preserve Expression value and a slow Correction Speed the original audio is let through almost unaffected.**

About adding Pitch Bend and Vibrato

It's also possible to add Pitch Bend and/or Vibrato via MIDI while using the automatic pitch correction:

▶ **Select "To Pitch Adjust" in the MIDI Input section.**



This allows for incoming MIDI Pitch Bend and Vibrato (Mod Wheel) data to control the output pitch and to add vibrato to the output signal.

- **Clicking and moving the wheels on the panel will also generate pitch bend and vibrato.**

Using manual pitch correction

It's possible to override the automatic (scale) pitch correction settings with monophonic MIDI note data at any time. This makes it possible to control the desired output pitches either by playing live on a MIDI master keyboard - or by playing back recorded MIDI notes from the Neptune track in the sequencer!

1. **Create a sequencer track for the Neptune device and select the Neptune track in the Track list.**
2. **To allow for MIDI note control of pitch correction, select "To Pitch Adjust" in the MIDI Input section:**



- **When you sing through Neptune and hold down a key on your MIDI master keyboard, the output pitch will correspond to the held MIDI note.**
  As soon as any MIDI note is received by Neptune, the Root Key, Scale and Catch Zone settings will be temporarily ignored. However, the Correction Speed (see "Setting Correction Speed") and Preserve Expression parameters (see "About the Preserve Expression parameter") will still be active.

! **Note that MIDI control of the pitch is monophonic.**

▪ **When pitch correction is controlled via MIDI, the corrected audio signal will also respond to Pitch Bend and Vibrato modulation.**

! **If you transpose pitches several semitones compared to the input pitch, there could be strange formant effects that may or may not be desirable. To make heavily pitched signals sound more natural, you can use the formant correction function described in "Using Formant control".**

! **Note that MIDI control of the pitch correction will only momentarily override the Root Key, Scale and Catch Zone settings. As soon as there is no MIDI Note present, the automatic (scale) pitch correction settings will take over again.**

▶ **It's also possible to generate polyphonic voices (harmonies) via MIDI using the Voice Synth function, see "Using the Voice Synth".**

Using pitch shifting (Transpose)

Pitch shifting basically means altering the pitch of the input audio by a set factor - the transpose value - and output the result. As opposed to pitch correction, pitch shifting can be made on any type of monophonic audio input signal; it doesn't even have to have a regular pitch (tone). Pitch shifting can be used to generate a number of cool effects, for example:

- **Voice doubling effects by using slight transposition of only 5-10 cents.**
- **Adding an additional voice one octave up or down from the original lead vocal.**
- **Creating dark spooky monster voices by transposing speech down heavily.**
- **Creating chipmunk effects by transposing speech up heavily.**

The list goes on...

Use the Transpose function as follows:

1. **Click the Transpose button to activate the Transpose section.**



2. **Adjust the transposition using the Semi and Cent spin controls in the Transpose section.**
   The Transpose range is ±12 semitones with a fine tuning range of ±50 cents.

▶ **If you want to transpose pitch corrected signals, make sure the Pitch Adjust section is on and has the desired parameter settings.**

▶ **If you want to transpose non-pitched signals, such as speech, switch off the Pitch Adjust section.**

Using Formant control


What are formants?

Formants can be described as a sonic "footprint" of an acoustic space. The practical effect of formants could be compared to a multi-peak filter acting on the frequencies in a sound. An acoustic guitar, for example, has a body shape which makes is sound the way it does. The same goes for a human vocal tract (throat and mouth cavity); every human vocal tract has a unique "shape" which gives the voice its character. It is these shapes that produce formants. A big difference between a vocal tract and a guitar body, though, is that the vocal tract changes shape as you sing different vowels. This also means that the formants will change.

When you pitch shift a signal up or down, the formant "multi-peak filter" will move up or down with the signal frequency (just like a traditional synthesizer filter would with full keyboard tracking activated). The result will be a signal that not only is pitched but also changes character. In some situations this might be what you want, but when it comes to pitch shifting vocals you will probably often want the pitch-shifted signal to sound like it's sung by the same person. Therefore, Neptune features a formant control function.

The Formant section in Neptune lets you control the formants so they don't move along with the pitched signals. Neptune continuously samples and analyses the input audio and determines both the pitch and the current formants of the signal in real-time. The formants are then automatically applied to the pitch-adjusted output signal in real-time.

The picture below shows schematic examples of a 500 Hz signal, pitch-shifted down and up one octave respectively, without and with formant correction. The formants are the peaks of the gray dotted lines in the graphs:



Pitch-shifting without and with formant correction applied. The left column shows -1 octave pitch-shifting and the right column +1 octave.

Using the Formant function

When the Formant section is not active, the formants will move along with the pitched signal. On vocals this could generate unnatural "gender change" effects, especially on heavily pitched voices. If this is not the desired effect, you should activate the Formant section:

1. **Activate the Formant function by clicking the Formant button.**



2. **Adjust the Formant shift with the Shift knob.**
   The Shift range is ±1 octave.

- **The default 12 o'clock position means that the formants will be "locked" to the input signal and won't move with the shifted pitches.**
  Used on vocals this will give the impression of the same person singing at the adjusted pitches. (Refer to the picture in the "What are formants?" section for graphical examples of this particular Shift setting.)
- **Turned further counter-clockwise, the formants will be "locked" to the input signal and displaced downwards relative to the input signal.**
  Used on vocals this will give the impression of a more deep male character voice.
- **Turned further clockwise, the formants will be "locked" to the input signal and displaced upwards relative to the input signal.**
  Used on vocals this will give the impression of a more soprano/female/child character voice.

! **Note that Voice Synth has its own separate "built-in" formant correction and is not affected by the Formant section settings.**

Using the Voice Synth

The Voice Synth function lets you use Neptune as a harmony processor to generate polyphonic voices out of a monophonic input signal. The application is similar to how you would use a vocoder, such as the BV512 Vocoder, for example. However, using the Voice Synth in Neptune will produce completely transparent and natural sounding harmonies with pitches controlled from MIDI Note data.

1. **Create a sequencer track for the Neptune device and select the Neptune track in the Track list.**
2. **Click the MIDI radio button to select "To Voice Synth" in the "MIDI" section. Also make sure the Voice Synth volume slider is raised:**



- **When you sing through Neptune and hold down a note or a chord on your MIDI master keyboard, the output pitch(es) will correspond to the held MIDI note(s).**
- **The Voice Synth harmonies will also respond to any Pitch Bend and Vibrato modulation.**


! **The parameters in the Pitch Adjust, Transpose and Formant sections are ignored by the Voice Synth.**

▶ **You can mix Pitched Signal with the Voice Synth signal in the Mixer section. If you only want the Voice Synth sound, lower the Pitched Signal fader.**

Panel parameters

On the front panel of Neptune, you will find the following parameters and displays:

Level Meter and Bypass/On/Off switch



Parameter	Description
Bypass/On/Off switch	In Bypass mode, the input signal passes through unaffected to the main outputs of the device. The separate Voice Synth outputs are automatically muted. In On mode, the device outputs the processed signal. If the Voice Synth is used, its output signal are routed to the separate Voice Synth outputs. Off mode mutes the inputs, silencing the device.
Level meter	Shows the input signal level.

Bend and Vibrato wheels

! **Choose what the Bend and Vibrato wheels should control by selecting desired destination in the MIDI Input section - see "MIDI Input".**



- **The Pitch Bend wheel is used for bending the pitch of notes, much like bending the strings on a guitar or other string instrument.**
- **The Vibrato wheel can be used for applying vibrato to pitch corrected signals or to the Voice Synth harmonies.**

Most MIDI keyboards have Pitch Bend and Modulation controls. Use these to control pitch bend and vibrato, or use the wheel controls on the panel by clicking and moving the mouse.

Bend Range

The Range parameter sets the maximum amount of pitch bend, i.e. how much it is possible to change the pitch by turning the wheel fully up or down. The maximum range is ±12 semitones (±1 octave). You change the value by clicking the spin controls above of the display.

Vibrato Rate

Use the Rate knob to set the rate of the vibrato controlled by the Vibrato wheel.

Input signal type



Here, you define the characteristics of the input signals you use.

Low Freq

Activating Low Freq mode will ensure more accurate tracking of low-frequency audio signals, such as bass voices. Low Freq mode is suitable for input frequencies below the note F1, which is approximately 44 Hz. The detection in Low Freq mode will work down to approximately 22 Hz which corresponds to note F0.

! **Note that the pitch detection latency will be somewhat longer in Low Freq mode due to the longer cycles times of low frequency signals.**

Wide Vibrato

If your input audio has a heavy vibrato, this can cause Neptune to detect the wrong pitches. The result can be wobbling notes, unwanted swoops and glides etc. Activating the Wide Vibrato button will make the pitch detection ignore any vibrato in the input audio, eliminating the problems.

Note however that the vibrato can still be retained in the processed sound, by raising the Preserve Expression parameter (see "About the Preserve Expression parameter").

Live Mode

This is an ultra-fast tracking mode, perfect for when you want to monitor your pitch adjusted signal in real-time. However, we recommend that you turn this off when it's time to play back and mix your recordings, for the highest audio quality.

MIDI Input



The MIDI Input section features a radio button which allows you to route incoming MIDI to either of the following destinations:


Pitch Adjust

Routes incoming MIDI Note data to the Pitch Adjust section for manual control of pitch correction, see "Using manual pitch correction". Pitch Bend and Vibrato (Mod Wheel) MIDI data will also be routed to the Pitch Adjust section.

Voice Synth

Routes incoming MIDI Note data to the Voice Synth for generating additional harmony voices, see "Using the Voice Synth". Pitch Bend and Vibrato (Mod Wheel) MIDI data will also be routed to the Voice Synth.

Pitch Adjust section



Pitch Adjust section On/Off

Click the Pitch Adjust button to activate/deactivate the Pitch Adjust section.

Root, Scale and Keyboard

Set the Root key and Scale with the spin controls. You can also create your own custom scales by selecting individual notes in the Keyboard display. See "Setting Root Key and Scale" for more details on how to use these functions.

Scale Memory

The purpose of Scale Memories is to allow for automation of different Root Key, Scale and Catch Zone settings. A selected Scale Memory slot automatically stores which Root Key and Scale notes are active. The Scale Memory slots also store Catch Zone settings.

The edits you make of the Root, Scale and Catch Zone parameters are automatically stored in the selected Scale Memory slot. The settings of the Scale Memory are saved together with the rest of the Song data. Refer to "About the Scale Memory" for details on how to use the Scale Memory slots.

Catch Zone Size

With the Catch Zone Size slider you set the range of the input pitches to be corrected to specific notes. Refer to "Setting Catch Zone Size" for details on how to use this function.

Correction Speed

Set the time is should take to adjust the pitch to the set scale. See "Setting Correction Speed" for more details.

Preserve Expression

Set how much vibrato in the input audio should be let through when you use a fast Correction Speed setting. See "About the Preserve Expression parameter" for more details.

Transpose section



Click the Transpose button to activate the Transpose section. When active, the output pitch will be transposed according the settings of the Semi and Cent parameters. The Transpose function can be used either on pitch corrected signals (with the Pitch Adjust section active) or on non pitch corrected signals (with the Pitch Adjust section deactivated).

Semi and Cent

Set desired transposition value, in semitones and cents, with the spin controls. The range is ±12 semitones and ±50 cents.

See "Using pitch shifting (Transpose)" for more details.

Formant section



Click the Formant button to activate the formant control function. When active, the formants of the input signal will be preserved and won't move with the adjusted output pitches.

! **The Formant section settings have effect on the Pitch Adjust section and on the Transpose section, if they are active. However, the Formant section can also be used stand-alone to only displace the formants of the input signal.**

Shift

Use the Shift knob to displace the formants within an range of ±1 octave.

See "What are formants?" and "Using the Formant function" for more details.

The Output Mixer section



The Pitch Adjust and Voice Synth parameters control the output from the Neptune in the following way:

Pitched Signal

This slider controls the total output volume of the Pitch Adjust, Transpose and Formant sections routed to the Left and Right outputs (see "Audio Out").

Voice Synth

This slider controls the output volume of the Voice Synth routed either to the main Left and Right outputs or to the separate Voice Synth Left and Right outputs if these are connected (see "Voice Synth Out").

! **Note that the Voice Synth function must be activated, otherwise this control will have no effect - see "Using the Voice Synth".**

Connections

Flipping the Neptune around reveals an array of connection possibilities. Some of these are CV (control signal) related and some are audio signal related.



Sequencer Control

Note

The Note input allows you to control the pitch of either the Pitch Adjust or Voice Synth (depending on what is currently selected in the MIDI Input section - see "MIDI Input"). The pitch could be controlled from a Note CV output of a Matrix or an RPG-8, for example.

! **A Gate signal on the Gate input (see below) must also be present for the Note Input to work.**

Gate

The Gate input should be used in combination with the Note modulation input (see above). As soon as a gate signal is present, any note modulation on the Note input will be activated. The Gate could be controlled from a Gate CV output of a Matrix or an RPG-8, for example.

CV In

These control voltage (CV) inputs can be used for modulating various Neptune parameters from other devices. The inputs control the following parameters:

Bend

The Pitch Bend input allows you to control pitch bend of either the Pitch Adjust or Voice Synth (depending on what is currently selected in the MIDI Input section - see "MIDI Input"). The pitch bend could be controlled from a Pitch Bend CV output of an RPG-8, for example.

Vibrato

The Mod Wheel input allows you to control the Vibrato amount of either the Pitch Adjust section or Voice Synth (depending on what is currently selected in the MIDI Input section - see "MIDI Input"). The Vibrato could be controlled from a Mod Wheel CV output of an RPG-8, for example.

Formant

The Formant Shift input allows you to control the Shift parameter in the Formant section from a CV source on another device. The Formant Shift parameter accepts bipolar control signals (-63 to +64).

CV Out

These control voltage (CV) outputs can be used for modulating other device parameters from Neptune:

Pitch

The Pitch output allows you to control the pitch of other devices from the Pitch Adjust section, either directly or via the Transpose section (depending on if Transpose is active or not). The Pitch CV corresponds to the pitch of the pitch adjusted and transposed signal. The Pitch output could be connected to the OSC Pitch CV input of another synth device, for example.

Amplitude

Neptune features an internal envelope follower. The Amplitude output sends out a control signal from this envelope follower based on the audio input level to Neptune. The Amplitude output could be connected to the Master Volume or Level CV input of a synth device, for example.

Audio In

Route your audio input signal(s) to the Left (and Right) audio input(s) to the right on the rear panel.

! **If you want to use Neptune in mono, connect only to the Left input.**

Voice Synth Out

Connect to these outputs if you want to break out the audio from the Voice Synth as separate signals and, for example, route to a separate Mix Channel for separate processing.

! **When these are connected, the Voice Synth audio will be removed from the main Audio Out outputs.**

Audio Out

The Left and Right outputs are the main stereo outputs of Neptune. Here, the audio from the Pitch Adjust, Transpose and Formant sections are routed. If the Voice Synth Sep Output (see "Voice Synth Out") are not connected, the Voice Synth audio output are also routed to the main outputs.

! **If you want to use Neptune in mono, connect only to the Left output.**




Pitch adjustment tips and tricks

With Neptune you can use the pitch adjustment effects separately or in various combinations to generate different types of pitch effects. In this section a number of useful setups are described.

Using automation for temporary pitch correction

To get the most natural-sounding results from Neptune you can use automation in the sequencer to momentarily apply pitch correction only where it's necessary on the audio track. The example below shows a lead vocal track which sounds great most of the time, but has a few flat passages that we want to correct.



1. **Use Neptune as an Insert Effect on the lead vocal track.**

Between the middle of bar 13 and bar 15 there are a couple of flat notes that need to be corrected slightly. Between the middle of bar 23 and bar 27 there are some notes that we want to change several semitones.

2. **Create a sequencer track for the Neptune device.**
3. **Set the Pitch Adjust button parameter to "Off" and create an automation lane for the parameter.**
   This will allow you to switch on and off pitch correction automatically.
4. **Set the desired Scale or click the notes you want to use on the virtual keyboard.**
5. **Adjust the Correction Speed and Preserve Expression parameters to values that will make the pitch correction sound natural.**
6. **Activate the Formant section so that any adjusted pitches will have the original formants preserved.**
7. **Create an automation clip and change the Pitch Adjust button parameter to "On" between the middle of bar 13 and 15.**
   This will switch on pitch correction only in these bars.

In bar 23-27 we want to change some pitches several semitones. We can't use the automatic pitch correction here because this would correct the pitches to the closest notes in our scale and that is not what we want here. We could create a new custom scale in another Scale Memory slot and use here, but the easiest would be to just override our scale with MIDI notes.

8. **Change the Pitch Adjust parameter to "On" in bars 23-27.**
   This will switch on pitch correction again in these bars.
9. **Next, make sure that the MIDI Input in Neptune is set to "Pitch Adjust".**
   This ensures that any incoming MIDI notes will control the Pitch Adjust section (and not the Voice Synth).
10. **Place the sequencer Song Position Pointer at bar 23 and start recording on the Neptune note lane.**
    Record the new notes from your MIDI master keyboard at bar 23 through bar 26.

Now, pitch correction has been applied only where necessary on the audio track. In bar 13-15 pitch correction was automatically applied using a defined scale, and in bar 23-27 the automatic pitch correction was overridden by MIDI notes.

▶ **If you like, you could freeze your pitch processed track with the effects - see "About "freezing" pitch adjustments on audio tracks".**

Hard pitch correction of a vocal track

1. **Use Neptune as an Insert Effect on the vocal audio track.**
2. **Use a suitable scale setting and set the Correction Speed parameter to max and Preserve Expression to minimum in the Pitch Adjust section.**
   If needed, adjust the Scale to fit the song key. If necessary, override certain passages manually with MIDI (see "Using automation for temporary pitch correction" above for a practical example).

- ▶ **If you want to control the pitch adjustment via your MIDI keyboard, create a sequencer track for the Neptune device and select the Neptune track in the Track List.**
- ▶ **If you like, you could freeze your pitch processed track with the effects - see "About "freezing" pitch adjustments on audio tracks".**

Pitch correction with changed voice character

If you want to pitch-correct your lead vocal but make is sound like another person is singing, you can easily do that:

1. **Set up the Pitch Adjust section for automatic pitch correction as desired (see "Using automatic pitch correction").**
2. **Activate the Formant section.**
3. **Adjust the Shift parameter up or down to change the voice character of the output.**
   Adjust down to generate a deeper (male) character and up to create a more soprano-like female character.

Octave dub

1. **Use Neptune as a Send Effect in the Main Mixer Master Section.**
2. **Turn off the Pitch Adjust section and activate the Transpose section.**
3. **Set the Semi parameter to +12 to transpose up 1 octave.**
4. **Play back, or input audio in real-time on your mixer channel.**
5. **Use the Send FX control on the mixer channel strip to balance the level of the octave-shifted voice.**

- ▶ **Use the Formant Shift control to make the transposed voice sound more natural (or unnatural, if that's what you want).**

Pitch-shifting drums (non-pitched input)

1. **Route the drum sound to the audio input(s) of Neptune.**
2. **Turn off the Pitch Adjust section and activate the Transpose section.**
3. **Set Semi and Cent parameters to desired values.**

- ▶ **Use the Pitch Bend control for special bend effects.**
- ▶ **Activate the Formant section and experiment by shifting the formants if you like.**

Speech effects

To create various types of atonal speech effects you can use the Transpose section, alone or together with the Formant section:

1. **Make sure the Pitch Adjust section is deactivated (off).**
2. **Activate the Transpose section.**
3. **Set desired transposition ratio with the Semi and Cent spin controls in the Transpose section.**
   Adjust down to generate a darker voice and up to create a brighter voice.

- ▶ **To lock the formants and thus preserve more of your voice's original character, activate the Formant section and set the Shift parameter to the 12 o'clock position.**
  To change the voice character, adjust the Shift parameter down to generate a bassier (male) character and up to create a more soprano-like female character.
- ▶ **Experiment with different combinations of Transpose values and Formant Shift values to create different "characters".**

About "freezing" pitch adjustments on audio tracks

In all examples below that describe pitch adjustments of recorded audio tracks, you can choose to "freeze" the tracks afterwards. By using the Bounce Mixer Channels function you can have your pitch processed audio track rendered to a new track in the sequencer, complete with pitch adjustment effects and all. Just be sure to use the following settings in the "Bounce Mixer Channels" dialog:

- **Range to Bounce: "Song" (to get the entire track rendered, if that's what you want)**
- **Bounce to: "New Tracks in Song"**
- **Apply Mixer Settings: "All" or "All except fader section" (to include the pitch adjustment effects)**

Refer to "Bouncing Mixer Channels" for more details.

Chapter 56
Pulveriser

Introduction



Pulveriser is a very versatile stereo in/out compression+distortion+filter device, capable of mangling any sound literally beyond recognition, but also capable of producing more subtle musical effects. Pulveriser features a wonderful compressor, coupled with a nice warm distortion, plus a multi-mode filter. The different sections of Pulveriser can be modulated by an LFO and by an Envelope Follower to allow for really organic modulation effects. Pulveriser also features a Dry/Wet mix control so you can utilize parallel processing in the unit itself, i.e. mix in the processed signal in parallel with the dry signal - great for parallel compression of drum loops etc.

About the Patch format

Pulveriser features programmable effect presets. Included are a number of factory Patches which can be used as they are or provide you with a good starting point for further tweaking.

Patches use the file extension "*.pulver". Loading and saving Patches is done in the same way as for instrument devices.

Parameters

Pulveriser contains three main effect sections; Squash (compression), Dirt (distortion) and Filter (multi-mode filter with cutoff and resonance controls). In addition, Pulveriser features two modulation sections - an LFO with selectable waveforms and an Envelope Follower which can modulate the effect sections. The parameters in each section are as follows:

Common effect device parameters

While the specific parameters for the Pulveriser effect device are described below, some features and procedures are common to all effect devices. Please, refer to "Common effect device features" for information about the Bypass/On/Off switch.

Note, however, that the Input Meter is different on the Pulveriser device. Instead of the standard multi-segment LED indicator found in other Reason effect devices, Pulveriser features a red lamp which reflects the intensity of the input signal.

Signal Routing selector




With the Signal Routing selector to the bottom left on the front panel you determine the signal flow through Pulveriser:

- **Squash > Dirt > Filter**
  This setting puts the compressor before the distortion and filter sections in series:



  In this configuration the compressor and distortion affect the entire unfiltered input signal.

- **Filter > Squash > Dirt**
  This setting puts the filter before the compressor and distortion sections in series:



  In this configuration the compressor and distortion affect the filtered input signal. This way you can define what frequencies should enter the compressor and distortion sections.

The Squash section



The Squash section is where you set the compression of the signal - from subtle compression to heavily "pumping" effects.

Squash

The Squash knob affects compression ratio, threshold and make up gain in a nice and musical way.

Release

The Release knob controls the compressor release time. If you set this to a fairly low value and have the Squash amount fairly high, you will get that nice "pumping" compression effect.

The Dirt section



The Dirt section is where you can add distortion to the signal - from gentle to screaming outrage.

Dirt

The Dirt knob controls the level of distortion.

Tone

The Tone knob controls a lowpass filter. Turned fully clockwise the filter is completely open, letting all frequencies through.

The Filter section



The Filter section features five different filter types. Each filter type has controls for Frequency and Peak (resonance amount).

Filter selector

Select one of the following different filter types (or bypass):

- **Bypass**
  This will let the input signal through the Filter section unaffected.
- **Lowpass 24**
  This is a lowpass filter with a slope of 24dB/octave, similar to the LP24 lowpass filter in the Subtractor (see "24 dB Lowpass (LP 24)" in the Subtractor chapter).
- **LP12+Notch**
  This is a lowpass filter with a slope of 12dB/octave, in series with a notch filter. The cutoff frequency of the lowpass filter and the center frequency of the notch filter are the same. Changing the Frequency control will generate sort of an "animated" effect.
- **Band Pass**
  This is a bandpass filter similar to the BP12 filter in the Subtractor (see "Bandpass (BP 12)" in the Subtractor chapter.
- **High Pass**
  This is a highpass filter with a slope of 12dB/octave, similar to the HP12 filter in the Subtractor (see "Highpass (HP12)" in the Subtractor chapter.
- **Comb**
  This is a comb filter similar to the "Comb +" Filter in Malström (see "Comb + & Comb –" in the Malström chapter).

Frequency

The Frequency knob controls the cutoff frequency or center frequency depending on selected filter type.

Peak

The Peak knob controls the resonance amount.

The Tremor section



The Tremor section in Pulveriser is an LFO which can modulate the Filter Frequency parameter and/or the main output Volume parameter. The Tremor section features the following parameters:

Rate

Controls the LFO rate. The Rate range in Pulveriser is very wide and can reach way up in the audio frequency range. The rate can also be synced to the sequencer tempo by clicking the Sync button to the right (see "Sync" below). In sync mode, the Rate knob controls the sync resolution.

As a special feature, the rate can also be modulated from the envelope follower in the Follower section, see "The Follower section".

Waveform selector

Select one of nine LFO waveforms. Apart from standard waveforms (sine, triangle, square etc.) there are random, non-linear and stepped waveforms. The shape of the waveforms are shown in the display and reflect how the modulated signal is affected.

Sync

Click the Sync button to synchronize the LFO Rate to the main sequencer tempo. In Sync mode the LFO cycle is also synced to the sequencer, which means that the LFO cycle chases the current sequencer position.

Control the sync resolution with the Rate knob, see "Rate" above.

Spread

The Spread button introduces a stereo effect by modulating the left and right audio channels with two LFO signals phase shifted 180 degrees in relation to each other. This means that you are able to generate kind of a "roto-speaker" effect to the processed signal.

Lag

The Lag control acts like a lowpass filter on the LFO signal, making the LFO signal smoother. This is especially noticeable on waveforms with sharp edges or transients like the square, sawtooth and stepped waves. On the sinewave you will barely notice any effect since it's already "smooth" by nature.

Modulation Amount knobs

On either side of the Tremor section are two bipolar modulation amount knobs, with zero modulation at the 12 o'clock position. Since the modulation parameters are bipolar it means that if the knob is in the "-" sector it will invert the LFO wave shape. This is especially useful in LFO Sync mode where you can define the "direction" of the modulation in relation to the sequencer playhead.

- ▶ **Turn the left knob to control the modulation of the Frequency parameter of the Filter section.**
- ▶ **Turn the right knob to control the modulation amount of the wet signal of the Volume parameter.**
  This will introduce a tremolo effect to the Wet signal fed via the Volume control.

! **Note that the Dry signal in the Blend section is never affected by the tremolo effect! This means that if the Blend knob is set to fully Dry, there won't be any tremolo effect of the volume.**

The Follower section



The Follower section features an envelope follower which analyzes the amplitude of the incoming signal and outputs a modulation (CV) signal that corresponds to the incoming audio level. The modulation signal can then control the Frequency parameter in the Filter section and/or the LFO Rate parameter in the Tremor section. The Follower section features the following parameters:

Trig

Click/hold the Trig button to manually trig/gate the envelope follower. Clicking/holding the Trig button will make the envelope follower output a modulation signal according to the settings of the Attack and Release parameters described below. If you hold the Trig button for a longer period than the Attack time, the Follower will output maximum CV signal level. When you then release the Trig button, the CV signal level will drop according to the Release time and continue to follow the audio input signal level instead.

Threshold

This defines at which input signal level the envelope follower should trig. Set to a low value, the envelope follower will react as soon as there is any audio signal present on the Pulveriser inputs. Set to a high value, the envelope follower will react only on loud input signals, or from a manual Trig signal.

The red lamp to the right of the Threshold knob gives a visual indication of the CV signal level.

- **On the back of Pulveriser you will find a Follower CV output - this delivers the CV signal from the envelope follower, allowing you to dynamically control parameters in other devices.**

Attack

This controls how fast the envelope follower should react after the input signal has reached above the Threshold value. Note that the attack time can only be increased compared to the input signal - never shortened.

Release

This controls how fast the envelope follower CV signal should drop to zero after the input signal has decreased below the Threshold value. Note that the release time can only be increased - never shortened.

Modulation Amount knobs

To the left of the Follower section are two bipolar modulation amount knobs.

▶ **Turn the upper left knob to control the modulation of the Rate parameter of the Tremor section.**
If the modulation knob is in the "+" sector the rate will increase according to increased audio level. If the modulation knob is in the "-" sector the rate will decrease according to increased audio level.

If Sync is enabled in the Tremor section, the rate will jump between the different resolutions according to the Follower modulation amount.

! **Modulating the Tremor Rate in Sync mode can produce noise when the Rate parameter switches between resolutions. This noise can be eliminated by increasing the Lag amount in the Tremor section, see "Lag".**

- **Turn the lower left knob to control the modulation amount of the Frequency parameter of the Filter section.**
  If the modulation knob is in the "+" sector the Filter Frequency will raise according to increased audio level. If the modulation knob is in the "-" sector Filter Frequency will drop according to increased audio level.

Blend




With the Blend knob you control the mix between the dry and wet signal. With the knob set somewhere in between the Dry and Wet position you will have parallel processing. This can be useful if you, for example, want to process a drum loop with compression (Squash) and distortion (Dirt) and mix the processed signal with the dry before sending it to the outputs.

Volume



With the Volume knob you set the total output level of the dry+wet signals.

Modulation inputs and outputs



CV Modulation inputs

On the back of Pulveriser you will find CV inputs for controlling the following parameters:

Squash

Use this for dynamically changing the amount of compression in the Squash section.

Dirt

Use this for dynamically changing the amount of distortion in the Dirt section.

Filter Frequency

Use this for dynamically changing the Frequency parameter in the Filter section.

Tremor Rate

Use this for dynamically changing the LFO Rate parameter in the Tremor section.

If the LFO is in Sync mode, the rate will jump between the different resolutions according to the CV modulation input signal amount.

Volume

Use this for dynamically changing the output volume from Pulveriser.

Follower

Use this for controlling the envelope follower signal from an external source. The internal envelope follower signal is replaced with the CV signal that is inserted here.

! Note that the Attack and Release controls can still be used to shape the CV input signal.

Audio Modulation inputs

! Note that these modulation inputs accept audio rate signals, which is really cool!

Filter Frequency

Use this for dynamically changing the Frequency parameter from an external audio signal. The result of this modulation is Filter FM.

Volume

Use this for dynamically changing the output volume from an external audio signal. The result of this modulation is amplitude modulation (AM) of the Pulveriser output signal.

CV Modulation outputs

Follower

On this output the control signal from the Follower is present.

Tremor

Here, the LFO CV signal from the Tremor section is present.

Demolition tips and tricks

Don't restrict yourself to using Pulveriser as a basic compressor or distortion unit - you may be surprised to find how often Pulveriser can add power, warmth, color and "movement" to your sounds. Here are some examples:

Beef up your sounds

Use Pulveriser to fatten up your sounds:

1. **Select the Low Pass 24 filter type in the Filter section.**
2. **Set the Frequency parameter to a low value so you can barely hear the lowest frequencies.**
3. **Set the Threshold, Attack and Release knobs in the Follower section to minimum values.**
4. **Slowly increase the Follower > Filter Amount knob until you can hear the lower frequencies of the sound.**
5. **Adjust the Blend knob until you are satisfied with the mix.**
6. **Adjust the Blend, Squash and Dirt knobs to fine-tune the sound.**

Make your pads tremble

Use Pulveriser to create movements in your pad sounds:

1. **Select the Comb filter type in the Filter section.**
2. **Set the Peak knob in the Filter section to a fairly low value.**
3. **Turn the Tremor > Filter Modulation amount knob past the 12 o'clock position.**
4. **Set the Tremor Rate knob to around the 10 o'clock position.**
5. **Set the Threshold, Attack and Release knobs in the Follower section to minimum values.**
6. **Set the Follower > Tremor Amount knob to around the 2 o'clock position.**
7. **Set the Tremor > Volume knob to around the 3 o'clock position.**
8. **Play a pad sound which has long Attack, Decay and Release times and a fairly low Sustain value on its amp envelope.**
   Notice how the Tremor Rate and intensity change and modulate the filter and volume according to the pad volume.

Chapter 57
Quartet
Chorus Ensemble

Introduction




Quartet Chorus Ensemble is a fabulous sounding chorus device, with four different characteristic chorus/ensemble algorithms. Each of the four algorithms can have their own unique parameter settings - including the Dry/Wet parameter - so you could switch between the algorithms and get the exact result you are looking for.

Quartet is designed to be used mainly as an insert effect, for spicing up individual instrument sounds with nice dense choruses and modulations.

Panel reference


Global controls

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Routing



▶ **Click the Routing selector to select "Stereo" or Dual Mono" from the pop-up menu.**
Stereo: With this selected the L+R input signals are mixed before being sent into the stereo effect. This means you can connect a mono input signal and get stereo output signals.

Dual Mono: The L+R input channels are processed independently.


Width



The Width control can be used for setting the stereo width - from mono to nice and wide stereo.

! **Note that the Width parameter can be set individually for each of the four chorus algorithms.**

Dry/Wet



This controls the mix of the dry and processed signals.

! **Note that the Dry/Wet parameter can be set individually for each of the four chorus algorithms.**

! **Note that all chorus/ensemble effects require some amount of dry signal to produce the desired effect. Therefore, 100% Wet also includes a certain amount of dry signal.**


▶ **If you are using Quartet as a send effect you would probably want to have the Dry/Wet knob set to 100%.**


Chorus



The Chorus effect algorithm simulates multiple detuned "copies" of the input signal. The Chorus is basically a delay line with adjustable feedback. The principle is to split the input signal in two, run one signal dry and the other through the delay line, and then sum the two signals.

The picture below shows the basic principle of the chorus:





Delay



Here you set the delay time between the dry and processed signals. In practice, this determines where the notches/peaks will appear in the frequency spectrum.

Range: 1.00-30.00 ms

Mod Depth



This determines the depth of the LFO modulation, i.e. by how much the delay time should be modulated. If you set this to 0, the delay time will be static (most effective if you add some feedback).

Mod Rate



This determines the frequency of the LFO modulating the delay time. The higher the value, the faster the sound will oscillate.

Range: 0.10-5.00 Hz

Feedback




This governs the amount of effect signal fed back to the input, which in turn affects the intensity and character of the chorus effect. Turning this towards 100% produces a flanger type of effect with a pronounced resonance “tone”, while keeping it around 50% produces a more gentle chorus effect.


BBD




The BBD is a bucket brigade delay line which simulates vintage ensemble effects. Historically, the bucket brigade delay line was built up by a series of (analog) capacitors, that were clocked to consecutively transmit signals, via one capacitor at a time, thus creating a delayed signal. The BBD algorithm in Quartet features three chorus effects in parallel, and therefore provides a much richer and denser effect than the Chorus algorithm.

The picture below shows the basic principle of the BBD algorithm:





Delay



Here you set the delay time between the dry and processed signals. The delay is preset scaled between the three delay lines. In practice, this determines where the notches/peaks will appear in the frequency spectrum.

Range: 1.00-30.00 ms

Mod Depth



This determines the depth of the LFO modulation, i.e. by how much the delay time should be modulated. If you set this to 0, the delay time will be static (unless you are using Noise Mod, see "Noise Mod").

! **If Mod Depth and Noise Mod (see "Noise Mod") are both set to 0, the Width control (see "Width") has no effect.**

Mod Rate



This determines the frequency of the LFO modulating the delay time.

Range: 0.20-10.00 Hz


Noise Mod



This amplitude-modulates the signal with lowpass filtered noise, and generates a kind of "sparkling" effect.

! **If Noise Mod and Mod Depth (see "Mod Depth") are both set to 0, the Width control (see "Width") has no effect.**

FFT



The FFT algorithm simulates a type of chorus/ensemble effect by utilizing noise modulation of the signal partials. First the signal is analyzed using FFT (Fast Fourier Transform) and converted to a representation in the frequency domain. Then, the partials are modulated by noise to achieve a very nice and dense ensemble effect.

FFT Size




This sets the accuracy (and speed) of the frequency analysis. "1" is the fastest detection and preserves transients in the signal - but this also leaves out detection of low frequencies. "4" is the most accurate detection. However, it's also slower since it also detects low-frequency material (which takes a little longer to detect).

Mod Depth




This determines the depth of the noise modulation of the signal's partials. The parameter controls a combination of noise amplitude and bandwidth. The result also depends on the Frequency Range parameter (see "Frequency Range").

The picture below shows how the Mod Depth parameter affects the partials at full Frequency Range:




Frequency Range




The Frequency Range parameter determines which part of the frequency range should be noise-modulated and which part should be left unaffected.


- **Set the desired Frequency Range by dragging either "handle" sideways.**



- **To move the Frequency Range while maintaining the currently set bandwidth, drag the area between the "handles" sideways.**




The picture below shows how the Mod Depth parameter affects the partials in the signal at two different Frequency Range settings:




The first example shows the modulation of the partials at full bandwidth. The second example shows the partial modulation with the lower Frequency set to a higher value. In the second example, only the upper partials are modulated. The lower partials are left unaffected.

Grain



The Grain algorithm generates an ensemble effect by "extracting" grains from the input signal in real-time and then cross-fading through the grains in various ways. The method is similar to the "Long Grains" algorithm used in the Grain Sample Manipulator device in Reason. The picture below shows the principle for the Grain algorithm:



An example of a signal generated from 5 grains of the input signal.

Phase



The Random Phase function randomly alters the phase of the grains to create a “bubbly” kind of effect, caused by phase cancellation. This is especially noticeable when the Jitter parameter (see “Jitter”) is set to a low value.

Size



This controls the grain length. High values produce a more smooth effect, whereas low values generate more of a “stuttering” effect.

Mod Depth



This randomly changes the initial pitch of the grains.

Jitter



The Jitter function modulates the grain playback position randomly. The Jitter function can be great for generating chorus-like effects and to make a sound more “alive”, depending on the other settings.

Density



The Density function is a combination of grain size, playback rate and the amount of grain overlap. High values produce a really fat and dense chorus/ensemble effect, whereas low values generate a “thinner” effect.

Connections



CV Input

Mod Depth

This CV input can be used for modulating the Mod Depth parameter in the different algorithms. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

! **Note that the CV Modulation is global for the Mod Depth control in all algorithms.**

Width

This CV input can be used for modulating the Width parameter in the different algorithms. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

! **Note that the CV Modulation is global for the Width control in all algorithms.**

Dry/Wet

This CV input can be used for modulating the Dry/Wet parameter in the different algorithms. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

! **Note that the CV Modulation is global for the Dry/Wet control in all algorithms.**

Input Left & Right

▶ **Patch the audio signals you want to process here.**
If your input signal is in mono, connect only to the L (left) input.

! **Note that the result also depends on the current Routing setting (see "Routing").**

Output Left & Right

These are the audio outputs.

! **Note that the result also depends on the current Routing setting (see "Routing").**

Chapter 58
Ripley Space Delay

Introduction



Ripley Space Delay combines delay and reverb with powerful sound shaping and deep modulation for delay effects with character.

At its heart Ripley Space Delay is a stereo delay with a unique band filter in the feedback loop, a lush reverb, and several effects (including noise, drive, sample rate & bit reduction, and EQ) for coloring your sound. Combined in different ways you can get everything from clean and digital taps and warm analog delay to crazy lo-fi chirps and washed out ambiances. Coupled with extensive modulation options, Ripley Space Delay is a delay design playground.

Panel overview

The Ripley Space Delay front panel contains the following sections:




The Ripley Space Delay front panel sections.

- **1. Delay section.**
- **2. Feedback Filter section.**
- **3. Reverb section.**
- **4. Patch selector (for browsing, loading and saving patches).**
- **5. Noise section.**
- **6. Distortion section.**
- **7. Bitcrusher section.**
- **8. Output section.**
- **9. EQ section.**
- **10. Ducking section.**
- **11. Modulation and Modulation Matrix sections.**

Signal flow

The picture below shows the signal flow in Ripley Space Delay:



Ripley Space Delay signal flowchart.

- **The green patch points in the picture above indicate where the routable sections (Noise, Dist, Digital, EQ, and Ducker) could be routed.**

Panel reference

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

The Delay section



The Delay section features parameters relating to delay time, tempo sync, feedback, wobble and stereo behavior.

Sync, Keep Pitch and Dual Delay buttons




- **Click the Sync button to enable Tempo Sync, which affects the "Delay Time" parameter(s).**
- **Click the Keep Pitch button to eliminate pitch changes when the delay times are changed.**
  Note that the pitch will change if you are changing Multiply values, though (see "Multiply")
- **Click the Dual Delay button to get separate delay times for the Left and Right channels (see below).**

Delay Time



- **Drag up/down in the display, or turn the Time knob. to change the delay time. Alternatively, repeatedly click the Tap button to manually tap the desired delay time.**
  Range: 2-5000 ms. In Sync mode, the range is 1/128 to 8/4.



- **In Dual Delay mode, drag up/down in the respective L/R display, or set the time for the respective channels with the Time L and Time R knobs.**
  Alternatively, repeatedly click the Tap buttons to manually tap the desired delay time for the Left and Right channels respectively.
  Range: 2-5000 ms. In Sync mode, the range is 1/128 to 8/4.

Multiply



- **Set the Multiply selector to 1/2 to reduce the delay Time(s) and Offset by half, or to X2 to double the Time(s) and Offset values.**

! **Note that changing the Time Multiply parameter always re-pitches the delayed signal (one octave up or down), regardless of the Keep Pitch parameter setting. This simulates the characteristic "octave effect" found in old delay effects.**

Offset



- **Set the delay time offset between the left and right channels.**
  Setting a delay offset is perfect for creating stereo delay effects.

Feedback and Freeze



- **Turn the Feedback knob to set the number of delay repetitions.**
  At zero Feedback there will only be a single repeat. Unity gain is achieved at 100%, where the delay repetitions will be infinite. If you increase the Feedback beyond 100% the gain will increase for every repeat so a distorted signal is produced. You can limit the level/distortion using the "The Feedback Limiter".
  Range: 0-130%
- **Click the Freeze button to freeze the audio currently in the delay buffer.**
  This will cause infinite repeats of the delay repetitions and also stop new audio from entering the delay buffer - great for temporary stutter/loop effects, and also for creating special time/pitch effects using the "Multiply" function.

Wobbler



This emulates a tape speed wobbling effect where the speed of the "tape" (and consequently, the pitch of the signal) wobbles randomly.

- ▶ **Set the wobble amount with the knob.**
  Note that the pitch will always wobble, regardless of if the Keep Pitch function is active or not.

Ping Pong



With Ping-Pong enabled, the stereo position of each delay repeat will alternate between the left and right channels. The Pan knob determines the stereo width as well as the position of the initial repeat. When the Pan knob is set to full Left, the first delay repeat will be panned hard Left, the second will be panned hard Right, the third repeat will be panned hard Left, and so on. When the knob is set to full Right, the order is reversed (R > L > R etc).

Delay Width



- ▶ **Set the desired stereo width of the Delay output signal with the Delay Width knob.**

The Feedback Filter section



The Feedback Filter makes it possible to filter the delay repeats so that each repeat is filtered slightly differently. A great example of this is the "dub delay" effects you could achieve with tape echo effects back in the day.

The Feedback Filter has two (internal) modes:

- **Band mode**
  The Band mode features eight fixed bandpass filters where you can control the level of each band.
- **Hi-Lo mode**
  The Hi-Lo mode features a single bandpass filter, where you can set the lower and upper cutoff frequencies to create a filter band.

! **It's also possible to process the feedback signal by connecting external devices to the "External Feedback Loop Send & Return L&R" jacks on the rear panel. Any added effects device(s) will be connected in series before the Feedback Filter, i.e. they will not bypass the Feedback Filter.**

The Band mode



- **Click or drag the level bars of each frequency band to get the desired initial frequency response of the delay repeats.**
  Note that for each repeat the frequency response is altered slightly.

! **Note that setting high levels (above the center line) of the bands will increase the volume for each "loop", which could cause loud volumes! As a protection, you can use the Feedback Limiter function, see "The Feedback Limiter".**

- **Turn the Freq Shift knob to shift all the filters up or down in frequency, changing the character of the feedback signal.**
  This parameter can also be modulated from the "The Modulation Matrix", for phaser-like sweeps and special effects.
- **Turn the L/R Offset knob to offset the frequencies of the Left and Right channels, to create a stereo effect.**

The Low/High mode



- **Drag either edge of the band horizontally to set the cutoff frequencies.**
- **Drag the entire "frequency band" horizontally to change the band's position.**
- **Drag the Low Cut and Hi Cut "boxes" up/down to change the cutoff frequencies.**

The Feedback Limiter



The Feedback Limiter is useful if you have set high levels of the bands in Band mode (see "The Band mode"). Activating Feedback Limiter will reduce the levels of any "overdriven" filter bands. The Feedback Limiter also prevents loud volumes in external feedback loops (see "External Feedback Loop Send & Return L&R").

The Reverb section



The Reverb section contains a lush stereo reverb with selectable routing and width control.

- **Set the reverb level with the Amount knob.**
- **Set the reverb time with the Decay knob.**
- **Set the reverb "room size" with the Size knob.**
- **Click the Parallel button, or the routing image, to switch between Serial and Parallel processing of the delay and reverb effects.**
- **Set the desired stereo width of the reverb signal with the Space Width knob.**

The Noise section



The Noise section allows you to add noise to the signal - or to amplitude-modulate the signal by noise - to simulate the noise of old hardware echo machines, for example. At the bottom of the Noise section you can choose where to apply the noise in the signal chain.

- **Set the noise level with the Amount knob.**
- **Set the noise frequency content with the Character knob.**
- **Add high-frequency noise (before running the signal through the Noise Type section) with the Hi End knob.**

- **Select noise type with the Noise Type selector.**
  The hand-crafted Noise Types simulates various types of noises, spanning from High Frequency (HF) noise down to Low Frequency (LF) Noise.
- **Click the Stereo button to get the noise effect in stereo.**
- **Click the triangular routing selector to choose one of the following destinations for applying the noise:**
  "Input" applies the noise to the audio inputs of Ripley Space Delay.
  "Feedback" applies the noise to the Feedback Filter section.
  "Delay Out" applies the noise to the Delay Out signal.
  "Space Out" applies the noise to the Reverb Out signal.
  "Output" applies the noise to the main output signal.
- **See the "Signal flow" picture to see the patch points.**

The Distortion section



The Distortion section allows you to distort the signal. At the bottom of the Distortion section you can choose where in the signal chain the distortion should be applied.

- **Set the distortion character with the Tone knob.**
- **Set the distortion mix level with the Dry/Wet knob.**
- **Set the overdrive amount with the Drive knob.**
- **Click the triangular routing selector to choose where to insert the distortion to the signal:**
  "Input" applies the distortion to the audio inputs of Ripley Space Delay.
  "Delay Out" applies the distortion to the Delay Out signal.
  "Space Out" applies the distortion to the Reverb Out signal.
  "Output" applies the distortion to the main output signal.
- **See the "Signal flow" picture to see the patch points.**

The Digital section



The Digital section allows you to add digital distortion (sample rate and bit reduction) to the signal. At the bottom of the Digital section you can choose where in the signal chain the distortion should be applied.

- **Set the sample rate with the Rate Crush knob.**
  Setting a lower sample rate will cause aliasing, which adds inharmonic overtones to the signal.
- **Set the bit depth with the Bit Crush knob.**
  The lower the bit depth, the more digitally distorted the signal.
- **Click the triangular Output routing selector to choose where to apply the bitcrushing:**
  "Input" applies the rate/bit crushing to the audio inputs of Ripley Space Delay.
  "Delay Out" applies the rate/bit crushing to the Delay Out signal.
  "Space Out" applies the rate/bit crushing to the Reverb Out signal.
  "Output" applies the rate/bit crushing to the main output signal.
- **See the "Signal flow" picture to see the patch points.**

The EQ section



The EQ section features low and high shelving bands with fixed frequencies, plus a parametric mid band. At the bottom of the EQ section you can choose where in the signal chain the EQ should be applied.

- **Low Gain**
  Defines how much the level of the fixed frequency low band should be boosted (positive values) or lowered (negative values).
  Range: +/-18 dB
- **Freq**
  This determines the center frequency of the EQ mid band, e.g. at which frequency the level should be decreased or increased.
  Range: 61.0 Hz to 12.69 kHz
- **Gain**
  Specifies how much the level of the mid band (Freq) should be boosted (positive values) or lowered (negative values).
  Range: +/-18 dB
- **Q**
  This governs the width of the affected area around the set mid band (Freq) frequency. The higher the value, the narrower the affected frequency range.
- **High Gain**
  Defines how much the level of the fixed frequency high band should be boosted (positive values) or lowered (negative values).
  Range: +/-18 dB

- **Click the triangular Output routing selector to choose where to apply the EQ to the signal:**
  "Input" applies the EQ to the audio inputs of Ripley Space Delay.
  "Delay Out" applies the EQ to the Delay Out signal.
  "Space Out" applies the EQ to the Reverb Out signal.
  "Output" applies the EQ to the main output signal.
- **See the "Signal flow" picture to see the patch points.**

The Output section



The Output section consists of a Dry/Wet knob and an Output Gain knob.

- **Set the relation between the unprocessed and the processed signal with the Dry/Wet knob.**
  If you use Ripley Space Delay as a send effect, set the Dry/Wet knob to 100% Wet.
- **Set the output level with the Output Gain knob.**
  Range: -Inf to +18.1 dB

The Ducker section



Ducking attenuates the level of the Wet (processed) signal until the amplitude of the Dry signal drops, at which time the Wet signal is faded back in. This is useful for adding the effect to the silence that comes after you have played/sung your lovely lead line. The effect will be attenuated while you are still playing/singing so you will avoid muddling up the sound.

- **Set the ducking level of the effect signal with the Amount knob.**
  At 100%, the effect signal will be completely silent as long as there is a signal coming into Ripley Space Delay. The ducking attenuation level is shown by the orange bar below the Amount knob.
- **Click the triangular Output routing selector to choose where to apply the ducking effect:**
  "Delay Out" applies the ducking to the Delay Out signal.
  "Space Out" applies the ducking to the Reverb Out
  "Output" applies the ducking to the main output signal.
- **See the "Signal flow" picture to see the patch points.**

The Modulation and Modulation Matrix sections



The Modulation and Modulation Matrix section consists of two separate LFOs, one Envelope Follower and a Macro & Matrix section. All four sections can be active at the same time.

LFO 1 & LFO 2



An LFO (Low Frequency Oscillator) is used for generating cyclic modulation. The LFO section features two separate general purpose LFOs, that can be assigned to control selectable Destination parameter(s) in the Modulation Matrix section, see "The Modulation Matrix".

- **Click the LFO 1 or LFO 2 buttons to access the parameters for the respective LFO.**
  LFO 1 and LFO 2 are identical in functionality.
- **Select an LFO waveform by clicking the spin controls to the right of the waveform display, or by dragging up or down in the display.**
  Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.

! **All LFO signals are bipolar (+/-), except for the Exponential Pulse, which is unipolar (+).**

- **Set the LFO frequency with the Rate knob.**
- **Click the Beat Sync button to sync the LFO to the main sequencer Tempo.**
  The Rate parameter now controls time divisions.
- **Turn the Phase knob to adjust the phase of the LFO waveform.**
  Range: +/-180 degrees
- **Assign the desired Destination parameters in the Modulation Matrix, as described in "The Modulation Matrix".**
  The LFO signal affects the assigned Destination parameters of the Modulation Matrix according to the orange bipolar level indicator. The center of the indicator represents the zero level of the LFO signal:



Follow



The Envelope Follower allows for modulation based on the level of an audio signal. The modulation can be assigned to control selectable Destination parameter(s) in the Modulation Matrix section, see "The Modulation Matrix".

- **Select modulation source from the Source drop-down.**
  The sources are: Input signal, Delay Out signal, Space Out signal, the Freeze Button and the Macro Button.
- **Set at which input signal level the envelope follower should trig with the Sens knob.**
  Set to a low value, the envelope follower will react as soon as there is any signal present at the selected Source. Set to a high value, the envelope follower will react only to loud input signals - or when triggered from the Freeze button or Macro button signal, if any of these are selected as Source.

  Range: +/-12 dB

- **Set how fast the envelope follower should react after the input signal has reached above the Sens value with the Rise knob.**
  Note that the Rise time can only be increased compared to the input signal - never shortened.
- **Set how fast the envelope follower should drop back to zero after the input signal has decreased below the Sens value with the Fall knob.**
  Note that the Fall time can only be increased compared to the input signal - never shortened.
- **Assign the desired Destination parameters in the Modulation Matrix, as described in "The Modulation Matrix".**
  The envelope follower signal affects the assigned Destination parameters of the Modulation Matrix according to the orange unipolar level indicator. The center of the indicator represents the zero level of the envelope follower signal:



Macro & Matrix



The Macro & Matrix allows for modulation controlled by the Macro Button and Knob, or by a number of other selectable Sources. The modulation can be assigned to control selectable Destination parameter(s) in the Modulation Matrix section.

1. **Select the desired Source(s) in the Modulation Matrix:**



2. **Select the desired Destination parameters and modulation Amounts in the Modulation Matrix:**



- **Click the Button to activate, or click the LED above the Button to trigger momentarily.**

The Modulation Matrix



The Modulation Matrix section in Ripley Space Delay is derived from the one in other Reason instrument devices, so if you are familiar with Reason you will quickly find your way around in Ripley Space Delay's Modulation Matrix.

There are three "Source –> Destination 1 –> Destination 2 –> Scale" buses.

A Source parameter can modulate two Destination parameters per bus. Each bus also has a Scale parameter that affects the relative modulation Amount for the Destinations.

! **Note that the Source column is only available in the Macro & Matrix mode (see "Macro & Matrix"). In the other modes the LFOs and Envelope Follower are the default modulation Sources.**

▶ **Note that it is possible to assign the same source parameter as Source in several buses. This allows you to control more than one Destination parameter from the same Source.**

1. **In Matrix & Macro mode, select the desired Source parameters by clicking the corresponding Source box and selecting from the list.**

The following parameters can be used as modulation Sources:

Parameter	Description
LFO 1/2	This allows you to modulate parameters from LFO 1/2.
Env. Follower	This allows you to modulate parameters from the Envelope Follower signal.
Macro Knob	This allows you to modulate parameters from the Macro Knob.
Macro Button	This allows you to modulate parameters from the Macro Button.
Constant	This sends out a constant value.
Ducker Follower	This allows you to modulate parameters from the Ducker modulation signal.
CV1/2 Inputs	This takes the current value on the CV 1 and CV 2 inputs on the rear panel and sends to the desired destination(s).

Modulation Matrix Source parameters

2. **Set the Amount for the Destination 1 by clicking and dragging vertically in the corresponding AMT box.**

! **Note that the Amount range is +/-100. This means that the Amount value can exceed the modulated parameter's range. When this happens, the modulated parameter simply stays at its extreme value until the Amount value gets within the parameter's range again.**

3. **Click the desired Destination box and select the Destination parameter from the list.**

The following parameters can be used as modulation Destinations:

Parameter	Description
Delay: Delay Time	This affects the Delay Time parameter in "single delay" mode.
Delay: Time Offset L-R	This affects the Time Offset L-R parameter.
Delay: Time Multiplier	This affects the Time Multiplier parameter.
Delay: Feedback	This affects the Feedback parameter.
Delay: Feedback Offset L-R	This affects the "under the hood" Feedback Offset L-R parameter which allows the Left and Right delay signals to have their own separate feedback.
Delay: Ping Pong Pan	This affects the Ping Pong Pan parameter (if Ping Pong is active).
Delay: Freeze	This affects the Freeze button. The Freeze parameter is activated as soon as the Source modulation level is >50% (>64).
Delay: Delay Level	This affects the "under the hood" Delay Level parameter, which controls the output level from the Delay section.
Delay: Wobbler Amount	This affects the Wobbler Amount parameter (if Wobbler is active).
Delay: Delay Width	This affects the Delay Width parameter, which affects the delay stereo spread.
Delay Dual: Delay Time L	This affects the Delay Time L parameter in Dual Delay mode.
Delay Dual: Delay Time R	This affects the Delay Time R parameter in Dual Delay mode.
Delay Dual: Delay Pan L	This affects the "under the hood" Delay Pan L parameter in Dual Delay mode.
Delay Dual: Delay Pan R	This affects the "under the hood" Delay Pan R parameter in Dual Delay mode.
Delay Dual: Delay Level L	This affects the "under the hood" Delay Level L parameter in Dual Delay mode.
Delay Dual: Delay Level R	This affects the "under the hood" Delay Level R parameter in Dual Delay mode.
Feedback Filter: Lo Cut Frequency	This affects the Lo Cut Frequency parameter in Low/High mode in the Feedback Filter.
Feedback Filter: Hi Cut Frequency	This affects the Hi Cut Frequency parameter in Low/High mode in the Feedback Filter.
Feedback Filter: Hi & Lo Frequency Shift	This affects the Frequency Band position in Low/High mode in the Feedback Filter.
Feedback Filter: Band Frequency Shift	This affects the Frequency Shift parameter in Band mode in the Feedback Filter.
Feedback Filter: Band Offset L-R	This affects the Offset L-R parameter in Band mode in the Feedback Filter.

Parameter	Description
Feedback Filter: Band 1-8 Level	This affects the respective Band Level parameters in Band mode in the Feedback Filter.
Feedback Filter: Band Odd Level	This affects the “under the hood” levels of the odd (1-3-5-7) Bands in Band mode in the Feedback Filter.
Feedback Filter: Band Even Level	This affects the “under the hood” levels of the even (2-4-6-8) Bands in Band mode in the Feedback Filter.
Space: Space Amount	Affects the Amount parameter in the Space section.
Space: Space Decay	Affects the Decay parameter in the Space section.
Space: Space Width	Affects the Space Width parameter in the Noise section.
Noise: Noise Amount	Affects the Amount parameter in the Noise section.
Noise: Noise Character	Affects the Character parameter in the Noise section.
Noise: Noise High End	Affects the Hi End parameter in the Noise section.
Noise: Noise Stereo	Affects the Stereo button in the Noise section.
Dist: Dist Dry-Wet	Affects the Dry/Wet parameter in the Dist section.
Dist: Dist Tone	Affects the Tone parameter in the Dist section.
Dist: Dist Drive	Affects the Drive parameter in the Dist section.
Digital: Digital Dry-Wet	Affects the Dry/Wet parameter in the Digital section.
Digital: Digital Bit Crush	Affects the Bit Crush parameter in the Digital section.
Digital: Digital Rate Crush	Affects the Rate Crush parameter in the Digital section.
EQ: Low Gain	Affects the Low Gain parameter in the EQ section.
EQ: Mid Frequency	Affects the Freq parameter in the EQ section.
EQ: Mid Gain	Affects the Gain parameter in the EQ section.
EQ: Mid Q	Affects the Q parameter in the EQ section.
EQ: High Gain	Affects the High Gain parameter in the EQ section.
Modulation: LFO 1/2 Rate	Affects the LFO 1/2 Rates
Modulation: CV 1/2	This sends out the source modulation value(s) to the CV1/2 Output on the rear panel.
Output: Ducker Amount	Affects the Amount parameter in the Ducker section.
Output: Dry-Wet	Affects the Dry/Wet parameter in the Output section.
Output: Output Gain	Affects the Output Gain parameter in the Output section.

Modulation Matrix Destination parameters

4. **Repeat the procedure from Step 2 for the AMT(2) and Destination 2 parameters.**

5. **If desired, click the Scale box and select a Scale parameter.**
   The available Scale parameters are the same as the Source parameters, see “Modulation Matrix Source parameters”.

   Selecting a source here means the modulation is scaled by that source.


   For example, if you set up a modulation as follows:

Source	AMT	Destination 1	Scale
LFO 1	50	Delay: Feedback	Macro Knob

   then the LFO will modulate the Feedback parameter in the Delay section, but the modulation will be scaled by the Macro Knob in the Macro & Matrix section. When the Macro Knob is at zero, there will be no modulation at all. Raising the Macro Knob will gradually increase the modulation up to the set Amount (50).

- **To clear an assigned Source, Destination or Scale parameter, hold down [Ctrl](Win) or [Cmd](Mac) and click the Source/Destination/Scale box. Alternatively, click the Source/Destination/Scale box and select “Off” from the list.**
- **To reset an Amount value to 0, hold down [Ctrl](Win) or [Cmd](Mac) and click the desired Amount box.**
- **To clear an entire modulation assignment (a whole row), click the circular X button to the right of the corresponding Scale box.**

Connections



Audio jacks

Input L&R

- **Patch the main audio input signal(s) here.**
  If your input signal is in mono, connect only to the L (left) input.

Output L&R

- **Patch the main audio output signal(s) here.**
  If your input signal is in mono, connect only to the L (left) input.

External Feedback Loop Send & Return L&R

- **If you want to route the Feedback signal via external effects, connect the effect here.**
  The signal is tapped and returned before the Feedback Filter in Ripley Space Delay. Any added effects device(s) are connected in series before the Feedback Filter, i.e. they will not bypass the Feedback Filter. If you want to tap the signal in mono, connect only to the L (left) Send and Return input and output.

CV Inputs

These CV inputs can be used for modulating various Ripley Space Delay parameters from external sources (devices). Each input also has an attenuator knob for tuning the modulation range.

Delay Time

- **Modulate the Delay Time parameter (in "single delay" mode) by a CV signal patched to this input.**

Feedback

- **Modulate the Feedback parameter by a CV signal patched to this input.**

Freeze

- **Modulate the Freeze button by a CV signal patched to this input.**

Time Multiplier

- **Modulate the Time Multiplier switch by a CV signal patched to this input.**

Dry/Wet

- **Modulate the Dry/Wet parameter in the Output section by a CV signal patched to this input.**

CV1/2 In

- **Connect the CV signals you want to assign as Sources in the Modulation Matrix.**

CV Outputs

LFO1/2, Envelope Follower and CV1/2 Out

- **Patch these to the desired destinations to modulate parameters in external devices.**
  Note that all CV Outs can send bipolar signals, except for the Envelope Follower, which only sends positive signals.

Chapter 59
RV-9
Reverb Station

Overview



The RV-9 Reverb Station offers both classic reverb effects and new, experimental sounds, in combination with an easy user interface that is quick and intuitive. With the lower panel closed, you get access to patch browsing and the most important parameters for quick tweaks. Open the lower panel for detailed sound sculpting.

RV-9 can be used as an insert effect or as a send effect—especially good if you want several tracks to use the same reverb.

Panel reference

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Common parameters

Reverb Type



The type selector determines the character of the effect, from traditional plates and halls to futuristic Spectral and Granular reverbs. Changing type will also affect which parameters are shown in the lower, foldable part of the panel.

The types are:

Parameter	Description
Room, Hall, Arena and Cathedral	Representations of actual reverberating spaces, differing in size. These use a combination of convolution and algorithmic reverbs.
Spectral	A reverb synthesized using phase vocoder technology, allowing detailed control over the frequency spectrum and resonances.
Granular	Creates a reverb by randomly playing back grains—small bits of the input sound. Results can be glitchy or cloudy depending on the settings.
Echoverb	Combines a straightforward delay with diffusion that gradually turns the echo into reverb.
Plate	Emulates the sound of a mechanical plate reverb.
Spring	Emulates the sound of a spring reverb.

Decay



Affects the length of the reverb. The actual, resulting decay time (shown above the parameter) also depends on other parameters in the lower panel such as Size and the Delay Time for Echoverb.

Low and High Damping



Damping means introducing a filter in the internal reverb feedback, which gradually removes low or high frequencies while the reverb decays.

- **Low Damping is a high pass filter that lets through signals above a frequency. Raising the Low knob means raising this filter frequency, making the reverb tail gradually thinner.**
- **High Damping is a low pass filter that lets through signals below a frequency. Raising the High knob means lowering this filter frequency, making the reverb tail gradually darker.**

Width



The stereo width of the delay. Default is 100% (full width), but it can be effectful to narrow this a bit (or even turn it down to mono, for vintage spring and plate reverb sounds).

Dry/Wet



Sets the balance between dry, unprocessed signal and reverb. When using the RV-9 as a send effect, you typically want this to be set to fully wet; when using it as an insert effect, set it to taste.

! **Note: The Dry/Wet setting isn't stored in patches. This means you can set Dry/Wet as needed and then browse reverb patches without having to change the setting back.**

Ducking section



Ducking lowers the level (and/or the decay time) of the reverb while the input signal level is high. Turn on Ducking with the On button, then set the amount of Level ducking and Decay time ducking with the respective parameters. The LED rings around the knobs indicate the amount of level and decay reduction in real time.

When the input signal level drops, the reverb comes back to normal, quickly or slowly depending on the Recover Time setting. For example, Ducking is great for keeping vocals clear and unmuddled, bringing up the reverb in the pauses between phrases.

Predelay section



The Predelay settings can be found to the left in the lower part of the panel, for all Reverb Types. When turned on, Predelay creates an initial delay before the reverb sets in. This is another way of keeping the dry sound clean and unmuddled by the reverb, but can also be very useful as a rhythmic, special effect. You can set the delay time in ms or as a note value (when the Beat Sync button is on). The predelay time is also indicated by a small arrow at the beginning of the reverb display in most modes.

EQ section



The EQ section can be found in the lower part of the panel, for all Reverb Types. It lets you tailor the sound of the reverb by emphasizing or rolling off frequencies.

The EQ has two parametric bands along with low and high shelving bands. When the EQ button is turned on, the four bands are represented by circles in the EQ curve display.

- **Click and drag a circle to move it, shaping the EQ curve.**
  The numerical readouts above and below the curve display will show the frequency, gain and Q value (for the parametric EQ bands).
- **Hold [Cmd](Mac) or [Ctrl](Win) and click a circle to reset that EQ band.**
- **You can also click and drag a numeric value for an EQ band.**
  This is useful if you just want to change the gain without accidentally changing the frequency, etc.

The frequency ranges of the EQ bands are 63Hz-16kHz (parametric bands), 63Hz-250Hz (low shelving) and 4kH-16kHz (high shelving). Gain range is ±18dB for all bands.

Note: The Spectral Reverb has a separate Spectral EQ, allowing for more extreme shaping of the sound.

Shimmer section



The Shimmer section can be found to the right in the lower part of the panel, for all Reverb Types. Shimmer introduces pitch shifts in the internal feedback loop, gradually adding more pitches to the reverb. The result can be described as glassy, dreamy or even a bit atonal.

Turn Shimmer on with the On button and adjust the amount of Shimmer effect with the Amount parameter. The Shimmer Interval setting determines the initial pitch shift amount:

- **The default Octave setting will transpose the reverb in octave steps, for a harmonically neutral effect.**
- **Fifth and Fourth will transpose the reverb by 7 and 5 semitones respectively, causing new notes to be added to the sound.**
- **Oct. Dwn will transpose the reverb in octave steps downwards.**

Room/Hall/Arena/Cathedral Reverb parameters



The four first Reverb Types (Room, Hall, Arena and Cathedral) use a combination of convolution and algorithmic reverb to emulate actual reverberating spaces. They share the same parameters in the lower panel.

Early Level

Sets the level of the early reflections - the initial part of the reverb that is important for the character. The early reflections are based on convolution, using impulse responses of real locations.

Size

The size of the space. This affects the actual reverb decay time, as shown above the Decay parameter.

Modulation

Introduces slight pitch modulation in the reverb tail. Lowering the modulation amount makes the reverb static and unnatural (which can be cool!); raising it adds a detuned, chorus-y character. A mid setting often feels most natural.

Freeze and Kill

Turning on Freeze will freeze the sound for an infinite reverb tail. While Freeze is on, no input signal will be fed into the reverb (but the dry input sound can be heard if the Dry/Wet parameter is less than 100% wet).

- **During Freeze, clicking the Kill button will cut off the frozen reverb and temporarily open the input to the reverb, letting you "fill" the frozen reverb tail with new sound. The timing of the Kill button click can affect the result greatly.**
- **Turning off Freeze lets the reverb decay normally.**
- **You can also use Kill without Freeze, to abruptly cut off lingering reverb tails. This can be used for effects similar to gated reverb.**
- **Both Freeze and Kill can be triggered via CV on the back panel.**

The Freeze and Kill functions are available for the Room, Hall, Arena, Cathedral and Spectral types.

! **Note that Freeze is implemented differently in Spectral mode. During Spectral Freeze, changes to Damping or Shimmer won't affect the sound.**

Spectral Reverb parameters



The Spectral Reverb uses phase vocoder technology to synthesize a reverb. This allows detailed control over the frequency spectrum and resonances not possible using other techniques.

Early Level

Sets the level of the early reflections - the initial part of the reverb that is important for the character. The early reflections are based on convolution, using impulse responses of real locations.

! **The Early Reflections are not affected by Spectral EQ or Tonal Resonance.**

Size

This sets the size of the FFT used to calculate the reverb. Larger Size means slower, longer and more detailed reverb. Like the regular Size parameter in other Reverb Types, this affects the total Decay time as shown over the Decay parameter.

Spectral EQ

This section presents a number of preset EQ curves that affect the reverb algorithm directly, drastically changing the sound. Select an EQ preset from the popup menu below the display, or step through them by clicking the up/down arrow buttons. The selected curve is shown in the display.

- **The Amount parameter sets how much the reverb sound is affected by the EQ curve.**
- **Shift lets you move the EQ curve "sideways", offsetting the affected frequencies.**


Tonal Resonance

Tonal Resonance lets you "tune" the reverb in musical pitches.

1. **Turn on Tonal Resonance.**
2. **Click one or several notes on the keyboard display.**
3. **Turn up the Amount parameter.**
   This will now damp all reverb frequencies *except* the ones matching the activated keyboard notes (in all octaves). The result is that only the selected notes ring out, turning the reverb into a musical note or chord.

There are four Tonal Resonance Preset buttons, serving as "chord memories". If you turn on different notes in the different presets, you can automate the Preset selection over the course of a song, to fit different song sections and keys.

Granular Reverb parameters



The Granular algorithm randomly plays back grains (small bits of the sound) to create a reverb. This is a very experimental type of reverb where tweaking the parameters can result in really unique sounds.

Grain Length

Sets the length of the grains. Very short grains can result in a smattering, glitchy reverb, while very long grains overlap and smear the sound.

Rate

Sets how often new grains are triggered.

Buffer Size

The Granular Reverb puts sound into an input buffer and reads grains for playback from this buffer. The size of the buffer determines how far back in time the grains can be read, and thus the variation.

P.Mod

Introduces pitch modulation to the grains, creating detuned, swirling effects.

Diffuse

Smears the grain playback, making it sound less glitchy and more like a reverb.

Reverse

Sets the chance of a grain being played backwards, for further variations.

Echoverb parameters




Delay Time

Echoverb is basically a delay effect, and this sets the delay time, either in ms or as a note value (if the Beat Sync button is on). The Decay parameter serves as the Feedback parameter on a delay in this mode.

Diffuse


The Diffuse Amount and Spread parameters turn the plain echo into a reverb by smearing the delay repeats.

Plate parameters



This mode emulates a classic plate reverb. There are four types of plates (1-4) with different acoustic characteristics. The Size parameter equals changing the size of the plate, and also affects the total decay time as shown above the Decay parameter.

Spring parameters



This mode emulates a spring reverb. There are four types of springs (1-4) with different acoustic characteristics. The Size parameter equals changing the length of the spring, and also affects the total decay time as shown above the Decay parameter. Flutter affects the tension of the spring. At low values the reverb tail will be more even and dense, while high settings produce a tremulant flutter.

Connections



Audio jacks

Input L & R

Connect the audio input signals here. If your input signal is in mono, use only the left input.

Output L & R

Connect the audio output signals here. Since the RV-9 generates a stereo reverb, both left and right outputs are typically used (even if the input is in mono).

CV Inputs

The CV inputs let you modulate RV-9 parameters from external sources such as LFO devices or CV outputs on other instruments. Each input has an attenuator knob for tuning the modulation range.

- **The Decay, LF Damp, HF Damp, Dry/Wet and Shimmer Amount CV inputs modulate the corresponding parameters, available for all reverb types.**
- **The Kill and Hold (Freeze) inputs control the Kill and Freeze functions (Room, Hall, Arena, Cathedral and Spectral types), allowing timed effects from a CV sequencer or LFO.**
  Note that the buttons won't light up on the front panel when triggered via these CV inputs.
- **The Spectral EQ Shift, Spectral EQ Amount and Tonal Resonance Amount CV inputs control the corresponding parameters for the Spectral reverb type.**

CV Output

The Ducking CV output lets you modulate a parameter on another device with the ducking signal from the RV-9, creating a kind of sidechaining effect.

- **When no ducking is applied, the output is "high" (it sends a continuous +1.0 CV value).**
- **When Ducking is on, and an input signal is fed into RV-9, the Ducking CV output goes low, down to 0 (depending on the level of the input signal).**
- **When the input signal stops, the Ducking CV signal will rise quickly or slowly, depending on the Recover setting on the front panel.**

Chapter 60
RV7000 Mk II
Advanced Reverb

Overview



The RV7000 Mk II is a high quality reverb processor. It features ten different reverb and echo algorithms, ranging from rooms and halls to special effects. The Mk II version also incorporates a high-quality zero-latency convolution algorithm, which makes it possible to load sampled impulse responses - and even sample and use your own impulse responses!

Since the RV7000 Mk II comes with a number of useful reverb presets, you could simply select one and tweak the most important parameters on the main panel - or you could use the Remote Programmer panel to fine-tune the reverb in great detail.

The RV7000 Mk II also contains an equalizer and a gate section. Both of these are for processing the actual reverb sound, making it possible to get virtually any kind of reverb character, including gated reverb.

About the Patch format

The RV7000 Mk II features programmable effect presets. In the Factory Sound Bank you will find a number of preset Patches which can be used as they are or provide you with a good starting point for further tweaking.

Patches use the Windows file extension "*.RV7". Loading and saving Patches is done in the same way as for instrument devices.

! **Songs and/or Patches that use Convolution (or have an Impulse Response sample loaded) can not be opened in older Reason versions. The same goes for Combi Effect patches that contain RV7000 Mk II in Convolution mode (or with a sample loaded, or with the Combi programmer referencing Convolution parameters).**

! **Convolution patches that use samples only contain references to the samples - not the sample itself. This is the way all sampler devices in Reason work.**

Connections

Typically you connect the RV7000 Mk II as a send effect, as this allows you to use it for processing several different mixer channels. However, it's also possible to use it as an insert effect - use the Dry/Wet control on the main panel to adjust the balance between the dry, unprocessed sound and the reverb. Note:

- **The RV7000 Mk II is a true stereo reverb (except in Convolution mode), which means that it will use the stereo input information when processing both channels (without summing the input channels).**
  It's also possible to use it as a mono in - stereo out effect. Which type of connection to use (mono or stereo in) depends on the material. If the audio sources are in mono (or in stereo but with no important difference between the left and right channel) using a mono input is sufficient.
- **If you want to use RV7000 Mk II's Reverse reverb effect, you should consider connecting it as an insert effect or using a Send on the Mixer, with Pre-fader mode selected (and the channel fader lowered).**
  This is because you typically don't want to hear the dry sound when using the Reverse effect. See "The Gate section".

The main panel




The RV7000 Mk II main panel.

When you create an RV7000 Mk II, only the main panel will be shown. This contains a section for handling patches, on/off buttons for the EQ and Gate sections, the most important reverb parameters and a dry/wet mix control. To select a reverb patch and make coarse adjustments, this is all you need.


The Remote Programmer

Clicking the arrow button next to the "cable slot" on the main panel brings up the remote programmer panel.



This is where you make detailed settings for the reverb. Note:

- **The Edit Mode button to the left determines which section to make settings for, Reverb, EQ or Gate.**
- **Settings are made with the eight dials around the graphic display. The functions of the dials differ depending on the selected Edit Mode and the selected reverb algorithm. Next to each dial, the display shows the name and value of the corresponding parameter.**



- **Not all modes and algorithms use all eight dials. If a dial isn't used in the selected mode, nothing will be shown next to it in the display.**
- **You cannot make settings in the graphic display itself - this is for showing a graphic representation of the selected reverb.**

Reverb algorithms and parameters

Common effect device parameters

While the specific parameters for the RV7000 Mk II effect device are described below, some features and procedures are common to all effect devices. Please, refer to "Common effect device features" for information about the Input meter, the Bypass/On/Off switch and Signal Flow Graphs on the effect device.

About the main panel parameters




On the main panel you find three parameters that are available for all algorithms:

Parameter	Description
Decay	This governs the length of the reverb or the feedback if an echo algorithm is selected.
HF Damp	Controls how quickly the high frequencies should decay in the reverb. Raise it to gradually remove high frequencies, making the reverb sound warmer and less bright.
HI EQ	This is a high-shelving EQ that works much like a typical treble control on a mixer or amplifier. Lower the setting for a softer reverb sound or raise it to get more high frequencies.

Selecting an algorithm

You select a reverb algorithm in the remote programmer panel:

1. **Click the remote programmer arrow button on the main panel to display the remote programmer panel.**
2. **Make sure the Edit Mode button is set to Reverb.**
3. **Use the top left dial to select a reverb algorithm.**
   The selected algorithm is shown in the display next to the dial.



Here's a quick overview of the ten algorithms - for details and parameter descriptions, see below.

Algorithm	Description
Small Space	Emulates a small enclosed space (a small room or a resonant body).
Room	Emulates a room with adjustable shape and wall character.
Hall	Emulates a hall.
Arena	Emulates a large arena, with separate pre-delay for the left, right and center reverbs.
Plate	Emulates a classic plate reverb.
Spring	Emulates a spring reverb, as used in e.g. guitar amplifiers.
Echo	An echo effect with gradually diffusing echo repeats. Can be synced to Reason's tempo.
Multi Tap	A multi-tap delay with four different delay lines and tempo sync.
Reverse	A reverse reverb that "pushes" the dry sound to appear after the reverb. The result is a backwards reverb leading up to the direct sound.
Convolution	The zero-latency Convolution algorithm uses impulse response samples. The samples are used for generating the desired reverb effect (or actually any type of effect - depending on what sample you use).

Small Space

This algorithm places the sound in a small enclosed space, ranging from a tiny resonant body to a room. The parameters are:

Parameter	Description
Size	The size of the emulated space.
Mod Rate	The reverb can be randomly modulated for a more even sound (or for special effects). This parameter sets the rate of modulation (the amount is set with Mod Amount).
Room Shape	Select from four different room shapes, affecting the character of the reverb.
LF Damp	Controls how quickly the low frequencies should decay in the reverb. Raise it to gradually remove low frequencies, making the reverb sound "thinner" and less boomy.
Wall Irreg	Adjusts the positioning of the emulated walls in the small space. The lowest setting emulates two directly opposed walls while higher settings emulate more walls and angles, for a more complex resonance.
Predelay	Sets the predelay time, i.e. the delay between the source signal and the start of the reverb.
Mod Amount	Sets how much the reverb will be modulated. Use fairly low settings when emulating real rooms and resonant bodies, and higher settings for special effects.

Room

Emulates a medium-sized room, with the following parameters:

Parameter	Description
Size	The size of the emulated room.
Diffusion	At low Diffusion settings, you will hear the individual reverb "bounces" more clearly, while higher settings produce a more "smeared", dense and even reverb.
Room Shape	Select from four different room shapes, affecting the character of the reverb.
ER->Late	The first "answers" in the reverb are called early reflections (ER) and are typically more pronounced than the actual reverb tail. This parameter sets the time between the early reflections and the reverb tail. This is set as a percentage - the actual delay time depends on the Size setting.
ER Level	Adjusts the level of the early reflections. "0" is normal level.
Predelay	Sets the predelay time, i.e. the delay between the source signal and the start of the early reflections and reverb.
Mod Amount	Sets how much the reverb will be modulated. Moderate modulation gives a natural, less static sound.



Hall

Emulates a hall. The parameters are the same as for the Room algorithm above (but the Hall algorithm offers larger Size settings).

Arena

Emulates the ambience in an arena or concert hall, with long pre-delay times (separate for left, right and center):

Parameter	Description
Size	The size of the emulated arena or hall.
Diffusion	At low Diffusion settings, you will hear the individual reverb "bounces" more clearly, while higher settings produce a more "smeared", dense and even reverb.
Left Delay	The predelay time for the left side of the reverb.
Right Delay	The predelay time for the right side of the reverb.
Stereo Level	Adjusts the level of the left and right sides of the reverb. "0" is normal level.
Mono Delay	The predelay time for the mono (center) reverb signal.
Mono Level	Adjusts the level of the mono (center) reverb signal. "0" is normal level.

Plate

A classic plate reverb, excellent for vocals for example. The parameters are:

Parameter	Description
LF Damp	Controls how quickly the low frequencies should decay in the reverb. Raise it to gradually remove low frequencies, making the reverb sound "thinner" and less boomy.
Predelay	Sets the predelay time, i.e. the delay between the source signal and the start of the reverb.

Spring

An emulation of a spring reverb as can be found in guitar amplifiers, organs, etc. The spring reverb has the following parameters:

Parameter	Description
Length	Sets the length of the simulated spring.
Diffusion	At low Diffusion settings, you will hear the individual reverb "bounces" more clearly, while higher settings produce a more "smeared", dense and even reverb.
Disp Freq	When sending a signal to a real-life spring reverb, the initial transient will produce a quick, characteristic sweeping tonal noise. This is because different frequencies in the sound are delayed by different amounts (a phenomenon called dispersion). This parameter controls the frequency of that sound.
LF Damp	Controls how quickly the low frequencies should decay in the reverb. Raise it to gradually remove low frequencies, making the reverb sound "thinner" and less boomy.
Stereo (on/off)	Determines whether the output of the spring reverb should be in mono or stereo.
Predelay	Sets the predelay time, i.e. the delay between the source signal and the start of the early reflections and reverb.
Disp Amount	Sets the amount of dispersion effect (see Disp Freq above).



Echo

This is an advanced echo effect, with diffusion controls and tempo sync. When Echo is selected, the Decay control on the main panel controls the echo feedback (the number of echo repeats). The parameters are:

Parameter	Description
Echo Time	Sets the time between each echo. When Tempo Sync (see below) is off, the echo time is set in milliseconds (10 - 2000 ms); when Tempo Sync is on you set the echo time as a number of 1/16 notes or 1/8 triplet notes, in relation to the current song tempo.
Diffusion	When this is set to 0, the echo will sound as a standard delay with clear, precise repeats. Raising the Diffusion setting will introduce additional echoes very close to the "main" echo repeats, causing a "smeared" echo sound. This will also expand the echo stereo image.
Tempo Sync	Determines whether the echo time should be freely set ("off") or synchronized to Reason's tempo ("on").
LF Damp	Controls how quickly the low frequencies should decay in the echoes. Raise it to gradually remove low frequencies.
Spread	Adjusts the spacing of the additional echoes added by the Diffusion parameter. For a very smeared echo (sound more like a reverb), set both Diffusion and Spread to their maximum values.
Predelay	Sets an additional delay time before the first echo repeat.

Multi Tap

The Multi Tap delay produces up to four different delays with separate delay times, panning and level. The whole set of four delay taps can then be repeated at a given rate. Again, the Decay control on the main panel controls the feedback (the number of repeats for the whole multi tap set). All delay times can be tempo synced.

Note: this algorithm is handled a bit differently since you make separate settings for each delay tap:

- **The parameters to the left of the display are common for all taps.**
- **You use the Edit Select parameter in the top right corner to select which tap to make settings for - the three parameters below affect the currently selected tap.**



Tap 2 selected for editing.

- **You can also set Edit Select to "Repeat Tap" - this is where you specify the repeat time for the whole multi tap "package".**
  With short Repeat times, the first tap may be repeated before the last tap has sounded. This can be used to create very complex multiple delay effects.



The common parameters (to the left) are:

Parameter	Description
Tempo Sync	Determines whether the delay times and repeat times should be freely set ("off") or synchronized to Reason's tempo ("on").

Parameter	Description
Diffusion	Raising the Diffusion setting will introduce additional echoes very close to the "main" repeats, causing a "smeared" delay sound.
LF Damp	Controls how quickly the low frequencies should decay in the echoes. Raise it to gradually remove low frequencies.

When Tap 1 - 4 is selected with the Edit Select parameter, you can make the following settings for the selected delay tap:

Parameter	Description
Tap delay	Sets the delay - the time from the source signal to the tap. When Tempo Sync is off, the delay time is set in milliseconds (10 - 2000 ms); when Tempo Sync is on you set the delay as a number of 1/16 notes or 1/8 triplet notes, in relation to the current song tempo.
Tap level	Adjusts the level of the selected tap.
Tap pan	Adjusts the pan of the selected tap.

When Repeat Tap is selected with the Edit Select parameter, there is only one parameter to the right in the display:

Parameter	Description
Repeat Time	Sets the time between each repeat of the whole multi tap set. The number of repeats is set with the Decay control on the main panel. When Tempo Sync is off, the repeat time is set in milliseconds (10 - 2000 ms); when Tempo Sync is on you set the repeat time as a number of 1/16 notes or 1/8 triplet notes, in relation to the current song tempo.

Reverse

The Reverse reverb algorithm in RV7000 Mk II is special in that it actually "moves" the source audio as well. Sounds fed into the Reverse reverb are "sampled", a reverse reverb is created and played back and finally the "sampled" original sound is played back. For example, if you feed a snare drum hit into the Reverse reverb, you will hear a rising "backwards" reverb, followed by the snare drum hit.

Therefore, you probably don't want to hear the first, original (dry) sound. There are two ways to set this up:

- **Connect the RV7000 Mk II as an insert effect and make sure the Dry/Wet control on the main panel is set fully to "Wet".**
- **Connect the RV7000 Mk II as a send effect using one of the Sends on the Mixer, activate the Prefader (PRE) switch for the send and lower the mixer fader completely for the source signal.**
  That way, the signal will be sent to the reverb but the dry sound from the Mixer channel isn't heard. Again, the Dry/Wet control should be set to "Wet".


Note that with this algorithm, raising the Decay setting on the main panel will make the reverse reverb start earlier and build up under a longer time. Similarly, the HF Damp parameter affects how fast the high frequencies are built up in the reverse reverb. In the remote panel, the Reverse algorithm has the following parameters:

Parameter	Description
Length	This sets the time from when the source signal is fed into the reverb until it is played back again. It is during this time you will hear the reverse reverb, as shown in the display. The time can be set in milliseconds or as note values, depending on whether Tempo Sync is off or on. Note: As stated above, the Decay setting determines the length of the actual reverse reverb - in essence how soon it starts after the source signal. But of course, the reverse reverb cannot start *before* the original source signal! If you set Decay to a longer time than the Length setting, the reverse reverb will start abruptly, immediately when the source signal is fed into the reverb. If this sounds complicated, just take a look at the RV7000 Mk II display and try the settings - you will soon see how it works. Note also that very high Length settings demand a lot of processor power. This can be reduced by adjusting the Density parameter, see below.
Density	Density governs the "thickness" of the Reverse effect. If this parameter is turned down to zero, the effect produces individual delays rather than a dense "wash", which can be used as a special effect. Worth noting is that if Density is set to around 50%, this can considerably reduce the CPU load without altering the sound of the effect too much. Exactly how much the Density parameter can be reduced without altering the sound depends on the source material.



Parameter	Description
Rev Dry/Wet	Sets the balance between the "moved" source signal ("dry", low values) and the reverse reverb ("wet", high values).
Tempo Sync	Determines whether the Length setting should be freely set ("off") or synchronized to Reason's tempo ("on").


Convolution




The zero-latency Convolution algorithm uses impulse response samples to generate effects. Basically, "convolution effects" are the results of multiplying the frequency spectra of the input signals with the frequency spectra of impulse response samples, and thus generating a signal with the "character" of the impulse response sample. If the impulse response sample is a recording of the reflections of a large room, for example, the resulting effect will be "the input audio signal played back in a large room".

RV7000 Mk II comes with three built-in preset impulse response samples. You can also use any other samples for the convolution algorithm, to generate all kinds of reverbs and special effects. You can even sample your own impulse responses and use in the convolution algorithm in RV7000 Mk II.

Note that in the Convolution algorithm the input signals for the effect are first summed to mono (except in Parallel Stereo Mode (see "Stereo Mode")) and then processed with the impulse response sample. The figures below shows the signal routings in the Convolution algorithm:



(All Stereo and Mono modes)



(Parallel mode)

In the remote panel, the Convolution algorithm has the following parameters:

Parameter	Description
Sample Preset	Here you select one of the preset impulse response samples - plus your own sample (if you use that, see "Loading impulse response samples").
Length	Sets the length (end point) of the currently used impulse response sample.
Size	Simulates the "size" of the impulse response sample, in practice its pitch, in semitone steps. -12 means pitching up the impulse response sample 1 octave and 12 means pitching it down 1 octave.
LF Damp	Controls how quickly the low frequencies should decay. Raise it to gradually remove low frequencies, making the effect sound "thinner" and less boomy.

Parameter	Description
Stereo Mode	Determines how the output signal should be presented. Note that the stereo effect is derived from the impulse response sample itself. So, the wider the stereo effect in the impulse response sample, the wider the stereo effect in the output. Note that if you use a mono impulse response sample, all effects below will be in mono! Stereo: The input signals are summed and then a stereo effect with a spread of 100% is applied. Stereo75%: The input signals are summed and then a stereo effect with a spread of 75% is applied. Stereo50%: The input signals are summed and then a stereo effect with a spread of 50% is applied. Stereo25%: The input signals are summed and then a stereo effect with a spread of 25% is applied. Mono: The input signals are summed and then the effect is panned to a centered mono signal (0% spread). M->S Slow: From Mono slowly panned out to full Stereo. M->S Fast: From Mono quickly panned out to full Stereo. S->M Slow: From full Stereo slowly narrowed down to Mono. S->M Fast: From full Stereo quickly narrowed down to Mono. Parallel: Individual processing of the two L and R stereo input signals (dual mono).
Predelay	Sets the predelay time, i.e. the delay between the source signal and the start of the convolution effect. A negative predelay masks the start of the sample, so if the sample has unwanted initial transients or silence, these can be "removed".
Gain	Sets the amplification or attenuation of the effect signal.

Below are some things to keep in mind when you are working with the Convolution algorithm:

- **If you want the impulse response sample to play back exactly like the original, make sure the Decay knob is at max, the LF Damp knob at zero and the Hi EQ knob at its 12 o'clock position. Also, make sure the Length parameter is at 100% and the Size parameter at 0.**
- **The Length value of the impulse response sample is also affected by the Decay knob setting.**
  If the impulse response sample is quiet at the end, reduce the Length value to cut it off a little earlier. The Decay parameter introduces a smoother "cutoff" at the end, which might be desirable in many situations.
- **Changing some convolution parameters re-calculates the impulse response in real time. Therefore, modulating these parameters might give unexpected results. Specifically:**

  Using CV to modulate the RV7000 Mk II in Convolution mode is not recommended.

  If you're using the Gate function (see "The Gate section") in combination with Convolution, we recommend setting the Decay Mod parameter to 0 (see "Decay Mod").

Loading impulse response samples

Besides the preset impulse response samples, you can load any other samples into the RV7000 Mk II and use as impulse responses. Loading a sample automatically switches the Algorithm to Convolution.

▶ **Drag and drop a sample onto the RV7000 Mk II panel to automatically load it in the Convolution Algorithm.**

Or, do as follows:

1. **Click the Browse Samples button on the Programmer panel to set browse focus to the RV7000 Mk II.**



2. **Select the desired sample in the Browser and load it.**



Here we have selected and loaded the "Fx_DubHead.WAV" sample to use as impulse response. You can see that the sample name is now displayed to the right of the Preset knob.

! **Note that the maximum length of a sample used as an impulse response is approximately 12 seconds. Longer samples are automatically truncated to 12 seconds (non-destructive).**

! **Note that any embedded loop data in the samples are disregarded when loaded into the RV7000 Mk II!**

! **Note that the Programmer display only shows the first 4 seconds of longer samples.**

▶ **To achieve stereo effects in the Stereo Mode alternatives (see "Stereo Mode") you have to use stereo samples.**

3. **Edit the Convolution parameters on the RV7000 Mk II panel until you are satisfied.**

▶ **If you want to save your RV7000 Mk II patch with your impulse response sample, click the Save Patch button on the upper panel:**



! **Note that the impulse response sample is NOT saved in the patch itself - only a reference to the sample! If you have loaded an external sample (that is not in the Factory Soundbank), you may want to save the patch with the sample in your song. See "About Self-Contained Songs".**

Sampling your own impulse response samples

You can also sample your own impulse response samples and use with the Convolution algorithm. The sampling procedure is the same as for any other sampler device in Reason:

▶ **Click the "Start sampling" button on the Programmer panel to record your own sample:**



! **Note that the maximum length of a sample used as an impulse response is approximately 12 seconds. Longer samples are automatically truncated to 12 seconds (non-destructive).**

! **Note that any embedded loop data in the samples are disregarded in the RV7000 Mk II!**

! **Note that the Programmer display only shows the first 4 seconds of longer samples.**

▶ **To achieve stereo effects in the Stereo Mode alternatives (see "Stereo Mode") you have to sample in stereo.**

Please refer to the "Sampling" chapter for details on how to set up and sample in Reason.

The EQ section



The equalizer in RV7000 Mk II affects the wet reverb sound only and is used for shaping the character of the reverb. There are two EQ bands, one for low frequencies (shelving) and one full-range parametric EQ.

- **To activate the EQ, click the EQ Enable button on the main panel so that the indicator lights up.**
- **To make EQ settings, select "EQ" with the Edit Mode button to the left in the remote programmer panel.**
- **In this mode, the remote programmer display shows a frequency curve, indicating the settings you make with the EQ parameters.**

The parameters are:

Parameter	Description
Low Gain	The amount of cut or boost of the low-shelving filter.
Low Freq	The frequency below which the Low Gain cut or boost is applied.
Param Gain	The amount of cut or boost for the parametric EQ.
Param Freq	The center frequency of the parametric EQ, e.g. at which frequency the level should be decreased or increased.
Param Q	This governs the width of the affected area around the set center frequency. The higher the value, the narrower the affected frequency range.

- **Remember that you have a third EQ band at your disposal - the HI EQ parameter on the main panel.**
  The reason why this is on the main panel and not in the EQ section is simply that it's a setting you may want to adjust often, without having to open the remote programmer panel.

The Gate section



The Gate section allows you to create gated reverb effects with a lot of options and possibilities. You can either trigger the gate from the source audio signal or via MIDI or CV.

When triggering the gate from the source audio signal, it works like this:

- **The gate "listens" to the source (dry) signal and opens whenever the signal reaches a certain threshold level.**
- **The reverb sound is sent through the gate - when the gate is closed you won't hear the reverb.**
- **When the source signal level drops below the threshold level, the gate closes after a time that depends on the Hold parameter and the level of the source signal (see the parameter table).**

▶ **If you need the gate to be open for an exact duration (time), you should trigger it via MIDI or CV.**
In audio trigger mode, the actual gate time will vary depending on the source signal.

When triggering the gate via MIDI or CV, it works like this:

- **The reverb sound is sent through the gate - when the gate is closed you won't hear the reverb.**
- **Whenever the gate receives any MIDI note (sent to the RV7000 Mk II) or a gate signal (connected to the Gate Trig CV input on the back of the RV7000 Mk II), the gate opens for the duration of the note or gate signal.**

Note:

▶ **To activate the Gate, click the Gate Enable button on the main panel so that the indicator lights up.**

▶ **To make Gate settings, select "Gate" with the Edit Mode button to the left in the remote programmer panel.**

▶ **In this mode, the remote programmer display shows two meters - one showing the signal level (with an indication of the threshold level) and one showing the status of the gate.**
This is useful for checking what happens, how the gate triggers, etc.

The parameters for the Gate section are:

Parameter	Description
Threshold	When Trig Source is set to “Audio”, this determines the audio signal level at which the gate opens. If you raise this setting, only very loud sounds will open the gate.
Decay Mod	This modulates the reverb Decay parameter so that the decay time is lowered when the gate closes. When this is set to zero, no decay modulation happens - this means that if the gate is closed and then opened again, you may hear “previous” reverb tails that are still ringing. If you raise the Decay Mod setting, the decay will automatically be lowered when the gate is closed, eliminating this effect.
Trig Source	Determines whether the gate should be triggered by audio or MIDI/CV, as described above.
High Pass	A high-pass filter that affects the audio that triggers the gate (only active when Trig Source is set to “Audio”). If you raise this setting, sounds with low frequencies only will not open the gate. Note that this setting doesn’t affect the sound of the reverb, only the triggering mechanism.
Attack	Determines how long it takes for the gate to open after a triggering signal has been received.
Hold	This parameter is only active when Trig Source is set to “Audio”. Hold affects how quickly the gate closes, in the following way: Internally, the gate is controlled by an envelope follower that analyzes the source signal level and generates a “level CV signal” accordingly. This signal is compared to the Threshold level to determine whether the gate should be opened or closed. The Hold parameter affects how quickly the envelope follower responds when the source signal level drops - you could say that this is the decay control for the envelope follower. The higher the Hold setting, the longer it will take for the envelope follower signal to drop below the threshold level and close the gate. But the resulting time also depends on the source signal level - with a loud signal, it will take longer time for the envelope follower to drop to the threshold level. Therefore, the actual gate time depends both on the Hold setting and on the character of the source audio.
Release	Determines how long it takes for the gate to close after the Hold time.

CV Inputs



On the back of the RV7000 Mk II you find three CV inputs. These are:


Parameter	Description
Decay	Controls the reverb decay or echo/delay feedback via CV.
HF Damp	Controls the HF Damp parameter on the main panel.
Gate Trig	Used for triggering the Gate section with a gate signal. The length of the gate signal determines the length of the gated reverb.

! Using the CV inputs to modulate the RV7000 Mk II in Convolution mode is not recommended.

Chapter 61
Scream 4 Sound Destruction Unit



Scream 4 Sound Destruction Unit



Scream 4 is a very versatile stereo in/out sound destruction device, capable of warping any sound literally beyond recognition, but also capable of producing more subtle musical effects. Scream 4 features a wide range of algorithms for distortion and sound mangling which can be combined with an EQ and a resonant "Body" section to provide everything you need to add an edge to your sounds. This effect is most often used as an insert effect.

About the Patch format

Unlike most of the other effect devices, Scream 4 features programmable effect presets. Included are a number of factory Patches which can be used as they are or provide you with a good starting point for further tweaking.

Patches use the Windows file extension "*.SM4". Loading and saving Patches is done in the same way as for instrument devices.

Parameters

Scream 4 contains three main sections; Damage (distortion and other types of sound destruction), Cut (EQ) and Body (places the sound in a resonant environment - can serve as anything from a cabinet emulator to a wah-wah to completely new special effects) which can be switched on or off independently. The parameters in each section are as follows:

Common effect device parameters

While the specific parameters for the Scream 4 effect device are described below, some features and procedures are common to all effect devices. Please, refer to "Common effect device features" for information about the Input meter, the Bypass/On/Off switch and Signal Flow Graphs on the effect device.

Damage section controls



The "Damage" section is where you specify the basic sound mangling algorithm and make settings to inflict the desired amount of damage to the sound. There are ten basic algorithms to chose from, ranging from classic distortion effects to digital-sounding warping and modulation effects.

There are five controls in this section, with the following functions:

Parameter	Description
Damage button	This switches the Damage section on or off.
Damage Control knob	This controls the input gain which in turn determines the amount of damage inflicted. The higher the value, the more destruction! When raising the Damage Control you may need to lower the Master level to maintain the same output level (and vice versa).
Damage Type knob	This selects the type of effect - see the table below for a description of the available damage methods.
P1/P2 knobs	The functionality of these knobs vary according to the selected Damage Type - see the table below for a description.

Description of the various Damage Type algorithms

Here follows a basic description of the ten Damage Types available, and what parameters the P1/P2 knobs control for each type:

Type	Description
Overdrive	This produces an analog-type overdrive effect. Overdrive is quite responsive to varying dynamics. Use lower Damage Control settings for more subtle "crunch" effects. - The P1 knob controls the basic tone of the effect. Turn clockwise for a brighter sound. - The P2 knob controls Presence. Presence boosts frequencies in the high midrange *before* the distortion stage which in turn affects the character of the distortion. Turn clockwise for more Presence boost.
Distortion	Similar to Overdrive, but produces denser, thicker distortion. The distortion is also more "even" across the Damage Control range compared to Overdrive. - The P1/P2 knobs control Tone and Presence, respectively - see Overdrive for a description.
Fuzz	Fuzz produces a bright and distorted sound even at low Damage Control settings. - The P1/P2 knobs control Tone and Presence, respectively - see Overdrive for a description.
Tube	This emulates tube distortion. - The P1 knob controls Contour, which is somewhat like a high pass filter, changing the tone and character of the distortion. - The P2 knob controls Bias, which changes the "symmetry" of the tube distortion. Setting this to the minimum or maximum value will produce asymmetrical distortion (typical of a real-life tube amplifier), while a 12 o'clock setting will produce symmetrical distortion (odd harmonics only).
Tape	This emulates the soft clipping distortion produced by magnetic tape saturation and also adds compression which adds "punch" to the sound. - The P1 knob controls Speed, which simulates tape running at different speeds. The higher the Speed setting the more of the original high frequency material in the signal. Turn clockwise for a brighter sound. - The P2 knob controls the amount of Compression. Turning the knob clockwise increases the compression ratio.
Feedback	This effect combines distortion in a feedback loop which can produce many interesting and sometimes unpredictable results. Feedback is basically when a sound source is fed back to itself. An open microphone picking up sound from a nearby loudspeaker that is also being used to amplify sound from the microphone will produce a feedback loop with the associated typical howling. For this effect the Damage Control knob controls the gain of the feedback loop. - The P1 knob controls Size, which could be described as the "length" (i.e. the distance between the microphone and the loudspeaker in the above example) of the feedback loop. - The P2 knob controls Frequency, which for this effect determines which overtones will "howl".
Modulate	Modulate first multiplies the signal with a filtered and compressed version of itself, and then adds distortion. This can produce resonant, ringing distortion effects. - The P1 knob controls Ring, which is the resonance of the filter. Turn clockwise for more pronounced ringing effects. - The P2 knob controls Frequency, which is the filter frequency. Turn clockwise to raise the filter frequency which generally produces a sharper, more piercing effect.

Type	Description
Warp	Warp distorts and multiplies the incoming signal with itself. - The P1 knob controls Sharpness. Lower values will produce a soft, compressed distortion, while higher values produces more harmonics and a sharper sound. - An effect of multiplying a signal with itself is that the fundamental pitch is removed from the signal, leaving overtones only. The P2 knob controls Bias - raise this to reintroduce the fundamental pitch in the sound.
Digital	Lo-fi anyone? This reduces the bit resolution and sample rate for raw and dirty sounds or for emulating vintage digital gear. - The P1 knob controls (bit) Resolution. If the knob is turned fully to the right there is no bit reduction, fully the left the resolution is 1-bit. - The P2 knob controls the sample rate. If the knob is turned fully to the right the sample rate is not reduced; turning it to the left gradually reduces the sample rate.
Scream	Similar to Fuzz, but with a bandpass filter with high resonance and gain settings placed before the distortion stage. - The P1 knob controls the basic tone of the effect. Turn clockwise for a brighter sound. - The P2 knob controls the filter frequency. The high resonance setting of the filter makes it suitable for wah-wah effects.

Cut section (EQ)



The sliders in the Cut section are tone controls, allowing you to cut or boost the level by up to 18dB in the low, mid and high frequency areas. The Cut section is activated with the Cut button above the sliders.

Move the slider from the middle upwards to boost the level, and from the middle downwards to cut the level of the corresponding frequency area.

Body section



The Body section is just what it says - it places the sound in a resonant “body”. Depending on the settings, the result can be similar to a speaker cabinet simulator, an auto-wah effect, or effects with no real-world counterpart. The section is based on 5 basic body types, which simulate how a sound is affected by different physical enclosures. The size and resonance of the Body types can be changed, and the section also features an envelope follower.

The Body parameters are as follows:

Parameter	Description
Body button	This switches the Body section on or off.
Body Type knob	This is used to select one of the five available Body types (A-E).
Body Reso knob	This simulates the resonance of the selected Body. Turning the knob clockwise gives a more resonant effect.
Body Scale	The Body Scale parameter could be said to control the "size" of the Body. Note that this is "inverted" - turning the knob clockwise reduces the emulated size.
Auto knob	Determines the amount of envelope follower effect on the Scale parameter - see below.

About the envelope follower

The Body section features an envelope follower for dynamic control of the Scale parameter. The envelope follower analyzes the amplitude of the incoming signal and changes the Scale setting accordingly - the louder the incoming signal the higher the value of the Scale parameter. The operating frequency (or size) range is set with the Scale parameter, and the envelope follower amount is set with the Auto parameter. A typical use for this is auto-wah effects - try Body Type "B" for a pronounced wah effect.

- **On the back of the Scream 4 you will find an Auto CV output - this delivers the CV signal from the envelope follower, allowing you to dynamically control parameters in other devices. See "Creating a real dynamic wah effect with the envelope follower" for an example.**

About the Master level control



The Master level control should be used when you need to increase or decrease the output level, while retaining the basic character of the effect. It can also be used to balance the level between the distorted sound and the "clean" (unprocessed) sound if the effect is to be switched in and out in the mix.

If the output level is too high, turning down the Damage Control setting would lower the output, but it would also change the character of the distortion, as would changing eq or presence settings.

Simply lowering the mixer channel level (for the channel that Scream 4 is connected to) would also work of course, but this would also mean that the level difference between the unprocessed and processed sound would increase.

So if the clip indicator lights up on the Transport, or if the distorted sound is too loud compared to the normal sound, the solution is to lower the Master output level.

As pointed out elsewhere in the manual, audio out clipping (indicated by the red clip indicator lighting up on the Transport Panel) can only happen in the Reason Hardware Interface. In other words, you never have to worry about levels passed internally from device to device. However, bear in mind that if you use high Master output settings (or a lot of boost in the Cut section) Scream 4 can quite easily cause audio out clipping - and that is most likely not a distortion effect you want!

CV inputs and outputs



On the back of the Scream 4 you will find CV inputs for controlling the following four parameters:

- **Damage Control**
  Use this for dynamically changing the amount of damage effect.
- **P1**
  The use for this depends on the selected Damage Type. For example, if the Feedback effect is selected, this will control the Size parameter - connect it to the CV Out on a Matrix or synth LFO for strange, flanger-like sweeps.
- **P2**
  The use for this depends on the selected Damage Type. For example, if the Scream effect is selected, this will control the Frequency parameter, producing a distorted wah wah sound.
- **Scale**
  Lets you control the Scale parameter in the Body section from another CV source, for wah wah-like effects, etc.

In addition, you find a CV output from the “Auto” (envelope follower) function in the Body section. By connecting this to a CV input for a parameter in another device, the level of the signal going into the Scream 4 will affect that parameter. See below for an example on how to use this.

Screamy tips and tricks

Don't restrict yourself to using Scream 4 as a basic distortion stompbox, but try it in as many ways as possible - you may be surprised to find how often Scream 4 can add power, warmth and color to your sounds. Here are some examples:

Creating a heavy drum sound

Scream 4 is ideal for processing drums. Try connecting it as an insert effect to a Redrum device and experiment with the Damage Types and settings.

- **For classic distorted drums, try the Tube, Tape or Distortion algorithms.**
- **The Scream algorithm is excellent for a really raw body or industrial drum sound.**
- **For more weird, synth-like effects, try the Modulation or Warp effects.**

Remember that you don't have to route the whole drum kit through the Scream device - sometimes it may be better to route the individual outputs from the bass drum, snare and/or toms to a Spider Audio Merger (see "Spider Audio Merger & Splitter"), connect the merged output of the Spider to the Scream 4 and route this to a separate channel in the Mixer. That way, hi-hats, cymbals and similar are unprocessed.

Warming up a mix with the Tape effect

If you find your mixes a bit sterile, the Tape algorithm is excellent for providing some warmth and gentle distortion:

1. **Create a Scream 4 device and connect it between the main outputs of the Mixer and the Audio Hardware device.**
2. **Set the Damage Type to Tape.**
   Make sure the Cut and Body sections are turned off.
3. **Start with a low Damage Control setting and P1 (Speed) and P2 (Compression) at 12 o'clock.**
4. **Play back your mix and adjust the settings.**
   Raise the Damage Control for more tape saturation distortion, adjust P1 to get the desired brightness and raise P2 if you want a more controlled, compressed sound. If you like, you could also activate the Cut section and use the three-band EQ to further adjust the sound.

Using the Body section as a sound enhancer/phaser/wah

Nothing stops you from using the Body section on its own, without Damage. Try this:

1. **Create a sampler device (e.g. an NN-19) and select an electric piano patch.**
2. **Select the sampler and create a Scream 4.**
   It is added as an insert effect.
3. **Turn off the Damage section and instead activate the Body section.**

You will find that this adds a resonant character to the sound, which will make it more "alive" and help it stand out in a mix. You should experiment with the Body settings to find the character that suits you best. You could also activate the Cut section- if you e.g. find the sound too bassy, just lower the "Lo" slider a bit.

4. **Flip the rack around and connect the CV out from the sampler's LFO to the Scale CV input on the Scream 4.**
   As you can hear, the Scale is modulated by the LFO.
5. **Adjust the amount of Scale modulation with the pot next to the CV input on the back of the Scream 4, and the speed (and waveform) of the modulation in the LFO section on the sampler device.**
   With this type of modulation setup, it's easy to get lush, dreamy phaser effects. For a more wah wah-like sound, select Body type B and raise the Reso and Scale settings.



Emulating vintage digital gear

The first generations of digital instruments (drum machines, synths and samplers) used 8 or 12 bit sampling and processing, at low sample rates. This "lo-fi" sound is still in high demand, e.g. in hip-hop and R'n'B. Try this:

1. **Connect a Scream 4 as an insert for a Redrum, with a suitable kit selected.**
2. **Set Damage Type to Digital and turn P1 and P2 fully right.**
3. **Play back and lower P1 (bit depth) and P2 (sample rate) to get the sound you want.**
   You may also want to use the Cut section to emphasize or cut frequencies in the sound.

Creating a real dynamic wah effect with the envelope follower

As we have shown, you can get auto-wah-like effects with the Body section in Scream 4 (by using the Auto parameter). You could also use the ECF-42 envelope controlled filter and trigger this with a gate signal - this is after all a "real" filter and sounds even more like a wah effect. However, to get a "real" auto-wah effect that responds to the signal level, you need to combine both these devices:

1. **Create an instrument device that you want to process with an auto-wah.**
   It should be velocity responsive so that the harder you play, the louder it sounds.
2. **Create a Scream 4 device and an ECF-42 device.**
   Both these should now be connected as insert effects to the instrument device.
3. **Turn off all three sections in the Scream 4.**
   This is of course a matter of taste - but here we will show how to use the envelope follower in Scream 4, not its sound destruction capabilities.
4. **Flip the rack around and connect the Auto CV Output on the Scream to the Freq CV input on the ECF-42.**
5. **Lower the pot next to the CV input a bit - the envelope follower is rather sensitive and you probably don't want the filter to open too much.**
   You can adjust this later if needed.
6. **On the ECF-42, select the BP 12 (bandpass) mode and set the Res setting rather high.**
7. **Play the instrument device and adjust the Freq setting on the ECF-42 to taste.**
   As you can hear, the harder (or the more notes) you play, the more the filter will open.

- **If you find the auto-wah too responsive, you could add a compressor between the instrument device and the Scream 4 to even out the level differences a bit.**
- **The Spider CV Merger and Splitter (see "Spider CV Merger & Splitter") can be used to invert and split the Auto CV output for even greater flexibility.**

Chapter 62
Sidechain Tool

Introduction



Sidechain Tool is an all-in-one device for creating that characteristic sidechain pumping effect. Sidechain Tool does both automatic pumping to tempo (no external routing needed!), triggered pumping, and regular sidechain compression. Sidechain Tool is mainly suited as an Insert Effect - on a Mix Channel or Output Bus channel - for rhythmically "ducking" the channel volume. However, you can also use it as a Send Effect, using the Send Mode function.

Panel reference

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Auto Pump/Trigger/Sidechain mode switch



- **Select which mode you want the Sidechain Tool to operate in:**
  Auto Pump uses the built-in ducking curve synced to an internal clock, which can be set to suitable tempo intervals. The clock is automatically synced to the tempo of the main (Reason/DAW) sequencer.

  Trigger mode also uses the built-in ducking curve, but you trigger the ducking either via MIDI notes, from the Sidechain Audio inputs, or from the Trig CV input on the rear panel.

  Sidechain mode uses the built-in compressor, for traditional sidechain compression, see "Sidechain mode specific parameters".

Ducking curve parameters (Auto Pump and Trigger modes)



The ducking curve display and parameters are common to the Auto Pump and Trigger modes.

Here is where you can shape the curve that ducks the incoming audio.

Ducking curve presets



- **Click to select a ducking curve preset.**
  You could then edit and adjust each curve preset to your liking, as described below.

Attack, Hold, Release, Attack Shape, Release Shape and Slide

- **Turn the Attack, Hold, Release, Attack Shape and Release Shape knobs to change the ducking curve shape.**
  Any changes are immediately reflected in the display.
- **Alternatively, click the blue square points in the display and drag to shape the ducking curve.**
  The changes are also reflected by the Attack, Hold and Release knobs to the left of the display:



- **Click and drag the Attack/Release Shape curves to change their shapes.**
  The changes are also reflected by the Attack Shape and Release Shape knobs to the left of the display:



- **Turn the Slide knob to slide the entire curve back or forth, to affect the timing of the ducking:**



Ducking Amount



- **Set how much you want to attenuate (duck) the incoming audio.**
  The attenuation (ducking amount) is reflected by the blue shaded area above the curve in the display.

Auto Pump mode specific parameters


Rate



- **Turn the Rate knob to set the desired repetition rate (time division) of the ducking.**
  Range: 8 bar, 4 bar, 3 bar, 2 bar, 4/4, 3/4, 2/4, 3/8, 1/4, 1/4T, 3/16, 1/8, 1/8T, 1/16, 1/16T and 1/32.


Trigger mode specific parameters

Audio/MIDI switch



- **Select if you want to trig the ducking from an audio input signal connected to the a sidechain input(s) on the rear panel (see "Sidechain Input Left & Right") - or via MIDI Notes (see "MIDI Trigger").**

Audio Threshold



- **Set the desired Threshold level by dragging the triangular "slider" up/down.**
  As soon as the audio on the sidechain input on the rear panel reaches above the set Threshold, the orange Trig indicator lights up above the Rate knob.


MIDI Trigger

To be able to trigger the ducking curve from MIDI Notes, you first have to create a sequencer track for the Sidechain Tool device. In Reason you do that as follows:

1. **Right click the device panel and select "Create track for Sidechain Tool".**
   A sequencer track for the Sidechain Tool has now been created in the sequencer.
2. **Make sure the sequencer track has Keyboard Focus (is selected in the sequencer).**

The default setting when you switch to MIDI Trigger is "All", i.e. any MIDI Note# will trig the ducking curve.

If you like you could change this so that only a specific MIDI Note will trigger the curve:



1. **Click the Note triangle and select "Note" from the popup.**
2. **Click the Learn button and play the desired note on the keyboard.**
3. **When you are satisfied with the selected note, click the Learn button again.**
4. **Play the selected note on the keyboard to trig the ducking.**
   The orange Trig indicator now lights up above the Rate knob.

Sidechain mode specific parameters



In Sidechain mode Sidechain Tool works as a regular sidechained compressor, i.e. it does not make use of the Ducking Curve function. Instead it uses the Gain, Threshold, Attack Release and Ratio parameters to control the built-in compressor.

Gain

- **Set the "drive" of the compression with the Gain knob.**
  This determines how much compression the signal will have in conjunction with the Threshold. Range: ±24 dB.

Listen

- **Click the Listen button to listen only to the sidechain signal (input on the Sidechain Input(s) on the rear panel, see "Sidechain Input Left & Right").**

Frequency band display



By filtering the sidechain signal you can make the compression more or less sensitive to a certain frequency range. A typical application for this is to isolate the bass frequencies of a kick drum, to have the kick drum trigger the compressor. Another typical application is de-essing - where harsh "S"-sounds in vocal material is reduced or eliminated. E.g. for de-essing you should set the frequency "boundaries" to isolate the offending "S" frequencies as much as possible.

- **Click and drag the frequency lines horizontally in the display to set the frequency band of the sidechain signal that should trigger the compressor.**

Threshold

- **Set the level at which onset of compression should occur.**
  When the input level is below the Threshold setting the signal is unaffected. When the input level exceeds the threshold, compression kicks in.

  In practice, this means that the lower the Threshold setting (and the higher the Input Gain), the more compression will be applied. Range: -52 dB to 0 dB


Attack

- **Set how quickly the compressor should apply its effect when signals rise above the set Threshold.**
  If you raise the Attack, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds. Range: 1ms to 1s.

Release

- **Set how long it should take before the compressor lets the sound through unaffected - after the signal level has dropped below the set Threshold.**
  Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics. Range: 20ms to 5.02s.

Compression display



This display shows how the signal is being compressed (attenuated) by the sidechain signal over time.

Ratio

- **Set the amount of gain reduction that should be applied to the signals above the set Threshold.**
  The Ratio can be set from 1:1 (no reduction) to Infinite:1

Common parameters for all modes

Send Mode



- **Click the Send Mode button if you are using Sidechain Tool as a send effect instead of an insert effect.**
  This will make Sidechain Tool send out only the processed signal, without any of the unprocessed signal.


Band Mode



With Band Mode active you can force Sidechain Tool to only duck a certain frequency band of the signal. A typical example would be to have it duck only the bass frequencies when triggered/sidechained from a kick drum.

- **Click and drag the blue dot horizontally in the display to define the desired frequency band to duck.**
  The ducked frequency band is indicated by the shaded blue area in the display.
- **Click the triangular button to select "Lo Band" or "Hi Band".**
  "Lo Band" ducks low frequencies and "Hi Band" ducks high frequencies.

Connections



CV Input

Pump Amount (Auto Pump and Trigger modes only)

- **Modulate the Ducking Amount parameter by a CV signal patched to this input.**

Attack & Shape (Auto Pump and Trigger modes only)

- **Modulate the Attack time by a CV signal patched to the Attack input.**
- **Modulate the Attack curve Shape by a CV signal patched to the Shape input.**

Hold (Auto Pump and Trigger modes only)

- **Modulate the Hold time by a CV signal patched to this input.**

Release & Shape (Auto Pump and Trigger modes only)

- **Modulate the Release time by a CV signal patched to the Attack input.**
- **Modulate the Release curve Shape by a CV signal patched to the Shape input.**

Band Freq

- **Modulate the Frequency parameter (when Band Mode is active) by a CV signal patched to this input.**

Trig CV (Trigger mode only)

- **Modulate the Trig button (in Trigger mode) by a CV signal patched to this input.**

CV Output

Trig, Hold, End (Auto Pump and Trigger modes only)

- **These outputs send out high Gate CV pulses (in Auto Pump and Trigger modes) according to the graphic on the rear panel.**
  Trig is sent at the start of the ducking curve, Hold is sent out at the end of the Hold stage and End is sent out when the curve has finished.

Curve Out & Inverted

- **These outputs send out continuous CV signals according to the current ducking curve or compression value.**
  The Inverted output sends the curve signal values inverted.

! **Note that the Curve Out sends negative CV signals and the Inverted sends positive CV signals.**

Sidechain Input Left & Right

- **Patch the audio signal(s) you want to control the compressor (in Sidechain mode) here.**
  If your input signal is in mono, connect only to the L (left) input.

Input Left & Right

- **Patch the audio signal(s) you want to duck/compress here.**
  If your input signal is in mono, connect only to the L (left) input.

Output Left & Right

These are the stereo audio outputs.

Chapter 63
Softube Amps

Introduction



The Softube Amp at the top and the Softube Bass Amp at the bottom

As from Reason Version 9, the Softube Amp and Softube Bass Amp replace the previously available Line 6 Amps. The Softube Amp and Softube Bass Amp are amplifier and speaker cabinet simulators based on the renowned modelling algorithms developed by Softube. The two devices feature accurate simulations of some of the most coveted vintage amplifier and cabinet models, that you can freely mix and match. Setting up a great amp tone for your guitar or bass is easy, regardless of what type of sound you are looking for.

In this chapter the two devices will be described together using the collective name “Softube Amps”. Where parameters differ between the two devices this will be duly noted.

In Reason the Softube Amp and Softube Bass Amp Rack Extension devices can be found on the Effects palette.

Basic usage

The Softube Amps can be used to process any signal but are best used “live”, i.e. as insert effects on the Audio Track Channel that a live instrument is connected to, so that you can monitor the effect as you play and record.

When recording electric guitar or bass, the basic tonal character of the amp/cabinet very much affects how the instrument responds, which in turn affects your playing. The Softube Amps allow you to set up a good basic tone with a minimum of fuss so you can start recording straight away!

Using a “real” amp requires that you set up the amp tone exactly right prior to recording, as you have very limited means of changing it afterwards. But as Insert FX are transparent in Reason (i.e. they are not a part of the recorded signal) you can tweak the tone, change Amp model etc., as much as you like after recording, right up to the creation of the final mixdown audio file (or Mixer Channel bouncing).

Important note about using the Softube amps as insert effects

- **To use a Softube Amp as an insert fx when you're recording an audio track, you need to monitor through Reason (see "Play in background") - otherwise you won't hear the sound of the Softube Amp during recording.**
  For this to feel comfortable you will want as low latency as possible (see "Buffer Size settings"). With good audio hardware and drivers, you can usually get down to a latency of a few milliseconds, which is about the same delay you'd get standing a meter from a real guitar amplifier.

Front panel

The Softube Amps front panel can be divided into two main sections; the display area with Patch/Amp/Cabinet selectors at the top, and a set of standard amplifier tone controls below. The Amp parameters (tone controls) are described in "Amp panel controls".

Common effect device parameters

While the specific parameters for the Softube Amps are described later in this chapter, some features and procedures are common to all effect devices. Please, refer to "Common effect device features" for information about the Input meter, the Bypass/On/Off switch and Signal Flow Graphs on the Softube Amps.

Using the Softube Amps

Loading and saving patches



Loading and saving patches in the Softube Amps is done in the same way as with any other Reason/Reason Essentials device - see "Sounds, Patches and the Browser" for more details.


Selecting Amp and Cabinet model

There are six basic Amp models to choose from; four in the Softube Amp and two in the Softube Bass Amp. There are also four Cabinet + microphone combination models in the Softube Amp and three Cabinet + microphone combination models in the Softube Bass Amp.

You can use any Amp model with any Cabinet + microphone model. For general model descriptions see "About the Amp and Cabinet models".

Selecting Amp model

- **To select Amp model, click the desired Amp button:**




Amp selectors on the Softube Amp and Softube Bass Amp respectively.

- **To bypass the Amp section, click the Bypass button.**

Selecting Cabinet model

You can use any Cabinet with any selected Amp model.

- **To switch Cabinet model, click the desired Cab button:**



Cabinet selectors on the Softube Amp and Softube Bass Amp respectively.

- **To bypass the Cabinet section, click the Bypass button.**

About the Amp and Cabinet models

Softube Amp

The following Amp models are available in the Softube Amp:

Amp Model	Amp modeled on
Twang	A silvery American classic, great for clean and slightly overdriven guitars. Popular for country, blues and more.
Crunch	British 60's classic that keeps its chiming, present character whether you play it clean or drive it so hard it's on the verge of breaking down.
Rock	A yummy, warm, fat, tube distortion. Just like Mama used to make it.
Lead	The boogie man has come in all his high gain glory! Screaming leads and power chords that sustain for days.

The following Cabinet models are available in the Softube Amp:

Cabinet Model	Cabinet + microphone modeled on
Bright	A 2x12 cabinet with deep lows and heavenly highs. The oh-so-familiar dynamic mic is placed on axis but still lets a hint of room into the sound.
Room	A more midrange present 2x12, with the small diaphragm dynamic mic placed off axis and a wide stereo room added.
Fat	Fat, solid 4x12 classic. Captured with a German condenser microphone on axis for that full bodied sound.
Tight	Slightly midrange scooped 4x12 cabinet. The large diaphragm dynamic microphone gives an in your face presence.

Softube Bass Amp

The following Amp models are available in the Softube Bass Amp:

Amp Model	Amp modeled on
Modern	A contemporary version of a classic tube design from one of the most popular bass amplifier brands. Modern has all the clarity and punch you'd expect from a modern amplifier, but still with the pleasant three-dimensionality that well designed tube amplifiers offer.
Vintage	Got grit? Vintage gives you a dark, dirty, steamy bass sound that adds power and attitude, and helps making the bass instrument cut through the mix.

The following Cabinet models are available in the Softube Bass Amp:

Cabinet Model	Cabinet + microphone modeled on
Dark	A classic 8x10 cabinet with a snappy response across the frequency spectrum. Captured with a German large membrane dynamic microphone, straight on axis for a clear sound and a rock solid low end.
Bright	A British 4x12 bass cabinet with great midrange presence. The dynamic microphone is placed off axis for a slightly roomy sound.
Room	A 4x10 cabinet, captured with a German classic large membrane condenser mic at a distance. Roomy with a nice depth and width that caters for a very natural sound in the mix.

Amp panel controls

Softube Amp



The panel controls are used for tweaking the sound. The following controls can be found in the Softube Amp:

Control	Description
Gate knob	Here you can set a gate threshold for the Softube Amp. Signals below the set threshold are not let through.
Boost switch	This boosts the input gain, for more crunch.
Gain	This controls the input gain. The higher the Gain value, the more crunch you get.
Bass/Mid/Treble controls	These are tone controls which you can use to cut or boost the bass, midrange and high frequencies, respectively.
Poweramp Gain	This is the gain control for the modeled power amp.
Volume	Controls the master volume of the Softube Amp.

Softube Bass Amp



The panel controls are used for tweaking the sound. The following controls can be found in the Softube Bass Amp:

Control	Description
Drive	This controls the input gain. The higher the Drive value, the more crunch you get.
Bass/Middle/Mid Freq/Treble controls	These are tone controls which you can use to control the bass, midrange and high frequencies, respectively. The Bass and Treble controls also have Ultra Lo/Hi buttons for emphasizing the low and hight frequency ranges even further. There is also a Mid Freq selector where you can select different Mid Frequency EQ characteristics.
Volume	Controls the master volume of the Softube Bass Amp.

Connections



- **Both Softube Amps have Left/Right inputs and outputs.**
  If you only connect in mono to the Left input, the output will still be in stereo (if you connect both outputs).
- **The Softube Amp has CV inputs for controlling Gate, Gain and Volume.**
- **The Softube Bass Amp has CV inputs for controlling Drive and Volume.**

Chapter 64
Stereo Tool

Introduction



The Stereo Tool is a stereo widener, which can take a mono source signal and turn it into a big, wide stereo signal without causing any phase problems. You could for example use it for breathing new life into vocals - or for generating stereo signals from mono instrument devices like Subtractor. The Stereo Tool can also be used to further widening stereo source signals.

Panel reference

Widening



- **Set the stereo spread amount with the Widening knob.**
  At 0%, stereo input signals will have the same stereo spread as the original input signals.
  Turn up the knob to make the stereo output signals wider. As opposed to other stereo widening effects, Stereo Tool also works on mono input signals. Note that the stereo widening is achieved without causing any phase problems.

Low Bypass



- **Set how much of the low frequencies in the input signal(s) you want to bypass from the spread effect.**
  This function is great if you only want to widen the higher frequencies of the input signal(s) and keep the lower frequencies unaffected.

Frequency Adjust



- **Adjust the Frequency Adjust knob to change the built-in comb filter frequency.**
  This will change the frequency spectrum of the output signal. Tweak to taste if you, for example, should experience that the signal is louder in one of the stereo channels.
- **Connect a triangle LFO signal to the Frequency Adjust CV input on the rear panel to create kind of a stereo chorus effect, see "Frequency Adjust CV In"!**

Mono



▶ **Click the Mono button to output a mono signal.**
Stereo input signals will also be output in mono.

Connections



CV In

Widening CV In

- **Modulate the Widening parameter by a CV signal patched to this input.**

Frequency Adjust CV In

- **Modulate the Frequency Adjust parameter by a CV signal patched to this input.**
  Connect a triangle LFO signal to create a stereo chorus effect.

Input Left & Right

- **Patch the audio signal(s) you want to process here.**
  If your input signal is in mono, connect only to the L (left) input.

Output Left & Right

These are the stereo audio outputs.

Chapter 65
Sweeper
Modulation Effect

Introduction



The Sweeper Modulation Effect device is a great sounding Phaser/Flanger/Filter device.

By drawing your own unique modulation curve in the display and assigning this curve to the desired effect parameters, you also get a very flexible system for repeatedly sweeping/modulating the effects parameters - in perfect sync with the sequencer.

Sweeper is designed to be used mainly as an insert effect, for spicing up instrument sounds with nice sweeps and modulations, but you could of course use it as you like!

Panel reference

Global controls

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Volume



This is the master volume control.

Routing



- **Click the Routing selector to select "Stereo" or Dual Mono" from the pop-up menu.**
  Stereo: With this selected the L+R input signals are mixed before being sent into the stereo effect. This means you can connect a mono input signal and get stereo output signals.

  Dual Mono: The L+R input channels are processed independently.

Spread



The Spread control detunes the stereo channels to generate a nice and wide stereo effect. Note, though, that the Spread control works a little differently and has different ranges in the Phaser, Flanger and Filter.

Dry/Wet



This controls the mix of the dry and processed signals.

LFO -> Freq



This controls the modulation amount from the LFO (see "LFO") to the Frequency control of the Phaser (see "Frequency"), Flanger (see "Frequency") and Filter (see "Frequency") section.

The control is bipolar, which means that negative values will invert the modulation.

Mod -> Freq



This controls the modulation amount from the Modulator (see "The Envelope Modulator" and "The Audio Follower Modulator") to the Frequency control of the Phaser (see "Frequency"), Flanger (see "Frequency") and Filter (see "Frequency") section.

The control is bipolar, which means that negative values will invert the modulation.

LFO -> Volume



This controls the modulation amount from the LFO (see "LFO") to a separate built-in amplifier. The control is bipolar, which means that negative values will invert the modulation.

Mod -> Volume




This controls the modulation amount from the Modulator (see "The Envelope Modulator" and "The Audio Follower Modulator") to a separate built-in amplifier.


The control is bipolar, which means that negative values will invert the modulation.

The Phaser



The Phaser consists of a number of all-pass filters (1 to 40) with feedback, which can be used for creating really nice phasing effects. An all-pass filter lets all frequencies of a signal through - but phase inverted 180 degrees. The principle is to split the input signal in two, run one signal dry and the other through a series of all-pass filters, and then sum the two signals. The picture below shows the basic principle of a phaser:





Frequency




Here you set the frequency of the all-pass filter(s) in the phaser.


Range: 37.6 Hz to 16.17 kHz

Bandwidth



This controls the bandwidth of the all-pass filter(s) in the phaser.







Feedback



This controls the level/intensity of the phaser peaks and notches.






Stages



In a phaser, a stage (also known as “pole”) is represented by an all-pass filter. Here you set the number of all-pass filters you want to use. Each all-pass filter contributes with one notch/peak in the frequency spectrum.


Range: 1-40 stages (notches)



Polarity




Pressing this button will invert the polarity of the Phaser filter, so that instead of notches in the frequency spectrum, there will be peaks:



Mute Dry



Pressing this button mutes the dry signal in the Phaser section, turning the effect into a frequency-dependent delay. Since no dry signal is mixed with the effect signal, there will be no notches in the frequency spectrum:





This will give more of a “tremolo” effect rather than phasing.

The Flanger



The Flanger is basically a Comb Filter with adjustable feedback, which can be used for creating a wide variety of chorus effects and frequency swirls. The principle is to split the input signal in two, run one signal dry and the other through a comb filter delay, and then sum the two signals. The picture below shows the basic principle of a flanger:






Frequency



Here you set the comb filter frequency (in practice, the delay time between the dry and processed signals).

Range: 37.6 Hz to 16.17 kHz

Feedback





This intensifies the flange effect by increasing the resonance peaks via feedback.

Polarity




Pressing this button will invert the polarity of the Flanger, so that instead of peaks in the frequency spectrum, there will be notches:






Mute Dry



Pressing this button mutes most of the dry signal in the Flanger section:



The Filter



The Filter section features a selection of great sounding filters with various characteristics, derived from the Europa Shapeshifting Synthesizer.

Drive



This amplifies and introduces an overdrive type of distortion to the signal in the filter.

Frequency



Here you set the cutoff frequency (for the HP and LP filter types) or the center frequency (for the BP and Notch filter types).

Resonance



This controls the resonance amount, i.e. the amplification of the signal around the cutoff frequency.


! In the SVF Notch filter, the Resonance knob controls the width of the notch - from wide to narrow.

(Filter) Type




▶ Click the TYPE selector to select one of the following filter types from the pop-up menu:

- **SVF HP 12dB**




A state variable (SVF) highpass filter with a 12dB/octave slope.

- **SVF BP 12dB**




A state variable (SVF) bandpass filter with 12dB/octave slopes.

- **SVF LP 12dB**




A state variable (SVF) lowpass filter with a 12dB/octave slope.

- **SVF Notch**



A state variable (SVF) notch filter.


- **Ladder LP 24dB**



A ladder-type lowpass filter with a 24dB/octave slope. The resonance peak more narrow in this filter type than in the MFB LP 24dB filter (see below). The filter can be driven to self-oscillate.


! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

- **MFB LP 12dB**



A multiple feedback (MFB) lowpass filter with a 12dB/octave slope. If you turn up the Resonance high, additional resonance peaks appear.


- **MFB LP 24dB**



A multiple feedback (MFB) lowpass filter with a 24dB/octave slope. The resonance peak is wider in this filter type that in the Ladder filter (see above). The filter can be driven to self-oscillate. If you turn up the Resonance high, additional resonance peaks appear.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**


- **MFB HP 24dB**



A multiple feedback (MFB) highpass filter with a 24dB/octave slope. If you turn up the Resonance high, additional resonance peaks appear.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

- **K35 LP 12dB**



An "early MS-20 type" of lowpass filter with a 12dB/octave slope. The filter can be driven to self-oscillate.

! **Be careful when using this filter type as high Resonance values could generate quite extreme audio levels!**

LFO



The LFO can be used for cyclic modulation of the Frequency parameter of the Phaser/Flanger/Filter section - and/or for modulating the Volume. The LFO Rate can also be synced to the Reason sequencer. You can also modulate the LFO Rate from the Modulator (see "The Envelope Modulator" and "The Audio Follower Modulator").

Waveform selector



▶ **Click the up/down triangles - or drag the waveform display up/down - to select the desired LFO waveform.**
Ten different LFO waveforms are available. Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.

! **Note that all waveforms except the "Decay" are bipolar, i.e., they generate both positive and negative levels.**

Rate



Here you set the LFO Rate.

Range: 0.050-50.00 Hz

- **Click the SYNC button to sync the LFO Rate to the main sequencer tempo.**
  Range in Sync mode: 8 Bars to 1/64.


Rate Mod



If you like, you can modulate the LFO Rate from the Modulator signal (see "The Envelope Modulator" below). If the LFO is in SYNC mode, modulating the Rate will force the LFO to switch between the sync divisions.

- **Set the desired LFO Rate Modulation amount with the knob.**

The Envelope Modulator



The Modulator section features an Envelope and an Audio Follower. You can use either the Envelope or the Audio Follower (but not together).


The Envelope is taken straight from the Europa Shapeshifting Synthesizer, so if you are familiar with Europa you will find your way around easily. The Envelope is extremely flexible, and you can draw your own custom modulation shapes by clicking and drawing in the display area. There are also a number of preset shapes that you can use as starting points (or use as is). If you use Loop mode, you could turn the envelope into an advanced LFO and design your own wave shapes.

The Envelope can then be used for modulating the Frequency parameter of the Phaser/Flanger/Filter section, for modulating the Volume, and for modulating the LFO Rate.


- **The envelope/loop playback starts as soon as there is audio present in Sweeper - or you can trigger playback using the Audio Trig function (see "Audio Trig") or a CV trig signal on the rear panel (see "Trig Envelope") instead.**


Preset

1. **Click the Preset button to bring up a palette of envelope preset curves:**




2. **Click the desired envelope preset curve to place it on the display.**
   Let's select a standard ADSR style of envelope curve:





Adding and removing envelope points


- **Double click, or hold down [Ctrl](win) or [Cmd](Mac) and click in the envelope display to add points to the envelope curve:**



- **To remove a point, double click, or hold down [Ctrl](win) or [Cmd](Mac) and click, on an existing point on the envelope curve.**


Changing the envelope curve shape

- **Click a line segment (between two points) and drag up/down to change the curve shape:**



Looping the envelope

- **Click the Loop button to turn the envelope into a kind of LFO.**




Here we have edited a stepped curve from the Presets. We have also enabled Sync and set the rate to 4/4. This means that each step in the curve now represents an 1/16th note.

- **The loop playback is synced to the Reason sequencer and time line (so that the loop always start on the "one") and continues for as long as there is still audio present through the Sweeper device.**


Editing levels only

▶ **To restrict the editing to levels only, without affecting the time positions, click the Edit button:**



In this mode you cannot change the time positions of the envelope points, only their levels (height). This is extra useful with a stepped Preset curve, because dragging up or down will change the value of an entire segment, turning the Envelope into a pseudo-sequencer.

! **To be able to adjust the level of a segment, the two points on either side of the segment have to be on the exact same time positions. Otherwise, only the closest point will be changed. Also, any inclining/declining segment will automatically turn horizontal when edited:**




Adjusting the level of a segment.

Creating “free form” envelope curves


In the Edit mode, you can also draw “free form” curves:

▶ **To continuously add new consecutive points, hold down [Ctrl](win) or [Cmd](Mac) and drag in the envelope display:**



▶ **To erase points, hold down [Shift] and [Ctrl](win) or [Cmd](Mac) and drag in the envelope display.**

Audio Trig



It’s also possible to trigger the envelope from the audio running through Sweeper.


▶ **Activate the Audio Trig function and set the Threshold value as desired.**



When the audio level in Sweeper exceeds the set Threshold value, or quickly increases when above the Threshold level, the envelope is triggered.

- **If the envelope is not in Loop mode, one complete cycle is completed at the most. The cycle continues to play back as long as there is audio present through the Sweeper device.**
- **If the envelope is in Loop mode, the loop plays back from the very beginning when an Audio Trig signal is received. The loop continues to play back as long as there is audio present through the Sweeper device.**

The Audio Follower Modulator



The other part of the Modulator section is the Audio Follower. This is basically an envelope follower, which tracks the level of the audio running through Sweeper and outputs a control signal that can be used for modulating the Frequency parameter of the Phaser/Flanger/Filter section, for modulating the Volume, and for modulating the LFO Rate. The tracked (followed) audio level is shown in real-time in the display.

Gain In

Here you can attenuate or gain the modulation signal level, to adjust it to the audio signal level.


Attack

This controls how fast the envelope follower should react after the input signal level has increased from one value to a higher.

Release

This controls how fast the envelope follower should react after the input signal level has decreased from one value to a lower.

Connections



CV Input

Frequency

This CV input can be used for modulating the Frequency parameter in the Phaser/Flanger/Filter. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

Feedback/Reso

This CV input can be used for modulating the Feedback or Resonance parameter in the Phaser/Flanger/Filter. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

Spread

This CV input can be used for modulating the Spread parameter in the Phaser/Flanger/Filter. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

Dry/Wet

This CV input can be used for modulating the Dry/Wet parameter in the Phaser/Flanger/Filter. The input accepts bipolar control signals. The input signal can be attenuated with the corresponding attenuation knob.

Trig Envelope

This CV input can be used for triggering the Envelope Modulator. The Envelope Modulator is triggered as soon as the CV value goes from zero to a positive value.

If the Audio Trig function is active (see "Audio Trig"), the Trig Envelope function will co-exist with this.

CV Output

LFO

This sends out the LFO signal as a bipolar CV signal.

Fol/Env

This sends out the Audio Follower or Envelope signal as a unipolar CV signal.

Trigger

This sends out a unipolar CV trig signal as soon as the Audio Trig function (see "Audio Trig") is triggered.

Input Left & Right

▶ **Patch the audio signals you want to process here.**
If your input signal is in mono, connect only to the L (left) input.

! **Note that the result also depends on the current Routing setting (see "Routing").**


Output Left & Right

These are the stereo audio outputs.

! **Note that the result also depends on the current Routing setting (see "Routing").**

Chapter 66
Synchronous
Timed Effect Modulator

Introduction



The Synchronous Timed Effect Modulator device is a very flexible multi effect "loop" device with freely designable effect parameter modulation curves. Synchronous features built-in Distortion, Filter, Delay and Reverb effects that can be modulated simultaneously by up to three modulation curves.


By drawing your own unique modulation curves in the display and assigning these curves to the desired effect parameters, you get a very flexible system for repeatedly modulating the effects parameters - in perfect sync with the Reason sequencer.

The standard loop length is 2 bars. However, if you run Synchronous in half speed, you will get a maximum loop length of 4 bars.

Synchronous is designed to be used mainly as an insert effect, on individual tracks, or as a "loop mangling" effect hooked up to the outputs of a Dr Octo Rex or Redrum device, for example.

Panel overview

Below is a description of the different sections in Synchronous:



Synchronous panel sections

- **1. Patch selector (for browsing, loading and saving patches).**
- **2. Curve design tools, rate, speed, phase, master offset and curve dimming controls.**
- **3. Modulation curves display with selection, freeze, kill and loop length controls for each curve.**
  The display is where you draw your effect modulation curves.
- **4. Modulation control section.**
  Here is where you set how much each modulation curve should affect each effect.
- **5. Dist section.**
  Features two distortion effects, ring modulation, and a lo-fi effect.
- **6. Filter section.**
  Features lowpass, bandpass, highpass and comb filter types.
- **7. Delay section.**
  Features regular delay, ping-pong delay and roll (freezed delay) effects.
- **8. Reverb section.**
  Features a stereo reverb.
- **9. Level modulation section.**
- **10. Master dry/wet and level controls.**

Using Synchronous

Loading and saving patches



Loading and saving patches is done in the same way as with any other internal Reason device, see "Loading patches" and "Saving patches" for details.

Drawing and assigning modulation curves - a tutorial


To describe the basic principles with modulation curves, let's have a look at an example of how you can design a modulation curve and then have it modulate a couple of effect parameters:

1. **Create a Dr Octo Rex device.**
   A Dr Octo Rex device is created and the default Rex loops are loaded in the device.
2. **Select the Dr Octo Rex device in the rack and create a Synchronous device.**
   The audio outputs of the Dr Octo Rex device are automatically connected to the audio inputs of the Synchronous device. The audio outputs of the Synchronous device are also automatically routed to the Dr Octo Rex's Mix Channel.
3. **Select the Synchronous device in the rack and select "Reset Device" from the context menu or Edit menu.**
   All parameters in the Synchronous device are now reset to their default values. The yellow modulation curve is automatically selected and reset to a straight line down in the display.
4. **Click Play on the sequencer Transport Panel in Reason.**
   The default Rex loop in the Dr Octo Rex device starts to play back and the Position Indicator at the top of the Synchronous display starts to advance in sync with the sequencer.




The Position Indicator advances in sync with the sequencer tempo.

5. **Stop the sequencer.**
6. **Click the Positive Sawtooth Tool button and then the 1/8 Rate button:**



7. **Place the mouse pointer to the far left on the display, in the curve area.**
8. **Click-hold and then drag the mouse pointer to the right on the display.**
9. **Release the mouse button when you have reached the second thicker vertical grid line.**
   A sawtooth wave is now visible in the display. The rate of the sawtooth wave is 1/8th of a bar, since you selected this when you clicked the 1/8 button. The amplitude of the sawtooth wave is increased or decreased according to your vertical drawing direction.



10.Now, click the Stepped Line Tool button and the Free button:



The Rate buttons have now disappeared from the panel, since they are of no importance when you use the Line tools.

11.Click-hold the mouse pointer at the second thick line and then draw to the right throughout the rest of the display area.

Alter the amplitude (y-axis positions) as you draw.

12.Release the mouse button when you have reached the far right of the display.

Now, you have half a bar of a 1/8th sawtooth waves and one and a half bars of a stepped "free hand" curve:



Now, let's assign the yellow modulation curve to the effect parameters to be modulated. In this example we will assign the curve to the Freq and Resonance parameters of the Filter section:

1. **Click the Filter button to switch on the Filter section:**




2. **Turn the Freq knob to a low value and the Resonance knob to a high value:**



3. **Raise the yellow Freq Modulation knob (above the Freq knob) to a positive value (past its 12 o'clock position). Then, set the Resonance Modulation knob (above the Resonance knob) to a negative value.**

Yellow modulation amount semicircles appear around the Freq Modulation knob and around the Resonance Modulation knob, to indicate the modulation amounts and their "directions" (positive or negative modulation):



Setting the modulation amounts.

4. **Start the sequencer.**

Congratulations, you have now created your first looped Filter modulation in Synchronous!

Editing modulation curves - a tutorial

Basically, there is one way you can edit an existing Modulation Curve: by redrawing the part of the curve you want to change. The examples below describe two basic use cases.

Changing an existing curve's amplitude

If you want to adjust the modulation curve's amplitude anywhere throughout the modulation loop, proceed as follows:

1. **Click the Curve Select button for the modulation curve you want to edit.**
   The curve is highlighted in the display.
2. **Click the Tool button which corresponds to the existing curve in the display.**
   If the curve is a waveform, make sure you also click the correct Rate button.
3. **Now, you have two options:**

- ▶ **To change the amplitude in a linear fashion (with a constantly increasing or decreasing amplitude), make sure the Free button is deselected (off). Place the mouse pointer where you want the change to begin and then draw to the right to where you want the change to end.**
  The amplitude starts at the level where you placed the mouse pointer and ends at the level where you released the mouse button. The level change between the start and end point is linear.
- ▶ **To change the amplitude individually between each vertical grid line, make sure the Free button is on. Place the mouse pointer where you want the changes to begin and then draw to the right to where you want the changes to end.**
  The amplitude starts at the level where you placed the mouse pointer, then follows your drawing directions, and ends at the level where you released the mouse button. The levels changes are now individual between each vertical grid line.

- ! **Note that the shortest interval you can replace (or add) curves in is in 1/16th note "steps" of a bar, i.e. in between two vertical grid lines in the display (in Speed x 1 mode). The mouse pointer automatically "snaps" to the closest leftmost vertical grid line when you draw.**

- ▶ **If you are not satisfied with your amplitude changes, just use the standard [Ctrl](Win)/[Cmd](Mac)+[Z] command to undo the operation.**

Replacing a part of a curve with another one

To replace the current modulation curve with a different curve anywhere in the modulation loop, use the same principle as described above in "Changing an existing curve's amplitude". The only exception here is that you now freely choose the new curve shape, regardless of the existing curve shape. You can replace an existing curve in as many places throughout the loop as you like.

- ! **Note that the shortest interval you can replace (or add) curves in is in 1/16th note "steps" of a bar, i.e. in between two vertical grid lines in the display (in Speed x 1 mode). The mouse pointer automatically "snaps" to the closest leftmost vertical grid line when you draw.**

- ▶ **If you accidentally overwrite a curve part that you want to keep, just use the standard [Ctrl](Win)/[Cmd](Mac)+[Z] command to undo the operation.**

Panel reference

The display section



Tool buttons and the Free button



- **Click the Stepped Line button when you want to draw a curve that has fixed levels between each vertical grid line in the display:**

  The result when you draw will be a jagged curve with vertical steps.

- **Click the Linear Line button when you want to draw straight lines between the vertical grid lines in the display:**

- **Click any of the Waveform buttons when you want to draw (repetitive) waveforms in the display:**

  In these situations, the Rate buttons define the waveform cycle lengths, see "Rate buttons".

- **Click the Free button in combination with a Line button to be able to freely define the amplitude between each of the vertical grid lines in the display:**

- **Click the Free button in combination with a Waveform button to be able to freely define the waveform's amplitude between each of the vertical grid lines in the display:**

Rate buttons



- **Use the Rate buttons to define the waveform cycle length when you draw waveforms in the display.**
  You can alter between different time rates throughout the loop by clicking another Rate button and continue drawing from where you stopped.

! **When you have selected a Line tool, the Rate buttons automatically become invisible.**

Speed control




- ▶ **Use the Speed x control to set the playback speed of the currently selected modulation curve.**
  The Speed can be set to 2, 1 or 0.5 times the main sequencer tempo, and are set individually for each of the three modulation curves. The speeds are indicated by the Position Indicators' advancement when the main sequencer is running.
- ▪ **In Speed x 1, the display covers 2 bars.**
  The vertical grid lines in the display represent 1/16th note.
- ▪ **In Speed x 0.5, the display covers 4 bars.**
  The vertical grid lines in the display now represent 1/8th note.
- ▪ **In Speed x 2, the display covers 1 bar.**
  The vertical grid lines in the display now represent 1/32th note.

Phase knob



- ▶ **Set the phase of the currently selected modulation curve.**
  Range: 0-360 degrees.

  The phase is changed individually for each curve type (waveform) used in the loop. The picture below shows the same modulation curve with a Phase setting of 0 and ~180 degrees, respectively:



The same modulation curve at 0 degrees (top) and 180 degrees (bottom) Phase values.

As you can see in the picture above the first part of the curve, which is a sinewave with a 1/4th note rate is phase shifted 180 degrees. The second part, which is a stepped line, is not changed at all. The third part of the curve, which is a sawtooth wave with a 1/8th note rate is also phase shifted 180 degrees. However, since the third part has a 1/8th note rate, the actual "distance" it has been moved is half as long as the 1/4th note rate sinewave in the first part of the curve. This is because all waveform curves are phase shifted individually throughout the modulation curve.

! **Stepped Line and Linear Line curves are not affected by the Phase parameter - they stay fixed regardless of the Phase value.**

▶ **If you want to "time shift" the entire modulation curves, including the Line curves, use the Master Offset function described below.**

Master Offset knob



▶ **Set the common offset for all three modulation curves.**
This determines where in the modulation loop the playback should begin. Negative Master Offset values moves the playback start position backwards, and vice versa.

! **The Master Offset is indicated only by the Position Indicators - i.e. the curves are not displaced in the display.**

Range: +/- 32 16th notes (in Speed x 1 mode).

Range: +/- 32 8th notes (in Speed x 0.5 mode).

Range: +/- 32 32th notes (in Speed x 2 mode).

Dim knob



▶ **Turn the Dim knob to adjust the dimming amount of the currently unselected modulation curves.**
At zero, all modulation curves are equally bright all the time.
At maximum level, only the selected modulation curve is visible in the display.

! **Note that the Dim value is also saved with the patch.**

Curve Select buttons




▶ **Click one of these buttons to select the modulation curve you want to edit.**

Setting the loop lengths

The three modulation curves can have their own individual loop lengths. The loop length for a modulation curve can be adjusted, simply by repositioning its loop locator:

1. **Click the Curve Select button for the modulation curve you want to edit.**
2. **Click-hold and drag the colored triangular loop locator horizontally to the new desired position.**




Setting the loop length for the yellow modulation curve.

3. **Release the mouse button to set the new loop length.**
The loop locator will snap to the closest leftmost vertical grid line in the display. In Normal speed, this means it will snap to a 1/16th note grid.


▶ **By setting different loop Lengths for the three modulation curves, you can get very animated variations in the modulations over longer periods of time.**

FRZ (freeze) buttons



1. **Click a FRZ (freeze) button to stop the playback of the corresponding modulation curve and freeze its current modulation value.**
2. **Click again to deactivate the freeze function.**
   The playback automatically continues at the position in the loop where it should have been if the freeze function had not been activated.

Kill buttons




1. **Click a Kill button to deactivate (mute) the corresponding modulation curve.**
   The modulation curve is preserved but does not modulate any parameter as long as the Kill function is active. Also, the killed curve becomes invisible in the display.
2. **Click again to deactivate the Kill function.**
   The modulation curve is activated and automatically continues with the modulation at the current position in the loop.

Modulation controls




The Modulation Control knobs are used for setting a modulation amount (positive or negative) for the effect parameter right below each Modulation Control knob. To set up a modulation, proceed as follows:

1. **Select the modulation curve you want to use for the modulation by clicking its Curve Activate button.**
   All assignable Modulation Control knobs are automatically colored according to the selected modulation curve:



2. **Set the modulation amount for the corresponding effect parameter by turning the desired Modulation Control knob.**



Setting the modulation amount.

A colored semicircle appears around the Modulation Control knob. The semicircle shows how much the selected modulation curve affects the corresponding effect parameter (below each Modulation Control knob) - and in which direction (positive or negative).

- **If you want the selected modulation curve to modulate other effect parameters, adjust the Modulation Control knobs above the other desired effect parameters.**

3. **If you want other modulation curves to modulate the same - or other - effect parameters, click the desired Curve Activate button and repeat the modulation assignment procedure from Step 1.**
All Modulation Control knobs can be modulated by all three modulation curves at the same time if you like. The modulation amounts and directions can be set independently for each modulation curve. The picture below shows a Modulation Control knob which is affected differently by all three modulation curves:



Different modulation amounts set for each of the three modulation curves.

Dist section



Amount knob

- **Set the distortion amount.**
At 0, the signal is left unaffected.

Character knob

- **Set the frequency content of the distorted signal.**
The effect varies depending on the selected distortion type (see below).

Distortion type selector

- **Select distortion type by clicking the corresponding LED button.**
  In Ring Mod mode, the Character knob controls the ring modulator frequency.
  In Lo-Fi mode, the Character knob controls the sample rate. There is no anti-aliasing filter in this algorithm, so there will be a lot of nice lo-fi character to the sound.

Post Filter button

- **Click the Post Filter button to route the Dist section after the Filter section (instead of before, which is the standard routing).**
  The routing order can have a big impact on the frequency content in the sound. Since the Dist section adds frequencies to the sound, you might want to preserve these by routing the Dist section after (Post) the Filter section.

Dist On/Off button

- **Click the Dist button to switch on/off the Dist effect section.**
  If switched off, the signal is bypassed unaffected.

Filter



Freq knob

- **Set the cutoff frequency (for the HP, LP and Comb filter types) or center frequency (for the BP filter type).**


Resonance knob

- **Set the resonance amount of the filtered signal.**


Filter Type switch

▶ **Click to select the desired filter type.**
The filter types are:


- **12 dB highpass (HP):**




- **6 dB bandpass (BP):**



- **24 dB lowpass (LP):**



- **Comb filter with positive feedback:**



Lag knob

- **Increase the Lag to get smoother frequency variations when the Freq parameter is modulated.**
  This works like a sort of "portamento" for the Freq parameter, i.e. the Freq parameter will move more slowly when modulated if the Lag value is high.

Filter On/Off button

- **Click to switch on/off the Filter effect section.**
  If switched off, the signal is bypassed from the Filter section.

Delay



Amount knob

- **Set the amount of the delay signal.**
  At 0, the signal is left completely dry.

Time knob

- **Set the time between the delay repetitions.**
  If the "Sync button" is on, the Time values can be stepped between time divisions (e.g. 1/1, 1/2, 1/4, 1/8 etc.) relative to the main sequencer tempo.

Feedback knob

- **Set the feedback amount, i.e. the amount of repetitions, of the delayed signal.**

Keep Pitch button

When you manually change the Rate during recording or playback, you will notice that the pitch of the delayed signal also changes. If this effect is undesirable, you can enable Keep Pitch, which will ensure that the pitch remains fixed regardless of changes in Rate.

Ping Pong button

With Ping Pong enabled, the stereo position of each delay repeat will alternate between left and right. The "Pan knob" determines the stereo width as well as the position of the initial repeat. When the Pan knob is set to full Left, the first delay bounce will be panned hard Left, the second will be panned hard Right, and so on. When the knob is set to full Right, the order is reversed (R > L > R etc).

Sync button

- **Click the Sync button to sync the delay times to the main sequencer tempo.**
  Set the time divisions (e.g. 1/1, 1/2, 1/4, 1/8 etc.) with the "Time knob".

Roll button

The Roll function works like a "freezed" delay, perfect for stutter, repeat and glitch effects. When the Roll button is on, and you turn up the Feedback knob, the input signal to the Delay section is gradually suppressed, while the feedback is automatically raised internally. In Roll mode, the Amount knob controls the level of the delay signal when the Feedback parameter is turned up. When the Feedback is set to zero, the Amount value is disregarded.

1. **Click the Roll button to switch from the regular delay settings to Roll mode.**
2. **Turn the Feedback knob to set the mix between the rolled delay signal and the dry signal.**


- **To get an instant stutter/repeat effect, turn the Feedback knob up quickly from zero at the point where you want the stutter effect. Then, quickly turn the Feedback knob back to zero again when you want the effect to disappear.**
- **Experiment by changing the Time parameter to get different "stutter" times.**

Pan knob

- **Use the Pan knob to set the stereo position of the delay repetitions. In Ping Pong mode, the Pan parameter defines where the initial delay bounce should be placed in the stereo panorama, see "Ping Pong button".**

Send/Return switch

- **Select whether you want the Amount knob to control the Send level or the Return level of the delay effect.**
  The picture below shows the different configurations schematically:



The schematic placement of the Amount knob in Send and Return mode, respectively.

Delay On/Off button

- **Click to switch on/off the Delay effect section.**
  If switched off, the signal is bypassed from the Delay section.

Reverb



Amount knob

- **Adjust the balance between the unprocessed and the reverberated audio signal.**

Decay knob

- **Set the decay time of the reverberated signal.**

Size knob


- **Set the emulated room size, from small room to large hall, with the Size knob.**
  Lowering this parameter results in a closer and gradually more "canned" sound. Raising the parameter results in a more spacey sound, with longer pre-delay.

Damp knob

- **Set the high-frequency damping amount of the reverberated signal.**
  Raising the Damp value cuts off the high frequencies of the reverb, thereby creating a smoother, warmer effect.

Send/Return switch

- **Select whether you want the Amount knob to control the Send level or the Return level of the reverb effect.**
  The picture below shows the different configurations schematically:



The schematic placement of the Amount knob in Send and Return mode, respectively.

- **To create gated or "reversed" reverb effects, set the switch to Return and modulate the Amount Modulation parameter from a modulation curve.**

Reverb On/Off button

- **Click to switch on/off the Reverb effect section.**
  If switched off, the signal is bypassed from the Reverb section.

Level



Level knob

- **Set the default level.**
  Range: - INF to + 12 dB.

! **If the Level is modulated by a modulation curve, the volume will increase above the default level, according to the modulation amount.**

In & Out switch

- **Select if the Level control should be routed before or after the rest of the effect sections in the signal chain.**

Master Controls



Dry/Wet


- **Set the balance between the dry input signal and wet signal for the entire effect chain.**
  At 0 the effects are completely bypassed and the input signal is passed through Synchronous unaffected.

Master Level

- **Set the master output level from Synchronous.**
  Range: - INF to + 12 dB.

About automation of display section parameters

As with other Reason and Rack Extension devices it is possible to automate most of the panel parameters and control them from parameter automation lanes in the main sequencer in Reason. Besides the regular panel parameters in Synchronous, parameters in the display section can also be automated:



The parameters in the display section that can be automated are:


- **The Master Offset control.**
- **The Speed control for each modulation curve.**
- **The Phase control for each modulation curve.**
- **The Loop Locator for each modulation curve.**
- **The FRZ (Freeze) and Kill buttons for each modulation curve.**
- **The Modulation Control knobs for each modulation curve.**

To automate any of the parameters described above, proceed as follows:

1. **Select the Synchronous device in the rack and select "Create Track for Default Synchronous" from the Edit menu or context menu.**
   A track for the Synchronous device is created in the sequencer and the track is automatically selected.
2. **Now, you have two options for recording parameter automation of the display parameter(s):**

▶ **Click the Record button on the sequencer transport panel and then click and turn/move the desired parameter(s) in the display section.**
The assigned parameters get separate parameter automation lanes on the sequencer track, as well as automation clips that contain automation data.

▶ **Alternatively, click the Track Parameter Automation button and select the parameter you want to automate from the drop-down list that appears.**




The selected parameter gets a parameter automation lane. Now you can draw a clip on the lane and then open the clip and draw parameter automation curves in the clip.

3. **When you are done with the parameter automation procedure, and you have stopped the sequencer, the assigned parameters are surrounded by green automation borders.**

! **Note that you cannot enable parameter automation by right-clicking and assigning controls in the display section! This can only be done with regular (non display section) panel parameters.**

Connections



CV In

Curve 1/2/3

These CV inputs accept bipolar control signals. Each input CV signal is added to the corresponding Modulation Curve signal and the resulting signal then modulates the assigned effect parameters.

The input signals can be attenuated with the corresponding attenuation knobs.

! **If the resulting modulation curve value should be negative (below zero), the assigned effect parameters are modulated with reversed polarity.**

Freeze 1/2/3

CV signals with levels >0 patched to these inputs will activate the Freeze function for the corresponding Modulation Curve. When the CV signals drops to 0 or below, the Freeze function is deactivated. See "FRZ (freeze) buttons" for more information.

Master Level CV In

A CV signal on this input can modulate the "Master Level" parameter. You can attenuate the input CV signal with the attenuation knob.


CV Out

Curve 1/2/3 and Curve 1/2/3 Inverted

These CV outputs send out positive unipolar control signal levels according to the shapes of Modulation Curves 1-3 respectively.

The "Inverted" CV outputs below each "regular" CV output send out inverted negative unipolar control signal levels according to the shapes of Modulation Curves 1-3 respectively.

The picture below shows a Curve signal (dark red) and its corresponding Curve Inverted signal (orange):



- **By patching one of the positive control signals to one destination and the corresponding inverted negative control signal to another destination, you are able to control the parameters in a "mirrored" fashion. For example, patch the positive CV signal to the Filter Cutoff modulation of a synth device and the negative signal to the Resonance modulation of the same synth.**

Audio In L&R

- **Patch the audio signals you want to process here.**
  If your input signal is in mono, connect only to the L (left) input.

Audio Out L&R

These are the stereo audio outputs.

Chapter 67
The Echo

Introduction



The Echo is an advanced stereo in/out echo and delay device with a multitude of parameters for tweaking the color and shape of the echo effect - diffusion, filtering, distortion and more. In addition to the normal mode where The Echo behaves like a regular send or insert effect, there are two additional modes called Triggered and Roll which let you automate momentary echo effects as well as create interesting stutter and repeat effects on the fly. The Echo also features breakout jacks which allow you to insert any number of other effect units into the feedback loop - this opens up endless possibilities for creative sculpting of the echo repeats.

About the Patch format

The Echo features programmable effect presets. Included are a number of Factory Patches which can be used as-is or provide you with a good starting point for further tweaking. The Patches use the file extension "*.echo". Loading and saving Patches is done in the same way as for instrument devices.

Parameters

The Echo is comprised of six main sections; Mode (Normal, Triggered and Roll), Delay (time, tempo sync and stereo behavior parameters), Feedback (including a Diffusion subsection), Color (Drive and resonant Filter), Modulation (Envelope, Wobble and LFO) and Output (Dry/Wet control and Ducking).

Common effect device parameters

While the parameters specific to The Echo are described in detail below, some features and procedures are common to all effect devices. Please refer to "Common effect device features" for further info about the Bypass On/Off switch. It should however be noted that the Input Meter on The Echo differs from the standard 7-segment LED meter found on other effect devices in Reason; The Echo features a 3-segment meter with the usual green, yellow and red LED (the latter indicates clipping).

The Mode section

The Mode section acts as a signal gate with three different ways of passing the input signal on to the subsequent main sections.



Mode

This switch has three positions:

- **Normal**
  The standard send/insert effect behavior where the input signal is fed continuously into the device.
- **Triggered**
  This mode keeps the signal unprocessed until you hit the Trig button. This mode is for situations where you only want the echo effect momentarily, e.g. on every 4th snare hit, or individual words on a vocal track.
- **Roll**
  In Roll mode, the unprocessed signal passes through unaffected until you turn up the Roll slider, see "Roll slider". This gradually suppresses the Dry signal while simultaneously raising the Feedback and mixing the delay/echo output into the Wet signal. The Roll mode is useful for repeat, stutter and glitch effects. For Roll mode, we recommend that the Dry/Wet parameter in the Output section (see below) is set to (or close to) Wet.

▶ **See "Using the Roll function" for an example of how to use the Roll function.**

Trig

This button is only functional when the Mode switch is set to the Triggered position. When you press the Trig button it opens the Input signal gate, which stays open until you release the button again. Think of it as momentarily enabling an effect send.

Roll slider

This slider is only functional when the Mode switch is set to the Roll position. The Roll slider does three things:

- **Turns up the feedback (internally) to unity (100%) or to the Feedback setting on the front panel, whichever is higher.**
  This starts happening during the slider throw, to catch a good amount of input signal.
- **Closes the input to the delay (you don't want the delay to continue catching the input sound during the roll).**
  This happens late, with a slight delay - meaning it catches a little bit of sound after you've hit the Roll position.
- **Changes the internal mix from dry to wet.**
  This also happens a bit late, so that if you hit a drum beat perfectly with the roll, you will hear that beat (dry) before the delay repeats (roll).

! **Note that the "internal mix" mentioned above is the signal sent to the "Wet" channel in Roll mode. The "Dry" channel still carries the dry signal at all times.**

The key thing here is that you shouldn't set the slider to a value in between - it should go from 0 to full Roll and back. So why do we use a slider and not a switch? Well, things start happening during the slider throw (and actually a bit after you've moved the slider fully to the right).

The slider allows for some sloppiness, making it easier to catch a beat and roll it fully. The result is slightly different depending on how fast you move the Roll slider - in most situations it works best to move it pretty fast and hit Roll exactly on the beat.

- **Although you will probably most often set The Echo to full Wet when Rolling, it might make sense to have a little bit of dry signal leaking through during the roll (making it easier to keep time and return from the roll exactly on the beat). Then you just set Dry/Wet balance to something like 85% Wet, see** "Dry/Wet".
- **See "Using the Roll function" for an example of how to use the Roll function.**

The Delay section



The Delay section features parameters relating to delay time, tempo sync and stereo behavior.

Time

This knob controls the delay time. The delay time range is 1 to 1000 milliseconds. When Sync is enabled, the range is 1/128 notes up to ½ note.

Offset R

This unipolar knob controls the Right channel delay time offset. The higher the Offset R value, the more the Right channel will be delayed in relation to the Left channel - perfect for creating stereo delay effects!

The Offset range is 1 to 1000 milliseconds. When Sync is enabled, the Offset range is "no offset" up to ½ note (according to the same resolution table as for the Time parameter). However, the 1/128 notes offset value is replaced by "no offset".

Keep Pitch

When you manually change the Delay time during recording or playback, you will notice that the pitch of the delay signal also changes. If this effect is undesirable, you can enable Keep Pitch, which will ensure that the pitch remains fixed regardless of changes in Delay time.

Sync

This button enables Tempo Sync, which affects the Time and Offset R parameter.

Ping-Pong

With Ping-Pong enabled, the stereo position of each delay repeat will alternate between left and right. The Pan knob determines the stereo width as well as the position of the initial repeat. When the Pan knob is set to full Left, the first delay bounce will be panned hard Left, the second will be panned hard Right, and so on. When the knob is set to full Right, the order is reversed (R > L > R etc).

The Feedback section



The Feedback section consists of a main section with Feedback and Offset R controls, as well as a Diffusion subsection which allows you to add a kind of 'smearing' effect to the echo.

Feedback

The Feedback knob sets the amount of feedback, i.e. the amount of wet signal fed back into the delay. This determines the number of repeats. At zero feedback there will only be a single repeat. Unity gain is achieved at 100%. If you increase the feedback beyond this it will increase the gain so a distorted signal is produced.

Offset R

This bipolar knob controls the offset in delay Feedback on the right channel. By default, both channels have the same amount of feedback (as determined by the Feedback parameter), but the Offset R knob allows you to add or subtract feedback separately for the Right channel only. The practical result is that you will hear the echo gradually wander from the center to the left or right side.

This control combined with the Offset R in the Delay section can be useful for controlling the length of the effect for the right channel.

Diffusion

Diffusion introduces kind of a "smearing" effect, somewhat reminiscent of diffusion on a reverb. Raising the Amount will introduce additional delay repeats very near the 'original' repeats, and raising the Spread value will spread these repeats out wider.

The Color section



This section features a distortion/limiter and a resonant filter. Each echo repeat is colored before being fed back into the loop, meaning that the distortion and filter effects will be more pronounced with each repeat.

Drive

This knob sets the amount of the selected distortion/limiter effect.

Type

The Type Switch lets you select between 4 different effect algorithms:

- **LIM (Limiter)**
  This produces that typical "compression" effect which you would get from analog limiters.
- **OVDR (Overdrive)**
  This produces an analog-type overdrive distortion effect.
- **DIST (Distortion)**
  Similar to overdrive, but denser.
- **TUBE**
  This emulates tube distortion.

Filter

This is a resonant bandpass filter, hence it lets you create filter effects where either the lower or the higher frequency range is cut (or boosted, in case the Reso control has been turned up).

Freq

This control sets the change in frequency. For each delay repetition, the frequency content will shift in accordance with the frequency setting.

Reso

This knob determines the amount of resonance on the delay repetitions. A different frequency range will be amplified depending on the setting of the Freq parameter.

The Modulation section



This section features parameters for modulating the pitch and stereo image of the echo effect.

Env

The envelope parameter lets you create a kind of bend effect where the pitch of the echo repeats wanders down or up, depending on whether you turn the knob left or right. The knob is bipolar, meaning that there is no Env effect in the default middle (zero) position.

Wobble

This emulates a tape speed wobbling effect where the speed of the "tape" (and consequently, the pitch of the signal) wobbles randomly.

LFO

The LFO subsection modulates the pitch of the left and right channels independently, meaning that it functions as a kind of stereo spread at modest settings and warps the echo completely at heavier settings.

Rate

This knob sets the speed of the LFO.

Amount

This knob sets the amount of LFO.

The Output section



This section is the final output stage where the processed effect signal goes through the standard Dry/Wet control, as well as the optional Ducking control.

Dry/Wet

This is a traditional dry/wet parameter for controlling the relation between the unprocessed and the processed signal. When Roll mode is enabled (see the Mode section for more info), we recommend that the Dry/Wet control is set to Wet only even when The Echo is used as an insert effect.

Ducking

Ducking attenuates the level of the Wet (processed) signal until the amplitude of the Dry signal drops, at which time the Wet signal is faded back in. This is useful for adding a delay effect to the silence that comes after you have played your lovely lead line. The delay will not be heard while you are still playing so you will avoid muddling up the solo.

CV/Gate inputs



On the back of The Echo you will find the following CV inputs:

Trig

This is a Gate input for controlling the Trig function in the Mode section.

Roll

Use this for dynamically changing the Roll amount (corresponding to the Roll slider on the front panel) in the Mode section.


Delay Time

Use this for dynamically changing the Delay Time in the Delay section.

Filter Freq

Use this for dynamically changing the Filter Frequency in the Color section.

The Breakout Jacks



The Echo features special Breakout jacks which allow you to insert other effect devices into the feedback loop. The signal is processed externally and then fed back into the loop, meaning that each delay repeat will be more colored by the effect(s) connected to the breakout jacks.

Tips and Tricks

Using the Roll function

Here's a quick example of how you can typically use the Roll function in The Echo:

1. **Have some signal running through The Echo, e.g. a drum loop.**
2. **Set The Echo to Roll mode and full Wet output (see "Dry/Wet").**
   The Roll slider is at 0. You will hear the drum loop unprocessed, since Roll isn't engaged yet.
3. **On the beat you want to roll (or freeze, to use another term), move the Roll slider quickly all the way to the right.**
   This replaces the dry signal with that beat, being rolled at whatever delay time you set.

- **A nice thing is to set the Delay to Sync mode (see "Sync") so the repeats will be in sync with the loop, e.g. to 1/16th notes or other desired resolution.**

4. **To go back to the (dry) loop, move the Roll slider quickly back to 0.**

Creating "pitched" delay

1. **Set the delay time to minimum (1ms).**
2. **Increase feedback to 100%.**
3. **Enable Diffusion and increase the Amount to maximum.**
4. **Play a drum loop or similar though The Echo.**

Now you have set up a sonic playground that equals no other delay! Experiment with Diffusion Spread, Modulation Env and Delay Time to achieve various interesting sonic results.

Distorted external feedback

1. **Connect an instrument device to the input(s) of The Echo.**
2. **Connect a Scream 4 device in the feedback loop.**
   Connect the Scream 4 inputs and outputs to the Breakout jacks of The Echo, see "The Breakout Jacks".
3. **Play the instrument device and try different distortion algorithms on the Scream 4.**
   Be careful with the master volume in Scream 4 as this is very sensitive to the feedback level in The Echo.

Chapter 68
Half-Rack Effects

Common effect device features

While the specific parameters for each effect device are described below, some features and procedures are common to all effect devices:


The Input meter



This shows the level of the incoming audio signal, giving you an indication of which devices are active, connected and playing. However, you don't need to worry about clipping in effect devices, even if the meter goes into the red.

The Power/Bypass switch

This is located in the upper left corner of each effect device. The switch has three modes, according to the following figure:



Mode	Description
Bypass	In this mode, the input signal is passed directly to the audio output, without being affected by the effect device. This is useful when the effect device is connected as an insert effect, and you want to compare the effect sound with the dry sound.
On	This is the default mode, in which the device processes the incoming signal.
Off	In this mode, the effect device is turned off and neither dry nor effect sound is sent out. This is useful when the device is connected as a send effect and you want to turn it off temporarily.

About making settings

You adjust effect parameters using the regular editing techniques.

▶ **A quick way to reset the parameters to their default values is to hold down [Ctrl](Win) or [Cmd](Mac) and click the corresponding knob.**

About Connections

- **All effect devices have stereo inputs and outputs, and can be connected as send effects or as insert effects.** However, some effects are best used as one of these only. This is stated for each effect on the following pages. See also the section about the signal flow graphs below.
- **Most of the effect devices have one or several CV inputs on the back panel.** These allow you to control various effect parameters in real-time, from another device in the rack. See "Routing CV and Gate signals" for details about routing CV.

The Signal Flow graphs



On the back of each effect device, you will find two or three small "graphs". These indicate how the effect device handles mono and stereo signals, depending on the connections. The selection of graphs for a device tells you how it should be used, according to the following rules:

Graph	Description
	Can be connected as a mono-in, mono-out device. (Of course, all effect devices *can* be connected in mono. However, if this graph isn't shown for a device, this means that a mono-in, mono-out connection may not give the proper results).
	Can be connected as a mono-in, stereo-out device. This means that the device creates some sort of stereo effect (e.g. a reverb) or a mono effect that can be panned.
	If you connect both inputs and outputs in stereo, the two sides will be processed independently (dual mono processing).
	If you connect both inputs and outputs in stereo, the two sides are summed before the effect processing. However, the actual effect is in stereo (and the dry signal will remain in stereo, if it is passed through the effect).
	"True stereo" processing, or "stereo in - stereo out" processing. When you connect the inputs in stereo, each channel in the effect uses the signal information from both inputs. However, the inputs are not summed - the two channels are processed differently. This mode is available on the RV7000 Advanced Reverb - see "RV7000 Mk II Advanced Reverb".

DDL-1 Digital Delay Line



This is a mono delay (where the output can be panned in stereo) that can be synchronized to the song tempo. The delay can be used as a send effect or an insert effect.

Parameters

Parameter	Description
Delay time	The display to the left on the device panel shows the delay time, either as note value steps (based on the sequencer tempo and the Step Length parameter) or in milliseconds, depending on the setting of the Unit switch. The maximum delay time is two seconds (2000 ms) while the maximum number of steps is 16. Note that if the tempo is low, you may reach the maximum delay time at a lower number of steps than 16 (in which case raising the steps value will not make any difference).
Unit	This is where you select whether you want a tempo-based delay ("Steps" mode) or a free time delay ("MS" mode). In the Steps mode, you specify the delay time in note value-based steps. This means that if you change the tempo in the transport panel, the delay will maintain its rhythmic relation to the music (provided that the resulting delay time doesn't reach the maximum value). This mode is useful for creating rhythmic patterns. If you change the tempo when using the delay in MS mode, the delay time will remain the same. See also the note about switching Unit modes below.
Step length	Governs whether each step in Steps mode should be a sixteenth note (1/16) or an eighth triplet note (1/8T).
Feedback	Determines the number of delay repeats.
Pan	Pans the delay effect to the left or to the right.
Wet/Dry	If you are using the delay as an insert effect, you use this parameter to adjust the balance between the unprocessed audio signal (dry) and the delay effect (wet). If the delay is used as a send effect, this should be set all the way to wet only, since you can control the balance by using the AUX send controls in the Mixer.

CV Inputs

The following CV inputs are available on the back panel of the device:

- **Pan CV.**
  This allows you to control the panning of the delay signal. Connect an LFO to this for moving delay effects, or use a Matrix pattern to simulate random delay panning.
- **Feedback CV.**
  This allows you to control the amount of feedback (the number of delay repeats) from another device. Useful for dub-type echoes on certain beats or notes only.

Switching between Unit modes

When you switch between the two Unit modes (Steps and MS), the following rules apply:

- **If you switch from Steps mode to MS mode, the delay will be set to the same actual delay time as was used in the Steps mode.**
  This means that you can set up an exact rhythmic delay in Steps mode, and then switch to MS mode to adjust it slightly.
- **If you switch from MS mode to Steps mode, the delay is reset to the previously used Steps value.**

CF-101 Chorus/Flanger



The CF-101 is a combined chorus and flanger effect. It adds depth and movement to the sound by adding a short modulated delay to the audio signal. The delayed signal is then mixed with the original (either in the effect device or manually by you - see below). The CF-101 can be used as an insert or send effect.

Parameters

Parameter	Description
Delay	This is a manual control for the delay time used to create the chorus/flanger effect. Usually, flanger-type effects use fairly short delay times while chorus-type effects use medium long delays.
Feedback	This governs the amount of effect signal fed back to the input, which in turn affects the intensity and character of the effect. Turning this to the extreme left (negative feedback) or right (positive feedback) produces different flanger effects with a pronounced resonance "tone", while keeping it in between produces a more gentle chorus effect.
LFO Rate	This is the frequency of the LFO modulating the delay time. The higher the value, the faster the sound will oscillate.
LFO Sync	This button lets you activate/deactivate LFO sync. When it is activated, the frequency of the LFO is synchronized to the song tempo, in one of 16 possible time divisions. The LFO Rate knob is then used for setting the desired time division. Turn the knob and check the tooltip for an indication of the time division.
LFO Mod Amount	This determines the depth of the LFO modulation, i.e. by how much the delay time should be modulated. If you set this to 0, the effect will be "frozen" (most effective if you add some feedback).
Send Mode	This determines whether the delayed signal and the dry signal should be mixed in the effect device or not. If you use CF-101 as an insert effect, you should turn this off - the device will then output a mix of the dry signal and the modulated delay signal. If you use the device as a send effect, you should activate Send mode. Then, the device will only output the modulated delay signal, allowing you to mix it with the dry signal using the AUX send controls in the mixer. See also the note below about using the CF-101 as a vibrato effect!

CV Inputs

The following CV inputs are available on the back panel of the device:

- **Delay CV.**
  Allows you to control the delay time from another device. This may give best results if you turn off the LFO modulation in the device (turn LFO Mod Amount to zero). For example, by controlling the delay parameter from a Matrix, you can create "stepped flanger" effects, in sync with the tempo.
- **If you use the Delay CV input for "playing" the feedback tone, note that a higher delay value gives a lower pitch.**
- **Rate CV.**
  Lets you control the rate of the modulating LFO from another device.

About Stereo and Mono connections

The CF-101 can be connected using mono or stereo inputs, as shown by the graphs on the back panel. Note the following:

- **A "moving" stereo effect is only obtained when you use a mono input and stereo outputs.**
  With a stereo input, the two sides are processed in parallel, maintaining the stereo image of the original sound.

- **When you are using a mono input and stereo outputs, there will only be a stereo effect if the internal LFO is used.** If you turn LFO Mod Amount to zero, both stereo outputs will carry the same signal (mono). This is because the "fake stereo" effect is produced by inverting the modulation for one of the output channels.

Tip: Using the CF-101 as a vibrato effect

The Send mode is intended for when using the CF-101 as a send effect. In this mode, the device will only output the modulated delay signal - you get the actual "chorusing" by mixing this signal with the dry, unprocessed signal in the Mixer.

However, if you activate Send mode while using the device as an insert effect, the result will be a pitch modulated version of the original sound - in short, a vibrato effect. Along with a little feedback, this can be used for special effects.

Spider Audio Merger & Splitter




The Spider Audio Merger & Splitter is not an effect device, but a utility. It has two basic functions:

- **To merge up to four audio input signals into one output.**
- **To split one audio input signal into four outputs.**

There are no controls on the front panel of this device, only signal indicators.

Merging audio



On the back panel of the Spider are several audio connectors. The left half of the panel contains four stereo audio input connectors, and to the right of these, one merged stereo output.

- **The principle is simple; all audio signals connected to any of the four inputs will be merged and output via the output connectors.**
  If you connect a mono signal (to a L/Mono input, with nothing connected to the corresponding R input) it will be output on both merged outputs. This way you can merge stereo and mono signals freely.
  If you connect a signal to the R input only (with nothing connected to the corresponding L/Mono input) it will be output on the R output only.

Practical uses of merging audio

There are many practical uses of merging audio signals together, for example:

- **Process several audio signals with the same insert effect(s).**
  Perhaps you want to process certain channels in a mix with the same compressor, or use one ECF-42 to filter a group of instruments in a mix. You can also set up a chain of insert effects and process the merged signals.
- **Sub-grouping signals.**
  It may be practical to control several audio signals using one channel strip in the Mixer.
- **Use merged signals as either carrier or modulator source for the BV512 Vocoder.**
  You could use several sounds as carrier signal, or modulate the carrier with several signal sources.

Splitting audio

The right half of the back panel contains two signal splitters, labeled “A (L)” and “B (R)”. The two splitters work independently, in the following way:

- **The signal fed to the input connector will be simultaneously output by all four outputs.**
  For splitting stereo signals you simply use both splitters with “A” for the left channel and “B” for the right channel.



Audio inputs **Four split output pairs**

Practical uses of splitting audio

There are many practical uses of splitting audio signals - here a few examples:

- **Create “pseudo” stereo effects from mono signals.**
  For example, you could route the mono output of a Subtractor to the Spider and then send two split outputs (from the same row) to different effects and on to different Mixer channels panned left and right.
- **It provides a way to instantly switch between (or mix) different variations of the same signal.**
  This is a neat way of applying “spot effects” in a mix. An instrument output is split and sent to three different combinations of insert effect processing. The outputs from the three effects are routed to separate channels in the Mixer, which could in turn have different send effects, eq, etc. You then have three different variations of the same signal that can be easily switched in and out of the mix for drastic sonic changes - or combined for huge layered sounds.

Spider CV Merger & Splitter




The Spider CV Merger & Splitter is not an effect device, but a utility. It has two basic functions:

- **To provide one merged CV output from up to four CV input sources.**
- **To split CV or Gate inputs into several outputs.**
  Two inputs, A and B, are provided, each with four outputs, where one of the outputs will invert the polarity of the control signal. One reason for having two splitable inputs is to make it possible to split Gate and Note CV, to control several instrument devices with one Matrix for example.

There are no controls on the front panel of this device, only CV signal indicators. The four horizontal indicators light up to indicate signals connected to the corresponding merge input. The two indicators to the right indicate signals connected to the corresponding split inputs.

Merging CV



On the back panel of the Spider there are several CV connectors. The left half of the panel contains four CV/Gate input connectors with associated trimpots, and to the right of these, one merged CV output.

- **The merged CV output will produce a CV signal that represents the "sum" of all connected CV inputs.**

A few things to note:

- **Gate CV signals typically trigger notes or envelope cycles and are normally routed to a Gate input.**
- **CV signals typically control note pitch or for modulating parameters and are typically routed to CV Note or Modulation inputs.**

There are no strict rules involved, but the facts mentioned above means that it is generally better to stick to using either Gate CV signals or CV signals but not a mixture when merging. simply because the CV/Gate signals usually go to different input destinations.

For instance, merging Note CV and Gate CV from a Matrix does not make much sense if you want to use Matrix to play melodic patterns via the Sequencer Control inputs of an instrument device. There would only be one merged output whereas the instrument device would need a separate Gate and Note CV signal to work properly.

Practical uses of merging CV

The practical applications of merging CV are perhaps less obvious compared to splitting CV. But there are numerous applications for a merged CV control output, a few of which are listed below:

- **You can create interesting modulation effects by merging several Modulation outputs from LFO's and other CV modulation sources.**
  For example, merging the Modulation outputs from several LFO's would produce a "mixed modulation" output. This merged output signal could be likened to a "super LFO" capable of generating several modulation cycles simultaneously, each with a different waveform and modulation rate! In addition to this, by using the trim control for each CV input, you have full control over the amount of modulation applied by each LFO.

  The above example could of course also include Curve CV outputs from a Matrix or Mod Outs from Malström etc., in short any CV Modulation output.

- **Use the ECF-42 Filter to apply envelope controlled filter effects.**
  This can create the sound of "synthesized" percussion, and other interesting effects.

This is done using the following method:

1. **Connect the audio outputs of a Redrum to a ECF-42 Envelope controlled filter.**
2. **Connect the Gate outputs from up to 4 Redrum drum channels to the merge inputs of a Spider CV.**
3. **Route the merged output to the Env Gate input on the ECF-42.**
   If you add a touch of velocity the connected Gate signals will trigger the ECF-42 filter envelope. Again, the trim pots on the Spider allows you to adjust the amount of filter envelope applied.

- **Create an "arpeggiator" using two Matrix devices and the Spider CV Merger & Splitter.**

By merging the Note CV output from one Matrix with a Curve CV output of another Matrix, you can transpose the Matrix pattern in real-time, a bit like an arpeggiator.

1. **Create a Subtractor and a Matrix device.**
   Connect the Matrix Note and Gate CV outputs to the Subtractor Sequencer CV and Gate inputs, respectively.
2. **Program a pattern for the Matrix.**
   In the following text this is referred to as "Matrix 1".


3. **Now create a Spider CV and a second Matrix device and connect them as in the picture below.**



Note that the Note CV output from Matrix 1, and the Curve CV output of Matrix 2 should be connected to the Spider. The merged output is connected to the Sequencer Control Note CV input on the Subtractor.

4. **On the Spider CV, turn the trimpot for the input connected to the Note CV output fully to the right.**
   This setting will retain the correct pitch relationship for the notes played by the pattern.


5. **On the Spider CV, turn the trimpot for the input connected to the Curve CV output to "32".**
   This will produce a Curve CV output that corresponds to semitone steps.



6. **Set the Curve type switch to "Bipolar" on the back of the second Matrix (Matrix 2).**
7. **Flip the rack around so that the front panels are showing, and make the following settings for the "Matrix 2":**

- **Set the number of steps to "1".**
- **Set the Curve/Keys switch to "Curve".**

8. **Adjust the Matrix 2 curve for step 1 (the only step used) so that it is in the middle of the bipolar curve as the picture shows.**



9. **If you now activate Play from the transport, the pattern you programmed for Matrix 1 is played back. By carefully adjusting the Matrix 2 Curve step 1 up or down the Matrix 1 pattern is transposed in semitone steps.**
   By programming different values for the "pattern" played by Matrix 2 and saving them in different pattern locations, you can use the Pattern selectors to transpose the Matrix 1 pattern to different keys!

Splitting CV



On the right half of the back panel you will find two split inputs "A" and "B", each with four output connectors. The signal connected to a Split input will be output by all four corresponding outputs, where one is inverted.

Practical uses of splitting CV

There are many practical uses of splitting CV signals - here are a few examples:

- **Connecting the CV Note and CV Gate outputs from a Matrix to Split Input A and B, allows you to connect the Matrix to several instrument devices.**
  Simply route the CV and Gate outputs to the corresponding Sequencer Control CV/Gate inputs on the instrument devices. Although this could also be done by copying the Matrix Pattern data to several sequencer tracks and routing the outputs to the desired devices, the advantage by using Split is if you are editing Matrix pattern data this will be immediately be reflected in all the connected devices, without any copy/paste operations.
- **Splitting modulation outputs from LFO's, Curve CV data etc. allows you to apply modulation from one source to several parameters.**
  By using the inverted output, you can create interesting modulation crossfades, where one parameter value rises and another parameter value is lowered for example.

RV-7 Digital Reverb



Reverb adds ambience and creates a space effect. Normally, reverb simulates some kind of acoustic environment such as a room or a hall, but you could also use it as a special effect.

- **The Reverb device can be used as a send effect or an insert effect.**
  If several devices uses the same type of reverb, you should connect the reverb as a send effect, to conserve computer power.

Parameters

The display to the left on the panel shows the selected reverb algorithm - the general type of reverb. By clicking the arrow buttons you can change algorithm, with the following options available:

Algorithm	Description
Hall	Emulates a fairly large, smooth hall.
Large Hall	Emulates a larger hall, with pronounced pre-delay.
Hall 2	A hall reverb with a brighter attack than “Hall”.
Large Room	Emulates a large room with hard early reflections.
Medium Room	Emulates a medium-sized room with semi-hard walls.
Small Room	A smaller room, suitable for “drum booth”-type reverbs.
Gated	A gated reverb, that is abruptly cut off.
Low Density	A thinly spaced reverb, where you clearly can here the individual echoes. Useful for strings and pads and as a special effect.
Stereo Echoes	An echo effect with the repeats alternating between stereo sides.
Pan Room	This is slightly similar to “Stereo Echoes”, but the echo repeats have soft attacks.

▶ **If you need to conserve computer power, try using the Low Density algorithm. This uses much less power than the other algorithms.**

The selected reverb algorithm can be tweaked using the parameters on the device panel:

Parameter	Description
Size	Adjusts the emulated room size. Middle position (value 0) is the default size for the selected algorithm. Lowering this parameter results in a closer and gradually more "canned" sound. Raising this parameter results in a more spacey sound, with longer pre-delay. For the "Stereo Echoes" and "Pan Room" algorithms, the Size parameter adjusts the delay time.
Decay	This governs the length of the reverb effect. Middle position is the default decay time for the selected algorithm. Note: Decay is not used for the "Gated" algorithm.
Damp	Raising the Damp value cuts off the high frequencies of the reverb, thereby creating a smoother, warmer effect.
Dry/Wet	If you are using the reverb as an insert effect, you use this parameter to adjust the balance between the unprocessed audio signal (dry) and the effect (wet). If the reverb is used as a send effect, this should be set all the way to wet only, since you can control the balance by using the AUX send controls in the Mixer.

CV Inputs

You can control the Decay parameter via the CV input on the back of the Reverb device.



D-11 Foldback Distortion



The D-11 is a simple but effective distortion effect, capable of producing anything from just a whisper soft touch of distortion, to complete thrashing. This effect is most often used as an insert effect.

Parameters

The distortion has the following parameters:

Parameter	Description
Amount	This controls the amount of distortion. The higher the value, the more distortion.
Foldback	This adjusts the character of the distortion by introducing foldback, which makes the waveform more complex. The default value is in the middle position. This produces a "flat" clipping distortion, which is the most common type. Lowering the parameter makes the sound rounder and more gentle, raising it makes the sound sharper and more evil.

CV Inputs

On the D-11 you will find a CV input for controlling the Amount parameter. This can produce very drastic effects, especially if you control parameters in the instrument device (such as filter frequency and resonance) at the same time.

ECF-42 Envelope Controlled Filter



The ECF-42 is a multimode filter with a built in envelope generator. It is mainly designed to be used together with pattern devices to create pattern controlled filter and envelope effects, but it can also be triggered via MIDI, or used as a "static" filter for shaping the sound of an instrument device or a whole mix.

Usage

The Envelope Controlled Filter is best connected as an insert effect. However, unlike the other effects it is not a pure "stand-alone" device. To make the most of the ECF-42, you need either CV/Gate from an external device or MIDI notes from a sequencer track.

- **If you connect a device to the ECF-42 using audio inputs/outputs only, it will simply act as a filter with no velocity or envelope modulation.**
  Hence, all filter parameters are "static", unless you manually turn the knobs or automate them in the sequencer.
- **Connecting a gate signal to the Env Gate input on the back panel of the device allows you to trigger the envelope generator for the filter.**
  Note that the ECF-42 envelope generator is not triggered by the audio itself - the envelope parameters won't do anything unless the device receives gate signals.
- **By creating a sequencer track connected to the ECF-42, you can have the envelope triggered by MIDI notes on the track.**
  The envelope is affected by the position, length and velocity of the MIDI notes (but not by their pitch).

▶ **If you are unfamiliar with basic filter and envelope parameters, please refer to "Envelopes - General" in the Subtractor chapter for a description of these.**

The Filter Parameters



The ECF-42 filter section has the following parameters:

Parameter	Description
Mode	This button sets the desired filter mode. Three modes are available: 24dB/octave lowpass, 12dB/octave lowpass and 12dB/octave bandpass.
Freq	This is the filter cutoff frequency. When using the ECF-42 in "static" mode (without triggering the envelope), this parameter adjusts the frequency content of the sound. When using the envelope, the Freq parameter serves as the start and end frequency for the filter sweep.
Res	This is the filter resonance. Raising this produces a more extreme, "synthy" effect.
Env Amt	Determines how much the filter frequency should be affected when the envelope is triggered. The higher the value, the more drastic the effect. Note though, that if the Freq parameter is set high, raising the Envelope Amount will not make any difference over a certain value! This is because the filter is already fully opened - try lowering the Freq parameter in that case.
Velocity	This parameter determines how much the gate velocity value should affect the envelope amount.

The Envelope Parameters



This is a standard envelope generator with Attack, Decay, Sustain and Release parameters. It is triggered by a gate signal connected to the Env Gate input on the back panel, or by MIDI notes on a sequencer track connected to the ECF-42. The parameters have the following functionality:

Parameter	Description
A (Attack)	When the envelope is triggered, this is the time it takes before the envelope signal reaches its max value.
D (Decay)	After reaching its max value, this is the time it takes for the envelope signal to reach the sustain level.
S (Sustain)	If the gate remains open (or the MIDI note is held), the envelope signal will remain on this level.
R (Release)	When the gate is closed (gate CV goes back to 0) or the MIDI note ends, this is the time it takes for the envelope signal to drop from its current value to the start value (set by the Freq parameter).

- **The Gate indicator lights up when the device receives a signal to the Env. Gate input on the back panel or a MIDI note from a sequencer track.**

CV/Gate Inputs

On the back panel of the ECF-42, you can find the following CV/Gate inputs:


- **Freq CV.**
  Use this for controlling the filter frequency from another device. For smooth filter modulation, try connecting an LFO to this input.
- **Decay CV.**
  For controlling the envelope decay parameter from another device.
- **Res CV.**
  Allows you to control the filter resonance from another device. Can be very effective in combination with filter frequency sweeps.
- **Env. Gate.**
  This is where you connect a gate signal (e.g. from a Matrix or Redrum device) for triggering the envelope.

Pattern Controlled Filter - An Example

This example shows how to use the ECF-42 and the Matrix to create pattern controlled filter effects. Proceed as follows:

1. **Start with an empty Song.**
2. **Create a Mixer.**
3. **Create a Subtractor Synthesizer.**
   An Init Patch will work fine for these examples.
4. **Create an ECF-42.**

5. **Create a Matrix Pattern Sequencer.**
   If you flip the rack around, you can see that the audio out from the Subtractor is passed through the ECF-42 and then on to the Mixer. The Matrix Curve CV is connected to the ECF-42 Frequency CV parameter, and the Matrix Gate CV is connected to the ECF-42 Env Gate input.



6. **Select the Track connected to the Subtractor (given that you are handling MIDI input via the sequencer) so that you can play it from your keyboard.**
   If you play a few notes and turn the ECF-42 filter freq knob, you should hear the sound being filtered.
7. **Draw a Gate pattern in the Matrix, using mixed velocity values.**
   Draw only a Gate pattern, not a Curve pattern.
8. **Set both the Env.Amt and Vel knobs on the ECF-42 to about "40".**
9. **Click the Run button on the Matrix panel.**
10. **While in Run mode, hold a chord down on your keyboard.**
    Now you should hear the envelope (controlling the filter) being triggered with every gate step.

- **By increasing the Env.Amount, you determine how much the envelope parameters should affect the filter frequency.**
- **By increasing the Vel. parameter, you determine how much the gate velocity should affect the filter frequency.**
- **If the filter effect isn't very noticeable, try lowering the filter frequency, and raising the Res value.**

11. **Set both the Env.Amt and Vel knobs on the ECF-42 to "0".**
12. **With the Matrix still playing, draw a Curve pattern in the Matrix pattern window.**
    Now, you should hear the filter frequency being modulated by the curve pattern. By combining the various parameters you can create many new filter effects.

- **You can also control the ECF-42 from other devices with CV and/or Gate outputs.**

Triggering the ECF-42 via MIDI

To trigger the envelope in the ECF-42, proceed as follows:

1. **Create a sequencer track for the ECF-42.**
   This is easiest done by bringing up the context menu for the device and selecting “Create Track for XX” (where “XX” is the name of this particular filter device).
2. **Record or draw some notes on the sequencer track.**
   Remember that the envelope takes the note length and velocity into account. The note pitches doesn't matter.
3. **Play back the track.**
   The actual notes will not be heard (since the track is connected to the ECF-42, which produces no sound in itself) but the envelope will be triggered according to the notes.

- **You can even control the envelope “live” via MIDI: just set Master Keyboard input to the sequencer track for the ECF-42 and play your MIDI instrument!**
  To route MIDI input to a track, click on the device icon in the track list, so that the Master Keyboard Input frame appears around it.

PH-90 Phaser



The PH-90 Phaser is a classic phaser effect with some special features for fine-tuning the sound. It can create the classic sweeping phaser sounds suitable for pads or guitars, but also more extreme effects if you like. The phaser is best used as an insert effect.

Theory

A phaser works by shifting portions of the audio signal out of phase, and then adding the processed signal back to the original one. This way, narrow bands of the frequency range ("notches") are filtered out. When these frequencies are adjusted, a sweeping phaser sound is created.

The PH-90 is a four-stage phaser, which means that there are four "notches" in the frequency response curve (this is a little like using four notch filters with different filter frequencies - see "Notch" in the Subtractor chapter for an explanation of notch filters).

When the phaser frequency is adjusted (manually or by the built-in LFO), these notches will move in parallel in the frequency spectrum. Furthermore, you can adjust the distance between the notches (Split) and their Width. Adding feedback raises the filter gain just below each notch in the frequency range, creating a more pronounced effect.

Parameters

Parameter	Description
Frequency	Sets the frequency of the first notch. Adjusting this will move the other notches correspondingly. This is the parameter modulated by the LFO to create phaser sweeps.
Split	This adjusts the distance between the notches in the frequency range, thereby changing the character of the effect.
Width	Determines the width of the notches. Raising the Width deepens the effect and simultaneously makes the sound more hollow and thin. This will also have an effect on character of the feedback "tone".
LFO Rate	This is the speed of the LFO modulating the frequency parameter. The higher the value, the faster the phaser sweeps.
LFO Sync	This button lets you activate/deactivate LFO sync. When it is activated, the frequency of the LFO is synchronized to the song tempo, in one of 16 possible time divisions. The LFO Rate knob is then used for setting the desired time division. Turn the knob and observe the tooltip that appears for an indication of the time division.
LFO Freq. Mod	This determines the depth of the LFO modulation, i.e. by how much the frequency parameter should be modulated. If you turn this to zero, the effect will be a static, formant-like sound (most effective if you add a little feedback).
Feedback	This is similar to the resonance control on a filter. Raising the feedback gives a more pronounced "tone" in the effect. For "singing" phaser sounds, try raising this to the maximum.

CV Inputs

The following CV inputs are available on the back panel of the device:

- **Freq CV.**
  Adjusts the frequency parameter. Use this e.g. for creating envelope controlled phasing (preferably with LFO Freq. Mod turned off in the device).
- **Rate CV.**
  Lets you control the speed of the modulating LFO from another device.

About Stereo and Mono connections

The PH-90 can be connected using mono or stereo inputs, as shown by the graphs on the back panel. Note the following:

- **A "moving" stereo effect is only obtained when you use a mono input and stereo outputs.**
  With a stereo input, the two sides are processed in parallel, maintaining the stereo image of the original sound.
- **When you are using a mono input and stereo outputs, there will only be a stereo effect if the internal LFO is used.**
  If you turn LFO Mod Amount to zero, both stereo outputs will carry the same signal (mono). This is because the "fake stereo" effect is produced by inverting the modulation for one of the output channels.

UN-16 Unison



The UN-16 simulates the sound of several detuned voices playing the same notes simultaneously. The voices are individually slightly delayed and also pitch modulated by low frequency noise. This produces a rich chorus effect with the voices spread across the stereo field (given that stereo outputs are used).

The UN-16 can be used as an insert effect or a send effect.

Parameters

Parameter	Description
Voice Count	This switch sets the number of voices for the effect; 4. 8 or 16.
Detune	This sets the amount of detuning for the voices. Turn clockwise for stronger detuning effects.
Dry/Wet	If you are using the UN-16 as an insert effect, you use this parameter to adjust the balance between the unprocessed audio signal (dry) and the effect (wet). If the UN-16 is used as a send effect, this should be set all the way to wet only, since you can control the balance by using the AUX send controls in the Mixer.

CV Input

One CV input is available on the back panel of the device. This controls the Detune parameter.

COMP-01 Auto Make-up Gain Compressor



The COMP-01 compressor levels out the audio, by making loud sounds softer. To compensate for the volume loss, the device has an automatic make-up gain, that raises the overall level by a suitable amount. The result is that the audio levels become more even and individual sounds can get more "power" and longer sustain.

The COMP-01 should be used as an insert effect, either for a single instrument device or for a whole mix (e.g. inserted between a Mixer device and the Hardware Interface). There are no CV inputs for this device.

Parameters

Parameter	Description
Ratio	This lets you specify the amount of gain reduction applied to the signals above the set threshold. The value is expressed as a ratio, from 1:1 (no reduction) to 16:1 (levels above the threshold are reduced by a factor 16).
Threshold	This is the threshold level above which the compression sets in. Signals with levels above the threshold will be affected, signals below it will not. In practice, this means that the lower the Threshold setting, the more the compressor effect.
Attack	This governs how quickly the compressor will apply its effect when signals rise above the set threshold. If you raise this value, the response will be slower, allowing more of the signal to pass through the compressor unaffected. Typically, this is used for preserving the attacks of the sounds.
Release	When the signal level drops below the set threshold, this determines how long it takes before the compressor lets the sound through unaffected. Set this to short values for intense, "pumping" compressor effects, or to longer values for a smoother change of the dynamics.
Gain meter	This shows the amount of gain reduction or increase (in dB), caused by the combined compression and make-up gain.

PEQ-2 Two Band Parametric EQ



While there is a simple two-band shelving equalizer available for each channel in the mixer, the PEQ-2 gives you much more precise control over the tone color. The device consists of two independent, fully parametric equalizers and is most often used as an insert effect, in mono or stereo.

About the two EQ modules

The two independent EQs are labeled “A” and “B”.

- **EQ A is always active (provided that the effect device is in “On” mode and that you have set the Gain to a value other than 0).**
- **To activate EQ B, click the button next to the EQ B parameters, so that the LED lights up.**

▶ **If you only use one EQ, it’s a good idea to turn EQ B off, to conserve computer power.**

Parameters

For both EQs (A and B), the following parameters are available:

Parameter	Description
Frequency	This determines the center frequency of the EQ, e.g. at which frequency the level should be decreased or increased. The range is 31 Hz to 16 kHz.
Q	This governs the width of the affected area around the set center frequency. The higher the value, the narrower the affected frequency range.
Gain	Specifies how much the level of the selected frequency range should be boosted (positive values) or lowered (negative values). The gain range is ±18 dB.

About the graphic display

The graphic display to the left in the device panel shows the frequency response curve as set by the EQ parameters. This gives a visual feedback and helps you tailor the EQ settings.

CV Inputs

The following CV inputs are available on the back panel of the device:

- **Freq 1 CV.**
  Allows you to control the frequency of EQ A from another device, creating subtle or dramatic EQ sweeps depending on the Q and Gain settings.
- **Freq 2 CV.**
  Allows you to control the frequency of EQ B in the same way.

Chapter 69
The Combinator



Introduction



A custom made Combinator front panel.

The Combinator is a special device that allows you to save and recall any combination of Reason/Rack Extension/VST (Reason stand-alone only) devices (instruments, effects, mixers etc.) and their internal connections. A saved Combinator setup can be loaded as a patch, called a "Combi". The Combinator device itself acts as a container for the devices in a Combi.

The basic idea behind the Combinator device is simple, but very powerful. Being able to save multiple devices as a Combi enables you to instantly recall any type of setup, however complex, as simply as loading a patch!

The original version of the Combinator was first released with Reason 3. In Reason 12 we have made a major overhaul, to make it even more powerful and flexible!

Here are some of the Combinator features:

- **Design your own custom front panel with back-drops, control configurations and layouts.**
  Now you can choose what controls - and how many of each - you want to have on the Combinator front panel. You can also select the height of the Combinator panel (1U to 6U) and add your custom back-drop image to use as background on your Combinator.
- **Create split or layered multi-instruments.**
  Add any number of instrument devices and play them as a single layered instrument. Instrument devices in a Combi can also be assigned to specific keyboard/velocity zones.
- **Save instrument/effect combinations.**
  Save an instrument together with your favorite effect(s).
- **Create multi-effect devices.**
  You can create and save complex effect chains as Combis.

About the Combi patch format

The Combinator saves files in the Combi (.cmb) patch format. When you load a ready-made Combi patch, all devices included in the Combi, their corresponding parameter settings and audio and CV connections are instantly recalled.

The Factory Soundbank includes many preset Combinator patches, divided into various categories.

There are two basic types of Combi patches; instrument and effect combis.

- **Instrument Combis contain instrument devices and generate sound.**
- **Effect Combis contain effect devices and are used to process sound.**
  These Effect Combis can e.g. be loaded as insert effects in the Main Mixer channel strips and Master Section, by dragging and dropping from the Browser to the open Insert FX container. They can also be created as send effects in the Main Mixer Master Section using the "Create Send Effects..." command on the Create menu.

Combinator overview

In the picture below an unfolded Combinator device is shown with its Editor and Devices container. The Combinator in this example contains a pre-made patch, that's why there are devices in it, and assigned controls.



The front of the Combinator consists of the following elements (from the top down):

- **1. The narrow panel at the top is always shown, even when the whole Combinator is folded.**
  It contains a display which (amongst other things) shows the name of the currently loaded Combi, and standard Select/Browse/Save patch buttons.
- **2. Next is the Control panel, which is always shown if the Combinator is unfolded.**
  You can configure and design your own unique control panel, see "Configuring the Combinator panel".
- **3. The Editor contains views for mapping devices and controls, and for configuring the Control panel.**
  Here are also parameters for Key and Velocity Zone mapping as, well as Modulation Routing settings.

  The Editor can be shown/hidden by clicking the "Editor" button on the Control panel.
- **4. At the bottom are the devices included in the Combi.**
  At the top of the device section is an 8-channel stereo summing mixer, which allows for quick audio routing of devices in the Combi. The summing mixer is always present and cannot be removed.

  Devices can be shown or hidden by clicking the "Devices" button on the Control panel.

Creating a Combinator device

Creating an empty Combinator device

- **Add a Combinator device from the Utilities palette in the Device Palette.**
  Either double click the device or drag and drop from the device palette to the rack.
- **Select "Combinator" from the "Utilities" sub-menu on the Create menu.**
  This will create an empty Combinator. Empty Combinator devices can be used as a starting point when creating new Combi patches. It also allows you to browse for existing Combi patches.

Creating a Combinator by combining devices

You can create a Combinator device by combining existing devices:

1. **Select two or more devices in the rack by [Ctrl]-clicking (Win) or [Shift]-clicking (Mac).**
   The devices do not have to be adjacent in the rack.

! **Note that you should never select any Mix Channel or Audio Track devices (Reason stand-alone only), since this will disable the "Combine" function described below.**

2. **Select "Combine" from the Edit menu or context menu.**

This creates a Combinator device containing the devices that were selected according to the following rules:

- **A sequencer track is created for the Combinator, just as when creating instrument or pattern devices.**
- **The new Combinator device appears at the position below the selected device that is farthest down in the rack.**
- **The selected devices are moved to be contained within the Combinator's "container".**
  Their internal order is not changed. Reason attempts to autoroute the first "input device" and first "output device" to the Combinator Mixer To/From Devices connectors - see "About internal and external audio connections". Other connections are unchanged.
- **Devices outside the Combi remain in the same order as before.**

! **Please see "Adding devices to a Combi" for details about auto-routing.**

Creating a Combinator by browsing patches

Double clicking, or dragging & dropping a Combinator (.cmb) patch from the Browser to the rack will automatically create the Combinator device in the rack and load the selected patch.

About internal and external audio connections

Unlike other devices, the Combinator contains both external and internal audio connections.

- **External connections are used to connect a Combinator to devices outside the Combi.**
- **Internal connections are how devices within the Combi are connected.**

External audio connections



- **The Combinator Input connectors are the inputs to the Combinator (used for effect Combis only).**
  Internally, these inputs are connected to the "To Devices" connectors of the Combinator Mixer (see below).
- **The Combinator Output connectors carry the audio output of the Combinator Mixer.**
  This output connects with a device outside the Combi, normally a mixer. Internally, this output is connected to the "From Devices" connectors. When you create a new Combinator this output will be auto-routed to the first available mixer input channel.

Internal audio connections



- **The "To Devices L/R" outputs on the Combinator Mixer connect to an input on a device in the Combi when the Combinator is used as an effect.**
- **The "From Devices" inputs on the Combinator Mixer is where the outputs from devices in the Combi are connected.**
  The "From Devices" outputs consist of 8 stereo output pairs.

About External Routing

If an individual device in the Combi is directly connected to a device outside the Combinator - or if an external device is connected to any of the "From Devices" connectors on the Combinator Mixer - this is known as an "External Routing" connection, which should generally be avoided. The reason for this is that such connections are not saved with the Combi patch.

! **Therefore, all connections to/from a Combi should pass via the To/From Device connectors on the Combinator device if you wish to make the Combi "self-contained".**

If a Combi contains any external routing connections, this is indicated by the "External Routing" LED on the front and back of the (unfolded) Combinator Mixer:



It is still possible to use a Combi with External Routing connections within the context of a song (where all routings are saved with the song). Just keep in mind that the external routing connections will not be part of the Combi patch!

How to avoid external routing connections

As explained previously, all connections to/from a Combinator device should pass via the To/From Device connectors in order to make the Combi self-contained. If you should have used up all "From Devices" connectors you need to include a mixer device and route the outputs of that mixer to a free "From Devices" connector pair.

▶ **If you should run out of "From Devices" connectors, or want more mixing capabilities, like panning and Effect Sends, the Line Mixer 6:2 is ideally suited for mixing device outputs in Combis (see "The Line Mixer 6:2").**

Adding devices to a Combi

Creating new devices in a Combi

To add devices to a Combi, you can drag and drop them from the Device Palette as usual.

If you want to add devices using the Create menu or by double clicking in the device palette, you need to make the Combinator the target device in one of the following ways:

▶ **Click in the empty area at the bottom of the open device container so that the red insertion line is shown:**



If you create a device with the insertion line showing, the new device will appear at the bottom of the Combi container.

▶ **If the Combi already has devices in it, select a device in the Combi (but not the Combinator device itself).**
When you add a device from the Create menu it will appear below the selected device (just like in the rack).

! **No sequencer tracks will be automatically created for devices added to a Combi.**

About auto-routing

The auto-routing of devices in a Combi is similar to devices in the rack:

- **If a device in a Combi is selected, the new created device will appear below the selected device according to standard rules.**
- **If an effect is selected and you create a new effect device, these will be connected serially.**
- **If an instrument device is selected and you create an effect it will be connected as an insert effect to the instrument device.**
- **If a mixer is selected and you create an effect it will be connected as a mixer send effect.**
- **If an instrument device is selected and you create another instrument device it will be added below the selected device and connected to the first available Combinator Mixer input channel.**
- **If you hold down [Shift] and create a new device, no auto-routing will take place.**
- **If you hold down [Option] (Mac) or [Alt] (Windows) and create a new device, a sequencer track will be created for the device.**

▶ **If you add a device to an empty Combi, its output(s) will be auto-routed to the first available "From Devices" connector(s) of the Combinator Mixer. For effect devices, the input will also auto-route to the "To Devices" connectors.**

Adding existing devices to the Combi from the rack

You can move devices in the rack that are currently outside the Combi into the Combinator holder. This works as follows:

1. **If you want to add more than one device at the same time, [Ctrl]-select (Win) or [Shift]-select (Mac) the devices.**
2. **Click on the panel area of a device.**
   You can click anywhere outside the actual parameters and displays.
3. **Drag the device(s) into the Combinator.**
   A thick orange vertical line indicates where the device(s) will be positioned. Note that the orange line can be to the left of a device (indicating that the moved device will be inserted before the other device) or to the right of a device (indicating that the moved device will be inserted after the other device). You can also add devices to the empty space at the bottom of the Combi holder.

- **No auto-routing will take place.**
  The existing connections to the rack will be kept, so there may be external routing connections (see "About External Routing"). If there are, "External Routing" will be shown the Combinator name display (and on the back of the Combinator a LED indicator will be lit).
- **If you drag devices into the Combi with [Shift] pressed, the devices will be disconnected from the rack and auto-routed according to the insert position.**
  The routing between dragged devices will be kept. If it isn't possible to auto-route a dragged device (e.g. if there are no free From Devices inputs on the Combinator Mixer), the device will become unconnected.
- **If you drag devices into the Combi with [Alt](Win) or [Option](Mac) pressed, the devices will be copied. No auto-routing takes place.**
  Using [Shift] at the same time will attempt to auto-route according to the same rules as described above.

Combining two Combis

- **If you select two Combinators in the rack and then select "Combine" from the Edit/context menu the lower Combi will be uncombined and the devices added to the upper Combi in the rack when combining.**
  Existing routing will be unchanged.

Combinator handling

Moving the entire Combi

This works much the same as for other devices in the rack.

- **Select the Combinator by clicking on the Control panel background and dragging to a new position.**
  An outline of the Combinator is shown when you drag, and an orange line shows the insert position. All connections are kept.

Moving devices within a Combi

Just as for devices in the rack, an outline of the devices is shown when you drag, and an orange line shows the insert position. All connections are kept.

Moving devices out of a Combi

If you move devices out of a Combi the following applies:

- **The routing in the Combinator is unchanged, and the External Routing indicator is likely to light up.**
  If you press [Shift] when dragging, the device(s) will attempt to auto-route to the rack according to standard rules.

Deleting devices in a Combi

This works exactly as for devices in the rack.

- **Select the device and then either select "Delete Devices and Tracks" from the Edit menu or context menu, or press [Backspace].**

Uncombining devices

You can uncombine a whole Combi or selected devices within a Combi in the following way:

- **If you select a Combinator and then select "Uncombine" from the Edit/context menu, the Combinator device will be removed, and all devices contained in the Combi will be moved to the rack.**
  The devices previously connected to the To/From Devices connectors will now be connected to the rack in the same way the Combinator device was (via the Combinator output and input).
- **If you uncombine a few selected devices in a Combi these will be removed from the Combi and added to the rack below the Combi.**
  Connections are unchanged, so external routing is likely to happen.

Sequencer tracks and playing Combis

When you create a Combinator device, a sequencer track is automatically created. This track is also given Master Keyboard Input just like standard instrument devices.

- **When the Combinator track receives incoming MIDI data, this will be routed to all instrument devices in an instrument Combi.**
  This means that the devices will be layered when you play (taking default velocity and key ranges into account).
- **You can turn off MIDI Note reception and/or selected Performance controller data for individual instrument devices on the Editor panel.**
  See "Key Mapping instrument devices" for details.



Configuring the Combinator panel



This is the default Combinator panel - the one that appears after you have selected "Reset Device" from the Edit/context menu. Like standard instrument devices it features Pitch and Mod wheels and various controls.

About the virtual controls

- **The default four Rotary knobs and buttons in the middle of the Control panel are "virtual" controls that can be assigned to parameters and functions in devices contained in the Combi.**
  These controls are by default not assigned to any parameters in new Combis.
- **You can also add or remove controls, to design your own custom panel, see "Adding and positioning controls on the front panel".**
- **You assign parameters to the controls in the Modulation Routing section of the Editor panel (see "Using Modulation Routing").**
- **Movements of the virtual controls can be recorded as automation.**
- **Each control can be assigned to any number of parameters.**
- **Up to four virtual controls can be modulated from the Control CV inputs on the rear panel, see "Control CV In".**
- **Double clicking on the label for a control lets you type in an appropriate name for it.**

The Pitch Bend and Modulation wheels

The Pitch and Mod wheels on the Control panel will mirror the corresponding actions on your master keyboard, just like for standard instrument devices.

- **When a Combinator device has Master Keyboard input and the Combi contains several instrument devices these will all receive pitch bend and modulation data.**
  The settings in the instrument devices determines what happens when applying pitch bend or modulation.
- **For example, moving the Mod wheel could apply vibrato for one device and change the filter cutoff frequency for another device.**
- **Pitch Bend will also be applied according to individual settings in the Range field for all instrument devices in a Combi.**

Opening the Configuration panel

1. **Open the Editor by clicking the Editor button at the top of the Combinator front panel:**




2. **Click the Configure button to open the panel Configuration panel:**




Setting the front panel size

▶ **Select the desired panel height from the "Panel size" drop-down list.**
You can choose from 1U (rack unit) to 6U.



Selecting front panel background color

▶ **Select the desired panel background color from the Background Color drop-down list.**




Selecting a backdrop image



This function allows you to change the "skin" of the Combinator front panel. You can design your own labels for the assignable controls, and change the color and look of the whole panel.

▶ **Click the Backdrop drop-down on the Config panel in the Editor:**



The Backdrop drop-down features the items "None", "Default" and "Load..."

- **"None" leaves the panel with the selected background Color (see "Selecting front panel background color").**
- **"Default" is a semi-transparent texture which gives a higher quality look to the front panel.**
  Since the texture is semi-transparent the selected background Color will shine through.
- **Selecting "Load..." will open the image browser.**
  Here you can select image file in JPEG (.jpg) or PNG format.

  Instead of selecting "Load..." from the drop-down you could select the Combinator device and choose "Select Backdrop..." from the Edit/context menu.

▶ **Transparent PNG files are also supported, if you want to layer a backdrop image on top of a background color.**

- **For full hi-res support the width of the image should be 3770 pixels.**
  The height depends on what front panel size you have selected, see "Setting the front panel size".

  These are the optimal height dimensions for each of the front panel sizes:


  1U: 345 pixels
  2U: 690 pixels
  3U: 1035 pixels
  4U: 1380 pixels
  5U: 1725 pixels
  6U: 2070 pixels

  If you select an image with other pixel dimensions, the image will be automatically scaled.
- **The knobs, buttons, patch name display and patch buttons cannot be redesigned using a backdrop.**

▶ **If you wish to design your own text labels for the virtual controls, you should first remove the original text labels:**
Double click on a control label, remove the current text and press [Enter]. Alternatively, uncheck "Show Label" in the Configuration panel in the Editor, see "Changing the appearance of the controls").


▶ **To remove a Backdrop, select "Remove Backdrop" from the Combinator context menu - or select "None" in the Backdrop drop-down on the Config panel in the Editor.**
The currently selected Background Color of the Combinator panel is restored.

About "Using Legacy Backdrop"




This is automatically turned on when you load a legacy Combi patch with a backdrop, and will show buttons in the same way as on the original Combi (including Show Editor/Show Devices buttons on the panel) and hide the Bypass/On/Off label as this is expected to be in the backdrop.

About the "Bypass Label"



The "Bypass Label" item is available only when the "Using Legacy Backdrop" is de-selected.

- **Select the desired color (or presence) of the Bypass/On/Off text from the drop-down.**
  The setting affects the color of the text on the top left of the Combinator panel:



About the "Combi Layout Templates" folder


In Factory Sound Bank/Combinator Patches/ there is a folder named "Combi Layout Templates". This folder contains a selection of pre-made Combinator panel configurations and layouts that can serve as starting points/inspiration for your own Combinator designs.

Selecting, positioning and editing front panel controls

1. **Open the Editor by clicking the Editor button at the top of the Combinator front panel.**
2. **Click the Configure button to open the panel Configuration panel.**

Adding and positioning controls on the front panel

To the left on the Editor Configuration panel are a selection of pre-made knobs, faders, buttons and wheels that can be freely laid out on the Combinator front panel:



Controls selector on the Configuration panel.


1. **Click a desired control icon on the Configuration panel.**
   The control shows up with a frame around it on the Combinator front panel.



Adding a new control to the front panel.

2. **Click and drag the control to the desired position on the Combinator front panel.**
   Visual guides appear as you move the control so you can easily place the control aligned with other controls already on the panel.

- ▶ **Use the [Arrow] keys on the computer keyboards to adjust the position, if desired.**
- ▶ **Double click the label and type in a new name, if desired:**



3. **Click a new control to add another one.**


- ▶ **You can also select multiple controls, by dragging or by [Shift]-clicking on the panel, and move them together on the front panel.**
  Alternatively, [Command]/[Ctrl]-click the controls in the Panel Elements list to select multiple controls.



! **The maximum number of controls that can be placed on a Combinator panel is 32 knobs/faders plus 32 buttons, 2 wheels (pitch and modwheel), 1 Run button and 1 Bypass FX button.**

It's also possible to align and distribute a selection of controls, to get perfect position with even spacing on the panel.

▶ **Select the group of controls you want to align/distribute, click the black arrow button on the control you want to use as reference, and select action from the pop-up:**



About the "Run" and "Bypass FX" buttons



The "Run" button can be used to start/stop all (Reason) pattern devices included in the Combi. This works exactly as pressing the Run button on the pattern device panel. The on/off status of this button is not saved with the Combi patch. Pressing play on the transport panel in the Sequencer will automatically activate "Run Pattern Devices".

▶ **In the Reason Factory Sound Bank, Combi patches containing pattern devices have "(run)" at the end of their patch names.**

The "Bypass FX" button allows you bypass all effect devices in a Combi. It works as follows:

- **All insert effect devices in the Combi are switched to Bypass mode.**
- **All effects connected as send effects to a mixer device are switched off.**
- **Clicking this button will not affect effect devices that were bypassed or turned off already.**

Changing the appearance of the controls

It's possible to change the appearance of the controls.

1. **Click the control you want to edit, either on the Combinator front panel or in the Panel Element list on the Configuration panel.**
   The characteristics of the selected control is now displayed in the Settings section:




- **The control type is shown in the Type display.**
- **The Name display shows the control name.**
  (To edit the name, double click the name label on the Combinator panel.)
- **Select control style from the Style drop-down list.**
- **Select the Scale appearance (if the control features a scale)**
- **Click the check mark to show/hide the control name label on the Combinator front panel.**
- **Select the label text color from the Text Color drop-down list.**
- **Choose where you want the text label positioned around the control from the Position drop-down list.**

Deleting controls on the front panel

1. **Select a control (or multiple controls, by dragging or by [Shift]-clicking the controls on the front panel).**
   Alternatively, click in the Panel Element list ([Command]/[Ctrl]-click to select multiple controls).
2. **Press [Delete]/[Backspace] on the computer keyboard to delete the selected control(s)**

- **Alternatively, click the X next to the control name in the Panel Elements list to delete one control at a time:**



Assigning panel controls to parameters in the Editor

The Editor is used for key mapping and setting velocity ranges for instrument devices, and for Modulation Routing; assigning device parameters to the knobs/buttons/sliders on the Control panel.

▶ **To bring up the Editor panel, click the "Editor" button on the unfolded Control panel.**
The Editor appears below the Control panel.




A fully assigned Combinator.

- **To the left on the Editor panel the devices in the current Combi are listed in the order they appear in the Combinator container - from top to bottom.**
  Clicking on a device in the list selects it for editing.
- **To the right is the Modulation Routing section where you can assign parameters to the controls on the Control panel.**
  See "Using Modulation Routing".

Key Mapping instrument devices

About the Key (receive MIDI Notes) column



To the right of the Device name is a Key column.


▶ **Click to select if the device should respond to MIDI Note input.**

- **If you deactivate the "Key" checkbox the selected device will not respond to incoming MIDI note messages.**
  For devices that cannot use MIDI notes (such as most effect devices), there is no checkbox in this column.

Setting the Key Range

Each instrument device can have its own separate key range, the lowest and the highest key that will trigger the device. This allows you to create splits and layers for instrument devices in a Combi.

1. **Make sure the "Key" checkbox is ticked for the instrument devices you want to edit the Key Range.**
   The Key Range is shown as a horizontal bar, and as note numbers on either sides of the bar. By default, the entire note range is selected (C -2 to G 8).



There are several ways you can change the Key Range:

- **By clicking in the Key Range value fields and moving the mouse up or down.**
- **By moving the handles of the horizontal bar.**
- **By dragging the horizontal bar itself you can also move entire key zones horizontally, thereby changing their key ranges.**

2. **Using either method, set the desired key range for the desired device(s).**
   When done, the device(s) will only play back notes in the set key range.

- **By setting up key ranges for devices in a Combi, you can create split instruments.**
  For example playing notes below C 2 could trigger a device playing a bass sound, whereas playing notes above C 2 could trigger a device playing a pad sound.
- **Instrument devices in a Combi that share the same key range will be layered - i.e. play at the same time.**
  This given that no velocity ranges have been set up - see below.
- **You can of course set up overlapping ranges where notes within a set key range will layer two (or more) devices, but notes above and below the set range will play separate devices.**


About the Transpose function



The Transpose field to the far right on the panel allows you to transpose the instrument devices. It will not shift the key mapping, just the pitch of the device.

- **Click and drag up/down in the Transpose field to edit the transposition.**
  The range is +/- 3 octaves, in semitone steps (+/-36 semitones).


Enabling/disabling Performance Controllers



To the bottom right of the panel is a drop-down list that features all standard MIDI Performance Controllers (Pitch Bend/Mod Wheel/Breath/Expression Pedal/Sustain Pedal/Aftertouch) for the selected instrument.

- **The check boxes in the drop-down list allow you to control whether MIDI Performance Controller data is to be received for each instrument device in a Combi.**
- **If you deactivate any of the Performance Controllers, the corresponding controller(s) will not be received by the selected instrument device.**
  All Performance Controllers are on by default.

Setting Velocity Ranges for instrument devices



When instrument devices are set up so that their key ranges overlap – completely or partially – you can use velocity switching to determine which devices should be played back depending on how hard or soft you play on your MIDI keyboard.

This is done by setting up velocity ranges.

Each time you press a key on your MIDI keyboard, a velocity value between 1-127 is sent to Reason. If you press the key softly, a low velocity value is sent and if you press it hard, a high velocity value is sent.

This velocity value determines which devices will be played and which will not.

1. **Select an instrument device in the Device list (non-instrument devices, e.g. effects and mixers do not have velocity ranges).**
   By default, the entire range is selected (0 - 127).

There are several ways you can change the current Velocity Range:


- **By clicking in the "Lo" and "Hi" value fields and moving the mouse up or down.**
- **By moving the handles of the horizontal bar.**
- **By dragging the horizontal bar itself you can also move entire Velocity Range.**

2. **When you have set a range, the device will only be triggered by notes played within this velocity range.**

About overlapping Velocity Ranges

You can set overlapping velocity ranges. Here's an example of how this can work:

- **Device 1 has a velocity range from 1-45.**
- **Device 2 has a velocity range of 33-88.**
- **Device 3 has a velocity range of 76-127.**



Now, velocity values between 33 and 45 will trigger notes from both Device 1 and Device 2. Likewise, velocity values between 76 and 88 will trigger sounds from Device 2 and Device 3.

Using Modulation Routing



The Modulation Routing section to the right on the Editor panel allows you to assign any parameter or function in devices included in a Combi to any of the virtual controls on the Control panel.

You can also control Combi parameters by connecting external CV modulation sources to any of the Source CV inputs on the back of the unfolded Editor panel, see "Wheel CV In and Source CV In".

About Rotary/Slider and Switch controls

The virtual Rotary/Slider and Switch controls operate much like the equivalent controls on the real devices:

- **A Rotary/Slider control can change continuous parameter values (e.g. a level control), or step through fixed values (like the Oscillator waveform spin controls on a Subtractor).**
  The actual Rotary/Slider control on the Combinator will always move smoothly (never "stepped"), though.
- **A Switch control will switch between two set values like an on/off switch.**
  Worth noting is that there are buttons on several Reason devices that will step through a series of values, for example LFO Waveform buttons. If LFO Waveform is assigned to one of the virtual Buttons you will only be able to switch between two of the six LFO waveforms (which waveforms is determined by the Min/Max range).
- **The available range for each selected parameter is shown in the Modulation Routing Min/Max fields.**
  Most sliders and rotary knobs on the actual devices have the standard 0-127 or -64 to 63 range. Selectors and spin controls can have any value range.


About the CV Inputs

On the back of the Editor panel are CV Modulation Inputs for connecting external CV signals to modulate any of the parameters that are accessible in the Target section in the Editor, see "Wheel CV In and Source CV In".

Assigning panel controls to device parameters

Assigning Combinator panel controls to device parameters can be done in two different ways:


1. **Right click the desired device parameter and select the desired Combinator panel control to assign it to from the "Map to Combi Control" pop-up:**




Assigning the "Master Volume" control on an Europa device to the "Level" control on the Combinator panel.

If you chose the method described above you can continue directly to step 4 below in this description.

▶ **Alternatively, select the device you wish to assign parameters on in the device list to the left:**




The Modulation Routing section to the right contains four columns:




- **In the Source column, any currently assigned Combinator panel controls are listed.**
  Each field can be changed to any Control/Slider/Switch/CV Input or Performance Controller by clicking the arrow and selecting from the drop-down list.
- **The drop-down lists in the Target column contain all parameters for the currently selected device.**
  Lastly in each Target drop-down list is the option to receive note data or not. This is useful if you want to temporarily enable/disable MIDI Note input for specific devices, e.g. to temporarily enable layered instruments - or switch instrument playback.
- **The Min/Max columns allow you to specify a value range for the virtual control.**
  It's also possible to set the Min value higher than the Max value, meaning that the value will decrease when you turn up the knob/slider.

2. **Click the small black triangle in the Source column and select the Combinator panel control from the drop-down list:**



Setting the "Level" Combinator panel control as Source.

3. **Click the small black triangle in the Target column and select the desired Target parameter from the drop-down list:**
In the drop-down, all the available parameters for the device are listed.




Assigning the Europa "Master Volume" parameter as Target.

4. **You can specify a range for the assigned parameter by clicking in the Min and Max columns and moving the mouse up or down, or by dragging the handles of the horizontal Range bar, or by dragging the Range bar (to offset the range).**
By the maximum available range is set by default:




- **It's also possible to "reverse" the range by dragging the Range handles past each other, or dragging the Min/Max boxes so that the minimum value becomes max and the maximum value becomes minimum.**
  The result is that the Target parameter value will decrease when you turn up the Source knob/slider, and vice versa. Here is an example of how to reverse the range for a parameter:




The Filter Reso parameter edited to have a reversed Range, as indicated by the light gray Range bar.

- **It's also possible to set a Source Range for each Source control, so that the knob/slider only affects the Target parameter in a certain region/interval of the Source control:**



The Filter Freq stays at 200 Hz in this span.




Linear change from 200 Hz to 3 kHz in this span.

Source Range for Rotary 1 set to 50-100%.


5. **If you select another device in the Device list to the left in the Editor, you can assign another parameter to the same Rotary or Button control using the same basic methods.**
   This means that you can create multi-function controls that operate simultaneously on several parameters. E.g. if you have two Subtractors and a Malström in a Combi you could create a "master" filter cutoff knob, that controls this parameter for all three devices. See "Controlling multiple Target parameters differently from a single Source control" for an example.

- ▶ **If you want to clear all mappings and start from a clean slate, click the "Clear Mappings" X button:**



Controlling multiple Target parameters differently from a single Source control

You can also have the same Source control assigned to multiple Target parameters on the same device. In the example below the “Eng1 Filter Freq” and the “Eng1 Filter Reso” parameters on the Spectral Filter in a Europa device are assigned to the same FILTER control on the Combinator panel:



The “Eng1 Filter Reso” parameter Range is reduced and reversed (light gray Range bar), so when you turn up the FILTER knob on the Combinator panel, the Filter Frequency is raised but the Resonance is decreased. The “Eng1 Filter Reso” parameter also has the Source Range set to 0-50%, which means the Resonance will decrease only during the first half of the FILTER knob range.

The picture below shows how the “Eng1 Filter Freq” and “Eng1 Filter Reso” parameters are affected when you turn up the FILTER knob on the Combinator panel. You can also see the differences in the Spectral Filter display:



Controlling both the Freq and Reso parameters from the FILTER control on the Combinator panel.

Controlling a single Target parameter from multiple Source controls

This is also possible, by simply selecting the same Target parameter from different Source controls in the Modulation Routing section.

CV Connections



The rear panel of the Combinator.

CV connections between devices in the Combi are saved with the Combi patches. This is also true for CV connections between devices in Combi and the Combi itself - e.g. if you have connected a Matrix in the Combi to one of the CV inputs on the back of the Combi panel.

The following CV connectors can be found at the back of the Combinator:

Sequencer Control inputs

The Sequencer Control CV and Gate inputs allow you to play the Combinator from another CV/Gate device (typically a Matrix or a RPG-8). The signal to the CV input controls the note pitch, while the signal to the Gate input delivers note on/off along with velocity.

Control CV In



These CV inputs can be used for controlling four selectable controls on the Combinator front panel.

- **Click the drop-down and select which panel control you want to modulate.**
  All currently available front panel controls are shown in the drop-down list.
- **Attenuate the input signal with the corresponding attenuation knob.**

Wheel CV In and Source CV In

In this section you will find standard CV Pitch Bend and Mod Wheel modulation inputs, as well as eight modulation inputs which can be assigned as Sources in the Editor. Here you can connect external CV modulation sources for modulating any of the Target parameters in the Editor (see "Using Modulation Routing").

▶ **Click the Editor button to show the Wheel CV In and Source CV In connectors on the rear panel:**



Next to each CV Input are one sensitivity knob and one polarity switch that work as follows:

- **The sensitivity knobs can be used for attenuating the CV Input signal.**
- **The polarity switches should be used for defining the polarity of the CV Input signal.**
  For example, if you have connected a CV signal from an envelope generator, the switch should be set to Unipolar. If you are modulating from a standard LFO, the polarity switch should be set to Bipolar.



Chapter 70
Gain Tool


Introduction



Gain Tool is a utility for managing your signal levels, panning, and routing. It's particularly useful at the end of a signal chain, to do complex automation without having to use up the Mixer controls for this task. For Combinator builders and Reason Rack Plugin users, Gain Tool acts as the fader part of a channel strip and also enables some clever x-fading for more intricate patch building.

Signal flow

The picture below shows the signal flows for the different input and output modes in Gain Tool:



Gain Tool signal flowchart.

Panel reference

The input mode switch




▶ **Select which input mode you want Gain Tool to operate in:**
In Gain input mode Gain Tool works as a signal attenuator and amplifier for a stereo or mono input signal.

In Mix input mode Gain Tool works as a mixer for two stereo or mono input channels.

In X-Fade input mode Gain Tool works as a crossfade mixer between two stereo or mono input channels.

The Gain input mode



- **Click the Gain button to activate the built-in amplifier.**
- **Set the desired gain/attenuation with the Gain knob.**
  The gain/attenuation level is shown in the Gain Display. The display also shows a percentage figure of the amplification.

  Range: -Inf to +18.1 dB (0-800%)

The Mix input mode



In Mix input mode you can connect two separate stereo input signals (Main and Aux) and control their individual gain.

- **Set the desired gain/attenuation for the Main and Aux inputs with corresponding the Gain knobs.**
  The gain/attenuation is shown in the corresponding Gain Display.


  Range: -Inf to +18.1 dB (0-800%)

The X-Fade input mode



In Mix input mode you can connect two separate stereo input signals (Main and Aux), control their individual gain and also crossfade between the input channels.

- **Set the desired gain/attenuation for the Main and Aux inputs with corresponding the Gain knobs.**
  Range: -Inf to +18.1 dB (0-800%)
- **Set the desired crossfade between the input channels with the X-Fade slider.**



The output mode switch



- **Select which output mode you want Gain Tool to operate in:**
  In Width/Pan output mode you can set the stereo width of any connected stereo input signals, as well as control the panning of the input signal(s).

  In Dual Pan output mode you can pan the Left and Right channel(s) of the input signal(s).

  In Router output mode you can crossfade the output mix to the Main Out and Split Out jacks on the rear panel.

The Width/Pan output mode



- **Set the stereo width of the input stereo signal(s) with the Width knob.**
  At the 12 o'clock position the width of the stereo input signal(s) are unaffected. Turn counter-clockwise to turn the signal(s) more towards mono. Turn clock-wise to enhance the stereo width of the stereo input signal(s). Since Width affects the differences between the left and right channels, enhancing a stereo signal will not cause any phase problems.

! **Note that mono input signals are not affected by the Width parameter - mono signals will always remain in mono.**

- **Turn the Pan knob to pan the input signal(s) Left or Right.**
  If you have both the Main and Aux inputs connected, it's the combined signal that will be panned.

The Dual Pan output mode




- **Pan the Left and Right stereo channels individually with the Pan Left and Pan Right knobs.**
  If both Pan knobs are at their 12 o'clock positions the output signal will be mono.

The Router output mode



▶ **Move the Output slider to crossfade the output signal to the Main Out and Split Out jacks on the rear panel.**



The Output buttons



To the right of the front panel are a number of buttons.

▶ **Click the Mute button to mute the output signal(s) of both the Main Out and Split Out jacks on the rear panel.**

▶ **Click the Inv L and Inv R buttons to invert the phase of the corresponding stereo channel.**
Note that the phases of the Split Out signals are also inverted.

▶ **Click the Swap L-R button to swap the left and right output channels.**

▶ **Click the Mono button to get the output signal(s) in mono.**

The output level meters

To the far right of the front panel are the output level meters.


- **In the Width/Pan and Dual Pan output modes the meter shows the output levels of the Left and Right Main Out channels:**



- **In the Router output mode the meter shows the output levels of the Main Out and Split Out channels respectively:**



Connections



Audio Inputs

Main Input L&R

- **Patch the main audio signal(s) here.**
  If your input signal is in mono, connect only to the L (left) input.

Aux Input L&R

- **Patch the additional audio signal(s) that you want to use in Mix or X-Fade mode here.**
  If your input signal is in mono, connect only to the L (left) input.

CV Inputs

The first three CV inputs control parameters in the Input section. Each CV input also has an attenuator knob:

Main Gain, Aux Gain and X-Fade

- **Modulate the Gain parameter in Gain, Mix and X-Fade mode by a CV signal patched to this input.**
- **Modulate the Aux Gain parameter in Mix and X-Fade mode by a CV signal patched to this input.**
- **Modulate the X-Fade parameter in X-Fade mode by a CV signal patched to this input.**

The last three CV inputs control parameters in the Output section. Each CV input also has an attenuator knob:

Width/Pan L, Pan/Pan R and Output Router

- **Modulate the Width parameter in Width/Pan mode - or the Pan L parameter in Dual Pan mode - by a CV signal patched to the Width/Pan L input.**
- **Modulate the Pan parameter in Width/Pan mode - or the Pan R parameter in Dual Pan mode - by a CV signal patched to the Pan/Pan R input.**
- **Modulate the Output parameter in Router mode by a CV signal patched to the Output Router input.**

Audio Outputs

Main Out L&R

- **Patch the main audio output signal(s) here.**

Split Out L&R

- **Patch the Split Out audio output signal(s) that you use in Router mode here.**

Chapter 71
The Line Mixer 6:2

Introduction



The Line Mixer 6:2 allows you to control the level, stereo placement (Pan) and effect mix (AUX Send) of each connected audio device.

The Line Mixer is configured with 6 (stereo) input channels, which are combined and routed to the Left and Right Master outputs.

Channel parameters

The channels are identical and contain an Auxiliary Send, Mute and Solo buttons, a Pan control, and a Level control:

Item	Description
Level control	This controls the output level of each corresponding channel, allowing you to set the desired mix (balance) between different devices connected to the Line Mixer.
Channel label	Each channel in the mixer that has a device connected to it, displays a read-only label with the name of the device.
Channel meter	The meter is a graphical representation of the channel output level. If the signal level pushes the meter into the range of the red area, try lowering either the output level of the device connected to the channel, or the Level control itself, to avoid distortion.
Pan control	Use this control to set the left/right position of the channel in the stereo field. [Ctrl]-click (Win) or the Pan knob to set Pan to the default "0" (center position).
Mute (M) and Solo (S) Buttons	Clicking a channel's Mute button silences the output of that channel. Click the button again to unmute the channel. Clicking a channel's Solo button silences all other mixer channels, so that you only hear the soloed channel. Several channels can be soloed at the same time. If this is the case, note that soloed channels can't be muted with the Mute button. To mute one of several channels in solo mode you simply "unsolo" it.
Auxiliary (AUX) Effect Send	The AUX Send controls the amount of channel signal that is to be sent to other devices - typically effect processors. The effect output is then normally returned to the Mixer via the AUX Return input where it is mixed with the dry (non-processed) signal. If you create an effect device when the Mixer is selected, the effect is auto-routed to the Send/Return connectors. You can then control the amount of effect that is to be applied to any device connected to a Line Mixer channel via the AUX Send knob. The Send can be taken pre or post channel level - see "Auxiliary (AUX) Send".

The Auxiliary Return section

The AUX Return channels provide inputs for a connected send effect device. The Aux Return channels have a single level control on the front panel.

Master level

The Master L/R fader controls the summed output level of all channels in the Mixer. Use this to change the relative level of all channels, to make fade-outs etc.

Connections

All input and output connectors are as usual located on the back panel of the Line Mixer.

Mixer Channel Connections

- **Each mixer channel features stereo left/right inputs for connecting audio devices.**
  Use the left input when manually connecting a mono signal source.
- **In addition, there is a Control Voltage (CV) input, for voltage controlling channel Pan from other devices.**

Auxiliary (AUX) Send

- **The Send connectors are used to connect to the inputs of effect devices.**
  To connect the send to a mono-input device, use the Left (Mono) output.

When a Send is connected to an effects device, the corresponding AUX Send knob determines the level of the signal sent to the effect device for each channel.

The Send Output can be taken Pre or Post channel level by using the switch to the left of the Send connectors.

Auxiliary (AUX) Return

These are normally connected to the left and right outputs of effect devices.


Master Left/Right Outputs

- **The Master outputs are auto-routed to the input pair of the first available Mix Channel device in the rack.**
  If no Mix Channel device is available, one will be automatically created when you create a Line Mixer device.

  If used in a Combi, the Master Outs are normally connected to the "From Devices" connectors on the Combinator.

Chapter 72
Matrix Pattern Sequencer


Introduction



The Matrix is a pattern-based device. Matrix doesn't generate sound on its own, but has to be connected to another instrument device. It basically works by sending pattern data in the form of Note CV (pitch) and Gate CV (note on/off plus velocity) or Curve CV (for general CV parameter control) signals to a device or device parameter. The patterns can be up to 32 steps, and there are 32 memory locations for storing pattern data. The Matrix is monophonic and can control one voice in an instrument device.

Unlike most other devices in Reason, the user interface of the Matrix is not modeled on any existing hardware equivalent. The hardware devices that could be said to have similar functionality are analog step sequencers, which usually had rows of knobs that controlled the note pitch and gate values for each step.

About the three Output types




Note and Gate CV values.

The Matrix can produce three types of output: Curve CV, Note (Key) CV and Gate CV.

- **Note CV normally controls note pitch.**
  When connected to an instrument device Sequencer Control input, the values correspond to semitone steps.
- **Gate CV represents a note-on/off value, plus a *level* value (that could be likened to velocity).**

Both of these two outputs are typically connected to the Sequencer Control Gate and CV inputs on a compatible instrument device. For example, if you create a Matrix with either a synthesizer (Subtractor, Malström) or a sampler (NN-19, NN-XT) selected, they will be auto-routed in this way, and will control one voice in the device.

- **Curve CV is a separate pattern, programmed separately from the Note/Key and Gate CV.**



Curve CV values (upper window).

This is useful for programming CV curves that control other parameters other than note pitch (although you could do this too). This way you could control the note pitch and triggering from the Key and Gate outputs for a device, then add a second independent pattern using the Curve CV output that could control filter cutoff for example.

It should be stressed that all three outputs can be used in any number of ways. For example, you could use the Gate CV to trigger a drum in Redrum, or let the Curve CV control the feedback parameter of a delay, etc.

Programming patterns

Pattern basics

Matrix contains a built-in pattern sequencer. Unlike the main sequencer in Reason, the Matrix sequencer repeatedly plays back a pattern of a specified length. The typical example in the "real world" (as well as in Reason) is a drum machine which plays drum patterns, usually one or two bars in length.

Having the same pattern repeat throughout a whole song may be fine in some cases, but most often you want some variations. The solution is to create several different patterns and program pattern changes (automatic switching from one pattern to another) at the desired positions in the song.

How the Matrix pattern sequencer integrates with the main Sequencer

The built-in pattern sequencer in the Matrix interacts with the main Reason sequencer in the following ways:

- **The tempo set on the transport panel is used for all playback.**
  If the Tempo track (see "Recording tempo automation") is used, Matrix will follow this.
- **If you start playback for the main sequencer (on the transport panel), the Matrix will automatically start as well (provided the pattern sequencer hasn't been disabled - see below).**
- **You can mute and solo Matrix tracks in the sequencer.**
  If the Matrix has a track in the sequencer and you mute this track, Matrix will automatically be muted as well. This is indicated by a Mute indicator on the device panel. If there are several note lanes on the Matrix track, their respective mute status will not be indicated on the device panel.
- ▶ **You can also run Matrix separately (without starting the main sequencer) by clicking the Run button on the device panel.**
  This starts the built-in pattern sequencer in the device. To stop playback, click the Run button again or click the Stop button on the Transport panel.
- **If you are running Matrix separately and start playback of the main sequencer, the pattern device will automatically restart in sync with the sequencer.**

- **Pattern changes can be controlled by a pattern lane in the main sequencer.**
  In other words, you can record or create pattern changes in the main sequencer, and have them occur at the correct position on playback.

Selecting Patterns

The Matrix has 32 pattern memories, divided into four banks (A, B, C, D).



The Bank and Pattern buttons for the Matrix pattern sequencer.

- ▶ **To select a pattern in the current bank, click on the desired Pattern button (1-8).**
- ▶ **To select a pattern in another bank, first click the desired Bank button (A, B, C, D) and then click the Pattern button.**
  Nothing happens until you click the Pattern button.

The pattern change takes effect on the next downbeat according to the time signature set in the transport panel or on the transport track.

The Pattern Enable switch



The Pattern Enable switch.

Next to the Bank and Pattern buttons you will find an additional switch, which is normally activated. If you click this to turn it off, the pattern playback will be disabled, starting at the next downbeat - exactly as if you had selected an empty (silent) pattern. For example, this can be used for bringing Matrix patterns in and out of the mix during playback.

Steps

Matrix patterns consist of a number of discrete steps. For each step, you can enter a note, a CV value and a Curve value. When you run the pattern, each step will be played back in turn and will play a sound or send out the information programmed for this step. If you have ever used a drum machine, this will be obvious to you.

Clearing a Pattern

To clear (empty) a pattern, select it and use the Clear Pattern command on the Edit menu or device context menu.

- ! **Note that clearing a pattern doesn't affect the pattern length, resolution or shuffle settings!**

Using Cut, Copy and Paste

By using the Cut, Copy and Paste Pattern commands on the Edit menu or device context menu, you can move or duplicate patterns. The following rules apply:

- **Copy Pattern makes a copy of the currently selected pattern and places the copy on the clipboard.**
- **Cut Pattern moves the currently selected pattern to the clipboard.**
  This is the same as first performing Copy Pattern and then Clear Pattern.
- **Paste Pattern copies the pattern on the clipboard to the selected pattern location in the selected device.**
  This overwrites the selected pattern with the one on the clipboard.

Transferring patterns between Reason songs

If you want to copy patterns between different Reason songs, you use copy and paste:

1. **Open both songs.**
2. **Select the pattern you want to copy.**
3. **Select Copy Pattern from the Edit menu or the device context menu.**
   You can also hold [Ctrl](Win) or [Cmd](Mac) and press [C] to copy.
4. **Make the other song active.**
   This is done by clicking in the song window or by selecting the song from the Windows menu.
5. **Select the bank and pattern location to which you want to copy the pattern.**
   Note that any pattern already stored in that location will be overwritten!
6. **Select Paste Pattern from the Edit menu or the device context menu.**
   You can also hold [Ctrl](Win) or [Cmd](Mac) and press [V] to copy.

Tutorial


The programming procedure of the Matrix is to input note and gate values into the upper and lower fields of the pattern window respectively. You can input values by clicking or dragging in the pattern window. Proceed as follows:

1. **Create a Subtractor synth.**
   You don't have to use the Subtractor device to use the Matrix, in fact you don't have to use an instrument device at all, but for this basic tutorial we will use a "standard" setup.


2. **With the Subtractor selected, create a Matrix Pattern Sequencer.**
   The Matrix Note and Gate CV outputs will now be auto-routed to Subtractors Sequencer Control Gate and CV inputs, as you can see if you flip the rack around.




3. **Make sure that the switch to the left of the pattern window is set to "Keys" position.**
   As you can see, there are two rows of red rectangles. The one with horizontal rectangles at the bottom of the upper field in the pattern window represent note pitch, for each step in a pattern. At the moment they are all set to the same note pitch. The row of vertical rectangles in the lower field represent Gate velocity values - currently these are all set to a velocity value of 100 for all steps.



4. **Click inside the upper grid section of the Matrix pattern window.**
   An orientation line is displayed in the grid to make it easier for you to find the desired note, and the red rectangles are placed according to where you click. You can drag to input continuous note values.




5. **Click and drag in the lower area of the pattern window.**
   You can create vertical Gate velocity strips of varying heights. The higher the strip, the higher the velocity value.



6. **Press the Play button on the Matrix.**
   The pattern you "programmed" in the previous steps is now repeated. At the top of the pattern window, a red rectangle indicates every step of the pattern.

- **If you now click or drag in the upper grid section with the pattern playing, you can hear how the note pitches change.**
  The note pitch corresponds to the keyboard printed to the left of the pattern window, in a one octave range, and as previously mentioned, an orientation line is visible when clicking or dragging, making it easy to find the note pitch on the keyboard.
- **If you now click or drag in the lower gate section while the pattern is playing, you can hear how the timbre and volume changes.**
- **If you drag some of the vertical rectangles down so that they disappear from view, the corresponding steps of the pattern are completely silenced.**
- **By using the 5-way switch below the "Keys/Curve" switch you can input notes in other octave ranges (over five octaves).**
  Note that there can only be one note for each step in the pattern.



7. **By using a combination of the methods described in the above steps, you can program suitable note values for each step, decide which steps should be played and set their velocity with the gate values.**

Using Curve Patterns


Curve patterns are independent patterns that can be applied separately to the note pattern programmed in "Keys" mode. If you switch the Keys/Curve switch to "Curve", the note, but not the gate steps, disappear from view, and leaves the upper area of the pattern window empty. You can now start programming a curve pattern. Proceed as follows:

1. **Draw a curve, using the same method as for notes or gates.**
   As you can see, the Curve pattern looks like large vertical gate steps.


- **If you play the pattern, nothing has changed, i.e. the pattern sounds exactly like it did before the Curve pattern was drawn.**
  This is because the Curve CV output hasn't been connected to any parameter yet.

2. **Flip the rack around so you can see the back panel of the Matrix.**
3. **Connect the Curve CV output to the Filter Cutoff Modulation Input on the Subtractor.**
   Now the curve pattern controls the filter frequency of the Subtractor.

- **If the effect isn't very noticeable, try raising the filter Q parameter, and lowering the filter frequency.**
- **The Curve CV output can be connected to any device CV or Modulation input.**
  Actually, Curve CV signals can also produce Gate triggers (used for triggering samples or envelopes for example).
- **A Gate trigger is produced for each curve pattern step that follows a value of "0".**
  If you look at the picture below, steps 2,4 and 6 will produce a trigger, because steps 1, 3 and 5 are set to zero, but the rest of the pattern would not.




About Unipolar and Bipolar Curves




On the back panel of the Matrix you will find a switch, allowing you to select between "Unipolar" or "Bipolar" Curves. The difference is as follows:

- **A unipolar curve has values starting from "0" and up.**
  "0" is the value produced by all steps when they are "empty" (not visible). Unipolar is the default setting of this switch when a new Matrix is created.



Unipolar curve

- **A bipolar curve is divided in the "middle", with the middle representing a value of "0".**
  The curve reflects this. If no curve has been drawn and you switch to bipolar mode, all steps go from the bottom up to the middle of the scale printed to the left of the pattern window. Thus, all steps are at "0", and the curve can be drawn both up and down from the middle.



Bipolar curve

Bipolar curves are essential in some instances. If you want to use the Matrix to CV control the Pan parameter for a mixer channel for example, a unipolar curve would start at zero - which for Pan equals center position. This means that you would only be able to use the curve to pan in *one direction* from this center position. A bipolar curve however, will have the zero value in the middle, allowing you to draw pan curves in both directions. Bipolar curves can also be used for controlling parameters with positive and negative values.

Setting Pattern Length



You may want to make settings for Pattern length, i.e. the number of steps the pattern should play before repeating:

- **The "Steps" spin controls are used to set the number of steps you wish the pattern to play.**
  The range is 1 to 32. You can always extend the number of steps at a later stage, as this will merely add empty steps at the end of the original pattern. You could also make it shorter, but that would (obviously) mean that the steps you remove won't play back. The steps you remove aren't erased though, if you set the step number back again, anything recorded in the previously removed step locations will be played back.

Using Tied Notes

If you activate "Tie" to the left of the Gate pattern window, you can create longer notes (eighth notes, quarter notes etc.). A quick way to draw tied gates is to hold down [Shift] when you input the gate values.



Entering tied gate values.

- **Each step that has one tied gate value will be twice the length compared to a normal step.**
  Tied gate steps are indicated by being twice as wide in the pattern window.
- **If two or more notes of the same pitch are tied together, the result will be even longer notes.**


Tied notes are also essential if you want to create typical TB-303 "Acid"-type lead lines - see "Programming "Acid Style" lead lines".

Setting Pattern Resolution


Matrix always follows the tempo setting on the transport panel, but you can also make Matrix play in different tempo "resolutions" in relation to the tempo setting.

Pattern Shuffle

Shuffle is a rhythmic feature, that gives the music a more or less pronounced swing feel. It works by delaying all sixteenth notes that fall in between the eighth notes.



Straight sixteenth note pattern (viewed in the sequencer).



The same sixteenth note pattern with shuffle applied.

In Reason, you can activate or deactivate shuffle individually for each pattern in a pattern device. However, the amount of shuffle is set globally with the Global Shuffle control in the ReGroove Mixer. The ReGroove Mixer is described in "The ReGroove Mixer".



The Shuffle on/off switch in Matrix and the Global Shuffle control in the ReGroove Mixer on the transport panel.

Pattern Mute

If you deactivate the "Pattern" button above the Pattern select buttons, the pattern playback will be muted, starting at the next downbeat (exactly as if you had selected an empty (silent) pattern). For example, this can be used for bringing different pattern devices in and out of the mix during playback.

If you mute the Matrix track in the sequencer, it is muted instantly and the Mute indicator lights up on the panel. Note that all tracks connected to the Matrix must be muted for this to work.

Pattern Functions

When a pattern device is selected, you will find some specific pattern functions on the Edit menu (and on the device context menu).

Shift Pattern Left/Right

The Shift Pattern functions move the notes and corresponding gate values in a pattern one step to the left or right.

Shift Pattern Up/Down

! **This function does not alter the Curve CV. This is because the values produced by the Curve CV do not necessarily correspond to semitone note steps at all.**

The Shift Pattern functions will transpose all the notes in a pattern one semitone up or down.

Randomize Pattern

The Randomize Pattern function create random patterns. These can often be great starting points and help you get new ideas. Both Note, Gate and Curve CV values will be created.

Alter Pattern

The Alter Pattern function modifies existing patterns. Note that there must be something in the pattern for the function to work on - using an Alter function on an empty pattern will not do anything.

! **Note that Randomize and Alter affects both the Gate, Note and Curve CV!**

Chaining Patterns

When you have created several patterns that belong together, you will most probably want to make these play back in a certain order.

- **Simply activate record for the track with the Matrix as the destination in the sequencer and use the Pattern and Bank buttons to determine the playback order as the Song is playing.**
  The Patterns play to the end before changing, so you won't have worry too much over the "timing" of the pattern changes you input manually. When you are done, the sequencer track will contain pattern change data, and the patterns will automatically switch according to the order set while recording. More on recording pattern changes on "Recording pattern automation".
- **An alternative way to do this is editing directly in the Pattern Edit lane in the sequencer.**
  Editing in the Pattern lane is described in the Sequencer chapter.

Converting Pattern data to notes in the main sequencer

You can convert Matrix Patterns to notes in the main sequencer. This allows you to edit the notes freely, create variations or use Groove quantizing.

The "Copy Pattern to Track" function

This function is useful when you have created a single pattern in the Matrix device and want to render individual note events on a sequencer track.

! **Curve patterns cannot be converted to sequencer data! Only the note pattern and the gate values will be converted.**

Proceed as follows:

1. **Set the Left and Right Locators to encompass the section you want to "fill" with the notes in the pattern.**
   You may want to make sure that the space between the locators is a multiple of the pattern length, to avoid "cutting off" the pattern.
2. **Select the track you wish to copy the rendered notes to.**
   You should not copy the notes to the Matrix track, but to the track for the device controlled by the Matrix (since the Matrix doesn't produce any sound in itself). You can also copy the notes to any other instrument track if you like.
3. **Select the Matrix device in the rack and select "Copy Pattern to Track" from the Edit menu or the device context menu.**
   The pattern is converted to a single note clip on the track, with Note and Gate (Velocity) values. If the space between the locators is greater than the pattern length, the pattern will be repeated in the clip to fill up the space.

When you use the "Copy Pattern to Track" function with the Matrix, you should note the following:

- **A note will be created for each pattern step which has a Gate value greater than zero.**
  The notes will have the pitch according to the key CV value for the step, and the velocity according to the Gate value.

! **The Curve CV is not copied.**

- **You may want to disconnect or even remove the Matrix device after performing this function.**
  This is because you probably don't want both the Matrix and the sequencer notes to play the device at the same time and thus cause "note doubling".

▶ **The procedure above copies a single pattern to notes in the sequencer. If you have automated pattern changes, you can copy a complete pattern track to notes, taking all pattern changes into account.**

The "Convert Pattern Automation to Notes" function

If you have recorded or drawn pattern automation on a Matrix track, you can have the whole track converted to notes, in the following way:

1. **Select the track with the pattern automation.**
2. **Select "Convert Pattern Automation to Notes" from the Edit menu or the context menu for the track.**
   For each pattern clip, the corresponding pattern is converted to note clips on the track (following the same rules as for the "Copy Pattern to Track" function). The track will play back just the same as when you played the pattern device with the pattern changes.

▶ **After the operation, the Pattern Select lane is switched off.**
The Pattern (Enable) button on the device is automatically turned off.

▶ **When you use this with a Matrix, you need to move the note clips to the track of an instrument device (typically the device to which the Matrix is connected).**
This is because the Matrix doesn't make any sound itself.


Example usage

As mentioned previously, the Matrix is a very flexible device. Here follows a few examples of how you can use the Matrix Pattern Sequencer.

Using the Matrix for modulation

You can effectively use the Matrix as a modulation source, much like an LFO. Just like the LFOs in Reason's instrument devices, the Matrix can generate modulation that is synchronized to tempo, which has many advantages. Proceed as follows:

1. **Create a Synthesizer (e.g. a Subtractor or Malström).**
2. **Create a Matrix Pattern Sequencer, or if one already exists, set it to an empty pattern.**
3. **Flip the rack around and disconnect the Gate and Note CV outputs.**
   Gate/Note CV is not used in this example
4. **Flip the rack around and connect the Curve CV output on the Matrix back panel to the "Amp Level" Modulation input on the synthesizer.**
   This parameter is used for modulating the output level (volume) of the synthesizer. Volume modulation is often referred to as Tremolo. You can use a unipolar curve (see "About Unipolar and Bipolar Curves") for this example.
5. **Flip the rack back again, and switch the Matrix to display the Curve pattern window.**
6. **Draw a curve like the one shown in the illustration below.**
   If you use fewer or more steps than16 (as shown in the picture), just draw the curve so that it roughly matches the shape in the picture.



7. **Activate Click on the Transport Panel.**
8. **Select the track that is routed to the synthesizer, so that you can play it from your MIDI keyboard.**
9. **Activate Play on the transport panel, and hold a chord down on your keyboard.**
   You should now hear the volume being modulated by the Curve pattern.
10. **While still in play mode, you can use the Resolution knob to change the modulation "rate" in relation to the tempo.**
    For each clockwise resolution step the modulation speed is doubled and vice versa, but it will always stay in sync with the tempo.

Programming “Acid Style” lead lines

By “acid style” lead lines we mean patterns that use a combination of Legato and slide (or portamento) effects to produce the widely used hypnotic “wavy” sound produced by the original Roland TB-303, and recreated in the Propellerhead Software product ReBirth. To approximate this typical sound using Reason, proceed as follows:

1. **Create a Synthesizer (Subtractor or Malström).**
2. **Create a Matrix Pattern Sequencer, or if one already exists, set it to an empty pattern.**
3. **Make sure that the Note and Gate CV outputs are connected to the synthesizers Sequencer Control CV and Gate inputs, respectively.**
4. **For Subtractor, select either a Init Patch, or use the “TB Synth” patch in the Monosynth category of the Reason Factory Sound Bank.**

▶ **If you use an Init patch, it is important that you make the following settings:**

- **Set Polyphony to “1”.**
- **Switch Trigger Mode to “Legato”.**
- **Set Portamento to a value around “50”.**

5. **Create a pattern in Matrix, and keep it playing back.**

▶ **If “Tie” (see “Using Tied Notes”) now is activated for a step, the note will be tied to the next and the pitch will continuously “glide” to the pitch of the following step.**
Please note that Tie should be activated on the note you wish to slide from, and not the note you slide to.

▶ **If you have several tied notes, one after the other, they will play as one long legato phrase. This can be used to create “wavy” lead lines with pitch bend effects.**

6. **Experiment with different Note, Tie and Gate values.**
If you have ever used a TB-303 or ReBirth, you should now begin to get the hang of how you can create patterns in that particular style by using the Matrix together with a synthesizer.

▶ **Adding a DDL-1 (delay), and a D-11 (distortion) effect device will make it sound even more “ReBirth”-like, but of course you are also able to get a much wider range of timbres by utilizing Reason’s other sound and modulation capabilities.**

Triggering samples

The Gate CV output can be used to trigger samples, either in Redrum or in the NN-19 or NN-XT Sampler.

▶ **Connect the Matrix Gate CV out to the Gate (Sequencer Control) in on the NN-19/NN-XT or to one of the individual Gate Channel inputs of Redrum.**
Gate values will now trigger the sample on each step with Gate values above “0”.

Chapter 73
Mixer 14:2

Introduction




The Mixer 14:2 allows you to control the level, stereo placement (Pan), tone (EQ) and effect mix (AUX Sends) of each connected audio device.

If you have ever used a conventional hardware audio mixer, you will most likely find the Mixer very straightforward to use. It is configured with 14 (stereo) input channels, which are combined and routed to the Left and Right Master outputs. The vertical channel "strips" are identical and contain - from the top down - four Auxiliary Sends, an EQ section, Mute and Solo buttons, Pan control, and a Level fader.

Every mixer parameter can of course be automated.

The Channel Strip




Each channel strip in the Mixer 14:2 contains the items listed in "Channel Strip Controls".

Channel Strip Controls

Item	Description	Range
Channel Fader	The channel fader is used to control the output level of each corresponding channel. By adjusting the faders, you can set the desired mix (balance) between different devices connected to the Mixer.	0 - 127
Channel Label	Each channel in the mixer that has a device connected to it, displays a read-only label with the name of the device to the left of the fader.	N/A
Channel Meter	The meter is a graphical representation of the channel output level. If the signal level pushes the meter into the range of the red area, try lowering either the output level of the device connected to the channel, or the channel fader itself, to avoid distortion.	N/A
Pan Control	Use this control to set the left/right position of the channel in the stereo field. [Command]/[Ctrl]-click the Pan knob to set Pan to the default "0" (center position).	-64 – 0 – 63
Mute (M) and Solo (S) Buttons	Clicking a channel's Mute button silences the output of that channel. Click the button again to unmute the channel. Clicking a channel's Solo button silences all other mixer channels, so that you only hear the soloed channel. Several channels can be soloed at the same time, but if this is the case, note that soloed channels can't be muted with the Mute button. To mute one of several channels in solo mode you simply "unsolo" it.	On/Off
EQ Treble and Bass controls	The EQ Treble and Bass controls is used to cut or boost the higher and lower frequencies of the signal, respectively. Click on the EQ button to activate the EQ. If you need more advanced EQ, you can always use a PEQ2 parametric EQ as an insert effect for a device. Note also the two EQ modes - see "About the EQ modes".	Treble: +/- 24 dB at 12 kHz. Bass: +/- 24 dB at 80 Hz.
Auxiliary (AUX) Effect Send 1-4	The four independent AUX Sends control the amount of channel signal that is to be sent to other devices - typically effect processors. The effect output is then normally returned to the Mixer via the AUX Return inputs (see "The Auxiliary Return Section") where it is mixed with the dry (non-processed) signal. If you create an effect device when the Mixer is selected, the effect is auto-routed to the first available Send/Return connectors. You can then control the amount of effect that is to be applied to any device connected to a Mixer channel via the corresponding AUX Send knob. The AUX Send outputs are taken post channel fader, but you have the option of selecting Pre-fader mode for AUX Send 4 (by clicking the "P" button next to the send so that it lights up). In that mode, the send level is independent of the channel fader. The sends are in stereo but can be used in mono as well.	0 - 127

The Mixer signal flow

The basic signal flow for a channel in the Mixer 14:2 is as follows:



Note that the Solo function is true "in-place" solo, meaning that if the channel uses Auxiliary sends routed to effect devices, the soloed output signal will also include the soloed channel(s) including any Aux Send effects.

Note also that if the pre-fader send mode is activated for Aux 4 the send is tapped after the EQ and Pan controls but before the channel fader.

About the EQ modes



With Reason 2.5, the EQ modules in the Mixer were improved to get an even better sound and character. However, if you want to play back songs made in previous Reason versions, you may want to use the "old" EQ mode to ensure that the songs sound exactly the same.

On the back of the Mixer 14:2 you will find a switch for this - select "Improved EQ" for the new EQ types or "Compatible EQ" for the old-style EQ. The parameters are exactly the same in both cases.

The Auxiliary Return Section



The Auxiliary Returns provide an "extra" four stereo inputs in addition to the Mixer 14:2's 14 stereo channels. The main function of Return channels is to provide inputs for connected Send effects devices. Each Aux Return channel has a level control, and a read-only tape label that display the name of the device connected to the Return channel.

The Master Fader



The Master L/R fader controls the summed output level of all channels in the Mixer 14:2. Use this to change the relative level of all channels, to make fade-outs etc.

Connections

All input and output connectors are as usual located on the back panel of the Mixer 14:2. Special connectors are used for "chaining" two or more Mixer 14:2 devices together. This is described on "Chaining several Mixer 14:2 devices".

Mixer Channel Connections

- **Each mixer channel features stereo left/right inputs for connecting audio devices.**
  Use the left input when manually connecting a mono signal source.
- **In addition, there are two Control Voltage (CV) inputs (with associated voltage trim pots), for voltage controlling channel Level and Pan from other devices.**

Auxiliary (AUX) Send Out



- **There are four stereo Send Out connectors, which normally are used to connect to the inputs of effect devices.**
  To connect a send to a mono-input device, use the Left (Mono) output.

When a Send is connected to an effects device, the corresponding AUX Send knob determines the level of the signal sent to the effect device for each channel. The Send Output is taken post-channel fader but you have the option of selecting pre-fader mode for AUX Send 4.

- **Note that some effects (for example the Comp-01 compressor or the PEQ2 parametric EQ) are effect types which are not designed to be used as AUX Send effects, but rather as insert effects, where the whole signal is passed through the effect.**
  Alternatively, you could use AUX Send 4 in pre-fader mode and lower the channel fader completely.

Auxiliary (AUX) Returns




- **There are four stereo Return input connectors.**
  These are normally connected to the left and right outputs of effect devices.

Master Left/Right Outputs



- **The Master outputs are auto-routed to the input pair of the first available Mix Channel device in the rack.**
  If no Mix Channel device is available, one will be automatically created when you create a Mixer 14:2 device.
- **In addition to the Master Out connectors, there is a Control Voltage (CV) input (and an associated trim pot), for voltage controlling the Master Level from another device.**

Chaining several Mixer 14:2 devices



Two chained Mixer 14:2 devices are connected like this, the top Mixer being the "Master" Mixer.

If you want more Mixer channels, you can chain several Mixer 14:2 devices.

- ▶ **Select the existing Mixer 14:2 device and choose "Create:Mixer 14:2" from the Create menu or context menu.**
  The new Mixer is automatically connected via the "Chaining Master" and "Chaining Aux" connectors of the selected Mixer.
- ▪ **The newly created Mixer's Master Output is connected to the original Mixer's Chaining Master input.**
  The Master Out Level for the new Mixer is now controllable from the original Mixer's Master fader - so that this fader now controls the Master output level of both mixers.
- ▪ **The newly created Mixer's four stereo Aux Send outputs is connected to the original Mixer's Chaining Aux connectors.**
  The new Mixer will now have access to any Aux Send effects connected to the original Mixer, via the same corresponding Aux Send(s).

This way, the two Mixers operate as "one".

! **One exception is the Mute/Solo function, which is not chained. Thus, soloing a channel in one of the Mixers, will not mute the channels in the other Mixer.**

You can create as many Mixers as you like, they will be chained in the same way, with one Mixer remaining the "master" (i.e. it controls the Master level of all chained Mixers and supplies the Aux Send effect sources).

Partially or Non-Chained Mixers

You can also have several Mixers that are only partially or not chained at all.

- ▪ **You may for example wish to have different Aux Send effects for one Mixer.**
  Then simply disconnect one or more of the Send Out to Chaining Aux connectors, and assign new Send effects.
- ▶ **You could for example send the Master output of one Mixer to another Mix Channel device, instead of the Chaining Master inputs.**

Chapter 74
Pulsar Dual LFO

Introduction



The Pulsar Rack Extension device is a very flexible and versatile dual LFO module. LFOs (Low Frequency Oscillator) are used for generating cyclic modulation signals. A typical example is to have an LFO modulate the pitch of an oscillator to generate vibrato, but there are countless of other applications for LFOs.

Pulsar features two separate LFOs that can be used for modulating parameters in other rack devices. The two LFOs can also modulate each other to generate complex modulation signals. The LFOs in Pulsar can reach way up in the audible frequency range, which opens up for really interesting applications. As an additional feature the LFO rates can also be tracked from a MIDI keyboard.

In Reason the Pulsar Rack Extension device can be found on the Utilities palette.

Panel parameters

LFO 1&2 common parameters

Rate



This controls the LFO rate. The Rate range in Pulsar is very wide and can reach way up in the audio frequency range. The rate is indicated by the lamp to the left above the Rate knob. The rate can also be synced to the sequencer tempo by clicking the Tempo Sync button below the Rate knob (see "Tempo Sync" below). In sync mode, the Rate knob controls the sync resolution.

The LFO 1 Rate can be modulated and/or synced by LFO 2, see "Rate (LFO 2 to LFO 1 Rate)" and "Sync". The Rates can also be modulated from the Envelope, see "Envelope". As a special feature, the Rates can also be controlled from a MIDI keyboard, see "KBD Follow".

Range: 0.06Hz-1.05kHz (synced: 32/4 to 1/64th)

! **When the Rate is modulated, it can reach far beyond the default frequency range.**

Waveform selectors



Here you can select one of nine different LFO waveforms. Besides the standard waveforms (sine, triangle, pulse, etc.) there are random, slope and stepped waveforms. The shape of the waveforms are shown in the display.

! **Note that all waveforms are bipolar, i.e., they generate both positive and negative levels.**

- **Select waveform for each LFO by clicking the up/down arrow buttons or by clicking and holding in the waveform display and dragging up/down.**

Level




Here you set the output level of the LFO signal. The LFO 1 Level can be modulated by LFO 2, see "Level (LFO 2 to LFO 1 Level)". The Levels can also be modulated by the Envelope, see "Envelope".

Phase




The Phase control lets you offset the phase of the LFO cycle, i.e. decide where in the cycle the waveform should start. The range of the Phase control is 0-360 degrees:



Shuffle



The Shuffle function affects two adjacent LFO cycles, in pairs. Increasing the Shuffle value lengthens the first cycle and shortens the second one:



Note that the total length of the cycle pair is always 2 regular cycles, which means that shuffling will work great also in Tempo Sync mode, see "Tempo Sync".

Range: 50% (no shuffle) to 75%

Lag



The Lag control acts like a lowpass filter on the LFO signal, making the signal smoother. This is especially noticeable on waveforms with sharp edges or transients like the square, sawtooth and stepped waves. On the sinewave you will barely notice any effect since it's already smooth by nature.


Tempo Sync



Click the Tempo Sync button to sync the LFO Rate to the sequencer tempo. This is great for creating animated effects in sync with the song's tempo. In Tempo Sync mode, the Rate knob controls the sync resolution, see "Rate".

LFO 1 specific parameters

ENV Sync



With ENV Sync active, whatever triggers the Envelope will also restart LFO 1, see "Envelope".

If Tempo Sync is also active (see "Tempo Sync") the LFO will continue to sync to the sequencer tempo. However, *when* you actually press a key or hit the Trig button will affect the LFO cycle start. In some situations this could be perceived as the LFO is losing sync but it's not; it's merely the LFO cycle start that is changing.


LFO 2 specific parameters

On/Off



Click this to activate LFO 2.

LFO 2 to LFO 1 modulation parameters



Rate (LFO 2 to LFO 1 Rate)

This controls the modulation amount from the LFO 2 signal level to LFO 1's Rate. The result is frequency modulation (FM) of LFO 1.

Level (LFO 2 to LFO 1 Level)

This controls the modulation amount from the LFO 2 signal level to LFO 1's Level. The result is amplitude modulation (AM) of LFO 1.

Sync

With the Sync button on, every new LFO 2 cycle automatically restarts LFO 1.

Envelope



This is an AR (Attack-Release) envelope. The Envelope can be triggered from any of these four sources:

- **The Trig button, see "Trig".**
- **LFO 2, see "LFO 2 Trig".**
- **Envelope Gate In modulation input on the rear panel, see "Envelope Gate In".**
- **MIDI Note On from a connected MIDI keyboard.**

The Envelope can modulate the Levels and Rates of LFO 1 and/or LFO 2.

! **If the envelope is retriggered before all envelope stages are completed, the envelope will simply restart at the current level (similar to how a monophonic synthesizer works).**

LFO 2 Trig

With the LFO 2 Trig button on, the Envelope is automatically synced by the LFO 2 signal. This means that every time LFO 2 begins a new cycle, the envelope is triggered.

Trig

This is a non-latching gate button which gates/triggers the envelope.


Attack and Release

The attack and release times of the envelope when the gate opens/closes are set with these knobs. For a gated effect set both controls to zero and control the gate time with the Trig button, CV Gate In modulation input or MIDI Notes. You can also let LFO 2 trig/gate the envelope as described above.

Range: 0.1ms-3.00s (Attack) and 0.0ms-10.00s (Release)


Rate (LFO 1 and 2 Envelope modulation)

The Rate knobs control the modulation amount of the Rate parameters of LFO 1 and 2 respectively. With these you can force the LFO rates to vary according to the envelope's Attack and Release times:



Env Attack = 0, Env Release > 0, Rate modulation = +50%


The Rate modulation controls are bipolar, with no modulation at 12 the o'clock position, negative modulation to the left and positive to the right. Negative modulation means that the LFO Rate gets slower during the envelope stage and then goes back to the set Rate:



Env Attack = 0, Env Release > 0, Rate modulation = -50%


Level (LFO 1 and 2 Envelope modulation)

The Level knobs control the modulation amount of the Level parameters of LFO 1 and 2 respectively:



Env Attack = 0, Env Release > 0, Level modulation = +50%

The Level modulation controls are bipolar, with no envelope modulation at 12 the o'clock position, negative modulation to the left and positive to the right. Negative modulation means that the LFO signal decreases in level during the envelope stages and then goes back to set Level:



Env Attack = 0, Env Release > 0, Level modulation = -50%

KBD Follow



It's possible to control the LFO Rates in Pulsar from a connected MIDI keyboard:

- **Create a sequencer track for Pulsar by selecting "Create Track for Pulsar n" from the context menu (right-click the device in the rack).**
  A sequencer track is created and is automatically selected.

With the KBD Follow knob you can define how the LFO Rates should be modulated by incoming MIDI Note data. The KBD Follow parameter is bipolar:

- **At zero (12 o'clock position), the Rates are not modulated at all.**
- **At 100 the LFO Rates track the incoming MIDI Notes 1:1, which means you can "play" the LFOs chromatically from a connected MIDI keyboard.**
- **At -100 the LFO Rates tracks the incoming MIDI Notes "backwards" chromatically, which means the LFOs run slower the higher up on the keyboard you play, and vice versa.**
  The center MIDI note, i.e. where the LFO Rates "intersect" with the MIDI Note, is C3.

If Tempo Sync is enabled for the LFO(s) you will be able to do cool wobble effects by playing various notes on your MIDI keyboard, see "Tempo Sync".

Modulation inputs and outputs



LFO 1&2 input sections



Rate

Use this for dynamically modulating the Rate of the corresponding LFO. Attenuate the input signal with the knob.

Phase

Use this for dynamically modulating the Phase of the corresponding LFO. Attenuate the input signal with the knob.

Shuffle

Use this for dynamically modulating the Shuffle amount. Attenuate the input signal with the knob.

Amount

Use this for dynamically modulating the Level of the corresponding LFO. Attenuate the input signal with the knob.

LFO 1&2 output sections



CV

There are two CV signal outputs for each LFO, plus two additional outputs for the CV signal phase inverted.

Audio

There are two Audio signal outputs for each LFO, plus two additional outputs for the Audio signal phase inverted.

The difference between the Audio outputs and the CV outputs is that the signals on the Audio outputs have higher quality for use in e.g. audio processing applications.

Output LFO 1+2




CV

There is one CV signal output for the LFO 1 and 2 signals summed with each other.

Audio

There is one Audio signal output for the LFO 1 and 2 signals summed with each other at audio quality.

Envelope connections



Envelope Gate In

A CV signal with a value > 0 present on this input will gate the Envelope (see "Envelope"). When the CV input signal decreases to zero or below, the gate is opened (deactivated).

Envelope CV Out

There is one CV signal output for the Envelope signal.

Tips and Tricks

Patch between LFO 1 and LFO 2 on the back for more flexibility

- **By connecting one LFO CV output to the Phase CV input of the other LFO you can achieve some very interesting rhythms. Try using a square wave and set the CV Trim rotary to around 25%.**
- **Try connecting an LFO CV output to the Shuffle CV input of the other LFO. Use the sawtooth waveform, at a slow Rate, in the first LFO to gradually add more shuffle over time.**
- **With the Envelope CV Out you can control both Shuffle and Phase from the Envelope and with the Envelope CV In you can trigger this effect with any CV signal.**

Using Pulsar as a monophonic synth

Because the LFO 1&2 can work in audio rate and can be tracked from a MIDI keyboard, it's possible to use Pulsar as a two oscillator mono synth with a lot of character. Here's how to set this up:

1. **Make sure the level of the LFO(s) you want to use is completely turned down.**
2. **Connect the Audio output of the LFO(s) you want to use to a Mix Channel device.**
3. **Create a sequencer track for Pulsar by right-clicking the device in the rack and selecting "Create Track for Pulsar n".**
   A sequencer track is created and is automatically selected.
4. **Turn KBD Follow up to 100%.**
5. **Turn up the Level knob(s) in the Envelope section for the LFO(s) you want to use.**
   This decides how much the level of the LFO(s) will be affected by the envelope when you play.
6. **You can now play Pulsar from your MIDI keyboard!**

! **You have to tune Pulsar manually by adjusting the Rate(s) of the LFO(s) you are using. You can set the Rate knob(s) to max (1.05kHz) to be completely in tune - however, the Pulsar will then be 2 octaves above played MIDI note. Lower octaves can be found at around 524Hz and 263Hz (hold [Shift] to fine tune).**

! **Note that Pulsar is an LFO device and therefore doesn't feature the standard sound improvement features of a synth device (anti-aliasing filters etc.).**

▶ **By using LFO 2 to LFO 1 Rate modulation you can modulate the frequency of LFO 1, resulting in frequency modulation (FM).**

▶ **By using LFO 2 to LFO 1 Level modulation you can modulate the level of LFO 1, resulting in amplitude modulation (AM).**

▶ **By modulating the Shuffle you can achieve a sound similar to pulse width modulation (PWM), great for harsher tones!**

Chapter 75
RPG-8 Arpeggiator

Introduction



An arpeggiator generates rhythmic note patterns (arpeggios) from notes or chords. The RPG-8 Arpeggiator doesn't generate sound on its own, but has to be connected to another instrument device (just like the Matrix). It works by converting MIDI note data (input to the RPG-8) to Note CV (pitch) and Gate CV (note on/off plus velocity) signals. These CV/Gate signals are sent to the corresponding Sequencer Control inputs of an instrument device.

In addition to standard arpeggiator features the RPG-8 is equipped with a 16 step pattern editor for creating rhythmic variations.


The RPG-8 is monophonic and can control one voice in a connected instrument device.

Using the RPG-8

Setting up

The basic procedure is to input note data, either live or recorded, to the RPG-8 device. This note data is in turn sent to a target device via its Sequencer Control CV/Gate inputs. The resulting output from the target device can either be arpeggiated notes or simply mirror what is played on your control surface device. Proceed as follows:

1. **Create an instrument device, e.g. a Subtractor.**
   Select a suitable patch, preferably one with a short attack time.
2. **With the instrument device selected, create an RPG-8 Arpeggiator.**
   A sequencer track with MIDI focus named "Arp 1" is created for the RPG-8. The RPG-8 Note and Gate CV outputs will be auto-routed to the instrument device Sequencer Control Gate and CV inputs, as you can see if you flip the rack around. In addition, the Mod Wheel and Pitch Bend CV outs are also auto-routed to the corresponding modulation inputs on the target device.



3. **Make sure the Arpeggiator Enable ("On") button on the upper part of the panel is activated.**



4. **With Master Keyboard input set to the Arp 1 sequencer track, play a few notes.**
   The notes in the chord you play are now arpeggiated for as long as you hold down the keys. The arpeggio will change directly if you release all notes and play another note or chord. If you add notes while holding down a chord, the arpeggio will continue with the added notes.



- **The display shows the notes played by the arpeggio pattern, with small bars indicating pitch for each step. The display is continuously updated as you play.**
- **The arpeggio will play in sync with song tempo by default in new RPG-8 devices.**
- **You do not need to start playback to generate arpeggios.**

- **Try changing the arpeggiator mode using the Mode knob.**
  The various modes govern how the notes are arpeggiated. For example "Up" means from lowest note to highest note, Up+Down from lowest to highest note, then back down to lowest note again. For a description of all the modes see "Mode switch".
- **By activating the Hold button the arpeggio will continue to play even if you release the keys.**
  If you play a new chord the arpeggio will continue to play, using the new notes. To stop the arpeggio, deactivate the Hold button or hit Stop on the transport. See "Hold On/Off".
- **The "Insert" buttons can be used to introduce further variations to the arpeggio.**
  See "Insert buttons".
- **If you change the Rate parameter the rate of the arpeggiated notes will follow the song tempo at the selected note value resolution.**
  Straight, triplet and dotted note values are available. The arpeggiator can also be free running, i.e. not synced to tempo - see "Rate".
- **The Gate Length knob allows you to adjust the length of the arpeggiated notes.**
  If the knob is turned fully clockwise ("Tie"), the gate is always open (the notes will be played legato). If it is turned fully counter-clockwise, the gate is closed (no sound). See "Gate Length".
- **By using the Octave buttons beside the Mode knob you can increase or decrease the octave range of the arpeggio.**
  With "1 Oct" selected the arpeggiated notes will be those that you press down on the keyboard. If "2 Oct" is selected the range will be expanded so that the arpeggiated notes play over two octaves, and so on - see "Octave range buttons".
- **You can transpose the arpeggio up or down in octave steps using the Octave Shift buttons.**
  See "Octave Shift".
- **By using the Velocity knob you can set the arpeggio to play with a fixed velocity value (selectable between 1 to 127) for all notes. Turning the knob fully clockwise to the "Manual" position means that the arpeggio notes will use the same velocity as the MIDI notes you input.**
  By using the Manual mode and varying the velocity for individual notes the arpeggio will become more animated and rhythmic. See "Velocity".

That covers the basic principles of how to set up and use the RPG-8 to arpeggiate notes that you play in real time. But to make full use of the RPG-8 there are many further applications:

- **You can of course record and edit the notes you input.**
  You can also render the arpeggio output "to track" for full sequencer edit control of the notes generated by the RPG-8 - see "Rendering arpeggio notes to track".
- **You can introduce rests for more complex rhythmical arpeggios by using the Pattern editor.**
  See "Pattern editor" for a description.
- **You can use the RPG-8 as a MIDI to CV converter which allows you to freely assign common performance MIDI controllers like Mod Wheel and Aftertouch to control parameters - see "Using the RPG-8 as a MIDI to CV converter".**

Recording MIDI note data for the RPG-8 - simple tutorial

The notes that you feed into the Arpeggiator can be recorded and edited in the sequencer. This works pretty much like recording/editing normally, but with a few exceptions which will be duly noted.

In this section we will go through the basic principles of recording MIDI data. As several functions are described later in this chapter (e.g. the Pattern editor) we will keep things simple in this tutorial.

To record the notes you play into the RPG-8 you proceed as follows:


1. **Set Master Keyboard input to the "Arp" track.**
   Make sure the RPG-8 is connected to a target instrument device as described in "Setting up".
2. **Make sure the "On" button for the Arpeggiator is activated.**
   If you play a chord, this will now be arpeggiated.
3. **Set up the RPG-8 as you want it to play arpeggios.**
   For detailed descriptions of all the parameters, see "RPG-8 Parameters".

- **Note that if an arpeggio is playing before you enter recording, the notes that generated this arpeggio will not be recorded! This is because the note-ons have already occurred before recording commenced - only the notes that you enter after recording has started will be recorded.**

4. **Click the Record button in the main sequencer and start playing.**
5. **Hit stop when you are done recording.**

A clip has now been added to the Arp track containing the notes you just recorded. If you play back the clip from the top the arpeggio will play back as you recorded it.

- **If you switch to Note Edit mode for the Arp track, you will see that only the notes that you input to the RPG-8 were recorded - not the actual arpeggio notes generated by the RPG-8 and sent to the target device.**



The arpeggio you "recorded" is actually still being generated rather than played back. The only difference is that now the arpeggio is generated from the notes you recorded on the track rather than from the notes you played live. Thus, if you change any RPG-8 parameters like Rate or Mode this will change the arpeggio you hear.

When using this method the following points should be noted:

- **It will not be possible to edit the individual notes generated by the arpeggiator, only the source notes you play.**
  This may be fine, depending on the situation. If you simply played some wrong notes you can easily edit them in the sequencer as usual.
- **If you used Hold when recording (or if you activate Hold during playback) the arpeggio will play for as long the sequencer is in Play mode or until Hold is deactivated.**
  It is generally better to have Hold off when recording.

Depending on the situation, the above limitations may or may not be of concern. But there is a quick and effective solution to all above mentioned issues; the "Render Arpeggio Notes to Track" function (see "Rendering arpeggio notes to track").

Using multiple Lanes

You can record note data on several Lanes of the RPG-8 (Arp) track. If you do this, any overlapping note data will be merged and will not play separate arpeggios. The Arp track will always produce a monophonic output regardless of how many overlapping Lanes there are.

If you want to use separate simultaneous arpeggios, with each controlling one voice in a device, you have to use the "Arpeggio Notes to Track" function (see "Rendering arpeggio notes to track") to separate Lanes in the target device track.

Generating arpeggios from already recorded tracks

The RPG-8 can also be used to arpeggiate notes copied/moved from other tracks:

1. **Copy the clip(s) containing the notes you wish to arpeggiate.**
   You can also drag and drop clips between tracks to do this.
2. **Paste the clip(s) to the "Arp" track.**
3. **Activate Arpeggio On and activate playback.**
4. **If you only wish to hear the arpeggio, mute the sequencer track/lane you copied the source data from.**
   If you leave it unmuted you will hear both the original chords and the arpeggio.


Rendering arpeggio notes to track

This function allows you to render the arpeggio generated by RPG-8 to the target device track. The arpeggio output - rather than just the source notes that generate the arpeggio - will be rendered as notes allowing for full sequencer edit control.

After rendering, the target device track will have a clip with the arpeggio notes and the RPG-8 track should be muted, so no arpeggiator parameter settings can be changed - only the actual notes can be edited. You can of course always go back to the original Arp track, change arpeggiator parameters and perform the rendering again at any time.

To perform the rendering, proceed as follows:

1. **First, record some notes in the sequencer.**
   The Arp track should be selected when recording as usual.
2. **Set the left and right locators to the desired range or length.**
   If the range set is longer than the arpeggio pattern(s), the data will be repeated to fit the range.
3. **Select the sequencer track that the RPG-8 is connected to, i.e. the target track, not the "Arp" track.**
4. **Select the RPG-8 device you wish to copy the arpeggio(s) from in the rack.**
5. **Select "Arpeggio Notes to Track" from the Edit menu or the RPG-8 device context menu.**
   Now notes will be created on the target device track between the left and right locators, according to the selected arpeggio.
6. **Mute the Arp track originally used to generate the arpeggio. If you now activate playback from the transport the arpeggio will play back as note data (the RPG-8 is inactive).**
   If you enter sequencer Edit mode for the target device track, you can freely edit the arpeggio notes.



- **Performance data (e.g. Pitch Bend or Mod Wheel) recorded on the Arp track are not included in the "Arpeggio Notes to Track" operation.**
  If you have performance data that should be played back with the arpeggio, you need to copy it manually to the rendered note clip.

RPG-8 Parameters

MIDI-CV Converter parameters



The MIDI-CV Converter section to the left contains parameters that affect the CV output from the RPG-8, regardless of whether the Arpeggiator section is activated or not. The following parameters are available:

Velocity

The Velocity knob can be used to set a fixed velocity value for the notes that are output via the Gate CV Out jacks on the back of the RPG-8. If you set the Velocity knob to a value between "0" and "127", the Gate CV Out will be fixed (at the set value) regardless of the velocity of the incoming MIDI notes.

Turning the knob fully to the right activates Manual ("Man.") mode (a LED is lit when activated). In Manual mode the velocity levels will be sent out via the Gate CV Out with the same velocity value as they are input, i.e. "what goes in, will come out". Manual mode is on by default in new devices.

There is also a "Velocity CV" input at the back. If this is connected to a controller source (a LFO modulation output for example), the output will be a merge between the Velocity setting and the applied CV modulation by the LFO - see "CV Inputs".

Hold On/Off

If the Hold parameter is activated (lit button), an arpeggio will continue to run even if you release all keys. It will continue to arpeggiate the last notes played until a new note-on is received.

- **If you continue to hold down at least one key when Hold is on, any new notes will be added to the existing arpeggio as opposed to starting a new arpeggio.**
- **If the Arpeggiator section is off, and the Hold function is activated, there will be no note-offs for incoming notes played (i.e. the CV Gate stays open).**
- **The Hold On/Off status responds to Sustain Pedal messages - as long as the pedal is pressed down, Hold will stay activated.**

Octave Shift

This allows you to transpose the RPG-8 Note CV output in octave steps. You can octave shift up or down 3 octaves.

Octave Shift can also be CV controlled.

Arpeggiator parameters



The middle section contains the Arpeggiator parameters that govern how the arpeggio is played. The following parameters are available:

Arpeggiator "On" button

This switches the Arpeggiator on or off.

Mode switch

This determines the direction of the arpeggio notes.

Mode	Description
Up	This will generate an arpeggio that plays from the lowest note to the highest note.
Up+Down	Notes are played from lowest note to highest, then from highest back down to the lowest. The very lowest and the highest arpeggio notes are not repeated. I.e. the arpeggiator will play the lowest note to the second highest note, then the highest note to the second lowest note.
Down	Notes are played from the highest note to the lowest note.
Random	The notes you input will be arpeggiated randomly.
Manual	Notes are arpeggiated in the same order they are played when input.

Octave range buttons

The Octave buttons allow you to set the octave range of the arpeggio.

Use as follows:

Octave range	Description
1 Oct	The arpeggiated notes will be those that you press down on the keyboard.
2 Oct	If you select this, the arpeggio will be extended to a two octave range, i.e, the arpeggio pattern is played then repeated one octave up. In Random mode, the notes you input are played in random order over 2 octaves.
3 Oct	Same as 2 Oct but extended to a three octave range.
4 Oct	Same as 2 Oct but extended to a four octave range.

Insert buttons

Insert can be used to add variations to the arpeggio by repeating certain notes in a predetermined order. It works as follows:

Insert mode	Description
Off	No Insert repeat.

Insert mode	Description
Low	The lowest note is repeated in between every second note in the arpeggio.
Hi	The highest note is repeated in between every second note in the arpeggio.
3-1	The arpeggio will play 3 notes forward, then step 1 note back and from there play 3 notes forward etc.
4-2	The arpeggio will play 4 notes forward, then step 2 notes back and from there play 4 notes forward etc.

Rate

This sets the rate of the arpeggio. There are two basic modes for the Rate parameter:

- **If Sync is activated, the Arpeggiator will play in sync with the sequencer tempo. By changing the Rate you can make the Arpeggiator play in different tempo resolutions in relation to the tempo setting.**
  Straight, dotted or triplet note values are available in 1/2 to 1/16 resolutions. In addition, there are also 1/32, 1/64 and 1/128 (straight) note resolutions.
- **If the "Free" button is activated, the arpeggio rate is free running, and not synced to tempo.**
  The Rate is then selectable from 0.1 to 250Hz.

Gate Length

This determines the length of the arpeggio notes. Minimum value is 0 (Gate closed - no output). Maximum value is "Tie", meaning the gate is open all the time. This parameter can be controlled via CV.

Single Note Repeat


Single Note repeat governs how the arpeggiator behaves when the user plays single keys or monophonic lines.

- **When Single Note Repeat is on, a single key will retrigger the gate, meaning the note will repeat.**
  If the Octave setting is 1 Oct, the note will simply repeat (given the Gate Length setting is not set to "Tie"). If the Octave setting is set to anything else, the note will repeat according to the Octave, Mode and Insert settings.
- **When this is off, single notes will not repeat and RPG-8 will play arpeggios when the user plays more than one key (chords).**

Shuffle

Shuffle is a rhythmic feature, that gives the arpeggio a more or less pronounced swing feel. It works by delaying all sixteenth notes that fall in between the eighth notes.

In the RPG-8 you can switch Shuffle on or off using the corresponding button. However, the amount of shuffle can be set globally (for all devices that incorporate this feature) with the Global Shuffle control in the ReGroove Mixer.



The Shuffle on/off switch in RPG-8 and the Global Shuffle control in the ReGroove Mixer.

Pattern editor




The Pattern editor allows you to introduce rests for arpeggio steps which can produce more rhythmic results. The Pattern editor has 16 step buttons at the top, and a main grid display where the arpeggio notes are represented as horizontal bars for each step in the arpeggio. The pitch of the arpeggio notes are shown on the vertical axis. Notes within the C-1 to C7 octave range are shown. Notes cannot be edited in the display, they are only a visual representation of the arpeggio.

- **The Pattern editor is activated with the "Pattern" button.**
  When activated, the Pattern button and the 16 Step buttons light up.

- **When you play a chord (or in case you have recorded notes, when you start playback) the arpeggio will play according to the current Arpeggiator parameter settings, as normal.**
  The only difference is that a pattern will be repeated in the display so that all 16 steps play the pattern.



A three note chord with Pattern off...



...and with Pattern on.

- **If you click on a step button it goes dark. This means that this step will insert a rest in the arpeggio pattern.**
  Note that no arpeggio notes are "skipped". Inserting a rest means that the step will be silent and the next active step will play the next note in the arpeggio pattern.
- **The "Steps -/+" buttons can be used to set the number of steps in the Pattern editor.**
  E.g. if you press the "Steps minus" button four times the last four step buttons will go dark and the Pattern editor cycle will start over after step 12.

Pattern functions

When the Pattern editor is activated, you will find some specific pattern functions on the Edit menu (and on the device context menu). These are as follows:

Function	Description
Alter Pattern	The Alter Pattern function modifies existing step patterns. Note that there has to be a pattern to start with - using the Alter function if all step buttons are active (or inactive) won't do anything.
Randomize Pattern	The Randomize Pattern function creates random patterns.
Invert Pattern	This will invert the pattern, i.e. active steps will become rests and vice versa.
Shift Pattern L/R	The Shift Pattern functions move the pattern one step to the left or right.

Automating the Pattern editor

To automate the RPG-8 step buttons a little planning is necessary.

- **In the sequencer, each automation point represents all the possible combinations of each of the 16 step buttons on/off status, so the numbers become slightly bewildering (there are 65535 possible variations).**
  This makes it difficult to control the automation by drawing events in the sequencer as each position represents a different combination of *all* the button's on/off status.
- **You can of course automate the buttons manually while recording but this is not always a solution as you may wish to change the on/off status of several buttons simultaneously.**

The solution to both these issues is to record "snapshots" of the Pattern editor:

1. **Set up the buttons as you want them from the start of the song, e.g. all buttons "on".**
   This will be your "static value" which is active from the start.
2. **Right-click the buttons and select "Edit Automation" from the context menu.**
   An automation lane is created and the Pattern buttons will have a green rectangle around them to indicate that they are automated.



3. **Start the sequencer in play mode, and set up the buttons as you want them (except one - see below) for the new pattern combination.**
   Note that the Automation override indicator on the transport will light up, but this is as it should be.


To record the button's status, you need to press at least one button after entering record mode. Thus, you need to save one "last" button to press during record to automate the Pattern editor to an exact combination of the 16 button's on/off status.

4. **Enter record mode and press the "last" step button where you want the automation to happen. Continue recording for as long as you wish the pattern to play, then click stop.**
   A clip has been added on the Pattern automation lane.
5. **If you open the clip by double-clicking on it in the Arrange view you can see that the clip has one automation point.**
   Note that it is the clip that governs the start and duration of the automation, not the point itself.

- **If the snapshot automation is not in the right time position, you can simply reposition the clip so that it starts where you want the change to occur using the usual methods.**
  When the clip you recorded ends, the buttons will revert to the static value you set up in step 1.

6. **By using this general method you can continue to add further clips to the Pattern lane, each containing a "snapshot" of the Pattern editor buttons.**

CV connections



On the back of the RPG-8 you can find a number of useful CV connectors. These are as follows:

CV Inputs


There are five CV inputs, of which four can be used to control RPG-8 parameters that have associated controls on the front panel. These parameters are Gate Length, Velocity, Rate and Octave Shift.

If you use an external source to modulate these parameters, the incoming CV is merged with the setting on the front of the device.

An example: Velocity is set to 50 on the front panel. A Matrix (bi-polar curve) that varies between +- 20, with the voltage trim pot set to 64 (50%) is connected to the Velocity CV input. The resulting Velocity should then vary between 40-60.

In addition to the above CV inputs, there is a "Start of Arpeggio Trig In" connector. This restarts the arpeggio figure from step 1 when this input receives a gate trigger. See "Triggering arpeggios" for a tip on how this can be used. If something is connected to this input the RPG-8 will not generate arpeggios unless a Gate trigger is received.

Note: If you are modulating the arpeggio using the CV Input jacks, this will not affect the rendered arpeggio notes.



CV Outputs

The following CV outputs are available:

- **Gate CV Out (Velocity) transmits a gate/velocity value that corresponds to the Velocity parameter setting.**
  This is normally auto-routed to the Sequencer Control Gate input on an instrument device.
- **Note CV Out transmits the notes generated by the Arpeggiator (or if this is off, the notes you input to the RPG-8).**
  This is normally auto-routed to the Sequencer Control CV input on an instrument device.
- **Mod Wheel/Pitch Bend Outputs will normally connect to the corresponding inputs of the instrument device controlled by RPG-8.**
- **The common MIDI performance controllers Aftertouch/Expression/Breath can be used to control any parameters using these CV outputs.**
- **Start of Arpeggio Trig Out - every time the arpeggio figures start over this output will send a gate signal.**
  This can be used to trigger filter, amp and mod envelopes in other devices, e.g. Subtractor. The length of this gate is the same as the length of the first note in the arpeggio.
- **Sustain Pedal Gate Out - the sustain pedal can be used to trigger envelopes in other devices.**
  If you plug a cable into the "Sustain Pedal Gate Out" the normal pedal to the Hold parameter connection is broken and the sustain pedal function is changed to send out a gate signal with velocity equalling the Velocity setting knob (if Manual mode is on then velocity defaults to a value of 100).

Tips and tricks

Using the RPG-8 for modulation

You can use the RPG-8 as a modulation source, much like an LFO. The RPG-8 can generate stepped modulation that is both synchronized to tempo and controlled by note input. In this and in following examples we assume you already have a RPG-8 connected to an instrument device.

- **With the RPG-8 selected in the rack, create a Spider CV Merger/Splitter.**
  The RPG-8 Note and Gate CV outputs are auto-routed to the Spider Split A and B inputs, and the Spider first split Note and Gate outputs are connected to the instrument device (as they were before creating the Spider).

You now have 2 (and 1 Inverted) additional Note and Gate CV outputs via the Spider.

- **Try using the Note CV split outputs to modulate other parameters in the instrument device, e.g. filter frequency.**
  The filter frequency will then track the notes generated by the Arpeggiator.
- **You can of course also connect the Note CV out to various parameters in any device, not just the device connected to the RPG-8.**
- **You can connect the Spider split CV/Gate outputs to the corresponding Sequencer Control CV inputs to another instrument device so that the RPG-8 controls two (or more) devices. (This can of course also be done by connecting the RPG-8 to a Combinator device.)**

Triggering arpeggios

On the back panel there is a "Start of Arpeggio Trig In" CV connector. This restarts the arpeggio figure from step 1 when this input receives a gate trigger. You could use this in the following way:

- **One or more Redrum channels Gate out can reset the step pattern to create rhythmic patterns in sync.**
- **You could use the Matrix in the same way - each positive Gate signal will restart the arpeggio figure.**

! **Note that no arpeggio will be generated unless a Gate trigger is received when something is plugged in to the "Start of Arpeggio Trig In" CV connector.**

Triggering samples

The Gate CV output can be used to trigger samples, either in Redrum or Kong or in the NN-19 or NN-XT Sampler.

- **Connect the RPG-8 Gate CV out to the Gate (Sequencer Control) in on the NN-19/NN-XT or to one of the individual Gate Channel inputs of Kong or Redrum.**
  Gate values will now trigger the sample on each step with Gate values above "0".

Using the RPG-8 as a MIDI to CV converter

You can also use the RPG-8 as a stand-alone MIDI to CV converter without generating arpeggios. In this mode (Arpeggiator Off) you can play instrument devices just like as if MIDI input was directly connected to the target device.

The main benefit of this mode is that you can use note pitch and velocity to control parameters, not only in the target device but in any device.

Chapter 76
Menu and Dialog Reference



Reason menu (macOS)

About Reason

This menu item opens up a dialog that informs you about the version of the program and the people behind it.

Settings...

This menu item opens up the Settings dialog. See "Settings – User Interface", "Settings – Browsing", "Settings – Audio", "Settings – MIDI", "Settings – Sync", "Settings – Other Controls", "Settings – Folders" and "Settings – Account" for detailed descriptions about the functions and settings in this dialog.

Open Reason Companion

This menu item launches the Reason Companion application, in which you can install Rack Extensions and Sound Packs (Reason+).

My Account

This menu item launches your default web browser and brings you to your products page at Reason Studios, where you can view your list of owned products, including download ReFills and Rack Extensions.

Check for Updates...

This checks for recent Reason updates on the Reason Studios server.

Services

The Reason menu contains the standard macOS Services item. Please consult the Macintosh Help for descriptions about these.

Show/Hide

These are the standard macOS Hide/Show options which lets you choose what to view.

Quit and Log out

This allows you to quit the program and also log out. Logging out means removing the stored login credentials - do this if you're not going to use Reason on this particular computer, or if you need to log in to another Reason Studios user account.

The next time you run Reason, you will need to enter your Username/e-mail and password in the "Welcome to Reason" dialog again. Internet connection is then required again.

Quit Reason

This allows you to quit the program. If there are any documents open with unsaved changes you will be asked whether you want to save those changes before quitting.

File menu

New

When you select this, a new song appears. The exact contents of this song is determined on the "Browsing" tab in Settings (see "Default song").

New from Template

On the sub-menu you can create a new song based on the selected Template Song. The selected Template Song will appear in a new document window.

- **On Windows platforms, the document will be named "Document n" where "n" is an incremental number.**
- **On macOS platforms, the document will be named "untitled n" where "n" is an incremental number.**

You can then save your song with a new name. See "Creating a new Song from a Template" for more details.

Last in the sub-menu you can choose to open and show the Template folder in Explorer (Win) or Finder (Mac). This makes it easy to place other songs in the Template folder, if you like.

Open...

! **The "Open..." item is only available if you run Reason in Authorized Mode (see "Registering Reason (licensed version only)").**

To open a Song, proceed as follows:

1. **Pull down the File menu and select Open.**
   The Reason Browser appears (if hidden).
2. **Navigate to the desired folder on disk or within a ReFill.**
3. **When you have located the song file, select it and click Open in the Browser (or double click the file).**
   The song appears in its own document window.

▶ **You can have several songs open at the same time if you like. This allows you to copy and paste audio, note and automation clips, tracks, devices, mixer channels and patches between songs. However, all open songs consume some memory and performance, so you may want to close songs you don't need.**

See "Opening a Reason Song" for more details.

Open Demo Song

! **The "Open Demo Song" item replaces the "Open..." item if you run Reason in Demo Mode (see "Running Reason in Demo Mode").**

▶ **Choose the Demo Song to open by selecting it from the sub-menu that appears.**
The song appears in its own document window.

See "Opening a Reason Demo Song" for more information.

Close

▶ **Select "Close" to close the active window.**
If the window is a song document window and has unsaved changes, you will be asked whether you want to save those changes.

Closing the last open song document window will quit Reason (Windows only).

Save

This saves the active song document to disk.

- **If the song document hasn't yet been saved, the "Save As" dialog appears, requesting you to enter a file name and specify a location for the file on disk (see "Save As...").**
- **If the document has already been saved at least once, the document will simply be saved without any questions.**

Save As...

This saves the active song document to disc. A standard Save As dialog appears requesting you to enter a file name and specify a location for the file on disk. The "Save As" command will also automatically optimize the song file size when applicable (see "Save and Optimize").

▶ **You can set things up so that any samples used in the song are included in the song file itself by specifying self-contained settings (see "About Self-Contained Songs").**

Save and Optimize

When you record audio in the sequencer, the recordings are stored in your song document. If you remove recordings in your song, there might be "empty" areas left in the document, similar to a fragmented hard disk. To "defragment" the song document, and thus reduce the file size, you can use the "Save and Optimize" command.

See "Saving and optimizing a Song" for more details.

Song Information...

This brings up a dialog that allows you to add contact information and comments etc. about your song.

See "Including Song Information" for information.

Song Self-contain Settings...

If you want to open your song on another computer, or send it to another Reason user, you would also have to bring all samples and REX files used by the Reason devices in the Song. To make this easier, Reason allows you to create "self-contained" songs. A self-contained song contains not only the references to the used samples and REX files, but also the files themselves. By selecting the "Song Self-Contain Settings", you can choose what files to include in your song.

See "About Self-Contained Songs" for more information.

Import Audio File...

Selecting "Import Audio File..." opens the Browser (if hidden), which displays compatible audio files. Select audio files to import to audio tracks in Reason.

See "Importing audio to the sequencer" for more information.

Import MIDI File...

Reason can import standard MIDI files (SMF). This allows you to import MIDI data to Reason from other applications. Selecting "Import MIDI Files..." opens the Browser (if hidden), which displays compatible MIDI files. Select MIDI files to import to ID8 tracks in Reason.

See "Importing Standard MIDI Files" for more information.



Export MIDI File...

Reason can export standard MIDI files (SMF). Selecting "Export MIDI Files..." brings up the Export MIDI File dialog from which you can export all instrument tracks and automation tracks from the Reason sequencer as a Standard MIDI File (SMF).

See "Exporting Standard MIDI Files" for more information.

Save Device Patch As...

This item is available for a selected device that can save patches. The menu item name reflects the type of device selected (for example "Save Combinator Patch As...").

Even though the device settings are stored in the song, you may want to save any settings you have made for a device as a separate patch file. This allows you to use the patch in other songs, and lets you try out other patches in your song without risking to lose your original sound.

- **The different types of patch files have different file extensions.**
  These are:

  ".cmb" (Combinator patch files)

  ".zyp" (Subtractor patch files)

  ".thor" (Thor patch files)

  ".xwv" (Malström patch files)

  ".smp" (NN-19 patch files)

  ".sxt" (NN-XT patch files)

  ".drp" (Redrum patch files)

  ".drex (Dr. Octo Rex patch files)

  ".drum" (Kong drum patch files)

  ".kong" (Kong kit patch files)

  ".rv7" (RV7000 patch files)

  ".sm4" (Scream 4 patch files)

  ".pulver" (Pulveriser patch files)

  ".gator" (Alligator patch files)

  ".echo" (The Echo patch files)

  ".repatch" (Rack Extension patch files)

- **If you have selected a patch, modified it and want to save it with the modifications, you could either save a separate, modified version of the patch (with a new name) or simply overwrite the old patch file on disk.**
  As usual, you will be asked whether you really want to replace the existing patch file.

▶ **You can also save a patch by clicking the floppy disk button on the device panel.**

▶ **You can save a patch under the same name and location (without having the save dialog appear) by holding down [Alt](Win) or [Option](Mac) and clicking the floppy disk button on the device panel. Note that this overwrites the original patch!**

Export Song/Loop as Audio File...

When you have created a complete song, you will want to mix it down to a WAV or AIFF audio file to make it playable for other people (who don't use Reason). You can either export the whole song, or only the loop (the region between the left and right locator in the sequencer).

See "Exporting Songs or parts of Songs" for more information.

Bounce Mixer Channels...

Bouncing Mixer Channels basically means "recording" the audio outputs from individual Audio Track Channels and/or Mix Channels to audio files. The audio files can then be saved to disk or placed on new Audio Tracks in your song.

See "Bouncing Mixer Channels" for information on how to bounce mixer channels.

Export REX as MIDI File...

This item is only available if a Dr. Octo Rex device is selected in the rack. If you have loaded a REX file into a Dr. Octo Rex device and wish to play back the loop via MIDI (typically from another sequencer), proceed as follows:

1. **Select the Dr. Octo Rex device in the rack.**
2. **Select "Export REX as MIDI File..." from the File menu.**
3. **Save the MIDI File to disk.**
4. **In the other application, open the MIDI file you just created.**
5. **Set up the other application to play back the MIDI File on the correct MIDI Output and MIDI Channel (the output and channel on which the Dr. Octo Rex device receives data).**

Export Device Remote Info...

This command exports a text file containing the remotable items for the currently selected device (native, Rack Extension or VST) in the rack. This is useful if you're creating or editing Remote map files.

Recent Songs list

Here is a list of the eight most recently opened Reason Songs. Select any of these songs to open them in new, separate document windows.

Exit and Log out (Windows)

This allows you to exit the program and also log out. Logging out means removing the stored login credentials - do this if you're not going to use Reason on this particular computer, or if you need to log in to another Reason Studios user account.

The next time you run Reason, you will need to enter your Username/e-mail and password in the "Welcome to Reason" dialog again. Internet connection is then required again.

Exit (Windows)

This allows you to quit and exit the program. If there are any song documents open with unsaved changes you will be asked whether you want to save those changes before quitting.

Edit menu

Undo

Virtually any actions in Reason can be undone. This includes creation, deletion and reordering of devices in the rack, parameter value adjustments, recording and editing in the sequencer and tempo/time signature adjustments. You can undo hundreds of actions.

! **Sequencer Transport commands are not "undoable".**

▶ **To undo the latest action, select "Undo" from the Edit menu or hold [Ctrl](Win) or [Cmd](Mac) and press [Z].**
The action to be undone is indicated next to the Undo command on the Edit menu. For example, if your latest action was to delete some device(s) from the rack, the Edit menu will say "Undo Delete Devices".

See "Undo and Redo" for more detailed information.

Redo

▶ **To redo an undone action ("undo the undo operation"), select "Redo" from the Edit menu or hold [Ctrl](Win) or [Cmd](Mac) or and press [Y].**
The action to be redone is indicated next to the Redo command on the Edit menu. You can undo/redo hundreds of actions.

See "Undo and Redo" for more detailed information.

Cut/Cut Tracks and Devices/Cut Channels and Tracks

This command takes the selected item(s), removes them and places them on the clipboard (an invisible storage location) from where they can later be pasted in.

Cutting applies to devices/channels and their sequencer tracks, sequencer clips, notes and automation points.

! **If "Auto-group Devices and Tracks" is selected in the Options menu, all devices in the Device Group will be cut - see "Creating devices".**

Copy/Copy Tracks and Devices/Copy Channels and Tracks/Copy Patch

This command takes the selected item(s), copies them and places the copies on the clipboard (an invisible storage location) from where they can later be pasted in.

Copying applies to devices/channels and their sequencer tracks, sequencer clips, notes, automation points and device patches. Also individual Kong Drum patches can be copied and pasted from one selected pad to another.

! **If "Auto-group Devices and Tracks" is selected in the Options menu, all devices in the Device Group will be copied - see "Creating devices"**

Paste/Paste Tracks and Devices/Paste Channels and Tracks/Paste Patch

This command takes the items that you have cut or copied to the clipboard and pastes them back into the document.

▪ **When you paste a sequencer track, its device will be pasted at the same time (and vice versa, if the device has a track).**
Pasted tracks and devices are inserted below the currently selected track in the track list and below the selected device in the rack, respectively.

! **If "Auto-group Devices and Tracks" is selected in the Options menu, all devices in the Device Group will be pasted - see "Creating devices".**

If nothing is selected, the pasted items will appear at the bottom of the track list/rack.

- **If you copy and paste several devices, the connections between these are preserved.**
- ▶ **If you hold down [Shift] when you paste a device, Reason will attempt to auto-route it.**
  For example, [Shift]-pasting an instrument device typically connects it to the first free Mix Channel device input(s) above it in the rack.
- ▶ **You can also paste the device(s), channel(s) and track(s) into another song, including all sequencer data and device settings.**
- **When you paste sequencer clips, they appear at the song position, on their original track(s).**
  If you have deleted the original tracks, or if you paste into another Reason song document, the clip will be pasted at the song position on the selected track (if the track type is the same as the original). Otherwise new tracks will be created. If the clip is a note clip, a new ID8 instrument track will be created.
- **Notes or automation points will be pasted at the song position on the selected track (if the track types are compatible).**
- **Individual Kong Drum patches can be copied and pasted from one selected pad to another.**

Delete/Delete Tracks and Devices/Delete Channels and Tracks

This menu item is used for deleting selected items. If you delete a sequencer track with this menu item (then called "Delete Tracks and Devices"), its device is also deleted.

! **If "Auto-group Devices and Tracks" is selected in the Options menu, an alert appears asking you if you want to delete only the selected device or the entire Device Group - see "Creating devices".**

Delete Tracks

This deletes the currently selected sequencer track(s) without removing the corresponding rack device(s) or mixer channels.

Duplicate Tracks and Devices/Duplicate Channels and Tracks

This creates a duplicate of the selected device and track, or channel and track, complete with all parameters and recordings/events. The duplicated items will appear below the selected device and track, respectively.

! **If "Auto-group Devices and Tracks" is selected in the Options menu, all devices in the Device Group will be duplicated - see "Creating devices".**

Minimize Tracks/Restore Track Heights

The "Minimize Tracks" function minimizes selected Sequencer tracks to minimum height. The "Restore Tracks" function restores the track height(s) of the selected track(s) to where they were before.

MIDI: Send All Notes Off

This function is enabled if there is at least one MIDI Out Device in the rack. Select this, or press [!] to send an All Notes Off MIDI command on the MIDI Out ports used by Reason. This function can be used if you are experiencing hanging notes when you are controlling external MIDI instruments from Reason. See "MIDI Out Device" for more information about MIDI controlling external equipment.

Select All/Select All Devices/Select All Tracks/Select All Channels

This selects all devices in the rack, all tracks in the track list, all channels in the Main Mixer, or all clips or all notes or automation points in an open clip. The result depends on which area (rack, track list, Main Mixer etc.) has focus. This is indicated by a thin frame around an area in the document window.

▶ **To set focus to the desired area, click somewhere in it.**



You can use this menu item to quickly apply a command to all items you are working on, for example deleting all devices in the rack (select Select All Devices and then press [Delete]) or for Quantizing all notes in an open clip (select Select All and then click the Quantize button in the Tool window).

Select All in Device Group

This will select all devices within the selected device's Device Group. See "About selecting all devices in a Device Group".

Auto-route Device

Auto-routing is when devices' audio and CV/gate connections are automatically routed according to default rules. Auto-routing is normally performed when:

- **A new device is created.**
- **Moving, duplicating or pasting devices with [Shift] pressed.**

However, if a device is already in the rack, you can "force" it to be auto-routed by selecting it and then select this menu item.

For more information about auto-routing rules, see "Automatic routing".

Disconnect Device

This disconnects all audio and CV/gate connections from the selected device(s).

Combine/Uncombine

- **By selecting several devices in the rack and selecting "Combine", a Combinator device will be created containing the selected devices.**
- **By selecting the Combinator (or one or several devices contained in a Combinator) and then selecting "Uncombine" will remove the devices from the Combinator and into the rack.**
  In case the whole Combinator is selected, this will be removed and the devices it contains will be moved into the rack.

See "The Combinator" for more details.

Copy/Paste Channel Settings (Main Mixer channel strips)

This function allows you to copy and paste the parameters of different sections of a Main Mixer channel strip and paste into another channel strip. The available parameter groups are:

- **Dynamics**
- **Filters and EQ**
- **Insert FX**
  This will copy all effect devices (with their internal routings) in the Insert FX container.
- **FX Sends**
  This will only copy the FX Send parameters in the channel strip - not any FX devices or patches.
- **All**
  This will copy all channel strip parameters, including any Insert FX devices.

Route to (Main Mixer channel strips)

This allows you to create, and automatically route, one or several selected Main Mixer channel strips to a new or existing Output Bus for sub-mixing purposes. See "Creating an Output Bus".



Create Parallel Channel (Main Mixer channel strips)

This allows you to create a parallel mixer channel for parallel processing purposes. See "Creating Parallel Channels".

Clear Insert FX

This disconnects and removes all Insert FX devices of a selected Mix Channel or Audio Track device in the rack, or of a selected channel in the Main Mixer. See "Deleting Insert effects" for more details.

Reset All Channel Settings (Main Mixer channel strips)

This will reset all channel strip parameters to their default values. Any Insert FX Combinator patches will be removed.

Reset Device

Sometimes it is useful to start with a "clean slate" when creating a sound or effect. This is done by selecting Reset Device from the device context menu or Edit menu. This sets all parameters to their default values. Resetting NN-19, NN-XT, Dr. Octo Rex, Redrum or Kong devices also removes samples from the device, allowing you to start from scratch.

Cut Pattern

Moves the current pattern in the selected Redrum or Matrix to the clipboard. The pattern is then cleared.

Copy Pattern

Copies the current pattern in the selected Redrum or Matrix to the clipboard.

Paste Pattern

Copies the pattern on the clipboard to the current pattern location in the selected Redrum or Matrix device. This overwrites the current pattern with the one on the clipboard. Note that this can be used to transfer patterns between different Reason songs.

Clear Pattern

This menu item clears (empties) the current pattern on the selected pattern device (Redrum or Matrix).

Browse Patches...

This menu item allows you to select a new Patch for a device. The menu item reflects which device is selected - in other words, you must select the device for the corresponding Browse Patches item to appear on the Edit menu.

When you select the menu item, the Browser appears (if hidden), allowing you to locate and select the patch, on disk or within a ReFill.

When you load a patch, the device's parameters will be set according to the values stored in the patch, and the name of the patch will be shown in the patch name display. As with any change you make, this operation can be undone.

! **Any parameter adjustments you make on the device panel after selecting a patch will not affect the actual patch file (for this you need to re-save the patch).**

- **If referenced samples are missing**
  Patches for the Redrum, Combinator (if any sampler devices are part of the Combi), NN-19, NN-XT Kong, Grain and Dr. Octo Rex devices contain references to samples. Just like patches, samples can be independent files on the hard disk or elements within a ReFill or a SoundFont. However, if sample files have been moved or renamed after a patch was saved, the sample file references in the patch will not be accurate.

  If this is the case when you select a patch, the program will tell you so. You can then choose to either manually locate the missing files, to have the program search for them in all stored locations and ReFills or to proceed without the missing sounds.

Browse Loops...

This menu item is used to add a loop to the selected Dr. Octo Rex Loop Slot. Files to be imported can be in REX, RCY or RX2 file format.

Loading a new REX file will replace any currently loaded file in the selected Loop Slot.

Browse Samples...

This menu item lets you load samples into the devices that use them; the Redrum, the NN19 and the NN-XT. The following sample formats can be loaded:

- **In Windows:**
  .wav, .aif, .mp3, .aac, .m4a and .wma.
- **In macOS:**
  .wav, .aiff, .3g2, .3gp, .mp1, .mp2, .mp3, .mpeg, .mpa, .snd, .au, .sd2, .ac3, .aac, .adts, .amr, .caf, .m4a .m4r and .mp4.
- **SoundFonts (.sf2)**
  SoundFonts are an open standard for wavetable synthesized audio, developed by E-mu systems and Creative Technologies.
- **REX file slices (.rx2, .rex, .rcy)**
  REX files are music loops created in the ReCycle program or when editing audio clips inline in Reason (see "Bounce Clip to REX Loop"). The NN19 and NN-XT let you load REX files either as complete patches or individual REX slices as separate samples. The NN-Nano lets you load separate slices from REX files as individual samples.
- **Any sample rate and practically any bit depth.**

Redrum:

To use this menu item to load a new drum sound into Redrum, proceed as follows:

1. **Select a channel in the drum machine, by clicking its Select button.**
2. **Select Browse Samples.**
   The Redrum channel gets Browser focus and displays compatible files.
3. **Navigate to a location containing any of the sample formats listed above, select one and click Load.**

NN19:

This menu item can also be used to add a sample to a key zone in a key map in the NN19 sampler.

1. **Select a key zone.**
   This can be empty, or contain a sample - it doesn't matter for now.
2. **Use the Browser to add one or several (see below) sample(s).**

The following will happen:

- **If the zone contained a sample prior to loading, this will be replaced, both in the zone and in the sample memory, unless the sample was also used by another key zone.**
- **If you loaded several samples, one of the samples (the sample that was selected furthest down in the Browser list) will be loaded into the key zone, and the other samples will be loaded into the sample memory.**

NN-XT:

This menu item is used for adding one or more sample(s) to a key zone in the NN-XT:

1. **Make sure the Remote Editor panel is folded out, by clicking the small arrow in the bottom left corner.**
   If the remote editor panel is folded in, you will only be able to browse for NN-XT *patches*.
2. **Use the Browser to add one or several sample(s).**
   The sample(s) will be placed in separate zones and mapped across the same key range.

- **If a zone is selected when you browse for samples, the sample will be loaded into that zone, replacing any previous sample.**
  Replacing samples this way is only possible when you load a single sample.

Automap Samples

This menu item applies to the NN19 Sampler. If you have a number of samples that belong together but haven't been mapped to key zones, you can use the "Automap Samples" function. This is used in the following way:

1. **Select all samples that belong together and load them in one go, using the sample browser.**
   One of the samples will be loaded to a key zone spanning the whole range, and the rest will reside in the sample memory.
2. **Select Automap Samples from the Edit menu.**

Now the samples currently in memory will be arranged automatically so that:

- **Each sample will be placed correctly according to its root note, and will be tuned according to the information in the sample file.**
  Most audio editing programs can save root key information as part of the file.
- **Each sample will occupy half the note range to the next sample's root note.**
  The root key will always be in the middle of each zone, with the zone extending both down and up in relation to the root position. Hence, no key zone high or low limits have to be manually set!

Mapping Samples Without Root Key or Tuning Information:

Some samples may not have any information about root key or tuning stored in the file (nor indicated in the file name). If this is the case, you can still make use of the Automap function:

1. **Select all samples that belong together and load them in one go, using the sample browser.**
   One of the samples will be loaded to a key zone spanning the whole range, and the rest will reside in the sample memory.
2. **Manually set the root key, and adjust the tune knob if the sample needs pitch fine-tuning.**
   Without any information stored in the file, or if the file name doesn't indicate the root key, you will have to use your ears for this step. Play the sample across different areas of the keyboard and listen to where it sounds the most "natural". As long as you are in the general area of the correct root key, the result should be o.k. You can always adjust this later.
3. **Select the next sample using the Sample knob, and repeat the previous step.**
   Proceed like this until you have set a root key for all the samples.
4. **Select "Automap Samples" from the edit menu.**
   The samples will be automatically mapped according to their set root key positions!



Delete Sample/Remove Sample

Redrum:

- **To remove a sample from a Redrum drum machine, select its drum sound channel and then select "Delete Sample" from the Edit menu.**
  The sample is removed from the drum sound channel and from sample memory.

NN19:

- **To remove a sample from an NN19 Sampler's memory, select the zone it belongs to, and then select "Delete Sample" from the Edit menu.**
  The sample is removed from the zone and from sample memory.

NN-XT:

- **To remove a sample from an NN-XT Sampler's memory, select the zone it belongs to, and then select "Remove Samples" from the Edit menu.**
  The sample is removed from the zone and from sample memory. The zone still remains though. To delete a zone, you must use the option "Delete Zones".

Delete Unused Samples

This menu item is used for the NN19 Sampler. When you select it, all samples that are not assigned to a key zone are deleted from sampler memory.

This way you can make sure that you are not wasting any sample memory for samples that are not actually used.

Split Key Zone

This menu item is used for the NN19 Sampler. It splits the currently selected key zone in the middle. The new zone is the upper half of the split, and is empty. The dividing point has a "handle" above it.

Delete Key Zone

This menu item is used for the NN19 Sampler. It deletes the currently selected key zone from the key map.

Reload Samples

This menu item is used with the NN-XT sampler. When you select this, any changes you have made on a loaded sample using the sample parameters (root key, loop settings, etc.) are immediately undone, and the settings revert back to the original.

Add Zone

This menu item is used with the NN-XT sampler. It is used for adding an empty zone to the key map. An empty zone can be resized, moved and edited in the same way as zones that contain samples.

An empty zone is indicated with the text "**No Sample**". After you have added an empty zone, you can assign a sample to it.

Copy Zones

This menu item is used with the NN-XT sampler. It copies the selected zone(s), and all of its settings - including references to any sample it may contain - and places it in the clipboard buffer. You can then select "Paste Zones" to create a new zone that is an exact replica of the copied zone(s). Note that copying/pasting zones can also be performed between separate NN-XT devices.



Paste Zones

This menu item is used with the NN-XT sampler. If you have used the "Copy Zones" command, with any number of selected zones, you can create exact duplicates of these by using the "Paste Zones" command. The pasted zones will then be added below any existing zones in the key map.

Duplicate Zones

This menu item is used with the NN-XT sampler. It lets you duplicate any number of already existing zones (containing samples or empty).

1. **Select the zone(s) you want to copy.**
2. **Select "Duplicate Zones".**
   The selected zones will now be copied and automatically inserted below the last one in the key map display.

The duplicated zones will contain references to the same samples as the original zones. They will also have the exact same key ranges and parameter settings.

Delete Zones

This menu item is used with the NN-XT sampler. Selecting this option will remove both the selected zones, and any samples they may contain.

Select All Zones

This menu item is used with the NN-XT sampler. This option will automatically select all zones in a key map.

Copy Parameters to Selected Zones

This menu item is used with the NN-XT sampler. It lets you easily copy parameter settings from one zone to any number of other zones. Proceed as follows:

1. **Select all the zones you want to involve in the operation.**
   By this we mean the zone with the settings you wish to copy, and the zone(s) to which you want to copy the settings.
2. **Make sure the zone that contains the settings you want to copy has edit focus by clicking on it.**
   Focus is indicated by a thick border.
3. **Select "Copy Parameters to Selected Zones".**
   All the selected zones will now get the exact same parameter settings.

! **Observe that this only applies to the synth parameters (LFOs, envelopes etc.). Sample parameters (root key, velocity range etc.) can not be copied.**

Sort Zones by Note

This menu item is used with the NN-XT sampler. This option lets you automatically sort the selected zones within a Group in descending order according to their key ranges. When you invoke this option, the selected zones will be sorted from top to bottom in the display starting with the one with the lowest range. If two or more zones have the same key range, they are instead sorted by velocity range.

Sort Zones by Velocity

This menu item is used with the NN-XT sampler. This option lets you automatically sort the selected zones within a Group in descending order according to their set low or high velocity values.

When you invoke this option, the selected zones will be sorted from top to bottom starting with the one with the highest "Lo Vel "value.

If two or more zones have the same velocity range, they are instead sorted by key range.



Group Selected Zones

This menu item is used with the NN-XT sampler. It lets you put any number of selected zones together in a group.

Grouping zones is good for two things:

- **To allow you to quickly select a number of zones that "belong together."**
  For example if you have created a layered sound consisting of piano and strings, you could put all string samples in one group and all piano samples in one group. Then you can quickly select all piano samples and make an adjustment to them by trimming a parameter.
- **To group zones that need to share group settings together.**
  For example, you may want to set a group to legato and monophonic mode and add some portamento so that you can play a part where you slide between notes.

Proceed as follows:

1. **Select the zones you want to group together.**
   The zones don't have to be contiguous in order to be grouped. Regardless of their original positions in the samples column, they will all be put together in succession.
2. **Select "Group Selected Zones".**
   The zones are grouped.

Note that there is always at least one group, since the zones you create are always grouped together by default.

Set Root Notes from Pitch Detection

This menu item is used with the NN-XT sampler. All instrument sounds have an inherent pitch. When playing a sample of such a sound on the keyboard, the keys you play must correspond to that pitch. For example, you may have recorded a piano playing the key "C3". When you map this onto the NN-XT key map, you must set things up so that the sampler plays back the sample at original pitch when you press the key C3, and this is done by adjusting the root note.

The NN-XT features a pitch detection function to help you set the root keys of loaded samples. This is useful if you for example load a sample that you haven't recorded yourself, and you don't have any information about its original pitch.

Proceed as follows:

1. **Select all the zones you want to be subject to pitch detection.**
2. **Select "Set Root Notes from Pitch Detection".**
   The samples in all the selected zones will now be analyzed, and the detected root keys will automatically be set for you.

! **Note that for this to work properly, the samples must have some form of perceivable pitch. If it is sampled speech, or a snare drum for example, it probably doesn't have any discernible pitch.**

Automap Zones

This menu item is used with the NN-XT sampler. The automap function can be used as a quick way of creating a key map, or as a good starting point for further adjustments of a key map.

Automap works under the assumption that you intend to create a key map for a complete instrument, for example a number of samples of a piano, all at different pitches.

1. **Load the samples you want to Automap.**
   Now you have three options:

- **Trust that the root note information in the files is already correct.**
- **Manually adjust the root notes (and tuning) for all the samples.**
- **Use "Set Root Notes from Pitch Detection" to automatically set up the root notes.**

2. **Select all zones you want to automap.**
3. **Select Automap Zones.**



All the selected zones will now be arranged automatically in the following way:

- **The zones will be sorted in the display (from top to bottom - lowest key first) according to the root keys.**
- **The zones will be assigned key ranges according to the root keys.**
  The key ranges are set up so that the split between two zones is exactly in the middle between the zones' root notes. If two zones have the same root key they will be assigned the same key range.

Automap Zones Chromatically

This menu item is used with the NN-XT sampler. It will map the selected zones chromatically (one zone per semitone) from C2 and up. This is useful if you are mapping non-pitched material (e.g. drum or percussion samples) and want one sample per key. Before you select Automap Zones Chromatically, you may want to adjust the order of the zones, since this determines which zone is mapped to which key.

Create Velocity Crossfades

This menu item is used with the NN-XT sampler. This is used for automatically setting up velocity crossfades for smooth transitions between overlapping zones. To set up crossfades, you adjust the fade out and fade in values for the overlapping zones.

An example:

- **Two zones are both set to play in the full velocity range of 1-127.**
- **Zone 1 has a fade out value of 40.**
  This means that this zone will play at full level with velocity values below 40, With higher velocity values, it will gradually fade out.
- **Zone 2 has a fade in value of 80.**
  This has the effect that as you play velocity values up to 80, this zone will gradually fade in. With velocity values above 80, it will play at full level.

Instead of manually setting up a crossfade, you can let NN-XT do it for you. Proceed as follows:

1. **Set up the zones so that their velocity ranges overlap, as desired.**
2. **Select the zones.**
   You can select as many zones as you wish, not just one pair of overlapping zones.
3. **Select "Create Velocity Crossfades".**
   NN-XT will analyze the overlapping zones and automatically set up what it deems to be appropriate fade in and fade out values for the zones.

Note the following important points:

- **This operation will not work if both zones have full velocity ranges.**
  At least one of the zones must have a partial velocity range (see "Setting crossfading for a Zone").
- **This operation will not work if the zones are completely overlapping.**

Copy Loop to Track

This menu item is used for the Dr. Octo Rex loop player device. To be able to make your REX loop start at the same time as other sequencer or pattern data, you "convert" the slices in the loop to note clips in the sequencer:

1. **Select the sequencer track for the Dr.Rex device.**
2. **Set the locators to encompass the section you want to fill with REX clips.**
   You may want to make sure that this area doesn't contain any note clips already, to avoid overlapping clips.
3. **Select desired Loop Slot in the Dr. Octo Rex player.**

4. **Pull down the Edit menu and select "Copy Loop to Track".**
   Now, the program will create a note for each slice, positioned according to the timing of the slices. The notes will be laid out in semitone steps, with the first note on C1, the second on C#1 and so on, with one semitone for each slice. If the range between the locators is longer than the loop length, the loop notes will be repeated to fill out the loop.

Now you can reorder, overdub onto, and otherwise edit the note data on the edit lanes in the sequencer.

Copy Pattern to Track

This menu item is used for the Redrum drum machine and Matrix pattern sequencer. It converts the selected pattern to notes on a sequencer track. Proceed as follows:

1. **Select a sequencer track.**
   When working with a Redrum, you want to select the track for the Redrum device. For the Matrix, you would typically select the track for the Matrix' target device (the instrument device to which the Matrix is connected). This is because the Matrix itself produces no sound, so the notes won't do any good on the Matrix track.
2. **Set the locators to the desired range or length.**
   If the range set is longer than the pattern(s), the data will be repeated to fit the range.
3. **Select the pattern device.**
4. **Pull down the Edit menu and select "Copy Pattern to Track".**
   Note clips will be created between the left and right locators, according to the selected pattern.

! **When copying Matrix patterns, only the Gate and Keys values will be included!**

▶ **If you copied a Redrum pattern, you may want to turn off the "Enable Pattern Section" before playing back the new track data.**
Otherwise, both the main sequencer and the pattern sequencer will play the drum sounds, simultaneously.

▶ **If you copied a Matrix pattern, you may want to disconnect the Matrix (or even remove it), to avoid having both the Matrix and the sequencer notes playing at the same time.**

▶ **If you have automated pattern changes for your pattern device, you can render all patterns to notes in one go, using the "Convert Pattern Track to Notes" menu item instead.**
See "Convert Pattern Automation to Notes".

Shift Pattern Left/Right

These menu items are used for Redrum, Matrix, Thor (called "Shift Sequencer Pattern Left/Right") and the RPG-8 Arpeggiator (when the Pattern editor is activated).

The Shift Pattern functions move the notes in a pattern one step to the left or right.

Shift Drum Left/Right

These menu items are used for Redrum.

The Shift Drum functions move the notes for the selected instrument one step to the left or right.

Shift Pattern Up/Down

These menu items are used for the Matrix.

The Shift Pattern functions will transpose all the notes in a pattern one semitone up or down.

! **This function does not alter the Curve CV.**

Random Sequencer Pattern

This menu item is used for the Thor synthesizer. It will assign random values to the pattern sequencer steps, but only for the property selected with the Edit knob. For example, if "Note" is the edited property, only the note pitches will be randomized; leaving velocity values, lengths, durations and curves intact.

- **Randomized note pitches will be kept within the range set with the Octave switch.**
- **The "Steps" setting (pattern length) will not be changed by randomizing.**
- **Steps outside the current pattern length will not be affected.**

Randomize Pattern

This menu item is used for the Redrum, Matrix and RPG-8 Arpeggiator (when the Pattern editor is activated).

The Randomize Pattern function create random patterns. These can often be great starting points and help you get new ideas.

! **Note that for the Matrix, Randomize affects both the Gate, Note and Curve CV!**

Randomize Drum

The Randomize Drum functions creates random patterns for the selected drum sound channel in the Redrum drum machine.

Alter Pattern

This menu item is used for the Redrum, Matrix and RPG-8 Arpeggiator (when the Pattern editor is activated).

The Alter Pattern function modifies existing patterns. Note that there must be something in the pattern for the function to work on - using an Alter function on an empty pattern will not do anything.

! **Note that for the Matrix, Alter affects both the Gate, Note and Curve CV!**

Alter Drum

This function modifies existing patterns for the selected drum sound in Redrum. Note that there must be something in the pattern for that channel for the function to work - using an Alter function on an empty pattern will not do anything.

Invert Pattern

This menu item is used for the RPG-8 Arpeggiator device, when the Pattern editor is activated. This inverts the pattern, so that active steps become rests and vice versa.

Arpeggio Notes to Track

This menu item is used for rendering the arpeggio from an RPG-8 to actual note clips. For this to work, you must have recorded chords or notes on the RPG-8 track and set the locators (so that an arpeggio is generated when you start playback from the left locator).

"Arpeggio Notes to Track" will create a note clip between the locators on the selected track, containing the generated arpeggio notes. You can then mute the original note clip(s) on the RPG-8 track and edit the rendered arpeggio notes as usual.

Create Track for.../Delete Track for...

A rack device can have one sequencer track or no sequencer track. Instrument devices are by default created together with a sequencer track, while effect devices, mixers etc. are created without tracks.



- **If a device without sequencer track is selected, this menu item is called "Create Track for [device name]".** Select it to create an empty sequencer track for the device.
- **If the selected device has a sequencer track already, this menu item is called "Delete Track for [device name]".** It will remove the sequencer track and all its contents, but leave the device.

Go To Track for

- **With a device selected in the rack, select "Go To Track for [device name]" to bring the corresponding sequencer track for the device into view.**

Insert Bars Between Locators (item on the "Timeline" submenu)

! The sequencer must have edit focus for this item to become available.

This function inserts an empty area between the locators in the main sequencer. All events after the left locator are moved to the right to "make room" for the inserted area. See "Inserting bars" for more information.

Remove Bars Between Locators (item on the "Timeline" submenu)

! The sequencer must have edit focus for this item to become available.

This function removes all material between the locators in the main sequencer. All events after the right locator are moved to the left to "fill out" the gap after the removed section. See "Removing bars" for more information.

Set Loop to Selection (item on the "Timeline" submenu)

This command sets the Left and Right Loop Locators to encompass all selected clips in the arrangement.

Set Loop to Selection and Start Playback (item on the "Timeline" submenu)

This command sets the Left and Right Loop Locators to encompass all selected clips in the arrangement. Then, sequencer playback is automatically started in Loop Mode. This function also has a keyboard shortcut: press [P].

Select All Clips

This selects all clips on the Arrange pane.

Open in Edit Area

This opens the selected clip(s) in Edit mode in the sequencer. If multiple note clips are selected, they are opened for editing in Multi Lanes mode, see "Multi Lanes editing".

Bounce in Place

The Bounce in Place function lets you bounce the sound generated from playing back note or audio clips, with any insert effects and channel strip coloration - but without Send FX and Master Section settings - to a new audio clip on a new audio track. See "Bounce in Place".

Bounce Clips to New Samples (Audio Clips)

It's possible to bounce Audio Clips to new Song Samples. You could then edit the samples in the Edit Sample window and then load into a sampler device for playback. See "Bounce Clip(s) to New Sample(s)".



Bounce Clip to Disk... (Audio Clips)

This function allows you to export a selected audio clip as a WAV or AIFF file to disk. See "The "Bounce Clip to Disk" function".

Bounce Clips to New Recordings (Audio Clips)

This function allows you to export the recording of a selected audio clip to an additional Comp Row. See "Bounce Clip(s) to New Recording(s)".

Bounce Clip to REX Loop (Single Take Audio Clips)

This lets you bounce an open Single Take audio clip to a Rex file. The Rex file ends up on the Song Samples tab in the Browser. See "Bounce Clip to REX Loop".

Bounce Audio Clips to MIDI

It's possible to convert Single Take audio clips to note clips. This is especially useful for monophonic audio that can be opened in Pitch Edit mode. See "Bouncing audio to MIDI notes".

Stretch and Transpose Type

This function allows you to choose which Stretch and Transpose Type to use for a selected Audio Clip. See "Opening audio clips for editing" for more information.

Correct Pitch (Audio in Pitch Edit Mode)

This lets you correct pitches of selected notes, or of all notes in an audio clip in Pitch Edit mode. See "Correcting pitches".

Reset Pitch (Audio in Pitch Edit Mode)

This lets you reset the pitches of selected notes, or of all notes in an audio clip in Pitch Edit mode. See "Resetting pitches".

Split At Slices (Single Take Audio Clips)

This lets you split an open Single Take audio clip at the selected Slice Markers, and thus create several separate audio clips out of a bigger one. See "Split at Slices".

Split At Notes (Single Take Audio Clips)

This lets you split an open audio clip in Pitch Edit mode at the selected notes, and thus create several separate audio clips out of a bigger one. See "Splitting the clip at notes".

Revert Slices (Single Take Audio Clips)

This lets you undo all Slice Marker edits you made in an open Single Take audio clip and revert to the clip the way it was before you edited it. See "Revert All Slices".

Revert Notes (Notes in Single Take Audio Clips in Pitch Edit Mode)

This lets you "undo" all edits you have made in Pitch Edit mode (similar to the "Revert Slices" function in Slice Edit mode). See "Reverting all notes".



Enable/Disable Stretch (Audio Clips)

This function lets you decide if a selected audio clip should stretch and follow tempo changes in the song. When disabled, the audio clip doesn't follow the song tempo. When enabled, the audio clip is stretched and follows the song tempo of the sequencer. See "About tempo changes and tempo automation of audio tracks".

Delete Unused Recordings (Audio Clips)

This function deletes all recordings that are not used in the selected clip - or anywhere else in the song. By using this function, the file size of the song can be reduced. See "Delete Unused Recordings".

Normalize Clips (Audio Clips)

This function increases the overall audio level of selected Audio Clip(s) so that the loudest peak touches 0 dB. See "Normalizing audio clips".

Reverse

This function reverses selected Clip(s) and plays them back backwards, from the end to the start. See "Reverse" for information about reversing note and automation clips and "Reversing audio clips" for information about audio clips.

Stretch Type for New Recordings

Here you can set what Stretch and Transpose Type your following recordings on the selected Audio Track should use by default. (You can always change the Stretch and Transpose Type for your recordings afterwards, if you like.)

Convert Pattern Automation to Notes

If you have recorded or drawn pattern changes on a Redrum or Matrix track, you can have the whole track converted to notes, in the following way:

1. **Select the track with the pattern changes.**
2. **Select "Convert Pattern Automation to Notes" from the Edit menu or the context menu for the track.**
   For each pattern clip, the corresponding pattern is converted to note clips on the track (following the same rules as for the "Copy Pattern to Track" function). The track will play back just the same as when you played the pattern device with the pattern changes.

- **After the operation, the Pattern Select lane is switched off.**
  "Enable Pattern Section" (Redrum) and the Pattern Enable switch (Matrix) are automatically turned off.
- **When you use this with a Matrix, you need to move the note clips to the track of an instrument device (typically the device to which the Matrix is connected).**
  This is because the Matrix doesn't make any sound itself.

Convert Block Track to Song Clips

This item is available only when the Blocks Track is on. Selecting this item will convert all Block Automation Clips on the Block Track to regular clips on the respective tracks and lanes in the song.

Commit to Groove

This function is available if the track list has focus and one or several note lanes on the selected track have ReGroove Mixer channels assigned.

Commit to Groove will move all notes (on all note lanes on the selected track) to their grooved positions and then reset the groove settings to "No Channel" for the note lanes. In other words, this makes the groove "permanent" - the track will play back exactly as before, but you can now view and edit the grooved notes.

New Note Lane

Adds a new note lane to the selected track(s). This is the same as clicking the "+ Lanes" button above the track list.

Merge Note Lanes on Tracks

If there is more than one note lane on the selected track, this menu item will merge all note clips on all lanes into a single lane.

- ▶ **If there are several clips containing the same performance controllers (e.g. mod wheel) on the same positions in the song, only the performance controller data from the topmost lane will be kept.**
  This is the same rule as during playback - performance control data in the topmost lane has priority.

Get Groove From Clip

This requires that a single note clip is selected. The function will look at the notes in the clip and extract a groove from these. You can apply this groove to other note lanes or save it as a groove patch for later use.

1. **Create or record a rhythmic note "pattern" of some kind.**
   You may for example record a drum pattern, or use the notes playing the slices in a REX loop.

- ▶ **For the groove to be useful in most common music styles, it's recommended that the note clip is an exact number of bars in length - preferably 1, 2, 4 or maybe 8 bars.**

2. **Open the ReGroove Mixer from the transport panel and select a channel for editing (by clicking its Edit button).**
   This is where your custom groove will end up - choose an unused channel if you don't specifically want to replace a groove.
3. **With the note clip selected, select "Get Groove From Clip" from the Edit menu or sequencer context menu.**
   The groove is assigned to the ReGroove Mixer channel as "User". By selecting that ReGroove Mixer channel for other note lanes, you can make the music fit with your custom groove.
4. **Select the Groove tab in the Tool window.**
   Here you can adjust how the groove should affect note timing, velocity and length and also save the groove as a Re-Groove Patch (including the settings of the sliders in the window).

Read more in "The ReGroove Mixer".

Join Clips

This requires that more than one clip is selected on the same lane. Join Clips will join the selected clips together.

- ! **If note or automation clips contain masked-out events in the range between the clips, these events will be deleted. Also, if note or automation clips overlap, any hidden events are deleted - see "Joining clips".**
- ▪ **If joined audio clips contain masked recordings, these will not be deleted but moved and masked on a new Comp Row - see "About joining audio clips".**

Mute Clips/Unmute Clips

If there are one or several unmuted clips selected, this menu item is called "Mute Clips". Muted clips (shown with angled stripes and dimmed borders) will not play back but can be edited and arranged as usual.

If only muted clips are selected, the menu item is called "Unmute Clips". The keyboard shortcut for Mute/Unmute Clips is [M].

Crop Events to Clips

Notes or automation events can be positioned outside the start or end of a clip. For example, this would happen if you have resized a clip after recording. Notes outside the clip become masked and won't be heard on playback, but you can view and edit them if you open the clip.

Selecting "Crop Events To Clips" removes all such outside events from the selected clip(s). If tracks are selected in the track list, this function is performed on all clips on the selected track(s). See "About masked recordings and events" for more details.

Add Labels to Clips/Remove Labels from Clips

This allows you to name the selected clips.

- **Clips with name labels (and their lanes) are shown slightly taller, to make room for the labels.**
- **If you select "Add Labels to Clips" with a single clip selected, this adds an "untitled" label and opens a text box for editing the label.**
  If you have several clips selected, the "untitled" label will be added to all selected clips. To edit the names of the clips, you need to double click each label.
- **If all selected clips have labels already, the menu item is called "Remove Labels from Clips".**

See "Naming clips" for more information.

Clip Color

Allows you to select a color for the selected clip(s). See "Coloring clips" for more details.

Channel Color/Track Color

Allows you to select a color for the selected channel(s) and track(s). The selected color is shown in the track list and will be assigned to all new clips you create on the track. However, clips that are already on the track will not be affected - to change color of existing clips, select the clips and use the "Clip Color" setting.

- **If "Auto-color New Sequencer Tracks" is activated on the Options menu, tracks will get colors assigned automatically when they are created.**

See "Coloring tracks".

Adjust Alien Clips to Lane

If an automation clip has been moved to a lane for a parameter with a different range (for example if you cross-browse to another device type), it will be shown as alien and won't play back. Depending on the data, you may be able to fix this by selecting the clip and selecting "Adjust Alien Clips to Lane". This scales the automation data in the clip to fit the range of the current lane.

! **If it's not possible to scale the data, an alert will appear to tell you this.**

See "About alien clips" for more information.

Select Notes of Same Pitch

If you have selected one or several notes in an open note clip, this function automatically selects all other notes of the same pitches in that clip.

Move/Duplicate Selected Notes to New Lane

If you have selected one or several notes in an open note clip, this function automatically moves/duplicates the notes to a new clip on a new note lane.



Transpose... (Note Tools submenu item)

Brings up the Transpose Notes dialog, where you can transpose and/or randomize Note pitches.

Note Velocity... (Note Tools submenu item)

Brings up the Note Velocity dialog, where you can change, scale and randomize Note Velocity. You can also generate Velocity Ramps.

Note Length... (Note Tools submenu item)

Brings up the Note Length dialog, where you can scale the note lengths and generate Legato.

Alter Notes... (Note Tools submenu item)

Brings up the Alter Notes dialog, where you can alter the pitches between several selected notes or all notes in a selected note clip.

Randomize Positions (Note Tools submenu item)

Brings up the Randomize Positions dialog, where you can randomize the offset of the note's start positions within the range of the set tick value.

Quantize

This lets you quantize note clips and Single Take audio clips, as well as selected notes in note clips, selected Slices in Single Take audio clips and selected notes in audio clips in Pitch Edit mode. See "Quantizing audio" and "Quantize".

Quantize Setup...

This brings up the Quantize Setup dialog, where you can choose quantize grid and quantize amount.

Crossfade

This lets you crossfade two partly overlapping audio clips. See "Crossfading audio clips" for more details.

Edit Sample

This command is available when a sample is selected in the Song Samples location. Selecting Edit Sample opens the sample in the Edit Sample window. See "Editing samples" for more information.

Duplicate Sample(s)

This command is available when one or several samples are selected in the Song Samples location. Select this to create a duplicate of the selected sample. The duplicated sample is placed in the All Self-contained Samples and Unassigned Samples folders. Several selected samples can be duplicated in one go. See "Duplicating samples" for more details.

Export Sample(s)

This command is available when one or several samples are selected in the Song Samples location. Select this to export the selected sample to disk. A dialog appears where you can select file format. Several selected samples can be exported in one go. See "Exporting samples" for more details.

Delete Sample(s)

This command is available when one or several samples are selected in the Song Samples location. Select this to permanently delete the selected sample(s) from the song. Note that samples from the Factory Soundbank and from ReFills will not be deleted from their original locations - only from the song document. Several selected samples can be deleted in one go. See "Deleting samples from a song" for more details.

Edit Keyboard Control Mapping...

This menu command is available when Keyboard Control Edit Mode is selected. It will open a dialog where you can assign a Keyboard Control for a selected parameter. See "Editing Keyboard Control" for more information.

Clear Keyboard Control Mapping

This menu command is available when Keyboard Control Edit Mode is selected. It will remove the Keyboard Control mapping for a selected assigned parameter. See "Editing Keyboard Control" for more information.

Clear All Keyboard Control Mappings for Device

This menu command is available when Keyboard Control Edit Mode is selected. It removes all keyboard mapping you have set up for the selected device. See "Editing Keyboard Control" for more information.

Edit Remote Override Mapping...

This menu command is available when Remote Override Edit Mode has been activated on the Options menu. It opens a dialog where you can assign a Remote Override for the selected parameter. See "Remote Override mapping".

Clear Remote Override Mapping

This menu command is available when Remote Override Edit Mode has been activated on the Options menu. It will remove the Remote Override mapping for a selected assigned parameter. See "Remote Override mapping".

Clear All Remote Override Mappings for Device

This menu command is available when Remote Override Edit Mode has been activated on the Options menu. It removes all Remote Override mapping you have set up for the selected device. See "Remote Override mapping".

Copy/Paste Remote Override Mappings

These menu commands are available when Remote Override Edit Mode has been activated on the Options menu. You can use them to copy override mappings from one device and paste them into a device of the same type.

If the device you paste into is in the same song as the device you copied from, the operation will replace the existing overrides. See "Remote Override mapping".

Go to Product Page...

With a Rack Extension device selected in the rack, selecting this item will start up your default web browser, which will take you to the product page for the R.E. at the Reason Studios web site.



Settings – User Interface



Trigger notes while editing

When this is selected, transposing notes, by manually moving them with the Selection Tool, will make the notes trigger - and sound. This is useful since you will hear when the notes reach the correct pitches.

Keep Events in Clip while Editing

This function determines how note and automation events behave if they are drawn, moved or pasted outside the boundaries of the open clip in Edit mode in the sequencer.

- **With "Keep Events in Clip while Editing" selected, events drawn, moved or pasted outside the boundaries of the open clip will still belong to the original clip - but will be masked.**
- **With the "Keep Events in Clip while Editing" deselected, the open clip will expand to contain the drawn, moved or pasted events - or, if this is not possible, the events will be placed in an existing, or new, clip.**

See "About drawing notes outside an open clip", "About moving notes outside or between clips" and "Pasting events outside an open clip" for detailed examples.

Ask before changing audio clip mode or stretch type

When this is selected you will get an alert when you switch clip mode (e.g. from Comp to Pitch Edit Mode) or stretch and transpose type (e.g. from Vocal to Allround) for an audio clip.

Reverse notes graphically

When selected, notes you reverse in a note clip will be reversed graphically instead of "musically". See "Reverse" for more details.

Return to last start position on stop

When active, clicking Stop in the sequencer will make the Song Position Pointer automatically return to the last start position. If not active (default), the Sequencer will simply stop at its current position.

Show parameter value tool tip

Normally, if you hold the mouse pointer over a parameter on a device panel for a moment, a Tool Tip appears displaying the name and the current value of the parameter. If you uncheck this option, Tool Tips will not be displayed.

Show automation indication

If a parameter is automated in the sequencer, this is by default indicated by a green frame around the parameter on the device panel. If you uncheck this option, automation will not be indicated.

Show Block clip content in Song View

Tick this box if you want to see the ghosted contents of the Block clips in the song arrangement in the Song View.

Auto color tracks and channels

Select this if you want each new sequencer track and Mixer channel to get a new color. If deselected, each new sequencer track and Mixer channel will get the same color.

Mouse Knob Range

This lets you adjust the response sensitivity of the various knobs in Reason when manipulating them with the mouse. A higher sensitivity gives a higher degree of precision. You can choose between Normal, Precise and Very Precise.

Automation Cleanup

The Automation Cleanup setting reduces the number of automation points when you record or draw automation. Adjust this setting if you find that recording or drawing results in too many or too few automation points.

- **This can also be done manually from the Tool window (Sequencer Tools tab) - see "The "Cleanup Automation" function".**

Hide Cables function

The selected alternative determines how cables on the back of the rack should be displayed when "Hide Cables" is selected on the Options menu:

- **Select "Shows cables for selected devices only" to only display the cables for selected devices.**
  All other (non-selected) devices will have "transparent" cables to make it easier to distinguish the cables of selected devices.
- **Select "Hides auto-routed cables" to only display manually routed cables.**
  All devices with auto-routed cables will have "transparent" cables to make it easier to distinguish the manually routed cables.
- **Select "Hides all cables" to hide all auto-routed and manually routed cables.**
  All cable connections on devices will be indicated with colored dots in the jacks, and no cables will be displayed.

See "Cable appearance" for more details.

Theme

Here you can choose from two different visual themes, i.e. how the user interface should be visually presented. The selected theme/color affects the Sequencer, Browser and Transport Panel areas. See "About different Themes".

! **Note that you have to restart Reason for the new Theme to take effect.**

Language (Windows only)

Reason is localized in several different languages. The language setting affects menus, dialogs, tool tips and some display texts, but generally not the texts on the device panels. If you run Reason under Windows, you can select preferred language on this page.

! **Note that you need to restart Reason for a language change to take effect.**

! **Under macOS, Reason will use the language selected in the operating system.**

Monitoring


In the Monitoring section you can choose how you want monitoring of the input signals to work on audio tracks.

- **Select "Automatic" to automatically monitor the input signals on all record enabled audio tracks when recording and when the sequencer is stopped.**
  Record enabling of audio tracks is done by clicking the Record Enable button on the track in the track list - see "Record enabling".

! **Note that if you have selected "Standard" in the "Master Keyboard Input" section on the "MIDI" page in Settings (see "The Master Keyboard Input setting"), selecting an audio track also automatically record enables it - and consequently enables monitoring in "Automatic" mode.**

- **Select "Manual" to manually activate monitoring by clicking the Monitor button on the track in the track list.**
- **Select "External" if you are monitoring directly through your audio interface outputs (and not via the Reason application) - or via an external mixer.**
  In "External" mode it's not possible to monitor in Reason.

Settings – Browsing



Load default sound in new devices

When this is activated and you create a new device (of a device type that supports patches), a default patch will be loaded. This way you can be sure that a new device generates sound right away. The default sound will also determine the default location in the Factory Sound Bank when you browse for patches for the new device.

If you turn this off, new devices will be initialized - parameters are reset to their default values and no samples are loaded in sample-based devices.

! **Note that "Sound" also implies patches for effect devices such as the RV7000 and Scream 4.**

Browsing starts in default sound folder (for new devices)

This option lets you decide where the Browser should start showing patches when you have created a new device. If the "Browsing starts in default sound folder (for new devices)" option is ticked, the browsing starts in the device's home folder, showing the patches and folders included with the device. Otherwise it starts in "All Locations", showing all patches for that device (including any you have created yourself).

Self-contain samples when loading from disk

When this is activated, any samples you load into a sampler device from disk will automatically become self-contained and saved together with the rest of the song data when you save your Song.

When importing audio...


Here you can choose how Reason should stretch, or not stretch, imported audio. Please see "About tempo matching imported audio to the sequencer" for detailed information.

Cloud folders (warn before adding as Shortcuts)

Here you can exclude folders that you have in the Locations and Favorites section of the Reason Browser from scanning and indexing. This is especially useful if you have cloud (e.g Dropbox) folders on your computer.

- ▶ **Click the Add button to add folders to be excluded from the indexing.**
- ▶ **Select a folder you want to remove in the list and then click the Remove button.**

If you add content from an (excluded) Cloud folder as e.g. a Shortcut in the Browser, you will get the following warning so that you can decide if you really want to add the folder as a Shortcut:



Warning message if you add content from an excluded Cloud Folder as a Shortcut in the Browser.

- ▶ **Click Continue to add the folder as a Shortcut anyway.**
- ! **Make sure that the folder is synced to disk and not "online-only".**
- ▶ **Click Cancel if you don't want to add the folder as a Shortcut.**

Device sorting in new songs:

Here you can choose the default device sorting method in your new songs. You can change the default "Rack per Track" setting to "Auto-Group Devices" or "No Grouping".

- **The "Rack per Track" alternative creates a separate Rack column for the devices of each audio or instrument track.** This makes it easy to navigate and focus on one track at the time. See "Rack per Track mode" for more details.
- **In "Auto-Group Devices" mode, all devices are shown in the same rack (although additional rack columns can be added manually).**
  Devices that belong to the same Device Group are kept together (for example an instrument, its effects and its mix channels). See "Creating devices" for more details.
- **"No Grouping" means that you can place and move individual devices completely freely in the Rack.**

Default song

It's possible to specify a certain song document which will automatically open as a "template" each time you select "New" from the File menu. The Default Song could be an empty document, a song you have created earlier, or a factory made Template song. See "Setting up a Default Song" for information on how to select Default Song.

Use Side Panel Browser in new songs

Tick this box if you always want the Browser to open in the side panel to the left in your new songs. This setting also determines how the Browser is shown when you open songs made in older Reason versions.

Open last song on startup


Checking this automatically opens the last saved song each time you launch Reason.

- ▶ **Tick the checkbox to open the last saved song the next time you launch Reason.**

Open Reason Companion on Startup

When this is activated, the Reason Companion application launches automatically when you launch Reason.

Settings – Audio



Audio Device – Windows

This menu lists all the available audio card drivers on your computer, and lets you select which one Reason should use. Which option to select depends on the audio hardware:

- **If you are using audio hardware for which there is a specific ASIO driver, you should select this.**
  With an ASIO driver written specifically for the audio hardware you will get lower latency (see below), support for higher sampling frequencies (up to 192 kHz in 24 bit/32 bit float resolution), and possibly better support for additional hardware features such as multiple outputs.
- **If there is no specific ASIO driver, you could select a generic ASIO driver (such as ASIO4ALL) for the audio hardware.**

! **Reason requires that the audio card uses an ASIO driver on Windows systems, if you want to use both audio in and audio out. Direct X and MME drivers only support audio out.**


Audio Device – macOS

This menu lists all the available audio devices on your system, and lets you select which one Reason should use. Which option to select depends on the audio hardware:

- **If you are using audio hardware for which there is a specific Core Audio driver, you should select this.**
  With a Core Audio driver written specifically for the audio hardware you will get lower latency (see below), support for higher sampling frequencies (up to 192 kHz in 24 bit/32 bit float resolution), and possibly better support for additional hardware features such as multiple outputs.

Active inputs and outputs

This displays the number of audio input and output channels the currently selected audio hardware supports. If your audio card has multiple inputs and/or outputs, and an audio driver that supports this is selected, the "Channels..." button will be enabled. Clicking this will bring up a window with check boxes for all available inputs and outputs. By ticking these boxes, you are able to select which input and/or output channels should be active.



Active inputs and outputs will be also indicated with yellow and green LEDs in the Reason Hardware Interface - see "How Reason communicates with your audio hardware".

Clock Source (ASIO Only)

If you are using an ASIO driver for your audio hardware, you have the possibility of selecting a Clock Source. This is used for determining the source to which audio playback should synchronize its sample rate. If you have an audio card and a driver that supports it, you can choose to synchronize to external sources.

Control Panel

If you have selected an ASIO or Core Audio driver, this button brings up a control panel window specifically for that audio hardware. This may contain buffer settings, routing options, synchronization alternatives etc.

Sample Rate

Sets the sample rate used for recording and playback. The available options depend on the audio interface and its driver.

If a song contains audio tracks recorded or imported at one sample rate, and you select another sample rate here, the audio will be sample rate converted on the fly. The original audio in the song is not affected.

See "Sample Rate settings for recording and playback" for more details.

Master Tune

This lets you adjust the global tuning in Reason. Standard tuning is "middle A" at 440 Hz. You can adjust this by +/- 100 cents. The Master Tune setting affects the tuning of all sound sources in Reason, including the Tuner function on the Audio Tracks. It also affects the tuning of the Redrum and Dr. Octo Rex loop player.

! Note that the Master Tune setting does NOT affect the pitch of the audio on audio tracks!

! Note that the Master Tune setting does NOT affect the pitch of any VST plugins used in the song!

Buffer Size

The Buffer Size determines the Input and Output Latency of the audio. Generally, the smaller the Buffer Size, the lower the latency. However, too low a Buffer Size setting could result in clicks, pops, dropouts, etc. in the audio. Therefore, the Buffer Size should be set to an "optimal" value rather than to the lowest value. See "Buffer Size settings" for more information.

Input and Output Latency

The Input Latency is the delay between when the audio is "sent" from a connected microphone or instrument and when it's detected by Reason. Output Latency is the delay between when audio is "sent" from Reason and when you actually hear it. The latencies in an audio system depends on the audio hardware, its drivers and their settings.

When you select a driver, its latency values are automatically reported by the audio card and displayed in the Settings-Audio dialog. Depending on the audio hardware and the driver, you may be able to adjust these values:

- **If you are using an ASIO driver specifically written for the audio hardware under Windows, you can in most cases make settings for the hardware by clicking the Control Panel button.**
  This opens the hardware's ASIO Device Control Panel, which may or may not contain parameters for adjusting the latency. Usually this is done by changing the number and/or size of the audio buffers - the smaller the audio buffers, the lower the latency. Please consult the documentation of your audio hardware and its ASIO drivers for details!

OK, so why not just set the latency to the lowest possible value? The problem is that selecting too low a latency is likely to result in playback problems (clicks, pops, dropouts, etc.). There are several technical reasons for this, the main one being that with smaller buffers (lower latency), the average strain on the CPU will be higher. This also means that the more CPU-intensive your Reason song (i.e. the more tracks and devices you use), the higher the minimum latency required for avoiding playback difficulties.

See "About latency" for more information.

Latency Adjustment

If you are monitoring via an external mixer, and have selected "External" in the "Monitoring" section on the "User Interface" tab in Settings (see "Play in background"), there might be situations where you experience that the recorded audio is generally played back too early - or too late - in the song. This could be because the latency values reported to Reason by the audio card were not completely accurate.

If you should experience that your audio recordings are played back too early or too late compared to the instrument tracks in your song, you can adjust this by editing the Latency Adjustment parameter.

- **If the recorded audio plays back too early, lower the Latency Adjustment value.**
- **If the recorded audio plays back too late, raise the Latency Adjustment value.**

See "Latency Adjustment" for information.

Max audio threads

Here you can select the maximum number of audio threads Reason should be allowed use. The “Default” setting equals the total number of physical cores in your computer’s CPU (corresponding to the old "Use multi-core audio rendering" option, but without the "Use hyper-threading audio rendering" option in older Reason versions). On Apple M1/M2/M3/M4/M5 the Max audio threads setting defaults to the number of Performance cores.

This setting can also be used to limit the number of threads if you want to leave room for other apps or perhaps multi-core VSTs.

- **If you should experience performance problems in Reason, try selecting another Max audio threads number, starting from the highest number and going down one number at a time until you get the best performance.**


▶ **If you are using a dual-core Intel CPU and previously used the "Use multi-core audio rendering" and "Use hyper-threading audio rendering" functions available in earlier Reason versions, select the "3 (HT)" setting to get the equivalent performance.**

With Reason 13.5.1 this function has been refined to also support Intel's new Performance Hybrid Architecture CPUs. Intel's hybrid CPUs can have up to three different types of cores: Performance cores (P-cores), Efficient cores (E-cores) and Low Power Efficient Cores (LPE-cores). They can also use hyper-threading.

Depending on the CPU core configuration in your specific Intel hybrid processor, you can now select some additional Max Audio Threads alternatives.

The "Default" alternative at the top of the Max Audio Threads list corresponds to one (1) audio thread for each P and E core (but no LPE cores or hyper-threading), minus one (1) thread, which is used to ensure that the main thread can run efficiently.

The example in the picture below shows a hybrid Intel CPU with 6 P-cores and 4 E-cores (but no LPE-cores), with hyper-threading:



Intel Performance Hybrid Architecture CPU example

Choosing "Default" in the Max Audio Threads dropdown in the example above would correspond to the "9 (6 P-cores, 3 E-cores)" alternative (1 thread per core, minus 1).

If you are experiencing performance problems, for example when using VSTs in your songs, try selecting another Max Audio Thread number, starting from e.g. "8 (6 P-cores, 2 E-cores)" in the example above and going down one number at a time until you get the best performance.

If you are not using any VSTs in your song you might want to try a higher (>9) Max Audio Threads number to see if this works better. It's mostly "trial and error", so make sure you check out the different alternatives.

See "Audio Basics" for more information on how Reason handles audio.

Render audio using audio card buffer size setting

The "Render audio using audio card buffer size setting" function should be selected (checked) for best plugin performance. When selected, the audio batches are rendered internally according to the set Buffer size (see "Buffer Size" above). For example, if you have a Buffer size of 512 Samples, each audio batch will be 512 samples internally. Raising the Buffer size will let Reason process larger audio batches in one go, which is often more efficient. Many plugins are also more efficient when doing larger audio batches. if you are using DSP-heavy VSTs (mastering effects, for example), these will run a lot smoother with this function selected.

! **Note that old songs might sound different with this function selected, if the songs uses feedback routings and CV connections.**


If unchecked (off), all audio batches are rendered internally at a fixed size of 64 samples - regardless of the Buffer size setting. This might be desirable if you are using feedback signal routings and CV connections in your songs, and want the internal latency of those connections to be fixed at a short value all the time. This might result in performance problems for DSP-heavy VSTs, though. Unchecked will give the same performance as in Reason 10.2 and earlier versions.

Play in background

When this is activated, Reason will not "release its grip" on the audio hardware when another application is active.

- **The advantage is that Reason will keep playing while you work in the other application.**
- **The disadvantage is that other audio applications may not be able to play any audio, depending on the type of driver used.**

Settings – MIDI



This is where you set up your MIDI hardware; keyboards and control surfaces.

- **The "Remote keyboards and control surfaces" list at the top shows the manually added surfaces/MIDI keyboards.** Selecting a surface in the list allows you to edit its settings or delete it from the list, by clicking the corresponding "Edit" or "Delete" button.
- **Clicking the "Auto-detect surfaces" button will scan for connected control surfaces.** This requires a USB connection or a two-way MIDI connection. Note that not all control surfaces support auto-detection - but you can always add control surfaces manually.
- **If you have surfaces added in the "Remote keyboards and control surfaces" list that you do not wish to use with Reason, you can uncheck the "Use with Reason" checkbox.**
- **The "Use no master keyboard" button allows you to disable MIDI note input in the sequencer.** The surface designated as Master Keyboard cannot be locked to a specific device - it always follows the sequencer Master Keyboard Input. By selecting the Master Keyboard surface in the Attached Surfaces list and clicking this button allows you use Surface locking, although you will not be able to play the device. See "Locking a surface" in the Remote chapter for details.

Adding or editing a control surface

To add a control surface, click the "Add" button to open the Control surfaces dialog. If you want to edit the settings for an existing control surface, click the "Edit" button. Then proceed as follows:

1. **Select the manufacturer of your control surface from the Manufacturer pop-up menu.**
   If you can't find it on the menu, see below.
2. **Select the model of your control surface from the Model pop-up menu.**
   If you can't find it on the menu, see below.
3. **An image of the selected control surface model is shown, often along with some information text - read this carefully.**
   For some control surfaces, you need to select a specific preset to use the surface with Reason - this is noted here.
4. **Use the MIDI Input pop-up to select the input port to which you have connected the surface.**
   If in doubt, you can click the "Find" button and then tweak a control or play a key on the control surface to have Reason find the correct input port for you.

- **Some control surfaces may have more than one MIDI Input pop-up menu.**
  You need to select ports on all MIDI Input pop-up menus.
- **Some control surfaces will have a MIDI Output pop-up menu.**
  In some cases this is labeled "Optional" - then you don't have to make a selection. In other cases, a MIDI Output is required. This is the case if the control surface uses MIDI feedback - motor fader, displays, etc.

5. **If you like, you can rename your control surface in the Name field.**
6. **Click OK to add the surface.**

▶ **Depending on the surface model, alerts may appear, reminding you to select a specific preset etc.**
In some cases, Reason can restore a preset in the control surface to factory settings for you. If so, you will be informed about this.

Finally you return to the MIDI Settings page, where your added surface is now listed.

If your control surface model isn't listed

If you can't find your control surface listed on the Manufacturer or Model pop-up menus when you try to add it, this means that there's no native support for that model. However, the program supports generic keyboards and controllers. Here's what to do:

▶ **Select "Other" on the Manufacturer pop-up menu and then select one of the three options on the Model pop-up menu.**

or, if the Manufacturer is listed but not your specific model:

▶ **Select one of the three "Other" options on the Model pop-up menu:**

In both cases, the options are:

- **MIDI Control keyboard**
  Select this is you have a MIDI keyboard with programmable knobs, buttons or faders. You need to set up your control surface so that the controllers send the correct MIDI CC messages, depending on which Reason device you want to control - check out the MIDI Implementation Chart in the Reason documentation.
- **MIDI Control Surface**
  Select this if you have a MIDI controller with programmable knobs, buttons or faders (but without keyboard). Again, you need to set your controllers to send the right MIDI CCs.
- **MIDI Keyboard (No Controls)**
  Select this is you have a MIDI keyboard without programmable knobs, buttons or faders. This is used for playing only (including performance controllers such as pitch bend, mod wheel, etc.) - you cannot adjust Reason device parameters with this type of control surface.

▶ **Under the "Other" Manufacturer, there are also two options called "MIDI Multichannel Control Keyboard" and "MIDI Multichannel Control Surface". Use these if the controls on your keyboard/control surface send the same MIDI message but on different MIDI channels. Read more in "Adding a specific control surface or keyboard" in the Remote chapter.**

After selecting a model, proceed with selecting MIDI input as described above.




About the Master Keyboard

One of the control surfaces can be the Master Keyboard. This is like any other control surface, but it must have a keyboard and it cannot be locked to a specific Reason device (in other words, it always follows the MIDI input to the sequencer). This is the surface you use to play the instrument devices in Reason.

- **The first surface with a keyboard that is added (or found by auto-detect) is automatically selected to be the Master Keyboard.**
  This is shown in the Attached Surfaces list on the Settings page.
- **If you want to use another surface as Master Keyboard, select it in the list and tick the "Master Keyboard" check box.**
  There can only be one Master Keyboard.
- **If you don't want to use any Master Keyboard at all, select the current Master Keyboard surface and uncheck the Master Keyboard box.**

Easy MIDI Inputs

By default Reason automatically scans and detects any unused MIDI In port(s) on your computer. If you have a MIDI keyboard or MIDI control surface connected to your computer, Reason automatically connects and lets you use it for controlling Reason. This way you don't have to do any manual set-up but can start controlling Reason right away.




See "Automatic set-up using the Easy MIDI Inputs function" for more details.

The Master Keyboard Input setting

This determines how you set Master Keyboard Input in the sequencer: to which track and device the Master Keyboard should be directed (which track to play from your keyboard):

- **In "Standard" mode, the selected track automatically gets Master Keyboard Input.**
  This way you can just click anywhere on a track in the track list to select it for playing (or use the arrow keys to step up and down in the track list).
- **In "Separated" mode, you need to click directly on the device icon to the left in the track list to set Master Keyboard Input.**
  This is useful if you're working with multiple selections in the track list, or if you want to select different tracks for editing without changing which device you play from your keyboard.
- **Master Keyboard Input is indicated by a grey MIDI Input indicator next to the device icon in the track list.**

Settings – Sync



MIDI Clock Sync In/Out

Using the Sync Input Port, you can synchronize Reason to external devices (tape recorders, drum machines, stand alone sequencers, workstations etc.) and other computer programs running on the same or another computer.

By using the Sync Output Port, Reason can act as MIDI Clock Sync host for external equipment and applications.

! **You can select several MIDI Output Ports if you want to send the MIDI Clock to multiple MIDI ports.**

As part of the MIDI Clock standard there are also options for sending out Start, Stop, Continue and Song Position Pointers, see "Using Reason as MIDI Clock Host".

- ▶ **By first selecting the appropriate MIDI input and/or Output using the MIDI Clock Input/Output pop-ups and then selecting "MIDI Clock Sync" on the Options menu, Reason is ready to receive or send MIDI Clock sync.**
  See the "Synchronization and Advanced MIDI" chapter for more information.
- ▪ **There are also controls for adjusting the Input and Output Offsets.**
  See "Adjusting for Latency" for more information.

Send MIDI Clock while Sequencer is Stopped

When this box is checked, Reason continues to send out MIDI clock signal also when the sequencer is stopped.

Send Song Position Pointer

When this box is checked, Reason sends out MIDI Song Position Pointer information to the device. If the synced device doesn't support Song Position Pointer, turning this setting off can improve synchronization. This is also useful if the synced device is playing a looped pattern and should disregard all positioning.

Send Stop/Continue when Repositioning


When this box is checked Reason sends out Stop/Song Position Pointer/Continue messages to the synced device, if the song position locator in the sequencer is moved (either manually or when in Loop mode) when the sequencer is running.

If unchecked, only Song Position Pointer messages are sent out if the song position locator is moved (or in Loop mode) while the sequencer is running.

Ableton Link

Here you can select if you want Ableton Link to synchronize start/stop. See "Synchronization using Ableton Link" for more information.


Settings – Other Controls



On-screen Piano Keys

In this section you can specify what computer keyboard keys should be used for the On-Screen Piano Keys function.

▶ **To change key assignment, click on a key in the window and then press another available key on the computer keyboard to assign it.**



▶ **Since many keyboard keys are already "locked" to other functions and commands in Reason, it's not really applicable to reassign all the actual "play" keys. It's more useful to reassign the Octave and Velocity (numeric) keys.**

▶ **Click the "Reset to defaults" button to revert to the preset keyboard keys assignment.**

See the "On-screen Piano Keys" chapter for information on how to use the On-screen Piano Keys.


External Control

The External control inputs provide up to 64 MIDI input channels divided into four buses, each with 16 channels.

▪ **These MIDI inputs are for individual control of Reason Devices from an external sequencer.**
This could be an external hardware sequencer or sequencer software that is installed on the same computer as Reason. See the chapter "Synchronization and Advanced MIDI" for more details.

! **The External control busses should NOT be used if you are using Reason's internal sequencer!**

Settings – Folders




VST Plugin Folders

Here you can select the folders you want Reason to scan for VST plugins during each launch. See "Defining custom VST folders" for more information.

Scratch Disk Folder

Here you can select where you want to locate the Scratch Disk Folder. The Scratch Disk Folder is a temporary storage for recorded audio files before they have been manually saved in a song document file. By default, Reason places the Scratch Disk folder in the system temp folder in your home directory. You can manually change the Scratch Disk folder location if you like. See "Changing Scratch Disk folder location" for more information.

Settings – Account



If you have logged in once in the Welcome to Reason login window, which appears at launch, you will be brought straight into Reason without getting prompted with the login window the next time you launch Reason.

On the Account tab you can see who is logged in (Name and User/Account name).

- **Clicking the Account page button brings you to your Reason Studios account web page.**
- **If you have a perpetual Reason license - or an Annual Reason+ subscription - you can authorize up to three different computers for long-term off-line use.**
  Please see "Authorizing a computer for long-term off-line use" for more information.

Create menu

Add Instrument.../Add Effect.../Add Player...

Selecting this will open the Browser and show the appropriate patch types. Selecting a patch will automatically create the corresponding device and load the patch into it. Depending on which menu item you selected, the Browser will be set to show Instrument, Effect or Player patches only.

Add Audio Track

Select this to create a new audio track in the sequencer, its associated Audio Track Device in the rack with its corresponding channel strip in the Main Mixer. The audio track, device and channel strip will be automatically named "Audio Track n", where "n" is an incremental number.

You could then rename the track, device and channel strip afterwards if you like - see "Naming tracks".

Add Mix Channel

Select this to create a new Mix Channel device in the rack with its corresponding channel strip in the Main Mixer. This function is handy if you, for example, want to route separate audio outputs from a device to several separate Mix Channels.

Find in Browser

Select this to open the Browser without Browse Focus. In the Browser you can select and load patches, samples etc. and create the corresponding device. See "Using the browser without Browse Focus".

Instrument Devices>/Effect Devices>/Utility Devices>/Player Devices>

- **To create a new device, select the desired item from one of the sub-menus.**
  Depending on what type of device you create, the result can be different. See "Creating devices" for a complete description of what happens when you create different device types.

  Rack Extension devices are sorted below the Reason devices, in alphabetical order per manufacturer. However, Reason Studios Rack Extension devices are always shown at the top of the Rack Extension section.

Find Device

Select this to set focus to the text/search field in the Device Palette, where you can search for devices.

View menu

Show/Hide Mixer

Select this (or press [F5]) to show or hide the Main Mixer. If you have selected "Show Mixer in Separate Window" on the View menu, the Mixer will open in a separate, floating window; otherwise it will open as an area in the document window.

Show/Hide Rack

Select this (or press [F6]) to show or hide the Rack. If you have selected "Show Rack in Separate Window" on the View menu, the Rack will open in a separate, floating window; otherwise it will open as an area in the document window.

Show Sequencer Only

Select this (or press [F7]) to hide the Rack and Mixer and view the Sequencer area only. If Rack or Mixer are in separate windows, this means closing them.

! **Note that it's not possible to toggle show/hide the Sequencer area - only show.**

Show Mixer in Separate Window

If this setting is ticked, the Main Mixer will appear in a separate floating window when it is open. If not, the Mixer will be shown as an area in the document window.

! **This is a global setting that affects all songs - set it according to how you prefer to work.**

Show Rack in Separate Window

If this setting is ticked, the Rack will appear in a separate floating window when it is open. If not, the Rack will be shown as an area in the document window.

! **This is a global setting that affects all songs - set it according to how you prefer to work.**

Show Rack Navigator

Selecting "Show Rack Navigator" will show the Rack Navigator to the right in the rack. De-selecting "Show Rack Navigator" will hide the Rack Navigator.

! **Note that the Rack Navigator is not available when Single Column mode is selected (in Rack per Track mode).**

Flip Rack

This switches the rack view between the front and rear panels. A quicker way to do this is to press [Tab], or click the Flip Rack button in the top bar of the Reason (or separate Rack) window.

Hide Cables

If there are many connections in Reason, the cables can sometimes obscure the view, making it difficult to read the text printed on the back panels of the devices. Cables can be displayed in "normal" mode and in "Hidden" mode.

▶ **Select "Hide Cables", or press [K], to "hide" the cables according to the setting you have made on the "User Interface" tab in Settings.**

See "Hide Cables function" for information on how to use this function.

Show/Hide Device Palette

Selecting this, or pressing [F3], will show or hide the Device Palette.

Show/Hide Browser

Selecting this, or pressing [F9], will show or hide the Browser area.

Show/Hide Track Panel

Selecting this will show or hide the Track Panel to the left of the Sequencer.

Show/Hide Edit Area

Selecting this, or pressing [F8], will show or hide the sequencer Edit Area.

Show/Hide ReGroove Mixer

Selecting this, or clicking the Groove button in the top bar, will show or hide the ReGroove Mixer.

Show/Hide Transport

Selecting this will show or hide the Transport Panel.

Show/Hide On-screen Piano Keys

Selecting this, or pressing [F4], will show or hide the floating On-screen Piano Keys window. See "On-screen Piano Keys" for information on how to use the On-screen Piano Keys window.

Show/Hide Spectrum EQ Window

Selecting this, or pressing [F2], will show or hide the Spectrum EQ Window. See "The Spectrum EQ Window" for more information.

Show/Hide Recording Meter

Selecting this, or pressing [Ctrl]+[F3], will show or hide the floating Recording Meter Window. See "The Recording Meter Window" for more information.

Show/Hide Missing Sounds Window

Selecting this brings up the Missing Sounds window. See "Handling Missing Sounds" for more information.

Application Zoom>

Select if you want to change the zoom level (size) of the entire Reason application. Choose the desired zoom level on the sub-menu, see "Application Zoom".

Options menu

Sync > Internal/MIDI Clock/Ableton Link/Send MIDI Clock

These four options are used to specify which type of tempo synchronization you want to use:

- **Internal**
  When this is activated, the program is not synchronized to any external source. It plays in the tempo set on the Transport Panel.
- **MIDI Clock**
  When this is activated, the program is synchronized to external MIDI Clock, as set up in the Settings|Sync dialog. The tempo setting on the Transport Panel is of no relevance; Reason plays in the tempo of the incoming MIDI Clock signals. See "Synchronization and Advanced MIDI" for more details.
- **Ableton Link**
  When this is activated, the program can be synchronized to other Ableton Link-enabled devices on the same wireless network. See "Synchronization using Ableton Link" for more details.
- **Send MIDI Clock**
  When this is activated, the program is MIDI Clock Sync host and can control external applications/equipment. See "Synchronization and Advanced MIDI" for more details.
- **Ableton Link: Synchronize Start/Stop**
  Use this if you are using Ableton Link and also want to synchronize Start and Stop.

Remote and Keyboard Control > Remote Override Edit Mode

All supported control surface devices have "standard remote mappings" for each Reason device. If you wish to override this standard mapping, you can do so in the following way:

1. **To get an overview of which parameters can be assigned remote overrides, select "Remote Override Edit Mode" from the Options menu.**
   Each device you select will show a blue arrow symbol beside every parameter that can be assigned a remote override. Standard mappings are marked with yellow knob symbols (only shown when the device has MIDI input). Assigned overrides are marked with a lightning bolt symbol.
2. **If you click on an assignable parameter to select it (selected parameters are orange in color), you can then select "Edit Remote Override Mapping..." from the Edit menu.**
   This opens a dialog where you can assign override mappings.
3. **Make sure that the "Learn from Control Surface Input" box is ticked.**
4. **Simply turn the knob (or slider etc.) that you wish to use to assign Remote Override for the parameter.**
   The "MIDI Received" field momentarily flickers as you turn the knob, and then the dialog shows the control surface device and the control you used.

You can also make override mappings manually:

- ▶ **Select a device from the Control Surface pop-up in the dialog, and then select a control from the Control pop-up.**
  On the Control pop-up, all the controls on the selected control surface are listed.

5. **Click "OK" to exit the dialog.**
   The selected parameter is now tagged with a lightning bolt symbol, indicating Remote Override mapping.
6. **To exit Remote Override Edit mode, deselect it from the Options menu.**
   You do not always have to use this method - see below.

If Remote Override Edit Mode is enabled on the Options menu, mapped parameters are "tagged", and the arrow indicators show the assignable parameters. In this mode, however, you cannot operate Reason normally. Remote Override Edit mode is primarily for overview of available parameters and the current assignments.



- **Another way to assign keyboard remote commands is to have "Remote Override Edit Mode" deselected on the Options menu, and to simply right-click (Win) or [Ctrl]-click (Mac) the parameter you wish to control.**
  This opens a pop-up menu, where one of the options will be "Edit MIDI Remote Override Mapping". Selecting this opens the "Edit Remote Override Mapping" dialog. Thus, you do not have to select Edit mode from the Options menu if you already know that a parameter is assignable.

See "Remote Override mapping" for more information.

Remote and Keyboard Control > Additional Remote Overrides...

Selecting this opens a dialog with remote functions that cannot be assigned using Remote Override Edit mode, such as switching target tracks, Undo/Redo etc.

See "Additional Remote Overrides..." for details.

Remote and Keyboard Control > Surface Locking...

This opens a dialog where you can lock a control surface to a specific device. This means that the locked device is always "tweakable", regardless of which track has MIDI input in the sequencer. This enables you to play and record notes for one device and at the same time control parameters for another device from a control surface.

For example, you could lock a control surface to control the main mixer, so you can always control overall levels while playing/tweaking other devices.

- **The Master Keyboard device cannot be locked!**
  If you ticked the Master Keyboard box on the MIDI tab in Settings, you can uncheck the "Master Keyboard" check box. You can then lock this control surface to a device and use its controllers to tweak parameters, but you will not be able to play the device.
- **Each control surface can be locked to one device at a time (but you can lock several control surfaces to the same device).**
  This locked device will always be controlled by the selected control surface, until you unlock the device or lock the surface to another device. You can lock as many devices you wish, as long as you have enough control surfaces.
- **Locked devices can use remote overrides, just like unlocked devices.**
  In other words, even if a device is locked to a control surface, some parameters could be overridden so they are controlled by another control surface, or some controls on the locked surface could be override-mapped to another device.

See the "Locking a surface" for more details.

Remote and Keyboard Control > Enable Keyboard Control

When this is activated, the computer's keyboard keys can be used to control devices, as set up with the Keyboard Control Edit feature. See "Editing Keyboard Control" for more information.

Remote and Keyboard Control > Keyboard Control Edit Mode

- **To get an overview of which parameters are keyboard controllable select "Keyboard Control Edit Mode" from the Options menu.**
  Each device you select will show a yellow arrow symbol next to every parameter that can be assigned.
- **If you click on an assignable parameter to select it, you can then select "Edit Keyboard Control Mapping" from the Edit menu.**
  This opens a dialog allowing you to select a key command for that parameter.

  You may use any key or a combination of [Shift] + any key.

▶ **Simply press the key (or key combination) you wish to use to remote control the parameter.**
The "Key Received" field momentarily indicates that it is "learning" the keystroke(s), and then the dialog displays the name of the key you have pressed. If [Shift] was used, the box beside the word Shift in the dialog is ticked.

You can also double-click on the arrow for an assignable parameter to set up keyboard control:

▶ **A rotating yellow rectangle appears, indicating Learn mode. Press the key (or key combination) you wish to use to remote control the parameter.**
The rotating stops and the rectangle will now display the key or key combination you used.

! **Note that the transport panel uses the numeric keypad for various commands. If you assign a parameter to a single numeric key, the corresponding transport functionality will be overridden!**

▶ **Another way to assign keyboard control commands is to have "Keyboard Control Edit Mode" deselected on the Options menu, and to right-click (Win) or [Ctrl]-click (Mac) the parameter you wish to keyboard control.**
This opens a pop-up menu, where one of the options will be "Edit Keyboard Control Mapping". Selecting this opens the Keyboard Control dialog. Thus, you do not have to enable/disable Edit mode from the Options menu if you know that a parameter is assignable.

! **If you try to assign a key control that is already in use, you will get an alert asking if you wish to change the current assignment.**

See "Editing Keyboard Control" for more information.

Rack Settings > Rack per Track

When the "Rack per Track" mode is selected, a separate Rack column is created for the devices of each audio or instrument track. This makes it easy to navigate and focus on one track at the time. See "Rack per Track mode" for more details.

Rack Settings > Auto-Group Devices

When the "Auto-Group Devices" mode is selected, all devices are shown in the same rack (although additional rack columns can be added manually). Devices that belong to the same Device Group are kept together (for example an instrument, its effects and its mix channels). See "Creating devices" for more details.

Rack Settings > No Grouping

When the "No Grouping" mode is selected, you can place and move individual devices completely freely in the Rack.

Rack Settings > Single Column Mode

This mode is available when the Rack is shown in a separate window, and Rack per Track mode is selected. When Single Column Mode is on, the Rack window shows a single rack column at a time, and sideways scrolling is disabled. This can also be turned on and off with the Single Column button at the top of the Rack window.

Rack Settings > Show CPU Load for Devices

Select "Show CPU Load for Devices" to have the devices in the rack display how much CPU they use, see "Checking processing power for individual devices".

Playback and Recording > Chase Notes During Playback

With this selected, the Sequencer plays back (re-triggers) notes even if you start the sequencer "in the middle" of notes. If de-selected, the Sequencer doesn't play back notes unless the song position pointer passes beginnings of notes.



Playback and Recording > Quantize Notes During Recording

When this option is turned on, MIDI notes will automatically be quantized when you record them. You can also turn this on or off with the Q Rec button on the Transport panel.

Playback and Recording > Record Automation into Note Clip

With this option activated, any device parameter automation will be automatically recorded into the note clips as "Performance Controllers" instead of on separate Parameter Automation Lanes.

Playback and Recording > Click

Select this, or press [C], or click the "Click" button on the Transport Panel, to activate the metronome click in the Sequencer.

Playback and Recording > Precount

Select this, or press [Cmd](Mac) or [Ctrl](Win) + [P], or click the "Pre" button on the Transport Panel, to activate the precount function of the metronome click in the Sequencer.

Number of Precount Bars

Here you select the number of precount bars to use when the "Pre" button on the Transport Panel is on. When you record in the sequencer with the "Pre" button active, the recording will begin after the set number of precount bars.

- **Select "One", "Two", "Three" or "Four" bars from the sub-menu that appears.**

Delay Compensation

Select "Delay Compensation" to activate the built-in delay compensation, see "Activating the Delay Compensation".

Manage VST Plugins...

Selecting this brings up the Manage Plugins window, where you can manage your VST plugins. See "Managing VST plugins".

Manage Rack Extensions...

Selecting this starts up the Reason Companion application, which displays the currently installed Rack Extension devices on your computer. Here you can also uninstall Rack Extension devices from your computer.

Enable Blocks

This enables the Blocks function in the Sequencer. See "Working with Blocks in the Sequencer".

Switch to Block View/Song View

This allows you to toggle the sequencer Arrangement between Blocks View and Song View.




Window menu (Windows version)

Stay on top

When this is activated, the Reason window will always stay on top of other program's windows.

Open Song Windows list

This lists all open song document windows. Selecting one makes it the active window. If songs have detached areas in separate windows, these will be included as separate items in the Open Documents list. The currently active window is indicated with a tick to the left of the window name:



In the picture above, the "AllAnalog.reason (Mixer)" window is the currently active window, and consequently the "AllAnalog.reason" song is the currently active song. The Mixer and Rack areas of this song are currently detached in separate windows. The asterisks (*) to the right of some of the windows show that the song currently contains unsaved edits.

Window menu (macOS version)

Here you will find all the standard macOS window handling functions

Open Song Windows list

This lists all open song document windows. Selecting one makes it the active window. If songs have detached areas in separate windows, these will be included as separate items in the Open Documents list. The currently active window is indicated with a tick to the left of the window name:



In the picture above, the “untitled 3” sequencer window is the currently active window, and consequently also the currently active song. The Mixer and Rack areas of this song are currently detached in separate windows and Minimized, as indicated by the symbols to the left. The round dots to the left of some of the windows show that the song currently contains unsaved edits.

Help menu

Reason Help...

This menu item opens up the on-line Help system in your default web browser. The Reason Help contains detailed information about all functions in Reason. You can choose to browse for information, either from the Table of Contents (TOC), or by using the Search box n the Help system.

Documentation in PDF format

This takes you to the support section at Reason Studios, where you can download manuals in pdf format.

Tutorials on the Reason Studios Website

Selecting this item will open up your default web browser and direct you to the Reason Video Tutorials page on the Reason Studios web site.

Go to the Reason Studios Website

Selecting this item will open up your default web browser and direct you the Reason Studios web site.

Check for Updates... (Windows only)

This checks for recent Reason updates on the Reason Studios server.

Open Reason Companion (Windows only)

This menu item launches the Reason Companion application, in which you can install Rack Extensions and Sound Packs (Reason+).

My Account (Windows only)

This menu item launches your default web browser and brings you to your products page on Reason Studios, where you can view your list of owned products, including download ReFills and Rack Extensions.

Get more Instruments, Sounds & Effects

This item starts up your default web browser and takes you to the Reason Studios Shop, where you can get more Rack Extension devices for your Reason rack and also purchase additional ReFills.

About Reason (Windows only)

This menu item opens up a dialog that informs you about the version of the program and the people behind it.



Chapter 77
Key Commands



About the Key Commands chapter

This chapter contains compiled lists of all keyboard shortcuts and modifier keys available in Reason - and in all Reason devices. Keyboard shortcuts are keys or combinations of keys that can be pressed to execute various functions. Modifier keys are keys that can be used in combination with the mouse, to execute additional functions.

! **In most cases, which key(s) to use is different on macOS and Windows. The keys to use are listed in the right column of the tables below, with the Mac key(s) to the left and the Windows key(s) to the right of the slash, i.e. [Mac key(s)]/[Windows key(s)].**

General keyboard shortcuts

Function	Key(s)
Show/Hide Main Mixer	[F5]
Show/Hide Rack	[F6]
Show Sequencer Only	[F7]
Show/hide Spectrum EQ Window	[F2]
Show/hide Device Palette	[F3]
Show Device Palette and set focus to the Text/Search field	[Shift]+[Command]/[Shift]+[Ctrl]+[F]
Show/hide Browser	[F9]
Show/Hide Recording Meter	[Command]/[Ctrl]+[F3]
Open Browser without Browse Focus	[Command]/[Ctrl]+[F]
Open Browser with Browse Focus for the selected device in the rack.	[Command]/[Ctrl]+[B]
Show/hide On-screen Piano Keys window	[F4]
Show/hide Edit Area	[F8]
Toggle Rack front/rear	[Tab]
Create new Song	[Command]/[Ctrl]+[N]
Open Song	[Command]/[Ctrl]+[O]
Save Song	[Command]/[Ctrl]+[S]
Save Song As	[Shift]+[Command]/[Shift]+[Ctrl]+[S]
Close active detached Rack or Mixer window	[Command]/[Ctrl]+[W]
Close Song (if the window containing the Sequencer is active)	[Command]/[Ctrl]+[W]
Import Audio File	[Command]+[Option]/[Shift]+[Ctrl]+[I]
Quit (macOS only)	[Command]+[Q]
Exit (Windows only)	[Alt]+[F4]
Undo	[Command]/[Ctrl]+[Z]
Redo	[Command]/[Ctrl]+[Y]
Delete Devices and Tracks	[Del] or [Backspace]
Delete Devices and Tracks (without warning).	[Command]/[Ctrl]+[Del] or [Command]/[Ctrl]+[Backspace]
Duplicate Devices and tracks, or selected clip(s), or selected comp row(s) in open audio clips, or selected note(s) in note clips, or selected automation point(s) in automation clips.	[Command]/[Ctrl]+[D]
Select All	[Command]/[Ctrl]+[A]
Route to > New Output Bus	[Command]/[Ctrl]+[G]
Create Audio Track	[Command]/[Ctrl]+[T]
Create Instrument	[Command]/[Ctrl]+[I]
Create Instrument (Windows only)	[Insert]

Function	Key(s)
Create Effect	[Command]/[Ctrl]+[E]
Create Mix Channel	[Command]+[Shift]/[Ctrl]+[Shift]+[M]
Open Browser without Browse Focus	Command]/[Ctrl]+[F]
Browse Patches for selected device.	[Command]/[Ctrl]+[B]
Toggle the “Hide Cables” option	[K]
Toggle the “Auto-group Devices and Tracks” option	[Command]+[Shift]/[Ctrl]+[Shift]+[G]
Toggle the “Follow Song” option	[F]
Toggle the “Keep Events in Clip While Editing” option	[Shift]+[Command]/[Shift]+[Ctrl]+[K]
Toggle the Show Block/Song View option (when Blocks are on)	[B]
Hide Reason (macOS only)	[Command]+[H]
Minimize Reason (macOS only)	[Command]+[M]
Open Settings (macOS only)	[Command]+[,]
Cut Track & Device (track selected in Track List), Cut Clip or Event (depending on current selection).	[Command]/[Ctrl]+[X]
Copy Track & Device (track selected in Track List), Copy Clip or Event (depending on current selection).	[Command]/[Ctrl]+[C]
Paste Track & Device, Paste Clip or Event.	[Command]/[Ctrl]+[V]
Open Help	[Command]+[?]/[F1]
Switch to one of the 10 corresponding global Remote variations (or "keyboard shortcut variations").	[Command]+[Option]/[Ctrl]+[Alt]+[1]...[0]

General modifier keys

Function	Key/Action
Duplicate (copy) the selected item and its corresponding components.	[Option]/[Ctrl]+drag and drop device/track/mixer channel
Disable auto-routing when creating device.	[Shift]+Create device
Disable rerouting when moving device in the rack.	[Shift]+move device
Fold/unfold all devices.	[Option]/[Alt]+Fold/unfold device
Fold/unfold all tracks.	[Option]/[Alt]+Fold/unfold track
Select multiple devices/tracks/channels	[Command]/[Ctrl]+Select
Select range of multiple devices/tracks/channels	[Shift]+Select
Select multiple clips/events in the Sequencer	[Shift]/[Ctrl]+Select (Windows only: [Shift]+Select to select a range of clips/events on a single Lane in the Sequencer)
Increase precision when making settings.	[Shift]+Move fader/knob
Reset parameter to default value.	[Command]/[Ctrl]+Click fader/knob
Prevent creation of Sequencer-track for devices that normally will get a track. Create Sequencer-track for devices that normally will *not* get a track.	[Option]/[Alt]+Create device
Create a parameter automation lane for the parameter.	[Option]/[Alt]+Click device fader/knob/button

Transport keyboard shortcuts

Function	Key(s)
Play	Numeric keypad [Enter]
Stop, Go to start position, Go to start of Song.	[Shift]+[Return] or numeric keypad [0]
Go to start of Song	[,]/[.] on numeric keypad



Function	Key(s)
Toggle Stop/Play	[Spacebar]
Record	[Command]/[Ctrl]+[Return] or numeric keypad [*]
Rewind	Numeric keypad [4]
Fast Forward	Numeric keypad [5]
Go to Loop Start	[Option]/[Alt] and left arrow key. Numeric keypad [1]
Go to Loop End	[Option]/[Alt] and right arrow key. Numeric keypad [2]
Move forward one Bar	Numeric keypad [8]
Go back one Bar	Numeric keypad [7]
Tempo Up	Numeric keypad [+]
Tempo Down	Numeric keypad [-]

Sequencer keyboard shortcuts

Function	Key(s)
Show/hide Edit Area.	[Shift]+[Tab] *or* [Command]/[Ctrl]+[E]
Toggle Song/Blocks view (only if Enable Blocks is selected on the Options menu).	[B]
Select Arrow tool.	[Q]
Select Pencil tool.	[W]
Select Eraser tool.	[E]
Select Razor tool.	[R]
Select Mute tool	[T]
Select Magnifying Glass tool.	[Y]
Select Hand tool.	[U]
Open selected clip for editing	[Return]
Close open clip	[Esc]
Quantize	[Command]/[Ctrl]+[K]
Duplicate Track & Device (device or track selected).	[Command]/[Ctrl]+[D]
Join selected Clips on the same lane - or join selected notes on the same note#	[Command]/[Ctrl]+[J]
Merge Note Lanes on Tracks.	[Command]/[Ctrl]+[R]
Move selected tracks to new Track Folder	[Command]+[Shift]/[Ctrl]+[Shift]+[T]
Mute/Unmute selected Clips or selected Notes in an open Note Clip.	[M]
Snap on/off.	[S]
Toggle Metronome click on/off	[C] or numeric keypad [9]
Toggle Metronome Pre-count on/off	[Command]/[Ctrl] and [P]
New Dub	[,] or numeric keypad [3]
New Alt	[.] or numeric keypad [6]
Loop on/off	[L] or numeric keypad [/]
Set Loop Locators to encompass all selected clips	[Command]/[Ctrl]+[L]
Set the Left and Right Loop Locators to encompass selected clips and start playback in Loop Mode.	[P]
Crossfade selected (partly) overlapping audio clips	[X]
Split selected Clips at the Song Position Marker	[Option]/[Alt]+[X]
Transpose selected notes up/down in octave steps	[Shift]+[Command]/[Shift]+[Ctrl] and up/down arrow keys
Minimize/Restore the height of selected tracks	[Option]/[Alt]+[M]

Function	Key(s)
Move Loop range one bar to the left	[Option]/[Alt]+[Shift] and up arrow key
Move Loop range one bar to the right	[Option]/[Alt]+[Shift] and down arrow key
Move current Loop range one loop length to the left.	[Option]/[Alt] and arrow up key.
Move current Loop range one loop length to the right.	[Option]/[Alt] and arrow down key.
Horizontal zoom in	[H] or [Command]/[Ctrl]+[+]
Horizontal zoom out	[G] or [Command]/[Ctrl]+[–]
Vertical zoom in	[Command]+[Option]/[Ctrl]+[Alt]+[+]
Vertical zoom out	[Command]+[Option]/[Ctrl]+[Alt]+[–]
Zoom To Selection/Show All (e.g. selected clips)	[Z] (horizontal only), [Shift]+[Z] (horizontal and vertical)
Follow Song on/off (auto-scrolling in Arrange/Edit panes)	[F]

Sequencer keyboard shortcuts in Audio Edit Mode

Function	Key/Action
Select Speaker tool	[I]
Change Comp Row assignment in the segment with focus in Comp Mode	[Command]+[Option]+[Shift]/[Ctrl]+[Alt]+[Shift] and up/down arrow keys
Change segment focus in Comp Mode.	[Command]+[Option]+[Shift]/[Ctrl]+[Alt]+[Shift] and left/right arrow keys
Exit Slice Edit mode for Single Take audio clips	[Esc] or [Return]
Correct note pitch(es) in Pitch Edit Mode.	[Shift]+[Cmd]/[Shift]+[Ctrl]+[C]

Sequencer modifier keys

Function	Key/Action
Select alternate tool in Toolbar	[Command]/[Alt]
Toggle Pencil/Line tool (velocity edit lane only).	[Option]/[Ctrl]
Edit velocity of selected notes only	[Shift]+click/draw with Pencil tool on Velocity lane
Create automation lane for parameter. If device has no track, a track will also be created.	[Option]/[Alt]+Click knob/fader/button
Add automation event exactly on the automation line	[Shift]+click with Pencil tool in the open automation clip.
Restrict movement direction to either horizontal or vertical.	[Shift]+Move events/clips
Zoom in/out horizontally on the Edit/Arrange pane.	[Shift]+Drag any of the Song Navigator handles sideways
Zoom in/out horizontally on the Edit/Arrange pane. (Drag sideways to scroll horizontally at the same time)	[Shift]+Drag up/down in Song Navigator frame
Copy data instead of moving it.	[Option]/[Ctrl]+Move data
Set Left Locator in ruler.	[Option]/[Ctrl]+Click
Set Right Locator in ruler.	[Command]/[Alt]+Click
Set End Marker in ruler.	[Shift]+Click
Switch to zoom out with the Magnifying Glass tool instead of zoom in (with either the Magnifying Glass- or the Hand tool selected).	[Option]/[Ctrl]+Click
Limit movement to one direction only. Horizontal or vertical.	[Shift]+Drag with Hand tool or Eraser tool
Disable vertical zooming. Horizontal zoom only.	[Shift]+Zoom with Magnifying Glass tool

Sequencer modifier keys with mouse wheel

Function	Key/Action
Scroll horizontally.	[Shift]+Mouse wheel
Zoom in/out horizontally.	[Command]/[Ctrl]+Mouse wheel
Zoom in/out vertically.	[Shift]+[Command]/[Shift]+[Ctrl]+Mouse wheel

Sequencer modifier keys in Audio Edit Mode

Function	Key/Action
Switch from Arrow tool to Cut (Razor) tool on the comp rows in an open audio clip	[Command]/[Altl]
Switch from Arrow tool to Speaker tool on the comp rows in an open audio clip	[Command]+[Shift]/[Alt]+[Shift]
Duplicate the Comp Row and create a new Cut or Segment in the duplicated Comp Row.	[Command]+[Option]/[Ctrl]+[Alt] and click or swipe on Comp Row
Fine-tune notes in Pitch Edit mode.	[Shift]+[Command]/[Shift]+[Alt]-drag notes up/down on the note pane.

Arrow keys

Function	Key/Action
Select next device up or down (rack selected), select next track up or down (track list selected), select clip on next/previous lane (Arrange view selected).	Arrow up/down keys
Select items in the Browser Item List	Arrow up/down keys
Select next/previous clip on lane (Arrange view selected), select next/previous value field (Position displays).	Arrow left/right keys
Nudge selection one Snap unit back/forward in the sequencer.	[Command]/[Ctrl]+Arrow left/right keys
Nudge selection one Beat back/forward in the sequencer.	[Shift]+[Command]/[Shift]+[Ctrl]+Arrow left/right keys
Nudge selection one Tick back/forward in the sequencer.	[Option]+[Command]/[Alt]+[Ctrl]+Arrow left/right keys
Transpose selected notes in Edit mode	[Command]/[Ctrl]+ up/down arrow keys

Save dialog keyboard shortcuts

These key commands can be used in the save dialog that appears if you close a song that contains unsaved changes:

Function	Key(s)
Cancel	[Command]+[.]/[Esc]
Yes (save song)	[Return]/[Y]
No (do not save song)	[Command]+[D]/[N]

On-screen Piano Keys keyboard shortcuts

These shortcuts are valid only when the On-screen Piano Keys window is open and set to “Computer Keys”:

Function	Key(s)
Sustain	[Shift]
Octave Down	[Z]
Octave Up	[X]
Velocity value = 1	[1]
Velocity value = 14	[2]
Velocity value = 28	[3]
Velocity value = 42	[4]



Function	Key(s)
Velocity value = 56	[5]
Velocity value = 70	[6]
Velocity value = 84	[7]
Velocity value = 98	[8]
Velocity value = 112	[9]
Velocity value = 127	[0]

NN-19 modifier keys

Function	Key/Action
Audition sample.	[Option]/[Alt]+Click in keyboard display
Edit selected sample	[Option]/[Alt]+Click the Start Sampling button

NN-XT keyboard shortcuts

Function	Key(s)
Remove zone(s) from key map.	[Delete] or [Backspace]
Select All Zones	[Command]/[Ctrl]+[A]
Copy selected Zone(s)	[Command]/[Ctrl]+[C]
Paste currently copied Zone(s)	[Command]/[Ctrl]+[V]

NN-XT modifier keys

Function	Key/Action
Audition sample. In sample column, at root pitch and unprocessed. In keyboard column, at corresponding pitch and with processing applied.	[Option]/[Alt]+Click in sample column or keyboard column
Set root note of sample with edit focus.	[Command]/[Ctrl]+Click in keyboard column
Edit selected sample	[Option]/[Alt]+Click the Start Sampling button

Dr. Octo Rex keyboard shortcuts

Function	Key(s)
Cut Loop.	[Command]/[Ctrl]+[X]
Copy Loop.	[Command]/[Ctrl]+[C]
Paste Loop.	[Command]/[Ctrl]+[V]

Dr. Octo Rex modifier keys

Function	Key/Action
Audition slice.	[Option]/[Alt]+Click slice in overview
Reset slice(s) to default parameter value in Slice Edit Mode	[Command]/[Ctrl]+ click/click and drag in overview.

Redrum keyboard shortcuts

Function	Key(s)
Cut Pattern.	[Command]/[Ctrl]+[X]
Copy Pattern.	[Command]/[Ctrl]+[C]
Paste pattern.	[Command]/[Ctrl]+[V]
Shift Pattern Left.	[Command]/[Ctrl]+[J]
Shift Pattern Right.	[Command]/[Ctrl]+[K]
Randomize Pattern.	[Command]/[Ctrl]+[R]
Alter Pattern.	[Shift]+[Command]/[Shift]+[Ctrl]+[P]

Redrum modifier keys

Function	Key/Action
Enter “Hard” note when programming Pattern.	[Shift]+Click Pattern Step button
Enter “Soft” note when programming Pattern.	[Option]/[Alt]+Click Pattern Step button
Edit selected sample	[Option]/[Alt]+Click a Start Sampling button

Kong modifier keys

Function	Key/Action
Audition slice in Nurse Rex.	[Option]/[Alt]+Click slice in overview
Toggle “Trig” for slice(s) in Nurse Rex	[Command]/[Ctrl]+ click in overview.
Edit selected sample	[Option]/[Alt]+Click the Start Sampling button in NN-Nano

Matrix keyboard shortcuts

Function	Key(s)
Cut Pattern.	[Command]/[Ctrl]+[X]
Copy Pattern.	[Command]/[Ctrl]+[C]
Paste Pattern.	[Command]/[Ctrl]+[V]
Shift Pattern Left.	[Command]/[Ctrl]+[J]
Shift Pattern Right.	[Command]/[Ctrl]+[K]
Shift Pattern Up.	[Shift]+[Command]/[Shift]+[Ctrl]+[U]
Shift Pattern Down.	[Shift]+[Command]/[Shift]+[Ctrl]+[D]
Randomize Pattern.	[Command]/[Ctrl]+[R]
Alter Pattern.	[Shift]+[Command]/[Shift]+[Ctrl]+[P]

Matrix modifier keys

Function	Key/Action
Allows you to draw lines and ramps.	[Shift]+Draw Key/Curve values
Temporarily toggle Tie mode on/off.	[Shift]+Draw Gate



RPG-8 keyboard shortcuts

Function	Key(s)
Shift Pattern Left.	[Command]/[Ctrl]+[J]
Shift Pattern Right.	[Command]/[Ctrl]+[K]
Randomize Pattern.	[Command]/[Ctrl]+[R]
Alter Pattern.	[Shift]+[Command]/[Shift]+[Ctrl]+[P]

MIDI Out Device keyboard shortcuts

Function	Key/Action
MIDI: Send All Notes Off	[!]

Europa modifier keys

Function	Key/Action
Add/remove Envelope points.	[Command]/[Ctrl]+Click in the Envelope display
Freehand drawing of Envelope curves in “Edit Y-Pos” mode.	[Command]/[Ctrl]+Click in the Envelope display
Erase points in “Edit Y-Pos” mode.	[Shift]+[Command]/[Shift]+[Ctrl]+Drag in the Envelope display

Grain modifier keys

Function	Key/Action
Add/remove Envelope points.	[Command]/[Ctrl]+Click in the Envelope display
Freehand drawing of Envelope curves in “Edit Y-Pos” mode.	[Command]/[Ctrl]+Click in the Envelope display
Erase points in “Edit Y-Pos” mode.	[Shift]+[Command]/[Shift]+[Ctrl]+Drag in the Envelope display

Sweeper modifier keys

Function	Key/Action
Add/remove Envelope points.	[Command]/[Ctrl]+Click in the Envelope display
Freehand drawing of Envelope curves in “Edit” mode.	[Command]/[Ctrl]+Click in the Envelope display
Erase Envelope points in “Edit” mode.	[Shift]+[Command]/[Shift]+[Ctrl]+Drag in the Envelope display

Mimic modifier keys

Function	Key/Action
Set Start Marker	Double click in the Waveform Display
Set End Marker	[Shift]+Double click in the Waveform Display
Preview Sample	[Option]/[Alt]+Click and hold in the Waveform Display
Set Loop Point (when Loop is active)	[Command]/[Ctrl]+Click in the Waveform Display
Set Root Note	[Shift]+Click a key in the Note/range indicator
Edit selected sample	[Option]/[Alt]+Click the Start Sampling button



Index



A

Ableton Link 659
Active Inputs (Settings) 1531
Active Outputs (Settings) 1531
Add Audio Track (Create Menu Item) 1543
Add Effect... (Create Menu Item) 1543
Add Instrument... (Create Menu Item) 1543
Add Labels To Clips 198, 1521
Add Long-Term Authorization 37
Add Mix Channel (Create Menu Item) 1543
Add Player... (Create Menu Item) 1543
Additional Remote Overrides... 649
    Assigning 650
Adjust Alien Clips to Lane 196, 1521
ADSR 1109
Advanced MIDI (Hardware Interface) 661
Advanced MIDI Device (Hardware Interface) 676
Alien Clips 196
All Locations (Location in Browser) 460
All Notes Off (MIDI) 879
Alligator 1162
    Dry Ducking 1170
    Effects 1168
    Filters 1166
    Mix Controls 1170
    Patterns 1164
Allround (Stretch and Transpose Type) 229
Alt
    On Audio Tracks 162
    On Instrument Tracks 173
Alt Button (Transport Panel) 135
Alt Group (Dr. Octo Rex) 688
Alter
    Pattern (Redrum) 1070
    Pattern (RPG-8) 1494
Alter (Note Pitches) (in Edit Area Inspector) 308
Alter Pattern (Matrix) 1461
Alternate Tools 129
Analyzer 506
Anchor Point (ReGroove Mixer) 617
Appearance (Cables) 479
Application Zoom 47, 1545
Arpeggio Notes to Track 1516
Arrange Area Inspector 138
ASIO Control Panel 665
Ask before changing audio clip mode or stretch type 1524
Assigned Samples 607
Audio
    Formats 578
    Importing to Sequencer Track 579
    Quantizing 239
Audio Clipping 84
Audio Clips
    Adding Crossfades 264
    Adding Cuts 263
    Adding Segments 264
    Bounce Clip to REX Loop 240
    Bounce Clip(s) to New Recording(s) 267
    Bounce Clip(s) to New Sample 272
    Changing Comp Row Assignments 266
    Comping 268
    Deleting Cuts 265
    Editing Fades 187, 189
    Editing Levels 187, 189
    Importing Audio to... 581
    Joining 203
    Moving Cuts 265
    Normalising 274
    Opening 231
    Quantizing 239
    Reversing 275
    Scale to Tempo 276
    Transpose Display (Inspector) 187
    Transposing 277
Audio Device (Settings) 1530
Audio Hardware 80
Audio In (to Application) 80
Audio Input List (Audio Tracks) 118
Audio Levels 84
Audio Out (from Reason) 80
Audio Quality 81
Audio Settings 81
Audio To MIDI Conversion 273
Audio Track Channel Strip 491
Audio Track Device 491
Audio Tracks
    Creating 108
    Monitoring 158
    Mono or Stereo 108, 157
    Record Enabling 151
    Recording 161
        From Mix Channels 164
        In Loop Mode 161
        Mixdown 166
        Over Existing Clips 163
    Recovering 574
    Selecting Audio Inputs 157
    Setting Input Levels 158
    Setting Up 157
Audiomatic Retro Transformer 1176
Auditioning Audio (in Audio Overview Edit Mode) 232
Author (Editing in Browser) 466
Authorizing Reason 36

Auto-group Devices 372
Auto-Group Devices (Rack Settings) 358
Auto-group Devices and Tracks 370
Automap Samples 997, 1510
Automap Zones 964, 1513
Automap Zones Chromatically 1514
Automation
  Creating Curves 324
  Deleting Events 324
  Drawing Events 323
  Editing 320
  Editing in the Edit Area 322
  Editing in the Song/Block View 320
  Matching 337
  Showing in Device Panels 1525
  Tempo 331
  Time Signature 333
    Deleting Clips 334
    Moving, Resizing and Duplicating Clips 334
Automation As Perf Ctrl 176
Automation Cleanup 327, 1525
  About 327
  In Settings 327
Automation Clips
  Opening 286
Automation Override Reset 179
Auto-route Device 483
Auto-routing 481
  Audio Input Signals 481
  CV/Gate Signals 483
  Effect Devices 482
  Instrument Devices 482

B

Back Panel (Rack) 485
Bank Select (MIDI Out Device) 880
Bars
  Inserting (in the Sequencer) 216
  Removing (in the Sequencer) 216, 217
Beat Map (Player) 386
BELL mode (EQ in the Main Mixer) 506
Big Waveform Zoom Mode 60
Bipolar Curves (Matrix) 1458
Blend (Pulveriser) 1256
Block Automation Clips
  Combining with Song Clips 351
  Converting to Song Clips 349
  Creating 344
  Muting Lanes in... 347
  Resizing 346
Blocks
  Coloring 343
  Defining Length of... 343
  Overview 341
  Renaming 343
  Selecting for Editing 342
Bounce
  Audio Clips 586
  Mixer Channels 584
Bounce Audio Clips To MIDI 273
Bounce Clip to Disk 586
Bounce Clip to REX Loop 240
Bounce Clip(s) to New Recording(s) (Audio Clips) 267
Bounce Clip(s) to New Sample (Audio Clips) 272
Bounce in Place 205
Browse Loops 1509
Browse Patches 1508
Browse Samples 1509
Browser
  Browse Focus 459
  Indexing 453
  Open and Close 452
  Using 450
Browsing Starts in Default Sound Folder (for New Devices) (Settings) 446
Buffer Size
  Settings 82
  Slider 665
Buffer Size (Settings) 1532
Bus FX Parameter 1 & 2 841
Bypass/On/Off Switch (on Effect Devices) 1390

C

Cables
  Appearance 479
  Automatic Routing 481
  Checking Connections 480
  Color 481
  Connecting by Dragging 486
  Connecting using Pop-up Menus 486
  Disconnecting 487
  Hiding and Showing 479
  Manual Routing 485
  Scroll to Connected Device 480
Calc (Audio Stretching) 237
Calc Indicator 332, 578, 583
Catch Zone Size (Neptune) 1233
Categories (Editing in Browser) 466
Categories Buttons (in Browser) 464
CC Assign (MIDI Out Device) 880
CF-101 Chorus/Flanger 1393
Channel 8 & 9 Exclusive 1075

Channel Color 500, 1521
Channel Dynamics 1199
Channel EQ 1205
Chase Notes During Playback 134
Chop Clips to 201
Chorus 1393
Chunk Trig (Kong) 831
Cleanup Automation 327
Clear All Keyboard Remote 1523
Clear Insert FX 521
Clear Keyboard Control Mapping 1523
Click
  Button 133
  Level 132, 154
Click and Pre-count 154
Clip Color 198, 1521
Clip Level Handle (Audio Clips) 252
Clip Overview
  Audio Clips 242, 251
Clipping (Audio) 84
Clips
  About Overlapping... 197
  Adjust Alien Clips to Lane 196
  Alien 196
  Coloring 198
  Creating 186, 291
  Cropping 1521
  Cut, Copy and Paste 197
  Deleting 189
  Duplicating 197
  Duplicating Parts of Clips 200
  Joining 202, 1520
  Length Display 187
  Level and Fades in Audio Clips 188
  Looping 210
  Masking Recordings or Events in... 191
  Match Values 208
  Moving 195
  Muting 204, 1520
  Naming 198, 1521
  Nudging 195
  Position Display 187
  Remove Clip Name 198
  Renaming 198
  Repeating 198
  Resizing 190
    Note Clips in the Edit Area 289
  Scaling Tempo 193
  Selecting 186
    Multiple 187
  Selecting with the Arrow Keys 188
  Splitting 199
Clock Source (Settings) 1531
Close (Songs) 568, 1501
Close Button (In Pitch Editor) 242
Cloud Folders (Settings) 1528
Combi Patches 1414
Combinator 1413
  Adding Devices 1419
  Bypass FX 1427
  Combining Devices 1416
  Creating 1416
  Creating by Browsing Patches 1416
  Creating New Devices 1419
  CV Connections 1438
  External Routing 1418
  Key 1429
  Key Mapping 1429
  Run 1427
  Select Backdrop 1423
  Setting Negative Parameter Ranges 1436
  Setting the Source Range 1436
  Setting Velocity Ranges for Devices 1431
  Uncombining Devices 1421
  Using Modulation Routing 1432
  Using the Editor 1429
Commit to Groove 627, 1519
Comp Clips in the Comp Editor (Audio Clips) 253
Comp Row 252, 254
  Adjusting Level 261
  Adjusting Recording Offset 262
  Cut, Copy and Paste 261
  Deleting 259
  Duplicating 260
  Level Matching 281
  Moving 260
  Selecting in a Single Take clip 258
  Selecting in Comp Mode 259
  Transpose Matching 281
Comp Row Handle (Audio Clips) 252
Comp Row Level Fader (Audio Clips) 252
Comp Rows
  Transpose 278
Comp-01 Compressor 1411
Compatible EQ (Mixer 14-2) 1468
Comping Audio 268
Compressor (Kong) 843
Computer (Location in Browser) 462

Context Menus 68
For Channels Strips 69
For Devices 69
For Parameters 68
For the Main Mixer 70
For the Rack 70
For the Sequencer 70
Control Panel (Settings) 1531
Controller Lane Selector 288
Convert Pattern Automation to Notes 331
Matrix 1462
Redrum 1071
Convolution Algorithm (RV7000 Mk II) 1305
Copy Channel Settings 499
Copy Devices and Tracks 377
Copy Loop to Track 1514
Copy Loop To Track (Dr. Octo Rex) 685
Copy Original Channel Settings 586
Copy Parameters to Selected Zones 1512
Copy Patch 449
Copy Pattern 1455
Copy Pattern to Track 1515
Matrix 1462
Redrum 1071
Copy Zones 954
Correction Speed (Neptune) 1234
Create Audio Track 108
Create Button (in Browser) 241
Create Instrument 458
Create Menu 1543
Create Send FX 523
Create Track for... 1516
Create Velocity Crossfades 1514
Crop (Edit Sample Window) 602
Crop Events to Clips 1521
Cross-browsing
Samples and REX files 458
Cross-Browsing Patches 455
Crossfade Loop 606
Crossfades (Audio Clips) 271
Adding 264
Matching 281
Curve (Matrix) 1458
About 1452
Curved Automation 324
Cut Crossfade Zones (Audio Clips) 253
Cut Devices and Tracks 377
Cut Handles (Audio Clips) 254
Cut Lines (Audio Clips) 254
Cut Pattern 1455
Cut Row (Audio Clips) 253
Cut Tool (Audio Clips) 127, 257
Cuts
Adding (Audio Clips) 263
Deleting (Audio Clips) 265
Moving (Audio Clips) 265
CV
About 478
Merging 1397
Routing 488
Splitting 1400
Trim Knobs 488
vs. Gate 1458

D

D-11 Foldback Distortion 1403
DDL-1 Delay Line 1392
Decay/Gate Switch 1073
Default Song 568, 1529
Delay 1392
The Echo 1380
Delay Compensation 550
Using 554
Delete Events Outside Clips 193
Delete Track for... 1516
Delete Unused Recordings (Audio Clips) 272
Delete Unused Samples 995
Demo Mode 39
Demo Songs
Opening 567
Device Groups
About 372
Cut, Copy and Paste 377
Duplicating 376
Device Palette 47, 361
Assigning Tags to Devices 367
Filtering 364
Filtering on Categories 365, 366
Hiding Devices 368
In Rack Window 361
Show/Hide Device Types 362
Using Tags 366

Devices
Creating 369
By Browsing Patches 454
Cut, Copy and Paste 377
Deleting 374
Deleting with their Tracks 113
Device Groups 372
Disconnecting 487
Duplicating 376
Duplicating and Copying with their Tracks 114
Folding/Unfolding 64, 378
Moving to a New Rack Column 375
Naming 377
Re-ordering and Rerouting in the Rack 374
Replacing 376
Routing 481
Routing Master Keyboard Input to 373
Selecting 372
Diffusion (The Echo) 1383
Direct Out (on Mix Channel and Audio Track Devices) 544
Dirt (Pulveriser) 1252
Disable Stretch (Audio Clips) 332
Disconnect
Cables 487
Device 483, 487
Distortion
D-11 1403
Scream 4 1312
Dither (Audio Export) 582, 587
Document Window 46
Navigating in the... 54
Dr. Octo Rex
About 680
Adding REX Loops 683
Copy Loop To Track 685
Editing Slices 687
Panel Parameters 693
Playing from Sequencer 685
Playing REX Loop Slices 684
Playing REX Loops 682
Dr.Rex Loops
Opening in Dr. Octo Rex 681
Drift (Vocal Edit Mode) 250
Drum Assignment (Kong) 815
Drum Edit View Mode (Note Clips) 290
Drum Output (Kong) 820
Drum Room Reverb (Kong) 842
Dual Arpeggio (Player) 394
Dub
On Instrument Tracks 172
Dub Button (Transport Panel) 135
Ducking
Alligator 1170
The Echo 1386
Duplicate Devices and Tracks 376, 1506
Dynamics 1067

E

E button (EQ in the TTM Mixer) 505
Easy MIDI Inputs 635
ECF-42 Envelope Filter 1404
Edit Area
For Automation Clips 284
For Note Clips 284
Edit Clip Name 198
Edit Focus 512
Edit Info (Browser) 467
Edit Menu 1505
Edit Remote Override Mapping 646
Editing
Buttons 63
Buttons (Multi Mode) 64
Display Values 65, 66
Faders and Sliders 63
Knobs 63
Editing Velocity 309
Effect Combi Patches 521
Effects 361
Recording with... 545
Empty (Default Song) 1529
Enable Blocks 1549
Enable Keyboard Control (Remote) 651
Enable Loop Playback (Dr. Octo Rex) 692
Enable Pattern Section 1071
Enable Pattern Section (Redrum) 1069
Envelope Controlled Filter 1404
Envelopes 1109
EQ
Main Mixer 505
Mixer 14-2 1467
Parametric 1412
RV7000 Mk II Advanced Reverb 1308
Eraser Tool 126
Europa Shapeshifting Synthesizer 703
Exit (Windows) 1504
Exit and Log out (Windows) 1504
Explode 314
Export Device Remote Info 1504
Export Loop as Audio File 582
Export MIDI File 575, 1503
Export REX as MIDI File 1504
Export Song as Audio File 582
Ext Mod (Subtractor) 1117
External Effect (Kong) 850
External Sync Offset 657

F

Fade Handles (Audio Clips) 252
Fade In/Out (Edit Sample Window) 603
Fade In/Out Displays (Audio Clips) 187
Fade In/Out Handles (Audio Clips) 189
Fast Forward Button (Transport Panel) 134
Favorite Lists (Location in Browser) 461
FFT (Vocoder) 1182
File Formats 474
Filter
- Dr. OctoRex 695
- Effect Device 1404
- Malström 859
- NN-19 999
- NN-XT 977
- Pulveriser 1253
- Subtractor 1104

Filter (Kong) 844
Filters To Dynamics Sidechain (Main Mixer) 503
Find Device (Create Menu Item) 1543
Find in Browser (Create Menu Item) 1543
Fine-Tune (Vocal Edit Mode) 249
Flam (Redrum) 1068
Flanger 1393
Flip Rack 379, 485, 1544
FM 1102
Folding/Unfolding Device Panels 64
Follow Selection (in Spectrum EQ) 507
Follow Song 95
Follower (Pulveriser) 1255
Formant (Neptune) 1238
Formant (Vocal Edit Mode) 250
Freezing Pitch Adjustments 1247

G

Gain Knob (Main Mixer) 501
Gain Reduction CV Out (Main Mixer) 504
Gain Tool 1441
Gate
- About 478
- Programming in Matrix 1457
- Routing 488
- vs. CV 1458

Gate (Alligator) 1162
Gate (Matrix) 1452
Gate (RV7000 Mk II Advanced Reverb) 1309
Gate mode (Redrum) 1073
Get Groove From Clip 1520
Global Shuffle 618
Go To Left/Right Locator (Transport Panel) 136
Go to Product Page... 1523
Go To Track for... 1517
Grain Sample Manipulator 739
Groove
- Assigning to Note Lanes 625
- Committing to 1519
- Creating from Clips 629
- Extracting 1520
- Factory Patches 631
- Making Permanent 627
- Mixer Parameters 617
- Settings 622

Group Selected Zones 1513
Groups
- NN-XT 954

H

Hand Tool 128
Hardware Device 80
Hardware Interface 674
Help 1552
Help Menu 1552
Hide Browser 1545
Hide Cables 479, 1544
Hide Cables function 1525
Hide Device Palette 1544
Hide Edit Area 1545
Hide On-screen Piano Keys 1545
Hide Recording Meter 1545
- Windows Version 1545

Hide ReGroove Mixer 1545
Hide Spectrum EQ Window 1545
Hide Transport Panel 1545
Hides All Cables 480
Hides Auto-Routed Cables 480
High Quality Interpolation
- NN-XT 941
- Redrum 1076

Hit Type (Kong) 816
Humana Vocal Ensemble 771
Hyper-threading 1533

I

ID8 Instrument Device 790
- Controlling Sounds 791
- Selecting Sounds 791

Import Audio File... 579
Import MIDI File 574
Improved EQ (Mixer 14-2) 1468
Impulse Response Samples
- Loading 1306
- Sampling Your Own 1307

Indexing (Browser) 453
Info Area (Browser) 470
Init Patch
- Kong 814

Init patch
Redrum 1063
Subtractor 1096
Input Focus Button (Hardware Interface) 658
Input Latency (Settings) 1532
Input Level
Setting for Audio Track 158
Input Meter (Audio Tracks) 118
Input Meter (Effect Devices) 1390
Insert Bars Between Locators 216, 1517
Insert FX
Adding 520
Copying Between Mixer Channels 522
Deleting 521
Inspector
Audio Editing in the... 279
Automation Editing in the... 335
Note Editing in the... 335
Inspector (Arrange Area) 138
Instrument Tracks
Creating 109
Record Enabling 152
Setting Up 170
Instruments
Creating 458
Interpolation
Dr. OctoRex 700
Invert
Pattern (RPG-8) 1494

J

Join Clips 202, 1520

K

Keep Events in Clip While Editing 294, 301, 302, 303
Keep Events in Clip while Editing 1524
Keep Pitch (The Echo) 1382
Key Commands
Syntax in Manual 35
Key Edit View Mode (Note Clips) 289
Key Maps
NN-19 994
NN-XT 951
Key Zones
NN-19 992
NN-XT 937
Keyboard Control (Remote) 651
Editing 651
Keyboard Control Edit Mode (Remote) 651, 1547
Keyboard Shortcuts
Transport Panel 137
Keyboards (MIDI) 1535
Keys (Matrix) 1452
Kit Patches 812
Kit Patches (Kong) 812
Klang Tuned Percussion 793
Knobs 63
Kong 812
Copying and Pasting Drums 816
MIDI Note Assignment 813

L

Lag (Pulveriser) 1254
Lanes
Adding/Creating 121
Deleting 123
Muting 125
Latency 88
Compensation 666
Optimization and Reduction 665
Latency Adjustment 666
Latency Adjustment (Settings) 1532
Legato (Edit Area Inspector 296
Length (Edit Area Inspector) 296
Length Display (Clips) 187
Level Display (Audio Clips) 187
Level Handle (Audio Clips) 189
Level/Pan CV (on Channel Strip) 511
Levels (Audio) 84
LFO Sync
Dr. OctoRex 698
NN-19 1002
Subtractor 1113
Line Mixer 6-2
About 1448
AUX Send and Return 1449
Channel Parameters 1448
Connections 1449
Line Tool (Velocity Editing) 312
Live Mode (Neptune) 1230
Load Default Sound in New Devices 1528
Load Default Sound in New Devices (Settings) 446
Locations (in Browser) 460
Locator Displays (Transport Panel) 136
Loop Locators 132
Loop Mode 155
Recording Audio Track in... 161
Recording Instrument Track in... 170
Recording Parameter Automation in... 178
Loop Mode (Edit Sample Window) 604
Loop On/Off Button (Transport Panel) 135
Loop Trig (Kong) 830
Looped Clips 210
Loops
In Drum Samples 1074
In Samples 996
Low BW 1005
Low BW (Dr. OctoRex) 700

Low Freq (Neptune) 1230, 1240

M

Magnifying Glass Tool 127
Main Mixer 51
  Channel Strip Sections 501
  Coloring Channel Strips 500
  Compressor Sidechaining 543
  Control Room Out (in Master Section) 518
  Copy Channel Settings 499
  Copying and Duplicating Channel Strips 498
  Dynamics Section 502
  Edit Focus 512
  EQ Section 505
  Fader Section (in Master Section) 518
  Fader Section (on Channel Strip) 510
  FX Return Section (in Master Section) 517
  Input Section 501
  Insert FX Section (in Master Section) 516
  Insert FX Section (on Channel Strip) 509
  Level/Pan CV 511
  Linking Fader Section Parameters on Mutliple Channels (on channel strip) 511
  Master Compressor 514
  Master Section 513
  Moving Channel Strips 498
  Naming Channel Strips 499
  Navigating in the... 494
  Overview 490
  Remote Controlling 538
  Reset Channel Strip Settings 499
  Selecting Channels 497
  Send FX Section (in Master Section) 515
  Send FX Section (on Channel Strip) 509
  Showing/Hiding Channel Strip Sections 495
  Signal Path Section 501
Make Ramp (Velocity in Edit Area Inspector) 311
Malström
  About 852, 1226
  Filters 859
  Graintables 855
  Modulators 857
  Oscillators 854
  Routing 865
  Routing external audio to 875
  Shaper 863
Manage Plugins Window (VST) 441
Manage Rack Extensions 1549
Manage VST Plugin 1549
Manual Rec 153
Mapping Variations (Remote) 640
Master Bus Compresssor 1211
Master Compressor (Main Mixer) 514
Master FX Parameter 1 & 2 841
Master Keyboard Input 104, 373, 1537
  Bypassing 662
Master Section Device 493
Master Section Mixer Strip 493
Master Tune 83
Master Tune (Settings) 1531
Matrix
  About 1452
  Application Examples 1463
  Programming 1453
Max Audio Threads 83, 1533
MClass Compressor 1221
MClass Effects
  About 1218
MClass Equalizer 1219
MClass Maximizer 1224
MClass Stereo Imager 1220
Melody (Stretch and Transpose Type) 229
Merge Note Lanes on Tracks 205, 1520
Metronome (Click) 154
MIDI
  Adding and setting up MIDI keyboards 1535
  Send All Notes Off 879
MIDI CC Automation (MIDI Out Device) 880
MIDI Clock 654
MIDI Controller Recording
  from Control Surface 881
  from MIDI Out Device 880, 882
MIDI Files
  Exporting 575, 1503
  Importing 574
MIDI Focus Button (Hardware Interface) 658
MIDI Note Chase 134
MIDI Out Device 878
  Setting up 878
Mimic Creative Sampler 891
Missing Device (Rack Extensions) 424
Missing Plugin (VST) 440
Missing Sounds 471
  Window 566
Mix Bus 526
  Creating 526
  Deleting 528
  Rerouting 528
Mix Channel Device 492
Mix Channel Strip 492
Mixdown
  Recording in the Sequencer 166

Mixer 14-2
About 1466
Auxiliary Return Section 1469
Chaining 1471
Channel Strip 1466
Channel Strip Controls 1467
Connections 1469
Signal Flow 1468
Monitor Button (Audio Tracks) 117
Monitoring Audio Tracks 158
Mono or Stereo on Audio Track 108, 157
Monotone Bass Synthesizer 921
More Audio (Hardware Device) 676
Mouse Knob Range 63, 1525
Mouse Mode (On-screen Piano Keys) 75
Multi Lanes 317
MultiCore Audio Rendering 83
Mute
Mixer 1448
Mixer 14-2 1467
Redrum 1072
Mute (M) Buttons 115
Mute Clips 204, 1520
Mute Notes 298
Mute Tool 127
My Account
macOS 1500
Windows 1552

N

Navigating in the Document Window 54
Neptune
Mixer Section 1242
Panel Parameters 1239
Pitch Display 1228
Pitch Processing of Live Audio 1229
Pitch Processing of Recorded Audio Tracks 1228
Setting up 1228
New (Song) 568, 1501
New Dub
On Audio Tracks 162
New from Template (Songs) 569, 1501
NN-19
About 988
Loading Samples 991
Parameters 998
NN-Nano Sampler (Kong) 826
NN-XT
About 936
Group Parameters 972
Groups 954
Loading Samples 938
Main Panel 940
Remote Editor Panel 943
Sample Parameters 970
Synth Parameters 974
Velocity Ranges 965
No Grouping (Rack Settings) 359
Noise Generator (Kong) 839
Non-Standard Routing Detected (Delay Compensation) 560
Normal Waveform Zoom Mode 60
Normalize (Edit Sample Window) 602
Note
Transposing 307
Note (in Edit Area Inspector) 307
Note Clips
Merging Note Lanes on Tracks 205
Opening for Editing 285
Reversing 315
Note Echo (Player) 402
Note Edit Lane (Note Clips) 288
Note Edit View Mode Selector (Note Clips) 288
Note Lanes
Adding/Creating 121
Deleting 123
Duplicating/Copying 124
Moving 124
Muting 125
Note To Slot (Dr. Octo Rex) 690
Note Tool (Player) 403
Note Tools (Context Menu Item) 1522

Notes
Altering Pitches 308
Chopping 299
Cut, Copy and Paste 303
Deleting 295
Drawing 293
Outside a Closed Clip 295
Outside an Open Clip 294
Duplicating 302
Extracting to Lanes 312
Joining 299
Matching 336
Moving 299
Outside or Between Clips 301
Muting 298
Nudging 302
Outside an Open Clip 302
Pasting Outside an Open Clip 303
Quantizing 304
Randomize 306
To Shuffle 306
Recording in the Sequencer 170
In Loop Mode 170
Over Existing Clips 171
Resizing 295
Selecting 292
Splitting 298
Transposing 301
Transposing in Octave Steps 301
Nudging
Note Positions 302
Recordings (Audio) 262
Nudging Slices 239
Nurse Rex Loop Player (Kong) 830

O

Octave (in Edit Area Inspector) 308
Offset R
Delay (The Echo) 1382
Feedback (The Echo) 1383
On-screen Piano Keys Window 75
Opening 74
Resizing 74
Open (Songs) 566, 1501
Open Demo Song 567, 1501
Open Last Song On Startup 567
Open last song on startup (Settings) 1529
Open Reason Companion on Startup 1529
Open Song Windows List
macOS Version 1551
Windows Version 1550
Optimizing RAM Usage 671
Optimizing Songs 669
Optimizing Your Computer 667
Options Menu 1546
Orkester Sound Bank 473
Orphan Audio Streams 574
Output Bus 526
Creating 526
Deleting 528
Rerouting 528
Output Latency (Settings) 1532
Overdrive/Resonator (Kong) 847
Overdubbing Audio in the Sequencer 162
Overlap (Edit Area Inspector)) 296

P

P Button (Mixer 14-2) 1467
Pad Group (Kong) 818
Pad Settings (Kong) 815, 817
Pads (Kong) 813
Pangea World Instruments 1009
Parallel Channels (Parallel Processing) 530
Parallel Output Bus 531
Parameter Automation
Record Enabling 153
Recording in the Sequencer 177
In Loop Mode 178
On Multiple Tracks 180
Over Existing Clips 179
Record Automation into Note Clip 180
Parameter Automation Lanes
Adding/Creating 122
Deleting 123
Folding/Unfolding 119
Muting 125
Parameter Automation Track
Creating 110
Parametric EQ 1412
Parametric EQ (Kong) 844
Paste Devices and Tracks 377
Paste Patch 449
Paste Pattern 1455
Paste Zones 954
Patch Cables 481, 485

Patches
About 446
Alligator 1162
Browsing 1508
Browsing for 455
Copy and Paste 449
Cross-Browsing 455
Exporting 1503
File Formats 474
Initializing 449, 1508
Kong 812
Loading 447
Missing Sounds 448, 1509
NN-XT 938
Pulveriser 1250
Redrum 1062
RV7000 Mk II 1298
Saving 448
Scream 4 1312
Searching for 463
Subtractor 1096
The Echo 1380
Pattern Automation
Deleting Clips 330
Drawing 329
Editing 328
Moving, Resizing and Duplicating Clips 330
Record Enabling 153
Recording in the Sequencer 181
Pattern Automation Lanes
Creating 122
Deleting 124
Pattern Changes
Converting Patterns to Notes 331
Pattern Controlled Filter - an Example 1405
Pattern Shuffle 1068
Patterns
Alligator 1164
Cut, Copy and Paste 1455
Muting in Matrix 1454
Muting in Redrum 1069
Redrum 1064
Running 1064
Selecting in Matrix 1454
Selecting in Redrum 1065
PEAK (Big Meter) 677
Pencil Tool 126
Drawing Notes 293
PEQ-2 EQ 1412
Performance Controller Automation
Creating New Lanes 325
Deleting Lanes 326
Editing 325
Hiding Lanes 326
Recording in the Sequencer 175
Over Existing Clips 176
Performance Controller Edit Lanes (Note Clips) 288
PH-90 Phaser 1408
Phase Controls (Subtractor) 1101
Phaser 1408
Physical Bass Drum (Kong) 835
Physical Snare Drum (Kong) 835
Physical Tom Tom (Kong) 835
Ping-Pong Delay (The Echo) 1383
Pitch
Notes 307
Pitch Adjust (Neptune) 1229
Pitch Adjustments
Freezing on Audio Track 1247
Pitch Bend Range (Kong) 825
Pitch Correction
Automatic 1231
Manual via MIDI 1235
Pitch Processing of Live Audio (Neptune) 1229
Pitch Processing of Recorded Audio Tracks (Neptune) 1228
Pitch-Correcting Audio (In Vocal Edit Mode) 244
P-LAN signals 479
Play Button (Transport Panel) 134
Play in Background (Settings - Audio) 1534
Players 382
Plugin Delay Compensation 550
Using 554
Plugin Window (VST) 431
Polyphony
Dr. OctoRex 699
Malström 870
NN-19 1004
NN-XT 972
Subtractor 1117
Polytone Dual-Layer Synthsizer 1025
Position (Edit Area Inspector) 299
Position Display (Clips) 187
Post-fader Sends (Mixer 14-2) 1467
PPM (Big Meter) 677
Pre-Align (ReGroove Mixer) 621
Preserve (Vocal Edit Mode) 250
Preserve Expression (Neptune) 1235
Preview (Dr. Octo Rex) 683
Program Change (MIDI Out Device) 879
Programmer CV In (Combinator) 1433
Pulsar Dual LFO 1474

Pulveriser 1250
Dirt 1252
Filter 1253
Follower 1255
Squash 1252
Tremor (LFO) 1254

Q

Q Rec Button (Transport Panel) 136
Q Record button 306
Quantize 1522
Audio 239
Randomize 306
To Shuffle 306
Quantize (Edit Area Inspector) 304
Quantize Button (Transport Panel) 136
Quantize Notes During Recording 306
Quantize Value (Transport Panel) 136
Quartet Chorus Ensemble 1259
Quit and Log out (macOS) 1500
Quit Reason (macOS) 1500

R

Rack 52
Creating New Rack Columns 375
Device Groups 372
Flipping Around 485
Navigating 360
Resizing 360
Scrolling in the... 360
Rack Extensions 420
Deleting 421
Installing 421
Managing 421
Missing Device 424
Trying and Buying 420
Using 422
Rack Per Track (Rack Settings) 356
Radical Piano 1047
RAM 671
Random Sequencer Pattern 1516
Random Timing (ReGroove Mixer) 624
Random Tool (Player) 409
Randomize
Pattern (Redrum) 1070
Pattern (RPG-8) 1494
Randomize (Velocity in Edit Area Inspector) 310
Randomize Notes (in Edit Area Inspector) 309
Randomize Pattern (Matrix) 1461
Rattler (Kong) 846
Razor Tool 127
RCY files 681
Reason Factory Sound Bank 473
Reason Library (Location in Browser) 461
Reason Menu (macOS) 1500
Record Automation as Performance Controllers 1549
Record Automation into Note Clip 176, 1549
Record Button (Transport Panel) 135
Record Enable Button (Audio Tracks) 117
Record Enabling
Audio Track 151
Instrument Track 152
Parameter Automation 153
Pattern Automation 153
Sequencer Tracks 150
Recording in the Sequencer
Audio 161
From Mix Channels 164
In Loop Mode 161
Over Existing Clips 163
General Procedure 156
Mixdown 166
Notes 170
In Loop Mode 170
Over Existing Clips 171
Parameter Automation 177
In Loop Mode 178
On Multiple Tracks 180
Over Existing Clips 179
Record Automation into Note Clip 180
Pattern Automation 181
Performance Controller Automation 175
Over Existing Clips 176
Tempo Automation 182
Undoing 157
Recording Meter Window 160
Recording Offset (Audio Clips) 262
Recording Offsets
Matching 280
Recording with Effects 545
Recordings
Nudging 262
ReCycle 680
Redo 71, 1505
Multiple 71
Redrum
Individual Outputs 1077
MIDI Notes for 1076
Parameters 1072
Patches 1062
Programming Patterns 1064
ReFills
About 473
Registering Reason 36

ReGroove Mixer
Assigning to Note Lanes 625
Creating ReGroove Patches 629
Factory Patches 631
Making Grooves Permanent 627
Parameters 617
Settings 622
Reload Samples 1511
Remote
About 634
Adding a Control Surface/Keyboard 635
Basics 640
Example Setups 639
Locking a Control Surface 642
Mapping Variations 640
Standard vs Remote Override Mapping 640
Surface Locking 642
Surface Locking Dialog 642
Unlocking a Control Surface 644
Remote Base Channel
Setting 538
Remote Override
Additional 649
Assigning 650
Edit Mode 645, 1546
Mapping 646
Remove Bars Between Locators 216, 217, 1517
Remove Long-Term Authorization 38
Render Audio Using Audio Card Buffer Size Setting 83, 667, 1534
Replacing Devices 376
Reset (Automation) 179
Reset Band Levels (Vocoder) 1188
Reset Device 449, 1508
Resetting Pitches (In Vocal Edit Mode) 244
Resizing Areas in Song Window 57
Resolution (Redrum Pattern) 1067
Reverb
RV-7 1401
RV7000 Mk II 1298
RV-9 Reverb Station 1288
Reverse (Audio Clips) 275
Reverse (Edit Sample Window) 602
Reverse (Note and Authomation Clips) 315
Revert All Notes (In Vocal Edit Mode) 244
Revert All Slices (In Slice Edit Mode) 241
Rewind Button 134
REX Edit View Mode (Note Clips) 290
REX files 474
Loading in Dr.Rex 681
Loading in NN-19 990
Loading in NN-Nano 826
Loading in NN-XT 939
Loading in Nurse Rex Loop Player 830
Loading in Redrum 1063
REX Loops
Creating Sequencer Notes 685
Editing Slices 687
Editing Sound 693
Loading 683
Playing in Dr. Octo Rex 682, 684
Ring Modulation (Subtractor) 1103
Ring Modulator (Kong) 845
Ripley Space Delay 1269
Roll (The Echo) 1381
Root and Scale (Neptune) 1231
Routing (Cables)
Automatic 481
Manual 485
RPG-8
About 1484
Arpeggiator parameters 1491
Arpeggio Notes to Track 1489
MIDI-CV Converter Parameters 1490
Setting up 1485
Ruler 132
Run button 1066
Run Button (Redrum) 1064
RV-7 Digital Reverb 1401
RV7000 Mk II Advanced Reverb 1298
RV-9 Reverb Station 1288
Rytmik Drum Machine 1079

S

S1/S2 controls (Redrum) 1072
Sample Rate
For Playback 668
Settings 82
Sample Rate (Settings) 1531

Samples
Browsing 1509
Browsing for 456
Cropping 602
Cross-browsing 458
Crossfading 606
Deleting 608
Duplicating 610
Editing 598
Exporting 611
Extracting from Self-contained Songs 572
Fading In/Out 603
File Formats 474
Including in Self-contained Songs 571
Kong 811
Looping 604
Missing 471
NN-19 991
NN-XT 945
Normalizing 602
Redrum 1061
Renaming 606
Reversing 602
Saving 606
Searching for 463
Sampling 593
About 590
Kong 824
Setting up 591
Save (Songs) 569, 1502
Save Device Patch As... 1503
Scale (Velocity in Edit Area Inspector) 310
Scale Memory (Neptune) 1231
Scale Tempo 314
Audio Clips 276
Scales & Chords (Player) 412
Scratch Disk Folder 573, 1541
Scream 4 1312
Scroll to Connected Device 480
Scrolling and Zooming with Track Pad 62
Scrolling and Zooming with Wheel Mouse 61
Scrolling and Zooming with XY Wheel Mouse 62
Scrolling in the Song Window 58
Search Field (in Browser) 463
Segment Focus Indicator (Audio Clips) 253
Segments (Audio Clips) 253
Adding 264
Select All in Device Group 374
Select Slice Via MIDI (Dr. OctoRex) 687
Selection Tool 126
Self-contain Samples When Loading From Disk 1528
Self-contained Songs 571
Send FX
Chaining from Devices to Main Mixer 541
Creating 523
Deleting 525
Editing and Saving 525
Muting 525
Send Out (Redrum) 1072
Sends
Mixer 14-2 1467
Redrum 1072
Sequencer 49
Adjust Alien Clips to Lane 196
Bypassing Master Keyboard Input 662
Inspector 279, 335
Set Loop (Edit Sample Window) 605
Set Loop to Selection 1517
Set Loop to Selection and Start Playback 1517
Set Root Notes from Pitch Detection 1513
Set Sample Start/End (Edit Sample Window) 601
Settings
Audio 1530
Browsing 1527
MIDI 1535
User Interface 1524
Shift
Pattern (Matrix) 1461
Pattern (Redrum) 1070
Pattern (RPG-8) 1494
Shortcuts (Location in Browser) 461
Show Browser 1545
Show Browser in Separate Window 451
Show Browser in Side Panel 450
Show CPU Load for Devices 664
Show Device Palette 1544
Show Edit Area 1545
Show Missing Sounds Windowr
Windows Version 1545
Show Mixer in Separate Window 1544
Show On-screen Piano Keys 1545
Show Parameter Value Tool Tip 1525
Show Rack in Separate Window 1544
Show Rack Navigator 1544
Show Recording Meter 1545
Show ReGroove Mixer 1545
Show Sequencer Only 1544
Show Spectrum EQ Window 1545
Show Transport Panel 1545
Show/Hide Mixer 1544
Show/Hide Rack 1544
Show/Hide Track Panel 1545
Shows For Selected Devices Only (Cables) 480

Shuffle
Global 618
ReGroove Mixer 620
Setting for Pattern Devices 618
Shuffle (Redrum) 1068
Sidechain Tool 1319
Sidechaining (Main Mixer Compressor) 543
Signal Flow Graphs (on Effect Devices) 1391
Signal Paths
Audio Track 86
Instrument Track 87
Silence
Inserting in Audio Clips 263, 269
Silence Row (Audio Clips) 254
Single Column Mode 1548
Single Take Clips in the Comp Editor (Audio Clips) 251
Slice Edit Mode (Dr. Octo Rex) 689
Slice Markers
Moving Several 238
Moving Single 238
Slice Trig (Kong) 832
Slices
About 680
Creating Sequencer Notes 685
Making Settings for (Dr. Octo Rex) 688
Nudging 239
Reposition Slice Markers 237
Selecting 235, 687
Stretching 232, 237
Slide (ReGroove Mixer) 619
Small Waveform Zoom Mode 60
SMF (Standard MIDI Files) 574
Snap 129
Snap Sample Start/End To Transients (Edit Sample Window) 601
Softube Amps 1328
Solo
Mixer 1448
Mixer 14-2 1467
Redrum 1072
Solo (S) Button (in Sequencer) 116
Song End Marker 132
Song Information 1502
Including 570
Song Position Display (Transport Panel) 133
Song Position Pointer 132
Song Samples (Location in Browser) 461
Song Samples Location (in Browser) 596
Song Window
Resizing Areas 57
Scrolling in the... 58
Songs
Closing 568, 1501
Creating 568, 1501
Creating New from Template 569, 1501
Default... 568
Exporting as Audio Files 582
File Formats 474
Opening 566, 1501
Optimizing 669
Saving 569
Self-contained... 571
Setting up the Default Song 1529
Splash Picture 570
Sort Zones by Note 1512
Sort Zones by Velocity 1512
Sound Packs (Location in Browser) 461
Soundfont files 475
SoundFonts
NN-19 992
NN-XT 939
Sounds
Missing 471
Source Device (In Device Group) 372
Speaker Tool 129
Speaker Tool (Audio Clips in Comp Editor) 257
Speaker Tool (Audio Clips Inline) 235
Spectrum Analyzer 506
Spectrum EQ Window 506
Spider
Audio Merger and Splitter 1395
CV Merger and Splitter 1397
Splash Picture 570
Split at Notes (In Vocal Edit Mode) 244
Split at Slices 240
Split Clips 199
Split Clips at Song Position 200
Split Notes 298
Spread (Pulveriser) 1254
Squash (Pulveriser) 1252
Startup Song 567
Static Value (For Automated Parameter) 320, 322
Static Value Handles 288
Stay on Top (Windows Version) 1550
Stems
Recording in the Sequencer 166
Stereo or Mono on Audio Track 108, 157
Stereo Tool 1025, 1269, 1319, 1335, 1441
Stop Button (Transport Panel) 134
Stop Hit Type (Kong) 833
Stretch and Transpose Type 229, 332
Stretch Type for New Recordings (Audio Tracks) 1519
Stretching Audio 232, 237

Sub-Mix
Recording in the Sequencer 166
Sub-mixer 526
Subticks
In the Inspector 138
In the Position Display (Transport Panel) 133
Subtractor
About 1096
External Modulation 1117
Filter 1104
Oscillators 1097
Waveforms 1098
Support Generators (Kong) 839
Surface Locking (Remote) 642, 1547
Sweeper Modulation Effect 1339
Swiping (Audio Clips) 264
Switch to Block View 1549
Switch to Song View 1549
Sync
About 654
Internal/MIDI Clock/Ableton Link/Send MIDI Clock 1546
Latency 657
Setting Up as a Client Device 656
Setting Up as Host 654
Sync Mode (Transport Panel) 136
Synchronous Timed Effect Modulator 1359
Synth Bass Drum (Kong) 837
Synth Hi-Hat (Kong) 838
Synth Snare Drum (Kong) 837
Synth Tom Tom (Kong) 837

T

Tags (Editing in Browser) 466
Tags Buttons (in Browser) 465
Tap Tempo Button (Transport Panel) 133
Tape Echo (Kong) 846
Template (Default Song) 1529
Template Songs 569
Creating Your Own 572
Tempo
Scaling 314
Tempo Automation
Drawing Events 331
Editing 331
Recording in the Sequencer 182
Tempo Data
In Exported Audio Files 583
In Imported Audio Files 578
Tempo Display (Transport Panel) 133
Text Field (in Browser) 463
The Echo 1380
Color Section 1384
Delay Section 1382
Diffusion 1383
Ducking 1386
Feedback Section 1383
Mode 1381
Modulation Section 1385
Thor
Assignable Controls 1125
Oscillator section 1130
Using the Programmer 1126
Tie Switch (Matrix) 1459
Time Position Display (Transport Panel) 134
Time Signature Automation 333
Deleting Clips 334
Moving, Resizing and Duplicating Clips 334
Time Signature Display (Transport Panel) 133
Timeline 132
Timeline (Context Menu Item) 1517
Toggle Rack Front/Rear 485
Tone Generator (Kong) 840
Tool Tips 67, 1525
Toolbar Tools 126
Alternate 129
Keyboard Shortcuts 131
Track Color 1521
Track Pad
Scrolling and Zooming with... 62
Track Panel 48, 139
Tracks
Coloring 115
Creating 107
Deleting 113
Duplicating and Copying 114
Moving 113
Muting 115
Naming 115
Record Enabling 150
Resizing 112
Routing Master Keyboard Input to 104
Selecting 111
Soloing 116
Types 105
Transient Shaper (Kong) 842
Transition (Vocal Edit Mode) 250
Transport Panel
Keyboard Shortcuts 137
Transpose
Audio Clips 277
Comp Rows 278
Notes 307

Transpose (Neptune) 1236
Transpose (Semitones) (in Edit Area Inspector) 308
Transpose Display (Audio Clips) 187
Transposing Audio (In Vocal Edit Mode) 244
Tremor (Pulveriser) 1254
Trig Next Loop (Dr. Octo Rex) 682
Trigger Buttons (Redrum) 1062
Trigger Notes while Editing 1524
Trim Knobs 488
Tuner
  Using on Audio Track 159
Tuner Button (Audio Tracks) 117
Tuning 83
Type Buttons (in Browser) 462

U

UN-16 Unison 1410
Unassigned Samples 607
Undo 71, 1505
  Multiple 71
Unipolar Curves (Matrix) 1458
Unison 1410
Unmute Clips 1520
Use Hyper-Threading Audio Rendering (Settings) 667
Use MultiCore Audio Rendering (Settings) 667
Use Side Panel Browser in new songs (Settings) 1529
User Library (Location in Browser) 460
Utilities 361

V

Velocity
  Editing 315
Velocity (in Edit Area Inspector) 310
Velocity Lane 309
View All
  Windows Version 1550
View Menu 1544
View Mode (Key Edit) 289
Vocal (Stretch and Transpose Type) 229
Vocal Edit Mode (Audio Clips) 242
Vocoder
  About 1182
  How it Works 1182
  Parameters 1188
  Setting up 1183
  Using as EQ 1187
Voice Synth (Neptune) 1238
VST
  About 426
  Adding to the Rack 428
  Automating Parameters 433
  CV Modulation 435
  Enabling 426
  Installing 426
  Keep Open 432
  Missing Plugin 440
  Plugin Folders (Defining in Settings) 444
  Plugin Rack Device 429
  Plugin Window 431
  Remote Controlling 438
  Selecting Programs 439
  Taking Screenshots 433
VST Plugin Folders 1541
VU (Big Meter) 677
VU Offset (Big Meter) 677

W

Warping Audio 232, 237
Waveform Zoom Mode 60
Wheel Mouse
  Scrolling and Zooming with... 61
Wide Vibrato (Neptune) 1230, 1240
Window Menu
  macOS Version 1551
  Windows Version 1550

X

XY Wheel Mouse
  Scrolling and Zooming with... 62

Z

Zoom (Application) 47
Zoom To Selection 60
Zooming in the Sequencer 59